


# Architecture in Detail II

Graham Bizley



**bd**



Architectural  
Press

# Architecture in Detail II



This page intentionally left blank

# Architecture in Detail II

**Graham Bizley**



**ELSEVIER**

AMSTERDAM • BOSTON • HEIDELBERG • LONDON • NEW YORK • OXFORD  
PARIS • SAN DIEGO • SAN FRANCISCO • SINGAPORE • SYDNEY • TOKYO

*Architectural Press is an imprint of Elsevier*



**Architectural  
Press**

Architectural Press is an imprint of Elsevier  
Linacre House, Jordan Hill, Oxford OX2 8DP, UK  
30 Corporate Drive, Suite 400, Burlington, MA 01803, USA

First edition 2010

Copyright © 2010, Graham Bizley. Published by Elsevier Ltd. All rights reserved

The right of Graham Bizley to be identified as the author of this work has been asserted in accordance with the Copyright Designs and Patents Act 1988

No part of this publication may be reproduced or transmitted in any form or by any means, electronic or mechanical, including photocopying, recording, or any information storage and retrieval system, without permission in writing from the publisher. Details on how to seek permission, further information about the Publisher's permissions policies and our arrangements with organizations such as the Copyright Clearance Center and the Copyright Licensing Agency, can be found at our website: [www.elsevier.com/permissions](http://www.elsevier.com/permissions).

This book and the individual contributions contained in it are protected under copyright by the Publisher (other than as may be noted herein).

#### Notices

Knowledge and best practice in this field are constantly changing. As new research and experience broaden our understanding, changes in research methods, professional practices, or medical treatment may become necessary.

Practitioners and researchers must always rely on their own experience and knowledge in evaluating and using any information, methods, compounds, or experiments described herein. In using such information or methods they should be mindful of their own safety and the safety of others, including parties for whom they have a professional responsibility.

To the fullest extent of the law, neither the Publisher nor the authors, contributors, or editors, assume any liability for any injury and/or damage to persons or property as a matter of products liability, negligence or otherwise, or from any use or operation of any methods, products, instructions, or ideas contained in the material herein.

#### **British Library Cataloguing-in-Publication Data**

A catalogue record for this book is available from the British Library

#### **Library of Congress Cataloging-in-Publication Data**

A catalog record for this book is available from the Library of Congress

ISBN: 978-0-08-096535-2

For information on all Architectural Press publications  
visit our website at [books.elsevier.com](http://books.elsevier.com)

Typeset by MPS Limited, a Macmillan Company, Chennai, India

[www.macmillansolutions.com](http://www.macmillansolutions.com)

Printed and bound in China

10 9 8 7 6 5 4 3 2 1

Working together to grow  
libraries in developing countries

[www.elsevier.com](http://www.elsevier.com) | [www.bookaid.org](http://www.bookaid.org) | [www.sabre.org](http://www.sabre.org)

ELSEVIER

BOOK AID  
International

Sabre Foundation

# Contents

<i>Preface</i>	ix
<i>About the author</i>	x
<i>Thoughts on Construction</i>	2
 <b>Arts and Culture</b>	
Royal Festival Hall, London <i>Allies &amp; Morrison</i>	17
Neues Museum, Berlin <i>David Chipperfield Architects</i>	21
Newlyn Art Gallery, Cornwall <i>MUMA</i>	25
The North Wall Arts Centre, Oxford <i>Haworth Tompkins</i>	31
Regent's Park Open Air Theatre, London <i>Prewett Bizley Architects</i>	37
Bluecoat Arts Centre, Liverpool <i>Biq Architecten</i>	41
Ruthin Craft Centre, Denbighshire <i>Sergison Bates Architects</i>	45
Siobhan Davies Dance Centre, London <i>Sarah Wigglesworth Architects</i>	49
Rich Mix, Bethnal Green, London <i>Penoyre &amp; Prasad</i>	53
MIMA, Middlesbrough <i>Designed by Erick van Egeraat</i>	57
Multi Purpose Hall, Aurillac, France <i>Brisac Gonzales Architects</i>	61

## **Civic and Leisure**

ARC, Hull 65  
*Niall McLaughlin Architects*

Resource Centre, Grizedale Forrest Park, Cumbria 69  
*Sutherland Hussey Architects*

Thermae Bath Spa, Bath 75  
*Nicholas Grimshaw & Partners*

Civil Justice Centre, Manchester 81  
*Denton Corker Marshall*

Sean O'Casey Community Centre, Dublin 85  
*O'Donnell + Tuomey*

## **Schools**

Bellingham Gateway Building, Lewisham, London 91  
*Cottrell & Vermeulen Architecture*

Maryland Early Years Centre, Stratford, London 95  
*Fluid*

Emmaus School, Wybourn, Sheffield 99  
*DSDHA*

Bedford School Music School, Bedford 105  
*Eric Parry Architects*

Sanger Building, Bryanston School, Dorset 111  
*Hopkins Architects*

Scitec, Oundle School, Northamptonshire 115  
*Feilden Clegg Bradley*

## **Education**

Ann's Court, Selwyn College, Cambridge 121  
*Porphyrios Associates*

Wolfson Building, Trinity College, Cambridge 125  
*5th Studio*

Information Commons, University of Sheffield 129  
*RMJM*

## **Health**

St Johns Therapy Centre, Wandsworth, London 133  
*Buschow Henley Architects*

**Residential**

Christchurch Tower, City of London <i>Boyarskiy Murphy</i>	137
Halligan House, St Albans <i>Simon Conder Associates</i>	141
Herringbone Houses, Wandsworth, London <i>Alison Brooks Architects</i>	147
GreenHouse, BRE, Watford <i>Gaunt Francis Architects</i>	151
Focus House, Finsbury Park, London <i>bere:architects</i>	155
80% House, De Beauvoir Town, London <i>Prewett Bizley Architects</i>	159

**Housing**

Clay Field Housing, Elmswell, Suffolk <i>Riches Hawley Mikhail Architects</i>	165
Chance Street Housing, Bethnal Green, London <i>Stephen Taylor Architects</i>	171
Islington Square Housing, Manchester <i>FAT</i>	175
EMV Social Housing, Vallecas, Madrid <i>Feilden Clegg Bradley</i>	179

**Offices**

The Johnson Building, Clerkenwell, London <i>Allford Hall Monaghan Morris</i>	183
One Coleman Street, City of London <i>Swanke Hayden Connell in association with David Walker Architects</i>	187
Vernon Street Offices, Kensington, London <i>Terry Pawson Architects</i>	191

**Transport**

Southern Cross Station, Melbourne, Australia <i>Grimshaw Jackson JV</i>	195
Project Credits	198
Project Details	210



This page intentionally left blank

# Preface

Since April 2004 working details from contemporary building projects have been published in Building Design. This book collates 35 of these studies as a continuation of the series begun by *Architecture In Detail*. In 2006, The Concrete Centre also began commissioning working detail features for their journal *Concrete Quarterly*, which promotes innovative use of concrete in construction. Five of these are included in this volume. In response to feedback received from the first book, the projects have been classified according to the type of building. There is also an index matrix at the back so the projects can be searched by criteria such as structural system, budget or whether work to a listed building was involved.

The purpose of the details is not to provide ready-made solutions but to add to the resource base and stimulate thought. There are aspects of them all that can be criticised. Although the principles applied in solving different problems may be similar, the final details are always specific to the conditions of the particular situation. The projects are presented here in the belief that, by offering a tentative, analogous solution that can then be criticised, we gain insight into our own problem and find fresh strands of thought to follow.

I would like to thank all the architects, engineers and photographers who have allowed their work to be reproduced in this book. A full list of credits for each project is given at the end.

## About the author

Graham Bizley studied architecture at Bath University and ESTAB in Barcelona. He has worked for various architects in the UK, India and Zimbabwe. In 2005, he set up Prewett Bizley Architects with Robert Prewett. He is a regular contributor to *Building Design* and since 2004 has prepared a regular working detail feature under the title 'In Detail'. A first volume of *Architecture In Detail* was published by the Architectural Press in 2007.

# Thoughts on Construction

It is difficult to identify in the work of one's own time what will be viewed in the future as significant development and what will be forgotten or dismissed. What is lauded is often that which is novel and novelty immediately invites suspicion that an achievement has not been sufficiently interrogated to merit such attention. The buildings in this book have not yet stood the test of time, but rather than try to be judgmental my intention is to attempt to understand the conditions and ideas that make them the way they are. By their inclusion here all the buildings can be assumed to exhibit some innovation or at least to have some design ambition to distinguish them from the norm. To get beyond personal prejudice and establish a critical view it is necessary to see them in the context of their creation and to take a longer view of the trends prevalent when they were made.

Architecture's basic functions of providing shelter from the elements, an ergonomic environment and emotional stimulation have not changed. The ways in which they can be accomplished however are constantly evolving and the balance between the different aims shifts in response to technological, cultural, political and economic trends. An analysis of construction or detailing inevitably becomes a wider discussion because choices of materials and techniques are bound up with more complex issues.

In many fields, not least in politics, the latter half of the 20th Century saw a gradual retreat from dogmatic positions towards more inclusive viewpoints that take in the nuanced, often contradictory nature of situations. Grand philosophical ideas no longer seem credible as all-encompassing solutions. We no longer believe that technology alone will solve our problems or that one lifestyle or belief is objectively superior to another. In architecture a truce has been drawn in the tedious conflict over style that dominated debate in the 1970s and 1980s. The city is appreciated as a dynamic patchwork of diverse, interrelated communities where a variety of architectural expression is desirable to express individuality or collective identity. Meanwhile we find ourselves drawn together by the ever more urgent need to use resources more carefully and reduce the energy demand of our buildings.

Public interest in architecture has never been so high. The Sterling Prize is shown on prime-time TV and architects no longer struggle to persuade unwilling clients to choose modern over traditional design. Public buildings such as Tate Modern, Walsall Art Gallery or the Scottish Parliament have demonstrated the capability of innovative design to make awe-inspiring and accessible civic spaces. In the process materials such as concrete and steel, for so long associated in the public perception with drab post-war housing estates or industrial sheds have been rehabilitated as symbols of urban sophistication. Grand Designs and numerous makeover shows have empowered ordinary home owners to use modern design as a way of improving their quality of life, turning the natural tendency to project individuality and aspiration through the home into a consumer leisure activity.

While public interest in design must be a good thing, the media's obsession with novelty encourages the view that architecture has to be new or radical to be interesting. The day-to-day work of most architects who struggle with limited means to create a well planned environment, appropriate for its use and specific to its users is devalued by the emphasis on visual appearance. Rather than the traditional role as a team leader with a strategic overview of a project the architect is increasingly pushed to one of two extremes,

occasionally that of the figurehead providing a glamorous front for the project or that of the technician merely making sure it complies with the various rules and regulations. In the commercial environment the architect may only be given liberty where it is perceived design will add financial value. In public and commercial projects procurement systems often severely restrict the influence of the architect who is seen as a cause of risk and expensive design 'changes'. The role of the architect has been undermined by a loss of faith in their ability to manage cost and time, responsibility for which is often passed to project managers or contractors. To satisfy clients' demands for proven performance to eliminate risk architects are likely to become increasingly specialised in more technical roles. The split in the profession between building technicians and so-called 'design architects' is likely to widen further.

All but five of the buildings in this book are in the UK and only three were designed by architects based outside the UK. Comparing these examples with the projects that attract most press coverage globally there would seem to be limited correlation, pointing to the widening gulf between the work of the typical practice, particularly outside large urban centres and the pre-occupations of the global architectural elite. It also suggests that there may be something specifically British about this body of work. Are these just the High Street, poor man's versions of international haute couture designer brands or is there something more distinct about them?

Globalisation is often blamed for a loss of local variation. Images of new buildings are published simultaneously around the globe and the dominance of multi-national companies in the construction industry allows the same products to be used in vastly differing situations. Such concerns are not new. John Summerson for example, writing in 1941, pointed out the same phenomenon in relation to the spread of the International style. He was dismissive of the notion that wide dissemination of ideas encourages a ubiquitous response because design is produced by individuals who, despite the effects of globalisation still have vastly different influences making up their view of the world. According to Summerson, 'Architectural change occurs as the result of the irregular and incalculable incidence of men [sic] of genius – innovators'.<sup>1</sup> The schools that form around them through their teaching and former employees inevitably tend to evolve on a regional basis. In one sense the emphasis on the individual neatly side-steps the issue of a national or international style. It also avoids the suggestion that regionalism is inherently conservative or parochial. Valerio Olgiati, working from the small Alpine town of Flims concurs that 'Looking at the world in an individual way is the only way to make an architecture that has character. At the same time we also have to find something general in the individual so that it is understandable in a globalised world – it has to be contradictory'.<sup>2</sup>



Royal Festival Hall – detail of balustrade  
Photo: Denis Gilbert/VIEW

Modernism in its pure form never achieved widespread public acceptance in Britain. Those buildings that have won affection tend to exhibit a softening of the orthogonal grid, a response to context and a human scale. The Royal Festival Hall was the first post-war building to be listed grade I. As the centre-piece of the 1951 Festival of Britain it was designed as a symbol of a brighter future amongst the ruins of London. Conceptually the idea of the 'egg-in-a-box' auditorium protected from external noise by the surrounding cascades of public foyers is functional, democratic and entirely Modern but the purity of the diagram is softened by the gentle curve of the river façade, high quality materials and careful detailing. Bespoke elements such as the cast bronze door handles, Wilton carpet and timber handrails are found at the interfaces where people come into contact with the building. Between 2005 and 2007 it underwent a £117 million refurbishment to correct its poor acoustics, re-organise the foyers and introduce more commercial functions around it. The esteem in which it



*Rich Mix – new louvres on south façade  
Photo: Morley von Sternberg*

is held is partly a function of its architecture, but also of its symbolic role as a 'people's palace' on the river, a phenomenon enhanced by an 'open foyers' policy adopted since the late 1980s that has opened up the internal spaces to the public throughout the day and evening.

Most of the projects in these pages could comfortably be grouped under a banner of neo-Modernism, where formal manipulation, colour or regional materials have been used in a way that is not purely functional to make them more 'friendly' or give them a specific relationship to their location. The Rich Mix is an arts centre that occupies a converted 1950s garment warehouse on the edge of London's east end. The original structure was unremarkable but architects Penoyre & Prasad have re-clad the concrete frame with a bank of adjustable coloured louvres on the south-facing street façade that provide both solar shading and give the institution a dynamic, contemporary identity. Inside, finishes are modest and the services are left exposed. Rich Mix proudly wears its industrial heritage, playing on associations with spaces artists often chose as studios and with the 'street' culture of the post-war urban landscape.

Historian Alan Powers points to an inherent pragmatism in English culture which is suspicious of intellectual ideas. We rely on our foreign-born architects for free-forms and expressionism. When British architects break from the orthogonal it is with the firm justification of engineering or the givens of the site.<sup>3</sup> It is certainly true that most discussions with clients hinge around cost, programme and what the end product will look like rather than architectural concepts. The idea that architecture should have a theoretical basis or could achieve any political aim has slipped off the agenda, as Alejandro Zaera-Polo pointed out in a recent interview. 'Our generation of architects has not been politically active', he said. 'Architects' traditional role as visionaries and ideologists has become redundant as the sheer speed of change overtakes their capacity to represent politics ideologically. We have been consumed in the means of production and in simply making buildings'.<sup>4</sup> The contemporary city is built and run by corporations for multi-national shareholders' interests and the opportunity for representation of any off-message political ideal is limited. Politics itself has shifted away from a polarised left-right debate to a more nimble, issue-based discussion capable of engaging with independent individuals across a field of disparate issues.



*Manchester Civil Justice Centre  
Photo: Tim Griffith*

Openness and accessibility, by-words in the political arena in the new-labour years have found a literal expression in the use of glass and voluminous entrance halls in public buildings. Middlesbrough's Institute of Modern Art for example addresses a new public square with a wall of glass in front of a dramatically lit, fractured stone wall, a powerful gesture visible from across the square. On its other three sides the building presents unarticulated walls of white render, giving quite the opposite message, suggesting cheapness and alienation. The primary idea is a theatrical gesture rather than a material or constructional idea about the making of the building itself. Manchester's Civil Justice Centre achieves a better resolved relationship to the public realm in the round with a 12-storey atrium allowing views from the street of people moving around inside. Different cladding treatments are used to articulate distinct volumetric elements of the building so it reads as a sculptural assembly of forms with a tension between them. All you can see from outside in either example, however, are the circulation areas and a reception desk. Security and privacy concerns mean that the activities that are the building's purpose remain hidden. Transparency is used as a metaphor for democracy offering a sense of inclusion while actually establishing a tightly controlled series of barriers.





*Angel of the North, Gateshead*



*St John's Therapy Centre – south elevation  
Photo: Nick Kane*

Whatever their flaws, both these buildings suggest a strong belief in a public role for architecture to represent the values of society and to influence people's feelings about its institutions. For such gestures to succeed the emotions they evoke must correlate with people's feelings about those institutions, or at least express an ideal which is not beyond the realms of belief. In the 20th Century a crisis arose in the representational image of public buildings because the associations of a classical language no longer represented the mood of a more socially mobile public in a post-colonial age of mass communication, yet the functionalist alternatives often lacked the familiar imagery, spatial drama and crafted detail to inspire civic pride. As the population becomes more diverse, both ethnically and culturally, it becomes more difficult to provide something that will hold meaning for a wide domain of people. If an institution is to seek public attention with monumentality then there must be sufficient shared belief in the ideas it is vaunting or the gesture will just seem pompous.

Outside the sphere of architecture a public art project that has found a place in the public affection is the Angel of the North, a 20 m high steel figure by the sculptor Anthony Gormley which overlooks the A1 near Gateshead. Gormley uses the human form, stripped of all identifying features so that it might relate to anyone, and invites a very direct interaction with the work so that the individual can feel a personal relationship with it. The monumentality it achieves through its scale and form is enhanced by the use of a single material, Corten steel, which has a timeless quality in its surface variation and the way it weathers.

A building has much more complicated functional demands upon it so such simple gestures are seldom possible. The building envelope, and more particularly the surface are where much recent architectural innovation has been focused. The St John's Therapy Centre in Wandsworth is clad in a single material, timber veneered panels which give it the distinctive identity of a special object like a chestnut or a violin. Bigger elements of the programme were deliberately located at the front of the building so that their large windows could give a civic scale to that elevation, an effect enhanced by an integrated, super-graphic sign at roof level. It achieves a civic presence on the street by its materiality and scale. Apart from the joints between the panels the detailing of construction is not expressed, emphasising the sense of the building as a whole rather than an assembly of parts.

The 50 mm thick steel ribs and visible welds on the Angel of the North express the taut equilibrium between the structural endeavours of man and the forces of nature. The joints in the cladding of the Therapy Centre are suppressed and instead the thinness of the veneer is expressed by mounting the windows flush with the cladding and introducing a different coloured material where there are recesses. Long horizontal openings suggest structural daring although no elements of structure are directly visible. Without a visible structure the fabric can only communicate formal and sculptural articulation. With a design and build contract procured by a public body there is limited room for manoeuvre. The architects, Buschow Henley have understood well that attention has to be focused on a few strong moves that are robust enough to withstand the limitations of the budget.

The Manchester Civil Justice Centre achieves its monumentality through structural and compositional daring without reference to traditional symbols, achieving a presence in the city appropriate to its programme through sheer size. The programme has been manipulated to exaggerate the proportions of the building using different materials for the vertical elements containing circulation areas and the courtrooms. The glazing support metalwork and the joints between adjacent cladding elements are visible, but the articulation is at such a relatively small scale that it does not distract from the bigger



Multi-purpose hall, Aurillac  
Photo: Brisac Gonzales Architects



1 Coleman St, London  
Photo: Hélène Binet



*Midland Bank, Cheapside, London*

gestures. Holes in the cladding panels and compositions of colour behind the glass introduce further human scale elements that work as patterns on the larger surfaces.

A building that does achieve a civic identity through a singular gesture is the multi-purpose hall at Aurillac in France. It is clad in a ribbon of precast concrete panels backlit by LED lights. The volume is too big to express its function in a literal sense and relieved of the duty of relating to any neighbours by its edge of town location, the façades have been turned into a giant light sculpture. Whereas traditional articulation fails to deal with the scale of such a structure the lights can be programmed to change colour and pattern to create effects that wrap around the entire building. The construction supporting the ribbon is functional and unimportant as it is not visible to observers of the effect it is sustaining.

In the corporate world innovative architecture has frequently been used as a symbol of dynamic and positive thinking to set a company apart from its rivals. The prime agenda of the developer is to maximise lettable area so the domain of architectural expression is often limited to the building envelope, but the high budgets involved put these envelopes at the forefront of façade technology. 1 Coleman Street in the City of London is an interesting example where a standard steel frame has been clad in a system of precast concrete elements and identical windows. The building has a curved form and the floors bulge out in section. By faceting the precast elements and alternating the angles of the windows between floors an illusion of movement is created by the reflections as one moves around the building, an effect enhanced further by cladding the top floor in polished stainless steel. What is actually quite a simple, repetitive system has been turned into something more engaging by adding a virtual element to the way it is perceived.

It is worth comparing 1 Coleman Street with the nearby Midland Bank building designed by Edwin Lutyens from 1924-39. Its appearance is of a classical, load-bearing stone building but it too has a steel frame and Lutyens' manipulation of the detailing creates intrigue and ambiguity in the façade. In the ground storey a Doric column base and capital are set into the rustication so that the wall can be read simultaneously as a colonnade or a wall. The proportion of these 'phantom columns' has been thickened beyond the normal Palladian proportions to give the building a more massive appearance at the base. Higher up, the wall undergoes a number of setbacks and actually tapers back in section. Each stone course is shorter than the last and there is no cornice so not only is the weight of the façade distorted but the elements by which its scale might be determined are omitted towards the top.<sup>5</sup> Through tricks of perspective, distortion or reflection both buildings manipulate a reading of form and scale to create effects which are more than a simple sum of their parts.

To a Modernist's eye Lutyens' cladding of a steel frame with what looks like a load-bearing masonry façade is all wrong. As Lutyens himself pointed out many Modernist buildings did not express their actual structure and were more interested in appearing to tell a clear story even if that story were not actually true. The issue of honesty in structural expression was an ideal of the Modern movement but no longer appears to be of much concern in the contemporary debate. Of the projects in this book only a few gain their architectural expression from a literal expression of their structure. Southern Cross Station in Melbourne is the clearest example, where every component and connection of the steel roof structure is on view. As it does not require



*Southern Cross Station, Melbourne  
Photo: Markus Bachmann*



*St Ann's Court, Selwyn College,  
Cambridge  
Photo: Morley von Sternberg*



*Sanger Building, Bryanston School  
Photo: Anthony Weller*

a lined interior the railway station is one of the few building types suited to exposing the structure in this way. The use of a highly engineered structure as an expression of a belief in progress and technology goes back to the roots of Modernism in the 19th Century engineering structures that inspired the writing of Viollet-le-Duc.

For a number of reasons it has become increasingly difficult to build using a monolithic masonry structure. Laying brick or stonework requires skilled labour and is time-consuming as only a certain height can be built in one day. To prevent heat loss insulation is required and a cavity has to be incorporated to prevent water penetration. It is therefore cheaper and quicker to use framed construction. If brick or stone are used it is in a reduced role as an outer cladding to represent security or quality, a thin skin in front of the true structure.

This issue has been addressed in different ways in two educational buildings where higher than normal budgets have allowed the architects to build load-bearing masonry walls. Ann's Court is a new administration and residential building for Selwyn College in Cambridge. It has load-bearing cavity walls with the inner leaf taking the weight of the floors. The outer leaf is a whole brick thick, laid in Flemish bond to show its thickness which is a purely aesthetic luxury. In the ground floor arcade where thermal bridging is no longer a problem stone piers and arches carry the load of the whole wall. The building has the appearance and external detailing of a traditional brick and stone structure but to achieve this effect the overall wall thickness is 545 mm and a concrete beam is hidden in the wall above the arcade to tie the piers together. The façade appears to tell a neat story but the true version of events is slightly more complex. At Bryanston School the new science block has a load-bearing brick wall facing a central courtyard which is 1½ bricks thick with no cavity or insulation. The brick is laid in English bond, again to express the thickness of the masonry. Thermal performance has been sacrificed for the architect's desire for an honest structure. Since the time the decision was made energy conservation has become more of an ethical issue and with hindsight perhaps the priorities would have been different. Between the second floor and the roof the piers have concrete cores concealed within them to help resist wind loads and to tie down the roof.

It is in no way my intention to be negative about these deceptions. The demands on buildings are in most cases far too complex to achieve a pure expression of everything that is going on. The architect's task is to create a convincing story by choosing which issues to express and which to conceal as I discussed in the introduction to *Architecture in Detail* Volume 1. In most buildings a hybrid approach is taken where structure is expressed if it is appropriate to the performance requirements and the architectural intent is to some extent determined on a pragmatic basis. The demands on the building envelope include supporting the floors and roof, exhibiting an appropriate external appearance, thermal insulation, air tightness, solar control, security, and contributing to an appropriate atmosphere in a range of different internal spaces. Every building could therefore be said to have a layered construction with various elements or surface treatments carrying out different roles.

As the level of environmental performance of buildings increases building envelopes are likely to become more complex and will have to be built to more exacting standards. If there is a single issue that unites all aspects of the construction industry it is that of reducing the energy demand of buildings, both in the embodied energy of construction and in their energy





ARC, Hull

Photo: Niall McLaughlin Architects

consumption in use. Designers and contractors alike are having to consider every decision as part of a more holistic understanding of how construction can be made less harmful to the environment. Technology is moving quickly and we cannot be sure how the balance will play out in the long term. A building that has been designed to adapt to such changes is the ARC, a movable pavilion engineered to be carbon neutral by generating the same amount of energy as it uses through renewable sources. It has a programme of events demonstrating environmental issues and will be relocated to different locations in the Humber region. Architect Niall McLaughlin has committed to a long term relationship with the project. 'Each time we'll redesign it as necessary. I'd like to think that in 20 years time it might not look remotely like this', he says.<sup>6</sup>

Some building envelopes incorporate elements that can be adjusted by the occupier to affect the performance of the envelope. The louvres on the south façade of the Rich Mix are controlled manually in banks of twelve from inside each room to control how much direct sunlight reaches the glazing. The east, south and west courtyard elevations of the EMV Social Housing in Vallecas have external balconies with sliding screens which can be moved by each resident to block direct sunlight. In both cases the choices made by different occupiers creates a dynamic pattern that adds interest and human scale to the elevations. Low-technology solutions like these are robust as they do not rely on electronic control or complex maintenance regimes. Most importantly they allow the individual some control over their environment.

For a number of years 'green' architecture had a certain look characterised by clip-on gadgets such as solar panels and ventilation cowls. As low-energy construction is being adopted more widely, integration of energy-saving measures is becoming more subtle. In terms of saving energy the most effective measures can be invisible. The concrete used for the office building at 1 Coleman Street has a 50% recycled content by mass compared to a typical level in a commercial building of 5%. The steel used for the reinforcement was made from 100% scrap metal, the basement and upper floor slabs incorporate 100% secondary coarse aggregate in the form of china clay stent and the aggregate in the precast elements is 100% from secondary sources (by-products of other extractive industries).



Focus House – solid timber panels  
being craned into position  
credit: Bere Architects

Experimentation in low-energy and low-carbon construction is being led by private home owners who are prepared to use their own money to push the available technology and test new ideas. The Focus House in north London is built using a solid timber panel system that, rather than causing carbon emissions, has extracted and stored approximately 30 tonnes of carbon from the atmosphere. It has a very high level of air-tightness and uses a mechanical ventilation system with heat recovery to supply fresh air. For a given expenditure increasing the amount of insulation in the building envelope and making the construction air-tight can save a much greater amount of energy than can currently be produced by on-site energy generation at the level of the individual dwelling.

In contrast the house building industry and landlords are reluctant to deviate from tried and tested methods unless they can see a direct financial advantage. A number of experimental houses have been built at the Building Research Establishment (BRE) in Watford. In 2008 Barratt completed a house there which is claimed to be the first house in the country built by a volume house builder to achieve level 6 under the Code for Sustainable Homes. To achieve this level, however, the house is reliant on a bank of photo voltaic panels mounted next to it which stand in for the energy that would be supplied by a central biomass plant were the house part of a larger development.

The BRE has come under criticism for focusing on individual buildings rather than a holistic approach and allowing itself to be used as a marketing device by the private companies that provide the majority of its funding rather than carrying out independent scientific research.<sup>7</sup>



*Clay Field Housing, Elmswell*  
*Photo: Riches Hawley Mikhail Architects*

Innovation in larger scale housing developments has so far been limited. Working on a one-off house contractors will not be able to get to grips with new construction techniques quickly enough to represent their actual efficiency at a larger scale or benefit from economies of scale in purchasing components and materials. Clay Field Housing at Elmswell in Suffolk is a development of 23 affordable houses and flats carried out by a housing association but part-funded by a grant from the Housing Corporation. Domestic hot water and heating are provided by a central biomass boiler and materials with low embodied energies have been used throughout. The houses are grouped in threes and clad in cedar shingles and clay render. Although they look distinctive there is no gadgetry on show. Instead their character comes from their integration with the landscape, their materials and a sectional form designed to maximise passive solar gain.



*80% House – rear elevation*

New housing only represents a small part of the UK housing stock. The replacement rate for the existing stock is less than 0.1% per annum so buildings that exist today will account for over 70% of the total building stock by the year 2050. It quickly becomes apparent that a bigger problem is what to do with the millions of existing houses that are uninsulated and poorly sealed to significantly reduce their energy loss. The 80% House is a typical Victorian terraced house in Hackney that has undergone an 'extreme' environmental refurbishment, carried out by my office. Using the maximum possible carbon reduction as the primary criteria it was found that the best use of the available budget was to use as much high-performance insulation as possible and make the house air-tight. The additional embodied energy of the insulation is soon offset by its better performance in use. The refurbishment has achieved an 80% reduction in carbon emission from the house and it is calculated that the carbon emitted in the refurbishment work will be offset after six years. Refurbishment of existing houses is not cheap and is complicated by the fact that every house is different. Some are listed or, like the 80% House are in conservation areas where there are planning restrictions on what can be done. In some areas the cost of refurbishment will be hard to balance with what the house is worth so research must concentrate on finding mass-market, low cost ways of improving energy performance. Workers will have to learn new skills as the industry gets to grips with the necessary techniques for low carbon construction. The challenge is to see how quickly low-carbon construction can become the norm and will simply be known as construction.

Sixteen of the projects in this book are either extensions or incorporate elements of existing buildings. The Siobhan Davies Dance Centre in London and the North Wall Arts Centre in Oxford are both built on top of Victorian buildings. Newlyn Art Gallery in Cornwall and The Bluecoat in Liverpool are both extensions to important listed buildings. Each of these examples is characterised by respect for the existing building and a modest but distinctive expression of the new work. There is evidence of a deeper investigation and understanding of the urban fabric than has happened in the past and a resistance to approaches that ignore context. At Newlyn the old and new buildings are pulled apart and articulated with a glazed slot but the other three exhibit a more relaxed attitude that expresses a



Vernon Street offices  
Photo: Terry Pawson Architects



Sean O'Casey Community Centre,  
Dublin  
Photo: Terry Pawson Architects



Herringbone Houses, Wandsworth  
Photo: Cristobal Palmer

confidence in the architect's ability to knit the old and new together to their mutual benefit.

This approach has been taken to a magnificent extreme in one of the most daring restoration projects undertaken since the Second World War. The Neues Museum was one of five institutions on Berlin's Museum Island, now a world heritage site. It lay in ruins for 50 years after being destroyed by allied bombing. David Chipperfield Architects and Julian Harrap Architects have painstakingly constructed a new museum through a combination of repair, refurbishment, reconstruction and new building work. The symbolic significance of the project has been immense in Germany, particularly as it was carried out by British architects.

It must be said that in most of these cases the existing building has been preserved for its historical importance rather than as an energy saving measure. The fact that VAT (currently 17.5%) is payable on refurbishment but not on new-build work encourages destruction of perfectly serviceable structures. If the government is serious about reducing the embodied energy of construction, not to say the waste it generates, then the rates of VAT must be equalised.

Perhaps one reason why low-carbon construction has not become a general concern until recently is due to preconceptions about its aesthetic. Style-conscious architects and clients alike have been more interested in what a building looks like than how it performs and prefer to spend money on things they can see rather than on hidden insulation. A continuing preference for clean lines and light, open-plan spaces is evident in contemporary architecture, although the first decade of the 21st Century has also seen a resurgence of interest in decoration and ornament. The Vernon Street offices in Kensington fall firmly the first camp, with flush mounted glazing, invisible means of fixing, and suppression of detail. Rather than articulating the traditional elements of roof, walls and windows the architectural expression comes from the cubist idea of a composition of abstract forms. The heights and volumes relate to those of its neighbours but otherwise the crisp, smooth volumes make a stark contrast with the Victorian and Edwardian brick buildings near-by.

From a distance the volumes of the Vernon Street offices appear homogenous but on closer inspection a subtle grain is apparent due to the surface quality of the material and the fact that the walls are made up of multiple elements. The proportions of the precast concrete pieces are long and squat, emphasising horizontality and the surfaces have been acid-etched to expose the aggregate, making them matt with a slight texture. The overall effect is subtle but does give some articulation to the surface. It would be fanciful to call this decoration, but how far can the necessary elements be manipulated before it becomes decoration?

Two buildings on which the boundaries have been pushed a little further are the Sean O'Casey Community Centre in Dublin and the Herringbone Houses in south London. Like the Vernon Street offices both are composed of quite abstract forms, detailed to avoid expression of traditional elements like copings and architraves. The Community Centre has concrete walls, cast in-situ with a vertically corrugated surface. The corrugations give texture but also make the building more abstract as they do not reveal where the joints were in the materials that made up the formwork. The Herringbone Houses are clad in ipe, a hardwood which can be left unsealed to fade to a silvery-grey colour. The individual pieces of timber have been cut to identical sizes and fixed in a herringbone pattern. The horizontal bands catch the light





Islington Square housing, Manchester  
Photo: Tim Soar

differently, introducing another pattern the scale of which is bigger than the individual building components.

A more extreme approach is shown by a development of 23 social housing units at Islington Square in Manchester. Except for their front elevations the houses are timber-framed with flat roofs and are finished in white render. The front elevations are load-bearing brick cavity walls but the form of the façade does not follow that of the houses behind. The parapet steps and swoops to form a series of Dutch style gables with occasional openings revealing the sky behind like a stage set. Several colours of brick have been used in a large scale graphic pattern that works to tie the whole terrace together but also makes each house distinct by the way the pattern falls across its façade. Balconies, window boxes and brackets for hanging baskets have been made from timber cut in stylised shapes to evoke ideas of domesticity in an unashamedly kitsch way. FAT's design was chosen by the residents in a competition which suggests they are offering something that was lacking in the other proposals.

The most radical aspect of the New Islington development is its use of decoration in a way that goes beyond surface modulation into a realm of whimsical expression, but not without purpose. Form is certainly not following function but the form is serving a function, that of engaging with the residents and passers-by in a way that is playful but also serious.



Regent's Park Open Air Theatre –  
female wash area

Many architects are reticent about using colour unless it is the natural colour of a material. Green is a crucial part of the identity of the Information Commons building in Sheffield for example, but the colour comes from the weathered copper cladding rather than a treatment applied to the surface. Using a material's natural patina as the surface finish is very sensible as it will not require any maintenance whereas a painted or artificially coloured surface will deteriorate and fade over time.

In my office's design for the toilets at the Regent's Park Open Air Theatre we used colour to create an atmosphere one would not expect in such a prosaic facility. The ceiling, walls and doors are made from different timbers and plywoods. The floor is a poured red resin and in the female wash area the ceiling is painted a glossy pink. On one side the facilities are open to external gardens so the spaces also borrow greens from the plants and pinks and blues from the evening sky. Colour here has been used as part of a palette of materials and textures to build up richness and warmth.



Maryland Early Years Centre  
Photo: Morley von Sternberg

In two projects applied colour has been used in a more decorative way to modulate the surface and add another level of interest. The Bellingham Gateway building in south London houses a nursery, sports and community facilities. It is clad in translucent polycarbonate behind which some of the plywood sheathing has been painted in yellow, pink and green. The effect is slight and not always apparent in certain lights, but the uncertainty creates a level of intrigue a more obvious scheme would not have. The Maryland Early Years Centre is also clad in translucent polycarbonate but here the colour comes from the material itself. Two colours are used and there is no strong logic to where the transition occurs between them. The choice does not articulate a particular volume or component, it is simply a playful gesture.

It has become common in façade design to use multiple colours for repetitive components within a single system like the multi-coloured louvres on the Rich Mix or the brickwork pattern at New Islington. There is still a line however which has not been crossed in any of the examples here. Colour is always used within the confines of a particular building element like the brick wall at New Islington or a component like the copper cladding on the

Information Commons building. A pattern of colour never crosses from say a wall to a roof and a change in colour never occurs in the middle of a cladding panel. A few architects have bucked the trend, such as Surface Architects in their Centre for Film & Media at Birkbeck College but these are interiors where the colour has been applied on site as paint and does not have to resist the elements. As well as reflecting architects' adherence to an ingrained decorum the reasons for this may be partly practical. Production processes make it much more expensive to have bespoke components with different colour patterns and the systems used for walls have different characteristics than those used for roofs. The performance requirements of the building envelope make it costly and risky to deviate from the available systems.

Some degree of surface articulation is inevitable in any building as there will always be joints between components or different materials and all materials have their own qualities which are affected by how the surface is treated and finished. The modulation of surface is an unavoidable issue and one that has a prominent effect on the appearance of the building so there must be a positive strategy for its expression.

A strong desire has been evident amongst certain architects to break the constraints of the traditional building elements by making the envelope into a continuous surface. Although there are no examples in this book it is one of the most powerful trends of recent years and presents a fundamental challenge to the construction industry and to our preconceptions about how buildings are made. Built examples would include the Phaeno Science Centre in Wolfsburg by Zaha Hadid and the Selfridges department store in Birmingham by Future Systems. In these projects technology is being pushed to bridge the gap between the idea of an abstract entity with no relation or association with other objects and the conventional demands on a building.



*Phaeno Science Centre, Wolfsburg*

Self-compacting concrete was used extensively in the construction of the Phaeno because it can be used to make complicated shapes in single pours without the need for vibration. The construction joints in the concrete are deliberately mis-aligned with changes in geometry to enhance the sense of the building as a singular entity and to express its dynamic form. In comparison, if we look at the Information Commons building in Sheffield, all the construction joints in the concrete, the glazing mullions and the joints in the copper cladding can be seen to align with one another. The copper cladding wraps around corners and under soffits but the obsessive adherence to the rigour of the grid makes for a much more static composition.



*Information Commons Building,  
Sheffield*

*Photo: Hufton & Crow*

Hadid describes her work as a continuation of 'the incomplete project of Modernism',<sup>8</sup> in the sense that Modernism was an attempt to express in built form the advances in technology that were occurring in the 20th Century. 3-dimensional computer modelling software is crucial to such experimentation but Hadid uses these techniques in conjunction with hand drawing and physical modelling to help maintain control of the process. Technology is merely a tool in the drive for formal invention.

The buildings produced in this way may well let us experience spaces which are unfamiliar and exciting but it is hard to see how the advances made might usefully be applied in the wider industry struggling with the more pressing issues of cost and time. In 1998 the Construction Task Force, led by John Egan produced a report called *Rethinking Construction* which encouraged the industry to make radical changes to the processes through which it delivers projects. The report made a comparison with the car industry where standardisation and pre-assembly are critical to achieving efficiency and quality. The construction industry has finally taken up this challenge with some enthusiasm in a number of projects, particularly in the housing sector. Complete pre-fabrication of houses is too restrictive in terms

of transportation and the vast differences in specific site conditions and occupants to which they would have to be applicable. Instead it has proved efficient to prefabricate certain elements, particularly where wet-trades can be eliminated. If the building can be erected and made weather-tight quickly then work can commence on the internal fit-out at the same time as the external cladding is being applied.

Timber construction affords particular advantages in the UK climate and has the advantage that carbon is captured in the wood so offsetting the carbon footprint of the development. The Focus House in north London was built using a solid laminated timber panel system which is estimated to have locked up 42 tonnes of carbon. Each panel was precisely cut directly from the electronic drawing files by a CNC cutter and erected in a few days on site. For the Maryland Early Years Centre the walls and floors were fabricated offsite as timber framed panels with sheathing and insulation already in place.

Prefabrication works most efficiently where there is repetition which, on irregular urban sites or sloping ground is often difficult to achieve. Computer controlled fabrication machinery is making bespoke or irregular components easier to make but such systems need to be designed at an early stage of the project. Clients are usually reluctant to commit to a certain system prior to tender as it may restrict the number of contractors willing to bid for the work and hence the pricing will be less competitive. Over the past decade a huge variety of systems, materials and techniques have been tried out and no dominant approach has emerged. Whatever cost advantages it might have there is a public revulsion to the idea of standardisation in the built environment. The construction industry needs the skills to take advantage of prefabrication and standardisation where they are appropriate but also the flexibility to respond to the specific requirements of each building.

When modern design began to regain popularity in the UK in the mid-1990s high quality materials were an important factor in its acceptance. Projects like David Chipperfield's shop interior for Issey Miyake (1985) which used veined white marble and wide timber floorboards to make a rich, sophisticated environment, showed how modern design could be seductive and desirable rather than drab and functional. The work of Swiss architects like Peter Zumthor and Herzog & DeMeuron illustrated what can be achieved in a country which still has a highly skilled, craft-based construction industry. In popular culture the materials of Modernism were initially appropriated as a backdrop of gritty realism in film or for aspiring bands to express both alienation from society and a rebellious ability to survive in the aggressive post-war urban landscape. Art galleries such as the Lisson and nightclubs like the Hacienda recreated the atmosphere of the found industrial spaces used by artists as studios or where illegal raves took place. Since the late 1990s we have seen these materials, admittedly in a more bespoke, scrubbed-up state, creeping into expensive restaurants and corporate office buildings. In some cases they are there to lend an edge of cool to otherwise sanitised environments but more and more they are appreciated for their own intrinsic qualities.



*Emmaus School, Sheffield  
Photo: DSDHA*

Very few buildings have the budget for high quality materials or for bespoke fabrication. Furthermore procurement systems for commercial or public works often restrict the materials that can be used to tried and tested products on which a guarantee is available. A division has opened up between buildings made from products or systems and those made from crafted materials. The Emmaus School in Sheffield for example has a simple palette of white rendered walls and proprietary grey aluminium-framed windows. The architects, DSDHA realised the need to make the details robust so it could be built economically without the need for highly skilled labour. The refurbishment of the Wolfson Building at Trinity College, Cambridge on





Halligan House, St Albans  
Photo: Steve Ambrose



Thermae Bath Spa – stone cladding



Ruthin Craft Centre – detail of concrete  
Photo: Ioana Marinescu

the other hand features two new glass seminar rooms suspended beneath the existing concrete structure. The quirks of the existing building and the accuracy of bespoke construction required would have made the project very labour intensive on site for both the architects and the contractors.

The character we discern in a material is intrinsically linked to the level of craft which has been devoted to it. If detailed and built with sufficient care our perception of even quite humble materials can be raised. This is the approach we took with our additions to the Open Air Theatre in Regent's Park where bespoke toilet cubicles were made from inexpensive spruce panels detailed in a way that makes the material feel more refined. A similar approach is apparent in the Halligan House in St Albans where a bespoke glazing system was made very simply using standard double glazed units silicone-bonded to a folded piece of stainless steel on the front of a timber mullion. By using the limited budget carefully, in a targeted way Simon Conder Architects have achieved a quality usually only seen in projects with a much higher budget.

Our appreciation of a material can also be affected by the appropriateness of the way it has been used. If we look at the way Bath stone has been used in the Thermae Bath Spa for example, the pieces of stone are larger than in the surrounding Georgian buildings and are stack bonded. The detailing is well resolved and crisp but the stone is reduced to the role of cladding which removes some of the qualities which make it a desirable material. The stones are all the same size so there is less natural variation between the individual pieces than in the adjoining buildings. Because the stones are stack bonded there is not the sense of them acting together is lost. In a traditional masonry wall, made up of similar but not identical pieces, we may sub-consciously perceive an analogy with the relationship between the individual and society, which in a small but comforting way invokes empathy within us.

There has been a noticeable improvement in the level of craft in certain buildings. Often where an extremely high quality has been achieved it is through the involvement of a specialist sub-contractor who has a close working relationship with the architect and contractor. This trend could be described as a new Arts and Crafts tradition where specialist manufacturing skills form an inseparable part of the architectural intent. The precast concrete elements for the office building at 1 Coleman Street for example were made by Decomo in Belgium. The means of fabrication, transportation and installation were worked up by the sub-contractor with the design team to ensure each piece was prefabricated to precisely the right size and could be installed without damaging the finish.

The surface itself has become a focus of particular attention. A subtle change in the texture, sheen or colour of the material can have a big effect on the character of the building. The Ruthin Craft Centre is a single storey building made from full-height concrete slabs that were cast flat on the ground and then tilted up into position. The concrete is pigmented a similar red to the colour of the local stone from which several prominent public buildings in the town are made. While still wet, part of the surface of each slab was rolled to give it a lined finish above dado height. The architect and contractor experimented on site until they achieved an effect they were happy with. The lines work with the visible joints between the panels and shifts in geometry to break down the scale of the walls, but crucially they add a hand-crafted element to the construction which is both specific to that building and to its function.

Richard Sennett has defined craft as 'an enduring, basic human impulse, the desire to do a job well for its own sake'.<sup>5</sup> As well as a self-indulgent satisfaction for the maker there is also a sense of altruism in the term, an offering of something special to the community that harbours the maker.

If the opportunity to do a job well is denied then the result is frustration. Traditionally craftsmen were held in high esteem and played a part in the rituals of a town in an almost mystical way. The tendency towards anti-elitism, suspicion of authority and a de-skilling of the workforce marginalises the knowledge of the craftsman and erodes the motivation to do something for the greater good.

There is a need in a healthy society for spiritual compensation for the alienation of people from nature and the lack of control they feel over their own destinies. Once this was the role of religion alone but we now seek it in a variety of spheres, including buildings. Wonder can be inspired by the apparent magic of a floating roof, a flying cantilever or expanses of unusual materials with no visible fixings. Magical objects carry out a crucial role in a community of arousing emotions and in focusing those emotions into a useful agent for that community. According to the philosopher Robin Collingwood, 'magical activity is a kind of dynamo supplying the mechanism of practical life with the emotional current that drives it'.<sup>9</sup> The scale and public presence of architecture make it a natural provider of icons, a potential symboliser of the collective will. The difficulty is that many large buildings symbolise the will of corporations rather than that of a wider society, further alienating ordinary people rather than binding them together. Projects like the Angel of the North or the refurbishment of the Neues Museum in Berlin have achieved this role and in both there is a very strong element of craft.

I suggested in the introduction to *Architecture in Detail volume 1* that the buildings we find most satisfying are those which we feel empathy, those which are tuned in to human emotions. If a building conveys joy, pathos, humour or serenity it is communicated in the making of a joint, the way mass is expressed or the manner in which a material has been treated. Perhaps to accept a building as a shared symbol we need to feel strong evidence of the human endeavour that made it and sense that the task was undertaken at least in part for the greater good.

The construction industry has gone through a questioning phase as it tries to get to grips with its inefficiencies and reducing its impact on the environment. Each generation likes to think it has an architecture of its own, one that represents its superior achievements over what went before. If it is impossible to identify a single dominant approach it must mean that some thinking has been going on and we have not completely succumbed to superficial stylistic temptations or easy answers. Perhaps that is an architecture to be proud of.


## References

1. The Mischievous Analogy by John Summerson, written in 1941 and published in *Heavenly Mansions*, p 211, Norton, 1963.
2. Valerio Olgiati – *Architecture Today* no. 200, p 28, July 2009.
3. See *Britain – Modern Architectures in History* by Alan Powers, Reaktion Books, 2007.
4. Alejandro Zaera-Polo (interview with the author, 8 July 2009). See also *The Politics of the Envelope* in *Log* issue 13/14 (Autumn 2008) or issue 17 (November 2008).
5. See *The Details of Modern Architecture* by Edward Ford, p 118, MIT Press, 1996.
6. Niall McLaughlin quoted in *A lean-to to learn from* by David Littlefield, *Building Design*, 11 March 2005.
7. See *Building Design*, 27 June 2008. The BRE is currently 40% publicly funded and 60% privately funded.
8. Quoted in *Digital Hadid: Landscapes in Motion* by Patrik Schumacher, Birkhauser, London 2004.
9. *The Principles of Art* by Robin Collingwood, Oxford University Press, 1938, pp. 66–69.



Photo: Dennis Gilbert/VIEW





*Photo: Allies & Morrison*



*Photo: Dennis Gilbert/VIEW*

## Royal Festival Hall, London

Architect: Allies & Morrison

Acoustic Consultant: Kirkegaard Associates

The Royal Festival Hall was the centrepiece of the 1951 Festival of Britain on London's South Bank. Its acoustics have always suffered from 'dryness' due to an excess of absorbent surfaces and performers found it difficult to hear themselves on stage because the hall is designed to project as much sound as possible away from the stage to reach the back of the vast 3000 seat space.

In a controversial refurbishment quite a bit of the interior has been altered. The walls around the stage have been re-angled and the plywood canopy removed to project less sound away from the stage. Almost all the surfaces have been altered to decrease their acoustic absorbency and increase the reverberation time.

Legroom in the stalls has been increased by 80mm involving replacing the precast concrete step units that form the raked floor. The new units span between existing saw-tooth concrete beams, modified for the wider steps by breaking out or building up mass concrete on top of the beams. The existing carpet has been replaced with reclaimed teak strip flooring with vents in the risers for a displacement ventilation system.


The walls at the sides of the stalls, known as the Copenhagen walls are clad in knuckle-profiled elm strips, originally used in Copenhagen's Radihusets Concert Hall to diffuse sound. They originally had gaps between them and were mounted on a hollow studwork wall which distorted the sound. All the timber was stripped off and the existing studwork infilled with dense plasterboard. New timber profiles were made with walnut infill strips between to seal the gaps whilst maintaining a dark shadow-like appearance.

Seats were moved to make new aisles adjacent to the Copenhagen walls with new mahogany handrails that have bronze brackets with a nickel additive to give a silver finish matching the existing handrail brackets. Where the handrail meets the existing balustrade handrail at the top of the stalls the existing mahogany handrail has been cut away and re-shaped to integrate with the new rail.


According to critics the refurbishment has dramatically improved the clarity and vibrancy of the sound.




*Photo: Allies & Morrison*




Section through typical row in stalls – 1:20




Balustrade plan detail as original (1951) – 1:5



Balustrade plan detail as modified (2006) – 1:5



Level 4 plan – 1:800



Section – 1:600

Drawing labels:

1. Side annexe floor

Existing 160 mm reinforced concrete slab retained.  
Existing 60 mm foamed slag screed retained.  
Existing carpet and felt underlay removed.  
65 × 15 mm tongued and grooved teak parquet floorboards adhesive bonded to existing screed.

2. Side annexe support wall

Existing 230 mm brick walls supporting concrete slab and precast floors.

3. Raked floor to stalls

840 mm deep precast concrete step units with 200 × 200 mm integral beam spanning from masonry wall at perimeter onto existing concrete saw-tooth beams.  
Integral beam stopped 140 mm short of end of precast unit so that flat underside of unit bears on saw-tooth beam.  
Precast units bedded on 50 mm grout with 20 mm tolerance between adjacent units.

4. Floor sub-structure

Existing 230 mm wide reinforced concrete saw-tooth beams cut back as necessary to support new precast step units.  
New mass concrete built up on existing beams to increase depth of each step.

5. Floor to steps and stalls

Treads formed from 65 × 15 mm tongued and grooved reclaimed teak parquet strips screwed to timber battens cast into tops of precast concrete step units.  
40 × 40 × 4 mm mild steel angle fixed to front edge of precast step unit.  
75 × 25 mm reclaimed teak nosing screwed to angle from underside and grooved to take tongued ends of floorboards.  
Risers formed from 65 × 15 mm tongued and grooved reclaimed teak parquet strips with ventilation slots to plenum beneath floor for displacement ventilation system.

6. Balustrade structure

Existing 50 mm wide softwood carcass fixed to concrete slab and masonry walls retained.  
All existing timber cladding stripped off.

Carcass infilled with 50 mm thick plasterboard to increase density for sound absorption.

7. Lining to stalls

9 mm elm veneered plywood backing screwed and glued to carcass.  
9 mm elm veneered plywood skirting, head trim and end panel screwed and glued to backing ply.

8. Timber lining

47 × 32 mm solid elm strips with curved sound-diffusing profile screwed and glued to ply backing.  
18 × 18 mm solid walnut strips screwed and glued to ply backing between elm strips to give shadow effect.

9. Lining to side annexe

9 mm elm veneered plywood panel screwed and glued to carcass.

10. Balustrade capping

Existing 95 × 25 mm solid elm capping to top and end of balustrade retained, sanded and re-sealed.

11. Existing handrail


Existing 305 × 57 mm mahogany handrail retained, sanded and re-sealed.  
Existing 95 × 10 mm mild steel stiffening plate set into underside of handrail.  
Existing 50 × 10 mm mild steel vertical support bolted to softwood balustrade carcass.  
Existing 80 × 45 mm oval profile silvered bronze sheath to vertical supports retained and polished.

12. New aisle handrail

60 × 50 mm mahogany handrail to match edge profile of existing handrail.  
Silvered bronze fixing brackets with 60 × 30 mm fixing plate screwed to plywood backing on balustrade.

13. Modified existing handrail

1700 mm end section of existing 305 × 57 mm mahogany handrail cut back and new mahogany piece attached to make junction with new handrail to aisle.  
50 mm wide × 20 mm deep finger groove in top of new handrail section.



Copenhagen wall and handrail detail section at top of stalls






*Photo: Ute Zscharnt*



*Photo: Ute Zscharnt*



*Photo: Ute Zscharnt*



*Photo: Christian Richters*



*Photo: Ute Zscharnt*

## Neues Museum, Berlin

Architect: David Chipperfield Architects

Restoration Architect: Julian Harrap Architects

Designed by Friedrich Stüler, the Neues Museum was the second of five museums to be built on Berlin's Museum Island, now a world heritage site. It was completed in 1855 but was severely damaged in the Second World War and lay derelict for many years. After five years of meticulous work, costing £210 Million, the Museum reopened in 2009.

The task was defined by the architects as one of repair rather than restoration. Stüler's interiors were highly decorated and any remaining fragments of the surviving fabric have been conserved. Large missing sections of the building have been infilled with new construction using precast concrete to distinguish it from the existing.

The most dramatic interventions inevitably occur where wartime damage was greatest such as in the Egyptian Courtyard where sculptures will be displayed in eight vitrines beneath a flood of natural light. Only two walls of the courtyard are original and the other two have been constructed in reclaimed brick to match. The glass courtyard roof has a lattice structure of concrete beams supported on ten incredibly slender 24-metre high concrete columns. A free-standing platform divides the space in two vertically sheltering a 9-metre high gallery beneath.


All the structural elements are precast concrete. The floor edge beams are L-shaped to support precast floor slabs which are left exposed to the spaces below. The columns and beams have been sandblasted so they have a matt, stone-like surface. In contrast, the floor is paved with the same concrete but with a polished finish so the stone aggregate is much more apparent.

Services such as air supply ducts have been integrated into the new construction so as not to disturb the existing fabric. Air is supplied via bronze grilles set into the floors to rise and be extracted at roof level.


Around the platform laminated glass balustrades extend up three metres to define a more intimate space within the larger volume. The edges of the glass are protected with bronze T-sections that frame each side of the space.

The warm colour of the concrete tones with the buff brick walls, softening the light and making a serene centrepiece to the Egyptian collection.





Level 2 plan – 1:1000



Level 1 courtyard plan – 1:400




Rendering of section through Egyptian Courtyard

Drawing labels:

1. Basement floor  
60mm concrete paving with sandblasted surface.  
35mm strips of mortar supporting paving.  
Proprietary raised floor system with varying height void.  
Damp proof membrane turned up walls to finished floor level at perimeter.  
1250mm thick in-situ concrete floor slab.
2. Basement wall  
150mm precast concrete wall slabs with sandblasted surface, packed level on concrete plinth and fixed to in-situ wall with stainless steel ties.  
40mm cavity.  
In-situ cast concrete structural wall from basement to ground level.
3. Typical column  
500 × 500mm precast concrete column with sandblasted faces.
4. Ground floor  
60mm concrete paving with polished surface.  
35mm strips of mortar supporting paving.  
Proprietary raised floor system with 250mm height void.  
170mm precast concrete ceiling slab sandblasted on underside.
5. Ground floor edge beam  
775mm high × 500mm wide × 235mm thick precast concrete edge beam with sandblasted faces spanning across ground floor columns.  
Thickness of beam widens to 500mm at column positions to form continuous bearing for columns above.
6. New courtyard wall  
380mm (narrowing to 240mm at high level) face brick wall to courtyard made from reclaimed bricks, free-standing and tied to ribs of the concrete wall with stainless steel ties.  
350mm cavity.  
300mm in-situ concrete structural wall with 330 × 160mm vertical ribs.  
90mm cavity.  
180mm (150mm above picture rail level) precast concrete wall panels with sandblasted surface fixed to concrete wall with stainless steel ties.  
Precast elements stand on the in-situ floor and on one another.
7. Wall opening  
1270mm deep × 315mm thick precast concrete jamb with polished faces fixed to concrete wall with stainless steel ties.  
1270mm deep × 370mm thick precast concrete lintel with polished faces supporting brickwork only bearing on jambs and fixed to jambs with stainless steel pins.

8. Platform beams  
500 × 495mm precast concrete beams with sandblasted faces.  
Perimeter beams have 60 × 235mm upstand at edge to conceal in-situ floor.
9. Platform floor  
60mm concrete paving with polished surface.  
35mm strips of mortar supporting paving.  
Proprietary raised floor system with 350mm height void.  
Composite ceiling made up from 80mm precast concrete ceiling slabs sandblasted on underside spanning between beams with 150mm in-situ concrete structural topping.  
In-situ concrete perimeter upstand to support balustrade.  
500 × 490mm precast concrete edge coping with sandblasted faces fixed to floor with stainless steel pins.
10. New exhibition rooms (Greek Hall) at second floor  
60mm concrete paving with polished surface.  
35mm strips of mortar supporting paving.  
Proprietary raised floor system with 100mm height void.  
Composite structural floor made up from 50mm precast concrete ceiling slabs spanning between beams with 150mm in-situ concrete structural topping.  
480mm void for services.  
Ceiling consisting of 80mm thick sandblasted precast concrete ceiling slabs with 120 × 150mm ribs spanning between beams, movable on rollers to allow access to services later.  
The gap between these elements is closed with 30mm thick sandblasted precast concrete slabs or panels for lights and air grilles.
11. Ground floor balustrade  
1279mm high × 49mm thick toughened and laminated glass panels with satin-treated surfaces, clamped in a 245 × 99 × 15mm thick steel channel welded to 325 × 16mm plate bolted to precast edge beam.  
49 × 10mm bronze flat bar frame to three sides of glass with 10 × 3mm central downstand to engage with recess in glass.
12. Platform balustrade  
3400mm high × 49mm thick toughened and laminated glass panels with satin-treated surfaces, clamped in a 364 × 99 × 15mm thick steel glazing support channel welded to 410 × 16mm continuous steel plate bolted to edge of in-situ concrete upstand.  
49 × 10mm bronze flat bar frame to three sides of glass with 10 × 3mm central downstand to engage with recess in glass.
13. Air supply  
20mm thick cast bronze grating.  
33 × 25mm bronze angle frame for grating fixed to plenum channel.  
Galvanised steel plenum channel supplied by ductwork beneath raised floor.



Cut-away section through Egyptian Courtyard





*Photo: Allan Williams*






Photo: Allan Williams



Photo: Allan Williams



Photo: Allan Williams



Photo: MUMA

## Newlyn Art Gallery Cornwall

Architect: MUMA

Slate Consultant: Viv Stratton


Roofing Subcontractor: Forrester Roofing

Newlyn Art Gallery was designed by local architect James Hicks and opened in 1895. It occupies an enviable position at the end of a public promenade overlooking Mounts Bay. MUMA's refurbishment has created a new education room and entrance in a new building at the rear facing the sea. The new extension is clad in Trevillet slate hung in the traditional Cornish manner. A 'scantle' was used to set out the battens and slates to achieve a continuously diminishing coursing without any banding. A scantle is a length of timber, usually one of the roofing battens, marked up as a gauge to locate each course.


Concrete ground beams and a concrete floor slab sit on pile foundations. The first floor is also concrete with a perimeter ring beam supported on four internal circular concrete columns that allow the ground floor shop and café to be surrounded by continuous silicone jointed glass. Above the first floor the structure is steel with timber studwork infill. The highly insulated walls have an inner and outer leaf of studwork with a 175 mm services zone in between. Both roof and walls are clad in slate and the coursing has been carefully set out to ensure the courses on the gable end line through with the courses on the roof.

The slates have been wet-laid with a minimum triple lap (3½; gauge) on the walls and a quadruple lap (4½; gauge) on the roof to resist the severe Atlantic weather. Stainless steel screws have been used to secure the slates rather than the traditional oak pegs. Hydraulic lime mortar in a 1:2 lime:sand ratio was used without any cement, which might have caused efflorescence and staining of slates. The mortar was laid in a horseshoe-shaped bed to form voids so water cannot be drawn up into the roof by capillary action.


Integrating the roof and walls into a single material idea gives the extension a scale appropriate to its civic function. From the first floor education space, a 9-metre wide strip window gives a sweeping view of sea and sky, a reminder of the qualities that attracted artists to this part of the world.



Section – 1:500



First floor plan – 1:500



Ground floor plan – 1:500



Site location plan – 1:2000

#### Drawing labels:

##### 1. Structural frame

Steel frame above first floor level with  $203 \times 203 \text{ mm} \times 46 \text{ kg UC}$  (universal column) primary members.  
300 mm thick reinforced fair-faced concrete first floor slab with  $725 \times 575 \text{ mm}$  downstand perimeter ring beam.  
Four 300 mm diameter in-situ fair-faced concrete columns supporting first floor.

##### 2. Typical wall

Wet 'scantle' laid random width Trevillett slate laid in diminishing courses.  
 $25 \times 50 \text{ mm}$  horizontal tanalised softwood battens spaced to suit slate coursing and fixed to vertical battens with 25 mm stainless steel nails.  
 $50 \times 50 \text{ mm}$  vertical tanalised softwood battens at 400 mm centres coinciding with studs behind to provide continuous ventilation gap.  
Breather membrane.  
18 mm WBP plywood sheathing.  
 $100 \times 50 \text{ mm}$  tanalised softwood studs at 400 mm centres with 100 mm mineral wool insulation between.  
175 mm services zone with mineral wool packed in voids.  
 $75 \times 50 \text{ mm}$  tanalised softwood studs at 600 mm centres with 75 mm mineral wool insulation between.  
Vapour barrier.  
Two layers 12.5 mm plasterboard with skim coat and paint finish.

##### 3. Slate cladding

Wet 'scantle' laid random width Trevillett slate laid in diminishing courses.  
Slate to walls laid at 3.5 scantle and slates to roof laid at 4.5 scantle.  
Slates fixed with stainless steel screws through pre-drilled holes, two holes for wall slates and one hole for roof slates.  
Hydraulic lime mortar laid in horseshoe pattern between slate courses.

##### 4. Corner junction

Code 4 lead soakers extending full height of each slate and 225 mm either side of corner.  
Slate edges to be mitred at corner.

##### 5. Roof

Wet 'scantle' laid random width Trevillett slate laid in diminishing courses.

$25 \times 50 \text{ mm}$  horizontal tanalised softwood battens spaced to suit slate coursing and fixed to vertical battens with stainless steel screws.  
 $50 \times 50 \text{ mm}$  vertical tanalised softwood battens at 400 mm centres coinciding with studs behind to provide continuous ventilation gap.  
Breather membrane.  
18 mm WBP plywood sheathing.  
60 mm mineral wool insulation fitted over rafters.  
 $200 \times 50 \text{ mm}$  tanalised softwood rafters at 400 mm centres.  
200 mm mineral wool between rafters.  
65 mm phenolic foam-backed plasterboard with integral vapour barrier taped and skimmed with paint finish.

##### 6. Roof eaves


$203 \times 203 \text{ mm} \times 46 \text{ kg UC}$  steel eaves beam.  
 $75 \times 50 \text{ mm}$  tanalised softwood upstand built off top of wall to support gutter.  
Code 4 lead flashing fixed to plywood below breather membrane and lapped over gutter lining.  
Black insect mesh to cover ventilation voids.

##### 7. Gutter

Fleece-backed reinforced PVC membrane gutter lining.  
 $175 \times 60 \text{ mm}$  box gutter made from 18 mm WBP plywood.  
Continuous EPDM membrane to external face of gutter.  
Zinc alloy facing (coated on the underside with a protective layer) folded over external face and ends of gutter with drip to line through with slate coursing.

##### 8. Window

Prefabricated box frame welded up from 550 mm wide  $\times$  12 mm thick mild steel plate fixed to steel structure at jambs.  
18 mm WBP plywood external sheathing on tanalised softwood subframe.  
Continuous EPDM membrane to external faces of projecting sheathing lapped behind breather membrane behind slates.  
Folded zinc surround to front face of window.  
Window frame made from  $60 \times 60 \times 4 \text{ mm}$  stainless steel angles.  
Window casement made from  $50 \times 50 \times 3 \text{ mm}$  stainless steel box sections.



Cut-away section through west corner showing roof and wall construction

Stepped double-glazed sealed unit silicone-bonded to frame consisting of 6 mm toughened outer pane, 12 mm air gap, 6.4 mm laminated inner pane with low-E coating.  
Removable zinc-clad WBP plywood panels to head, cill and jamb external reveals.  
12 mm thick Corian internal cill with 20 mm thick leading edge.

9. Rooflight

120 × 120 × 10 mm RSA (rolled steel angle) welded to 203 × 203 mm × 46 kg UC steel ridge beam.

Tanalised softwood carcassing to form 9000 × 900 mm rooflight opening.

Stainless steel rooflight frame.

Double-glazed sealed unit consisting of 10 mm self-cleaning toughened outer pane, 16 mm air gap, 12.8 mm laminated inner pane with low-E coating.

Electric roller blind.

10. Ridge flashing

Zinc alloy sheet (coated on the underside with a protective layer) flashed over heads of slates with mastic seal in between and held down with zinc clips at 400 mm centres.

Code 4 lead soaker behind zinc and slate junction.

Continuous EPDM waterproof membrane beneath zinc lapped over soaker.

25 mm thick tanalised softwood square-edged board deck at 5 degree pitch.

50 × 50 mm tanalised softwood firings at 400 mm centres to provide continuous ventilation gap.

Breather membrane.

18 mm WBP plywood sheathing.

Roof construction as 5.

This page intentionally left blank





Photo: Philip Vile



Photo: Philip Vile



Photo: Philip Vile



Photo: Philip Vile



Photo: Haworth Tompkins



Photo: Philip Vile

## The North Wall Arts Centre, Oxford

Architect: Haworth Tompkins

Structural Engineer: Price & Myers

St Edwards, a boarding school in Oxford, has constructed a new Arts Centre on the edge of its grounds so that it can be used by both the pupils and the wider public. The Centre is a conglomerate of old and new elements. A Victorian swimming pool has been converted for use as a 250-seat theatre at one end, the slope in the pool itself forming the seating rake. At the other a foyer, gallery, drama studio and dance studio are housed in a new structure. The north wall itself is an old brick boundary wall to the road that has been preserved and penetrated to make the entrance.


The new building sits on concrete strip footings. A 300-mm thick reinforced concrete first floor slab spans 10 metres between a concrete beam on the north side and a load-bearing concrete blockwork collar wall on the south side.

In the drama studio, the particle board floor is fixed to isolating battens with mineral wool between to restrict noise transfer to the dance studio below. The dance studio has a floating sprung floor consisting of several layers of flexible material with a vinyl top layer.


English oak shingles have been used to clad the upper storey and roof, while the lower storey and gables are clad with narrow oak slats. A full height oak-slatted screen can be slid across a large sliding window, which looks out over the school grounds from the dance studio. Sliding MDF blackout doors are hung internally across the windows on both floors.

Two floor-to-ceiling windows light the drama studio. Aluminium angles bonded to the rear of the inner pane of the double-glazed unit carry the load of the glass via galvanised angles back to the floor and wall. The outer pane oversails the inner pane, smeared with black silicone around its perimeter on the rear to conceal the means of support. A pressed aluminium flashing seals all four edges of the window. The flashing was made in two pieces with a horizontal joint at mid-height where the two pieces interlock. The suppression of the frame makes the glass appear to float outside the oak shingle cladding.







East-west section – 1:700




Ground floor plan – 1:700



North-south section 1 through auditorium – 1:300



North-south section 2 through foyer – 1:300



North-south section 3 through new building with detail section shown red – 1:300

#### Drawing labels:

##### 1. Foundations

Minimum 900mm deep mass concrete strip footings.

##### 2. External paving

200mm wide gravel strip along edge of building. Black tarmac with white chippings.

##### 3. Ground floor

45mm composite sprung floor system with vinyl surface.  
75mm floating screed with mesh reinforcement.  
20mm rigid insulation.  
DPM dressed up over plinth and under door frame.  
235 × 38mm concrete paving cill.  
150mm reinforcement concrete slab with 600 × 300mm thickening at edges.  
225 × 90mm reinforced concrete plinth along south edge.  
50mm blinding.  
150mm compacted hardcore.

##### 4. First floor

3mm sacrificial MDF top layer sealed with black emulsion paint.  
Acoustic semi-sprung floor comprising two layers 18mm tongued and grooved chipboard screwed to 50mm isolation strips supported on 50 × 50mm softwood battens.  
Services zone for horizontal distribution.  
50mm mineral wool acoustic insulation between battens.  
300mm thick reinforced concrete slab left exposed on underside.

##### 5. Typical ground floor wall

210mm thick load-bearing concrete blockwork collar wall comprising two leaves 100mm blockwork tied together with stainless steel wall ties.  
60mm rigid foil-faced insulation.  
Prefabricated timber cladding panels fixed through insulation into blockwork with Helifix stainless steel wall ties at 400mm centres.  
Panels comprise vertical sawn 40 × 15mm unsealed oak slats at 30mm centres fixed from rear with stainless steel screws to 50 × 25mm horizontal sawn oak battens at 600mm centres fixed through three layers of grey fibreglass mesh to 50 × 25mm vertical softwood battens at 400mm centres.

##### 6. Typical upper floor wall

210mm thick load-bearing concrete blockwork collar wall comprising 2 leaves. 100mm blockwork tied together with stainless steel wall ties.  
60mm rigid foil faced insulation.  
50 × 25mm vertical softwood battens at 400mm centres fixed through insulation into blockwork with Helifix stainless steel wall ties at 400mm centres.  
50 × 25mm horizontal softwood battens at 127mm centres.  
Unsealed oak shingles fixed to battens with stainless steel nails.

##### 7. Glazed door

210 × 460mm deep reinforced concrete beam over opening.  
120mm wide PPC (polyester powder coated) aluminium door frame with two sliding aluminium-framed glass doors with double-glazed sealed units.  
150mm deep × 2mm PPC folded aluminium flashing with extruded polystyrene insulation bonded to inside screwed to blockwork and concrete beam.


##### 8. External sliding timber screen

Painted galvanised steel door frame welded up from 70 × 70 × 8mm equal angles.  
Galvanised steel track cast into concrete for sliding door roller.  
48 × 38mm galvanised steel head restraint track bolted via brackets to continuous 100 × 100 × 10mm galvanised steel angle welded to 150 × 150 × 10mm galvanised steel angle bolted to concrete beam.  
Prefabricated timber panels comprising vertical sawn 40 × 15mm oak slats at 30mm centres fixed from rear with stainless steel screws to 50 × 25mm horizontal sawn oak battens at 450mm centres fixed to 50 × 40mm vertical softwood battens at 400mm centres adhesive fixed to steel frame.

##### 9. Roof

Oak shingles fixed to battens with stainless steel nails.  
50 × 25mm horizontal softwood battens at 127mm centres.





Cut-away section through south elevation of new building

50 × 25 mm vertical softwood battens at 400 mm centres fixed through insulation into blockwork.  
Breather membrane.  
105 mm rigid foil faced insulation.  
18 mm WBP plywood deck fixed to rafters.  
150 × 75 mm softwood rafters at 600 mm centres.

10. Window

2515 mm high × 1800 mm wide double-glazed sealed unit consisting of 6 mm clear toughened low E inner leaf, 16 mm cavity, 6 mm clear toughened outer leaf with black silicone butted oversails.

20 mm wide × 2 mm thick PPC aluminium glazing clips at 500 mm centres across top and bottom of glass.

Continuous back-to-back 127 × 51 × 6 mm and 38 × 19 × 6 mm mill finish aluminium angle frames silicone bonded to rear of glass.

Angle frame bolted to continuous vertical 125 × 75 × 8 mm galvanised steel angles fixed to blockwork with resin anchor bolts at 500 mm centres.

Continuous horizontal 200 × 150 × 12 mm and 150 × 75 × 8 mm galvanised steel angles fixed to first floor edge with resin anchor bolts at 500 mm centres.

PPC folded 2 mm aluminium flashing with pre-welded corners made in two pieces with joints in vertical lengths screwed to blockwork.

25 mm extruded polystyrene insulation bonded to inside of flashing.

18 mm Douglas fir faced plywood internal lining screw and plug fixed to blockwork.

11. Black-out shutters

56 mm thick painted MDF solid core top-hung sliding black-out shutter on galvanised track bolted to concrete beam over opening.

This page intentionally left blank



Photo: Kilian O'Sullivan/VIEW



Photo: Prewett Bizley Architects



Photo: Kilian O'Sullivan/VIEW



Photo: Prewett Bizley Architects



Photo: Prewett Bizley Architects

## Regent's Park Open Air Theatre, London

Architect: Prewett Bizley Architects

Structural Engineer: Price & Myers

Hidden amongst the trees in the grade 1 listed landscape of Regent's Park, The Open Air Theatre is a much loved London institution. During the summer months the Theatre puts on two Shakespeare plays, a musical and a children's production in a 1200 seat outdoor amphitheatre hidden amongst the trees in the picturesque park landscape.


The project includes new toilets for the theatre itself and a new bar/rehearsal area attached to the Robert Atkins Studio, a space for small performances and corporate events. The new facilities are conceived as an extension of the romantic landscape of the theatre, a series of magical grottoes and hollows surrounded by hedges and trees.

The toilet areas have red resin coated concrete floors spanning above the ground between mini-piles to minimise the impact on the roots from a nearby plane tree, a survivor from the original planting of Regent's Park in 1811. The toilets use water from a borehole in the Park for flushing and all the rainwater from the roofs is distributed via land drains into the surrounding planting.


The walls above ground are all timber studwork on a primary steel frame, sheathed with birch plywood. The roof is made from Douglas fir joists and Douglas fir faced plywood, exposed on the underside. Following the English tradition of park buildings the external elevations are clad with green stained tongued and grooved softwood boards and concealed by planting.

The cubicles themselves are made from 42mm laminated spruce panels, opening directly onto the landscape. Internally, the walls in wet areas are clad with phenolic-faced birch plywood so they can be easily cleaned. Elsewhere the walls are clad in laminated spruce panels. The female washing area has a glossy pink painted ceiling and its own window out into the park, a boudoir amongst the trees. Over the winter period and at night it is possible to close the whole facility up with roller shutters. Using lighting and simple materials in unusual ways the new interventions extend the magical atmosphere of the performance into areas of the Theatre which are usually more functional.







Cubicle partition plan & section details – 1:20




East-west section – 1:500



North-south section – 1:500



Upper level plan – 1:500



Site location plan – 1:2000

Drawing labels:

1. Foundations  
250mm diameter reinforced concrete piles.
2. Floor structure  
Galvanised UB (universal beam) frame (sizes vary) bolted down to tops of piles.  
Galvanised  $150 \times 75 \times 10$  mm RSA (rolled steel angle) welded to tops of beams where floor edges exposed.
3. Floor  
5mm coloured epoxy mortar finish with 95mm coved skirtings.  
140mm concrete slab.  
Profiled galvanised steel deck with angle upstands at edges bolted to steel frame.
4. Columns  
Galvanised  $80 \times 80 \times 5$  mm SHS (square hollow section) steel columns with painted finish.  
Guide tracks for roller shutters bolted back-to-back to columns.
5. Roof structure  
Galvanised  $203 \times 102$  mm  $\times$  23kg UBs (universal beam) generally.  
Galvanised  $200 \times 90$  mm PFC (parallel flange channel) edge beams to provide flat face for fixing roller shutter.
6. Roof  
Bituminous felt waterproof membrane.  
18mm plywood screwed to firing strips.  
Douglas fir firing strips screwed to tops of joists to create fall.  
 $225 \times 50$  mm Douglas fir joists at 400mm centres bearing on flanges of steel beams.
7. Roller shutter  
Electrically operated hollow-core aluminium roller shutters bolted to steel frame.  
 $250 \times 250$  mm pressed galvanised steel box cover.
8. Spine wall  
Two parallel timber framed stud walls with air gap in between for services and sound isolation.  
Each wall made from  $75 \times 50$  mm softwood studs with 75mm mineral wool insulation in between.  
Joints between sheathing boards, skirting and roof joists sealed with mastic for acoustic insulation.

9. Timber carcass

Timber carcasses made from softwood studwork to form frames for WCs, cisterns, urinals and wash troughs.  
Softwood painted matt black where visible between wall panel boards.

10. Wall panels in wet areas

18mm phenolic faced birch plywood panels secret-fixed to studwork with lost-head nails.  
18mm phenolic faced birch plywood removable panels secret-fixed to studwork using plastic clips.  
Edges of all panels stained to match phenolic face.  
10mm shadow gaps between panels for tolerance and to facilitate removal.

11. Cubicle partitions

1900mm high  $\times$  42mm thick laminated spruce panels cut to form doors and partitions between cubicles, all secret-fixed.  
Door frames jointed to partitions using full-height  $40 \times 12$  mm hardwood strip routed and glued into both panels.

12. Partition support

310mm long turned stainless steel rods with brushed finish resin-bonded into concrete floor 100mm back from door to support each partition (thickness 35mm where exposed, 12mm where embedded in panel and floor).  
Partition panel drilled and dropped onto support rod prior to rod being epoxy bonded into floor.

13. Partition brackets


$40 \times 40 \times 3$  mm galvanised steel angles screwed to back edge of partitions for fixing into studwork wall.

14. Female lighting trough

$250 \times 95$  mm lighting trough made from two 42mm spruce sides and 19mm laminated spruce panel bottom.  
Trough secret-fixed down into cubicle partitions to tie partitions and door frames together.  
Fluorescent batten luminaires laid continuously in trough to up-light ceiling.

15. Male lighting trough

$125 \times 95$  mm lighting trough formed behind plywood wall panel.  
Fluorescent batten luminaires laid continuously in trough to up-light ceiling.



Cut-away section through theatre toilets







Photo: Stephan Muller



Photo: Stephan Muller



Photo: Stephan Muller



Photo: Biq Architecten



Photo: Stephan Muller

## The Bluecoat Arts Centre, Liverpool

Architects: Biq Architecten

Executive Architects: Austin-Smith Lord

Structural Engineer: Techniker


The Bluecoat Arts Centre has been refurbished and extended with a new wing housing a performance space and four galleries. The core of the complex is Bluecoat Chambers, a school building dating from 1716, which is arranged around two courtyards. The new wing replaces some nineteenth century buildings in the south-east corner of the site.

Wire-cut bricks have been used as a deliberate new texture in the historic development of the original grade 1 listed school building. Every brick is laid in the same orientation such that only stretchers are visible on the long sides and only headers are visible on the cross walls. The bricks are stack-bonded and were intended to be load bearing but the contractor chose to construct the building with a concrete frame. The cross walls above first floor level are still load bearing but the rest of the brick walls are tied to in-situ cast concrete walls that have been left exposed internally.


The 7.4 m high cloister piers have concrete cores and the brickwork contains no reinforcement. A capping beam ties the piers together at the top and they are tied back to the main building at roof level by timber rafters. Areas of wall with no concrete core have been constructed with bed joint reinforcement in every third course.

At first floor the exposed concrete walls define a performance space. Vertical recesses in the brick end walls and cast into the concrete flank walls contain metal channel track ready for mounting performance lighting. Glazed openings to the cloister below have independent inner and outer frames with laminated glass to provide acoustic separation.


The roof and upper level walls are clad in pre-patinated copper on a plywood deck. A secret gutter lined with a single-ply waterproofing membrane runs along above the cloister piers. The brown copper, bronze anodised window frames and burnt orange bricks harmonise with the existing buildings to complete the garden courtyard.




East-west section through new building – 1:400



Second floor plan 1:1500



First floor plan 1:1500



Ground floor plan (new building shaded grey) 1:1500




North-south section through east wing – 1:750

Drawing labels:

1. First floor beam  
1575 × 440 mm exposed in-situ reinforced concrete beam spanning between piers.
2. Ground floor internal pier  
1115 × 328 mm stack-bonded brickwork pier with 8 mm raked mortar joints painted white internally.  
665 × 215 mm in-situ reinforced concrete column exposed internally.
3. Internal doors  
1565 mm wide × 2990 mm high white painted timber doors in two pairs sections folding back onto internal face of piers on offset floor pivots.
4. First floor  
22 mm thick oak board floor on 45 × 48 mm softwood battens at 360 mm centres on 5 mm impact absorbing foam.  
Stainless steel tray containing underfloor heating pipes suspended between battens.  
Mineral wool insulation between battens.  
300 mm thick in-situ reinforced concrete slab exposed on underside in ground floor gallery.  
Proprietary suspended ceiling system over cloister gallery with sprayed rough-cast acoustic plaster on 12.5 mm plasterboard.
5. Ground floor cloister pier  
1565 × 553 mm stack-bonded brickwork pier with 8 mm raked mortar joints.  
1115 × 215 mm in-situ reinforced concrete column concealed inside pier.  
123 mm cavity with 75 mm partial-fill mineral wool insulation.  
Vertical DPC lapped into window frame with mastic seal and dressed 150 mm over insulation.  
25 mm mineral wool insulation to jambs behind DPC.
6. External glazing  
1135 mm wide × 2900 mm high bronze anodised aluminium framed glass door with window above.

7. Glazing head  
225 × 150 mm in-situ reinforced concrete capping beam spanning between piers.  
Pre-oxidised copper fascia with welted seams on geotextile layer.  
18 mm WBP plywood deck on 80 × 50 mm softwood carcass with 80 mm rigid urethane insulation.  
225 × 150 mm folded copper sheet secret gutter prefabricated with 60 mm rigid insulation fixed to back and underside.  
18 mm WBP plywood soffit with weep hole slot against fascia board.
8. Cloister roof  
Pre-oxidised copper roof finish with welted seams on geotextile layer.  
18 mm WBP plywood deck.  
110 mm rigid urethane insulation.  
Vapour barrier.  
18 mm WBP plywood deck.  
150 × 50 mm treated softwood rafters at 450 mm centres.  
Sprayed rough-cast acoustic plaster ceiling on two layers 12.5 mm plasterboard on 30 mm battens fixed to rafters.
9. First floor external wall  
120 mm thick rigid urethane insulation between treated softwood ladder frames made from 50 × 50 mm battens to avoid cold bridge.  
Vapour barrier.  
215 mm thick in-situ reinforced self-compacting concrete wall.  
122 × 56 mm vertical recesses cast into concrete containing galvanised steel channel fixed via acoustic resilient layer at 1350 mm centres to support performance lighting.
10. Performance space internal windows  
Back-to-back 100 × 60 mm stainless steel window frames to form 2085 mm high × 665 mm wide acoustic glazed partition with internal blinds.  
Laminated acoustic glass in each frame.





Cut-away section through main gallery and cloister







Photo: Ioana Marinescu



Photo: Ioana Marinescu



Photo: Sergison Bates Architects



Photo: Sergison Bates Architects



Photo: Dewi Tannatt Lloyd

## Ruthin Craft Centre, Denbighshire

Architect: Sergison Bates Architects

Structural Engineer: Greig Ling


Ruthin's new Centre for Applied Arts sits next to a roundabout between the town centre and an industrial zone of large sheds. It is a single storey building housing three galleries, six artist studios, education workshops, a tourist information gateway, a shop and a café. Most of the functions have independent entrances on to a central courtyard with a wide overhanging roof around the edge that forms an ambulatory.

The site was once a railway yard and has a 2-metre layer of gravel over its surface underlain by peat and clay. Penetrating the gravel layer would have introduced the need for piled foundations so the ground floor slab was cast as a 250 mm thick ribbed raft directly on the gravel.


The walls are load-bearing insulated concrete panels, cast flat on site and tilted up into position, which helps distribute the load evenly across the raft. The surface of the ground floor slab was power floated and coated locally with a de-bonding agent so the wall panels could be cast directly against it with 300 mm high timber upstand formwork.

A 150 mm inner structural leaf, or wythe, was cast first with a central layer of reinforcing mesh. A layer of rigid polystyrene insulation with protruding kevlar wall ties was pressed into the wet concrete surface. A 65 mm thick rust-coloured concrete outer wythe was then cast on top, the outer face of which was partially treated with a roller and scratched to give it a subtle vertical texture. The textured areas help break down the scale of the walls and introduce a hand-crafted quality poignant to the building's function. After 72 hours the panels were lifted up into the vertical position and packed level on steel shims.


Oak framed doors and windows have been set flush with the concrete walls preventing a reading of its thickness. The roof above has a timber structure with a steel beam at each ridge or valley cantilevering out beyond the walls to support the wide overhang around the courtyard. The geometry meant the softwood carcassing forming the overhang roof and soffit had to vary around the perimeter. The zinc roof rises and falls, echoing the form of the surrounding Clwydian hills.



Ground floor plan – 1:800



Photograph of model




North-south section through galleries – 1:200

Drawing labels:

1. Ground floor  
2.5 mm linoleum on levelling compound bonded to screed.  
75 mm trowelled screed with mesh reinforcement.  
50 mm rigid polystyrene insulation.  
Liquid-applied DPM (damp proof membrane).  
250 mm thick reinforced concrete slab.  
Raft slab thickening to 800 mm at perimeter.
2. Typical wall panel  
65 mm coloured concrete outer leaf tied to inner leaf with kevlar ties.  
104 mm rigid polystyrene insulation.  
150 mm structural reinforced concrete inner leaf.  
Panels located on slab edge with stainless steel dowels, packed to correct level on steel shims and gaps packed with grout.
3. Slab edge at opening  
Liquid applied DPM over slab edge.  
50 mm extruded polystyrene perimeter insulation.  
150 mm reinforced concrete inner leaf of panel.  
Levelled in-situ concrete upstand in front of inner wall panel up to ground level.  
Flexible liquid applied DPM over panel and upstand from slab up to finished floor level.
4. Timber spandrel panel  
20 mm rebated oak board cladding.  
Aluminium drip fixed to underside of bottom board.  
130 × 50 mm softwood frame with 130 × 68 mm softwood cill member packed up off panel upstand and sealed with compressible sealant.  
18 mm WBP plywood sheathing.  
94 × 32 mm softwood studwork inner frame.  
94 mm mineral wool insulation between studs.  
18 mm plywood internal lining.
5. Timber shutter  
130 × 50 mm softwood frame with 68 × 20 mm oak strip externally to form rebate for shutter.  
100 × 20 mm rebated oak board cladding.  
Aluminium drip fixed to underside of bottom board.  
44 mm solid core.  
Continuous weather seal to all sides of rebate.
6. Fixed window  
130 × 32 mm vertical softwood mullions with 68 × 20 mm oak strip externally to form rebate for glazing.  
Double-glazed sealed unit consisting of 4 mm outer pane, 16 mm argon filled cavity, 4 mm inner pane with low-e coating and anti-UV coating.  
100 × 20 mm softwood internal glazing beads.
7. Door  
130 × 50 mm softwood frame with 68 × 20 mm oak strip externally.  
Double-glazed sealed unit consisting of 4 mm outer pane, 16 mm argon filled cavity, 4 mm inner pane with low-e coating and anti-UV coating.

- 83 × 18 mm oak door stop screwed to frame and pelleted to hide screws.  
44 mm solid core door.  
125 × 20 mm oak glazing beads to outer face of door.  
22 × 14 mm softwood glazing beads internally.  
Mill finish aluminium sheet kick plate adhesive fixed to outer face of door below glass.  
Aluminium drip adhesive fixed to underside of bottom board.  
100 × 15 mm proprietary threshold ramp and bottom seal.
8. Roof  
Standing seam zinc sheet fixed on clips through insulation to plywood.  
Breather membrane.  
200 mm insulation.  
Bituminous vapour barrier.  
18 mm plywood deck.  
250 × 50 mm softwood joists at 400 mm centres spanning between steel beams.  
Steel beams spanning from ridge to eaves.  
75 × 60 mm softwood battens fixed to underside of joists.  
1200 × 600 × 15 mm wood wool panels screwed to battens.
9. Roof overhang  
Standing seam zinc sheet fixed on clips to plywood.  
Breather membrane.  
18 mm plywood deck.  
200 × 50 mm softwood counter-battens at 600 mm centres with firings fixed on top.  
200 × 50 mm softwood joists at 600 mm centres spanning between steel eaves beam and concrete wall.  
Steel eaves beam.  
50 × 40 mm softwood battens fixed to underside of joists.  
26 mm deep pressed zinc interlocking soffit panels secret-fixed to battens.
10. Fascia  
50 × 40 mm softwood battens fixed to softwood blocking in web of steel eaves beam.  
18 mm plywood fascia board.  
Standing seam zinc sheet cladding fixed on clips to plywood.  
Ventilation gap behind plywood with insect mesh over openings.
11. Gutter  
Pressed zinc gutter supported on formed plywood and softwood battens.
12. Courtyard paving  
150 mm concrete slab with jet washed finish to expose aggregate.  
Two separating layers of 1200 mm gauge polythene.  
Sand blinding on compacted hardcore.





Cut-away section through roof and wall opening to courtyard



Photo: Peter Cook/VIEW



*Photo: Peter Cook/VIEW*

## Siobhan Davies Dance Centre Southwark, London

Architect: Sarah Wigglesworth Architects

Structural Engineer: Price & Myers

Design & Build Contractor: Design & Display Systems


Five twisting ribbons of sky-blue GRP (glass reinforced plastic) make up the roof of a new dance studio for the Siobhan Davies Dance Company. The studio has been built on top of a London Board school building from 1898, which has been completely refurbished to make a new headquarters for the Company.



*Photo: Sarah Wigglesworth Architects*


A steel structure has been built across the top of the two-storey building to provide an unobstructed 190 square metre space for rehearsal and performance. Pairs of steel portals span 11.5 metres across the space at 3.4 metre centres. One portal in the pair is a mirror image of the other about their centreline and they are bolted 500mm apart. Steel purlins span between the portals defining the twisting shape of the roof.

The roof finish is a shell of GRP panels, made off-site by laying glass fibre sheets over a mould and coating them with resin. The final mould is itself made from GRP from an original bent plywood mould made up by joiners. A moulding process was suggested by the roof's complex two-directional curves and because each panel could be repeated several times. Ridges on the rear and a downstand on all sides mean the panels only require intermediate support at joint lines above the purlins. Once fixed in place the GRP panels were sprayed with insulating foam on the inside to deaden the noise of rainfall. Further acoustic insulation is provided by a 5mm thick acoustic membrane laid over mineral wool. The roof soffit is finished in birch-faced plywood strips, cut in the workshop to a tapered profile and fixed to timber battens behind.



*Photo: Sarah Wigglesworth Architects*


Glazing is fixed in aluminium channels between the ribbons of the roof. Strips of fluorescent lighting are concealed above and below the rooflight windows to avoid a harsh transition from day to night. The billowing roof achieves the client's apparently opposing desires for an introspective space in which to dance under the sky.




Diagrams showing roof setting out – NTS



East elevation – 1:400



Dance studio section – 1:400



Dance studio plan – 1:400



Site location plan – 1:1500

Drawing labels:

1. Primary steel structure  
Paired curved 254 × 146 × 87 kg universal beam (UB) portals at 3365 mm centres bolted 500 mm apart.

2. Purlins  
100 × 100 × 10 mm equal angle (EA) purlins at varying centres spanning between primary steels and bolted to 10 mm thick mild steel cleats welded to UBs.

3. Fixing cleats  
310 × 60 mm folded mild steel cleats bolted to purlins to support roof panels.

4. Roof panels  
3.5 m long × 2 m wide prefabricated GRP (glass reinforced plastic) roof panels bolted through edge downstands to fixing brackets and cleats on purlins.  
Joints between panels filled with silicone sealant.  
Small drip channel cast into cill to channel rainwater to roof edge and avoid staining of leading edge.

5. Fixing brackets  
Mild steel angle brackets bolted to lower UBs to support roof panel cill, glazing cill channel and performance lighting bar.  
Mild steel angle brackets bolted to upper UBs to support roof panel top edge, fascia and glazing head channel.

6. Fascia  
200 × 200 × 5 mm thick prefabricated GRP fascia bolted through edge downstands to fixing brackets.  
Small drip channel cast into top of fascia to channel rainwater to roof edge and avoid staining of leading edge.

7. Roof insulation build-up  
100 mm acoustic insulation spray applied to rear of panels to deaden sound of rainfall.

5 mm thick Tecsound acoustic membrane with joints lapped 200 mm.  
100 mm mineral wool insulation.  
3 mm hardboard.  
Continuous vapour barrier.  
50 × 50 mm softwood battens adhesive fixed to purlin angles.

8. Ceiling  
3660 mm long × 12 mm thick birch faced plywood strips pre-cut to taper from 100 mm to 79 or 89 mm wide.  
Each strip arrived on site with intermittent blocks pinned and glued on the back. The next piece was pinned and glued to the previous one through these blocks.  
Once the whole ceiling was fixed the ends of the boards were cut to a neat line.


9. Internal fascia  
12 mm thick birch faced plywood fascia pinned and glued to softwood battens behind.

10. Rooflight window  
50 × 50 mm aluminium channel bolted to fixing brackets at top and bottom of rooflight opening. Four double-glazed sealed units make up each rooflight.  
6.8 mm laminated acoustic glass inner pane with acid etching on face 3 facing cavity.  
Argon filled cavity.  
6 mm toughened outer pane with low-e coating on face 2 facing cavity.

11. Performance lighting bar  
48.3 mm diameter curved galvanised steel circular hollow section (CHS) with welded lugs for bolting to steel roof beams via fixing brackets.  
Bar is sized to hang standard theatre lights.

12. Lighting  
Fluorescent strip lights fixed in recesses above and below rooflight window.





Cut-away section through dance studio rooflight



*Photo: Morley von Sternberg*



Photo: Morley von Sternberg



Photo: Morley von Sternberg

## Rich Mix, Bethnal Green, London

Architect: Penoyre & Prasad

Specialist Subcontractor: Taurus Littrow



Photo: Penoyre & Prasad

A moving screen of louvres adds a dynamic new façade to an arts centre in a converted 1960s garment factory. Located on the vibrant and evolving fringe where the City of London peters out into the gritty streets of Bethnal Green the Rich Mix aims to be a point of exchange between the extraordinary mix of cultures in the area.

Recording studios, a performance space and three cinemas are all acoustically isolated from the existing concrete structure using 'box-in-box' construction. To ensure acoustic separation of each function a new concrete slab has been cast on neoprene isolators over the existing floor. Independent walls have been built off this slab separated from a conventional partition wall with an air gap to make a free-standing room. A new fourth floor and roof have been added using a steel structure with profiled aluminium cladding. The original roof slab has been strengthened with a reinforced concrete topping to carry the additional weight of the acoustic floor of the bar/performance space above.


On the main street façade the louvre screen is suspended from steel brackets bolted to the new steel structure. The louvres are bolted to stainless steel rods that are restrained back through the existing precast panels to the concrete structure. Fixing locations for the brackets have been carefully positioned to avoid the weaker panel edges. Groups of twelve louvres can be remotely angled from inside each room so the changing external pattern is derived directly from the desires of the users.




Photo: Morley von Sternberg

The louvres themselves are made up from four anodised extruded aluminium pieces clipped to an extruded aluminium core. One of the underside pieces is anodised gold giving the façade a reflective shimmer when seen from below. The silver top surfaces can be angled to reflect light into the rooms or when the louvres are closed completely, images can be projected onto the façade.






Second floor plan – 1:800



Ground floor plan – 1:800



North-south section – 1:500

Drawing labels:

1. Existing building structure  
510 × 240 mm reinforced concrete columns at nominal 6.400 m centres along façade.  
340 mm deep reinforced concrete beams spanning back to next row of columns.  
310 mm wide × 360 mm deep reinforced concrete down-stand beam along façade.

2. Existing building external wall  
1400 mm high × 100 mm thick precast concrete spandrel panels impregnated with carbon-arrest sealant and painted with black masonry paint.  
40 mm air gap.  
600 mm high × 150 mm thick reinforced concrete up-stand wall.

3. Existing fins  
100 × 45 mm aluminium rectangular hollow section fins fixed to window mullions.  
New coloured polyester powder coated (PPC) pressed aluminium sheath fixed to existing fins with self-tapping screws.

4. Cornice bracket  
1400 mm long tapered 300 × 300 mm galvanised steel T-bracket bolted to internal stub bracket.  
Galvanised steel internal stub-bracket bolted to new steelwork.  
40 mm thick structural grade nylon thermal break spacer between T-bracket and internal stub-bracket.  
3150 × 1230 mm galvanised steel grating brises-soleil spanning between T-brackets.

5. Fourth floor steelwork  
305 × 305 mm steel universal columns at nominal 6.4 m centres bolted to existing fourth-floor concrete slab.

6. Fourth floor glazing  
Continuous window with drained PPC aluminium curtain walling frame.  
Double-glazed sealed units.  
PPC pressed aluminium flashing cill to cover existing concrete coping.

7. Fascia and roof cladding  
Profiled aluminium standing seam cladding.  
200 mm thick mineral wool insulation compressed to 165 mm.  
Liner tray.  
PPC pressed aluminium flashing between fascia cladding and new glazing.


8. Fourth floor  
Existing roof build-up removed.  
Existing concrete scabbled and 75 mm reinforced concrete topping applied to reinforce existing slab.  
Neoprene isolating battens.  
18 mm plywood.  
130 mm reinforced concrete slab with 40 mm granolithic screed ground off and sealed.  
140 mm concrete blockwork inner wall built up of slab.

9. Louvre hanger  
60 × 40 mm stainless steel box section drop rod suspended from steel tab on cornice bracket with adjustable stainless steel turnbuckle.

10. Stabilising brackets  
Folded stainless steel flat bracket bolted with resin anchors into existing concrete upstand via 90 mm diameter zinc plated spacer tubes inserted in core drilled holes in precast panels.  
100 × 50 mm stainless steel box section bolted to bracket and bolted to drop rod.

11. Louvres  
570 × 74 × 3070 mm long aluminium louvres arranged in two banks of six operated together by one motor.  
Louvre blades made up from four anodised extruded aluminium face plates clipped onto an extruded aluminium core.  
30 × 12 mm silver anodised aluminium link arm connecting six louvres together.  
Electric motor fixed to drop rod and link arms.  
Armoured cable to control unit set into window cill board internally.





Cut-away section through south façade and louvers



*Photo: Christian Richters/VIEW*



*Photo: Christian Richters/VIEW*

## MIMA, Middlesbrough

Architect: Designed by Erick van Egeraat  
Structural Engineer: Buro Happold

Middlesbrough's new Institute of Modern Art is a distinctive free-standing pavilion facing the town hall across the town's principal civic space Victoria Square. The main approach to the Institute is across the square, which was the subject of a redesign at the same time by Dutch landscape architects West 8.



*Photo: Designed by Erick van Egeraat*

Addressing the square is a four-storey glass enclosure that wraps around a white limestone wall to make a 15-metre high foyer space. Three different surface textures have been used to give the stone variation. Most are rough sawn while some are pitched and some are bush-hammered. The thickness of the individual pieces varies and the coursing is irregular to make the stone sizes appear random. Each stone piece is individually supported by dowels welded to galvanised steel brackets (stainless steel on the external walls), which fit into a proprietary channel system. The channels in turn are fixed to a steel structure behind.


In the foyer a full length gash slices the stone wall in two, marking the location of the main staircase. The top half is hung vertically from the roof on  $150 \times 75$  mm steel channels. The lower part has a steel truss structure that sits on the ground at the bottom of the stair and spans 24 metres to a second truss cantilevering off the main steel frame just inside the line of the glazing. The truss incorporates the first, second and third floor edge beams to tie the whole structure together.



*Photo: Designed by Erick van Egeraat*

A self-supporting aluminium curtain wall encloses the foyer, its mullions tied back to primary oval section steel columns to resist wind loads with steel brackets that were site welded to make up for the difference in tolerance between the curtain wall and the structural steelwork. The oval columns support steel roof beams that cantilever out beyond the curtain wall. Irregularly spaced stainless steel wires tie the roof edge down to the ground to resist uplift, requiring precise adjustment of the tension so the wires remain taut under snow load but do not exert significant bending in the roof beams under standard loads. A dancing line of suspended light tubes signal the presence of the Institute at night to the town across the square.





East-west section through staircase – 1:600

Drawing labels:

1. Steel columns

480 × 240mm oval shaped hollow steel columns at 2130mm centres.  
Two coats of MIO (micaceous iron oxide) paint finish.

2. Curtain walling

125 × 60mm PPC (polyester powder coated) proprietary aluminium mullions at 2130mm centres.  
90 × 230 × 12mm Y-shaped steel lateral support plates at 3000mm centres, site welded to oval columns to transfer wind load back to steel columns.  
Two coats of MIO paint finish.  
110 × 60mm PPC proprietary aluminium transoms at 3000mm centres.  
Double-glazed sealed units with 8mm toughened glass outer pane, 12mm air gap, 10.8mm laminated glass inner pane held in place with vertical proprietary curtain walling pressure plates.  
Black structural silicone horizontal joints.  
Remotely operated louvre vent in roof void over curtain wall for natural ventilation.

3. Roof structure

356 × 171mm UBs (universal beam) at 2130mm centres cantilevering off oval columns to form roof overhang.  
Three 203 × 133mm UBs spanning between primary beams above stone curtain, above curtain walling and at roof edge.

4. Roof ties

20mm diameter stainless steel cables at varying centres fixed to roof edge beam.  
Bottom of cable fixed to stainless steel post-tensioning anchor fixed into concrete strip foundation.

5. Roof

Single ply membrane on 80mm rigid insulation.  
32mm liner panel supported on purlins at 1000mm centres set to roof profile with proprietary strut system.  
Metal decking to span between primary structure as a working platform for roof installation.

6. Ceiling

1200 × 2130mm galvanised expanded mesh panels fixed to 82 × 41mm galvanised box sections at 1200mm centres spanning between primary structural members.

7. Roof edge

Single ply membrane on 18mm marine grade ply.  
225 × 50mm tapering structural timber supports with galvanised brackets to secondary beams.  
200 × 300 × 6mm painted steel edge trim.

8. Stone curtain upper section

Primary structure consisting of vertical 150 × 75mm PFCs (parallel flange channel) at

2130mm centres, horizontal 150 × 75mm PFCs at 2860mm centres and 203 × 203mm UC (universal column) bottom cord.

Horizontal 142C13 galvanised steel light gauge sections with toes toward each other at 1000mm centres.

Proprietary galvanised steel (stainless steel externally) stone support system with vertical toothed channels at 600mm centres fixed to horizontal structure to accept adjustable dowel anchors.

1200mm long × 40/50/60mm thick × various heights Turkish limestone with nominal 3mm open joints.

Three surface textures used – rough sawn, bush-hammered and pitched.

9. Stone curtain lower section

Primary truss with 250 × 150mm RHS (rolled hollow section) top cord and 452 × 152mm UB bottom cord.

Continuous 95mm slot in stone, for continuous cold cathode light over stair.  
Stone as above.

10. Balustrade

15mm thick toughened glass balustrade.  
100 × 12mm continuous clamping plate fixed with M16 bolts at 500mm centres to steel angle bolted to steel structure.

11. Handrail

20 × 60mm polished stainless steel flat uprights with 60mm continuous stainless steel flat top rail.  
150 × 70mm profiled black cherry handrail with recess in underside screwed to top rail.

12. Staircase

30mm thick Italian sandstone stone treads and risers bedded on 3mm thin bed adhesive.  
Levelling screed applied to surface of in-situ concrete stair for a surface regularity of SR1.  
1800mm wide in-situ concrete staircase spanning between floor landings with intermediate support at landings.  
12.5mm plasterboard fixed to underside of stair on furring channels, with skim coat and paint finish.

13. Typical floor (upper floors) overall build-up 120mm

3–5mm liquid resin finish.  
50mm thick floating polymer modified fibre reinforced screed.  
70mm rigid insulation with underfloor heating.  
130mm concrete slab on galvanised steel deck spanning between steel beams.

14. Suspended ceiling

Proprietary suspended ceiling system.  
12.5mm plasterboard with skim coat and paint finish.




Second floor plan – 1:900




Ground floor plan – 1:900





Cut-away section through foyer roof, stair and glazing



*Photo: Brisac Gonzales*



Photo: Brisac Gonzales

## Multi Purpose Hall Aurillac, France

Architect: Brisac Gonzales Architects

A ribbon of precast concrete panels inlaid with glass blocks wraps around a new hall known as Le Prisme in the Auvergne region of central France. Essentially a black box, the 4500 seat hall will be used for theatre, concerts, fairs and sports events. The strong band of back-lit panels breaks the lumpen mass of the hall in two horizontally giving it a dynamic form and an identity at a scale commensurate with its function.

Up to mid-height, the hall has a structure of in-situ concrete walls that are exposed internally. Above this, a precast system of T-shaped columns at 11 m centres and 250 mm thick reinforced concrete wall panels takes over. Roof trusses spanning the full 40 m width of the hall span onto each column. The trusses sit on elastomeric pads to isolate them acoustically from the walls. The roof itself acts as an acoustic damper. A standard insulated metal deck system is raised off the purlins on brackets with a second layer of mineral wool acoustic insulation beneath. The gap between the two is ventilated to prevent condensation and the junction with the walls is sealed.

Externally the upper half of the building is clad in a 9 metre-high band of precast glass reinforced concrete panels set out in long curves. Each 50 mm thick panel is reinforced in two directions with stainless steel rods to avoid future corrosion problems. The panels are inlaid with over 25,000 pyramidal glass blocks with a Fresnel lens surface, which both reflects and refracts light. The joints between the panels are sealed with rubber wiper seals to prevent light leakage. A structure of galvanised steel members supports the panels off the main concrete walls and forms a void in between for maintenance access. During the day, the sun glints off the white concrete and outer faces of the blocks while at night the façades transform into shimmering curtains of coloured light.



Photo: Brisac Gonzales



Photo: Brisac Gonzales






Photo: Brisac Gonzales







Site plan 1:4000



Detail section through typical concrete panel showing glass lens and fixing bracket – 1:5



North-south section – 1:1500



Ground floor plan – 1:1500

Drawing labels:

1. External wall

800 × 300 mm T-shaped precast reinforced concrete columns at nominal 11 m centres.  
250 mm thick precast reinforced concrete wall panels bolted to columns.  
175 mm void for acoustic attenuation with horizontal closers to prevent stack effect air movement in cavity.  
100 mm mineral wool thermal insulation.  
Vapour barrier.  
25 mm black wood-fibre acoustic panel inner lining.

2. Roof trusses

Steel roof trusses at 11 m centres tapered to form 3% fall to roof (3970 mm high at centre of roof) made up from:  
HEA 300 (290 × 300 mm I-section) top chord.  
HEA 200 (190 × 200 mm I-section) diagonal braces.  
IPE 180 (180 × 91 mm I-section) vertical members generally.  
HEA 260 (250 × 260 mm I-section) vertical end member.  
HEA 300 (290 × 300 mm I-section) bottom chord.

3. Roof trusses bracket

Steel bracket bolted to precast concrete wall. Truss rests on and is bolted to 300 × 300 mm elastomeric isolation pad which is bolted to the fixing bracket.

4. Roof

Multi-layer bituminous waterproof membrane.  
100 mm mineral wool insulation mechanically fixed to metal deck.  
56 mm deep galvanised steel deck supported on 200 × 50 mm brackets off purlins.  
Minimum 100 mm ventilated air gap.  
80 mm thick mineral wool acoustic insulation panels on profiled galvanised steel tray.  
Proprietary suspended ceiling system hung from tray with 600 × 600 mm acoustic absorbent panels between purlins.  
IPE 360 (360 × 170 mm I-section) purlins at nominal 2.5 m centres.

5. Roof edge

500 × 370 mm folded galvanised steel gutter supported on 600 × 500 mm galvanised steel

angle brackets bolted to precast wall at 1.5 m centres.

Galvanised steel edge capping fixed to roof edge and overlapped into gutter.  
End of acoustic panels wrapped in insulation.  
Gap between acoustic panels and top of concrete wall sealed with expanding foam.

6. Outrigger structure

IPE 360 (360 × 170 mm I-section) horizontal galvanised steel beams fixed back to concrete wall via horizontal galvanised steel struts with diagonal bracing.

7. Vertical rails

IPE 120 (120 × 64 mm I-section) galvanised steel vertical rails at 1500 mm centres bolted to horizontal out-rigger beams.

8. Brackets

230 mm long 50 × 50 mm galvanised steel angles with slotted holes welded to vertical rails.  
110 × 50 × 6 mm thick folded stainless steel brackets with slotted holes bolted to stainless steel sockets cast into cladding panels.  
Brackets bolted to angles on vertical rails using M12 stainless steel bolts via 28 × 14 mm slotted holes to allow alignment tolerance with neoprene isolation washers to prevent bimetallic corrosion.


9. Cladding panels

1490 × 1490 × 50 mm thick precast glass-reinforced concrete cladding panels with four M12 stainless steel fixing sockets cast into rear.  
160 × 160 mm pyramidal cast glass blocks cast into concrete panel at 300 mm centres.  
6 mm stainless steel reinforcement bars in both directions between glass blocks.  
Two M12 sockets cast into top edge of panel for lifting into position.

10. Lighting

Wide angle projector luminaires mounted on concrete wall in two offset rows at top and bottom of façade.  
Lamps have a fixed colour and each colour is on a separate circuit.





Cut-away section through façade and roof edge



*Photo: Niall McLaughlin Architects*



Photo: Niall McLaughlin Architects




Photo: Niall McLaughlin Architects



Photo: Niall McLaughlin Architects



Photo: Niall McLaughlin Architects

## ARC, Hull

Architect: Niall McLaughlin Architects

Structural Engineers: Price & Myers

M&E Engineers: XCO2 Conisbee


The ARC is an education resource intended to showcase building and environmental developments arising from regeneration activities in the Humber region. It is also a learning resource in itself, a building that stimulates debate, provides an exciting venue for events and is a dynamic landmark in Hull's city centre. It is intended to be dismantled and moved to different locations over a 20-year period, evolving as it goes to incorporate advances in construction and environmental technology. 'I'd like to think that in 20 years time it might not look remotely like this', says McLaughlin.

The building is engineered to be carbon neutral by generating the same amount of energy as it uses through renewable sources. An array of photovoltaic panels and wind turbines produce electricity and a wood pellet boiler supplies hot water to an underfloor heating system. Fresh air is drawn in at the eaves across an external gutter with water misters to provide evaporative cooling when necessary.


To enable the structure to be dismantled and reassembled, the foundations are a series of precast concrete padstones that sit on the ground. The floor is made from prefabricated steel framed 'cassette' units bolted together and filled with ballast to resist wind uplift. The roof is a lean-to structure of 24 steel beam rafters spanning from an eaves beam along the edge of the floor cassettes to a ladder truss at the ridge. Five steel framed 'caravans' containing offices, WCs and plant rest on their own concrete padstone foundations and support the ladder truss above.

Translucent GRP roof panels 13m long are fixed to the steel rafters forming a low thermal conductivity waterproof skin. A reflective, shimmering surface of curved aluminium mesh is fixed to the underside of the rafters and to the outside of the GRP panels as solar shading. In one event images of the sea, filmed in real time, were projected onto the mesh screen outside, reminding passers-by of the city's maritime past.







Rendered view from south end



Section – 1:500



Site plan – 1:500



Cutaway section through roof eaves

Drawing labels:

1. Padstone foundations  
900 × 900 × 125 mm thick concrete padstones at between 2.1 m and 2.8 m centres on compacted ground.  
Adjustable height steel pedestal on each padstone to allow levelling of floor cassettes.
2. Floor cassettes  
Prefabricated floor cassette with 152 × 76 mm steel channel edge frame on three sides for bolting to adjacent cassettes.  
203 × 203 mm universal column eaves beam on roof eaves edge to support roof steels.  
125 × 50 mm light gauge steel channels spanning between edge steels.  
12 mm WBP plywood sheathing screwed to channels on top and bottom faces.  
Voids filled with broken brick ballast to give weight to resist wind uplift.
3. Built-up floor  
100 mm thick rigid insulation laid between softwood studs.  
Underfloor heating pipes.  
18 mm WBP plywood floor screwed to softwood studs.  
2.5 mm linoleum floor finish adhesive fixed and wrapping up vertical face of eaves upstand.
4. Desk  
30 mm MDF desk with fold-down top finished with high gloss 2-pack toughened cellulose paint fixed to eaves upstand.
5. Gutter  
1000 × 250 mm deep stainless steel troughs in 4 m lengths bolted together to form gutter.  
150 mm wide aluminium ventilation grille with insect mesh set into plywood soffit over gutter.  
Ultraviolet filter in eaves upstand treats incoming air to kill bacteria.
6. Steel roof structure  
305 × 165 mm × 40 kg universal beam (UB) rafters at 1 m centres bolted to 700 × 200 mm steel connector plates bolted to eaves beam on floor cassettes.  
Bottom flange and lower half of web cut off where beam protrudes through envelope at eaves.

Bottom flange cut off where beam protrudes through envelope at top.  
305 × 102 mm × 31 kg UB purlins bolted between beams at minimum 1.8 m centres.

7. Translucent roof panels  
13 m long × 1 m wide × 80 mm thick translucent profiled GRP panels joined with proprietary metal capping strips.

8. Mesh roof panels  
1 mm thick marine grade aluminium mesh with channel frames to long edges fixed above and below roof steels over full height of roof.  
3 mm neoprene isolation strips full length between aluminium and polycarbonate/steel.


9. Steel ladder beam  
Steel ladder beam welded up from 90 × 50 mm rectangular hollow section (RHS) top and bottom members and 90 × 50 mm RHS verticals at nominal 600 mm centres.  
Roof steels bolted via cleats to top of ladder beam.

10. Glazing  
Polyester powder coated aluminium glazing bars fixed to face of ladder beam and to 60 × 40 mm RHS frames on sides of caravans.  
Double-glazed sealed units with toughened outer pane, argon filled cavity and laminated inner pane.

11. Aluminium flashing  
Polyester powder coated aluminium flashing with joints lapped and sealed with butyl sealant.

12. Caravans  
Five 'caravans' sitting on concrete padstones supporting ladder beam above.  
Each caravan has a steel carcass welded up from 60 × 60 mm square hollow sections (SHS).  
150 × 50 mm softwood studwork screwed to steel carcass and infilled with mineral wool insulation.  
12 mm birch faced plywood internal finish with vapour barrier.  
18 mm WBP plywood stressed skin outer sheathing with blue pigmented fibreglass resin finish.





Cutaway section through top of roof



*Photo: Sutherland Hussey Architects*





Photo: Sutherland Hussey Architects



Photo: Sutherland Hussey Architects



Photo: Sutherland Hussey Architects



Photo: Sutherland Hussey Architects




## Resource Centre Grizedale Forrest Park, Cumbria

Architect: Sutherland Hussey Architects  
Structural Engineer: Burgess Roughton


Grizedale Forrest Park is the headquarters of the Forestry Commission in the north-west of England. The Commission has a holistic vision for the 2500 hectare park which aims to create opportunities for visitors, local communities and businesses. In 2002, Sutherland Hussey won a competition to develop a masterplan for the whole estate, the first phase of which is a new Resource Centre that provides facilities for schools and community groups. The Centre consists of a new structure for the main classroom on the southern flank of an existing stone building that has been adapted for support spaces.

The classroom has a pitched roof rising to a 7.5m high glazed façade commanding spectacular views down the dale. Six inverted Douglas fir trusses carry the roof. To stabilise them in transit, and while they were lifted into place, they were assembled in softwood cradles which were cut away on site. On the south façade the roof trusses are carried on a flitched timber truss that spans the whole width of the building between two flitched columns. Below the truss a deep bay window is formed with a steel structure hung off the truss at the top and cantilevered off a concrete blockwork plinth at the bottom. In order to avoid intermediate columns beneath the truss the side walls of the classroom have additional bracing at high level so the south façade is effectively open in structural terms.


Above the bay window oak framed glazing has been fixed to the face of the truss. The glazing has a screen of timber strips sandwiched between the panes of glass to limit solar gain. Above the façade truss a line of solid timber opening flaps provide ventilation to the space. The roof is clad with cedar shingles which wrap down the timber framed upper parts of the flank walls and project forward in a cowl to shade the south façade glazing. Rather than closing the ventilation gaps with mesh a continuous slot has been left open to allow a colony of bats resident in the roof of the existing building to roost in the new roof.



Diagrams showing structural build-up



North-south section – 1:500



Ground floor plan – 1:500

Drawing labels:

1. Foundation

1850 × 600 mm reinforced concrete strip footing.  
215 mm dense concrete blockwork inner leaf supporting floor slab edge with bituminous tanking membrane applied to outer face.  
215 mm dense concrete blockwork outer leaf.  
25 mm cavity filled with lean-mix concrete up to DPC level.

2. Ground floor

129 × 22 mm tongued and grooved white oak floorboards with oiled finish.  
75 mm sand/cement screed with mesh reinforcement.  
75 mm rigid insulation.  
150 mm reinforced concrete ground-bearing slab.  
Bituminous tanking membrane.  
Sand blinding on compacted hardcore.

3. Façade truss

C24 grade Douglas fir façade truss spanning 10 m between 300 × 400 mm C24 grade Douglas fir flitch columns at either end.  
300 × 320 mm top boom with central steel flitch plate.  
300 × 320 mm bottom boom with central steel flitch plate.  
200 × 250 mm vertical struts.  
12 mm diameter tensile rod cross bracing bolted to flitch plates at nodes.

4. Inverted roof truss

Six C24 grade Douglas fir roof trusses spanning from south façade truss to reinforced concrete upstand in north wall at 1990 mm centres.  
300 × 125 mm top member.  
175 × 125 mm diagonals.  
300 × 125 mm bottom member.  
150 × 125 mm central post.  
Timber members planed and sanded all round.  
10 mm stainless steel plate connectors between members fixed with countersunk bolts.

5. Roof

Triple lapped 400 mm cedar shingles fixed to 38 × 19 mm treated horizontal battens at 95 mm centres.  
38 × 25 mm treated counter-battens aligned with purlins.  
Breather membrane.

18 mm plywood sarking board.

60 mm rigid urethane insulation.

100 × 50 mm treated softwood purlins.

50 mm rigid urethane insulation between purlins.

Vapour barrier.

144 × 16 mm tongued and grooved redwood soffit boards fixed to battens at 350 mm centres fixed to purlins.

Vacuum treated with fire retardant.

6. Roof edge

131 × 106 mm profiled cedar edge capping with 37 × 25 mm rout in back face to slot over and protect top of shingles.

20 mm ventilation gap below capping left open to allow access for bats.

Roof breather membrane dressed down and fixed to front of outrigger rafters.

270 × 19 mm oak fascia board.

144 × 30 mm American oak tongued and grooved soffit boards fixed to battens at 350 mm centres suspended below rafters at an angle to allow any moisture to drain out.

7. High level vents

65 × 65 mm oak window frame with 270 × 125 mm cill.

Opening vent panels made from 50 × 38 mm softwood frame with 18 mm oak veneered exterior grade plywood outer sheathing and 12 mm oak veneered plywood inner lining.

38 × 38 mm oak strips screwed and glued to plywood panel from behind.

8. Upper windows

300 × 132 mm oak head and cill supported off façade truss on continuous stainless steel Z-section at cill.

300 × 69 mm oak mullions at varying centres.

30 mm double-glazed sealed units with interstitial timber grid and self-cleaning coating. External oak beads flush with face of mullion (sizes vary to allow installation from outside).


9. Plinth

140 mm concrete blockwork inner leaf with bituminous tanking membrane applied to outer face.

25 mm cavity filled with lean-mix concrete up to DPC level.

150 mm Grizedale slate wall tied to 100 mm concrete blockwork with stainless steel ties.





Cut-away section through south façade

10. Lower window cill structure

Galvanised steel frame made from  
100 × 75 mm angles bolted to extended flitch  
plate of bottom member of façade truss.

11. Lower window cill

18 mm oak veneered plywood inner lining.  
Vapour barrier and cill DPC.  
140 × 50 mm softwood studwork frame.  
140 mm mineral wool insulation between studs.  
18 mm oak veneered exterior grade plywood  
deck fixed in steel angle frame.

12. Lower window roof structure

Galvanised steel frame made from  
100 × 75 mm angles bolted to extended flitch  
plate of bottom member of façade truss.  
200 × 90 mm PFC (parallel flange channel)  
gutter welded to outer face of frame.  
Pressed metal gutter lining.

13. Lower window roof

Single ply roofing membrane.  
Tapered rigid insulation.  
Vapour barrier.  
18 mm plywood deck fixed into steel angle  
frame.  
50 × 38 mm softwood frame with 38 mm  
insulation in between studs.  
18 mm oak veneered plywood inner lining.

14. Lower window

200 × 80 mm oak posts at 1990 mm centres  
fixed to upper and lower structure via steel  
brackets.  
24 mm double-glazed sealed unit.  
35 × 20 mm oak capping bead.  
221 × 91 mm cedar fascia fixed to steel  
structure at head, cill and sides of window with  
mitred corner joints.

This page intentionally left blank



*Photo: Edmund Sumner/VIEW*






Photo: Grimshaw



Photo: Grimshaw



Photo: Grimshaw



Photo: Edmund Sumner/VIEW



Photo: Edmund Sumner/VIEW

## Thermae Bath Spa Bath

Architect: Grimshaw Architects


Stone supply & installation: Bath Stone Group

A succession of baths have been built since Roman times to take advantage of the mineral-rich hot springs beneath the city of Bath, most significantly in the Georgian period when Bath was the most fashionable resort in England and from when much of the present day city survives. Following a bather's death from meningitis in 1978, however, the public baths closed. In 2006 a new spa complex opened enabling people once again to take the waters, albeit with much more stringent sanitary arrangements. The new spa is a cluster of new and refurbished buildings including the Hot Bath by John Wood the Younger and the Cross Bath by Thomas Baldwin and John Palmer.


The new building contains two bathing pools fed with water from the hot-springs. A rooftop pool sits on top of a Bath stone cube containing treatment facilities, held up on four mushroom columns emerging from a ground level pool. Plant is crammed into two basement levels surrounded by secant piled retaining walls. The mushroom columns were cast in-situ using glass reinforced plastic (GRP) formwork to give a smooth finish.

The roof-top pool is concrete with a hydrophobic and pore-blocking Ingredient to make it waterproof. A paint-on epoxy coating provides a further waterproof layer, although problems with it peeling off contributed to a 3-year delay on the project. The cube walls are stack-bonded Bath stone ashlar, cut from deep base strata in local mines. Steel and glass bridges span between the cube and the surrounding listed buildings. A glass skin wraps around the cube, suspended from the second floor slab on stainless steel tension rods and restrained against wind load by  $300 \times 200$  mm rectangular hollow section (RHS) posts which also help prop the terrace above.


The treatment areas have small circular glass windows providing daylight and limited views out while maintaining complete privacy. They sit flush with the stone on the outside and are lined inside with GRP cones. Massage and steam rooms are enclosed with curved 15 mm toughened glass held by stainless steel clamping plates top and bottom. Precast white concrete benches conceal lighting that glows through the steam-filled rooms.




Roof plan – 1:500



Second floor plan – 1:500



Ground floor plan – 1:500



East-west section through new building and Hot Bath – 1:500

Drawing labels:

1. Primary structure

Four reinforced concrete mushroom columns cast in-situ with fibreglass formwork. Epoxy paint finish.

2. Roof-top pool

Epoxy based paint system in pool areas. 200 mm thick reinforced concrete slab with waterproof additive.

3. Pool edge

700 × 380 mm precast concrete edge units with integral drainage channels. 500 mm wide solid Vitrathene polyethylene grating with specially designed anti-slip grooves and curved profiles.

4. Roof

300 × 900 × 20 mm thick Kashmir white granite paving slabs with flamed finish and sealant coating. 50 mm thick extruded polystyrene insulation. Minimum 90 mm thick proprietary quick-drying screed laid to fall. Underfloor heating pipes to prevent ice forming in winter. Solvent-free polyurethane-based waterproof membrane lapped up and sealed against precast edge units. Drain outlet as secondary protection and to allow any failure in the primary waterproofing to be identified. 200 mm thick reinforced concrete slab with waterproof additive.

5. Roof level balustrade

Laminated glass balustrade comprising 12 mm thick toughened inner layer, 1.5 mm interlayer and 12 mm thick toughened outer layer with acid etch effect to internal face. 60 mm diameter satin finish stainless steel handrail. 200 × 150 × 15 mm galvanised mild steel (MS) angle bracket bolted to concrete. 150 × 150 × 15 mm galvanised MS clamping angle.

6. Stone wall

1063 × 502 × 75 mm thick Bath stone ashlar with 8 mm lime mortar joints recessed to a depth of 10 mm.

Stainless steel shelf angles at each floor level to support stone.

Proprietary grade 316 stainless steel adjustable dowel and anchor system to restrain each stone.

45 mm air gap.

55 mm water repellent rigid glass mineral wool insulation.

Asphaltic membrane liquid applied to face of concrete.

Vertical mineral wool cavity barriers as fire stops at centrelines of cube.

175 mm thick reinforced concrete wall.

7. Windows

325 mm diameter hole cast into concrete wall. 220 mm diameter hole cut in stone.

Conical glass reinforced plastic (GRP) reveal with preformed DPM cloak fitted around opening.

190 mm diameter × 26 mm thick sealed double-glazed lens unit bonded to stainless steel ring with dowel fixing to rear of stone cladding in sealant bed to seal against stone façade.

Grade 316 stainless steel circular collar and GRP cone dressed to interior textured render wall finish.

8. Second floor

20 mm thick Kashmir white granite stone paving slabs with flamed finish and sealant coating.

Screed with underfloor heating.

50 mm thick extruded polystyrene insulation.

200 mm thick reinforced concrete slab.

9. Bench


140 × 540 mm precast reinforced white concrete bench units with concealed peripheral low voltage led lighting.

10. Pod glazing

15 mm thick curved 2850 mm diameter toughened/laminated glass.

Grade 316 stainless steel bottom channel bolted to screed.

Stainless steel top channel bolted into recess in column head with galvanised steel channel secondary support structure above suspended ceilings.



Cut-away section through west façade at second floor and roof levels

11. Terrace

300 mm wide random coursed 20 mm thick Kashmir white granite paving slabs with flamed finish and sealant coating.  
50 mm thick extruded polystyrene insulation.  
Minimum 90 mm thick proprietary quick-drying screed laid to fall.  
Underfloor heating pipes to prevent ice forming in winter.  
Proprietary single ply waterproof membrane with welded joints lapped up and sealed against anchored edge units.  
Drain outlet with secondary inlet bonded to membrane to collect water that has passed through finished floor.  
200 mm thick reinforced concrete slab.

12. Terrace balustrade

Laminated glass balustrade comprising 10 mm thick toughened inner layer, 1.5 mm interlayer and 8 mm thick toughened outer layer with acid etch effect to internal face.  
245 × 78 × 4 mm gauge folded stainless steel handrail with mild steel louvre to underside.  
Cold cathode lighting tube.  
160 × 80 × 8 mm rectangular hollow section (RHS) mullions at 1.5 m centres.  
48 mm diameter stainless steel tube welded to 10 mm plate screwed to top of mullion.

Glass bolted to 98 × 70 × 8 mm half-round lugs welded to mullions.

13. Secondary steel structure

300 × 200 mm galvanised steel posts at 4.5 m centres to assist in supporting terrace above and provide wind bracing to glazing.  
Post bolted to 203 × 102 mm preformed welded and galvanised MS bracket at head bolted into slab.

14. Glazing

Outer pane comprises 6 mm heat-soaked glass, 1.5 mm PVB interlayer, 6 mm heat-soaked glass.  
16 mm air gap.  
Inner pane comprising 8 mm toughened glass, 1.5 mm PVB interlayer, 10 mm toughened glass.  
Vertical aluminium carrier frame bolted to 54 × 50 mm aluminium mullion with two 40 × 12 mm aluminium stiffeners.  
12 mm diameter stainless steel tensionable rods bolted via steel bracket to slab to support glazing below.  
Glazed units supported by proprietary cast stainless steel spider fixings.  
12 mm wide black silicon seal joints to prefabricated sealed glazed units (maximum size 3558 × 1770 mm).



This page intentionally left blank



*Photo: Tim Griffith*



Photo: Denton Corker Marshall



Photo: Tim Griffith

## Civil Justice Centre Manchester

Architect: Denton Corker Marshall

Structural, Mechanical & Electrical Engineer: Mott MacDonald



Photo: Denton Corker Marshall

Manchester's new Civil Justice Centre contains 47 court rooms, 75 consultation rooms and is the Headquarters for the Ministry of Justice in the Northwest. The fiendishly complicated separate circulation requirements of a courthouse are resolved by dividing the floors into four strips in plan, an atrium on the west façade, then public circulation, then the courtrooms and finally the judges offices on the east façade. These divisions are expressed by changes of material and set-backs in plan and section. The 16-storey steel framed building is naturally ventilated with air taken in through wind scoops in the side of the atrium.

At the north and south ends courtrooms project out beyond the main building frame. Double columns at the end of the main frame provide seatings for 12 metre high prefabricated trusses which were craned into position and held with temporary bracing until the floors could be cast. Tension forces at the top of the trusses and compression forces at the bottom are distributed back to the building's concrete core through composite steel deck concrete floors.


Double-skinned façades on all three sides of the projecting volumes provide both acoustic isolation and environmental control. The inner skin is supported via a secondary structure of steel ladder beams bolted to the primary structure at each floor level. Insulated aluminium framed infill panels span between the steel beams. The steel and aluminium frames are clad with coloured 3mm aluminium sheets on the outside and galvanised steel sheets on the inside.




Photo: Denton Corker Marshall

The outer skin is laminated glass hung from galvanised steel beams bolted back to the secondary structure at the top. Stainless steel tension rods are bolted to galvanised steel struts at the bottom bolted back to the secondary structure. An intermediate stainless steel strut at mid-height braces the glazing against wind loads. A random pattern of colours on the inner skin interacts with reflections of the sky to give an ephemeral depth to the façade.






Level 7 floor plan – Scale 1:1000



North-south section – 1:1000



Site location plan – 1:2000

Drawing labels:

1. Structural steel frame  
356 × 406 mm × 287 kg UC (universal column) column.  
457 × 191 mm × 67 kg UB (universal beam) edge beams.  
457 × 191 mm × 74 kg UB floor and roof beams at 2840 mm centres.  
All steelwork clad with 30 mm 'Class O' fire encasement board to provide 2 hour fire resistance.

2. Roof  
600 × 600 × 50 mm concrete pavers as ballast on 15 mm plastic spacer supports.  
Geotextile membrane.  
160 mm extruded polystyrene insulation.  
7 mm rubber-modified bitumen waterproof membrane applied to concrete and up vertical face of angle with termination bar at top.  
145 mm thick reinforced concrete slab on profiled galvanised steel deck.  
400 × 100 × 2 mm galvanised steel angle screw-fixed to concrete to form upstand.  
Concealed grid MF suspended plasterboard ceiling.

3. Floor  
Proprietary raised access floor system consisting of 600 × 600 × 32 mm chipboard core with galvanised steel shell on galvanised steel adjustable pedestals to create 375 mm service zone.  
145 mm thick reinforced concrete slab on profiled galvanised steel deck.  
3 mm thick aluminium soffit panels with 120 mm mineral wool insulation fixed to aluminium secondary support system bolted to primary steelwork.

4. Secondary structure  
100 × 100 × 7 mm SHS (square hollow section) ladder frames bolted to galvanised steel brackets bolted to primary steel beams and concrete roof slab.  
120 mm mineral wool insulation between members.  
Breather membrane on outer face.  
80 × 60 × 5 mm aluminium channel brackets bolted to steel members at maximum 600 mm centres via thermal break spacers to support cladding.

5. Infill panels  
194 mm deep interlocking thermally broken aluminium mullion and transom profiles bolted to secondary structure.  
3 mm galvanised steel sheet inner lining secret-fixed to panel frames via angles bolted to rear of sheets.

6. Cladding  
PPC 3 mm aluminium sheets secret-fixed to panel frames via aluminium Z-profiles bolted to rear of sheets.

7. Window  
194 mm deep thermally broken aluminium window frame.  
Double-glazed sealed unit consisting of 12.8 mm laminated inner pane with low-E coating, 16 mm air gap and 8 mm toughened outer pane.

8. Outer skin upper support  
120 × 120 × 10 mm SHS cantilevered support beam bolted to secondary structure.  
100 × 50 × 6.3 mm RHS (rectangular hollow section) bolted between beams at mid-span.  
12 mm diameter stainless steel tension rods bolted to 60 × 12 mm stainless steel plate bracket bolted to end plates of support beams.  
Folded PPC (polyester powder coated) 3 mm aluminium sheet roof screwed to brackets on steel structure.


9. Outer skin lower strut  
80 × 60 × 7 mm galvanised RHS struts bolted to secondary structure.  
80 × 60 × 7 mm galvanised RHS bolted between struts at mid-span.

10. Outer skin central strut  
50 × 5 mm CHS (circular hollow section) brushed stainless steel strut bolted to 10 mm stainless steel plate bolted to aluminium infill panel frame.  
Brushed stainless steel cross-bracket consisting of 520 mm long 80 × 25 mm horizontal member welded to 520 mm long 80 × 12 mm vertical member welded to CHS.  
80 × 25 mm horizontal member is continuous over first two glass panels at corners in both directions for stiffness.

11. Outer skin glazing  
24.8 mm or 25.5 mm laminated glass mechanically fixed with 120 × 70 × 10 mm brushed stainless steel clamping plates.  
165 × 110 mm extruded aluminium angle frames bolted to support beams at top and to struts at bottom of glazing.

12. Floor of façade void  
30 mm deep galvanised steel grating with 80 × 6 mm edges bolted to lower struts.  
132 × 125 mm recessed aluminium up-lighter recess flush with grating.  
PPC 3 mm aluminium sheet soffit secret-fixed to steel struts via aluminium Z-profiles bolted to rear of sheets.





Cut-away section through projecting courtroom on north elevation



*Photo: Michael Moran*



Photo: Michael Moran

## Sean O'Casey Community Centre Dublin

Architect: O'Donnell + Tuomey  
Structural Engineer: Casey O'Rourke

Set in a neighbourhood of two-storey brick terraced houses, the corrugated concrete walls and circular windows of the Sean O'Casey Community Centre are a distinctive new landmark in the Dublin district of East Wall. The building houses four main facilities – a crèche, day care facilities for the elderly, a 153-seat theatre and a sports hall sharing a single entrance. The different elements of the brief are arranged around four courtyards that provide the necessary separation between activities while also allowing oblique visual links between them.



Photo: O'Donnell + Tuomey



Photo: O'Donnell + Tuomey




Photo: O'Donnell + Tuomey

Corrugated concrete walls with circular cut-out windows define the outer shell of the Centre. The walls are load-bearing and were cast in-situ using corrugated galvanised steel sheets screwed to the plywood face of the formwork. Circular voids were formed by fixing plywood drums to the formwork. The window frames are unsealed iroko that is already fading to grey to match the concrete. To control shrinkage cracking the walls were poured in a number of sections so one section would have a few days to dry out before the next section was poured. Day joints are concealed in flat strips, which also serve to break the walls up into carefully proportioned corrugated panels.

The roofs are also in-situ concrete with the smooth soffit exposed on its underside. The joints were all set out and the surface was laboriously rubbed down by hand once the phenolic faced birch plywood formwork was removed. Numerous trials and samples of the concrete mix were carried out on site. The concrete walls and steel columns are built off reinforced concrete strip foundations. Rather than using piled foundations a cheaper alternative was used of improving the ground using vibrated stone columns.

Internally the four courtyards are surrounded by full height glazed screens made from 250 × 75 mm iroko members. Around the courtyards the roof is supported on 114 mm diameter steel columns cast directly into the roof slab. The columns are at close enough centres that the concrete can form a beam between them. A head plate with shear studs welded to it ties into the reinforcement to resist punching shear.





East-west section – 1:500

Drawing labels:

1. Foundations

1200 × 400 mm reinforced concrete strip footing below external wall on 50 mm sand blinding.  
900 × 300 mm reinforced concrete strip footing below steel columns on 50 mm sand blinding.  
Vibrated stone columns at varying centres to improve ground below footings.  
Ground floor slab thickens at edges to 400 × 400 mm at courtyard perimeter.

2. Ground floor

55 mm brick pavers with two coats clear sealant.  
100 mm screed with underfloor heating pipes cast in.  
25 mm service void formed between edge of screed and wall using 18 mm WBP plywood formwork.  
75 mm rigid urethane insulation.  
DPM (damp proof membrane) laid over slab and finished 150 mm above finished floor level in cast-in groove in concrete upstand.  
265 mm thick reinforced concrete slab, thickening to 400 × 400 mm at courtyard perimeter.  
50 mm blinding and 200 mm compacted hardcore.

3. External concrete wall

500 mm high × 250 mm wide reinforced concrete kicker with hydrophilic strip on top.  
300 mm thick reinforced concrete wall cast in-situ with corrugated surface and class C finish externally.  
Internal breather membrane lapped over and bonded to DPM base.  
100 × 75 mm vertical softwood studs at 400 mm centres.  
100 mm high density insulation between studs.  
Vapour barrier.  
75 × 25 mm softwood battens forming 25 mm service void.  
15 mm skimmed plasterboard internal lining with painted finish.

4. Concrete formwork

1220 × 3810 × 0.4 mm corrugated galvanised steel sheets nailed to plywood and holes sealed. Sheets overlapped by 1½; corrugations to ensure consistent finish.

5. External window

Ex 150 × 75 mm iroko window frame screwed to concrete via galvanised steel angle brackets.

Bituminous DPC fixed to frame, dressed over internal breather membrane and bonded to concrete.

Breathable mastic seal externally.

15 mm skimmed plasterboard internal lining fixed to 50 mm softwood studwork to form window reveal.

6. Steel structure

114 × 6 mm galvanised steel CHS (circular hollow section) columns at 2.5 m centres to courtyard perimeter with painted finish.  
275 × 275 × 15 mm baseplate welded to CHS and bolted to concrete footing.  
Column cased in 50 mm mass concrete up to slab level as corrosion protection.  
400 × 200 × 20 mm thick steel plate welded to top of CHS and cast into roof slab 75 mm above underside.  
Ten 19 mm diameter × 120 mm high shear studs welded to top side of plate to tie column head into reinforcement of slab and resist punching shear.

7. Roof

Two layer polymer modified bitumen waterproof membrane with mineral chips on exposed surfaces.

Tapered PIR (polyisocyanurate) insulation varying from 110 to 270 mm thick to form 1:80 fall.

1.2 mm foil cored reinforced vapour barrier.  
300 mm fair-faced reinforced concrete roof slab left exposed internally with Class C patterned finish.

Plywood formwork with joints and fixings set out to correspond with plan arrangement.

8. Rooflight


375 mm high × 75 mm wide reinforced concrete upstand.

25 mm PIR insulation around upstand.  
75 × 50 mm softwood kerb screwed to concrete upstand.


Top layer of polymer modified bitumen waterproof membrane dressed up vertical face and under rooflight frame.

700/1400 or 2100 mm diameter circular extruded aluminium frame screwed to kerb to ensure 1:100 fall.

Walk-on double-glazed sealed unit consisting of 21.5 mm toughened laminated outer pane,




First floor plan – Scale 1:1000



Ground floor plan – Scale 1:1000





Cut-away section through daycare dining area and courtyard

16 mm air filled cavity, 6 mm soft coat low-E inner pane.

9. Courtyard glazed screen

250 × 75 mm iroko mullions, head and cill members.

Double-glazed sealed units.

10. Roof parapet at courtyard

250 mm wide × 260 mm high reinforced concrete upstand.

Glazed screen head member restrained back to upstand with galvanised steel angle bolted to concrete.

Vapour barrier laid up and over upstand.

DPM fixed to top of glazing frame and lapped over vapour barrier.

44 × 80 mm (tapering to 70 mm) treated softwood battens fixed to top of upstand.

18 mm WBP plywood fixed to battens and glazing frame.

Top layer of polymer modified bitumen waterproof membrane dressed up and over plywood.

3 mm galvanised steel coping fixed to plywood with galvanised steel clips.

11. Rainwater system

100 mm diameter × 1 m long stainless steel pipe between paired mullions.

Stainless steel chain fixed through hole in bottom of pipe to take rainwater to ground.

900 mm diameter reinforced concrete ring supported on 500 × 150 mm reinforced concrete footing.

Ring filled with hand selected 200–300 mm diameter Wicklow Granite river washed stones.

This page intentionally left blank



*Photo: Anthony Coleman*





Photo: Anthony Coleman



Photo: Anthony Coleman



Photo: Cottrell & Vermeulen  
Architecture



Photo: Cottrell & Vermeulen  
Architecture



Photo: Anthony Coleman

## Bellingham Gateway Building Lewisham, London

Architect: Cottrell & Vermeulen Architecture


Structural Engineer: Engineers HRW

The Gateway Building is a place where children and young people can take part in sport and leisure activities while meeting other people their own age in safe surroundings. Housed beneath an asymmetric pitched roof that snakes along the edge of a playing field, the building contains a nursery for 0–2 year-olds, an activity room and a café. The leisure facilities, funded by Sport England are intended to introduce young people from deprived backgrounds to activities they may not otherwise get the chance to try.


The structural frame is made up of a series of steel portals built off a concrete raft foundation with a perimeter ring beam. The frame is stiffened with 175 mm deep softwood purlins and noggins braced with a plywood deck. Working on a very low budget the architects have made something special out of very basic materials.

Different types of cladding and rooflights allow light in and out of the building in a playful way without breaking the roof profile. On the north and west sides corrugated cement fibre cladding is used near ground level where it is susceptible to vandalism painted with an anti-graffiti coating. Translucent glass reinforced plastic (GRP) sheets cover the rest of the roof and walls with insulation, a breather membrane and a ventilation gap behind. On the east side sedum covers part of the roof so that the surface of the park seems to wrap up and engage with the building. The plants are held in place on the 25 degree pitch by a woven geotextile 'blanket'.


Above the entrance porch the insulation and plywood sheathing have been left out so that light can shine right through the roof and illuminate the lobby below. The lobby ceiling externally and the sliding folding gates are made from the same translucent GRP, backlit to emphasise the entrance. Elsewhere on the west elevation the plywood behind the GRP cladding has been painted in bright colours so that at night the building seems to glow from within.




Steel portal frame structure



East-west section through entrance – Scale 1:400



Ground floor plan – Scale 1:400




Site location plan – 1:2000

Drawing labels:

1. Steel frame generally  
Seventeen steel portals at between 3.15 m and 3.75 m centres made up from welded 356 × 171 mm universal beams (UB) bolted down to concrete slab.
2. Steel frame over entrance  
356 × 171 mm UB ridge beam.  
356 × 171 mm UB eaves beam over entrance.  
203 × 133 × 30 UB tie beam over central spine wall.  
152 × 152 mm universal column (UC)  
secondary steels to support timber purlins.
3. West elevation low-level cladding  
175 × 38 mm treated softwood purlins at 600 mm centres.  
Corrugated cement-fibre sheet cladding fixed at 65 degree angle with self-tapping screws.  
Clear anti-vandal permeable paint finish.  
Independent timber framed wall behind made up from 150 × 38 mm softwood studwork.  
100 mm polyisocyanurate (PIR) insulation between studs.  
12 mm sheathing ply and breather membrane externally.  
Vapour barrier.  
Plasterboard lining internally in nursery and office areas.  
15 mm gypsum bonded wood particle board in activity rooms, café, corridor and reception.
4. West elevation high-level cladding  
Corrugated translucent glass reinforced plastic (GRP) external cladding fixed to SW battens through plywood with self-tapping screws at 1800 mm centres.  
9 mm hardwood facing plywood pre-decorated with weathershield paint where colour required, the rest of the plywood pre-decorated with wood stain.  
50 × 50 mm horizontal softwood battens at nominal 600 centres.  
Breather membrane.  
150 × 50 mm vertical battens at 1250 mm centres fixed with stainless steel brackets.  
100 mm PIR insulation with 50 mm ventilation gap above.  
Vapour control layer.  
18 mm plywood deck.  
175 × 38 mm softwood purlins at 600 mm centres.

5. GRP cladding to entrance area  
Corrugated translucent GRP external cladding fixed to softwood purlins with self-tapping screws.  
175 × 50 mm softwood purlins at 2.27 m centres fixed to steel frame.
6. Aluminium flashing  
Folded 2 mm mill finish aluminium flashing used to roof ridge area.  
Polyester powder coated (PPC) aluminium corner flashing and window surrounds.
7. East elevation green roof  
Sedum blanket held in place by retention strips.  
5 mm root-resistant layer.  
4 mm bitumen and high-tensile woven glass fibre waterproof layer.  
100 mm PIR insulation boards.  
Vapour barrier.  
18 mm plywood decking.  
175 × 38 mm softwood purlins at 600 mm centres.
8. Gutter  
240 × 160 mm folded PPC aluminium gutter over entrance fixed to steel with self-tapping screws.
9. Entrance external soffit  
Corrugated translucent GRP ceiling lining fixed to 50 × 50 mm softwood battens above with self-tapping screws.
10. Entrance lobby ceiling  
Corrugated translucent GRP ceiling lining fixed to 125 × 50 mm timber battens above with self-tapping screws.  
6 mm perforated hardboard.  
100 mm PIR insulation.
11. Entrance gates  
2330 mm high folding-sliding steel framed gates with corrugated translucent GRP in-fill panels.  
Steel frame made up from 50 × 50 mm galvanised steel angles.  
Track bolted to steel beam above.
12. Entrance doors  
PPC aluminium door frames with double-glazed sealed units.



Cut-away section through entrance





Photo: Morley von Sternberg





Photo: Fluid



Photo: Fluid




Photo: Fluid



Photo: Morley von Sternberg

## Maryland Early Years Centre Stratford, London

Architect: Fluid  
Structural Engineer: Conisbee  
Prefabricated Panels: Framework CDM


Maryland Early Years Centre in east London was built in an incredibly short 5-month period using a prefabricated timber panel superstructure. The single-storey Centre houses a daycare room for 2–5-year-olds, a staff training room and a classroom which is shared with the next-door primary school.

Deep concrete trench footings pass through 1.5m of fill to bear on a sand and gravel layer below. Basements from a previous row of terraced houses that were discovered during the works had to be filled with concrete in places to ensure a firm base. A 200mm thick ground floor slab spans between the footings with a 140mm perimeter upstand to raise the timber wall panels off the ground.

The walls and roof were prefabricated and brought to site in panels. The wall panels consist of 140mm softwood studs with insulation between, breathable wood-fibre board external sheathing and an OSB (oriented strand board) inner lining. A 360mm deep laminated softwood beam runs around the perimeter of the building at roof level and across the top of the central wall tying all the panels together. The roof panels consist of 350mm deep composite timber beams conjoined with a plywood top deck. They sit on the wall panels and fix laterally into the tie beam.

On the south side a steel framed canopy shelters an enclosed outdoor play space. The canopy has a translucent polycarbonate roof and the soffit is made up of larch strips with 10mm gaps between so some light can pass through it.

Externally the walls are clad with GRP (glass-fibre reinforced plastic), a material normally used for roofing, chosen so that its translucency would reveal something of the construction beneath. The GRP is wrapped around the corners in a curve, reinforcing the horizontality of the building and softening its edges. The bright orange and lime-green façades provide a splash of much needed colour in a rather run-down setting.



East-west section – 1:150

Drawing labels:

1. Foundations

C35 mass concrete trench fill foundations to 1.5m depth into gravel.

2. External landscaping

Artificial grass laid on 9mm shock-absorbing pad.  
130mm trowelled concrete base laid to fall away from building.  
150mm granular sub-base.  
100mm concrete blinding.

3. Ground floor

3mm vinyl floor finish.  
22mm tongued and grooved particle board flooring.  
72mm extruded polystyrene insulation with integral underfloor heating pipes.  
200mm thick mesh reinforced C35 concrete slab spanning between trench footings.  
1200mm gauge polythene damp proof membrane.  
100mm well rolled sand blinding.

4. Ground floor slab edge

140 × 90mm concrete upstand.  
Bituminous DPM (damp proof membrane) lapped over polythene DPM below slab and over blinding externally.  
Bituminous DPM bonded to vertical face of slab edge.  
Liquid applied bituminous DPM applied to top and bottom joints to form continuous waterproof layer.  
3mm bituminous protection board.  
25mm extruded polystyrene insulation internally at floor edge.

5. Typical wall

51mm translucent sinusoidal GRP (glass reinforced plastic) with polyester film fixed back to purlins with lacquered self-drilling fasteners located in valleys of sinusoidal GRP.  
50mm cavity and vertical galvanised steel Z-profile purlins.  
Prefabricated wall cassettes made up from 140 × 38mm softwood timber studs at 600mm centres with mineral wool insulation.  
22mm thick wood-fibre board external sheathing.  
18mm oriented strand board and vapour control layer internally.  
12.5mm plasterboard with plaster skim finish internally.

6. Window

100 × 50mm aluminium box frame with 50 × 50mm aluminium framed tilt and turn window opening lights.  
Double-glazed sealed units made up from 4mm toughened inner pane, 16mm argon filled cavity, 4mm toughened outer pane with soft low E coating.

7. Window head

90 × 360mm laminated softwood beam over opening.  
22mm thick wood-fibre board sheathing.

135 × 30mm mill finish pressed aluminium external flashing fixed to beam.  
Plasterboard returned internally at head and jambs with skim coat and paint finish.

8. Tie beam

90 × 360mm laminated softwood tie beam bolted across top of all cassettes around building perimeter and across central spine wall.

9. Roof

EPDM waterproof membrane.  
150mm extruded polystyrene insulation laid to falls.  
Polythene vapour control membrane.  
350mm deep prefabricated roof cassettes made up from 350mm deep engineered timber beams with 18mm WBP plywood deck.  
18mm plywood soffit.  
1200 × 600mm high density glass wool acoustic ceiling panels on ceiling grid suspended from cassette soffit on isolating wires.

10. Parapet

Prefabricated upstand wall cassettes made up from 140 × 38mm softwood studwork.  
22mm wood-fibre board to external face of cassette.  
9mm OSB sheathing to internal face.  
EPDM waterproof membrane dressed up and over upstand.  
285 × 50mm mill finish aluminium coping.

11. Canopy steel structure


168mm diameter CHS (circular hollow section) columns at 5530mm centres.  
150 × 75mm steel UEA (unequal angle) bolted through plywood sheathing to timber beam.  
Paired 100 × 100mm SHS (square hollow section) cranked beams bolted to UEA and either side of CHS.  
200 × 100mm RHS (rectangular hollow section) bolted between SHS beams below gutter.  
125 × 65mm PFC (parallel flange channel) welded to ends of SHS beams along canopy edges.

12. Canopy gutter


300 × 75 × 1.5mm pressed aluminium box gutter fixed to 75 × 38mm softwood battens on both sides.  
76mm diameter aluminium rainwater pipes inserted inside CHS columns.  
300 × 150mm cut-out near base of columns for rainwater pipe outlet.

13. Canopy roof


10mm thick translucent polycarbonate sheets clamped into proprietary aluminium patent glazing bars at 655mm centres.  
Glazing bars screwed to 75 × 38mm softwood battens at 975mm centres.  
100 × 50mm C24 softwood joists at 655mm centres spanning between steel members.  
50 × 38mm treated softwood battens fixed to undersides of joists.  
50 × 25mm larch slats screwed to battens at 60mm centres.  
300mm deep mill finish pressed aluminium flashing to all three edges of canopy.



North-south section – Scale 1:400



Ground floor plan – Scale 1:400



Cut-away section through playspace canopy





Photo: Morley von Sternberg





# Emmaus School Wybourn, Sheffield


Architect: DSDHA  
Structural Engineer: Price & Myers

Draped across a hillside above Sheffield city centre, the Wybourn Estate has a dramatic landscape setting with panoramic views across to the Peak District. In 2005 the Council adopted a masterplan intended to counter the social problems that have blighted the area since the decline of local industries in the 1970s and 1980s. One of the first tangible products of the plan is the Emmaus Primary School that replaces and unites a Roman Catholic and a Church of England faith school that were suffering from declining numbers of pupils.


The foundation is a concrete raft to bridge across a fault line in the rock that runs diagonally under the building. The frame is steel with precast concrete plank floors and roof for speed and economy. The project was procured under a two-stage tender process allowing the contractor a lot of input on construction decisions.

Rooflights have been used extensively to give a high quality of light on a tiny budget. Two two-storey blocks containing classrooms, administration and a hall are oriented at a splayed angle to one another to make a central circulation space with a long rooflight over the staircase. At the entrance a precast concrete bridge spans from a retaining wall outside onto the building's steel frame. Precast elements have also been used for the long ramp down the north elevation and retaining walls for ease of maintenance and a predictable high quality finish. The entrance façade is a standard aluminium curtain walling system. Inside, the entrance bridge looks down on a double height 'sacred space' through a glazed wall, framed in hardwood to give a half-hour fire rating.

Published in 2003, Building Bulletin 93 set strict acoustic standards for the first time for new schools. A degree of experimentation was involved in detailing walls, floors and ceilings that would comply with the regulations and be economical and practical to build. In the circulation space large acoustic absorbent ceiling boards with taped and filled joints have been used in preference to a typical suspended ceiling grid. All classroom walls are made from two independent double-boarded metal studwork frames separated by mineral wool. At the façade the isolation is continued with two separate curtain wall mullions with an insulated aluminium panel between them.




Upper level plan – Scale 1:1000



Lower level plan – Scale 1:1000



North-south section – Scale 1:1000



Site location plan – 1:2000

#### Drawing labels:

##### 1. Primary structure

Steel frame.

Precast concrete planks spanning between steel beams.

##### 2. First floor

10 mm carpet floor finish.

25 mm tongued and grooved particle board floor.

35 mm rigid polystyrene insulation with underfloor heating pipes.

5 mm impact absorbing layer turned up at edges.

50 mm sand-cement screed.

150 mm precast concrete planks.

Acoustic suspended ceiling panels.

##### 3. Entrance bridge

20 mm thick coir mat flush with adjacent floor finish.

12 mm plywood base.

35 mm rigid acoustic insulation.

Acoustic isolating membrane.

75 × 75 mm mild steel angle at entrance threshold.

50 mm sand-cement screed.

150 mm thick precast concrete floor slab.

##### 4. Typical external wall

20 mm sand-cement render external finish with stainless steel angle stop beads.

100 mm concrete blockwork.

100 mm full-fill mineral wool insulation.

100 mm concrete blockwork.

12.5 mm plasterboard fixed to blockwork on dabs with taped joints and painted finish internally.

##### 5. Internal acoustic wall

Two layers 12.5 mm plasterboard with painted finish.

80 × 40 mm galvanised steel inner stud frame with deflection head detail at top.

30 mm mineral wool insulation suspended in cavity between studs.

80 × 40 mm galvanised steel outer stud frame independent from inner frame with deflection head detail at top.

Two layers 12.5 mm plasterboard with painted finish.

##### 6. Internal/external wall junction

35 mm insulation and damp proof membrane between blockwork and metal studs.

Black painted softwood packer between curtain wall frame and internal wall.

##### 7. Roof

20 mm mastic asphalt with solar reflective treatment.

Separating membrane.

100 mm fully bonded PIS (polyisocyanurate) insulation.

Liquid applied bituminous vapour control layer.

Minimum 35 mm thick sand-cement screed laid to 1:70 fall.

200 mm precast concrete slabs spanning between primary steel members.

75 × 50 mm softwood battens.

Suspended ceiling panels perforated for acoustic absorbency.

##### 8. Parapet

525 mm wide PPC (polyester powder coated) pressed aluminium coping fixed on clips to plywood.

PPC pressed aluminium flashing forming 170 mm high × 50 mm deep recess.

18 mm WBP plywood base for flashings on softwood studwork fixed to steel frame.

200 × 90 mm PFC (parallel flange channel) bolted between stub posts.

200 mm insulation retained to studwork with galvanised wire mesh.

Vapour barrier.

170 mm insulation behind anodised aluminium curtain wall panel.

##### 9. Rooflight upstand

20 mm mastic asphalt on separating layer.

18 mm WBP plywood external sheathing.

150 × 50 mm softwood studwork frame.

150 mm insulation between studs.


Vapour barrier.

12.5 mm plasterboard internal lining with paint finish.

##### 10. Rooflight

PPC aluminium frame screwed to 50 × 50 mm softwood sub-frame.

Double-glazed sealed units with 6.4 mm inner pane, 10 mm cavity, 6 mm toughened outer pane.



Cut-away section through entrance

11. External glazed wall

130 × 50 mm aluminium curtain walling box frame with anodised finish.  
Double-glazed sealed units with 6 mm inner pane, 10 mm cavity, 6 mm outer pane.  
Opaque panels made up from PPC pressed aluminium front and rear sheets with thermally isolating spacers and rigid insulation between.

12. Internal glazed screen

150 × 50 mm hardwood frame with paint finish to provide 30 minutes fire resistance.  
Laminated fire resistant single glazing.  
32 × 20 mm hardwood glazing beads screw fixed on both sides of glass.

13. Curtain wall/glazed screen junction

100 × 100 mm SHS (square hollow section) steel post.

50 × 50 mm solid softwood blocking with 12 mm painted MDF faces.

Intumescent perimeter seals to give 30 minutes' fire resistance.

14. Entrance ramp

9 m long × 1920 mm wide × 375 mm thick precast concrete slab spanning between steel frame and retaining wall in landscaping.

100 × 100 mm galvanised steel angle cast into end of concrete slab bears on 300 × 100 mm PFC beam spanning between 100 × 100 mm SHS posts at entrance.

50 mm asphalt surface finish.

1100 mm high balustrade made up from 1200 mm wide × 1530 mm high galvanised steel grating panels bolted to edge of ramp.




This page intentionally left blank




*Photo: Hélène Binet*









Ground floor plan – Scale 1:600



Isometric view from west end



Site location plan – 1:5000



East-west section – Scale 1:600

#### Drawing labels:

##### 1. Foundations

600 × 500 mm reinforced concrete ground beam.  
500 mm diameter reinforced concrete piles.  
200 mm wide × 1070 mm high reinforced concrete upstand retaining wall.  
100 mm thick × 725 mm wide reinforced concrete toe to form base of plenum.  
50 mm extruded polystyrene insulation around ring beam and toe.

##### 2. Plenum

815 × 700 mm plenum for air supply to recital room.  
100 mm wide dense concrete blockwork wall to form inside edge.  
Floor and walls of plenum painted with bituminous waterproof membrane.  
50 mm extruded polystyrene insulation around walls and floor of plenum.  
Perforated metal wearing surface to floor.

##### 3. Ground floor

15 mm thick engineered oak laminate timber sprung floor fixed with clips.  
75 mm thick sand/cement screed.  
50 mm thick high density expanded polystyrene insulation.  
200 mm thick precast concrete planks spanning between reinforced concrete and blockwork walls.  
Void beneath floor ventilated by telescopic vents.

##### 4. Structural frame

Load-bearing ladder-frames made up from two 203 × 102 mm × 23 kg universal beam (UB) columns at 1495 mm or 1443 mm centres, horizontal 100 × 50 mm parallel flange channel (PFC) members at 1690 mm centres and 100 × 50 mm PFC diagonal cross-braces.  
All steelwork delivered to site with two-coat zinc phosphate paint system and pre-clad with stainless steel.

##### 5. Ground floor slab edge

50 mm high 4 mm stainless steel recessed skirting fixed down to concrete upstand at base of solid panels.  
Sleeved 100 mm wide vent slot supply air from plenum between columns rising to wall grilles.  
DPC bonded to stainless steel window frame and dressed down over face of concrete upstand wall.  
125 mm wide gravel strip between building and grass.

##### 6. External wall cladding

4 mm thick × 5500 mm high × 1740 mm wide bead-blasted stainless-steel panel with laser-cut vertical abutments bolted to supporting structure in rigid joints.  
Stainless steel pressed section subframe for stiffening pre-drilled for fixing back to mild steel frame with isolating spacers to prevent bi-metallic corrosion.  
Pre-drilled midpoint noggins fixing cladding back to pre-drilled mild steel angle cross-bracing at 850 mm centres approx.  
Puddle welded pressed stainless steel corner stiffening angles stop short at top and bottom by 20 mm to sleeve over inboard skirting U-section.  
12 mm plywood backing to stainless steel panel up to 1500 mm height to prevent 'barrelling' impact noise.

##### 7. External wall internal linings

Water repellent insulation between columns.  
Vapour barrier.  
1250 × 200 mm low-velocity supply ventilation/heating air duct with 1100 × 300 mm grilles.  
69 × 44 mm softwood studwork framing.  
25 mm thick MDF panels with routed grooves to line up with door divisions above secret-fixed to studwork.  
Three-coat shop finish paint system to MDF internal lining.


##### 8. Acoustic boxes

Five 3585 mm high × 331 mm wide × 44 mm thick pivot-hung MDF doors.  
Stainless steel bar on ratchet mechanism fixed to bottom lip of doors so all doors open and close together.  
Black fabric lining over acoustic insulation inside boxes.

##### 9. Glazing

Fixing plate welded across flanges of UB columns at 1800 mm vertical centres.  
Glazing angle frame made from 125 × 65 × 8 mm stainless steel folded plate welded at corners and bolted to plates on UBs with isolating membrane to prevent bi-metallic corrosion.  
50 × 50 × 6 mm stainless steel angle glazing bead fixed to frame with countersunk bolts.  
1800 × 5500 mm double-glazed sealed unit formed from 12 mm clear toughened inner pane, 16 mm cavity, 12.8 mm laminated Pilkington 'K' glass outer pane.





Cut-away section through west elevation of recital hall

10. Roller shutter

External deployable solar shading on rolling mechanism fixed at head to steel frame. Vertical guides screwed to 150 mm long  $\times$  50  $\times$  5 mm stainless steel flats welded to glazing angle frame at 1340 mm centres.

11. Roof

0.7 mm gauge zinc-alloy standing seam roof finish.  
8 mm acoustic underlay and breather membrane.  
WBP plywood deck.  
305  $\times$  165 mm UB roof beams at 3400 mm centres.  
250  $\times$  50 mm C24 softwood joists at 600 mm centres notched into roof beams.  
250 mm mineral wool insulation between joists.  
Vapour barrier.  
Two layers 12.5 mm plasterboard with 3 mm skim coat.

12. Gutter

1 mm thick zinc-coated aluminium coping and 400 mm high fascia fixed over upstand and in shadow gap under.  
Single-ply waterproof membrane.  
18 mm WBP plywood deck laid to 1:100 minimum fall.  
150  $\times$  150  $\times$  8 mm square hollow section (SHS) gutter support beam bolted between primary roof beams.  
788  $\times$  383 mm  $\times$  10 mm thick gutter steel support brackets bolted to gutter support beam at 800 mm centres.  
Eye bolts for clip-on safety system fixed to 90  $\times$  90  $\times$  5 mm steel SHS stubs welded to 15 mm thick plates bolted to gutter support beam.

13. Soffit

1 mm thick zinc-coated aluminium panels fixed to studwork behind.  
Removable panels to soffit to allow maintenance access to sunshade roller shutters.

This page intentionally left blank



*Photo: Anthony Weller*





*Photo: Anthony Weller*



*Photo: Anthony Weller*



*Photo: Anthony Weller*



*Photo: Anthony Weller*


## Sanger Building, Bryanston School Dorset

Architect: Hopkins Architects Ltd  
Structural Engineer: Buro Happold


The Sanger Building contains classrooms, laboratories and a 120-seat lecture theatre for science and maths teaching at Bryanston, a school for 13–18-year-olds in Dorset. Red hand-made bricks with precast concrete details relate the horseshoe shaped block to the vast Richard Norman Shaw house dating from 1897 at the centre of the school estate. The outside elevation is an insulated cavity wall with a half-brick thick (102.5 mm) outer leaf laid in stretcher bond. The inner elevation addresses a landscaped courtyard. Here the brick wall is laid in English bond and is fully load-bearing. Regular openings are formed with solid brick flat arches spanning 1810 mm between 890 mm wide piers, which are occupied by Douglas fir framed windows.

To carry the weight of the three-storey elevation the courtyard wall needs to be one and a half bricks thick. In the lower storey the loadings are near the limit of the bearing capacity of the bricks, while in the top storey the piers do not have sufficient mass to resist wind loads, so reinforcement rods were inserted in a void in the centre of the piers and concrete poured around them to make a wind post that also serves to hold down the lightweight roof. The floor slabs nominally span between the courtyard and park elevations but Building Regulations require a degree of redundancy to avoid disproportionate collapse so the slabs also bear on the cross walls. On the courtyard elevations, the floor slabs are isolated from the walls with strips of insulation to prevent load being transferred into the arches. At each pier a pocket was left in the brick and the slab cast into the pier to ensure a rigid connection.


Were the piers to be insulated, and a true load-bearing English bond external wall maintained, the piers would become excessively thick and the floor slabs would still have to penetrate the insulation and cavity to bear on the external wall. The detail illustrates the difficulties in achieving current standards of thermal performance with monolithic construction.




North-south section through site – Scale 1:1500



East-west section – 1:1500



First floor plan – 1:1000



Section through lecture theatre and external walkway – 1:400

Drawing labels:

1. External walls  
328mm thick load-bearing handmade brick (compressive strength 25 N/mm<sup>2</sup>) wall laid in English bond.  
Lime mortar mixed 1:1:6 (1 part Portland cement, 1 part hydrated lime and 6 parts sand).
2. Brick arch  
328mm wide × 440mm high arch built from pre-formed special tapered bricks with 20mm camber and spanning 1810mm.
3. Boss  
Precast concrete capping built into external course of brickwork to indicate bearing of floor slab behind.  
Floor slab cast into brick pier.
4. Colonnade floor  
400 × 400 × 65mm concrete pavers on 15mm sand bed.  
Damp proof membrane.  
Rigid insulation tapered from 50mm to fall to outside.  
250mm reinforced concrete slab.
5. Plant room floor  
130mm wearing screed in plant room.  
Damp proof membrane.  
250mm reinforced concrete slab.  
215mm walls supporting slab formed from 215 × 102.5 × 65mm blocks laid flat.
6. Balustrade  
1700 × 1100mm painted steel balustrade bolted to brickwork piers on both sides.  
Balustrade made up from 45mm diameter handrail, 18mm diameter rods, 60 × 15mm flat uprights, top and bottom flat rails.
7. Second floor openings  
Douglas fir window panels consisting of Douglas fir framed opening windows and insulated spandrel panel below.  
Double-glazed sealed units consisting of two panes of 6mm glass with 12mm air gap.  
75 × 50mm softwood studwork frame with mineral wool insulation between studs.  
Vapour barrier fixed to inner face of studs.  
Internal and external solid panels made up from 50 × 25mm hardwood Douglas fir frames with 69 × 19mm tongued and grooved board infill.
8. Lecture theatre floor  
Carpet floor finish.  
Minimum 200mm thick precast concrete elements to form rake for seating with 850 × 392mm steps.


203 × 133mm UB (universal beam) at back of rake supported on SHS posts in plant room wall.

9. Second floor  
Carpet floor finish.  
75mm sand/cement screed.  
25mm insulation.  
250mm reinforced concrete slab.  
15mm calcium silicate board soffit.

10. Plant room wall  
125 × 125mm concrete upstand at base.  
5.1m high 120 × 120 × 10mm SHS (square hollow section) posts at 2.3m centres.  
120 × 45mm softwood studs at 715mm centres vertically and 1300mm centres horizontally.  
15mm plasterboard internal lining to provide 1 hour fire rating.  
Mineral wool insulation between studs.  
15mm WBP plywood external sheathing painted dark green.  
106 × 25mm solid larch louvre blades fixed to 110 × 45mm notched vertical larch battens at a 45 degree angle.  
130 × 25mm larch external skirting.  
Localised cut-outs in partition where necessary for ducts from plant equipment with intumescent grille behind louvres to maintain fire protection.

11. Roof  
Zinc alloy standing seam roof finish.  
Fibre mat underlay to create air gap preventing moisture build-up and corrosion.  
120mm polyurethane insulation boards with integral softwood strips to allow fixing of zinc clips.  
Vapour barrier.  
Two layers 18mm plywood deck.  
100 × 100mm softwood joists.  
495 × 165mm glulam timber beams at 2055mm centres spanning 9.4m from gable end wall to cross wall.  
Plywood soffit panels.  
Alternate rows of panels have slots with black fabric and 30mm mineral fibre insulation behind to absorb sound.

12. Gutter  
Precast concrete coping fixed down to brickwork with stainless steel dowels.  
Lead flashing dressed down over gutter lining.  
Single ply PVC membrane gutter lining.  
Vapour barrier.  
Two layers 18mm plywood gutter deck.



Cut-away section through colonnade and rear of lecture theatre





*Photo: Amos Goldreich*





Photo: Amos Goldreich



Photo: Amos Goldreich

## Scitec, Oundle School Northamptonshire

Architect: Feilden Clegg Bradley

Structural Engineer: Jane Wernick Associates



Photo: Amos Goldreich

Scitec is Oundle School's new science and technology centre, a development intended to provide a unifying focus to the disparate school facilities, currently scattered about the town. Phase 1, completed in the summer of 2007, consists of 16 laboratories over two floors accessed from a top-lit gallery space. It has a structure of concrete walls and slabs on a raft foundation, all cast in-situ. The next phases include art and design studios, a library and a lecture theatre, which will all be accessed off a central mall parallel and open to the laboratory circulation space.

Externally the walls are clad in 100 mm thick ashlar blocks of Clipsham limestone laid with thin 3 mm joints. The stone walls are divided into three lifts with stainless steel shelf angles at first floor and roof levels. The stones in the bottom row of each lift have a stepped profile to sit on the shelf angle and allow a 3 mm joint so the horizontal movement joints look like all the other joints. At the base of the wall the stone bears on a concrete nib set just below ground level.

At the west end of the gallery, a stair winds up around a central concrete column that widens into a wall at roof level. Each stone tread appears to cantilever off the concrete wall but in fact merely rests on the tread below, carrying the vertical load down to a concrete landing at the bottom. The treads are not built into the concrete walls but are each attached by two stainless steel dowels that resist the tread's tendency to twist and transfer the resulting torsion into the wall. The stone treads have been rebated on the underside so that they interlock, ensuring they cannot twist relative to one another.

To allow the first floor landing to be set away from the walls its outer edge is hung from the roof on two stainless steel rods. The handrail and balustrades are fixed to steel uprights that cantilever from the ends of the stone treads. Each material has been used deliberately to exploit its primary characteristics. The staircase is intended as a teaching tool where forces of compression, tension, bending, torsion and shear can be clearly explained.







Photo: Amos Goldreich



West staircase first floor plan – 1:125



West staircase north-south section – 1:125



First floor plan – 1:1250

Drawing labels:

1. Ground floor  
50 mm concrete paving slabs.  
85 mm screed.  
Polythene vapour barrier.  
90 mm extruded polystyrene insulation acting as raised floor for services routes.  
200 mm thick reinforced concrete raft thickening to 400 mm at edges.  
Bituminous tanking membrane.  
Sand blinding on compacted hardcore.
2. External wall below ground level  
100 mm extruded polystyrene insulation.  
Liquid applied bituminous tanking membrane.  
250 mm thick in-situ concrete internal walls.  
Translucent sealed finish.
3. Wall detail at ground level  
Continuous 220 × 200 mm reinforced concrete nib to support outer leaf.  
Liquid applied bituminous damp proof membrane dressed down over tanking below.  
Heavy duty protection board.  
Engineering brick external leaf below ground level.  
Bituminous damp proof course minimum 150 mm above external ground level fixed with tape and mechanical fixing.
4. External wall  
100 mm thick load-bearing Clipsham limestone in variable courses and random lengths.  
Stone bedded on 3 mm mortar joints and dowelled onto stainless steel cavity ties fixed back to concrete wall.  
Stainless steel shelf angle supporting stone at first floor level.  
120 mm cavity with 100 mm mineral wool insulation.  
Liquid applied bituminous damp proof membrane.

250 mm thick in-situ concrete internal walls.  
Translucent sealed finish.

5. External window  
125 × 50 mm aluminium box section frame bolted back to concrete with intermittent steel angle brackets.  
Double-glazed sealed unit.  
285 × 26 mm veneered MDF internal lining fixed to concrete wall with 10 mm shadow gap in between.  
Internal venetian blind fixed into recess in oak head lining.

6. Internal wall  
200 mm thick in-situ concrete internal walls.  
Translucent sealed finish.

7. Window between stair and laboratory  
125 × 55 mm box section frame bolted into concrete.  
Double-glazed sealed unit.  
Window to provide acoustic separation and 1 hour fire resistance.  
60 × 20 mm pressed aluminium channel to accommodate tolerance between wall and frame.

8. Central column  
1000 × 250 mm reinforced concrete column between ground floor and first floor landing supporting spine wall above.

9. Landings  
200 mm thick reinforced concrete landings cast in-situ.  
30 mm thick stone finish to top and edge bedded on 20 mm flexible adhesive bed.  
Continuous aluminium strip at perimeter of landings secret-fixed to concrete to cover mortar bed.



Cut-away east-west section through west stair

10. Stair

1100 mm long  $\times$  389  $\times$  228 mm profiled stone treads between first and second floors.

1200 mm long  $\times$  354  $\times$  208 mm profiled stone treads between ground and first floors.

Two 450 mm long  $\times$  25 mm diameter stainless steel dowels resin bonded into holes in wall and tread.

11. Hangers

Two 25 mm stainless steel hanger rods to support first floor landing from roof slab above. Hanger rod passes through landing via stainless steel sleeve cast into pre-drilled 28 mm diameter hole in slab.

3 mm neoprene pad on 12 mm thick  $\times$  75 mm diameter stainless steel plate on underside

of slab fastened with stainless steel nut on threaded end of rod.

Gap between rod and sleeve and joint with stone filled with resin.

12. Balustrade

Painted steel balustrade.

75  $\times$  12 mm profiled flat uprights at 900 mm centres fixed into ends of stone treads with resin anchor bolts.

10  $\times$  25 mm flat horizontal and vertical members forming intermediate balustrade panel bolted to uprights.

47 mm diameter waxed oak balustrade drilled and glued to 10 mm stainless steel rods seam welded to top rail.



This page intentionally left blank



*Photo: Morley von Sternberg*





*Photo: Porphyrios Associates*



*Photo: Porphyrios Associates*



*Photo: Morley von Sternberg*



*Photo: Morley von Sternberg*

## Ann's Court, Selwyn College Cambridge


Architects: Porphyrios Associates  
Structural Engineer: Hannah Reed

In 1996 Porphyrios Associates won an invited competition for a major building programme at Selwyn College. Ann's Court, the first phase to be complete, houses the College's administration offices, a basement archive and 44 new study-bedrooms. The building has load-bearing masonry cavity walls supporting pre-cast concrete plank floors and a timber roof. At ground floor an arcade of six stone arches shelter a covered walkway which, in phase 2 will be extended around the quadrangle lawn.


A watertight basement has been made for the archive using secant piling, a technique where concrete piles are poured at centres just under twice their diameter. Before they have fully gone off the intermediate spaces are drilled out, cutting into the piles on either side. Softer concrete is then poured into the new holes forming a continuous waterproof wall. The area inside the piles was dug out and an in-situ concrete facing cast against the inner faces to prevent degradation of the soft concrete. A drained cavity and concrete blockwork inner leaf provide belt-and-braces protection against water ingress.

French Farge limestone has been used to make the arcade columns and voussoirs, simply bonded with lime mortar in the traditional way. The stone could happily take the vertical load but the two end piers are not wide enough to resist outward thrust from the arches so a reinforced concrete beam has been cast just below first floor level to tie the arches together. The voussoirs act as permanent formwork for the concrete beam, tied into it with stainless steel dowels.

The outer leaf of the main walls is one brick thick. Flat arches over the windows at ground and second floors were prefabricated by bonding special shaped bricks to a concrete lintel to look like a traditional brick arch with a 10mm camber. Ann's Court is a true load-bearing masonry building unafraid to use modern methods where tight tolerances are required or traditional techniques cannot be proven satisfactory by calculation.



Site location plan – 1:1200



Ground floor plan – 1:500

Drawing labels:

1. Foundations

600 mm diameter concrete piles at 3040 mm centres below each arcade column.  
1200 × 500 mm reinforced concrete ground beam.

2. Arcade floor

50 mm thick York stone paving.  
30 mm mortar bed.  
70 mm thick screed.  
350 mm thick reinforced concrete slab.  
80 mm thick York stone edge step.

3. Load bearing masonry walls

215 mm thick Coleford Saxon Multi brick outer leaf (265 mm below ground floor cill).  
25 mm cavity.  
75 mm rigid polystyrene insulation.  
215 mm thick concrete blockwork inner leaf.  
13 mm plaster.  
200 × 32 mm profiled softwood skirting.

4. Arcade columns

655 × 655 mm solid Farge limestone columns made up of 450 mm high blocks with no dowels.

5. Arcade arch

Nine 720 × 325 mm Farge limestone voussoirs built off column capitals with mortar joints to form arch.  
Temporary timber formwork propped on scaffolding to support stones until each arch is complete.  
Two 20 mm diameter stainless steel dowels glued into each stone to provide key with concrete beam above.

6. Concrete beam

450 mm thick reinforced concrete poured over arches to form continuous beam tying

arches together and resisting outward thrust at ends.

Polythene sheet between stone and concrete to prevent staining of stone.  
730 mm high × 225 mm thick reinforced concrete up-stand above first floor level.

7. First floor

180 mm deep proprietary suspended floor system with adjustable steel pedestals and 600 × 600 mm particle board floor panels.  
200 mm thick precast concrete planks bearing on concrete beam.  
75 mm mineral wool insulation.  
50 × 50 mm softwood battens.  
Two layers calcium silicate board ceiling with paint finish.  
40 × 40 mm softwood moulding around perimeter.

8. Brickwork below cill

102 mm thick Coleford Saxon Multi brick outer leaf restrained to concrete with stainless steel wall ties.


9. Stone band

535 × 440 mm profiled Ketton stone cill course.

10. Typical window

Hardwood window.  
Precast concrete boot lintel at head in inner leaf.  
Flat arches in outer leaf prefabricated from bricks bonded to concrete lintel.  
25 mm thick softwood cill.  
Recess in head lining internally for roller blind.





Cut-away section through arcade



*Photo: David Stewart*





*Photo: 5th Studio*



*Photo: David Stewart*

## Wolfson Building Trinity College, Cambridge

Architect: 5th Studio

Structural Engineer: Cameron Taylor

Glazing Installer: F. A. Firman



*Photo: 5th Studio*


Two new glass seminar rooms have been hung beneath the cave-like undercrofts of the Wolfson Building, a 90-bedroom student hall of residence for Trinity College hidden amongst the courtyards of central Cambridge. Designed by the Architects Co-Partnership's and completed in 1972, the Wolfson Building exhibits a primitive palette of rough in-situ concrete and exposed brickwork in a wilfully monastic interpretation of college life. 5th Studio's refurbishment has raised the quality of the accommodation to reflect the more demanding expectations of the university's current students and conference clients.

On one side the hanging room's steel floor structure is bolted into the existing second floor concrete slab. The other side is suspended from the third floor on a single  $50 \times 50$  mm steel box section hanger. Two larger box section posts support the façade glazing and transfer wind loads back to the concrete structure. The north façade is completely glazed with two sealed units, the largest of which measures  $3.7 \times 2.6$  m. The only road access to the site is via a ramp shared with a supermarket below the building so manoeuvring the panes into place involved several operations using hoists to negotiate the changes in level. To prevent flexial deflection of the glass the units were moved in purpose-made timber cradles.




*Photo: David Stewart*


The building's exposed concrete slabs and un-insulated brick cavity walls are uneven so the space had to be carefully surveyed before the steel was ordered. Once in place, the steel was surveyed before the glass was ordered. Stainless steel channels were bonded to the rear of the large glass units with structural silicone so they could be secret-fixed back to steelwork and in places where access to the fixings from behind is restricted the glass is fixed with planar glazing bolts. The back face of the glass is painted black in places to conceal the floor or wall build-up behind. Two sections of laminated glass floor allow views up into the hanging room from the entrance below. The underside of the floor is clad in black laminated glass bringing natural light and reflections of the adjacent gardens into the once dark circulation core.




North hanging room Level 2  
plan – 1:125



North hanging room east-west  
section – 1:125



Site location diagram



Level 2 floor plan – 1:600

Drawing labels:

1. Existing building fabric

185 mm thick reinforced concrete floor slabs with  $475 \times 235$  mm upstand beams at edges. 300 mm thick cavity walls with brick inner leaf, 90 mm cavity and brick outer leaf.

2. Corner steelwork

$1000 \times 350 \times 20$  mm head plate bolted into existing second floor slab with twelve expanding anchor fixings.  $600 \times 150 \times 15$  mm bearing plate welded to top of head plate to sit on top of concrete upstand beam and relieve shear force on bolt fixings.  $50 \times 50 \times 6.3$  mm SHS (square hollow section) hanger welded to head plate via 10 mm flat plates. Two  $100 \times 100 \times 5$  mm SHS windposts welded to head plate via 10 mm flat plates.  $120 \times 100$  mm T-section welded to bottom of hanger and windposts for attachment to floor beam below.

3. Structural steel floor

$203 \times 203$  mm UC (universal column) floor beam with  $900 \times 100 \times 10$  mm flat welded to top to connect to hanger above. Three  $152 \times 152$  mm UC joists bolted to floor beam and to existing second floor.  $150 \times 100$  mm RHS (rectangular hollow section) edge beam bolted to floor beam and to existing second floor.

4. Large fixed window

Two double-glazed sealed units fixed to steel cleats welded to steelwork or brackets bolted to existing walls and soffits. Glass fixed using both proprietary countersunk black headed M8 bolts and stainless steel channels factory bonded to glass with structural silicone and bolted to steel cleats. Sealed units made up from 12 mm toughened outer pane and 18 mm thick clear toughened laminated inner pane.

Outer leaf partially printed black on rear face to conceal floor, wall and ceiling build up.

5. Glass floor

Clear laminated glass floor made up from two thermally toughened glass layers and one heat strengthened layer bearing onto neoprene strips and packers. Joints pointed with silicone sealant. Edges printed black to conceal supporting structure and floor build up.

6. Solid floor

22 mm thick oak boards secret-nailed and glued to 18 mm plywood sheathing. Vapour barrier.  $150 \times 50$  mm softwood joists located in webs of steel joists. 150 mm mineral wool insulation. 12 mm calcium-silicate board fixed below steelwork to provide fire protection.

7. Soffit glazing

Black laminated glass made up from 6 mm float upper leaf and 12 mm thermally toughened lower leaf bolted to brackets off primary structure.

8. Vertical black glass

Black laminated glass made up from 6 mm float upper leaf and 12 mm thermally toughened lower leaf bolted to brackets off steel windposts.


9. Solid panel

$175 \times 50$  mm softwood stud frame. Mineral wool insulation between studs. Polythene vapour barrier. 22 mm thick oak boards secret-nailed and glued to 18 mm ply substrate.

10. Window

Inward opening steel framed door and frame with micaceous iron oxide paint finish.  $1450 \times 1055$  mm toughened glass balustrade bolted to steel angle below cill of door.





Cut-away section though north hanging room



*Photo: Hufton & Crow*





Photo: Hufton & Crow



Photo: Hufton & Crow

## Information Commons University of Sheffield

Architect: RMJM

Structural Engineer: Ramboll Whitby Bird



Photo: RMJM

Information Commons is a 24-hour facility providing 1350 study places, a reference and loan library, a café and staff offices in a 11 500 square metre building near Sheffield city centre. The building is intended as the gateway to the campus, forging a strong relationship with the public realm and nearby transport links.

An innovative system called Cobiax, a hybrid precast/in-situ concrete slab using recycled plastic void formers, has been used to form the floor slabs. 1.8m wide pre-cast soffit panels incorporating 225mm diameter hollow plastic balls were craned in and supported in place on a temporary scaffold. Held in place by a steel reinforcement cage, the balls replace concrete that would be structurally redundant, reducing the weight of the finished slab by up to 35%. Once positioned a top layer of in-situ concrete is poured to form a two-way spanning flat slab. Typically Cobiax uses 15–20% less reinforcement than a traditional flat slab and as the floor is lighter, wider spans can be achieved with fewer columns. Services are contained in a raised floor void so much of the concrete structure can be left exposed. The contractor estimates that a time reduction of 20% was achieved over traditional methods of building a flat slab.

Where extra strength is required around the column heads the void formers were omitted. Additional reinforcement is provided to resist punching shear by an array of shear links, C-shaped steel bars that tie the top and bottom layers of reinforcement together. The precast panels have a 12mm chamfer on all edges and are tightly butt jointed except on column lines where a 50mm wide recess has been left for tolerance. To disguise the different colour of the in-situ concrete the gap was plugged with a foam strip during pouring to make a 35mm shadow gap.

Where a floor slab meets the atrium or one of several double-height spaces it has been covered by a precast concrete edge beam. As there are twelve different profiles of edge beam the budget did not stretch to steel shuttering. As an alternative, perspex was used to line a timber mould for the faces to be exposed and an exceptionally high quality finish was achieved.




Photo: RMJM




East-west section – 1:1200



North-south section – 1:1200



Second floor plan – 1:1200



Ground floor plan – 1:1200

Drawing labels:

1. Typical column  
450 mm diameter circular in-situ concrete column.
2. Structural floor  
1800 mm wide  $\times$  70 mm thick precast concrete slab with fair face exposed on underside supported on temporary formwork. Reinforcement mesh cast into precast slab with minimum 20 mm cover. Precast panels typically butt jointed except on column lines. 12 mm chamfer on all four edges of each panel to form shadow gaps. Reinforcement trusses cast into precast slab at 590 mm centres. 225 mm diameter HDPE (high density polyethylene) void former balls made from 70% recycled plastic. Void formers held in place with steel cage cast into precast slab. T2 mesh laid over void formers on site. 270 mm thick in-situ concrete topping with minimum 20 mm cover over void formers and reinforcement. Level finish to top surface.
3. Joint on column line  
50 mm gap between precast floor panels. 35 mm recess formed by temporary rigid foam strip between panels during pouring of in-situ topping.
4. Column junction  
Void formers omitted around column heads for extra strength to resist punching shear.

300 mm high steel shear links cast into precast slab around column to strengthen floor locally.

5. Edge beam  
660 mm high  $\times$  varying width precast concrete edge beam.


6. Balustrade  
180  $\times$  40 mm solid beech cill.  
10 mm shadow gap painted out to match beech.  
18 mm beech veneered MDF perforated acoustic panel.  
25 mm mineral wool insulation.  
100  $\times$  50 mm light gauge steel channel frame bolted to concrete edge beam.  
12.5 mm plasterboard internal lining on proprietary steel rails.

7. Raised floor  
600  $\times$  600  $\times$  25 mm proprietary floor panels. Proprietary steel pedestals to create 375 mm floor void for services.

8. Air supply units  
600  $\times$  200 mm aluminium grilles set into special floor panel.  
Terminal zone air supply unit fixed to floor panel with integral fan to control air supply locally.

9. Lighting  
Light fittings lined up with joints in precast floor panels above.  
Electrical wiring fed through 50 mm diameter hole drilled through panel joint from floor void above.





Cut-away section through floor slab edge at atrium



Photo: Nick Kane



*Photo: Nick Kane*



*Photo: Buschow Henley Ltd*



*Photo: Nick Kane*

## St John's Therapy Centre Wandsworth, London

Architect: Buschow Henley Architects  
Structural Engineer: Price & Myers

St John's is a community healthcare building constructed under the LIFT (Local Improvement Finance Trust) scheme, a public-private partnership to design, build and operate community health buildings and local authority services. It combines two GP practices with services that have traditionally been provided in hospitals but do not require a patient to stay overnight, such as mental health, podiatry and physiotherapy clinics.


The primary frame consists of concrete columns and floor slabs. Where walls are required the frame has been infilled with a secondary structure of light-gauge steel channels. The building is clad in timber veneered panels made from wood fibre and paper bonded with phenolic resin and compressed at high pressure.

The windows have been detailed to respond to varying light, privacy and acoustic requirements of the different elevations. On the south side several windows project 100mm beyond the face of the cladding. These are supported off the steel structure on aluminium angles and have bronze anodised aluminium curtain walling frames. Insulated flashings prevent a cold bridge around the edges of the frame. All other windows are timber, recessed flush with the inside face of the wall and clad externally with aluminium for ease of maintenance. On the east and west elevations, fins project on the south side of the windows to provide both solar shading and acoustic protection from traffic noise. The fins have a 6mm steel plate core welded to a square hollow section (SHS) post that spans between the concrete floor slabs.


A galvanised steel balcony cantilevers off the concrete floor slab on the north elevation, made up in 2.4m lengths for ease of transportation. The balustrade is made from 20mm square steel bars except for the verticals at the end of each 2.4m length which are 10mm thick so that when two adjacent sections are joined the balustrade appears as one continuous run.

Larger elements of the programme have been located at the front of the building and the many cellular consulting rooms towards the rear. This arrangement allows the front elevation to be more loosely composed with fewer, big openings that give the Centre a strong civic presence. The shiny lustre of the panels brings to mind a smaller, tactile object like a chestnut.







North-south section – 1:600



East-west section – 1:600



Axonometric view from south-east



First floor plan – 1:600

Drawing labels:

1. Structural frame

500 × 200mm in-situ reinforced concrete columns.

2. Typical floor

Rubber flooring on levelling screed.  
300mm thick reinforced concrete floor slab spanning between columns.  
Painted exposed concrete soffit.

3. External wall infill structure

225mm light gauge galvanised steel channel studs spanning from floor to ceiling.  
225mm light gauge galvanised steel channel top and bottom tracks fixed to floor and ceiling.

4. Typical external cladding

10mm thick timber veneered panels made from wood fibre and paper bonded with phenolic resin and compressed at high pressure. Panels screw-fixed to continuous vertical aluminium angle rainscreen cladding rails. T-section cladding rails screwed to aluminium brackets screwed to sheathing at 900mm centres vertically and 600mm centres horizontally. 50mm rigid phenolic insulation. Breather membrane. 10mm cement particle board sheathing fixed to steel channels.

5. Internal lining

Vapour barrier.  
Two layers 12.5mm plasterboard taped and jointed with paint finish.  
80 × 15mm softwood architraves around windows.

6. Typical opening window

Laminated softwood window frame with polyester powder coated (PPC) aluminium cladding and beads. Double-glazed sealed unit consisting of 4mm toughened inner pane, 16mm air gap and 4mm toughened outer pane. Damp-proof membrane (DPM) fixed to rear of window frame and dressed around cement particle board lining to lap over breather membrane. 10mm cement particle board sheathing screwed to steel structure at head and jambs. 50mm rigid PIS insulation in steel channel at jambs and head. 10mm thick timber veneered panel window reveals screwed to steel structure.

7. Vertical fins

60 × 60mm galvanised rectangular hollow section (RHS) post with 80 × 60mm unequal angle brackets welded top and bottom bolted to slab via 10mm nylon spacers for thermal isolation. 2425 × 715 × 6mm thick galvanised steel plate welded to RHS post.

2600mm high × 10mm thick timber veneered panels screwed to both sides of steel plate. 70 × 70mm satin anodised aluminium T-section sandwiched between panels to stiffen and protect edges of panels.

8. Projecting windows on south elevation

Bronze anodised aluminium window frames made up from 125 × 50mm curtain walling box sections. Bronze anodised aluminium flashing with 25mm extruded polystyrene insulation screwed to window frame. Double-glazed sealed unit consisting of 4mm toughened inner pane, 16mm air gap and 4mm toughened outer pane. DPM bonded to outside of frame and dressed over cement particle board lining to lap over breather membrane. Plasterboard internal reveals. White painted MDF cill board.

9. Soffit

10mm thick timber veneered soffit panels screwed to aluminium rails. 100mm air gap. 50 × 50mm aluminium angle rails fixed to concrete slab via 50 × 50mm aluminium angle hangers at 600mm centres. 75mm rigid phenolic insulation. Breather membrane.

10. Balcony structure

Galvanised steel balcony structure made up in 2400mm lengths with semi-gloss top coat paint finish. 1810mm long × 350mm deep × 90mm wide tapered steel angle brackets.


11. Balustrade

Galvanised steel balustrade made up in 2400mm lengths with semi-gloss top coat paint finish. 20 × 20mm square-section solid steel horizontal member welded to 20 × 20mm solid vertical members at 120mm centres continuously welded to 250 × 18mm bottom front plate. Front plate bolted to 100 × 75mm galvanised steel angle.

12. Balcony decking

70 × 70mm galvanised steel angles back-to-back in 2400mm lengths bolted to angle brackets. 65 × 45mm black stained preservative treated softwood battens on softwood packers bolted to angles. 125 × 22mm black stained timber boards with 6mm gaps.






Cut-away section through first floor wall and windows



*Photo: H  l  ne Binet*



# Christchurch Tower, City of London

Architects: Boyarsky Murphy  
Structural Engineer: Greig Ling

An abandoned church tower in the City of London has been put to new use as a private house. Designed by Christopher Wren in 1677, Christchurch was bombed in the Second World War and only the tower survived. Twelve levels of floors and platforms have been inserted into the 50 metre-high tower connected by a helter-skelter of stairs and ladders.


Some repair work had already been carried out to the structure in the 1950s when the damaged steeple was taken down and rebuilt off a new concrete ring beam and an inner skin of Fletton brickwork was used to strengthen the stone ashlar. The original staircase built into the stonework in one corner of the tower has been enclosed with fire doors allowing a second circulation route to rise more freely through the house. The walls are 3 metres thick at the base but narrow higher up so the floor areas increase towards the top. The ninth floor is devoted to a living room with a spiral stair up to a library above. Glass is difficult to form to the 570 mm radius of the spiral staircase so an acrylic balustrade was made by heating the flat sheet and dropping it into a curved mould. The acrylic appears completely clear unlike glass that usually has a green tinge.

Where the tower narrows a retractable ladder takes the place of the stair. An 85 × 95 mm aluminium box fixed to the central post of the spiral stair contains a fold out ladder that leads up to another glass platform and then to a lookout terrace in the steeple. The glass platform has a steel frame held just off the double-curved stone walls by ferrule spacers around the resin-anchor bolts that hold it up.


The stonework has been JOS cleaned, a chemical-free process where a small amount of water and a fine abrasive powder are sprayed in a gentle swirling vortex to remove dirt without damaging the stone. A 'Hawksmoor detail' has been used for the window cills, so called by English Heritage because it was developed for St George's, the church he designed in Bloomsbury. New lead flashings have been laid over plywood to protect rather than repair the stone beneath and the lead dressed over the edge in the traditional manner without a projecting drip.









East-west section through tower – 1:250



9 – living room



10 – library



11 – mezzanine

Floor plans – 1:250

#### Drawing labels:

1. Existing walls below level 10  
Fletton solid bonded brickwork walls of varying thickness.  
Portland stone ashlar external facing.  
75 × 25 mm softwood battens.  
12.5 mm plasterboard with skim coat and white emulsion paint finish.
2. Ring beam  
710 mm deep concrete ring beam to support steeple above.  
1260 deep × 200 mm wide concrete upstand above ring beam.  
12.5 mm plasterboard with skim coat and white emulsion paint finish.
3. Existing walls above level 10  
Portland stone ashlar JOS cleaned internally and left exposed.
4. Flashing  
New code 4 lead flashing to parapet with 'Hawksmoor detail'.
5. Window  
Steel W20 window frame openable for cleaning and ventilation from outside only.  
6-12-6 double-glazed sealed unit with non-reflective glass.  
177 × 35 mm solid oak internal cill.  
New code 4 lead external cill.
6. Louvres  
New 900 mm wide × 195 × 40 mm Portland stone louvres bedded in existing grooves in stone window surrounds.
7. Level 10 landing  
160 × 80 mm rectangular hollow section (RHS) steel beams bolted into brickwork at both ends via 200 × 200 × 12 mm plates with four M16 expanding anchor fixings.  
125 × 75 × 8 mm unequal angle (UA) bolted to brickwork with M16 expanding anchors at 300 mm centres to support outside edges of landing.  
44 mm thick composite oak floor fixed to steelwork below at 300 mm centres.

#### 8. Level 11 landing

Prefabricated steel landing structure consisting of 100 × 60 × 6.3 mm gauge RHS leading edge beam and 100 × 50 mm parallel flange channels (PFC) to other three edges bolted to stone walls with resin anchored M20 threaded bars embedded min. 300 mm into stone. 40 mm diameter stainless steel ferrule spacers between steel frame and walls. Neoprene/silicone pads between steel and glass.

32 mm laminated clear glass floor made up from 18 mm toughened upper pane, pvb interlayer and 12 mm toughened lower pane. Glass panels decorated on top face with all-over bead-blast finish and protective coating.

#### 9. Balustrade

1100 mm high × 12 mm thick toughened clear glass balustrade.  
Polyester powder-coated (PPC) 160 × 12 mm mild steel clamping plate bolted at 500 mm centres with countersunk bolts to steel landing structure.  
Hard fibre isolation washers between steel and glass.

#### 10. Staircase

114.3 mm diameter stainless steel central pole. Polished stainless steel brackets welded to central tube.  
570 mm radius × 40 mm thick solid oak treads screwed to brackets from below.  
12 mm thick curved acrylic balustrade bolted to ends of treads with neoprene isolating washers. 35 mm diameter stainless steel handrail.


#### 11. Ladder

114.3 mm diameter stainless steel circular hollow section post welded to top of stair post. 6.25 m high proprietary extruded anodised aluminium pull-out ladder with 525 mm wide rungs and integral handrail.  
120 × 95 mm fixing brackets bolted to post at 1.5 m centres.  
Safety system channel bolted to vertical.


#### 12. Shelving

40 mm thick oak veneered shelving with solid oak lipping.





Cut-away section through levels 10 and 11



*Photo: Steve Ambrose*



Photo: Tom Ebdon



Photo: Steve Ambrose

## Halligan House St Albans

Architect: Simon Conder Associates  
Structural Engineer: Built Engineers



Photo: Steve Ambrose

A restricted budget has encouraged expedient use of inexpensive materials to make a new house in a sub-urban street in St Albans. When the building plot was sold off from the neighbouring house in 1965, a covenant was put in place restricting the building height to a single storey with a flat roof. The four-bedroom house is over 20 metres deep and extends the full width of the plot so light is brought in through courtyards and high-level clerestories over the kitchen and living room. A corridor bisects the house from front to back with the bedrooms on one side and the living spaces on the other. There are two studies for the parents who both work from home part of the time.

Load-bearing blockwork walls have been built off concrete strip footings, almost 40% of which remain from a previous house by John Winter that stood on the site. The ground floor is beam and block, spanning between the strip footings and topped with a floating concrete slab. A colour hardener has been worked into the surface of the concrete to form a resilient wearing surface. A power float could not reach the edges of the rooms so all the floors were hand-trowelled for an even finish.




Photo: Steve Ambrose


All the areas of glazing are framed with softwood posts that also support the raised clerestory roofs. Each softwood post has a hardwood strip routed and glued into its external face over which is screwed a pressed stainless steel profile. Double-glazed sealed units were bonded to the stainless steel plates in-situ using structural silicone. Where a timber post supports a roof joist the two were mitred and glued together with a biscuit joint. Softwood ribs were screwed and glued to the plywood roof deck so it could span further, enabling the spacing of the joists to match the 900 mm spacing of the vertical posts.

The external walls are clad in insulated render. A 3.2m-high screen made from iroko forms a trellis up which plants can grow, concealing the front of the house. The posts are bolted to stainless steel base plates on concrete pads. The iroko strips span across the gate and garage doors, filtering the view into the entrance space and hinting at the sequence of rooms and courtyards that lies beyond.






Exploded axonometric view



Site location plan – 1:1500



Ground floor plan – 1:300

Drawing labels:

1. Foundations

450 mm wide  $\times$  nominal 150 mm deep mass concrete strip foundations.  
275 mm wide 7 kN concrete foundation block wall.

2. Ground floor

155 mm deep precast concrete beams at 510 mm centres spanning between ground beams.  
440  $\times$  215  $\times$  100 mm medium density concrete blocks laid between beams grouted with sand/cement slurry.  
Three coats cold liquid-applied bituminous DPM (damp proof membrane).  
Rigid urethane insulation boards.  
Polythene sheet separating layer.  
72 mm thick floating C35 concrete slab with 10 mm aggregate.  
Under-floor heating pipes cast into concrete.  
Coloured metallic dry-shake hardener sprinkled and trowelled into surface of concrete to form wearing surface.

3. Ground floor slab edge

Epoxy bonding adhesive applied to top of foundation blocks and 145 mm wide in-situ concrete plinth cast on top.  
Three coats bituminous DPM applied to face of plinth.  
75 mm extruded polystyrene insulation.  
50  $\times$  3 mm aluminium plate screwed to glazing frame as render stop bead.  
Acrylic render external finish.

4. Glazing frame

145  $\times$  72 mm C24 strength European redwood posts at 900 mm centres.  
145  $\times$  72 mm C24 strength European redwood transom.  
70  $\times$  25 mm hardwood strips glued into grooves in external face of posts and transoms.  
72  $\times$  35 mm pressed stainless steel top hat sections screwed to hardwood strips.

5. Glazing

Double-glazed sealed units comprising 8 mm clear toughened glass outer, 16 mm air filled cavity, 8.8 mm 'K' laminated low-e glass inner. Outer leaf projects beyond spacer on all sides to cover stainless steel.  
Clerestory glazing same units but inner leaf sand blasted.


6. Vent panel

Two 1060 mm high  $\times$  340 mm wide vent panels made from 44 mm solid core door blanks with hardwood lips and seals to all sides.  
Two friction stay hinges rebated into side frames and two mortice latches operated by snib turns.  
Aluminium drip flashing at head.

7. Roof

145  $\times$  72 mm C24 strength European redwood joists at 900 mm centres.  
15 mm WBP birch plywood fixed to top of joists.  
9.5 mm plasterboard ceiling fixed to plywood between joists with plaster skim and painted finish.





Cut-away section through north elevation and entrance deck

30 × 30 mm C24 strength ribs glued and screwed to plywood at 400 mm centres to stiffen roof deck.  
30 mm rigid urethane insulation board between ribs.  
Polythene vapour control layer.  
75 mm rigid urethane insulation board.  
Fully adhered reinforced PVC waterproof membrane with polyester fleece backing.

#### 8. Roof edge detail

145 × 72 mm C24 strength European redwood transom at head of glazing.  
45 degree mitre at junctions of joists and posts fixed with circular 15 mm WBP ply biscuits and four dowels.  
145 × 44 mm European redwood pelmet.  
100 × 50 mm treated softwood edge strip fixed to plywood deck around roof perimeter.  
50 × 50 mm treated softwood batten fixed to edge strip around roof perimeter to control rainwater run-off.  
100 × 165 mm PPC (polyester powder coated) aluminium flashing with mitred corners fixed to softwood edge strip and hot-air welded to waterproof membrane.

#### 9. Typical wall construction

Acrylic render external finish.  
100 mm expanded polystyrene insulation bonded to blockwork.  
140 mm wide 7 kN concrete blockwork load-bearing wall.  
13 mm plaster internal finish.

#### 10. Front door

140 × 100 mm concrete lintel.  
152 × 58 mm hardwood frame with continuous groove to accept flange of plaster stop bead.  
235 × 72 mm hardwood threshold with continuous drip groove to underside.  
2100 mm high × 1200 mm wide × 44 mm thick solid core softwood door leaf with hardwood lips and seals to all sides mounted on floor pivot.

#### 11. Fence

450 × 450 × 400 mm deep concrete pads at 1350 mm centres.  
140 × 140 mm iroko posts with heads cut to 30° angle fixed to stainless steel base plates bolted to pads.  
38 × 38 mm iroko horizontal slats at 65 mm vertical centres to door head level and at 130 mm centres above with three staggered stainless steel screw fixings at each post.

#### 12. Decking

140 × 25 mm iroko decking with 10 mm gaps between planks with joints staggered and centred over joists fixed with two stainless steel screw fixings at each joist.  
150 × 50 mm Tanalith E treated softwood joists at 750 mm centres.  
150 × 50 mm continuous Tanalith E treated softwood wall mounted ledger spaced off render face.  
140 × 140 mm iroko post terminating directly under decking with rear of head notched to take continuous double joist comprising 144 × 44 mm iroko facing to continuous 150 × 50 mm treated softwood inner joist.

This page intentionally left blank



*Photo: Cristobal Palmer*





Photo: Cristobal Palmer



Photo: Cristobal Palmer

## Herringbone Houses Wandsworth, London

Architect: Alison Brooks Architects

Structural Engineer: Price & Myers



Photo: Alison Brooks Architects


Two houses in a leafy south London suburb are clad with hardwood in a herringbone pattern that gives them a distinctive identity from the surrounding Edwardian villas. The houses are approached down a 45m-long driveway along the side of a bowls club, their squat forms rising above a fence to survey the bowling green. Each house is composed around a dramatic two-storey central hallway with a rooflight above so light is brought down deep into the plan. The stair is offset to one side so that from the front door you see straight through to the back garden with the sky above. From many points on the ground floor the surrounding mature trees and gardens are visible in two or three directions at once, giving the sense of the house as the centre of a landscape of internal and external spaces.

Each house has a steel frame on a concrete basement structure. The floors are precast concrete planks with screed and underfloor heating. The external walls consist of two studwork frames between the primary steel members, one supporting the inner plasterboard lining and the other supporting the external sheathing and cladding. Above and below the large sliding windows the steel beams have been over-sized to support them and provide head restraint as this was deemed cheaper than constructing more complicated secondary steelwork off the primary structure.




Photo: Alison Brooks Architects


The cladding is Ipe, one of the hardest, most durable tropical hardwoods. Site cutting of the timber was minimised by using 800 mm lengths, pre-cut with angled ends. The boards have been laid in alternating horizontal rows at an angle of 22.5 degrees fixed with countersunk stainless steel screws to horizontal softwood battens which, in turn, were fixed to vertical battens to provide a continuous air gap for ventilation behind the timber. Each board is fixed with a single screw at either end rather than the normal two and the holes were drilled prior to delivery to site to reduce on-site labour. Finally, each screw hole was laboriously capped with an ipe plug and sanded off flush. At the corners a thin L-shaped strip of ipe covers the end grain without disturbing the sweep of the herringbone bands around the houses. Light reflects off the timber turning the whole building into a magnificent composition of shimmering silver and copper brown.




Second floor plan – 1:500




First floor plan – 1:500




Section AA – 1:500



Section BB – 1:500



Section CC – 1:500



Ground floor plan – 1:500

Drawing labels:

1. Primary steel frame  
UC (universal column) columns with cross bracing.  
RHS (rectangular hollow section) or UC beams.

2. Typical wall  
65 × 19mm profiled ipe boards, pre-cut in 800mm lengths and pre-drilled, fixed with two countersunk stainless steel screws at a 22.5° angle to vertical in herringbone pattern.  
50 × 25mm treated softwood horizontal battens at 800mm centres.  
50 × 25mm treated softwood vertical battens at 600mm centres.  
Breather membrane.  
50 × 50mm treated softwood battens at 600mm centres with rigid insulation in between.  
18mm plywood sheathing.  
20mm rigid insulation.  
195mm thick studwork made up from 100 × 50mm softwood studs at 600mm centres on external face and 70 × 50mm softwood studs at 600mm centres on internal face.  
Vapour barrier.  
12.5mm plasterboard with skim coat and 15 × 40mm aluminium angle skirting.

3. Upper floor  
150 × 20mm floating hardwood flooring.  
30mm acoustic absorbent insulation.  
65mm screed with underfloor hot water heating pipes.  
150mm deep precast hollow core concrete planks spanning between steel angles welded to sides of beams as necessary.  
Proprietary suspended ceiling system.  
12.5mm plasterboard with skim coat.

4. Balcony floor  
150 × 19mm ipe boards fixed with countersunk stainless steel screws to hardwood battens.  
Single ply PVC waterproof membrane with single piece welded scupper outlet in back corner to rainwater pipe concealed behind cladding.  
Tapered rigid insulation at 1 in 80 fall to concealed gutter at rear.  
150mm deep precast hollow core concrete planks spanning between steel angles welded to sides of beams as necessary.

5. Balcony flank wall  
50 × 25mm treated softwood carcassing to form tapered balcony flank wall.  
Straight wall at opposite end incorporates mild steel ladder frame made up from 50 × 50mm

SHS (square hollow section) edge members and 100 × 50mm RHS horizontal members for stiffness.  
65 × 19mm profiled ipe boards, pre-cut in 800mm lengths and pre-drilled, fixed with two countersunk stainless steel screws at a 22.5° angle to vertical in herringbone pattern.  
50 × 50mm ipe angle cover strip at corner.

6. Balustrade  
16mm clear toughened glass cantilevered balustrade.  
Steel plate bracket and clamping plate to secure balustrade back to primary steel frame at base.


7. Roof  
Single ply PVC waterproof membrane.  
120mm tapered rigid insulation.  
90mm sand-cement structural topping.  
Bituminous vapour barrier.  
150mm deep precast hollow core concrete planks spanning between steel angles welded to sides of beams as necessary.  
Proprietary suspended ceiling system.  
12.5mm plasterboard lining with skim coat and painted finish.

8. Roof perimeter upstand  
185 × 75mm softwood studwork upstand built up of roof edge beam.  
18mm WBP plywood sheathing.

9. Balcony roof  
Single ply PVC waterproof membrane.  
18mm WBP plywood on softwood carcassing.  
Painted steel angle members bolted back to roof edge beam to support balcony roof.  
100 × 70mm treated softwood battens at 800mm centres at 36° from horizontal to form soffit.  
65 × 19mm profiled ipe board soffit, pre-drilled and fixed with two countersunk stainless steel screws in herringbone pattern.

10. Window  
Satin anodised aluminium sliding window frame supported off primary steel floor beam on back-to-back steel angle brackets and restrained to roof beam at head.  
Aluminium flashing at window head fixed behind breather membrane.  
Double-glazed sealed units.

11. Window support steelwork  
Certain primary steel members oversized above and below windows to support and restrain window frames.



Cut-away section through south-west corner of upper floor





*Photo: Denis Jones*





Photo: Gaunt Francis Architects



Photo: Denis Jones

## GreenHouse, BRE, Watford

Architect: Gaunt Francis Architects

Structural, Environmental and Services Engineer: Arup



Photo: Peter White




A prototype house at the BRE Innovation Park in Watford was the first home built by a major house-builder to achieve level 6 under the Code for Sustainable Homes. The Barratt GreenHouse was the winner in a popular vote in the British Homes Awards' Home for the Future Competition in 2007. The competition demanded a house with excellent sustainability credentials and design qualities but crucially one that could be built by a mainstream volume house-builder. It has a highly insulated concrete structure to provide thermal mass and incorporates measures such as rainwater harvesting, solar-thermal water heating and an air-source heat pump to reduce its impact on the environment.

A 350mm thick reinforced concrete raft rests on 280mm of insulation below ground. The external walls are formed from load-bearing precast aerated concrete slabs that were craned into position and tightly butt-jointed together with thin joint mortar in between. Precast concrete floor planks span between the storey-height wall slabs. The load-bearing walls are kept to the perimeter to allow future flexibility in the arrangement of each floor internally. To achieve a very high air-tightness the walls were sprayed internally with a 4mm coat of polymer-bound plaster. At openings the gaps between the triple glazed window frames and the wall panels have been filled with expanding foam tape and then taped up with foil sealant strips. Over each window a track for a sliding shutter is fixed back to the masonry wall via an insulated structural element which is concealed beneath the render.




Photo: Peter White

The roof and triangular gables were prefabricated and delivered to site as cassettes with insulation already in place. Part of the roof has a sedum blanket finish and the rest is clad in photo-voltaic and solar-thermal panels over a single-ply waterproof membrane. There was not enough roof area to achieve Code 6 requirement for energy generation with the efficiency of solar panels available at the time so additional panels are located behind the house. Also, rather bizarrely, two arrays of solar-thermal panels are fixed on a wall close beneath the eaves so as to be partially in the shadow of the roof. The house is being rigorously tested but there is still a way to go before the practicalities and costs of achieving Code 6 are realistic for the mass-housing market.



Second, first and ground floor plans – 1:200



North-south section – 1:200



East-west section – Not to scale

Drawing labels:

1. Foundation and ground floor  
18 mm tongued and grooved timber floorboards.  
53 mm void formed with 45 × 45 mm softwood battens with foam isolating strips bonded to concrete floor at 400 mm centres.  
350 mm reinforced concrete ground floor slab and raft foundation.  
500 mm gauge polyethylene vapour barrier.  
80 mm extruded polystyrene thermal insulation.  
1200 mm gauge radon gas barrier consisting of polyethylene outer layers and aluminium foil core.  
200 mm extruded polystyrene thermal insulation.  
50 mm sand blinding.  
100 mm mass concrete.  
150 mm compacted hardcore.

2. External wall  
Insulated render system consisting of reinforced polymer render on 180 mm phenolic foam insulation boards mechanically fixed to concrete panels.  
600 × 200 mm storey-height load-bearing prefabricated aerated concrete panels with thin-joint mortar.  
4 mm spray applied polymer bound internal coating to panels to seal joints.  
25 mm vertical softwood battens.  
12.5 mm plasterboard dry lining with plaster skim finish.  
Shadow gap beads at top and bottom.  
90 × 15 mm softwood skirting.

3. Slab edge  
Insulated render system consisting of reinforced polymer render on 170 mm extruded polystyrene insulation boards mechanically fixed to concrete.  
Radon gas barrier dressed up face of concrete and mechanically fixed using render starter track.  
Sealant strip between render starter track and render below.

4. Upper floor  
18 mm tongued and grooved timber floorboards.  
53 mm void formed with 45 × 45 mm softwood battens with foam isolating strips bonded to concrete floor at 400 mm centres.  
150 mm thick precast concrete planks spanning between blockwork walls.  
20 mm plaster finish to ceilings.


5. Typical window  
Triple-glazed laminated softwood opening window.  
20 mm expanding foam strips on all sides between frame and blockwork.  
Foil strip bonded between frame and blockwork internally to seal joints.  
100 × 75 × 8 mm steel angle brackets.  
220 × 30 mm softwood external window surround fixed back to blockwork on 100 × 75 × 8 mm steel angle brackets.

6. Shutter  
Sliding shutters hung on extruded aluminium track.  
Top track mechanically fixed to insulated fixing element.  
Bottom guide track screwed to front of window cill.

7. External gable wall  
Insulated render system consisting of reinforced polymer render on 180 mm phenolic foam insulation boards mechanically fixed to spandrel panel.  
Prefabricated spandrel panel consisting of 95 × 50 mm softwood studwork frame with 13 mm plywood inner and outer linings.

8. Sedum roof  
Sedum roof blanket and waterproof system.  
Prefabricated roof panel system consisting of: 22 mm bitumen impregnated sheathing board made from sawdust and recycled paper.  
55 × 50 mm softwood battens at 500 mm centres with PIS (polyisocyanurate) insulation between.  
245 × 50 mm softwood rafters with PIS insulation between.  
12.5 mm OSB (oriented strand board) inner sheathing.  
Vapour barrier on inner face.

9. Roof verge  
300 mm wide pebble perimeter strip around sedum roof.  
270 × 140 mm timber upstand.  
Pre-patinated copper capping fixed to upstand on copper clips.  
525 mm deep pre-patinated copper cladding to verge on isolating membrane.  
Pre-patinated copper-clad soffit board.  
50 mm shadow gap with black plastic board lining between soffit and rendered wall.



Cut-away section through east façade





*Photo: Jefferson Smith*



Photo: bere:architects



Photo: bere:architects

## Focus House, Finsbury Park, London

Architect: bere:architects

Structural Engineer: Techniker



Photo: Jefferson Smith

Focus House incorporates low embodied energy materials and low lifetime energy consumption to minimise its carbon footprint. It is also a highly inventive home architecturally on a tight, infill site in north London. Only 2.8m wide at the entrance, the house widens to 7m at the back where it opens on to a small garden. The shell was constructed from prefabricated, cross-laminated, solid timber panels manufactured in Austria. The panels are made precisely to size with service chases, window and door openings factory-cut. Its thermal mass helps control temperature variations inside and the timber effectively stores 42.4 tonnes of carbon, easily offsetting the 3 tonnes emitted from its transportation.


Dark grey zinc-titanium cladding on all the external surfaces unites the volumes. The metal sheets are clipped to metal plates spiked directly into cellular glass insulation, so there are no thermal bridges across the insulation layer. The insulation is cut to falls and is 500mm deep at its thick edge. The roofs fall to the south edge where the zinc is folded to form a continuous gutter that runs down the vertical faces in place of rainwater pipes. The ventilation gap behind the zinc was eliminated because the insulation is completely waterproof and vapour impermeable and the zinc has a special anti-corrosion coating on the back. The outer face of the insulation was covered with a torch-on felt. Loosely woven spun nylon matting beneath the zinc traps a layer of air and separates it from the insulation allowing for expansion and providing some acoustic insulation.




Photo: Jefferson Smith

Fresh air is supplied to the whole house with a mechanical ventilation system using a 95% efficient heat exchanger to warm incoming air with waste heat from the bathroom extracts. More than half the annual water heating energy will come from a solar installation high up on the south elevation, supplemented by a gas-fired boiler. Total carbon storage benefits of the Focus House amount to a total CO<sub>2</sub> extraction of 30 tonnes. This is calculated by total emissions of 3.11 tonnes for the concrete slab and foundations including piles (70% GGBS) and 5.24 tonnes for the zinc cladding, which has the lowest embodied carbon of any metal, set against CO<sub>2</sub> extraction of 39 tonnes for the wood structure.







Second floor plan – 1:300



First floor plan – 1:300



Ground floor plan – 1:300



East-west section – 1:300

#### Drawing labels:

##### 1. Foundations

600 × 450 mm reinforced concrete ground beam with waterproof additive.  
200 mm thick reinforced concrete slab with waterproof additive spanning between ground beams.  
100 mm extruded polystyrene insulation below slab on 50 mm sand blinding.

##### 2. Ground floor

180 × 21 mm European oak engineered timber floorboards with grey oiled finish.  
Low temperature hot water underfloor heating pipes with metal radiation plates suspended between battens.  
50 × 50 mm treated softwood battens at 300 mm centres.  
50 mm rigid insulation between battens.  
Polythene vapour barrier.  
200 mm thick reinforced concrete slab with waterproof additive spanning between ground beams.  
100 mm extruded polystyrene insulation below slab on 50 mm sand blinding.

##### 3. Slab edge

200 × 150 mm concrete upstand around slab perimeter.  
Bituminous liquid-applied waterproofing membrane to side and top of upstand.  
100 mm rigid polystyrene insulation.  
40 mm thick precast concrete paving slabs fixed back to upstand on stainless steel brackets.

##### 4. Typical wall

Zinc alloy sheet cladding with angled double standing seams folded over clips spiked into insulation.  
Bituminous felt waterproof layer.

Liquid applied bituminous sealant to fill any gaps in insulation.

140 mm foamglass insulation bonded to solid timber panel with bituminous adhesive.

128 mm (94 mm on upper floor) solid cross-laminated timber wall panel notched over and fixed to softwood batten wall plate fixed to concrete upstand.

Plasterboard fixed to inside face of timber panel with skim coat and paint finish.

##### 5. Gutter

180 × 80 mm deep pre-formed folded zinc alloy sheet gutter folded over clips spiked into insulation.  
Bituminous felt waterproof membrane.  
Foamglass insulation around gutter.


##### 6. Typical window

Proprietary softwood framed double-glazed high-performance window.  
Softwood sub-frame fixed to structural timber panel.  
Preformed-zinc alloy cill slotted into route in bottom of window frame.

##### 7. Roof

Zinc alloy sheet cladding folded over clips spiked into insulation.  
10 mm spun nylon open-weave matting to allow ventilation, expansion and acoustic isolation.  
Bituminous felt waterproof layer.  
Liquid applied bituminous sealant to fill any gaps in insulation.  
Tapered Foamglass insulation varying from 500 mm maximum to 140 mm minimum thickness.  
146 mm solid cross-laminated timber panel structural deck sealed internally with coloured natural wax.





Cut-away section through side wall, window and roof.



*Photo: Prewett Bizley Architects*





Photo: Prewett Bizley Architects




Photo: Astrid Kogler

## 80% House, De Beauvoir Town London

Architect: Prewett Bizley Architects

De Beauvoir Town is a tranquil conservation area of Victorian villas and terraces due north of the City in Hackney. This 'extreme' refurbishment of a typical terraced house is aimed at reducing its carbon emissions by 80% in line with the Government's pledge to cut greenhouse gas emissions by that amount by 2050.

The house has been extended by 2 metres to the rear at the lower two levels to create a kitchen/dining room at lower ground and a generous living space at upper ground level. A rooftop extension provides a third bedroom. The extra space offsets the area lost to extra insulation and provides a layout more appropriate to current patterns of inhabitation.

The two most important measures in reducing energy loss are high levels of insulation and air tightness. At the front a new, independent insulated wall has been built inside the existing brickwork. The existing joists were cut back and re-supported on a steel beam spanning between the party walls to remove the cold bridge. New timber sash windows have been installed incorporating micro-double-glazed units with 20mm astragals to match the original windows.

The rear elevation has been rebuilt using the same stock bricks but as a 400 mm thick cavity wall with full-fill insulation and basalt-fibre wall ties to reduce cold bridging. The windows are triple glazed. Steel has been used to frame the large openings of the rear extension and concrete slabs at first and second floor provide thermal mass.

An excellent air tightness level of  $1.1 \text{ m}^3/\text{hr}/\text{m}^2$  @ 50 Pa has been achieved by lining the existing walls with OSB and taping all joints. Fresh air is supplied by a MVHR (mechanical ventilation heat recovery) system which uses a heat exchanger to transfer heat from the extract air to the fresh air at about 90% efficiency.

Because the floor area is very limited it was decided to use the insulation with the highest thermal performance in each location even if it does not have the lowest embodied energy as the potential lifetime energy savings are much higher. A photovoltaic array on the roof with a 1000 kWh output provides about half the annual electricity requirement. It has been calculated that after six years the energy saved will have offset the energy used to carry out the refurbishment.



Photo: Prewett Bizley Architects



Photo: Prewett Bizley Architects








Diagram showing MVHR system



Upper ground floor plan – 1:150



Sketch east-west section showing improvements carried out

Drawing labels:

1. Ground floor

Existing floor removed and ground excavated 150 mm.  
20 mm ceramic screed replacement tile finish.  
30 mm extruded polystyrene insulation with clip-in underfloor heating pipes.  
100 mm extruded polystyrene insulation.  
Liquid applied DPM (damp proof membrane).  
150 mm reinforced concrete slab with edge upstand to support wall lining.

2. Front wall

Existing 330 mm stock brick wall with external stucco finish up to upper ground floor level.  
15 mm sand/cement render applied to inner face to seal gaps.  
Minimum 25 mm air gap ventilated via weepholes and airbricks.  
25 mm aluminium top-hat sections screwed to brickwork at 400 mm centres.  
12 mm OSB (oriented strand board) sheathing.  
70 × 50 mm vertical rigid insulation spacer battens at 400 mm centres with glass mineral wool insulation in between.  
18 mm OSB air-tightness layer with all joints taped.  
70 × 50 mm horizontal rigid insulation spacer battens at 400 mm centres with glass mineral wool insulation in between.  
12 mm OSB sheathing.  
12 mm foil-backed plasterboard internal lining with plaster skim coat.

3. Front windows

New bespoke softwood sliding sash windows with four seals at all sash edges.  
Micro-double-glazed units consisting of 4 mm outer, 6 mm argon-filled cavity and 4 mm low-e inner pane.

4. Window linings

18 mm WBP plywood box fixed to outside of window frames on all sides prior to installation and sealed with two silicone beads.

DPM liquid applied to rear face of plywood and window frames.

Inside edges of plywood sealed to surrounding construction with air-tightness tape.  
Expanding foam to fill all gaps between frame and masonry.

5. First floor at front

150 × 20 mm tongued and grooved pitch pine floorboards secret-nailed to plywood.  
18 mm tongued and grooved plywood screwed to joists.  
203 × 102 mm × 23 kg UBs (universal beam) spanning between party walls.  
Existing softwood joists cut off and hung off steel beam on joist hangers to eliminate cold bridge.  
Two layers 12 mm plasterboard ceiling on softwood battens with plaster skim coat.

6. First floor in extension

Paired 203 × 102 mm × 23 kg UBs spanning between party walls.  
150 mm reinforced concrete slab.  
Floor and ceiling as 4 above.

7. Party wall linings


Existing stock brick wall.  
15 mm sand/cement render to seal gaps.  
50 mm light gauge steel studs screwed to wall at 400 mm centres with 50 mm glass mineral wool acoustic insulation in between.  
18 mm OSB air-tightness layer with all joints taped.  
12 mm plasterboard with plaster skim coat.

8. Air-tightness tape

Proprietary air-tightness tape to seal gaps between different materials.

9. Rear walls

102 mm reclaimed stock brick outer leaf.  
200 mm glass mineral wool full-fill insulation impregnated with silicone for moisture resistance.  
Basalt fibre wall ties to reduce cold bridging.  
100 mm aerated blockwork inner leaf.  
15 mm sand/cement render with skim coat finish.



Cut-away section through front and rear façades

10. Rear windows

Laminated softwood framed windows.  
Triple-glazed sealed units with argon filled  
cavities and low-e coating.  
Double seals on opening lights.  
Concrete cills cast on site with DPC below.

11. Second floor structure

Paired 203 × 102 mm × 23 kg UBs spanning  
between party walls and bearing on paired  
100 × 100 mm H columns.  
Existing joists re-used and hung off steel beam  
on joist hangers.  
Floor and ceiling as 4 above.

12. Insulation blocks

Single course of 115 × 100 mm foamglass  
insulation blocks built into walls to eliminate  
cold bridges.

13. Roof

Sedum planting in growing medium on  
geotextile layer.  
EPDM rubber waterproof membrane.  
140 mm rigid urethane insulation.  
50 mm insulation to upstands.  
Polythene vapour barrier continued up masonry  
walls to bond with DPCs.  
Sand/cement screed laid to fall.  
150 mm reinforced concrete slab.  
12 mm plasterboard ceiling on softwood  
battens with plaster skim coat.

14. Parapet

530 mm wide concrete copings cast  
on site.

DPC over cement-fibre slate cavity closers.



This page intentionally left blank



*Photo: Nick Kane*



Photo: Nick Kane



Photo: Nick Kane

## Clay Field Housing Elmswell, Suffolk

Architect: Riches Hawley Mikhail Architects  
Sustainability Consultant: Buro Happold



Photo: Riches Hawley Mikhail Architects

An affordable housing development in the Suffolk village of Elmswell combines strategies for sustainable construction, lifetime energy use and landscape to achieve exemplary low levels of embodied energy and carbon emission. The 22 houses and four flats each have their own private garden and are grouped in threes around three communal gardens. Rainwater is collected to flush toilets and to water the gardens. The houses are oriented east-west to maximise solar gain and heat and hot water are provided by a shared biomass boiler.

The dwellings have timber frames that were partially prefabricated in sections off-site. The walls are raised off the ground slightly on masonry plinths to protect the timber from rising damp and there are ventilated voids beneath the timber floors. 12 mm Sasmox sheathing, a gypsum reinforced fibreboard, has been fixed on the inside to brace the frame. The walls are insulated with Hemcrete, a mixture of hemp, hydrated lime and a small amount of Portland cement as a binder to accelerate the curing process, which sets to form a rigid, breathable layer. The Hemcrete was mixed on site and sprayed onto the timber frames to ensure there are no gaps that might compromise air-tightness.


On the gable walls the Hemcrete has been finished with 20 mm of lime render. The window openings on the gable are lined with 25 mm Heraklith wood fibre boards to form a square reveal and the lime render is returned into the reveals. The north and south elevations are clad in cedar boards on timber studwork battens built out from the primary frame. Isonat, another hemp-base product made with recycled cotton fibre and a thermoplastic binder has been used to insulate the roof. The building control officer deemed that the cedar shingle roof constituted a risk for spread of flame so the rafters have been 'overdrawn' with a layer of calcium silicate board to provide 30 minutes' fire protection.

Curved walls provide privacy and enclosure to the gardens. They are built from unfired clay blocks rendered both sides with lime render and capped with a cedar shingle coping. There are three low-maintenance gardens which are seen as part of a wider village life, a wild flower meadow, allotments and an orchard of Suffolk apples.




Photo: Riches Hawley Mikhail Architects






First floor plan of two bedroom house – 1:200



Ground floor plan of two bedroom house – 1:200



Section through two bedroom house – 1:200



Site plan – 1:2000

#### Drawing labels:

##### 1. Foundations

450 mm wide  $\times$  1000 mm deep reinforced concrete footings consisting of 50% GGBS (ground granulated blastfurnace slag).

##### 2. Ground below floor

Weak mix concrete blinding.  
Polythene DPM (damp proof membrane) dressed up plinth and bonded to blockwork with double sided tape.  
50 mm sand blinding.  
Minimum 150 mm compacted hardcore.

##### 3. Plinth

190 mm high  $\times$  215 mm wide concrete blockwork inner leaf plinth.  
DPC (damp proof course) bonded with polythene DPM and dressed over blockwork and up side of softwood floor structure.  
140  $\times$  32 mm treated softwood sole plate to support floor joists.  
215 mm high  $\times$  190 mm wide concrete blockwork outer leaf plinth where retaining – elsewhere 215  $\times$  100 mm.  
Five courses engineering brick with lime mortar.  
Gap between inner and outer plinths filled with 50 mm polystyrene insulation and weak mix concrete.  
DPC below top course of brick dressed over concrete and bonded to inner leaf DPM.

##### 4. Ground floor

18 mm tongued and grooved particle board floor.  
Breather membrane.  
194  $\times$  50 mm treated softwood joists at 400 mm centres.  
Breather membrane stapled to tops of joists and dressed down sides to carry insulation.  
150 mm insulation made from hemp and recycled cotton.  
238 mm ventilation gap below joists.

##### 5. Gable wall

Three coat limewash finish.  
20 mm lime render outer finish.  
250 mm Hemcrete sprayed onto prefabricated panel.  
Prefabricated structural wall panel consisting of 140  $\times$  50 mm softwood studs at 600 mm

centres with 12 mm gypsum reinforced fibreboard internal lining infilled with sprayed Hemcrete.  
Paint finish internally.

##### 6. Window in gable wall


25 mm Heraklith (magnesite woodfibre) board fixed back to timber studwork on all four sides to form opening in Hemcrete wall.  
Laminated softwood window frame fixed to timber studwork.  
Double-glazed sealed units with low-e coating.  
Pressed aluminium external cill fixed to frame and to wood-fibre board with aluminium clips.  
104  $\times$  32 mm softwood cill and internal lining to all four sides of opening.

##### 7. North and south walls

142 mm shiplapped tapered western red cedar boards fixed to battens with stainless steel nails.  
50  $\times$  25 mm vertical treated softwood battens at 600 mm centres.  
Breather membrane.  
75  $\times$  50 mm horizontal treated softwood battens at 600 mm centres.  
75 mm Hemcrete sprayed between battens.  
Prefabricated structural wall panel consisting of 140  $\times$  50 mm softwood studs at 600 mm centres with 12 mm gypsum reinforced fibreboard internal lining infilled with sprayed Hemcrete.  
Paint finish internally.

##### 8. Roof

Western red cedar shingles.  
50  $\times$  25 mm treated softwood battens at 123 mm centres.  
50  $\times$  50 mm treated softwood battens at 400 mm centres forming ventilation gap.  
Breather membrane.  
100 mm insulation made from hemp and recycled cotton between 100  $\times$  50 mm treated softwood battens.  
9 mm calcium silicate board to provide fire protection to structure below.  
175 mm insulation made from hemp and recycled cotton between 175  $\times$  50 mm treated softwood rafters at 400 mm centres.  
Vapour barrier.  
12.5 mm plasterboard ceiling with skim coat and paint finish.



Cut-away section through gable wall, roof and garden wall

9. Eaves

120 × 22 mm cedar fascia.

Galvanised steel half-round gutter on brackets screwed to fascia.

Breather membrane lapped over DPC and dressed into gutter.

9 mm calcium silicate board returned to provide fire protection to eaves beam.

10. Garden wall

314 mm wide engineering brick cavity wall plinth with lime mortar.

DPC 150 mm above ground level.

Cavity filled with weak mix concrete below DPC level.

Solid wall above plinth made from

350 × 100 × 255 mm unfired wide earth blocks bedded in lime mortar.

20 mm lime render to both faces with three coat limewash finish.

11. Garden wall coping

Cedar ridge cap.

Two courses cedar shingles with minimum 50 mm lap over outer faces of wall.

Breather membrane.

Continuous triangular treated softwood block.

Continuous plywood.

DPC.


Top course of brick bedded in lime mortar.



This page intentionally left blank




*Photo: Ioana Marinescu*



*Photo: Simon Lewis*



*Photo: Simon Lewis*



*Photo: Ioana Marinescu*



*Photo: Ioana Marinescu*

## Chance Street Housing Bethnal Green, London

Architect: Stephen Taylor Architects


Stair Fabricator: Tin Tab Ltd

In Victorian times the Nichol was a dense East End slum consisting of tiny terraced houses suffering from horrendous overcrowding and poverty. Most of it was demolished in the late nineteenth century but the narrow streets and cobbled surfaces remain. This development of three new terraced houses fills the whole of a 12 × 9 metre plot previously occupied by a single storey industrial shed. A three-storey brickwork façade completes the urban block, reinforcing the hard edge and intimate character of the street.


Each house is only 4 metres wide but the terrace is ingeniously planned with a narrow courtyard at the back that allows each house a dual aspect. The 2 × 2 metre courtyards are fully glazed on two sides and the other two walls have an outer leaf of white clay bricks to reflect light down. The timber framed glazing has a combination of fixed panels and folding/sliding doors to allow the rooms to open up and appropriate the courtyard. Dining/kitchen spaces are located on the top floor to take advantage of the best light. A ground floor porch provides a buffer between each house and the street, protected by a folded 'curtain' of perforated metal that allows eastern sunlight to penetrate.

A laminated timber staircase twists its way up next to the light well bringing a sculptural finesse to the interior. The stair is made from a single material, laminated timber, CNC cut into a kit of panels which were assembled off site into several large pieces. 19mm thick sheets were used for the treads and risers and 27mm for all other pieces. A 20mm gap was allowed on all sides for tolerance as the walls were already plastered and painted before the stair was installed. Stainless steel spacers were cut on site to suit and the bolt holes in the timber have been concealed with larch plugs. At ground floor the stair panels are birch-faced and stained dark like the brick on the main elevation facing the street. On the floor above, the stair has a knotty, strong-grained larch finish. The walls and ceiling are white so that looking up the stair you see a gradation from dark to light, enhancing the transition from the gritty street to the private domestic realm.







Second floor plan – 1:250




First floor plan – 1:250



Ground floor plan – 1:250



East-west section – 1:250



Sectional model through courtyards – David Grandorge

#### Drawing labels:

##### 1. Foundations

Reinforced concrete piles.  
600 × 400 mm deep concrete ground beams.

##### 2. Ground Floor

500 × 500 × 20 mm tiles on adhesive bed.  
5 mm flexible adhesive.  
Electric underfloor heating.  
50 mm polymer-modified cement/sand screed.  
Polythene vapour barrier.  
70 mm phenolic insulation.  
Damp proof membrane.  
225 mm thick reinforced concrete slab spanning between ground beams.  
50 mm concrete blinding.  
150 mm compacted hardcore.

##### 3. External party wall

100 mm concrete blockwork outer leaf.  
100 mm cavity.  
100 mm concrete blockwork inner leaf.

##### 4. Windows

Double 225 × 50 mm softwood joists at floor edges to support windows.  
64 mm thick laminated timber windows.  
Double-glazed sealed units.  
Folded aluminium external cills.

##### 5. Typical upper floor

1200 × 600 × 15 mm plywood panel floating floor.  
Underfloor heating layer consisting of moisture barrier on carbon heating film on 6 mm insulation.  
18 mm plywood deck.  
225 × 50 mm softwood joists at 400 mm centres.  
100 mm mineral wool insulation between joists.  
12.5 mm plasterboard ceiling with skim coat and paint finish.

##### 6. Internal partition

70 mm metal channel studs.

##### Mineral wool insulation between studs.

Two layers 12.5 mm sound insulating plasterboard to each side with skim coat and paint finish.

##### 7. Ground to first floor staircase

27 mm tri-ply laminated timber stringer.  
19 mm butt-jointed tri-ply treads and risers.  
27 mm tri-ply balustrade with profiled softwood handrail.  
Two layers 12.5 mm plasterboard fire resisting ceiling fixed below stair on isolating hangers.

##### 8. First-second floor stair stringer

27 mm tri-ply laminated timber stringer.  
Stair and landing stringers fixed to wall using 38 mm long M12 bolts screwed into 90 mm long × 25 mm diameter mild steel anchors chemically bonded into masonry.  
Bolt heads concealed with larch veneer plugs.  
Stringer held nominal 25 mm off plaster wall with 38 mm diameter stainless steel spacers.

##### 9. First-second floor stairs

830 mm wide × 19 mm thick butt-jointed larch-faced tri-ply treads and risers.  
Outer veneer of tread laps over riser to cover end-grain of riser.

##### 10. First-second floor balustrades


27 mm thick larch-faced tri-ply balustrade panels fixed to stringers.

##### 11. Second floor landing

27 mm thick larch-faced tri-ply stringers with 100 mm deep notches to accept joists.  
850 mm wide × 200 mm deep × 27 mm thick larch-faced tri-ply joists glued into notches in stringers at 250 mm centres.  
27 mm thick larch-faced tri-ply floor panel.

##### 12. First floor desk

1800 mm wide × 600 mm deep × 27 mm thick larch-faced tri-ply desktop with 75 mm deep downstand along front edge.  
Desktop jointed to 27 mm thick tri-ply stringer supporting stair above.



Cut-away section through staircase



*Photo: Tim Soar*





Photo: Edmund Sumner



Photo: James White



Photo: Edmund Sumner

## Islington Square Housing, Manchester

Architect: FAT

Structural Engineer: Whitby Bird


The Cardroom Estate was a deprived community just to the east of Manchester's city centre that was suffering from depopulation and a lack of shops and services. In a plan drawn up by Alsop Architects, Urban Splash are completely redeveloping and rebranding the area as New Islington. The new community will eventually boast 1400 new homes. For this development of 23 social housing units, FAT have worked closely with the residents to make a strong urban street frontage using conventional construction techniques and incorporating symbolic references to the idea of home. The dwellings were designed to Lifetime Homes standards and achieve an EcoHomes rating of 'excellent'. The units are a mixture of two bedroom flats and three or four bedroom houses laid out in two parallel terraces with private gardens in between.

New Islington is an ex-industrial area so the canals and land have had to be treated to remove contaminants. Piled foundations support ground beams and load-bearing masonry cavity walls. The ground floor has a beam and block structure which is ventilated to the outside via telescopic vents. The first floor and roof are timber and the roof has an aluminium sheet finish. The street façade is brick, precisely set out by the architects in a criss-cross pattern using three different colours of brick. Timber windows are recessed with almost a full brick reveal and the variety of shapes and sizes makes a lively elevation.


The brick wall is capped by a glass reinforced plastic (GRP) parapet that swoops and dives along the street linking the Dutch gabled fronts of the houses in a continuous line. The GRP is prefabricated in 1–1.5 metre lengths and fixed to the masonry with metal clips. L-shaped steel wind posts concealed in the masonry walls and fixed into the roof structure help support the free-standing gables. Balconies at first floor are supported by steel beams tied back to the floor structure. The balustrade is made of 150 mm wide timber planks CNC cut with a pattern and screwed to the steel structure from behind. The motifs in the façades are abstract and diverse enough to avoid any fixed association, allowing the development to achieve an identity entirely its own.




Photo: Tim Soar



Two bedroom house first floor plan – 1:200



Two bedroom house ground floor plan – 1:200



Site plan – 1:1000

Drawing labels:

1. Foundations

Reinforced concrete ground beam.  
Precast concrete driven piles.

2. Ground floor

70 mm thick sand-cement screed.  
100 mm thick insulation.  
Damp-proof membrane lapped over blockwork into cavity and bonded to cavity tray.  
155 mm deep precast concrete T-beams.  
100 mm thick concrete block infill between beams.

3. Ventilation

Minimum 150 mm ventilated void between ground and suspended floor.  
Proprietary telescopic underfloor ventilation units to give 1500 mm<sup>2</sup> airflow per metre length of wall.  
Air bricks in outer leaf of wall.

4. External wall

103 mm face brick outer leaf.  
60 mm air gap.  
90 mm partial fill mineral wool insulation.  
140 mm dense concrete blockwork inner leaf.  
13 mm plaster internal finish.

5. First Floor

21 mm particle board deck screwed to joists.  
150 × 50 mm softwood joists at 400 mm centres.  
13 mm plasterboard ceiling with vapour barrier fixed to softwood battens at 600 mm centres.

6. Window cill

Pressed aluminium cill polyester powder coated to match window frame.  
Mastic seal with backing rod at edges.  
Painted softwood internal cill.  
Insulated cavity closer with integral DPC.

7. Window head

Cavity tray with stop ends.  
Weepholes in perpends at 450 mm centres.  
180 mm wide galvanised steel T-lintel to outer leaf.  
215 mm high × 100 mm wide galvanised steel angle lintel to internal leaf.  
Gap between lintels packed with mineral wool insulation.  
Lath welded to lintel and plaster returned across internal reveal.

8. Window

2250 mm high softwood framed sliding patio door with cold bridge insulated aluminium/wood bottom rail.

26 mm thick double-glazed unit.

9. Balcony structure

2100 × 800 mm balcony made from 152 × 89 mm galvanised universal beams (UB) on front and sides bolted to first floor joists.  
150 × 50 mm treated timber joists spanning between steel beams.  
150 mm wide stained and treated timber board decking.

10. Balustrade

50 × 50 mm galvanised steel rectangular hollow section (RHS) posts in each corner.  
50 × 50 mm galvanised steel RHS top and bottom members spanning between posts.  
150 mm wide treated and painted softwood planks with CNC cut-out pattern screwed to steel structure from behind.

11. Roof


175 mm high × 200 mm wide aluminium upstand flashing with 25 mm insulation board behind.  
Pressed aluminium cover flashing polyester powder coated to match parapet render with mastic joint to render stop bead.  
Profiled aluminium roofing laid to 1 in 40 fall in 400 mm width strips with standing seam lock joints.  
200 mm mineral fibre insulation compressed to 183 mm.  
Thermally broken roof sheet brackets fixed through plywood deck to joists below.  
Vapour control and air-lock layer lapped up and mechanically fixed to blockwork.  
20 mm WBP plywood deck screwed to joists.  
200 × 50 mm softwood joists at 400 mm centres.  
13 mm plasterboard ceiling with vapour barrier fixed to softwood battens at 600 mm centres.

12. Windposts

L-shaped windpost frames welded up from 152 × 89 mm steel joists resting on steel beam in blockwork leaf and tied into timber roof structure.

13. Parapet

Prefabricated GRP (glass reinforced plastic) coping units clipped over fixing brackets bolted to top of masonry.  
Butt straps between adjacent sections.



Cut-away section through typical front wall and window





*Photo: Empresa Municipal de la Vivienda*



Photo: Elena Marco



Photo: Elena Marco



Photo: Elena Marco



Photo: Empresa Municipal de la Vivienda

## EMV Social Housing, Vallecas, Madrid

Architect: Feilden Clegg Bradley Architects

M&E Engineer: Max Fordham LLP


Environmental Engineer: Emma s.l

Vallecas is a south-eastern suburb of Madrid. In a massive expansion over 26,000 new housing units are being built, a proportion of which will incorporate renewable sources of energy, the efficient use of power, recycling and landscaping. Northern European expertise in sustainable design was brought in to create an exemplary low-energy 139 unit housing scheme.


Cross-ventilation and stack ventilation are an integral part of the architecture reducing the need for winter heating and summer cooling. Each flat will have dual aspect to the street and to an internal courtyard. A combination of full height windows, balconies and sliding screens on the west, south and east sides allow high levels of control of cross-ventilation and sunlight. In addition, each flat will have its own dedicated ventilation chimney in a central core to draw air up to roof level using stack effect. The ducts work in a similar way to the shared light wells in traditional Spanish urban apartment blocks but without the problems of odours and acoustic privacy. The negative pressure generated as the wind blows across the chimneys aids the stack effect.

The ducts are sized according to the volume of each flat and the height of the ventilation chimney. The taller the shaft, the smaller its cross-sectional area. Air is drawn out of the flat via a grille with an acoustic damper in the hallway set to open automatically on a timer at night. Thermal modelling was used to size the ducts, openings in the external envelope and grilles in or above the doors to the hallway. The timer can be over-ridden manually. The chimneys are used primarily for night-time cooling of the thermally massive structure of the building. The chimneys project 5 metres above the top floor in clusters giving the building a distinctive silhouette.

The building fabric is insulated with 100 mm of polystyrene as opposed to the normal 30–40 mm on Spanish housing. Rainwater from the roofs and hard surfaces is used to water the plants in the courtyard. Photo-voltaic cells on top of the chimneys provide enough electricity to light the communal areas and 140 square metres of solar-thermal collectors will heat water for winter heating. Energy consumption and the emission of CO<sub>2</sub> is intended to be 70% lower than in a conventional residential building.



Section showing natural ventilation airflow



Typical three bedroom flat plan – 1:300





Diagram showing individual chimneys for each flat



Roof plan – 1:1000

Drawing labels:

1. Roof

Curved galvanised steel roofing with standing seams at 450 mm centres.  
18 mm plywood deck.  
Galvanised steel edge flashings with continuous gap to ventilate roof void.  
Softwood firrings to form fall.  
150 × 50 mm softwood joists fixed to steel structure below.  
12 mm calcium silicate soffit boards fixed to steel via timber battens.

2. Chimney roof structure

Four 100 × 100 mm rectangular hollow section (RHS) posts bolted to gutter channel below.  
100 × 100 mm RHS horizontal frame bolted to posts.

3. Bracing

100 × 60 mm RHS bolted between horizontal roof frame members.  
Steel cable braces bolted to RHS above and to masonry walls below.

4. Gutter

Galvanised 260 × 90 mm parallel flange channel (PFC) forming gutter bolted to masonry walls below.

5. Central roof

Curved galvanised steel roofing with standing seams at 450 mm centres.  
18 mm plywood deck.  
100 × 50 mm softwood joists fixed to PFC gutter channel on steel cleats.  
12 mm calcium silicate soffit boards fixed to timber joists.

6. External wall

120 mm solid terracotta blockwork wall.

100 × 50 mm vertical softwood battens fixed to masonry.

100 mm mineral wool insulation between battens.

50 × 38 mm horizontal softwood battens forming ventilation gap.

Galvanised steel cladding panels on 18 mm plywood backing.

7. Coping flashing

Pressed galvanised steel coping flashing on 18 mm plywood on softwood battens.

8. Mesh

Rigid stainless steel mesh over duct openings to prevent ingress of insects and birds fixed to duct walls on stainless steel angle cleats.

9. Internal duct wall

120 mm solid terracotta blockwork wall, fair faced on duct side.  
Plaster with paint finish to flat side.


10. Typical floor

70 mm terrazzo floor finish.  
50 mm screed.  
50 mm concrete structural topping.  
250 mm deep terracotta pots spanning between concrete beams.  
250 mm deep precast concrete beams at 800 mm centres spanning between main reinforced concrete beams.  
25 mm plaster to ceiling with paint finish.

11. Ventilation in flat

0.5 square metre aluminium ventilation grille above cupboard in hall with motorised damper linked to automatic timer.





Cut-away section through chimney showing passive ventilation system



*Photo: Tim Soar*




Photo: Allford Hall Monaghan Morris



Photo: Tim Soar

## The Johnson Building Clerkenwell, London

Architect: Allford Hall Monaghan Morris

Structural Engineer: Price & Myers



Photo: Tim Soar

A dramatic atrium unites a refurbished 1930s building with a new concrete framed structure bringing natural daylight right down to the ground through a seven-storey office development in central London. Occupying the whole width of a city block in London's traditional jewellery quarter between Hatton Garden and Leather Lane the complex is actually a cluster of several buildings around a central courtyard. In addition to office space, Camden Council planners insisted that 14 apartments and a retail unit be provided, as well as a building dedicated for tenants in the jewellery trade.

The main office building is 37 metres wide so the atrium is essential for natural light at the centre of the plan. Daylight has been maximised by using a lightweight ETFE roof that requires much less structure than a glass roof. The ETFE is designed to be sacrificial in case of fire so that the atrium can be considered as an outdoor space, simplifying the fire escape strategy.


At each floor level, a concrete bridge connects the offices on both sides to a lift core. A precast concrete beam spans 7.5m from side to side supporting four precast concrete floor panels. The beams have a profiled section to conceal lighting. The precast floor panels were installed with their trowelled surface uppermost as a non-slip finish. Glass lenses were fitted on site as the holes were required for lifting the panels into position. All the precast elements were installed in one day and required careful protection for the rest of the contract period.

The concrete walls either side of the walkways were formed with steel shutters that had all their welds ground off and were then bead-blasted so the concrete would have a fine matt finish. Timber panels on the atrium walls have been carefully jointed with 60mm return pieces on three edges to appear like pieces of joinery rather than a thin veneer. The wall of the lift shafts facing the atrium is glazed and lit from behind with an 80% frit to diffuse the light evenly. The ghostly movement of the lifts behind adds life to the crisp serenity of the atrium.




Photo: Allford Hall Monaghan Morris






Site location plan – 1:2000



First floor plan – 1:1000



East-west section – 1:1000

Drawing labels:

1. Lift lobby floor

12 mm thick composite stone tile floor finish on adhesive bed.  
25 × 25 mm brushed stainless steel edge trim angle with silicone sealant between tiles and precast floor slabs.  
50 mm sand-cement screed.  
150 mm thick reinforced concrete slab with 375 × 140 mm thick downstand at slab edge.  
125 × 100 mm recess to carry walkway floor slabs.

2. Walkway wall

250 mm thick reinforced concrete shear wall cast with steel shutter.  
All welds on steel shutter ground smooth and surface bead blasted to give matt finish to concrete.

3. Walkway beams

7500 × 575 × 350 mm precast concrete beam with recessed profile on walkway side.  
Beam ends have T-profile to sit on 440 mm high × 350 mm wide reinforced concrete U-brackets cast as part of shear wall.  
Continuous 150 × 90 × 10 mm rolled steel angle (RSA) with intumescent paint finish fixed with captive bolts to galvanised steel channel cast into bottom flange of beam to carry floor panels.

4. Walkway floor

2720 × 1865 × 150 mm thick ordinary Portland cement precast concrete floor panels spanning between RSA and lift lobby floor edge.  
Glass lenses inserted on site bedded in tile adhesive.

5. Walkway balustrade

Continuous 200 × 100 mm painted steel T-bracket fixed with captive bolts to galvanised steel channels cast into concrete beam.  
Balustrade formed from five 905 mm high toughened glass sheets bolted via 40 mm diameter stainless steel spacers to T-bracket with brushed pignose bolts and rubber isolation washers.  
Cold cathode lighting tube fixed in recess below T-bracket.  
Continuous brushed folded stainless steel capping rail silicone bonded to top edge of glass.

6. Lift shaft glazing

50 × 25 mm rectangular section polyester powder coated (PPC) aluminium support at base of glazing.

150 × 75 mm steel unequal angle (UA) bolted to concrete beam at head to restrain glazing frame.  
50 × 25 mm PPC aluminium glazing frame with 28 × 22 mm aluminium angle glazing bead.  
12 mm toughened glass with 80% fritted film.

7. Bulkhead and ceiling

One layer 12.5 mm plasterboard fixed to proprietary galvanised steel suspended ceiling track system.  
Shadow gap beads at edges.  
Plaster skim coat with painted finish.

8. Typical office floor

440 mm deep proprietary raised floor system.  
275 mm thick reinforced concrete floor.  
Sprayed plaster finish to soffit.

9. Atrium walls

2740 × 1115 × 12 mm thick elm veneered cementitious board cladding panels with concealed fixings on atrium side with sanded lacquer finish.  
60 mm wide elm veneered cementitious board strips around lower and side edges on concealed fixings.  
58 × 50 mm softwood battens.  
590 high × 175 mm thick reinforced concrete upstand wall.  
12.5 mm plasterboard with plaster skim coat on 25 mm battens on office side.

10. Atrium glazing


12 mm clear toughened glass.  
50 × 25 mm PPC aluminium glazing frame with 28 × 22 mm aluminium angle glazing bead.  
210 × 15 mm painted MDF cill screwed and plugged on timber packers at 600 mm centres.  
120 × 70 mm continuous RSA glazing support bolted to concrete wall at cill.  
70 × 70 mm continuous RSA glazing restraint bracket bolted to concrete soffit at head.  
65 × 65 mm PPC aluminium angle subframe at head.

11. Doors

Glazed doors with 70 × 60 mm brushed stainless steel box section frames.

12. Side panel

High gloss lacquered 280 mm wide × 15 mm MDF panel at side of door to allow tenant to mount entry system.  
Softwood studwork frame fixed to 75 × 75 mm RSA door jamb.




Exploded section through atrium walkways


186









Detail section through typical cill – 1:10




Detail plan through typical jamb – 1:10



Typical floor plan – 1:1500



East-west section – 1:5000




Ground floor site plan – 1:1500

Drawing labels:

1. Typical façade column  
305 × 305 mm × 240 kg UC (universal column) steel column.  
Two 780 mm long × 150 × 75 mm PFC (parallel flange channel) fixing brackets bolted to column on site.  
200 mm long 305 × 305 mm × 240 kg UC stub shop-welded to column at floor level.
2. Typical façade beam  
300 × 220 mm × 240 kg RHS (rectangular hollow section) steel beam.  
Two steel plate brackets welded to beam, 450 × 330 × 300 mm approximately but varying depending on location.
3. Typical floor  
Proprietary 600 × 600 × 40 mm raised access floor panels on 110 mm pedestals.  
130 mm concrete slab on galvanised metal deck spanning between beams.  
457 × 152 mm × 60 kg UB (universal beam) with circular cut-outs in web to coordinate with building services.  
Polyester powder coated edge trim to plasterboard suspended ceiling.
4. Typical spandrel cladding element  
Nominally 4570 mm long (varies from 4280–4725 mm) × 895 mm high polished precast concrete element.  
Two 300 × 100 × 12 mm galvanised steel channels cast into rear of spandrel for bolting to steel beam brackets with M24 bolts and 50 × 50 × 8 mm packing shims.  
Two further M27 bolts tighten against steel bracket for final adjustment.  
30 mm vertical packing zone for tolerance filled with non-shrink grout once spandrel level in position.  
Bolt holes in channels and brackets slotted in opposite directions to allow tolerance in both directions.  
10 mm fall on top and bottom faces of spandrel.

Vented double external mastic seal within the 20 mm joints between adjacent precast elements.

5. Typical column cladding element  
3725 mm high × 1400 mm wide polished precast concrete element with concrete corbel cast into rear to bear on steel stub on column.  
Column element laterally restrained to steel column with M16 stainless steel threaded rods from PFC brackets to channels cast into rear of precast element.  
65 mm rigid phenolic insulation fixed to rear of element prior to delivery.
6. Typical window  
Nominally 4530 × 2790 mm polished stainless steel clad natural anodised aluminium window in each bay.  
145 × 85 mm black satin anodised aluminium external frame to form 100 mm recess on all sides bolted in three places to top and bottom precast concrete spandrel.  
20 mm gap between precast elements and frame for tolerance.  
112 × 50 mm polished stainless steel cladding on all sides fixed to aluminium frame.  
Double-glazed sealed unit consisting of 10 mm laminated outer pane, 16 mm argon filled cavity and 12 mm toughened inner pane with low-E coating.  
Natural anodised aluminium internal frame bolted to precast concrete on top and bottom.  
Roller blind at head.
7. Build-up behind precast column  
Rigid phenolic insulation and vapour barrier to seal junction between precast column and window frame.  
In-situ plasterboard linings to columns.
8. Build-up behind precast spandrel  
Standardised steel slab edge tray cranked to follow profile of rear of precast spandrel to minimise gap for fire stopping.  
Fire stop between slab edge and rear of spandrel.  
Rigid phenolic insulation and vapour barrier between spandrel and raised floor and between spandrel and ceiling void.



Exploded detail of typical façade column and beam junction





*Photo: Terry Pawson Architects*



Photo: Terry Pawson Architects



Photo: Terry Pawson Architects

## Vernon Street Offices Kensington, London

Architect: Terry Pawson Architects

Cast Stone Subcontractor: Histon Concrete Products Ltd



Photo: Terry Pawson Architects

Crisply detailed cast stone gives a new office building for a soft toy company in west London a strong material presence on a street of yellow stock brick houses. The new building is linked to the redundant West London Magistrates Court next door, a red brick and Portland stone free classical style building from 1914 which was also refurbished as office accommodation as part of the project. Six of the original 38 prison cells have been retained in the basement, complete with steel doors and graffiti, not something you would normally expect to find in a high-spec office development.


Adjacent to the street a basement has been formed with reinforced concrete walls insulated and tanked externally. The new building has a concrete frame and cavity walls with a self-supporting cast stone outer leaf. The cast stone walls of the new building relate to the Portland stone details of the courthouse and the rendered lower stories of the near-by terraced houses.

Cast stone is effectively concrete with an aggregate of crushed stone, in this case Portland, and a carefully balanced mix of cement, super-plasticizers and accelerators to match the colour and texture of natural stone.  $165 \times 100$  mm blocks were cast in several lengths from 1 to 2.2 metres. After being struck from the mould the faces to be exposed were acid etched to expose the aggregate. A blockwork inner leaf was built first with stainless steel cavity ties folded down so that the cast stone could be built later, reducing the time it had to be protected on site. Forty-two different shapes were made so that the quoins, cills, lintels and copings would be seamless with the walls.




Photo: Terry Pawson Architects


A 6-metre long concrete slab clad in cast stone forms a porch over the entrance. The cast stone elements below are coffered to reduce weight and hung on stainless steel rods that pass through the concrete slab to be carried by plates above. The upper cladding elements fall towards a central stainless steel gutter to remove rainwater. In a similar way a cast stone cill in a recess on the street elevation slopes backwards channelling rainwater to a slot at the rear into a concealed gutter. Careful detailing reduces potential staining by concentration of water on the visible edges.




Second floor plan – 1:1000




North-south section – 1:350



First floor plan – 1:1000



Ground floor plan – 1:1000



Basement plan – 1:1000

Drawing labels:

1. Basement wall

50 mm extruded polystyrene insulation.  
225 mm reinforced waterproof concrete basement wall.  
15 mm plaster internal finish.

2. Entrance courtyard floor

20 mm natural limestone stone paving.  
25 mm sand/cement bedding.  
Minimum 75 mm screed.  
50 mm extruded polystyrene insulation.  
120 × 125 mm stainless steel drainage channel.  
275 mm thick reinforced waterproof concrete slab.  
15 mm plaster internal finish.

3. Entrance porch

6735 × 2610 × 275 mm thick in-situ concrete slab spanning across entrance between concrete frame of main building and concrete columns in boundary wall.  
50 mm thick cast stone elements with 30 mm ribs for stiffness fixed with stainless steel bolts to concrete slab.  
25 mm slot between precast elements for drainage.  
190 mm wide stainless steel central drainage channel falling to 75 mm diameter stainless steel downpipe in boundary wall.  
Single ply waterproof membrane bonded to concrete and dressed into drainage channel.

4. Abutment to wall

Stainless steel masonry support angle on brackets bolted to channel cast into first floor slab edge.  
Bronze strip folded around 38 × 38 mm softwood (sw) packer screwed to 38 × 28 mm stainless steel angle welded to masonry support angle to form shadow gap at first floor level.  
White coloured damp proof membrane (DPM) bonded to inner leaf blockwork and dressed over masonry support angle.

5. Entrance gates

Galvanised head track channel fixed to concrete slab with resin anchor bolts.  
100 × 50 mm polyester powder coated (PPC) steel rectangular hollow section (RHS) frame.  
60 × 8 mm PPC flat bars at 120 mm centres.  
Two 16 mm diameter vertical rods welded between flats.

Bronze bottom guide channel fixed into groove in cast stone paving.

6. Base of wall

190 mm wide × 360 mm high reinforced concrete haunch cast at top of basement wall to carry outer leaf of masonry.  
Pea shingle and land drain adjacent to wall construction.  
Compressible drainage board adjacent to cast stone wall.  
Continuous 38 × 38 mm stainless steel angle to form slot between pavement and wall.

7. Meeting room floor

1200 × 600 × 20 mm thick lime stone paving slabs.  
25 mm sand/cement bedding.  
75 mm screed.  
35 mm extruded polystyrene insulation.  
275 mm reinforced concrete slab.

8. External wall

165 mm high × 100 mm thick cast stone blocks with stainless steel wall ties.  
50 mm air gap.  
50 mm rigid polyisocyanurate (PIS) insulation.  
140 mm concrete blockwork.  
12.5 mm plasterboard on 50 × 50 mm softwood studwork with plaster skim finish.


9. Cill in recess

Cast stone cill with fall to 30 mm wide drainage slot at rear.  
1650 × 100 × 75 mm stainless steel gutter box fixed to underside of cill.  
50 mm diameter insulated drainage pipe with trap connected into cast iron rainwater pipe internally.  
Continuous cavity tray behind cill.

10. Meeting room window

Double-glazed sealed unit made up from 6.3 mm laminated inner pane, 16 mm cavity, 10 mm toughened outer pane.  
51 × 38 × 6 mm angle carrier frame bonded to glass with structural silicone.  
Continuous 156 × 6 mm flat subframe screwed to carrier frame and fixed back to blockwork inner leaf with aluminium restraint straps.  
8 mm black silicone filled glass-to-glass corner joint.





Cut-away section through front wall and entrance



Photo: Markus Bachmann





Photo: John Gollings



Photo: Grimshaw



Photo: Grimshaw




Photo: Grimshaw



Photo: Grimshaw



Photo credit: John Gollings

## Southern Cross Station, Melbourne Australia

Architect: Grimshaw Jackson JV

Structural Engineer: Winward Structures

Services Engineers: Lincolne Scott Australia


A roof of shimmering zinc-coated aluminium billows across the platforms of Southern Cross Station in central Melbourne. The station is part of an AS\$350 Million redevelopment which unites the rail and bus terminals and was completed in time for the 2006 Commonwealth Games. The surrounding urban landscape has been re-configured so the station acts as a link rather than a barrier between the central business district and the docklands.

The undulating profile is designed to remove diesel fumes without the need for a costly mechanical system. Ventilation lanterns at the top of each dome allow the wind to draw out fumes by Venturi effect. Heat build up under a single skin metal roof would cause disturbance to the air flow, so an inner lining of faceted 200 mm thick triangular panels has been installed between the steel bracing to effectively insulate the roof. Air is drawn up through gaps between the ceiling panels into a void between the inner and outer layers.


The outer roof skin is curved in two directions using tapered strips of zinc-coated aluminium. Equipment was brought from Germany to roll the strip metal on site. To achieve the tight curves the strips were passed through the rollers four times in batches of five or ten strips, each batch with a slightly different tapered profile. This complex process was only possible because the roofing sub-contractor was appointed at the detailed design stage to develop fabrication details alongside the architects, a process Grimshaws say worked remarkably well.

The main structure is steel. Curved roof arches span up to 40 metres between trusses that are in turn supported on concrete filled steel columns. The long spans reduce the number of columns required allowing for future flexibility or re-arrangement of the platforms beneath. 900 mm wide gutters either side double as maintenance walkways. Above the trusses 20 metre long ETFE pillows provide natural light on the platforms. The ETFE is fritted to reduce heat gain from the summer sun bathing the platforms in a cool forest floor light.





North-south section – 1:1750



Typical gutter section – 1:40





Diagram showing natural ventilation via roof cowls



Level 1 plan – 1:5000

Drawing labels:

1. Typical column  
10mm thick circular mild steel (MS) column casing bolted down to concrete plinth.  
Casing tapers from 2000mm diameter at base to 1180mm at top.  
Height varies from 6m to 12m.  
Casing filled with concrete by pressure pumping from base once bolted in place.
2. Wishbone column arms  
Tapered arms made from varying thickness steel plates welded at edges with internal 6mm thick diaphragm stiffening plates at 1250mm centres.  
1000mm diameter  $\times$  16mm thick circular hollow section (CHS) welded through base of arm for connection to column.  
CHS connector located in column head and welded in place prior to filling column with concrete.
3. Spine truss  
Steel truss brought to site in prefabricated 4-bay sections.  
356mm diameter curved top and bottom chords.  
356mm diameter curved top horizontal member.  
273mm diameter vertical members.  
219mm diameter horizontal diagonal braces.  
168mm diameter diagonal braces either side of column connection.  
Three pin connections on truss prefabricated and site welded to each column arm.
4. Roof steelwork  
356mm diameter MS primary roof arches curved to form undulating roof profile.  
168mm diameter MS lateral struts bolted to cleats welded to arches.  
168mm diameter MS diagonal braces bolted to 356mm diameter bosses welded to arches.  
76mm diameter MS posts with brackets to support roof panels and cladding rails welded to primary arches at maximum 1500mm centres.
5. Ceiling panels  
200mm thick prefabricated triangular panels bolted between diagonal braces to cleats on MS posts.


Panel frame made from 150  $\times$  75mm galvanised light gauge steel channel sections.  
Profiled galvanised steel top sheet.  
Joints between panels covered with reinforced plastic strips.  
1.5mm thick polyester powder coated aluminium panels to underside to form finished ceiling.  
100mm gaps between ceiling panels above truss chords and primary arch to allow fumes to be drawn into roof void.  
Bird mesh fixed to rear of ceiling panels over gaps.

6. Cladding support rails  
114mm diameter curved aluminium rails bolted to MS posts to support roof cladding.

7. Roof cladding  
Tapered 1mm gauge zinc-coated aluminium standing seam roof cladding clipped over proprietary supports.  
Continuous void between roof cladding and ceiling panels to allow fumes to be drawn up to ventilation domes at tops of arches.

8. Gutter  
200  $\times$  75mm parallel flange channel (PFC) and 200  $\times$  200mm universal column (UC) gutter frame bolted to steelwork at each primary arch.  
930mm width  $\times$  20mm plywood gutter base bolted to steel frame.  
Non-slip single ply membrane gutter lining to act as maintenance walkway.  
4000  $\times$  700  $\times$  220mm deep sump with two outlets at each column position.  
Folded 2mm aluminium vertical cladding to conceal gutter below rooflight.  
Two 125mm diameter rainwater downpipes running down each column arm and cast into concrete trunk of column.  
One electrical conduit in each column arm running up into ceiling void.

9. Rooflights  
20 metre long ETFE pillows running along full length of roof over spine trusses with 18mm diameter white frit over 60% of surface.  
Extruded aluminium perimeter clamp plate bolted to UC gutter structure.  
Clamps at ends of ETFE pillows made from back-to-back angles to form expansion joint.



Cut-away view of typical column, truss, rooflight and roof

# Project Credits

The introduction and accompanying text for each project was written by Graham Bizley. The detail illustration for each project was drawn by Prewett Bizley Architects (Enrico Arrigoni, Graham Bizley, Joel Howland, Anurag Varma). All other drawings were supplied by the architects or engineers. I am grateful to the architects and clients for allowing their projects to be published in this book and for supplying the necessary information. The photographer for each image used is credited with the image and I am most grateful to them for allowing their images to be used.

## Individual Project Credits

### *Royal Festival Hall, London*

Completion: 2007  
Construction cost: £117.9 million including new building, riverside retail and public realm  
Gross floor area: 42,010sq m

Client: Royal Festival Hall, Southbank Centre  
Architect: Allies & Morrison  
Structural Engineer: Price & Myers  
M&E Services Engineer: Max Fordham and Partners  
Quantity Surveyor: Davis Langdon LLP  
Auditorium Acoustic Consultant: Kirkegaard Associates  
Theatre Designer: Carr and Angier  
Lighting Consultant: Speirs and Major  
New building Executive Architects: BDP Architects  
Landscape Architects: Gross Max  
Planning Supervisor: PFB Construction Management  
Planning Consultant: RPS Planning Plc  
Project Management: Bovis Lend Lease Consulting  
Masterplanning Architect: Rick Mather Architects  
Fire Consultant: Faber Maunsell  
Access Consultant: David Bonnett Associates  
Pedestrian flow: Space Syntax

Contractors and selected suppliers:  
Main refurbishment Contractor: ISG InteriorExterior  
New building Contractor: Taylor Woodrow  
Auditorium seating: Race Furniture  
Auditorium joinery & WC Fit Out: Taylor Made Joinery  
Specialist sliding screens: SpArt Andersen & Copenhagen  
Suspended ceilings: Clark & Fenn Skanska Ltd  
Stage machinery: Delstar Engineering Ltd  
Organ refurbishment: Harrison & Harrison Ltd  
Carpet and soft floor finishes: Loughton Contract Carpets Ltd  
Borehole Consultants: Parsons Brinkerhoff

French polishing: SJM (French Polishers) Ltd  
Stage machinery: Stage Technologies Ltd  
Tapestry/panel restoration: Textile Conservation  
Scaffolding: TRAD Scaffolding Company Ltd

Photographs:  
Dennis Gilbert/VIEW  
Allies & Morrison

### *Neues Museum, Berlin*

Completion: 2009  
Construction cost: €200 million approx.  
Gross floor area: 21,500sq m

Client: Stiftung Preußischer Kulturbesitz  
Architect: David Chipperfield Architects  
Restoration Architect: Julian Harrap Architects  
Consultant/site supervision (restoration): Pro Denkmal GmbH  
Structural Engineer: Ingenieurgruppe Bauen  
Quantity Surveyor: Nanna Fütterer  
Site supervision: Lubic & Woehrlin GmbH  
Project management: Ernst & Young Real Estate GmbH  
Heating, ventilation & sanitary engineer: Jaeger, Mornhinweg & Partner Ingenieurgesellschaft  
Electrical and security: Kunst und Museumsschutz Beratungs- und Planungs- GmbH  
Lighting Consultant: Kardorff Ingenieure Lichtplanung  
Building physics: Ingenieurbüro Axel C. Rahn GmbH  
Landscape Architect: Levin Monsigny  
Landschaftsarchitekten  
Exhibition design: Architetto Michele de Lucchi S.r.L

Photographs:  
Ute Zscharnt  
Christian Richters

### *Newlyn Art Gallery, Cornwall*

Completion: 2007  
Construction cost: £950,000  
Cost per sq m: £2110  
Gross floor area of new building: 138sq m  
Gross floor area of existing building: 267 sq m

Client: Newlyn Art Gallery  
Architect: MUMA  
Structural Engineer: Dewhurst Macfarlane  
M&E Engineer: Buro Happold



Quantity Surveyor: Davis Langdon LLP  
 Project Manager: Cyril Sweet  
 CDM Co-ordinator: Davis Langdon  
 Access Consultant: Lisa Foster Associates  
 Slate Consultant: Viv Stratton, Cornwall College  
 Camborne

Contractors and suppliers:  
 Main Contractor: Cowlin Construction (Truro)  
 Slate Supplier: Mill Hill Quarries Ltd, Tintagel  
 Slate Subcontractor: Forrester Roofing, St. Austell  
 Zinc cladding: J.E. Gibbings, Bristol  
 Glazing: Solaglass (Portsmouth)  
 Soffit grilles: Component Developments  
 Fair-faced concrete: Cornish Concrete Products, Bissoe  
 Concrete formwork: Luscombes  
 Concrete flooring: Permaban, Devon  
 Screed flooring: Sika  
 Architectural metalwork: Ferguson Engineering, Newton  
 Abbot  
 M&E Subcontractor: EIC (Redruth)  
 Gallery lighting: Concord/Selux  
 Ironmongery: Allgood  
 Counters/shopfitting: WFC, Newton Abbot  
 Hard landscaping: Mid Cornwall Landscaping,  
 St. Austell

Photographs:  
 Allan Williams

### *The North Wall Arts Centre, Oxford*

Completion: 2007  
 Construction cost: £2,665,000

Client: St Edward's School  
 Architect: Haworth Tompkins  
 Structural Engineer: Price & Myers LLP  
 M&E Engineer: Max Fordham LLP  
 Acoustic Engineer: Paul Gillieron Acoustic Design  
 Theatre Consultant: Charcoalblue Ltd  
 Quantity Surveyor: Bristow Johnson & Partners  
 Planning Supervisor: PFB Construction Management  
 Services Limited  
 Fire Engineer: Safe Consulting Ltd  
 Access Consultants: Tom Lister Associates

Contractor and Subcontractors:  
 Main Contractor: Benfield & Loxley (Oxford) Ltd  
 Mechanical services installation: F.G. Alden Limited  
 Electrical services installation: Lowe & Oliver Ltd  
 Electrical: Oxford Sound & Media  
 External windows: Specialist Cladding Services Ltd  
 Theatre staging: Steeldeck  
 Ironmongery: Yannedis Ltd

Photographs:  
 Philip Vile  
 Haworth Tompkins

### *Regent's Park Open Air Theatre, London*

Completion: 2008  
 Construction cost: £640,000  
 Cost per sq m: £2850  
 Gross floor area: 225 sq m  
 Contract: GC Works

Client: The New Shakespeare Company Ltd  
 Architect: Prewett Bizley Architects  
 Landscape Architect: Colvin & Moggridge  
 Structural Engineer: Price & Myers  
 M&E Services Engineer: Fulcrum Consulting  
 Project Manager: Rider Levett Bucknall UK  
 Quantity Surveyor: Rider Levett Bucknall UK  
 CDM: Rider Levett Bucknall UK  
 Arboricultural Consultant: CBA Trees

Contractor and Subcontractors:  
 Main Contractor: Ashe Construction Piling: Hill Piling  
 Steel frame: County Construction Ltd  
 Groundworks: Cara Plant Ltd  
 Steel decking: Richard Lees Ltd  
 Carpentry: Newman Martin Construction  
 Roof coverings: Russell Trew  
 Mechanical installation: Primary Plumbing Services Ltd  
 Electrical installation: Astra Electrical Ltd  
 Roller shutters: Kenrick Door Systems Ltd  
 Resin Floors: McDaId Screeding  
 Folding screen in bar/rehearsal area: AGB Narib Ltd  
 Fencing: Metalwood Contracts Ltd  
 Landscaping: A1 Landscaping  
 Sign writer: John Pope

Suppliers:  
 Roofing: Permanite  
 Windows: Rationel  
 Doors: Humphrey & Stretton  
 Roller shutters: Eurotherm by Shutter and Door  
 Components Ltd  
 Tilly Triboard linings and cubicle partitions: MCI Timpely  
 (now UCM Timber) Phenolic faced plywood linings:  
 FinnForrest  
 Resin Floors: Flowcrete  
 Entrance mats: Jaymart  
 Sanitaryware: Ideal Standard  
 Infra-red controls: Cisterniser  
 Translucent & opaque woodstain: Sikkens by Akzo Nobel  
 Paint: Dulux by ICI  
 External surface finish: Natratex by Bituchem  
 Fencing: Expamet Security Products  
 Pendant luminaires: Concord:marlin  
 Fluorescent batten luminaires: Philips  
 Emergency luminaires: Thorn  
 Fairy lights: Light projects

Photographs:  
 Kilian O'Sullivan/VIEW  
 Prewett Bizley Architects

*The Bluecoat Arts Centre, Liverpool*

Completion: 2008  
Construction cost: £9.5 million  
Cost per sq m: £2000  
Gross floor area: 4720sq m

Client: The Bluecoat  
Architect: Biq Architecten  
Executive Architect: Austin-Smith:Lord  
Conservation Architect: Donald Insall Associates  
Landscape Architect: Austin-Smith:Lord  
Project Manager: Buro 4  
Structural Engineer: Techniker  
M&E Services Engineer: Ernest Griffiths  
Cost Consultant: Tweeds  
Planning Supervisor: CDM Planning Supervisors  
Main Contractor: Kier North West

Photographs:  
Stephan Muller  
Biq Architecten

*Ruthin Craft Centre, Denbighshire*

Completion: 2008  
Construction cost: £3.1 million  
Cost per sq m: £1980  
Gross floor area: 1566sq m

Client: Denbighshire County Council  
Architect: Sergison Bates Architects  
Client's Consultant: MN Arts  
Landscape Architect: Pat Brown with Landscape Interface Studio  
Structural Engineer: Greig-Ling Consulting Engineers  
Services Engineers: BDP  
Lighting Consultants: BDP Lighting  
Project Managers: Turner & Townsend  
Quantity Surveyors: Smith Turner  
Main Contractor: Pochin Contractors Ltd  
Artists/makers (furniture): Jim Partridge and Liz Walmsley  
Artists/makers (gates): Brian Podschies

Photographs:  
Ioana Marinescu  
Dewi Tannatt Lloyd

*Siobhan Davies Dance Centre, London*

Completion: 2005  
Construction cost: £2.4 million  
Cost per sq m: £3042  
Gross floor area: 789sq m

Client: Siobhan Davies Dance Company  
Architect: Sarah Wigglesworth Architects

Structural Engineer: Price & Myers  
Building Services Engineer: Fulcrum Consulting  
Quantity Surveyor: Boyden & Company  
Project Manager: Jackson Coles  
Acoustic Consultant: Paul Gilleron Acoustic Design  
Theatre lighting & sound: Charcoal Blue  
Access Consultant: All Clear Design  
Main Contractor: Roof Ltd

Photographs:  
Peter Cook/VIEW  
Sarah Wigglesworth Architects

*Rich Mix, Bethnal Green, London*

Completion: 2006  
Construction cost: £12.5 million  
Cost per sq m: £1830  
Gross floor area: 6000sq m

Client: Rich Mix Cultural Foundation  
Architect: Penoyre & Prasad  
Structural Engineer: Arup M&E  
Services Engineer: Arup  
Quantity Surveyor: Peter Gittins Associates  
Project Manager: Bovis Lend Lease  
Planning Supervisor: Arup  
Acoustic Consultant: Paul Gillieron Acoustic Design  
Main Contractor: Mansell Construction Services Ltd

Photographs:  
Morley von Sternberg  
Penoyre & Prasad

*MIMA, Middlesbrough*

Completion: 2006  
Construction cost: confidential  
Cost per sq m: confidential  
Gross floor area: 4000sq m

Client: Middlesbrough Council  
Architect: Designed by Erick van Egeraat  
Structural Engineers: Buro Happold M&E  
Services Engineer: Buro Happold  
Quantity Surveyor: Gardiner & Theobald  
Project management: Turner & Townsend  
Civil engineer: White Young Green  
Landscape Architect: West 8  
Planning Supervisor: PFB Consultants  
Artists and collaborating designers: Graham Gussin  
Cafe design Consultant: Gijs Bakker  
Shop design Consultants: Andy Miller and Colin Williams Design  
Main Contractor: Miller Construction  
M&E Contractors: Hayden Young

Photographs:  
Christian Richters/VIEW  
Designed by Erick van Egeraat

### *Multi Purpose Hall, Aurillac, France*

Completion: 2008  
Construction cost: £6.5 million  
Cost per sq m: £1235  
Gross floor area: 5265 sq m

Client: Communauté d'agglomération du bassin d'Aurillac  
Architect: Brisac Gonzales  
Structural Engineer: VP Green  
Theatre Consultant: Ducks Sceno  
Acoustic Engineer: Xu acoustique  
M&E Services Engineer: INEX  
Quantity Surveyor: Lucigny Talhouët et Associés

Photographs:  
Brisac Gonzales

### *ARC, Hull*

Completion: 2005  
Construction cost: £550,000  
Cost per sq m: £2500  
Gross floor area: 220sq m

Client: ARC  
Architect: Niall McLaughlin Architects  
Structural Engineer: Price and Myers 3D Engineering  
Services Engineer: XCO2 Conisbee  
Quantity Surveyor: E.C. Harris  
Project Supervisor: Cameron Jemison

Contractor and Subcontractors (all local firms):  
Main Contractor: Wright Construction  
Steelwork: J&A Structural Services Ltd  
M&E: Neville Tucker Heating Ltd  
Roofing and cladding: RSR Cladding  
Glazing: Glass and Framing Solutions  
Security: Initial Electronic Security

Main Suppliers:  
Aluminium roof panels: Eltherington Aluminium Ltd  
Roofing Material: Brett Martin Daylight Systems  
Blue caravan paint: Holliday Pigments (donated all the high build paint free of charge)  
Caravan windows: Swift Group (donated windows and wheels free of charge)  
Sanitary ware: Ideal Standard/American Standard (donated all sanitary ware free of charge)  
Wood Pellet Boiler: The Organic Energy Company  
Solar panels: Solar Century  
Wind turbines: Windsun  
Flooring: Sealand Flooring Ltd

Photographs:  
Niall McLaughlin Architects

### *Resource Centre, Grizedale Forrest Park, Cumbria*

Completion: 2008  
Construction cost: £1.2 million

Client: Forestry Commission  
Architect: Sutherland Hussey Architects  
Project Manager: Turner Townsend  
M&E Services Engineer: David Eley  
Quantity Surveyor: Johnstons  
Structural Engineer: Burgess Roughton  
Main Contractor: Conlon Construction

Photographs:  
Sutherland Hussey Architects

### *Thermae Bath Spa, Bath*

Completion: 2006  
Construction cost: confidential  
Cost per sq m: confidential  
Gross floor area: 3650sq m

Client: Bath & North East Somerset Council & Thermae Development Co  
Architect: Grimshaw Architects  
Conservation Architect: Donald Insall Associates  
Structural Engineer: Arup  
M&E Services Engineer: Arup  
Energy Consultant: Arup  
Façade Engineer: Arup  
Quantity Surveyor: Bath & North East Somerset Council, Gleeds, Gardiner and Theobald  
Project Manager: Focus Consultants  
Lighting Consultant: Speirs & Major Associates  
Hydro-geological Consultant: Dr G. Kellaway, Dr Simon Kilvington

Contractor and Subcontractors:  
Main Contractor: Capita Symonds  
Services Subcontractor: Skanska  
Water treatment: Thermelek Engineering Services  
Glazing Subcontractor: MAG Hansen  
Stone Subcontractor: Bath Stone Group  
Lift Subcontractor: Otis Ltd  
Kitchen Subcontractor: Lockhart  
Glazed partitions: Prospec  
Metalwork: McGrath Group  
Ironmongery: Yannedis Ltd  
Interior stone: Bröls Natuursteen BV

Photographs:  
Edmund Sumner/VIEW  
Grimshaw Architects



*Civil Justice Centre, Manchester*

Completion: 2007  
Construction cost: £110 million  
Cost per sq m: £3235  
Gross floor area: 34,000sq m

Project Instigator: Her Majesty's Court Service  
Tenant: Ministry of Justice (North West)  
Developer: Allied London Properties  
Architect: Denton Corker Marshall  
Structural Engineer: Mott MacDonald  
M&E Services Engineer: Mott MacDonald  
Fire Engineer: Mott MacDonald  
Façade Consultant: Mott MacDonald  
Landscape Architect: Hyland Edgar Driver  
Acoustic Consultant: Sandy Brown Associates  
Stone Consultant: Harrison Goldman  
Façade access Consultant: REEF Associates

Contractor and Subcontractors:  
Main Contractor: Bovis Lend Lease  
Façades: Josef Gartner GmbH  
Mechanical Subcontractor: Axima  
Electrical Subcontractor: Hills  
Controls: Honeywell  
Fit-out including pods, concourse balustrading, concourse panelling, joinery, fitted furniture and equipment: Mivan Ltd  
Internal glazing: Clestra Hauserman  
Demountable partitions: Clestra Hauserman  
Blinds: Claxton Blinds  
Paving: English Landscapes Ltd  
Raised access floor: Kingspan Access Floors  
Architectural metalwork: Shawton  
Engineering Roofing: Topek (BUR) Ltd  
Stone flooring: Q Flooring Paint: Johns of Nottingham  
Roller shutters/smoke curtains: Bolton Gate Company  
Building maintenance unit: Cento  
Dry linings and partitions: Horbury Building Services  
Slipform concrete: PC Harrington  
Steelwork: William Hare Ltd  
Lifts: Thyssenkrupp  
Kitchen equipment: Tribourne  
Suspended ceilings: Clark and Fenn Skanska Ltd  
Blockwork: Irvine Whitlock  
Carpet Subcontractor: John Abbot Flooring Ltd  
Fire protection: R&S Dri-wall Ltd  
Signage: WSi Ltd  
Cafe sun-shade: Fabric Architecture

Suppliers:  
Ceilings: Armstrong  
Carpets: Interface  
Drywall: British Gypsum  
Doors: Leaderflush Shapland  
Door hardware: Allgood  
Sanitaryware: Duravit

Toilet partitions: Amwell Systems  
Glass balustrades: Alurail  
Interior metal panelling: Mercantile Met Tech  
Lighting: Zumtobel  
Raised access floors: Kingspan  
Demountable office partitions: Clestra Hauserman  
Blinds: Mechoshade  
Roof waterproof membrane: Permaquick 6100  
Roof paving: Marshalls  
Flat roof insulation: Dow Roofmate  
Concourse seating: OMK Design, Trax

Photographs:  
Tim Griffith  
Denton Corker Marshall

*Sean O'Casey Community Centre, Dublin*

Completion: 2008  
Construction cost: €7.9 million  
Gross floor area: 2319sq m

Client: Dublin Docklands Development Authority  
Architect: O'Donnell + Tuomey  
Structural Engineer: Casey O'Rourke Associates Ltd  
M&E Services Engineer: RPS Group  
Quantity Surveyor: Cyril Sweet  
Project Manager: Cyril Sweet  
Landscape Architect: Howbert and Mays  
PSDP (Health & Safety co-ordinator): OLM Consultancy  
Fire Consultant: OLM Consultancy  
Kitchen Consultant: QA Design

Contractor and Subcontractors:  
Main Contractor: P.J. Hegarty & Sons  
Concrete Subcontractor: Tricastle Ltd  
Mechanical installation: Walsh Mechanical Engineering Ltd  
Electrical installation: Harry Sheils  
Landscape: Avondale Landscapes Ltd  
External joinery: Woodfit  
Internal joinery: Essexford  
Specialist fitted furniture: Gem Group  
Fitted furniture: Brogan Jordan Homestyle Ltd  
Mondo turf pitch: Clive Richardson  
Metalwork: Hentech  
Specialist light fittings: Charles Furniture  
Lift: Otis Ltd

Photographs:  
Michael Moran  
O'Donnell + Tuomey

*Bellingham Gateway Building, Lewisham, London*

Completion: 2006  
Construction cost: £1.26 million

Cost per sq m: £1930  
Gross floor area: 650sq m

Client: London Borough of Lewisham Community  
Department, Bellingham Surestart and BECORP  
(Bellingham Recreation Project)  
External Funding Body: Active England – Sport England  
Architect: Cottrell & Vermeulen Architecture  
Structure Engineer: Engineers HRW  
M&E Services Engineer: Downie Consulting Engineers  
Project Management: Mace Ltd  
Quantity Surveyor: Mace Ltd  
Planning supervisor: Mace Ltd

Contractor and suppliers:  
Main Contractor: Buxton Building Contractors Ltd  
Extensive green roof system: Bauder  
Polycarbonate: Rodecca  
Profiled glass reinforced plastic: Brett Martin  
Profiled fibre cement: Eternit  
Windows: SWS  
Windows: Velux  
Sports flooring: Junckers  
Lining board: Sasmox

Photographs:  
Anthony Coleman  
Cottrell & Vermeulen Architecture

### *Maryland Early Years Centre, Stratford, London*

Completion: 2007  
Construction cost: £500,000  
Cost per sq m: £1760  
Gross floor area: 284sq m

Client: London Borough of Newham  
Key Stakeholders: Maryland Primary School, Sure Start  
Forest Gate Plus and Early Years Newham  
Architect: Fluid  
Structural Engineer: Conisbee and Associates  
Quantity Surveyor: London Borough of Newham

Contractor and Subcontractors:  
Main Contractor: Framework CDM  
Mechanical Subcontractor: Shires Building Services  
Electrical Subcontractor: Rivendell

Suppliers:  
Panelised timber building system: Framework CDM  
GRP cladding: Filon  
EPDM roof: Prelasti – AAC Waterproofing  
Windows & curtain wall glazing: AM Profiles Ltd  
Rainwater goods: Alumasc  
Rooflights: Whitesales  
Vinyl floor finish: Altro  
Underfloor heating: Underfloor Heating Now  
Ironmongery: Lloyd Worrall Ltd

Sliding door: Geze  
Lighting: Dextra  
Whiteboards & projectors: Promethean  
Washroom systems: Armitage Venesta  
Acoustic ceiling tiles: Ecophon  
Soft Internal linings: Sundeala  
External paving: Marshalls  
Impact absorbing play surface: Playtop  
Artificial grass: Evergreens

Photographs:  
Morley von Sternberg  
Fluid

### *Emmaus School, Wybourn, Sheffield*

Completion: 2007  
Construction cost: £3.6 million  
Cost per sq m: £2030  
Gross floor area: 1770sq m

Client: Diocese of Sheffield  
Architect: DSDHA  
Structural Engineer: Price & Myers  
Services Engineer: Atelier 10  
Quantity Surveyor: Davis Langdon LLP  
Landscape Architect: Watkins Daly  
Acoustic Consultant: Tim Lewers Acoustics  
Main Contractor: Allenbuild Ltd (Derby)

Photographs:  
Hélène Binet  
Morley von Sternberg

### *Bedford School Music School, Bedford*

Completion: 2007  
Construction cost: £2.1 million  
Gross floor area: 1131 sq m

Client: Bedford School  
Architect: Eric Parry Architects  
Structural Engineer: Adams Kara Taylor  
M&E Services Engineer: White Young Green  
Acoustic Consultant: Paul Gillieron Acoustic Design  
Quantity Surveyor: Davis Langdon & Everest  
Planning Consultant: Phillips Planning Services  
Fire Consultant: Fisec Consultants Ltd

Contractor and Subcontractors:  
Main Contractor: T & E Neville Ltd  
Structural steelwork: Convoy Structural Services Ltd  
Roof Subcontractor: Sterling Building Systems Ltd  
Fixed glazed panels: Solaglas Saint Gobain UK  
Blinds and shutters: Levlux  
Cladding supplier: Falzinc Metal  
Acoustic floor/strip supplier: CDM-UK

Electical Subcontractor: Landhurst Electrical Services

Photographs:  
Hélène Binet

*Sanger Building, Bryanston School, Dorset*

Completion: 2007  
Construction cost: £5.1 million  
Gross floor area: 3500sq m

Client: Bryanston School  
Architect: Hopkins Architects Ltd  
Structural Engineer: Buro Happold  
M&E Services Engineer: Cundall Johnston & Partners  
Quantity Surveyor: Turner Townsend  
Acoustic design: Buro Happold  
Contractor: Dean & Dyball Construction Limited

Photographs:  
Anthony Weller

*Scitec, Oundle School, Northamptonshire*

Completion: 2007  
Construction cost: £8 million  
Cost per sq m: £2469  
Gross floor area: 3240sq m

Client: Oundle School  
Architect: Feilden Clegg Bradley Architects  
Structural Engineer: Jane Wernick Associates  
M&E Services Engineer: Max Fordham LLP  
Project Manager: Davis Langdon LLP  
Quantity Surveyor: Davis Langdon LLP  
Landscape Architect: Churchman Landscape Architects  
Planning Supervisor: Davis Langdon LLP  
Fire Consultant: Fire Design Solutions  
Access Consultant: Colin Moore  
Building Control: Approved Inspector Services Ltd

Contractor and Subcontractors:  
Main Contractor: Willmott Dixon Construction  
Concrete frame Subcontractor: J. Reddington  
Stone Subcontractor: Ketton Architectural Stone and  
Masonry  
Glazing Subcontractor: Deane and Amos

Photographs:  
Amos Goldreich

*Ann's Court, Selwyn College, Cambridge*

Completion: 2005  
Construction cost: confidential

Cost per sq m: confidential  
Gross floor area: 2641 sq m

Client: Selwyn College  
Architect: Porphyrios Associates  
Structural Engineer: Hannah Reed  
M&E Services Engineer: Max Fordham LLP  
Project Manager: Davis Langdon LLP  
Quantity Surveyor: Davis Langdon LLP  
Landscape Architect: David Brown Landscape Design

Contractor and Subcontractors:  
Main Contractor: Bluestone  
Specialist stone masons: Ketton Architectural Stone &  
Masonry

Photographs:  
Morley von Sternberg  
Porphyrios Associates

*Wolfson Building, Trinity College, Cambridge*

Completion: 2006  
Construction cost: £4.7 million  
Cost per sq m: £1,336  
Gross floor area: 3555sq m

Architect: 5th Studio  
Structural Engineer: Cameron Taylor (now Scott Walker)  
M&E Services Engineer: Roger Parker Associates  
Quantity Surveyor: Gleeds  
Client Representative: Bidwells  
Planning Supervisor: AFP Construction Consultants  
Contractor and Subcontractors:  
Main Contractor: SDC Builders Ltd  
M&E Subcontractors: Dodd Group (Eastern) Ltd  
Lift: ThyssenKrupp Elevator UK Limited  
Frameless Glazing to Hanging Rooms: F.A. Firman (Harold  
Wood) Ltd  
Stair and Undercroft Glazing: J. Street and Co  
Windows: Alco Beldan Ltd  
Joinery: Janes and Albone Carpentry Ltd  
Steelwork: B and D Willett Fabrications Ltd  
Photo Voltaic installation: Equinox Energy  
Roofing: Cambridge Asphalt Co Ltd  
Ironmongery: Allgood  
Photographs:  
David Stewart  
5th Studio

*Information Commons, University of Sheffield*

Completion: 2007  
Project cost: £23 million  
Cost per sq m: £2210  
Gross floor area: 11,500sq m



Client: University of Sheffield  
 Architect: RMJM  
 Structural Engineer: Whitby Bird & Partners  
 M&E Services Engineer (pre-novation): RMJM  
 M&E Services Engineer (post-novation): Operon  
 Quantity Surveyor: Turner Townsend  
 Project Manager: Turner Townsend  
 Landscape Architect: Land Landscape  
 Planning Supervisor: RLF  
 Acoustic Consultant: Sharps Redmore Partnership  
 Fire Consultant: Safe & Buro Happold  
 Approved Building Inspector: Sheffield City Council

Contractor and Subcontractors:  
 Main Contractor: HBG Construction  
 Concrete void formers: Hanson Cobiax

Photographs:  
 Hufton & Crow  
 Broadstock Office Furniture

### *St John's Therapy Centre, Wandsworth, London*

Completion: 2006  
 Construction cost: £6.7 million  
 Cost per sq m: £1899  
 Gross floor area: 3529sq m

Client: South West London Health Partnership, on behalf of Wandsworth Primary Care Trust  
 Architect: Buschow Henley Architects  
 Structural Engineer: Price & Myers  
 M&E Engineer: Whitbybird  
 Quantity Surveyor: Davis Langdon LLP  
 Building Control: MLM Building Control  
 Main Contractor: Willmott Dixon Construction

Photographs:  
 Nick Kane

### *Christchurch Tower, City of London*

Completion: 2006  
 Construction cost: £1.1 million  
 Cost per sq m: £4400  
 Gross floor area: 250sq m

Client: Kate Renwick  
 Architect: Boyarsky Murphy  
 Structural Engineer: Alan Baxter & Associates and Greig Ling Consulting Engineers  
 M&E Services Engineer: McDonnell Langley Associates and Max Fordham LLP  
 Planning Consultant: Washburn Greenwood Development Planning  
 Historic building Consultant: Chris Miele  
 Building Control: JHAI Ltd

Contractor and Subcontractors:  
 Main Contractor: KoruBuild Ltd (Brockham)  
 Stonework: Paye Stonework & Restoration  
 Lead roofing: Able Waterproofing  
 Window supplier: Senlac, Windows & Doors  
 Window manufacturers: Jansen and Crittall  
 Window glazing: Pilkington Building Products UK  
 Front door: MSJ Joinery  
 Internal sliding door gear: Hafele UK  
 Glass balustrades and floor panels: Sharder Glass  
 Spiral staircases: Spiral Staircase Systems  
 Timber panelling & joinery: KoruBuild Ltd  
 Limestone flooring: Stone Age  
 Slate flooring: Delabole  
 Floor wax: OS hardwax oil by OSMO Ostermann & Scheiwe GmbH  
 Smooth masonry finish: Johnstones  
 Ironmongery: Allgood  
 Lighting: Lightgraphix, Bega, Erco, Kreon, SKK  
 Lighting controls: Panasonic  
 Lift: IMEM Ascensores SL

Photographs:  
 Hélène Binet

### *Halligan House, St Albans*

Completion: 2007  
 Construction cost: £312,400  
 Cost per sq m: £1360  
 Gross floor area: 230sq m

Client: Private  
 Architect: Simon Conder Architects  
 Structural Engineers: Built Engineers  
 Main Contractor: Dunworth Builders

Photographs:  
 Tom Ebdon  
 Steve Ambrose

### *Herringbone Houses, Wandsworth, London*

Completion: 2007  
 Construction cost: £1.63 million  
 Cost per sq m: £2200  
 Gross floor area: 2 × 400sq m

Client: Private  
 Architect: Alison Brooks Architects  
 Structural Engineer: Price & Myers  
 M&E Services Engineer: Peter Deer and Associates  
 Quantity Surveyor: Carruth Marshall Partnership  
 Planning Consultant: FPD Savills  
 Project Manager: Brian White  
 Planning Supervisor: Peter Deer and Associates  
 Building control: Wandsworth Council  
 Land Surveyors: W.P.G. Surveyors

## *Project Credits*

Party wall Consultant: BLDA Consultancy  
Archaeology: Compass Archaeology  
Arboricultural Consultant: Quaife Woodlands  
Main Contractor: Cobalt Green Construction Ltd

### Suppliers:

Cladding: Ipe timber by Tradelink Wood Products  
Roofing membrane: Sarnafil  
Breather membrane: Tyvek  
Insulation: Kingspan  
Aluminium windows: Fineline  
Oak flooring: HFL (Hardwood Flooring London)  
Precast concrete planks: Bison floors  
External render: Weatherby Insulated Render Systems  
Underfloor heating: Warmafloor Underfloor Heating  
Closets: Oval Workshop  
Staircase & glass balustrades: Fastrac Joinery  
Kitchen: Kitchen Clinic

### Photographs:

Cristobal Palmer  
Alison Brooks Architects

## *GreenHouse, BRE, Watford*

Completion: 2008  
Construction cost: confidential  
Cost per sq m: confidential  
Gross floor area: 133sq m

Client: Barratt Developments PLC  
Architect: Gaunt Francis Architects  
Structural Engineer: Arup (Newcastle)  
M&E Services Engineer: Arup (Newcastle)  
Acoustic Engineer: Arup (Newcastle)  
SAP/Sustainability Consultant: BRE  
BREEAM assessor: Arup (London)  
Building regulations inspector: NHBC

### Contractor and suppliers:

Main Contractor: Barratt North London  
Aircrete wall panels: H&H Celcon  
Precast floor slabs: Millbank  
Thermally broken slab connections: Schöck  
SIP roof panels: Smartroof Ltd  
Windows: Nordan  
Window sealant system: Tremco Illbruck Ltd  
Doors (main entrance and roof terrace): Russell Timber Technology  
Sunpipe: Monodraught Ltd  
Thermal insulation: Kingspan Insulation Ltd  
Vacuum insulation panels: Va-Q-tec through Passive House Solutions Ltd  
Roof coverings: Bauder Ltd  
Photovoltaic panels: Solarcentury  
External render: Weber building solutions  
Copper cladding: KME UK  
External cladding: Trespa U Ltd

Automatic sliding shutter gear: Hawa AG through Häfele  
Internal ceiling plaster: Knauf UK  
Internal thin coat spray plaster: Alltek UK  
Dry lining: British Gypsum  
External paving: Hanson  
Sockets & switches: LeGrand  
Kitchen: Symphony Kitchens  
Sanitaryware: Ideal Standard  
WC wall mounting system: Grohe  
Taps & showers: Bristan

### Photographs:

Denis Jones  
Peter White  
Gaunt Francis Architects

## *Focus House, Finsbury Park, London*

Completion: 2006  
Construction cost: confidential  
Cost per sq m: confidential  
Gross floor area: 120sq m

Client: Private  
Architect: bere:architects  
Structural Engineer: Techniker  
Landscape design: Declan Buckley Design  
Lighting design: John Cullen Lighting

### Contractor and Subcontractors:

Contractor: Vision Build Ltd  
Timber structure: KLH UK (massivholtz GmbH)  
Zinc cladding & roofing: PMF Roofcraft  
Bespoke furniture: Contrax Furniture

### Suppliers:

Structural timber: KLH Massivholz GmbH  
Zinc: VM Zinc UK  
Insulation: Pittsburgh Corning UK Ltd  
Gas fired hot water boiler: Viessmann  
Solar panel and hot water storage: Viessmann  
Whole house ventilation & heat recovery: Ubbink UK Ltd  
Flooring: Hutchison Flooring Ltd  
Drainage: Geberit UK  
Oak flooring: Hutchinson Flooring Ltd  
Timber windows external: Scandinavian Window Systems Ltd  
Aluminium windows & front door: Isaacs Glass Co Ltd  
Internal (non-fire rated) doors: Timbmet Group Ltd  
Ironmongery: Franchi Locks & Tools Ltd  
Tiles: Domus Tiles  
Entrance matting: Gradus Ltd  
Bath top: DuPoint Corian  
Hand basins & WC pans: Duravit UK Ltd  
Shower units: Grohe Ltd  
Bath: Bette GmbH & Co  
Sealant: Adshead Ratcliffe  
Drainage slot channels: ACO drain

Floor drains in shower: Dallmer  
 Water softener: The Fresh Filter Co. Ltd  
 Steel column radiators: Caradon Stelrad Ltd  
 Towel radiators: Bisque Radiators  
 Under floor heating: Warmfloor (GB) Ltd  
 Electrical accessories: MK Electric Ltd  
 Taps: Vola UK

Photographs:  
 Jefferson Smith  
 bere:architects

### *80% House, De Beauvoir Town, London*

Completion: 2009  
 Construction cost: £240,000  
 Cost per sq m: £1370  
 Gross floor area: 175sq m

Client: Private  
 Architect: Prewett Bizley Architects  
 Structural Engineer: Nabeii Consultancy  
 Building control approved inspector: JHAI

Suppliers:  
 Wall and roof insulation: Knauf  
 Insulated wall studs: Knauf  
 Perinsul blocks: Foamglas  
 Teplo wall ties: MagmaTech  
 Roofing membrane: Prelasti  
 Sash windows: Soundcraft  
 Double glazing (for sash windows): Slimlite  
 Triple glazed timber windows: Bayer supplied through Double Good  
 Front door: Soundcraft  
 Pitch pine flooring: Lawson's Timber  
 Timber stairs: Tidy joinery  
 Handrail: Haldane  
 MVHR box: Itho supplied through Green Building Store  
 MVHR ducting: Lindab  
 Airtightness tapes and seals: Proclima supplied through Green Building Store

Photographs:  
 Prewett Bizley Architects

### *Clay Field Housing, Elmswell, Suffolk*

Completion: 2008  
 Cost per sq m: £1300  
 Gross floor area: 2072 sq m

Client: Orwell Housing Association  
 Architect: Riches Hawley Mikhail Architects  
 Structural Engineer: BTA Structural Design Ltd  
 Sustainability Consultant: Buro Happold  
 M&E Services Engineer: Inviron

Quantity Surveyor: Hyams and Partners  
 Landscape Architect: J&L Gibbons LLP  
 Civil Engineer: Scott Wilson incorporating Cameron Taylor

Contractor and suppliers:  
 Main Contractor: O. Seaman and Son Ltd  
 'Hemcrete' Suppliers: Lime Technology & Lhoist  
 'Hemcrete' Subcontractor: Quickseal  
 Window Suppliers: Scandinavian Window Systems & The Rooflight Company  
 Cedar supplier: John Brash  
 Roofer (cedar shingles): Nigel Maguire

Photographs:  
 Nick Kane  
 Riches Hawley Mikhail Architects

### *Chance Street Housing, Bethnal Green, London*

Completion: 2007  
 Construction cost (new houses): £643,500  
 Cost per sq m (new houses): £1950  
 Gross floor area (new houses): 330sq m

Client: Rebecca Collings  
 Architect: Stephen Taylor Architects  
 Project Manager: Davis Langdon LLP  
 Quantity Surveyor: Measur  
 Structural Engineer: Paul Hardman Structural Engineers  
 M&E Services Engineer: Intengis

Contractor and Subcontractors:  
 Main Contractor: Charter Construction  
 Stair construction: Tin Tab Screens: J&R Fabrications

Photographs:  
 Ioana Marinescu  
 Simon Lewis

### *Islington Square Housing, Manchester*

Completion: 2006  
 Construction cost: £2.3 million  
 Cost per sq m: £1100  
 Gross floor area: 21,000sq m

Client: Manchester Methodist Housing Group  
 Architect: FAT  
 Structural Engineer: Whitby Bird  
 Eco Homes Assessor: Pozzoni Group  
 Employer's agent: Simon Fenton Partnership  
 Quantity Surveyor: Simon Fenton Partnership

Contractor and suppliers:  
 Main Contractor: Richardson Projects  
 Windows: Rationel  
 Bricks: Baggeridge  
 Roof: Kalzip



Render: Alumasc

Photographs:  
Tim Soar  
James White  
Edmund Sumner

*EMV Social Housing, Vallecas, Madrid*

Completion: 2005  
Construction cost: £8.5 million  
Cost per sq m: £646  
Gross floor area: 13,150 sq m

Architect: Feilden Clegg Bradley Architects  
Local Architect: Ortiz Leon Arquitectos  
Environmental Engineer: Emma s.l, Madrid, Spain  
M&E Services Engineer: Max Fordham LLP  
Structural Engineer: Integral

Photographs:  
Empresa Municipal de la Vivienda  
Elena Marco

*The Johnson Building, Clerkenwell, London*

Completion: 2006  
Construction cost: £22.2 million  
Cost per sq m: £1133  
Gross floor area: 19,587 sq m

Client: Derwent London plc  
Architect: Allford Hall Monaghan Morris LLP  
Structural Engineer: Price and Myers  
Project Manager: Buro4  
Quantity Surveyor: Davis Langdon LLP  
M&E Services Engineer: ARUP M&E  
Lighting Design: GIAEquation  
Fire Engineer: Exova Warringtonfire  
Landscape Designer: BBUK  
Landscape Architecture Access Consultant: All Clear Design  
CDM Coordinator: Jackson Coles

Contractor and Subcontractors:  
Main Contractor: E. Bowman & Sons  
Concrete Superstructure and Fair Faced Concrete: Duffy Construction  
Brickwork: Irvine Whitlock  
Roofing: WWR  
ETFE Atrium Roof: B&O Hightex  
Windows and Glazing: WRC  
Atrium Timber Cladding: LSA Contracts  
Stone floors: Harper and Edwards  
Architectural Metalwork: Steel Arts  
Stone and Brick façade refurbishment: PAYE Stonework and Restoration Ltd

Reception Desk: Benchmark

Photographs:  
Tim Soar  
Allford Hall Monaghan Morris

*One Coleman Street, City of London*

Completion: 2008  
Construction cost (shell & core): £35.32 million  
Cost per sq m: £1648  
Gross floor area: 21,203 sq m

Developer: Stanhope plc  
Property owner: Union Investment Real Estate AG  
Architect: Swanke Hayden Connell in association with David Walker Architects  
Structural Engineer: Arup  
M&E Engineer: Arup  
Quantity Surveyor: Davis Langdon LLP  
Construction Manager: Stanhope plc

Contractor and Subcontractors:  
Main Contractor: Bovis Lend Lease  
Concrete sub-structure and super-structure: John Doyle Construction  
Precast concrete Subcontractor: Decomo, Belgium  
Stent aggregate supplier for concrete: Bardon Aggregates

Photographs:  
Hélène Binet  
Swanke Hayden Connell

*Vernon Street Offices, Kensington, London*

Completion: 2006  
Construction cost: £3.5 million  
Cost per sq m: 1600  
Gross floor area: 2200 sq m

Architect: Terry Pawson Architects  
Structural Engineer: Barton Engineers  
Services Engineer: Max Fordham LLP  
Quantity Surveyor: Bucknall Austin  
Construction Management: Acuity Management Solutions  
Garden/Courtyard Design: Gatacre Garden Design  
General Builder: Pexhurst Services Ltd  
Cast Stone Subcontractor: Histon Concrete Products Ltd

Photographs:  
Terry Pawson Architects

*Southern Cross Station, Melbourne*

Completion: 2005  
Construction cost: confidential

Cost per sq m: confidential

Gross floor area: 60,000sq m

Client: State Government of Victoria

Architect: Grimshaw Jackson JV

Joint venture Architect: Jackson Architecture Pty Ltd

Structural Engineer: Winward Structures

Services Engineer: Lincolne Scott Australia P/L

Environmental engineer: AEC (Advanced Environmental Concepts)

Quantity Surveyor: DCWC Pty Ltd

Pedestrian flow Engineer: Scott Wilson Irwin Johnston Pty

Rail & civil Engineers: Maunsell Australia

Signalling Engineer: GHD

Access Consultant: Blythe Saunderson

Security Consultant: Honeywell

Acoustic Consultant: Marshall Day

Roof Shop Detailing: Precision Design

Contractor and Subcontractors:

Main Contractor: Leighton Contractors Pty Ltd

Suppliers:

Ground Floor Accommodation (Precast Concrete Panels): Bianco Constress

Escalator and Lift Metal Cladding (Alucobond): Red Earth

Ticket Office Cladding (Glass Reinforced Concrete): Glenn Industries

Pod Cladding (Formawall): HH Robertson

Soffit Panels (Luxalon): Schiavello

Steel Spine Trusses: Geelong Fabrications, AJ Mayer and Haywoods

Primary arches, secondaries, diagonals: Alfasi and Riband Steel, Riband Steel

Roof sheeting (Kalzip standing seam aluminium roof-sheet): Unison/BSI JV

Ceiling panel supply (aluminium panels): Unison

Skylights (ETFE cushions): Vector Foiltec

Columns (steel composite columns and arms): Shearform

Roof erection Subcontractor: Rigweld P/L

Spencer St & Collins St Glazed Façades Aluminium & glass façades: Riband/Clipfit

Bourke St Bridge & Western Glazed Façades Aluminium and glass façades: Alfasi/Clipfit

Main Station Entrance Doors: Airport Doors

Balustrades and Handrails: Applied Manufacturing

Concourse and Platform Seating (Downforce seats): Aura

Active Pedestrian Information Systems: Honeywell

Wayfinding: Bentleigh Signs

Heating/cooling systems: Entire

Lighting and Electrical: Downer

Paint: Ameron, Jotun

Paving: Bluestone, Bamstone

Photographs:

John Gollings

Markus Bachmann

Grimshaw

# Project Details

Project	Architect	Page no.	Building use									
			Gallery or museum	Theatre or dance	Cinema	Live music	Civic	Sport or leisure	Nursery	School	Higher education	Health
Royal Festival Hall, London	Allies & Morrison	17				•	•					
Neues Museum, Berlin	David Chipperfield Architects	21	•				•					
Newlyn Art Gallery, Cornwall	MUMA	25	•				•					
North Wall Arts Centre, Oxford	Haworth Tompkins Architects	31	•	•								
Regents Park Open Air Theatre, London	Prewett Bizley Architects	37		•								
Bluecoat Arts Centre, Liverpool	Biq Architecten	41	•	•		•	•					
Ruthin Craft Centre, Denbighshire	Sergison Bates Architects	45	•				•					
Siobahn Davis Dance Centre, London	Sarah Wigglesworth Architects	49		•								
Rich Mix, Bethnal Green, London	Penoyre & Prasad	53	•		•		•					
MIMA, Middlesbrough	Designed by Erick van Egeraat	57	•				•					
Multi Purpose Hall, Aurillac, France	Brisac Gonzales	61				•	•	•				
Arc, Hull	Niall McLaughlin Architects	65					•					
Resource Centre, Grizedale Forrest Park, Cumbria	Sutherland Hussey	69						•				
Thermae Bath Spa, Bath	Nicholas Grimshaw & Partners	75						•				
Civil Justice Centre, Manchester	Denton Corker Marshall	81					•					
Sean O'Casey Community Centre, Dublin	O'Donnell + Tuomey	85					•	•	•			
Bellingham Gateway Building, Lewisham, London	Cottrell and Vermeulen Architecture	91						•	•			
Maryland Early Years Centre, Stratford, London	Fluid	95							•			
Emmaus School, Wyebourne, Sheffield	DSDHA	99								•		
Bedford School Music School, Bedford	Eric Parry Architects	105								•		
Sanger Building, Bryanston School, Dorset	Hopkins Architects	111								•		
Scitex, Oundle School, Northamptonshire	Feilden Clegg Bradley	115								•		
Ann's Court, Selwyn College, Cambridge	Porphyrios Associates	121									•	
Wolfson Building, Trinity College, Cambridge	5th Studio	125									•	
Information Commons, University of Sheffield	RMJM	129									•	
St Johns Therapy Centre, Wandsworth, London	Buschow Henley Architects	133										•
Christchurch Tower, City of London	Boyersky Murphy	137										
Halligan House, St Albans	Simon Conder Architects	141										
Herringbone Houses, Wandsworth, London	Alison Brooks Architects	147										
GreenHouse, BRE, Watford	Gaunt Francis Architects	151										
Focus House, Finsbury Park, London	Bere Architects	155										
80% House, De Beauvoir Town, London	Prewett Bizley Architects	159										
Clay Field Housing, Elmswell, Suffolk	Riches Hawley Mikhail Architects	165										
Chance Street Housing, Bethnal Green, London	Stephen Taylor Architects	171										
Islington Square Housing, Manchester	FAT	175										
EMV Social Housing, Vallecas, Madrid	Feilden Clegg Bradley	179										
Johnson Building, Clerkenwell, London	Allford Hall Monaghan Morris	183										
One Coleman Street, City of London	David Walker Architects in association with Swanke Hayden Connell	187										
Vernon Street Offices, Kensington, London	Terry Pawson Architects	191										
Southern Cross Station, Melbourne	Nicholas Grimshaw & Partners	195										



				Construction cost					cost / sq m				Project Type				Primary Structure				Primary external materials										
Private house	Housing	Offices	Transport	< £1 Million	£1 – 5 Million	£5 – 15 Million	£15 – 50 Million	> £50 Million	< £1500	£1500 – 2000	£2000 – 3000	> £3000	New build	Refurbishment	Extension	Work to listed building/landscape	Concrete	Steel	Masonry	Timber	Brick	Stone	Concrete	Render	Glass	Timber cladding	Metal cladding	Metal screens/ louvres	Polycarbonate or GRP cladding	Other cladding	
								•			•	•		•		•	•		•			•	•			•					
				•				•			•	•		•		•	•		•			•	•								•
				•							•			•		•	•		•							•					
						•					•			•		•															
					•					•				•		•								•							
						•						•		•		•															
									•					•		•															
				•							•			•		•															
					•						•			•		•															
							•							•		•															
						•					•			•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															
														•		•															</