

# **Solar Engineering of Thermal Processes**

# Solar Engineering of Thermal Processes

Fourth Edition

**John A. Duffie (Deceased)**

*Emeritus Professor of Chemical Engineering*

**William A. Beckman**

*Emeritus Professor of Mechanical Engineering*

Solar Energy Laboratory  
University of Wisconsin-Madison

**WILEY**

Cover image: (top) Kyu Oh/iStockphoto; (bottom) Gyula Gyukli/iStockphoto  
Cover design: Anne-Michele Abbott

This book is printed on acid-free paper.

Copyright © 2013 by John Wiley & Sons, Inc. All rights reserved

Published by John Wiley & Sons, Inc., Hoboken, New Jersey  
Published simultaneously in Canada

No part of this publication may be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, scanning, or otherwise, except as permitted under Section 107 or 108 of the 1976 United States Copyright Act, without either the prior written permission of the Publisher, or authorization through payment of the appropriate per-copy fee to the Copyright Clearance Center, 222 Rosewood Drive, Danvers, MA 01923, (978) 750-8400, fax (978) 646-8600, or on the web at [www.copyright.com](http://www.copyright.com). Requests to the Publisher for permission should be addressed to the Permissions Department, John Wiley & Sons, Inc., 111 River Street, Hoboken, NJ 07030, (201) 748-6011, fax (201) 748-6008, or online at [www.wiley.com/go/permissions](http://www.wiley.com/go/permissions).

**Limit of Liability/Disclaimer of Warranty:** While the publisher and author have used their best efforts in preparing this book, they make no representations or warranties with the respect to the accuracy or completeness of the contents of this book and specifically disclaim any implied warranties of merchantability or fitness for a particular purpose. No warranty may be created or extended by sales representatives or written sales materials. The advice and strategies contained herein may not be suitable for your situation. You should consult with a professional where appropriate. Neither the publisher nor the author shall be liable for damages arising herefrom.

For general information about our other products and services, please contact our Customer Care Department within the United States at (800) 762-2974, outside the United States at (317) 572-3993 or fax (317) 572-4002.

Wiley publishes in a variety of print and electronic formats and by print-on-demand. Some material included with standard print versions of this book may not be included in e-books or in print-on-demand. If this book refers to media such as a CD or DVD that is not included in the version you purchased, you may download this material at <http://booksupport.wiley.com>. For more information about Wiley products, visit [www.wiley.com](http://www.wiley.com).

ISBN 978-0-470-87366-3 (cloth); ISBN 978-1-118-41541-2 (ebk); ISBN 978-1-118-41812-3 (ebk);  
ISBN 978-1-118-43348-5 (ebk); ISBN 978-1-118-67160-3 (ebk)

Printed in the United States of America

10 9 8 7 6 5 4 3 2 1

# Contents

---

Preface	xi
Preface to the Third Edition	xiii
Preface to the Second Edition	xv
Preface to the First Edition	xvii
Introduction	xxi

## **PART I FUNDAMENTALS 1**

### **1 Solar Radiation 3**

---

1.1	The Sun	3
1.2	The Solar Constant	5
1.3	Spectral Distribution of Extraterrestrial Radiation	6
1.4	Variation of Extraterrestrial Radiation	8
1.5	Definitions	9
1.6	Direction of Beam Radiation	12
1.7	Angles for Tracking Surfaces	20
1.8	Ratio of Beam Radiation on Tilted Surface to That on Horizontal Surface	23
1.9	Shading	29
1.10	Extraterrestrial Radiation on a Horizontal Surface	37
1.11	Summary	41
	References	41

### **2 Available Solar Radiation 43**

---

2.1	Definitions	43
2.2	Pyrheliometers and Pyrheliometric Scales	44
2.3	Pyranometers	48
2.4	Measurement of Duration of Sunshine	53
2.5	Solar Radiation Data	54
2.6	Atmospheric Attenuation of Solar Radiation	59
2.7	Estimation of Average Solar Radiation	64
2.8	Estimation of Clear-Sky Radiation	68
2.9	Distribution of Clear and Cloudy Days and Hours	71
2.10	Beam and Diffuse Components of Hourly Radiation	74
2.11	Beam and Diffuse Components of Daily Radiation	77

2.12	Beam and Diffuse Components of Monthly Radiation	79
2.13	Estimation of Hourly Radiation from Daily Data	81
2.14	Radiation on Sloped Surfaces	84
2.15	Radiation on Sloped Surfaces: Isotropic Sky	89
2.16	Radiation on Sloped Surfaces: Anisotropic Sky	91
2.17	Radiation Augmentation	97
2.18	Beam Radiation on Moving Surfaces	101
2.19	Average Radiation on Sloped Surfaces: Isotropic Sky	103
2.20	Average Radiation on Sloped Surfaces: KT Method	107
2.21	Effects of Receiving Surface Orientation on $\overline{H}_T$	112
2.22	Utilizability	115
2.23	Generalized Utilizability	118
2.24	Daily Utilizability	126
2.25	Summary	132
	References	133

### **3 Selected Heat Transfer Topics 138**

---

3.1	The Electromagnetic Spectrum	138
3.2	Photon Radiation	139
3.3	The Blackbody: Perfect Absorber and Emitter	139
3.4	Planck's Law and Wien's Displacement Law	140
3.5	Stefan-Boltzmann Equation	141
3.6	Radiation Tables	142
3.7	Radiation Intensity and Flux	144
3.8	Infrared Radiation Exchange between Gray Surfaces	146
3.9	Sky Radiation	147
3.10	Radiation Heat Transfer Coefficient	148
3.11	Natural Convection between Flat Parallel Plates and between Concentric Cylinders	149
3.12	Convection Suppression	154
3.13	Vee-Corrugated Enclosures	158
3.14	Heat Transfer Relations for Internal Flow	159



3.15	Wind Convection Coefficients	163
3.16	Heat Transfer and Pressure Drop in Packed Beds and Perforated Plates	165
3.17	Effectiveness-NTU Calculations for Heat Exchangers	168
	References	170

#### **4 Radiation Characteristics of Opaque Materials 173**

4.1	Absorptance and Emittance	174
4.2	Kirchhoff's Law	176
4.3	Reflectance of Surfaces	177
4.4	Relationships among Absorptance, Emittance, and Reflectance	181
4.5	Broadband Emittance and Absorptance	182
4.6	Calculation of Emittance and Absorptance	183
4.7	Measurement of Surface Radiation Properties	186
4.8	Selective Surfaces	188
4.9	Mechanisms of Selectivity	192
4.10	Optimum Properties	195
4.11	Angular Dependence of Solar Absorptance	196
4.12	Absorptance of Cavity Receivers	197
4.13	Specularly Reflecting Surfaces	198
	References	199

#### **5 Radiation Transmission through Glazing: Absorbed Radiation 202**

5.1	Reflection of Radiation	202
5.2	Absorption by Glazing	206
5.3	Optical Properties of Cover Systems	206
5.4	Transmittance for Diffuse Radiation	211
5.5	Transmittance-Absorptance Product	213
5.6	Angular Dependence of $(\tau\alpha)$	214
5.7	Spectral Dependence of Transmittance	215
5.8	Effects of Surface Layers on Transmittance	218
5.9	Absorbed Solar Radiation	219
5.10	Monthly Average Absorbed Radiation	223
5.11	Absorptance of Rooms	229
5.12	Absorptance of Photovoltaic Cells	231
5.13	Summary	234
	References	234

#### **6 Flat-Plate Collectors 236**

6.1	Description of Flat-Plate Collectors	236
6.2	Basic Flat-Plate Energy Balance Equation	237
6.3	Temperature Distributions in Flat-Plate Collectors	238
6.4	Collector Overall Heat Loss Coefficient	240
6.5	Temperature Distribution between Tubes and the Collector Efficiency Factor	254
6.6	Temperature Distribution in Flow Direction	261
6.7	Collector Heat Removal Factor and Flow Factor	262
6.8	Critical Radiation Level	266
6.9	Mean Fluid and Plate Temperatures	267
6.10	Effective Transmittance-Absorptance Product	268
6.11	Effects of Dust and Shading	271
6.12	Heat Capacity Effects in Flat-Plate Collectors	272
6.13	Liquid Heater Plate Geometries	275
6.14	Air Heaters	280
6.15	Measurements of Collector Performance	287
6.16	Collector Characterizations	288
6.17	Collector Tests: Efficiency, Incidence Angle Modifier, and Time Constant	289
6.18	Test Data	299
6.19	Thermal Test Data Conversion	302
6.20	Flow Rate Corrections to $F_R(\tau\alpha)_n$ and $F_R U_L$	305
6.21	Flow Distribution in Collectors	308
6.22	In Situ Collector Performance	309
6.23	Practical Considerations for Flat-Plate Collectors	310
6.24	Putting it all Together	313
6.25	Summary	318
	References	319

#### **7 Concentrating Collectors 322**

7.1	Collector Configurations	323
7.2	Concentration Ratio	325
7.3	Thermal Performance of Concentrating Collectors	327
7.4	Optical Performance of Concentrating Collectors	334
7.5	Cylindrical Absorber Arrays	335
7.6	Optical Characteristics of Nonimaging Concentrators	337

7.7	Orientation and Absorbed Energy for CPC Collectors	345
7.8	Performance of CPC Collectors	349
7.9	Linear Imaging Concentrators: Geometry	351
7.10	Images Formed by Perfect Linear Concentrators	354
7.11	Images from Imperfect Linear Concentrators	359
7.12	Ray-Trace Methods for Evaluating Concentrators	361
7.13	Incidence Angle Modifiers and Energy Balances	361
7.14	Paraboloidal Concentrators	367
7.15	Central-Receiver Collectors	368
7.16	Practical Considerations	369
	References	370

## 8 Energy Storage 373

8.1	Process Loads and Solar Collector Outputs	373
8.2	Energy Storage in Solar Process Systems	375
8.3	Water Storage	376
8.4	Stratification in Storage Tanks	379
8.5	Packed-Bed Storage	384
8.6	Storage Walls	392
8.7	Seasonal Storage	394
8.8	Phase Change Energy Storage	396
8.9	Chemical Energy Storage	400
8.10	Battery Storage	402
	References	406

## 9 Solar Process Loads 409

9.1	Examples of Time-Dependent Loads	410
9.2	Hot-Water Loads	411
9.3	Space Heating Loads, Degree-Days, and Balance Temperature	412
9.4	Building Loss Coefficients	415
9.5	Building Energy Storage Capacity	417
9.6	Cooling Loads	417
9.7	Swimming Pool Heating Loads	418
	References	420

## 10 System Thermal Calculations 422

10.1	Component Models	422
10.2	Collector Heat Exchanger Factor	424
10.3	Duct and Pipe Loss Factors	426

10.4	Controls	429
10.5	Collector Arrays: Series Connections	431
10.6	Performance of Partially Shaded Collectors	433
10.7	Series Arrays with Sections Having Different Orientations	435
10.8	Use of Modified Collector Equations	438
10.9	System Models	441
10.10	Solar Fraction and Solar Savings Fraction	444
10.11	Summary	445
	References	446

## 11 Solar Process Economics 447

11.1	Costs of Solar Process Systems	447
11.2	Design Variables	450
11.3	Economic Figures of Merit	452
11.4	Discounting and Inflation	454
11.5	Present-Worth Factor	456
11.6	Life-Cycle Savings Method	459
11.7	Evaluation of Other Economic Indicators	464
11.8	The $P_1, P_2$ Method	467
11.9	Uncertainties in Economic Analyses	472
11.10	Economic Analysis Using Solar Savings Fraction	475
11.11	Summary	476
	References	476

## PART II APPLICATIONS 477

### 12 Solar Water Heating: Active and Passive 479

12.1	Water Heating Systems	479
12.2	Freezing, Boiling, and Scaling	483
12.3	Auxiliary Energy	486
12.4	Forced-Circulation Systems	488
12.5	Low-Flow Pumped Systems	490
12.6	Natural-Circulation Systems	491
12.7	Integral Collector Storage Systems	494
12.8	Retrofit Water Heaters	496
12.9	Water Heating in Space Heating and Cooling Systems	497
12.10	Testing and Rating of Solar Water Heaters	497
12.11	Economics of Solar Water Heating	499

12.12	Swimming Pool Heating	502
12.13	Summary	503
	References	503

### **13 Building Heating: Active 505**

13.1	Historical Notes	506
13.2	Solar Heating Systems	507
13.3	CSU House III Flat-Plate Liquid System	511
13.4	CSU House II Air System	513
13.5	Heating System Parametric Study	517
13.6	Solar Energy–Heat Pump Systems	521
13.7	Phase Change Storage Systems	527
13.8	Seasonal Energy Storage Systems	530
13.9	Solar and Off-Peak Electric Systems	533
13.10	Solar System Overheating	535
13.11	Solar Heating Economics	536
13.12	Architectural Considerations	539
	References	541

### **14 Building Heating: Passive and Hybrid Methods 544**

14.1	Concepts of Passive Heating	545
14.2	Comfort Criteria and Heating Loads	546
14.3	Movable Insulation and Controls	546
14.4	Shading: Overhangs and Wingwalls	547
14.5	Direct-Gain Systems	552
14.6	Collector-Storage Walls and Roofs	557
14.7	Sunspaces	561
14.8	Active Collection–Passive Storage Hybrid Systems	563
14.9	Other Hybrid Systems	565
14.10	Passive Applications	565
14.11	Heat Distribution in Passive Buildings	571
14.12	Costs and Economics of Passive Heating	571
	References	573

### **15 Solar Cooling 575**

15.1	Solar Absorption Cooling	576
15.2	Theory of Absorption Cooling	578
15.3	Combined Solar Heating and Cooling	584
15.4	Simulation Study of Solar Air Conditioning	585
15.5	Operating Experience with Solar Cooling	589
15.6	Applications of Solar Absorption Air Conditioning	591

15.7	Solar Desiccant Cooling	592
15.8	Ventilation and Recirculation Desiccant Cycles	594
15.9	Solar-Mechanical Cooling	596
15.10	Solar-Related Air Conditioning	599
15.11	Passive Cooling	601
	References	601

### **16 Solar Industrial Process Heat 604**

16.1	Integration with Industrial Processes	604
16.2	Mechanical Design Considerations	605
16.3	Economics of Industrial Process Heat	606
16.4	Open-Circuit Air Heating Applications	607
16.5	Recirculating Air System Applications	611
16.6	Once-Through Industrial Water Heating	613
16.7	Recirculating Industrial Water Heating	615
16.8	Shallow-Pond Water Heaters	617
16.9	Summary	619
	References	619

### **17 Solar Thermal Power Systems 621**

17.1	Thermal Conversion Systems	621
17.2	Gila Bend Pumping System	622
17.3	Luz Systems	624
17.4	Central-Receiver Systems	628
17.5	Solar One and Solar Two Power Plants	630
	References	633

### **18 Solar Ponds: Evaporative Processes 635**

18.1	Salt-Gradient Solar Ponds	635
18.2	Pond Theory	637
18.3	Applications of Ponds	639
18.4	Solar Distillation	640
18.5	Evaporation	646
18.6	Direct Solar Drying	647
18.7	Summary	647
	References	648

## **PART III DESIGN METHODS 651**

### **19 Simulations in Solar Process Design 653**

19.1	Simulation Programs	653
19.2	Utility of Simulations	654

19.3	Information from Simulations	655
19.4	TRNSYS: Thermal Process Simulation Program	656
19.5	Simulations and Experiments	663
19.6	Meteorological Data	663
19.7	Limitations of Simulations	666
	References	667

## **20 Design of Active Systems: $f$ -Chart 668**

20.1	Review of Design Methods	668
20.2	The $f$ -Chart Method	669
20.3	The $f$ -Chart for Liquid Systems	673
20.4	The $f$ -Chart for Air Systems	679
20.5	Service Water Heating Systems	683
20.6	The $f$ -Chart Results	685
20.7	Parallel Solar Energy-Heat Pump Systems	686
20.8	Summary	690
	References	690

## **21 Design of Active Systems by Utilizability Methods 692**

21.1	Hourly Utilizability	693
21.2	Daily Utilizability	696
21.3	The $\bar{\phi}$ , $f$ -Chart Method	699
21.4	Summary	709
	References	710

## **22 Design of Passive and Hybrid Heating Systems 711**

22.1	Approaches to Passive Design	711
22.2	Solar-Load Ratio Method	712
22.3	Unutilizability Design Method: Direct Gain	721
22.4	Unutilizability Design Method: Collector-Storage Walls	727
22.5	Hybrid Systems: Active Collection with Passive Storage	736
22.6	Other Hybrid Systems	742
	References	743

## **23 Design of Photovoltaic Systems 745**

23.1	Photovoltaic Converters	746
23.2	PV Generator Characteristics and Models	747
23.3	Cell Temperature	757
23.4	Load Characteristics and Direct-Coupled Systems	759
23.5	Controls and Maximum Power Point Trackers	763
23.6	Applications	764
23.7	Design Procedures	765
23.8	High-Flux PV Generators	770
23.9	Summary	771
	References	771

## **24 Wind Energy 774**

24.1	Introduction	774
24.2	Wind Resource	778
24.3	One-Dimensional Wind Turbine Model	786
24.4	Estimating Wind Turbine Average Power and Energy Production	791
24.5	Summary	796
	References	796

## **APPENDIXES 797**

### **A Problems 797**

### **B Nomenclature 856**

### **C International System of Units 861**

### **D Meteorological Data 863**

### **E Average Shading Factors for Overhangs 870**

Index	887
-------	-----

# Preface

---

This fourth edition emphasizes solar system design and analysis using simulations. The design of many systems that use conventional energy sources (e.g., oil, gas, and electricity) use a worst-case environmental condition—think of a building heating system. If the system can maintain the building temperature during the coldest period, it will be able to handle all less severe conditions. To be sure, even building heating systems are now using simulations during the design phase. In addition to keeping the building comfortable during the worst conditions, various design choices can be made to reduce annual energy use.

This and earlier editions of this book describe TRNSYS (pronounced Tran-sis), a general system simulation program (see Chapter 19). Like all heating and air conditioning systems, a solar system can be thought of as a collection of components. TRNSYS has hundreds of component models, and the TRNSYS language is used to connect the components together to form a system. Following the Preface to the First Edition is the Introduction where a ready-made TRNSYS program (called CombiSys) is described that simulates a solar-heated house with solar-heated domestic hot water. TRANSED, a front-end program for TRNSYS is used so it is not necessary to learn how to develop TRNSYS models to run CombiSys. CombiSys can be freely downloaded from the John Wiley website (<http://www.wiley.com/go/solarengineering4e>).

CombiSys provides an input window where various design options can be selected (e.g., the collector type and design, storage tank size, collector orientation, and a variety of other choices). A series of simulation problems (identified with a prefix “S” followed by a chapter number and then a problem number) have been added to the standard problems of many chapters. The “S0” problems (that is, Chapter 0, the Introduction) require running CombiSys and answering general questions that may require performing energy balances and doing simple economic calculations. As new topics are discussed in this text new “S” problems are introduced, often with the objective to duplicate some aspect of CombiSys. With this approach it is hoped that the student will understand the inner workings of a simulation program and be made aware of why certain topics are introduced and discussed in the text.

The purpose of studying and understanding any topic in engineering is to make the next system better than the last. Part I in this study of solar systems contains 11 chapters devoted to understanding the operation of components (e.g., the sun, collectors, storage systems, loads, etc.). The results of these early chapters are mathematical models that allow the designer to estimate component performance (in the TRNSYS language, the outputs) for a given set of component conditions (i.e., TRNSYS inputs). It is easy to think of collectors, storage tanks, photovoltaic arrays, and batteries as components, but here even the sun and economics are treated as components. The sun component manipulates the available (generally measured but sometimes estimated) solar radiation data to obtain the needed solar radiation data on an arbitrarily oriented surface and in a desired time interval. The time scale of reported solar data ranges from a few seconds to yearly. Sometimes we even need to estimate the solar energy in a wavelength interval. The available measured solar radiation data is typically energy rates (i.e., power) from a specified and easily

calculated direction such as the “beam” radiation that comes directly from the sun and the “diffuse” radiation that has been scattered in some generally unknown manner over all parts of the sky. The mathematical model of the sun component must accommodate these various input and output requirements. The final chapter in Part I covers economics. Generally the objective of a solar system is to produce environmentally friendly power at an acceptable cost. The familiar calculations of levelized cost per unit of energy and/or life-cycle savings (versus some energy alternative) are not trivial since the time horizon of a solar system can be multiple decades, requiring the estimates of far-future economic conditions. The economic impact of externalities such as reduced pollutants is difficult to evaluate since these costs are not easily monetized.

Part II, chapters 12 through 18, discusses various thermal systems that have been built, the performance measured and the results published. They are descriptive chapters with the intent of providing the reader with a feeling of what can be accomplished. Many of these systems were built and tested during a time when governments were funding universities and laboratories where a requirement was to make the results public. Most solar systems today are privately funded and performance data is often difficult or impossible to obtain.

Chapters 19 through 22 of Part III are devoted to system design (sometimes called system sizing). Before the late 1970s personal computers were not available so simulations were done either by hand or on large main-frame computers and were very expensive. Research into “design methods” focused on the development of short-cut design assistance to replace expensive simulations. The earliest example is from the early 1950s, which used a radiation statistic called “utilizability” to assist in solar sizing (see Section 2.22 and Chapter 21). The next step, the  $f$ -chart method (see Chapter 21) is from the mid-1970s and used numerical experiments to develop correlations of the various nondimensional groups. This process is not unlike laboratory experiments that are used to correlate dimensionless heat transfer results (the Nusselt number) to dimensionless fluid parameters (Reynolds, Prandtl, and Grashof numbers). The significant difference is that the experimental results in the  $f$ -chart development were hundreds of detailed main-frame computer simulations and were validated with a few year-long experiments. These design methods still have a place in today’s engineering practice. They are extremely fast and thus provide an inexpensive alternative to annual simulations, especially for small systems. Large (and therefore expensive) systems can afford to be looked at using detailed simulations. Some of the problems in these chapters compare the detailed simulations using TRNSYS with the various design methods.

Chapters 23 and 24 of Part III cover sizing of photovoltaic (PV) and wind energy systems. It is obvious that the solar radiation processing developed in Chapter 2 is very important in the design and analysis of PV systems. The detailed physics of a solar cell is complex, but it is not necessary to understand these details to design a PV system. The current-voltage ( $I$ - $V$ ) characteristics of cells are discussed in detail and a mathematical  $I$ - $V$  model is presented that is useful in design. Wind energy systems are introduced with a simple analysis that leads to understanding of manufacturers wind turbine characteristics. The performance of an isolated turbine is discussed, but interference of the wind patterns with close-packed multiple turbines is not discussed.

WILLIAM A. BECKMAN

*Madison, Wisconsin*

# Preface to the Third Edition

---

It has been 14 years since the second edition was published, but during that period the fundamentals of solar engineering have not changed significantly. So, why is a third edition needed? The best explanation is to realize that the details of all engineering disciplines grow in complexity with time and new ways of presenting complex material become apparent.

In Part I, Fundamentals, the first two chapters on the solar resource have received only modest updates. The sun's position has been well understood for centuries and so Chapter 1 has been updated by recasting some equations in simpler forms. The understanding and modeling of the influence of the earth's atmosphere on the radiation striking surfaces of arbitrary orientation have been active research areas for many years. Some of this work has been used to update Chapter 2. Chapter 3 now includes heat transfer relations needed for transpired solar collectors and heat transfer relations for low-pressure conditions encountered in linear concentrating collectors. Chapters 4 and 5 on properties of opaque and transparent surfaces have not changed significantly. Chapter 6 on flat-plate collectors now includes an analysis of transpired collectors. Collector testing is important but has not changed significantly. However, different countries express test results in different ways so a more thorough discussion of alternative presentations has been added. Compound parabolic concentrators (CPCs) receive a more extensive treatment in Chapter 7 along with the heat transfer analysis of linear concentrating collectors. Energy storage, the subject of Chapter 8, now includes a discussion of battery models. Chapters 9 and 10 on solar system models have not been significantly changed. Chapter 11 on economic analysis methods, the final chapter in Part I, now includes a discussion of solar savings fraction.

There have been thousands of new installations of a wide variety of solar applications since the last edition. Most of these installations have been successful in that the designer's goals were reached. However, lessons learned from earlier installations are generally applicable to new installations. Consequently, Part II, Chapters 12 through 18, on applications has only a few changes. For example, the Solar Electric Generating Systems (SEGS) discussion in Chapter 17 has been updated with new data. The impressive result is that the systems work better each year due to a better understanding of how to control and maintain them.

Since the publication of the previous edition Part III, Design Methods, has been reduced in importance due to the advances in simulation techniques and the availability of fast computers. But even with very fast computers the time to prepare a simulation may not be time well spent. There remains a need for fast design methods for small systems and for survey types of analysis; Chapters 19 through 22 provide the basis for satisfying these needs. There have been significant advances in the modeling of photovoltaic cells so that Chapter 23 has been extensively revised. Chapter 24 on wind energy has been added as wind (an indirect form of solar energy) has become a significant source of electrical power.

The senior/graduate-level engineering course on solar energy has been taught here at the University of Wisconsin at least once each year for the past 40 years. Earlier editions of this book were a major part of the course. The students delight in finding and pointing



out errors. It is not possible to write a book without introducing errors. It has been our experience that the errors approach zero but never reach zero. If errors are found, please forward them to us. In the past we have provided errata and will continue to provide one on the University of Wisconsin Solar Energy Laboratory website.

Professor John Atwater (Jack) Duffie passed away on April 23, 2005, shortly after his 80th birthday. The two of us started the process of updating this book on the day we received copies of the second edition in 1991. Work started in earnest late in 2001 when we converted the T/Maker's WriteNow version of the second edition into a Word version.

We must again acknowledge the help, inspiration, and forbearance of our colleagues and graduate students at the Solar Energy Laboratory of the University of Wisconsin-Madison. Also colleagues around the world have pointed out problem areas and offered constructive suggestions that have been incorporated into this edition.

WILLIAM A. BECKMAN

*Madison, Wisconsin*  
*October 2005*



# Preface to the Second Edition

---

In the ten years since we prepared the first edition there have been tremendous changes in solar energy science and technology. In the time between 1978 (when we made the last changes in the manuscript of the first edition) and 1991 (when the last changes were made for this edition) thousands of papers have been published, many meetings have been held with proceedings published, industries have come and gone, and public interest in the field has waxed, waned, and is waxing again.

There have been significant scientific and technological developments. We have better methods for calculating radiation on sloped surfaces and modeling stratified storage tanks. We have new methods for predicting the output of solar processes and new ideas on how solar heating systems can best be controlled. We have seen new large-scale applications of linear solar concentrators and salt-gradient ponds for power generation, widespread interest in and adoption of the principles of passive heating, development of low-flow liquid heating systems, and great advances in photovoltaic processes for conversion of solar to electrical energy.

Which of these many new developments belong in a second edition? This is a difficult problem, and from the great spread of new materials no two authors would elect to include the same items. For example, there have been many new models proposed for calculating radiation on sloped surfaces, given measurements on a horizontal surface. Which of these should be included? We have made choices; others might make different choices.

Those familiar with the first edition will note some significant changes. The most obvious is a reorganization of the material into three parts. Part I is on fundamentals, and covers essentially the same materials (with many additions) as the first eleven chapters in the first edition. Part II is on applications and is largely descriptive in nature. Part III is on design of systems, or more precisely on predicting long-term system thermal performance. This includes information on simulations, on  $f$ -chart, on utilizability methods applied to active and passive systems, and on the solar load ratio method developed at Los Alamos. This section ends with a chapter on photovoltaics and the application of utilizability methods to predicting PV system performance.

While the organization has changed, we have tried to retain enough of the flavor of the first edition to make those who have worked with it feel at home with this one. Where we have chosen to use new correlations, we have included those in the first edition in footnotes. The nomenclature is substantially the same. Many of the figures will be familiar, as will most of the equations. We hope that the transition to this edition will be an easy one.

We have been influenced by the academic atmosphere in which we work, but have also tried to stay in touch with the commercial and industrial world. (Our students who are now out in industry have been a big help to us.) We have taught a course to engineering students at least once each year and have had a steady stream of graduate students in our laboratory. Much of the new material we have included in this edition has been prepared as notes for use by these students, and the selection process has resulted from our assessment of what we thought these students should have. We have also been influenced by the research that

our students have done; it has resulted in ideas, developments and methods that have been accepted and used by many others in the field.

We have drawn on many sources for new materials, and have provided references as appropriate. In addition to the specific references, a number of general resources are worthy of note. *Advances in Solar Energy* is an annual edited by K. Böer and includes extensive reviews of various topics; volume 6 appeared in 1990. Two handbooks are available, the *Solar Energy Handbook* edited by Kreider and Kreith and the *Solar Energy Technology Handbook* edited by Dickenson and Cheremisinoff. Interesting new books have appeared, including Iqbal's *Introduction to Solar Radiation*, Rabl's *Active Solar Collectors and Their Applications*, and Hull, Nielsen, and Golding, *Salinity-Gradient Solar Ponds*. The Commission of the European Communities has published an informative series of books on many aspects of solar energy research and applications. There are several journals, including *Solar Energy*, published by the International Solar Energy Society, and the *Journal of Solar Energy Engineering*, published by the American Society of Mechanical Engineers. The June 1987 issue of *Solar Energy* is a cumulative subject and author index to the 2400 papers that have appeared in the first 39 volumes of the journal.

We have aimed this book at two audiences. It is intended to serve as a general source book and reference for those who are working in the field. The extensive bibliographies with each chapter will provide leads to more detailed exploration of topics that may be of special interest to the reader. The book is also intended to serve as a text for university-level engineering courses. There is material here for a two semester sequence, or by appropriate selection of sections it can readily be used for a one semester course. There is a wealth of new problems in Appendix A. A solutions manual is available that includes course outlines and suggestions for use of the book as a text.

We are indebted to students in our classes at Wisconsin and at Borlänge, Sweden who have used much of the text in note form. They have been critics of the best kind, always willing to tell us in constructive ways what is right and what is wrong with the materials. Heidi Burak and Craig Fieschko provided us with very useful critiques of the manuscript. Susan Pernsteiner helped us assemble the materials in useful form.

We prepared the text on Macintosh computers using T/Maker's WriteNow word processor, and set most of the equations with Prescience Company's Expressionist. The assistance of Peter Shank of T/Maker and of Allan Bonadio of Prescience is greatly appreciated. If these pages do not appear as attractive as they might, it should be attributed to our skills with these programs and not to the programs themselves.

Lynda Litzkow prepared the new art work for this edition using MacDraw II. Her assistance and competence have been very much appreciated. Port-to-Print, of Madison, prepared galleys using our disks. The cooperation of Jim Devine and Tracy Ripp of Port-to-Print has been very helpful.

We must again acknowledge the help, inspiration, and forbearance of our colleagues at the Solar Energy Laboratory. Without the support of S. A. Klein and J. W. Mitchell, the preparation of this work would have been much more difficult.

JOHN A. DUFFIE  
WILLIAM A. BECKMAN

Madison, Wisconsin  
June 1991

# Preface to the First Edition

---

When we started to revise our earlier book, *Solar Energy Thermal Processes*, it quickly became evident that the years since 1974 had brought many significant developments in our knowledge of solar processes. What started out to be a second edition of the 1974 book quickly grew into a new work, with new analysis and design tools, new insights into solar process operation, new industrial developments, and new ideas on how solar energy can be used. The result is a new book, substantially broader in scope and more detailed than the earlier one. Perhaps less than 20 percent of this book is taken directly from *Solar Energy Thermal Processes*, although many diagrams have been reused and the general outline of the work is similar. Our aim in preparing this volume has been to provide both a reference book and a text. Throughout it we have endeavored to present quantitative methods for estimated solar process performance.

In the first two chapters we treat solar radiation, radiation data, and the processing of the data to get it in forms needed for calculation of process performance. The next set of three chapters is a review of some heat transfer principles that are particularly useful and a treatment of the radiation properties of opaque and transparent materials. Chapters 6 through 9 go into detail on collectors and storage, as without an understanding of these essential components in a solar process system it is not possible to understand how systems operate. Chapters 10 and 11 are on system concepts and economics. They serve as an introduction to the balance of the book, which is concerned with applications and design methods.

Some of the topics we cover are very well established and well understood. Others are clearly matters of research, and the methods we have presented can be expected to be out dated and replaced by better methods. An example of this situation is found in Chapter 2; the methods for estimating the fractions of total radiation which are beam and diffuse are topics of current research, and procedures better than those we suggest will probably become available. In these situations we have included in the text extensive literature citations so the interested reader can easily go to the references for further background.

Collectors are at the heart of solar processes, and for those who are starting a study of solar energy without any previous background in the subject, we suggest reading Sections 6.1 and 6.2 for a general description of these unique heat transfer devices. The first half of the book is aimed entirely at development of the ability to calculate how collectors work, and a reading of the description will make clearer the reasons for the treatment of the first set of chapters.

Our emphasis is on solar applications to buildings, as they are the applications developing most rapidly and are the basis of a small but growing industry. The same ideas that are the basis of application to buildings also underlie applications to industrial process heat, thermal conversion to electrical energy generation and evaporative processes, which are all discussed briefly. Chapter 15 is a discussion of passive heating, and uses many of the same concepts and calculation methods for estimating solar gains that are developed and used in active heating systems. The principles are the same; the first half of the book

develops these principles, and the second half is concerned with their application to active, passive and nonbuilding processes.

New methods of simulation of transient processes have been developed in recent years, in our laboratory and in others. These are powerful tools in the development of understanding of solar processes and in their design, and in the chapters on applications the results of simulations studies are used to illustrate the sensitivity of long-term performance to design variables. Simulations are the basis of the design procedures described in Chapters 14 and 18. Experimental measurements of system performance are still scarce, but in several cases we have made comparisons of predicted and measured performance.

Since the future of solar applications depends on the costs of solar energy systems, we have included a discussion of life cycle economic analysis, and concluded it with a way of combining the many economics parameters in a life cycle saving analysis into just two numbers which can readily be used in system optimization studies. We find the method to be highly useful, but we make no claims for the worth of any of the numbers used in illustrating the method, and each user must pick his own economic parameters.

In order to make the book useful, we have wherever possible given useful relationships in equation, graphical, and tabular form. We have used the recommended standard nomenclature of the journal of *Solar Energy* (21, 69, 1978), except for a few cases where additional symbols have been needed for clarity. For example,  $G$  is used for irradiance (a rate,  $\text{W/m}^2$ ),  $H$  is used for irradiation for a day (an integrated quantity,  $\text{MJ/m}^2$ ), and  $I$  is used for irradiation for an hour ( $\text{MJ/m}^2$ ), which can be thought of as an average rate for an hour. A listing of nomenclature appears in Appendix B, and includes page references to discussions of the meaning of symbols where there might be confusion. SI units are used throughout, and Appendix C provides useful conversion tables.

Numerous sources have been used in writing this book. The journal *Solar Energy*, a publication of the International Solar Energy Society, is very useful, and contains a variety of papers on radiation data, collectors of various types, heating and cooling processes, and other topics. Publications of ASME and ASHRAE have provided additional sources. In addition to these journals, there exists a very large and growing body of literature in the form of reports to and by government agencies which are not reviewed in the usual sense but which contain useful information not readily available elsewhere. These materials are not as readily available as journals, but they are referenced where we have not found the material in journals. We also call the reader's attention to *Geliotechnika* (Applied Solar Energy), a journal published by the Academy of Sciences of the USSR which is available in English, and the *Revue Internationale d'Heliotechnique*, published by COMPLES in Marseille.

Many have contributed to the growing body of solar energy literature on which we have drawn. Here we note only a few of the most important of them. The work of H. C. Hottel and his colleagues at MIT and that of A. Whillier at MIT continue to be of basic importance. In space heating, the publications of G. O. G. Löf, S. Karaki and their colleagues at Colorado State University provide much of the quantitative information we have on that application.

Individuals who have helped us with the preparation of this book are many. Our graduate students and staff at the Solar Energy Laboratory have provided us with ideas, useful information and reviews of parts of the manuscript. Their constructive comments have been invaluable, and references to their work are included in the appropriate chapters.

The help of students in our course on Solar Energy Technology is also acknowledged; the number of errors in the manuscript is substantially lower as a result of their good-natured criticisms.

Critical reviews are imperative, and we are indebted to S. A. Klein for his reading of the manuscript. He has been a source of ideas, a sounding board for a wide variety of concepts, the author of many of the publications on which we have drawn, and a constructive critic of the best kind.

High on any list of acknowledgements for support of this work must be the College of Engineering and the Graduate School of the University of Wisconsin-Madison. The College has provided us with support while the manuscript was in preparation, and the Graduate School made it possible for each of us to spend a half year at the Division of Mechanical Engineering of the Commonwealth Scientific and Industrial Research Organization, Australia, where we made good use of their library and developed some of the concepts of this book. Our Laboratory at Wisconsin has been supported by the National Science Foundation, the Energy Research and Development Administration, and now the Department of Energy, and the research of the Laboratory has provided ideas for the book.

It is again appropriate to acknowledge the inspiration of the late Farrington Daniels. He kept interest in solar energy alive in the 1960s and so helped to prepare for the new activity in the field during the 1970s.

Generous permissions have been provided by many publishers and authors for the use of their tables, drawings and other materials in this book. The inclusion of these material made the book more complete and useful, and their cooperation is deeply appreciated.

A book such as this takes more than authors and critics to bring it into being. Typing and drafting help are essential and we are pleased to note the help of Shirley Quamme and her co-workers in preparing the manuscript. We have been through several drafts of the book which have been typed by our student helpers at the laboratory; it has often been difficult work, and their persistence, skill and good humor have been tremendous.


Not the least, we thank our patient families for their forbearance during the lengthy process of putting this book together.

JOHN A. DUFFIE  
WILLIAM A. BECKMAN

*Madison, Wisconsin*  
*June 1980*

# Introduction

CombiSys is a special version of the system simulation program TRNSYS (pronounced tran-sis and discussed in Chapter 19) and can be downloaded for free from the Wiley website (<http://www.wiley.com/go/solarengineering4e>). The early paragraphs of Appendix A (Problems) provide instructions for downloading, installing, and running TRNSYS on your Windows computer. This program simulates a solar “CombiSystem” that supplies heat for both a house heating system and a domestic hot-water system. A diagram of the energy flows in a solar CombiSystem is shown below.



The system has the following major components:

The *weather* data comes from the TMY2 data set (Second version of the U.S. Typical Meteorological Year) and consists of 329 built-in U.S. weather stations. Additional data can be added; Problem S2.2 is concerned with adding new data. The data consists of hourly ambient temperatures and hourly beam (directly from the sun) radiation and diffuse (scattered) radiation both incident on a horizontal surface (EHorSol). A radiation processor converts this horizontal data into incident radiation on the plane of the collectors (EIncSol).

The *collector* is either a flat-plate liquid heater with one glass cover, similar to those shown in Figures 6.1.1 and 6.3.1, or an evacuated tube collector, similar to those shown in Figures 6.13(d)–(f). The collectors are mounted on the building [in a manner similar to that in Figure 13.2.5(b) and (c)]. The total roof area suitable for collectors is 75 m<sup>2</sup>. The collectors can face from due east to due west at a slope between 0 and 90°. Collector data can be supplied in two ways: one of six built-in collectors can be chosen (three flat-plate and three evacuated tube collectors, with each set having low, average, and high-performance collectors). The second option is to provide all of the usual data supplied by the collector

manufacturer. The default values when entering the detailed solar collector parameters are identical to choosing the second collector from the list of six. There are two accepted standards for reporting collector parameters; reporting data based on the collector inlet temperature or on the average of the inlet and outlet temperatures. Conversion from one standard to the other is discussed in Section 6.19. Collector analysis is treated in great detail in Chapters 6 and 7.

The *collector heat exchanger* (CHX) isolates the antifreeze solution in the collector loop from the water storage tank loop. If no heat exchanger is present, then set the effectiveness equal to one.

The *solar storage tank* is an insulated water storage unit that is sized in proportion to the collector area. Typical values range from 30 to 100 liters/m<sup>2</sup>. The tank can be fully mixed or stratified (whereby the hottest solar-heated water migrates to the top of the tank).

The solar *domestic hot water* (DHW) subsystem consists of a heating coil (heat exchanger) located inside the main storage tank (not shown). Mains water is heated as it passes through this heat exchanger. If solar energy heats the domestic hot water above 45°C (as it probably will in the summer) then a bypass system (not shown) takes mains water and mixes it with the too-hot water to deliver water at 45°C. If insufficient solar energy is available, then the auxiliary energy supply maintains the delivered water at 45°C. This heater is of sufficient capacity that it can supply all of the domestic hot-water energy needs if necessary. The hot-water load depends upon the number of people (0 to 50) and can vary from 0 to 100 liters per person per day. The mains temperature is assumed to be constant throughout the year.

The solar *space heating* subsystem withdraws water from the top of the tank and circulates it through a water-to-air load heat exchanger (LHX) and returns it to the tank. If the water is hot enough to more than meet the entire house heating load, then the flow rate of the water is reduced to exactly meet the load. If there is insufficient solar energy available to meet the load, then the house heating auxiliary heater is turned on to meet the remainder of the load. The building overall loss coefficient (*UA*) includes infiltration. Details of how systems are controlled and related matters are discussed in later chapters.

The first thing to do in preparation for a detailed study of solar energy is to run Problem S0.1. Additional CombiSys problems are provided that can be run without any additional knowledge. It is hoped that these exercises will provide motivation for an in-depth study of solar energy.

The TRNSYS program is run from a front-end called TRNSED (pronounced Trans-ed), which accepts inputs in the form of check boxes, radio buttons, pull-down menus, and input boxes. The individual inputs along with the default parameter values (shown in square brackets) are listed and described below. The defaults for radio buttons are shown as filled circles.

#### Simulation Period

Month of the Simulation (Pulldown: January to December) [January]

Day of Month for Simulation Start (Number 1–31) [1]

Length of Simulation (Pulldown: one day to one year) [One-Year Simulation]

Simulation timestep (Pulldown: 1, 5, 10, 15, 30 or 60) [60 Minutes]



## Radiation Calculations

Radiation Data: Pulldown with two choices

- Use Total Horizontal and Beam Normal
- Use Total Horizontal only

Tilted Surface Radiation Mode: Pulldown with four choices

- Isotropic Sky Model (Equation 2.15.1)
- Hay and Davies Model (Equation 2.16.4)
- HDKR Model (Equation 2.16.7)
- Perez Model (Equation 2.16.14)

## Location

City name (Pulldown with 239 choices of TMY2 weather data) [CO: Pueblo]

Collector slope (Number 0–90) [ $60^\circ$ ]Collector azimuth (Number; facing equator =  $0^\circ$ , East =  $-90^\circ$ , West =  $+90^\circ$ ) [ $0^\circ$ ]

## Solar Collectors Parameter Options

- Select Solar Collector from a List  
Collector Type (Pulldown: 6 collectors to choose from) [Choose 2nd]  
Collector Total Area (Number 0–75) [ $30 \text{ m}^2$ ]  
Collector–Storage Tank Heat Exchanger Effectiveness (Number 0–1) [0.80]  
Collector Efficiency Equation (Pulldown: Equation 6.17.3 or 6.17.5) [6.17.3]
- Enter Detailed Solar Collector Parameters  
Collector Total Area (Number 0–75) [ $30 \text{ m}^2$ ]  
Intercept (maximum) Efficiency (Number 0–1) [0.80]  
First-Order Loss Coefficient (Number) [ $3.1235 \text{ W/m}^2 \text{ K}$ ]  
Second-Order Loss Coefficient (Number) [ $0.012 \text{ W/m}^2/\text{K}^2$ ]  
Incidence Angle Modifier (IAM) Coefficient  $b_o$  (Number) [0.20]  
Collector Flow Rate during Tests (Number > 0) [ $40 \text{ l/h m}^2$ ]  
Collector–Storage Heat Exchanger Effectiveness (Number 0–1) [0.8]  
Collector Flow Rate (Number > 0) [ $40 \text{ liters/h m}^2$ ]  
Collector Efficiency Equation (Pulldown: 6.17.3 or 6.17.5) [6.17.3]

## Number of Storage Tank Nodes

- 1 Node Storage Tank
- 3 Node Storage Tank
- 5 Node Storage Tank



### Tank Parameters

Tank Volume per Collector Area (Number 10–100) [75 liters/m<sup>2</sup>]

Tank Loss Coefficient (Number 0.10–5.0) [0.5 W/m<sup>2</sup> K]

Maximum Tank Temperature (Number 40–110) [100°C]

### Load Parameters

Two check boxes to select or unselect:

- Turn Solar Domestic Hot Water Load ON
- Turn Solar Space Heating Load ON

### Domestic Hot-Water Load

Average Hot-Water Draw per Occupant (Number 0–100) [60 liters/day]

Number of Occupants (Number 0–50) [5]

Mains Temperature (Number 0–40) [10°C]

### Space Heating Load

Overall House Heat Loss Coefficient (Number 0–500) [350 W/K]

Spacing Heating Setpoint (Number 15–25) [20°C]

### Online Plotter Options

Two check boxes to select or unselect:

- Plot Instantaneous values
- Plot Integrated Energy

## THE PROBLEM

Run the simulation program CombiSys in Pueblo, Colorado, for an entire year using the default parameter set. Perform an energy balance on the main solar tank for the entire year. (Energy in – Energy out – Energy Stored = Error) The error is due to numerical tolerances in solving the equations. Express the error as a percentage of the delivered solar energy,  $100 \times \text{Error} / (\text{Solar Energy in}) = \% \text{error}$ .

In addition, you can change several of the design parameters of the system. These include:

The collector area (which cannot exceed 75 m<sup>2</sup>).

Storage unit size normally varies in proportion to the collector area; ratios of 50, 75, and 100 liters/m<sup>2</sup> can be assumed.

The collector slope can conceivably vary between 30° and 75°.

You are to write a brief report that is intended to inform a group of contractors and architects about the performance of the system and the effects of changes in the design on

system performance. Use plots or diagrams to illustrate your results. To reduce the number of runs, you can investigate storage size only for the  $60^\circ$  slope. The usual performance figure is the solar fraction,  $\mathcal{F}$ , defined as the ratio of the solar contribution to the load divided by the load.

Estimate how much the home owner can afford to pay for the solar equipment if the auxiliary energy is (a) natural gas and (b) electricity.

There are many other design parameters that for this problem you cannot change or do not need to change. These include the heating load of the building and the characteristics of the collector. We will look at the impact of other design parameters during the semester.

## COMMENTS AND SUGGESTIONS

It is suggested that you first simulate the system using the default conditions. The computing time will be very small, and you can use this first simulation to become accustomed to the program and what it does.

Quantities like solar energy collected, energy lost from the tank, auxiliary energy, and various temperatures are computed as a function of time. Energy rates are integrated to give monthly energy quantities.

### Examining the On-Line Plots

You may manipulate the on-line plots in a variety of ways. The right mouse button will start and stop the simulation. After the simulation is complete select NO to the question “Exit on-line Plotter”. With the plot on the screen, click on the various plot identifiers at the top of the plot—the individual plots should disappear and reappear. Click and drag the mouse over part of the plot for a blow-up of a region. Click near the top or bottom on either the right- or left-hand axis numbers to change the scale. If the simulation is more than one page, you may move back and forth in time with the tabs at the bottom. There are two tabs at the bottom for looking at either instantaneous values or integrated values. When finished, go to menu item Calculations and choose Exit.

### Examining the Output

Once the simulation has completed and you have returned to TRNSED, you will find an output file, COMBISYS.OUT, under the Windows menu item at the top of the screen. The output is a text file that you can copy and paste into Excel. The values printed in the output file are as follows:

UTank: change in internal energy of the storage tank from the *start of each month*

ESol: the integrated energy transferred across the collector loop heat exchanger

EAux: integrated auxiliary energy added to the space to meet heating load requirements

ELossTank: the integrated energy loss from the tank (assumed to be in an unheated area of the house)

EMains: the integrated energy entering the tank with the water from the mains

EDHW: the integrated energy leaving the tank with the DHW

EHouse: integrated energy losses from the house

EIncSol: the integrated solar radiation incident on the collectors

EHorSol: the integrated solar radiation incident on a horizontal surface

Values are printed for each month. If the simulation ends within a month, a value will be printed for the completed portion of the last month. You will need to add up the monthly values to obtain yearly values. Copy the file and paste into Excel (or other spreadsheet program) to do your calculations. Annual information of this type, as will be seen later, is essential information in determining the economics of the application.

If you look at “View Simulation Results”, you will find a summary of the performance for the total time of the simulation.

# Part I

---

## FUNDAMENTALS

In Part I, we treat the basic ideas and calculation procedures that must be understood in order to appreciate how solar processes work and how their performance can be predicted. The first five chapters are basic to the material in Chapter 6. In Chapter 6 we develop equations for a collector which give the useful output in terms of the available solar radiation and the losses. An energy balance is developed which says, in essence, that the useful gain is the (positive) difference between the absorbed solar energy and the thermal losses.

The first chapter is concerned with the nature of the radiation emitted by the sun and incident on the earth's atmosphere. This includes geometric considerations, that is, the direction from which beam solar radiation is received and its angle of incidence on various surfaces and the quantity of radiation received over various time spans. The next chapter covers the effects of the atmosphere on the solar radiation, the radiation data that are available, and how those data can be processed to get the information that we ultimately want—the radiation incident on surfaces of various orientations.

Chapter 3 notes a set of heat transfer problems that arise in solar energy processes and is part of the basis for analysis of collectors, storage units, and other components.

The next two chapters treat interaction of radiation and opaque and transparent materials, that is, emission, absorption, reflection, and transmission of solar and long-wave radiation. These first five chapters lead to Chapter 6, a detailed discussion and analysis of the performance of flat-plate collectors. Chapter 7 is concerned with concentrating collectors and Chapter 8 with energy storage in various media. Chapter 9 is a brief discussion of the loads imposed on solar processes and the kinds of information that must be known in order to analyze the process.

Chapter 10 is the point at which the discussions of individual components are brought together to show how solar process *systems* function and how their long-term performance can be determined by simulations. The object is to be able to quantitatively predict system performance; this is the point at which we proceed from components to systems and see how transient system behavior can be calculated.

The last chapter in Part I is on solar process economics. It concludes with a method for combining the large number of economic parameters into two which can be used to optimize thermal design and assess the effects of uncertainties in an economic analysis.

# Solar Radiation

The sun's structure and characteristics determine the nature of the energy it radiates into space. The first major topic in this chapter concerns the characteristics of this energy outside the earth's atmosphere, its intensity, and its spectral distribution. We will be concerned primarily with radiation in a wavelength range of 0.25 to 3.0  $\mu\text{m}$ , the portion of the electromagnetic radiation that includes most of the energy radiated by the sun.

The second major topic in this chapter is solar geometry, that is, the position of the sun in the sky, the direction in which beam radiation is incident on surfaces of various orientations, and shading. The third topic is extraterrestrial radiation on a horizontal surface, which represents the theoretical upper limit of solar radiation available at the earth's surface.

An understanding of the nature of extraterrestrial radiation, the effects of orientation of a receiving surface, and the theoretically possible radiation at the earth's surface is important in understanding and using solar radiation data, the subject of Chapter 2.

## 1.1 THE SUN

The sun is a sphere of intensely hot gaseous matter with a diameter of  $1.39 \times 10^9$  m and is, on the average,  $1.5 \times 10^{11}$  m from the earth. As seen from the earth, the sun rotates on its axis about once every 4 weeks. However, it does not rotate as a solid body; the equator takes about 27 days and the polar regions take about 30 days for each rotation.

The sun has an effective blackbody temperature of 5777 K.<sup>1</sup> The temperature in the central interior regions is variously estimated at  $8 \times 10^6$  to  $40 \times 10^6$  K and the density is estimated to be about 100 times that of water. The sun is, in effect, a continuous fusion reactor with its constituent gases as the "containing vessel" retained by gravitational forces. Several fusion reactions have been suggested to supply the energy radiated by the sun. The one considered the most important is a process in which hydrogen (i.e., four protons) combines to form helium (i.e., one helium nucleus); the mass of the helium nucleus is less than that of the four protons, mass having been lost in the reaction and converted to energy.

The energy produced in the interior of the solar sphere at temperatures of many millions of degrees must be transferred out to the surface and then be radiated into


---

<sup>1</sup>The effective blackbody temperature of 5777 K is the temperature of a blackbody radiating the same amount of energy as does the sun. Other effective temperatures can be defined, e.g., that corresponding to the blackbody temperature giving the same wavelength of maximum radiation as solar radiation (about 6300 K).

space. A succession of radiative and convective processes occur with successive emission, absorption, and reradiation; the radiation in the sun's core is in the x-ray and gamma-ray parts of the spectrum, with the wavelengths of the radiation increasing as the temperature drops at larger radial distances.

A schematic structure of the sun is shown in Figure 1.1.1. It is estimated that 90% of the energy is generated in the region of 0 to  $0.23R$  (where  $R$  is the radius of the sun), which contains 40% of the mass of the sun. At a distance  $0.7R$  from the center, the temperature has dropped to about 130,000 K and the density has dropped to  $70 \text{ kg/m}^3$ ; here convection processes begin to become important, and the zone from  $0.7$  to  $1.0R$  is known as the **convective zone**. Within this zone the temperature drops to about 5000 K and the density to about  $10^{-5} \text{ kg/m}^3$ .

The sun's surface appears to be composed of granules (irregular convection cells), with dimensions from 1000 to 3000 km and with cell lifetime of a few minutes. Other features of the solar surface are small dark areas called pores, which are of the same order of magnitude as the convective cells, and larger dark areas called sunspots, which vary in size. The outer layer of the convective zone is called the **photosphere**. The edge of the photosphere is sharply defined, even though it is of low density (about  $10^{-4}$  that of air at sea level). It is essentially opaque, as the gases of which it is composed are strongly



**Figure 1.1.1** The structure of the sun.

ionized and able to absorb and emit a continuous spectrum of radiation. The photosphere is the source of most solar radiation.

Outside the photosphere is a more or less transparent solar atmosphere, observable during total solar eclipse or by instruments that occult the solar disk. Above the photosphere is a layer of cooler gases several hundred kilometers deep called the **reversing layer**. Outside of that is a layer referred to as the **chromosphere**, with a depth of about 10,000 km. This is a gaseous layer with temperatures somewhat higher than that of the photosphere but with lower density. Still further out is the **corona**, a region of very low density and of very high ( $10^6$  K) temperature. For further information on the sun's structure see Thomas (1958) or Robinson (1966).

This simplified picture of the sun, its physical structure, and its temperature and density gradients will serve as a basis for appreciating that the sun does not, in fact, function as a blackbody radiator at a fixed temperature. Rather, the emitted solar radiation is the composite result of the several layers that emit and absorb radiation of various wavelengths. The resulting extraterrestrial solar radiation and its spectral distribution have now been measured by various methods in several experiments; the results are noted in the following two sections.

## 1.2 THE SOLAR CONSTANT

Figure 1.2.1 shows schematically the geometry of the sun-earth relationships. The eccentricity of the earth's orbit is such that the distance between the sun and the earth varies by 1.7%. At a distance of one astronomical unit,  $1.495 \times 10^{11}$  m, the mean earth-sun distance, the sun subtends an angle of  $32'$ . The radiation emitted by the sun and its spatial relationship to the earth result in a nearly fixed intensity of solar radiation outside of the earth's atmosphere. The **solar constant**  $G_{sc}$  is the energy from the sun per unit time received on a unit area of surface perpendicular to the direction of propagation of the radiation at mean earth-sun distance outside the atmosphere.

Before rockets and spacecraft, estimates of the solar constant had to be made from ground-based measurements of solar radiation after it had been transmitted through the




Figure 1.2.1 Sun-earth relationships.

atmosphere and thus in part absorbed and scattered by components of the atmosphere. Extrapolations from the terrestrial measurements made from high mountains were based on estimates of atmospheric transmission in various portions of the solar spectrum. Pioneering studies were done by C. G. Abbot and his colleagues at the Smithsonian Institution. These studies and later measurements from rockets were summarized by Johnson (1954); Abbot's value of the solar constant of  $1322 \text{ W/m}^2$  was revised upward by Johnson to  $1395 \text{ W/m}^2$ .

The availability of very high altitude aircraft, balloons, and spacecraft has permitted direct measurements of solar radiation outside most or all of the earth's atmosphere. These measurements were made with a variety of instruments in nine separate experimental programs. They resulted in a value of the solar constant  $G_{sc}$  of  $1353 \text{ W/m}^2$  with an estimated error of  $\pm 1.5\%$ . For discussions of these experiments, see Thekaekara (1976) or Thekaekara and Drummond (1971). This standard value was accepted by NASA (1971) and by the American Society of Testing and Materials (2006).

The data on which the  $1353\text{-W/m}^2$  value was based have been reexamined by Frohlich (1977) and reduced to a new pyrheliometric scale<sup>2</sup> based on comparisons of the instruments with absolute radiometers. Data from *Nimbus* and *Mariner* satellites have also been included in the analysis, and as of 1978, Frohlich recommends a new value of the solar constant  $G_{sc}$  of  $1373 \text{ W/m}^2$ , with a probable error of 1 to 2%. This was 1.5% higher than the earlier value and 1.2% higher than the best available determination of the solar constant by integration of spectral measurements. Additional spacecraft measurements have been made with Hickey et al. (1982) reporting  $1373 \text{ W/m}^2$  and Willson et al. (1981) reporting  $1368 \text{ W/m}^2$ . Measurements from three rocket flights reported by Duncan et al. (1982) were  $1367$ ,  $1372$ , and  $1374 \text{ W/m}^2$ . The World Radiation Center (WRC) has adopted a value of  $1367 \text{ W/m}^2$ , with an uncertainty of the order of 1%. As will be seen in Chapter 2, uncertainties in most terrestrial solar radiation measurements are an order of magnitude larger than those in  $G_{sc}$ . A value of  $G_{sc}$  of  $1367 \text{ W/m}^2$  ( $1.960 \text{ cal/cm}^2 \text{ min}$ ,  $433 \text{ Btu/ft}^2 \text{ h}$ , or  $4.921 \text{ MJ/m}^2 \text{ h}$ ) is used in this book. [See Iqbal (1983) for more detailed information on the solar constant.]


### 1.3 SPECTRAL DISTRIBUTION OF EXTRATERRESTRIAL RADIATION

In addition to the total energy in the solar spectrum (i.e., the solar constant), it is useful to know the spectral distribution of the extraterrestrial radiation, that is, the radiation that would be received in the absence of the atmosphere. A standard spectral irradiance curve has been compiled based on high-altitude and space measurements. The WRC standard is shown in Figure 1.3.1. Table 1.3.1 provides the same information on the WRC spectrum in numerical form. The average energy  $G_{sc,\lambda}$  (in  $\text{W/m}^2 \mu\text{m}$ ) over small bandwidths centered at wavelength  $\lambda$  is given in the second column. The fraction  $f_{0-\lambda}$  of the total energy in the spectrum that is between wavelengths zero and  $\lambda$  is given in the third column. The table is in two parts, the first at regular intervals of wavelength and the second at even fractions  $f_{0-\lambda}$ . This is a condensed table; more detailed tables are available elsewhere (see Iqbal, 1983).

---

<sup>2</sup>Pyrheliometric scales are discussed in Section 2.2.





**Figure 1.3.1** The WRC standard spectral irradiance curve at mean earth-sun distance.

**Table 1.3.1a** Extraterrestrial Solar Irradiance (WRC Spectrum) in Increments of Wavelength<sup>a</sup>

$\lambda$ ( $\mu\text{m}$ )	$G_{sc,\lambda}$ ( $\text{W}/\text{m}^2 \mu\text{m}$ )	$f_{0-\lambda}$ (—)	$\lambda$ ( $\mu\text{m}$ )	$G_{sc,\lambda}$ ( $\text{W}/\text{m}^2 \mu\text{m}$ )	$f_{0-\lambda}$ (—)	$\lambda$ ( $\mu\text{m}$ )	$G_{sc,\lambda}$ ( $\text{W}/\text{m}^2 \mu\text{m}$ )	$f_{0-\lambda}$ (—)
0.250	81.2	0.001	0.520	1849.7	0.243	0.880	955.0	0.622
0.275	265.0	0.004	0.530	1882.8	0.257	0.900	908.9	0.636
0.300	499.4	0.011	0.540	1877.8	0.271	0.920	847.5	0.648
0.325	760.2	0.023	0.550	1860.0	0.284	0.940	799.8	0.660
0.340	955.5	0.033	0.560	1847.5	0.298	0.960	771.1	0.672
0.350	955.6	0.040	0.570	1842.5	0.312	0.980	799.1	0.683
0.360	1053.1	0.047	0.580	1826.9	0.325	1.000	753.2	0.695
0.370	1116.2	0.056	0.590	1797.5	0.338	1.050	672.4	0.721
0.380	1051.6	0.064	0.600	1748.8	0.351	1.100	574.9	0.744
0.390	1077.5	0.071	0.620	1738.8	0.377	1.200	507.5	0.785
0.400	1422.8	0.080	0.640	1658.7	0.402	1.300	427.5	0.819
0.410	1710.0	0.092	0.660	1550.0	0.425	1.400	355.0	0.847
0.420	1687.2	0.105	0.680	1490.2	0.448	1.500	297.8	0.871
0.430	1667.5	0.116	0.700	1413.8	0.469	1.600	231.7	0.891
0.440	1825.0	0.129	0.720	1348.6	0.489	1.800	173.8	0.921
0.450	1992.8	0.143	0.740	1292.7	0.508	2.000	91.6	0.942
0.460	2022.8	0.158	0.760	1235.0	0.527	2.500	54.3	0.968
0.470	2015.0	0.173	0.780	1182.3	0.544	3.000	26.5	0.981
0.480	1975.6	0.188	0.800	1133.6	0.561	3.500	15.0	0.988
0.490	1940.6	0.202	0.820	1085.0	0.578	4.000	7.7	0.992
0.500	1932.2	0.216	0.840	1027.7	0.593	5.000	2.5	0.996
0.510	1869.1	0.230	0.860	980.0	0.608	8.000	1.0	0.999

<sup>a</sup> $G_{sc,\lambda}$  is the average solar irradiance over the interval from the middle of the preceding wavelength interval to the middle of the following wavelength interval. For example, at  $0.600 \mu\text{m}$ ,  $1748.8 \text{ W}/\text{m}^2 \mu\text{m}$  is the average value between  $0.595$  and  $0.610 \mu\text{m}$ .

**Table 1.3.1b** Extraterrestrial Solar Irradiance in Equal Increments of Energy

Energy Band $f_i - f_{i+1}$ (—)	Wavelength Range ( $\mu\text{m}$ )	Midpoint Wavelength ( $\mu\text{m}$ )	Energy Band $f_i - f_{i+1}$ (—)	Wavelength Range ( $\mu\text{m}$ )	Midpoint Wavelength ( $\mu\text{m}$ )
0.00–0.05	0.250–0.364	0.328	0.50–0.55	0.731–0.787	0.758
0.05–0.10	0.364–0.416	0.395	0.55–0.60	0.787–0.849	0.817
0.10–0.15	0.416–0.455	0.437	0.60–0.65	0.849–0.923	0.885
0.15–0.20	0.455–0.489	0.472	0.65–0.70	0.923–1.008	0.966
0.20–0.25	0.489–0.525	0.506	0.70–0.75	1.008–1.113	1.057
0.25–0.30	0.525–0.561	0.543	0.75–0.80	1.113–1.244	1.174
0.30–0.35	0.561–0.599	0.580	0.80–0.85	1.244–1.412	1.320
0.35–0.40	0.599–0.638	0.619	0.85–0.90	1.412–1.654	1.520
0.40–0.45	0.638–0.682	0.660	0.90–0.95	1.654–2.117	1.835
0.45–0.50	0.682–0.731	0.706	0.95–1.00	2.117–10.08	2.727

**Example 1.3.1**

Calculate the fraction of the extraterrestrial solar radiation and the amount of that radiation in the ultraviolet ( $\lambda < 0.38 \mu\text{m}$ ), the visible ( $0.38 \mu\text{m} < \lambda < 0.78 \mu\text{m}$ ), and the infrared ( $\lambda > 0.78 \mu\text{m}$ ) portions of the spectrum.


**Solution**

From Table 1.3.1a, the fractions of  $f_{0-\lambda}$  corresponding to wavelengths of 0.38 and 0.78  $\mu\text{m}$  are 0.064 and 0.544. Thus, the fraction in the ultraviolet is 0.064, the fraction in the visible range is  $0.544 - 0.064 = 0.480$ , and the fraction in the infrared is  $1.0 - 0.544 = 0.456$ . Applying these fractions to a solar constant of  $1367 \text{ W/m}^2$  and tabulating the results, we have:

Wavelength range ( $\mu\text{m}$ )	0–0.38	0.38–0.78	0.78– $\infty$
Fraction in range	0.064	0.480	0.456
Energy in range ( $\text{W/m}^2$ )	87	656	623

**1.4 VARIATION OF EXTRATERRESTRIAL RADIATION**

Two sources of variation in extraterrestrial radiation must be considered. The first is the variation in the radiation emitted by the sun. There are conflicting reports in the literature on periodic variations of intrinsic solar radiation. It has been suggested that there are small variations (less than  $\pm 1.5\%$ ) with different periodicities and variation related to sunspot activities. Willson et al. (1981) report variances of up to 0.2% correlated with the development of sunspots. Others consider the measurements to be inconclusive or not indicative of regular variability. Measurements from *Nimbus* and *Mariner* satellites over periods of several months showed variations within limits of  $\pm 0.2\%$  over a time when



**Figure 1.4.1** Variation of extraterrestrial solar radiation with time of year.

sunspot activity was very low (Frohlich, 1977). Data of Hickey et al. (1982) over a span of 2.5 years from the *Nimbus 7* satellite suggest that the solar constant is decreasing slowly, at a rate of approximately 0.02% per year. See Coulson (1975) or Thekaekara (1976) for further discussion of this topic. For engineering purposes, in view of the uncertainties and variability of atmospheric transmission, the energy emitted by the sun can be considered to be fixed.

Variation of the earth-sun distance, however, does lead to variation of extraterrestrial radiation flux in the range of  $\pm 3.3\%$ . The dependence of extraterrestrial radiation on time of year is shown in Figure 1.4.1. A simple equation with accuracy adequate for most engineering calculations is given by Equation 1.4.1a. Spencer (1971), as cited by Iqbal (1983), provides a more accurate equation ( $\pm 0.01\%$ ) in the form of Equation 1.4.1b:

$$G_{on} = \begin{cases} G_{sc} \left( 1 + 0.033 \cos \frac{360n}{365} \right) & (1.4.1a) \\ G_{sc} (1.000110 + 0.034221 \cos B + 0.001280 \sin B \\ \quad + 0.000719 \cos 2B + 0.000077 \sin 2B) & (1.4.1b) \end{cases}$$

where  $G_{on}$  is the extraterrestrial radiation incident on the plane normal to the radiation on the  $n$ th day of the year and  $B$  is given by

$$B = (n - 1) \frac{360}{365} \quad (1.4.2)$$

## 1.5 DEFINITIONS

Several definitions will be useful in understanding the balance of this chapter.

**Air Mass  $m$**  The ratio of the mass of atmosphere through which beam radiation passes to the mass it would pass through if the sun were at the zenith (i.e., directly

overhead, see Section 1.6). Thus at sea level  $m = 1$  when the sun is at the zenith and  $m = 2$  for a zenith angle  $\theta_z$  of  $60^\circ$ . For zenith angles from  $0^\circ$  to  $70^\circ$  at sea level, to a close approximation,

$$m = \frac{1}{\cos \theta_z} \quad (1.5.1)$$

For higher zenith angles, the effect of the earth's curvature becomes significant and must be taken into account.<sup>3</sup> For a more complete discussion of air mass, see Robinson (1966), Kondratyev (1969), or Garg (1982).

**Beam Radiation** The solar radiation received from the sun without having been scattered by the atmosphere. (Beam radiation is often referred to as direct solar radiation; to avoid confusion between subscripts for direct and diffuse, we use the term beam radiation.)

**Diffuse Radiation** The solar radiation received from the sun after its direction has been changed by scattering by the atmosphere. (Diffuse radiation is referred to in some meteorological literature as sky radiation or solar sky radiation; the definition used here will distinguish the diffuse solar radiation from infrared radiation emitted by the atmosphere.)

**Total Solar Radiation** The sum of the beam and the diffuse solar radiation on a surface.<sup>4</sup> (The most common measurements of solar radiation are total radiation on a horizontal surface, often referred to as **global radiation** on the surface.)

**Irradiance**,  $\text{W/m}^2$  The rate at which radiant energy is incident on a surface per unit area of surface. The symbol  $G$  is used for solar irradiance, with appropriate subscripts for beam, diffuse, or spectral radiation.

**Irradiation or Radiant Exposure**,  $\text{J/m}^2$  The incident energy per unit area on a surface, found by integration of irradiance over a specified time, usually an hour or a day. **Insolation** is a term applying specifically to solar energy irradiation. The symbol  $H$  is used for insolation for a day. The symbol  $I$  is used for insolation for an hour (or other period if specified). The symbols  $H$  and  $I$  can represent beam, diffuse, or total and can be on surfaces of any orientation.

Subscripts on  $G$ ,  $H$ , and  $I$  are as follows:  $o$  refers to radiation above the earth's atmosphere, referred to as extraterrestrial radiation;  $b$  and  $d$  refer to beam and diffuse radiation;  $T$  and  $n$  refer to radiation on a tilted plane and on a plane normal to the direction of propagation. If neither  $T$  nor  $n$  appears, the radiation is on a horizontal plane.

**Radiosity or Radiant Exitance**,  $\text{W/m}^2$  The rate at which radiant energy leaves a surface per unit area by combined emission, reflection, and transmission.

**Emissive Power or Radiant Self-Exitance**,  $\text{W/m}^2$  The rate at which radiant energy leaves a surface per unit area by emission only.

---

<sup>3</sup>An empirical relationship from Kasten and Young (1989) for air mass that works for zenith angles approaching  $90^\circ$  is

$$m = \frac{\exp(-0.0001184h)}{\cos(\theta_z) + 0.5057(96.080 - \theta_z)^{-1.634}}$$

where  $h$  is the site altitude in meters.

<sup>4</sup>Total solar radiation is sometimes used to indicate quantities integrated over all wavelengths of the solar spectrum.

Any of these radiation terms, except insolation, can apply to any specified wave-length range (such as the solar energy spectrum) or to monochromatic radiation. Insolation refers only to irradiation in the solar energy spectrum.

**Solar Time** Time based on the apparent angular motion of the sun across the sky with solar noon the time the sun crosses the meridian of the observer.

Solar time is the time used in all of the sun-angle relationships; it does not coincide with local clock time. It is necessary to convert standard time to solar time by applying two corrections. First, there is a constant correction for the difference in longitude between the observer's meridian (longitude) and the meridian on which the local standard time is based.<sup>5</sup> The sun takes 4 min to transverse  $1^\circ$  of longitude. The second correction is from the equation of time, which takes into account the perturbations in the earth's rate of rotation which affect the time the sun crosses the observer's meridian. The difference in minutes between solar time and standard time is

$$\text{Solar time} - \text{standard time} = 4(L_{\text{st}} - L_{\text{loc}}) + E \quad (1.5.2)$$

where  $L_{\text{st}}$  is the standard meridian for the local time zone,  $L_{\text{loc}}$  is the longitude of the location in question, and longitudes are in degrees west, that is,  $0^\circ < L < 360^\circ$ . The parameter  $E$  is the equation of time (in minutes) from Figure 1.5.1 or Equation 1.5.3<sup>6</sup> [from Spencer (1971), as cited by Iqbal (1983)]:

$$E = 229.2(0.000075 + 0.001868 \cos B - 0.032077 \sin B - 0.014615 \cos 2B - 0.04089 \sin 2B) \quad (1.5.3)$$

where  $B$  is found from Equation 1.4.2 and  $n$  is the day of the year. Thus  $1 \leq n \leq 365$ .

Note that the equation of time and displacement from the standard meridian are both in minutes and that there is a 60-min difference between daylight saving time and standard time. Time is usually specified in hours and minutes. Care must be exercised in applying the corrections, which can total more than 60 min.

### Example 1.5.1

At Madison, Wisconsin, what is the solar time corresponding to 10:30 AM central time on February 3?


#### Solution

In Madison, where the longitude is  $89.4^\circ$  and the standard meridian is  $90^\circ$ , Equation 1.5.2 gives

$$\begin{aligned} \text{Solar time} &= \text{standard time} + 4(90 - 89.4) + E \\ &= \text{standard time} + 2.4 + E \end{aligned}$$

<sup>5</sup>To find the local standard meridian, multiply the time difference between local standard clock time and Greenwich Mean Time by 15.

<sup>6</sup>All equations use degrees, not radians.



**Figure 1.5.1** The equation of time  $E$  in minutes as a function of time of year.


On February 3,  $n = 34$ , and from Equation 1.5.3 or Figure 1.5.1,  $E = -13.5$  min, so the correction to standard time is  $-11$  min. Thus 10:30 AM Central Standard Time is 10:19 AM solar time. ■

In this book time is assumed to be solar time unless indication is given otherwise.

## 1.6 DIRECTION OF BEAM RADIATION

The geometric relationships between a plane of any particular orientation relative to the earth at any time (whether that plane is fixed or moving relative to the earth) and the incoming beam solar radiation, that is, the position of the sun relative to that plane, can be described in terms of several angles (Benford and Bock, 1939). Some of the angles are indicated in Figure 1.6.1. The angles and a set of consistent sign conventions are as follows:

- $\phi$  **Latitude**, the angular location north or south of the equator, north positive;  $-90^\circ \leq \phi \leq 90^\circ$ .
- $\delta$  **Declination**, the angular position of the sun at solar noon (i.e., when the sun is on the local meridian) with respect to the plane of the equator, north positive;  $-23.45^\circ \leq \delta \leq 23.45^\circ$ .
- $\beta$  **Slope**, the angle between the plane of the surface in question and the horizontal;  $0^\circ \leq \beta \leq 180^\circ$ . ( $\beta > 90^\circ$  means that the surface has a downward-facing component.)



**Figure 1.6.1** (a) Zenith angle, slope, surface azimuth angle, and solar azimuth angle for a tilted surface. (b) Plan view showing solar azimuth angle.

- $\gamma$  **Surface azimuth angle**, the deviation of the projection on a horizontal plane of the normal to the surface from the local meridian, with zero due south, east negative, and west positive;  $-180^\circ \leq \gamma \leq 180^\circ$ .
- $\omega$  **Hour angle**, the angular displacement of the sun east or west of the local meridian due to rotation of the earth on its axis at  $15^\circ$  per hour; morning negative, afternoon positive.
- $\theta$  **Angle of incidence**, the angle between the beam radiation on a surface and the normal to that surface.

Additional angles are defined that describe the position of the sun in the sky:

- $\theta_z$  **Zenith angle**, the angle between the vertical and the line to the sun, that is, the angle of incidence of beam radiation on a horizontal surface.
- $\alpha_s$  **Solar altitude angle**, the angle between the horizontal and the line to the sun, that is, the complement of the zenith angle.
- $\gamma_s$  **Solar azimuth angle**, the angular displacement from south of the projection of beam radiation on the horizontal plane, shown in Figure 1.6.1. Displacements east of south are negative and west of south are positive.

The declination  $\delta$  can be found from the approximate equation of Cooper (1969),

$$\delta = 23.45 \sin \left( 360 \frac{284 + n}{365} \right) \quad (1.6.1a)$$

**Table 1.6.1** Recommended Average Days for Months and Values of  $n$  by Months<sup>a</sup>

Month	$n$ for $i$ th Day of Month	For Average Day of Month		
		Date	$n$	$\delta$
January	$i$	17	17	−20.9
February	$31 + i$	16	47	−13.0
March	$59 + i$	16	75	−2.4
April	$90 + i$	15	105	9.4
May	$120 + i$	15	135	18.8
June	$151 + i$	11	162	23.1
July	$181 + i$	17	198	21.2
August	$212 + i$	16	228	13.5
September	$243 + i$	15	258	2.2
October	$273 + i$	15	288	−9.6
November	$304 + i$	14	318	−18.9
December	$334 + i$	10	344	−23.0

<sup>a</sup>From Klein (1977). Do not use for  $|\phi| > 66.5^\circ$ .

or from the more accurate equation (error  $< 0.035^\circ$ ) [from Spencer (1971), as cited by Iqbal (1983)]

$$\begin{aligned}\delta = (180/\pi)(0.006918 - 0.399912 \cos B + 0.070257 \sin B \\ - 0.006758 \cos 2B + 0.000907 \sin 2B \\ - 0.002697 \cos 3B + 0.00148 \sin 3B)\end{aligned}\quad (1.6.1b)$$

where  $B$  is from Equation 1.4.2 and the day of the year  $n$  can be conveniently obtained with the help of Table 1.6.1.

Variation in sun-earth distance (as noted in Section 1.4), the equation of time  $E$  (as noted in Section 1.5), and declination are all continuously varying functions of time of year. For many computational purposes it is customary to express the time of year in terms of  $n$ , the day of the year, and thus as an integer between 1 and 365. Equations 1.4.1, 1.5.3, and 1.6.1 could be used with noninteger values of  $n$ . Note that the maximum rate of change of declination is about  $0.4^\circ$  per day. The use of integer values of  $n$  is adequate for most engineering calculations outlined in this book.

There is a set of useful relationships among these angles. Equations relating the angle of incidence of beam radiation on a surface,  $\theta$ , to the other angles are

$$\begin{aligned}\cos \theta = \sin \delta \sin \phi \cos \beta - \sin \delta \cos \phi \sin \beta \cos \gamma \\ + \cos \delta \cos \phi \cos \beta \cos \omega + \cos \delta \sin \phi \sin \beta \cos \gamma \cos \omega \\ + \cos \delta \sin \beta \sin \gamma \sin \omega\end{aligned}\quad (1.6.2)$$

and

$$\cos \theta = \cos \theta_z \cos \beta + \sin \theta_z \sin \beta \cos(\gamma_s - \gamma) \quad (1.6.3)$$

The angle  $\theta$  may exceed  $90^\circ$ , which means that the sun is behind the surface. Also, when using Equation 1.6.2, it is necessary to ensure that the earth is not blocking the sun (i.e., that the hour angle is between sunrise and sunset).



**Example 1.6.1**

Calculate the angle of incidence of beam radiation on a surface located at Madison, Wisconsin, at 10:30 (solar time) on February 13 if the surface is tilted  $45^\circ$  from the horizontal and pointed  $15^\circ$  west of south.

**Solution**

Under these conditions,  $n = 44$ , the declination  $\delta$  from Equation 1.6.1 is  $-14^\circ$ , the hour angle  $\omega = -22.5^\circ$  ( $15^\circ$  per hour times 1.5 h before noon), and the surface azimuth angle  $\gamma = 15^\circ$ . Using a slope  $\beta = 45^\circ$  and the latitude  $\phi$  of Madison of  $43^\circ$  N, Equation 1.6.2 is

$$\begin{aligned}\cos \theta &= \sin(-14) \sin 43 \cos 45 - \sin(-14) \cos 43 \sin 45 \cos 15 \\ &\quad + \cos(-14) \cos 43 \cos 45 \cos(-22.5) \\ &\quad + \cos(-14) \sin 43 \sin 45 \cos 15 \cos(-22.5) \\ &\quad + \cos(-14) \sin 45 \sin 15 \sin(-22.5) \\ \cos \theta &= -0.117 + 0.121 + 0.464 + 0.418 - 0.068 = 0.817 \\ \theta &= 35^\circ\end{aligned}$$

There are several commonly occurring cases for which Equation 1.6.2 is simplified. For fixed surfaces sloped toward the south or north, that is, with a surface azimuth angle  $\gamma$  of  $0^\circ$  or  $180^\circ$  (a very common situation for fixed flat-plate collectors), the last term drops out.

For vertical surfaces,  $\beta = 90^\circ$  and the equation becomes

$$\cos \theta = -\sin \delta \cos \phi \cos \gamma + \cos \delta \sin \phi \cos \gamma \cos \omega + \cos \delta \sin \gamma \sin \omega \quad (1.6.4)$$

For horizontal surfaces, the angle of incidence is the zenith angle of the sun,  $\theta_z$ . Its value must be between  $0^\circ$  and  $90^\circ$  when the sun is above the horizon. For this situation,  $\beta = 0$ , and Equation 1.6.2 becomes

$$\cos \theta_z = \cos \phi \cos \delta \cos \omega + \sin \phi \sin \delta \quad (1.6.5)$$

The solar azimuth angle  $\gamma_s$  can have values in the range of  $180^\circ$  to  $-180^\circ$ . For north or south latitudes between  $23.45^\circ$  and  $66.45^\circ$ ,  $\gamma_s$  will be between  $90^\circ$  and  $-90^\circ$  for days less than 12 h long; for days with more than 12 h between sunrise and sunset,  $\gamma_s$  will be greater than  $90^\circ$  or less than  $-90^\circ$  early and late in the day when the sun is north of the east-west line in the northern hemisphere or south of the east-west line in the southern hemisphere. For tropical latitudes,  $\gamma_s$  can have any value when  $\delta - \phi$  is positive in the northern hemisphere or negative in the southern, for example, just before noon at  $\phi = 10^\circ$  and  $\delta = 20^\circ$ ,  $\gamma_s = -180^\circ$ , and just after noon  $\gamma_s = +180^\circ$ . Thus  $\gamma_s$  is negative when the hour angle is negative and positive when the hour angle is positive. The sign function in Equations 1.6.6 is equal to  $+1$  if  $\omega$  is positive and is equal to  $-1$  if  $\omega$  is negative:

$$\gamma_s = \text{sign}(\omega) \left| \cos^{-1} \left( \frac{\cos \theta_z \sin \phi - \sin \delta}{\sin \theta_z \cos \phi} \right) \right| \quad (1.6.6)$$

**Example 1.6.2**

Calculate the zenith and solar azimuth angles for  $\phi = 43^\circ$  at **a** 9:30 AM on February 13 and **b** 6:30 PM on July 1.

**Solution**

**a** On February 13 at 9:30,  $\delta = -14^\circ$  and  $\omega = -37.5^\circ$ . From Equation 1.6.5,

$$\begin{aligned}\cos \theta_z &= \cos 43 \cos(-14) \cos(-37.5) + \sin 43 \sin(-14) = 0.398 \\ \theta_z &= 66.5^\circ\end{aligned}$$

From Equation 1.6.6


$$\gamma_s = -1 \left| \cos^{-1} \left( \frac{\cos 66.5 \sin 43 - \sin(-14)}{\sin 66.5 \cos 43} \right) \right| = -40.0^\circ$$

**b** On July 1 at 6:30 PM,  $n = 182$ ,  $\delta = 23.1^\circ$ , and  $\omega = 97.5^\circ$ . From Equation 1.6.5,

$$\begin{aligned}\cos \theta_z &= \cos 43 \cos 23.1 \cos 97.5 + \sin 43 \sin 23.1 \\ \theta_z &= 79.6^\circ \\ \gamma_s &= +1 \left| \cos^{-1} \left( \frac{\cos 79.6 \sin 43 - \sin 23.1}{\sin 79.6 \cos 43} \right) \right| = 112.0^\circ\end{aligned}$$

Useful relationships for the angle of incidence of surfaces sloped due north or due south can be derived from the fact that surfaces with slope  $\beta$  to the north or south have the same angular relationship to beam radiation as a horizontal surface at an artificial latitude of  $\phi - \beta$ . The relationship is shown in Figure 1.6.2 for the northern hemisphere. Modifying Equation 1.6.5 yields

$$\cos \theta = \cos(\phi - \beta) \cos \delta \cos \omega + \sin(\phi - \beta) \sin \delta \quad (1.6.7a)$$



**Figure 1.6.2** Section of earth showing  $\beta$ ,  $\theta$ ,  $\phi$ , and  $\phi - \beta$  for a south-facing surface.

For the southern hemisphere modify the equation by replacing  $\phi - \beta$  by  $\phi + \beta$ , consistent with the sign conventions on  $\phi$  and  $\delta$ :

$$\cos \theta = \cos(\phi + \beta) \cos \delta \cos \omega + \sin(\phi + \beta) \sin \delta \quad (1.6.7b)$$

For the special case of solar noon, for the south-facing sloped surface in the northern hemisphere,

$$\theta_{\text{noon}} = |\phi - \delta - \beta| \quad (1.6.8a)$$

and in the southern hemisphere

$$\theta_{\text{noon}} = |-\phi + \delta - \beta| \quad (1.6.8b)$$

where  $\beta = 0$ , the angle of incidence is the zenith angle, which for the northern hemisphere is

$$\theta_{z,\text{noon}} = |\phi - \delta| \quad (1.6.9a)$$

and for the southern hemisphere

$$\theta_{z,\text{noon}} = |-\phi + \delta| \quad (1.6.9b)$$

Equation 1.6.5 can be solved for the **sunset hour angle**  $\omega_s$ , when  $\theta_z = 90^\circ$ :

$$\cos \omega_s = -\frac{\sin \phi \sin \delta}{\cos \phi \cos \delta} = -\tan \phi \tan \delta \quad (1.6.10)$$


The sunrise hour angle is the negative of the sunset hour angle. It also follows that the number of daylight hours is given by

$$N = \frac{2}{15} \cos^{-1} (-\tan \phi \tan \delta) \quad (1.6.11)$$


A convenient nomogram for determining day length has been devised by Whillier (1965) and is shown in Figure 1.6.3. Information on latitude and declination for either hemisphere leads directly to times of sunrise and sunset and day length.

An additional angle of interest is the **profile angle** of beam radiation on a receiver plane  $R$  that has a surface azimuth angle of  $\gamma$ . It is the projection of the solar altitude angle on a vertical plane perpendicular to the plane in question. Expressed another way, it is the angle through which a plane that is initially horizontal must be rotated about an axis in the plane of the surface in question in order to include the sun. The solar altitude angle  $\alpha_s$  (i.e., angle  $EAD$ ) and the profile angle  $\alpha_p$  (i.e., angle  $fab$ ) for the plane  $R$  are shown in Figure 1.6.4. The plane  $adef$  includes the sun. Note that the solar altitude and profile angle are the same when the sun is in a plane perpendicular to the surface  $R$  (e.g., at solar noon for a surface with a surface azimuth angle of  $0^\circ$  or  $180^\circ$ ). The profile angle is useful in calculating shading by overhangs and can be determined from

$$\tan \alpha_p = \frac{\tan \alpha_s}{\cos(\gamma_s - \gamma)} \quad (1.6.12)$$



**Figure 1.6.3** Nomogram to determine time of sunset and day length. Adapted from Whillier (1965).



**Figure 1.6.4** The solar altitude angle  $\alpha_s$  ( $\angle EAD$ ) and the profile angle  $\alpha_p$  ( $\angle fab$ ) for surface  $R$ .

**Example 1.6.3**

Calculate the time of sunrise, solar altitude, zenith, solar azimuth, and profile angles for a  $60^\circ$  sloped surface facing  $25^\circ$  west of south at 4:00 PM solar time on March 16 at a latitude of  $43^\circ$ . Also calculate the time of sunrise and sunset on the surface.

**Solution**

The hour angle at sunset is determined using Equation 1.6.10. For March 16, from Equation 1.6.1 (or Table 1.6.1),  $\delta = -2.4^\circ$ :

$$\omega_s = \cos^{-1}[-\tan 43 \tan(-2.4)] = 87.8^\circ$$

The sunrise hour angle is therefore  $-87.8^\circ$ . With the earth's rotation of  $15^\circ$  per hour, sunrise (and sunset) occurs 5.85 h (5 h and 51 min) from noon so sunrise is at 6:09 AM (and sunset is at 5:51 PM).

The solar altitude angle  $\alpha_s$  is a function only of time of day and declination. At 4:00 PM,  $\omega = 60^\circ$ . From Equation 1.6.5, recognizing that  $\cos \theta_z = \sin(90 - \theta_z) = \sin \alpha_s$ ,

$$\begin{aligned}\sin \alpha_s &= \cos 43 \cos(-2.4) \cos 60 + \sin 43 \sin(-2.4) = 0.337 \\ \alpha_s &= 19.7^\circ \quad \text{and} \quad \theta_z = 90 - \alpha_s = 70.3^\circ\end{aligned}$$

The solar azimuth angle for this time can be calculated with Equation 1.6.6:

$$\gamma_s = \text{sign}(60) \left[ \cos^{-1} \left( \frac{\cos 70.3 \sin 43 - \sin(-2.4)}{\sin 70.3 \cos 43} \right) \right] = 66.8^\circ$$

The profile angle for the surface with  $\gamma = 25^\circ$  is calculated with Equation 1.6.12:

$$\alpha_p = \tan^{-1} \left( \frac{\tan 19.7}{\cos(66.8 - 25)} \right) = 25.7^\circ$$

The hour angles at which sunrise and sunset occur on the surface are calculated from Equation 1.6.2 with  $\theta = 90^\circ$  ( $\cos \theta = 0$ ):

$$\begin{aligned}0 &= \sin(-2.4) \sin 43 \cos 60 - \sin(-2.4) \cos 43 \sin 60 \cos 25 \\ &\quad + [\cos(-2.4) \cos 43 \cos 60 + \cos(-2.4) \sin 43 \sin 60 \cos 25] \cos \omega \\ &\quad + [\cos(-2.4) \sin 60 \sin 25] \sin \omega\end{aligned}$$

or

$$0 = 0.008499 + 0.9077 \cos \omega + 0.3657 \sin \omega$$


which, using  $\sin^2 \omega + \cos^2 \omega = 1$ , has two solutions:  $\omega = -68.6^\circ$  and  $\omega = 112.4^\circ$ . Sunrise on the surface is therefore  $68.6/15 = 4.57$  h before noon, or 7:26 AM. The time of sunset on the collector is the actual sunset since  $112.4^\circ$  is greater than  $87.8^\circ$  (i.e., when  $\theta = 90^\circ$  the sun has already set). ■

Solar azimuth and altitude angles are tabulated as functions of latitude, declination, and hour angle by the U.S. Hydrographic Office (1940). Highly accurate equations are available from the National Renewable Energy Laboratory's website. Information on the position of the sun in the sky is also available with less precision but easy access in various types of charts. Examples of these are the Sun Angle Calculator (1951) and the solar position charts (plots of  $\alpha_s$  or  $\theta_z$  vs.  $\gamma_s$  for various  $\phi$ ,  $\delta$ , and  $\omega$ ) in Section 1.9. Care is necessary in interpreting information from other sources, since nomenclature, definitions, and sign conventions may vary from those used here.

## 1.7 ANGLES FOR TRACKING SURFACES

Some solar collectors “track” the sun by moving in prescribed ways to minimize the angle of incidence of beam radiation on their surfaces and thus maximize the incident beam radiation. The angles of incidence and the surface azimuth angles are needed for these collectors. The relationships in this section will be useful in radiation calculations for these moving surfaces. For further information see Eibling et al. (1953) and Braun and Mitchell (1983).

Tracking systems are classified by their motions. Rotation can be about a single axis (which could have any orientation but which in practice is usually horizontal east-west, horizontal north-south, vertical, or parallel to the earth's axis) or it can be about two axes. The following sets of equations (except for Equations 1.7.4) are for surfaces that rotate on axes that are parallel to the surfaces. Figure 1.7.1 shows extraterrestrial radiation on a fixed surface with slope equal to the latitude and also on surfaces that track the sun about a horizontal north-south or east-west axis at a latitude of  $45^\circ$  at the summer and winter



**Figure 1.7.1** Extraterrestrial solar radiation for  $\phi = 45^\circ$  on a stationary collector at  $\beta = 45^\circ$  on north-south (N-S) and east-west (E-W) single-axis tracking collectors. The three dotted curves are for the winter solstice and the three solid curves are for the summer solstice.

solstices. It is clear that tracking can significantly change the time distribution of incident beam radiation. Tracking does not always result in increased beam radiation; compare the winter solstice radiation on the north-south tracking surface with the radiation on the fixed surface. In practice the differences will be less than indicated by the figure due to clouds and atmospheric transmission.

For a plane rotated about a horizontal east-west axis with a single daily adjustment so that the beam radiation is normal to the surface at noon each day,

$$\cos \theta = \sin^2 \delta + \cos^2 \delta \cos \omega \quad (1.7.1a)$$

The slope of this surface will be fixed for each day and will be

$$\beta = |\phi - \delta| \quad (1.7.1b)$$

The surface azimuth angle for a day will be  $0^\circ$  or  $180^\circ$  depending on the latitude and declination:

$$\gamma = \begin{cases} 0^\circ & \text{if } \phi - \delta > 0 \\ 180^\circ & \text{if } \phi - \delta \leq 0 \end{cases} \quad (1.7.1c)$$

For a plane rotated about a horizontal east-west axis with continuous adjustment to minimize the angle of incidence,

$$\cos \theta = (1 - \cos^2 \delta \sin^2 \omega)^{1/2} \quad (1.7.2a)$$

The slope of this surface is given by

$$\tan \beta = \tan \theta_z |\cos \gamma_s| \quad (1.7.2b)$$

The surface azimuth angle for this mode of orientation will change between  $0^\circ$  and  $180^\circ$  if the solar azimuth angle passes through  $\pm 90^\circ$ . For either hemisphere,

$$\gamma = \begin{cases} 0^\circ & \text{if } |\gamma_s| < 90 \\ 180^\circ & \text{if } |\gamma_s| \geq 90 \end{cases} \quad (1.7.2c)$$

For a plane rotated about a horizontal north-south axis with continuous adjustment to minimize the angle of incidence,

$$\cos \theta = (\cos^2 \theta_z + \cos^2 \delta \sin^2 \omega)^{1/2} \quad (1.7.3a)$$

The slope is given by

$$\tan \beta = \tan \theta_z |\cos(\gamma - \gamma_s)| \quad (1.7.3b)$$

The surface azimuth angle  $\gamma$  will be  $90^\circ$  or  $-90^\circ$  depending on the sign of the solar azimuth angle:

$$\gamma = \begin{cases} 90^\circ & \text{if } \gamma_s > 0 \\ -90^\circ & \text{if } \gamma_s \leq 0 \end{cases} \quad (1.7.3c)$$

For a plane with a fixed slope rotated about a vertical axis, the angle of incidence is minimized when the surface azimuth and solar azimuth angles are equal. From Equation 1.6.3, the angle of incidence is

$$\cos \theta = \cos \theta_z \cos \beta + \sin \theta_z \sin \beta \quad (1.7.4a)$$

The slope is fixed, so

$$\beta = \text{const} \quad (1.7.4b)$$

The surface azimuth angle is

$$\gamma = \gamma_s \quad (1.7.4c)$$

For a plane rotated about a north-south axis parallel to the earth's axis with continuous adjustment to minimize  $\theta$ ,

$$\cos \theta = \cos \delta \quad (1.7.5a)$$

The slope varies continuously and is

$$\tan \beta = \frac{\tan \phi}{\cos \gamma} \quad (1.7.5b)$$

The surface azimuth angle is

$$\gamma = \tan^{-1} \frac{\sin \theta_z \sin \gamma_s}{\cos \theta' \sin \phi} + 180C_1C_2 \quad (1.7.5c)$$

where

$$\cos \theta' = \cos \theta_z \cos \phi + \sin \theta_z \sin \phi \cos \gamma_s \quad (1.7.5d)$$

$$C_1 = \begin{cases} 0 & \text{if } \left( \tan^{-1} \frac{\sin \theta_z \sin \gamma_s}{\cos \theta' \sin \phi} \right) \gamma_s \geq 0 \\ +1 & \text{otherwise} \end{cases} \quad (1.7.5e)$$

$$C_2 = \begin{cases} +1 & \text{if } \gamma_s \geq 0 \\ -1 & \text{if } \gamma_s < 0 \end{cases} \quad (1.7.5f)$$

For a plane that is continuously tracking about two axes to minimize the angle of incidence,

$$\cos \theta = 1 \quad (1.7.6a)$$

$$\beta = \theta_z \quad (1.7.6b)$$

$$\gamma = \gamma_s \quad (1.7.6c)$$

### Example 1.7.1

Calculate the angle of incidence of beam radiation, the slope of the surface, and the surface azimuth angle for a surface at **a**  $\phi = 40^\circ$ ,  $\delta = 21^\circ$ , and  $\omega = 30^\circ$  (2:00 PM) and **b**  $\phi = 40^\circ$ ,  $\delta = 21^\circ$ , and  $\omega = 100^\circ$  if it is continuously rotated about an east-west axis to minimize  $\theta$ .



**Solution**

**a** Use Equations 1.7.2 for a surface moved in this way. First calculate the angle of incidence:

$$\theta = \cos^{-1}(1 - \cos^2 21 \sin^2 30)^{1/2} = 27.8^\circ$$

Next calculate  $\theta_z$  from Equation 1.6.5:

$$\theta_z = \cos^{-1}(\cos 40 \cos 21 \cos 30 + \sin 40 \sin 21) = 31.8^\circ$$

We now need the solar azimuth angle  $\gamma_s$ , which can be found from Equation 1.6.6:

$$\gamma_s = \text{sign}(30) \left| \cos^{-1} \left( \frac{\cos 31.8 \sin 40 - \sin 21}{\sin 31.8 \cos 40} \right) \right| = 62.3^\circ$$

Then from Equation 1.7.2b

$$\beta = \tan^{-1}(\tan 31.8 |\cos 62.3|) = 16.1^\circ$$

From Equation 1.7.2c, with  $\gamma_s < 90$ ,  $\gamma = 0$ .

**b** The procedure is the same as in part a:

$$\theta = \cos^{-1}(1 - \cos^2 21 \sin^2 100)^{1/2} = 66.8^\circ$$

$$\theta_z = \cos^{-1}(\cos 40 \cos 21 \cos 100 + \sin 40 \sin 21) = 83.9^\circ$$

$$\gamma_s = \cos^{-1} \left[ \text{sign}(100) \left( \frac{\cos 83.9 \sin 40 - \sin 21}{\sin 83.9 \cos 40} \right) \right] = 112.4^\circ$$

The slope is then


$$\beta = \tan^{-1}(\tan 83.9 |\cos 112.4|) = 74.3^\circ$$

And since  $|\gamma_s| > 90$ ,  $\gamma$  will be  $180^\circ$ . (Note that these results can be checked using Equation 1.6.5.) ■

## 1.8 RATIO OF BEAM RADIATION ON TILTED SURFACE TO THAT ON HORIZONTAL SURFACE

For purposes of solar process design and performance calculations, it is often necessary to calculate the hourly radiation on a tilted surface of a collector from measurements or estimates of solar radiation on a horizontal surface. The most commonly available data are total radiation for hours or days on the horizontal surface, whereas the need is for beam and diffuse radiation on the plane of a collector.

The geometric factor  $R_b$ , the ratio of beam radiation on the tilted surface to that on a horizontal surface at any time, can be calculated exactly by appropriate use of



**Figure 1.8.1** Beam radiation on horizontal and tilted surfaces.

Equation 1.6.2. Figure 1.8.1 indicates the angle of incidence of beam radiation on the horizontal and tilted surfaces. The ratio  $G_{b,T}/G_b$  is given by<sup>7</sup>

$$R_b = \frac{G_{b,T}}{G_b} = \frac{G_{b,n} \cos \theta}{G_{b,n} \cos \theta_z} = \frac{\cos \theta}{\cos \theta_z} \quad (1.8.1)$$

and  $\cos \theta$  and  $\cos \theta_z$  are both determined from Equation 1.6.2 (or from equations derived from Equation 1.6.2).

### Example 1.8.1

What is the ratio of beam radiation to that on a horizontal surface for the surface and time specified in Example 1.6.1?

#### Solution

Example 1.6.1 shows the calculation for  $\cos \theta$ . For the horizontal surface, from Equation 1.6.5,

$$\cos \theta_z = \sin(-14) \sin 43 + \cos(-14) \cos 43 \cos(-22.5) = 0.491$$

And from Equation 1.8.1

$$R_b = \frac{\cos \theta}{\cos \theta_z} = \frac{0.818}{0.491} = 1.67$$

■

The optimum azimuth angle for flat-plate collectors is usually  $0^\circ$  in the northern hemisphere (or  $180^\circ$  in the southern hemisphere). Thus it is a common situation that  $\gamma = 0^\circ$  (or  $180^\circ$ ). In this case, Equations 1.6.5 and 1.6.7 can be used to determine  $\cos \theta_z$  and  $\cos \theta$ , respectively, leading in the northern hemisphere, for  $\gamma = 0^\circ$ , to

$$R_b = \frac{\cos(\phi - \beta) \cos \delta \cos \omega + \sin(\phi - \beta) \sin \delta}{\cos \phi \cos \delta \cos \omega + \sin \phi \sin \delta} \quad (1.8.2)$$

In the southern hemisphere,  $\gamma = 180^\circ$  and the equation is

$$R_b = \frac{\cos(\phi + \beta) \cos \delta \cos \omega + \sin(\phi + \beta) \sin \delta}{\cos \phi \cos \delta \cos \omega + \sin \phi \sin \delta} \quad (1.8.3)$$

<sup>7</sup>The symbol  $G$  is used in this book to denote rates, while  $I$  is used for energy quantities integrated over an hour. The original development of  $R_b$  by Hottel and Woertz (1942) was for hourly periods; for an hour (using angles at the midpoint of the hour),  $R_b = I_{b,T}/I_b$ .

A special case of interest is  $R_{b,\text{noon}}$ , the ratio for south-facing surfaces at solar noon. From Equations 1.6.8a and 1.6.9a, for the northern hemisphere,


$$R_{b,\text{noon}} = \frac{\cos|\phi - \delta - \beta|}{\cos|\phi - \delta|} \quad (1.8.4a)$$

For the southern hemisphere, from Equations 1.6.8b and 1.6.9b,


$$R_{b,\text{noon}} = \frac{\cos|-\phi + \delta - \beta|}{\cos|-\phi + \delta|} \quad (1.8.4b)$$

Hottel and Woertz (1942) pointed out that Equation 1.8.2 provides a convenient method for calculating  $R_b$  for the most common cases. They also showed a graphical method for solving these equations. This graphical method has been revised by Whillier (1975), and an adaptation of Whillier's curves is given here. Figures 1.8.2(a–e) are plots of both  $\cos \theta_z$  as a function of  $\phi$  and  $\cos \theta$  as a function of  $\phi - \beta$  for various dates (i.e., declinations). By plotting the curves for sets of dates having (nearly) the same absolute value of declination, the curves “reflect back” on each other at latitude  $0^\circ$ . Thus each set of curves, in effect, covers the latitude range of  $-60^\circ$  to  $60^\circ$ .


As will be seen in later chapters, solar process performance calculations are very often done on an hourly basis. The  $\cos \theta_z$  plots are shown for the midpoints of hours before and after solar noon, and the values of  $R_b$  found from them are applied to those hours. (This procedure is satisfactory for most hours of the day, but in hours that include sunrise and sunset, unrepresentative values of  $R_b$  may be obtained. Solar collection in those hours is




**Figure 1.8.2(a)**  $\cos \theta$  versus  $\phi - \beta$  and  $\cos \theta_z$  versus  $\phi$  for hours 11 to 12 and 12 to 1 for surfaces tilted toward the equator. The columns on the right show dates for the curves for north and south latitudes. In south latitudes, use  $|\phi|$ . Adapted from Whillier (1975).




**Figure 1.8.2(b)**  $\cos \theta$  versus  $\phi - \beta$  and  $\cos \theta_z$  versus  $\phi$  for hours 10 to 11 and 1 to 2.



**Figure 1.8.2(c)**  $\cos \theta$  versus  $\phi - \beta$  and  $\cos \theta_z$  versus  $\phi$  for hours 9 to 10 and 2 to 3.



**Figure 1.8.2(d)**  $\cos \theta$  versus  $\phi - \beta$  and  $\cos \theta_z$  versus  $\phi$  for hours 8 to 9 and 3 to 4.



**Figure 1.8.2(e)**  $\cos \theta$  versus  $\phi - \beta$  and  $\cos \theta_z$  versus  $\phi$  for hours 7 to 8 and 4 to 5.

most often zero or a negligible part of the total daily collector output. However, care must be taken that unrealistic products of  $R_b$  and beam radiation  $I_b$  are not used.)

To find  $\cos \theta_z$ , enter the chart for the appropriate time with the date and latitude of the location in question. For the same date and latitude  $\cos \theta$  is found by entering with an abscissa corresponding to  $\phi - \beta$ . Then  $R_b$  is found from Equation 1.8.1. The dates on the sets of curves are shown in two sets, one for north (positive) latitudes and the other for south (negative) latitudes.

Two situations arise, for positive values or for negative values of  $\phi - \beta$ . For positive values, the charts are used directly. If  $\phi - \beta$  is negative (which frequently occurs when collectors are sloped for optimum performance in winter or with vertical collectors), the procedure is modified. Determine  $\cos \theta_z$  as before. Determine  $\cos \theta$  from the absolute value of  $\phi - \beta$  using the curve for the other hemisphere, that is, with the sign on the declination reversed.

### Example 1.8.2

Calculate  $R_b$  for a surface at latitude  $40^\circ$  N at a tilt  $30^\circ$  toward the south for the hour 9 to 10 solar time on February 16.

#### Solution

Use Figure 1.8.2(c) for the hour  $\pm 2.5$  h from noon as representative of the hour from 9 to 10. To find  $\cos \theta_z$ , enter at a latitude of  $40^\circ$  for the north latitude date of February 16. Here  $\cos \theta_z = 0.45$ . To find  $\cos \theta$ , enter at a latitude of  $\phi - \beta = 10^\circ$  for the same date. Here  $\cos \theta = 0.73$ . Then

$$R_b = \frac{\cos \theta}{\cos \theta_z} = \frac{0.73}{0.45} = 1.62$$

The ratio can also be calculated using Equation 1.8.2. The declination on February 16 is  $-13^\circ$ :

$$R_b = \frac{\cos 10 \cos(-13) \cos(-37.5) + \sin 10 \sin(-13)}{\cos 40 \cos(-13) \cos(-37.5) + \sin 40 \sin(-13)} = \frac{0.722}{0.448} = 1.61 \quad \blacksquare$$

### Example 1.8.3


Calculate  $R_b$  for a latitude  $40^\circ$  N at a tilt of  $50^\circ$  toward the south for the hour 9 to 10 solar time on February 16.

#### Solution

As found in the previous example,  $\cos \theta_z = 0.45$ . To find  $\cos \theta$ , enter at an abscissa of  $+10^\circ$ , using the curve for February 16 for south latitudes. The value of  $\cos \theta$  from the curve is 0.80. Thus  $R_b = 0.80/0.45 = 1.78$ . Equation 1.8.2 can also be used:

$$R_b = \frac{\cos 10 \cos(-13) \cos(-37.5) + \sin(-10) \sin(-13)}{\cos 40 \cos(-13) \cos(-37.5) + \sin 40 \sin(-13)} = \frac{0.800}{0.448} = 1.79 \quad \blacksquare$$

It is possible, using Equation 1.8.2 or Figure 1.8.2, to construct plots showing the effects of collector tilt on  $R_b$  for various times of the year and day. Figure 1.8.3 shows



**Figure 1.8.3** Ratio  $R_b$  for a surface with slope  $50^\circ$  to south at latitude  $40^\circ$  for various hours from solar noon.

such a plot for a latitude of  $40^\circ$  and a slope of  $50^\circ$ . It illustrates that very large gains in incident beam radiation are to be had by tilting a receiving surface toward the equator.

Equation 1.8.1 can also be applied to other than fixed flat-plate collectors. Equations 1.7.1 to 1.7.6 give  $\cos \theta$  for surfaces moved in prescribed ways in which concentrating collectors may move to track the sun. If the beam radiation on a horizontal surface is known or can be estimated, the appropriate one of these equations can be used in the numerator of Equation 1.8.1 for  $\cos \theta$ . For example, for a plane rotated continuously about a horizontal east-west axis to maximize the beam radiation on the plane, from Equation 1.7.2a, the ratio of beam radiation on the plane to that on a horizontal surface at any time is

$$R_b = \frac{(1 - \cos^2 \delta \sin^2 \omega)^{1/2}}{\cos \phi \cos \delta \cos \omega + \sin \phi \sin \delta} \quad (1.8.5)$$

Some of the solar radiation data available are beam radiation on surfaces normal to the radiation, as measured by a pyrheliometer.<sup>8</sup> In this case the useful ratio is beam radiation on the surface in question to beam radiation on the normal surface; simply  $R'_b = \cos \theta$ , where  $\theta$  is obtained from Equations 1.7.1 to 1.7.6.

## 1.9 SHADING


Three types of shading problems occur so frequently that methods are needed to cope with them. The first is shading of a collector, window, or other receiver by nearby

<sup>8</sup>Pyrheliometers and other instruments for measuring solar radiation are described in Chapter 2.

trees, buildings, or other obstructions. The geometries may be irregular, and systematic calculations of shading of the receiver in question may be difficult. Recourse is made to diagrams of the position of the sun in the sky, for example, plots of solar altitude  $\alpha_s$  versus solar azimuth  $\gamma_s$ , on which shapes of obstructions (shading profiles) can be superimposed to determine when the path from the sun to the point in question is blocked. The second type includes shading of collectors in other than the first row of multirow arrays by the collectors on the adjoining row. The third includes shading of windows by overhangs and wingwalls. Where the geometries are regular, shading is amenable to calculation, and the results can be presented in general form. This will be treated in Chapter 14.

At any point in time and at a particular latitude,  $\phi$ ,  $\delta$ , and  $\omega$  are fixed. From the equations in Section 1.6, the zenith angle  $\theta_z$  or solar altitude angle  $\alpha_s$  and the solar azimuth angle  $\gamma_s$  can be calculated. A solar position plot of  $\theta_z$  and  $\alpha_s$  versus  $\gamma_s$  for latitudes of  $\pm 45^\circ$  is shown in Figure 1.9.1. Lines of constant declination are labeled by dates of mean days of the months from Table 1.6.1. Lines of constant hour angles labeled by hours are also shown. See Problem S1.5 for other latitudes.

The angular position of buildings, wingwalls, overhangs, or other obstructions can be entered on the same plot. For example, as observed by Mazria (1979) and Anderson (1982), if a building or other obstruction of known dimensions and orientation is located a known distance from the point of interest (i.e., the receiver, collector, or window), the angular coordinates corresponding to altitude and azimuth angles of points on the obstruction (the object azimuth angle  $\gamma_o$  and object altitude angle  $\alpha_o$ ) can be calculated from trigonometric considerations. This is illustrated in Examples 1.9.1 and 1.9.2. Alternatively, measurements of object altitude and azimuth angles may be made at the site of a proposed receiver and the angles plotted on the solar position plot. Instruments are available to measure the angles.



**Figure 1.9.1** Solar position plot for  $\pm 45^\circ$  latitude. Solar altitude angle and solar azimuth angle are functions of declination and hour angle, indicated on the plots by dates and times. The dates shown are for northern hemisphere; for southern hemisphere use the corresponding dates as indicated in Figure 1.8.2.



**Example 1.9.1**

A proposed collector site at  $S$  is 10.0 m to the north of a long wall that shades it when the sun is low in the sky. The wall is of uniform height of 2.5 m above the center of the proposed collector area. Show this wall on a solar position chart with (a) the wall oriented east-west and (b) the wall oriented on a southeast-to-northwest axis displaced  $20^\circ$  from east-west.

**Solution**

In each case, we pick several points on the top of the wall to establish the coordinates for plotting on the solar position plot.

**a** Take three points indicated by  $A$ ,  $B$ , and  $C$  in the diagram with  $A$  to the south and  $B$  10 m and  $C$  30 m west of  $A$ . Points  $B'$  and  $C'$  are taken to the east of  $A$  with the same object altitude angles as  $B$  and  $C$  and with object azimuth angles changed only in sign.

For point  $A$ , the object azimuth  $\gamma_{oA}$  is  $0^\circ$ . The object altitude angle is


$$\tan \alpha_{oA} = \frac{2.5}{10}, \quad \alpha_{oA} = 14.0^\circ$$

For point  $B$ ,  $SB = (10^2 + 10^2)^{1/2} = 14.1$  m,


$$\tan \alpha_{oB} = \frac{2.5}{14.1}, \quad \alpha_{oB} = 10.0^\circ$$

$$\tan \gamma_{oB} = \frac{10}{10}, \quad \gamma_{oB} = 45.0^\circ$$

(a)



(b)




For point C,  $SC = (10^2 + 30^2)^{1/2} = 31.6$  m,

$$\tan \alpha_{oC} = \frac{2.5}{31.6}, \quad \alpha_{oC} = 4.52^\circ$$

$$\tan \gamma_{oC} = \frac{30}{10}, \quad \gamma_{oC} = 71.6^\circ$$

There are points corresponding to *B* and *C* but to the east of *A*; these will have the same object azimuth angles except with negative signs. The shading profile determined by these coordinates is independent of latitude. It is shown by the solid line on the plot for  $\phi = 45^\circ$ . Note that at object azimuth angles of  $90^\circ$ , the object distance becomes infinity and the object altitude angle becomes  $0^\circ$ .

The sun is obscured by the wall only during times shown in the diagram. The wall does not cast a shadow on point *S* at any time of day from late March to mid-September. For December 10, it casts a shadow on point *S* before 9:00 AM and after 3:00 PM.



**b** The obstruction of the sky does not show east-west symmetry in this case, so five points have been chosen as shown to cover the desirable range. Point *A* is the same as before, that is,  $\alpha_{oA} = 14.0^\circ$ ,  $\gamma_{oA} = 0^\circ$ .

Arbitrarily select points on the wall for the calculation. In this case the calculations are easier if we select values of the object azimuth angle and calculate from them the corresponding distances from the point to the site and the corresponding  $\alpha_o$ . In this case we can select values of  $\gamma_o$  for points *B*, *C*, *D*, and *E* of  $45^\circ$ ,  $90^\circ$ ,  $-30^\circ$ , and  $-60^\circ$ .

For point *B*, with  $\gamma_{oB} = 45^\circ$ , the distance *SB* can be calculated from the law of sines:

$$\frac{\sin 70}{SB} = \frac{\sin(180 - 45 - 70)}{10}, \quad SB = 10.4 \text{ m}$$

$$\tan \alpha_{oB} = \frac{2.5}{10.4}, \quad \alpha_{oB} = 13.5^\circ$$

For point  $D$ , with  $\gamma_{oD} = -30^\circ$ , the calculation is

$$\frac{\sin 110}{SD} = \frac{\sin(180 - 110 - 30)}{10}, \quad SD = 14.6 \text{ m}$$

$$\tan \alpha_{oD} = \frac{2.5}{14.6}, \quad \alpha_{oD} = 9.7^\circ$$


The calculations for points  $C$  and  $E$  give  $\alpha_{oC} = 5.2^\circ$  at  $\gamma_{oC} = 90^\circ$  and  $\alpha_{oE} = 2.6^\circ$  at  $\gamma_{oE} = -60.0^\circ$ .

The shading profile determined by these coordinates is plotted on the solar position chart for  $\phi = 45^\circ$  and is shown as the dashed line. In this case, the object altitude angle goes to zero at azimuth angles of  $-70^\circ$  and  $110^\circ$ . In either case, the area under the curves represents the wall, and the times when the wall would obstruct the beam radiation are those times (declination and hour angles) in the areas under the curves. ■

There may be some freedom in selecting points to be used in plotting object coordinates, and the calculation may be made easier (as in the preceding example) by selecting the most appropriate points. Applications of trigonometry will always provide the necessary information. For obstructions such as buildings, the points selected must include corners or limits that define the extent of obstruction. It may or may not be necessary to select intermediate points to fully define shading. This is illustrated in the following example.

### Example 1.9.2

It is proposed to install a solar collector at a level 4.0 m above the ground. A rectangular building 30 m high is located 45 m to the south, has its long dimension on an east-west axis, and has dimensions shown in the diagram. The latitude is  $45^\circ$ . Diagram this building on the solar position plot to show the times of day and year when it would shade the proposed collector.



### Solution

Three points that will be critical to determination of the shape of the image are the top near corners and the top of the building directly to the south of the proposed collector. Consider first point  $A$ . The object altitude angle of this point is determined by the fact that it is 45 m away and  $30 - 4 = 26$  m higher than the proposed collector:

$$\tan \alpha_{oA} = \frac{26}{45}, \quad \alpha_{oA} = 30.0^\circ$$

The object azimuth angle  $\gamma_{oA}$  is  $0^\circ$  as the point  $A$  is directly to the south.

For point  $B$ , the distance  $SB$  is  $(45^2 + 52^2)^{1/2} = 68.8$  m. The height is again 26 m. Then

$$\tan \alpha_{oB} = \frac{26}{68.8}, \quad \alpha_{oB} = 20.7^\circ$$

The object azimuth angle  $\gamma_{oB}$  is

$$\tan \gamma_{oB} = \frac{52}{45}, \quad \gamma_{oB} = 49.1^\circ$$

The calculation method for point  $C$  is the same as for  $B$ . The distance  $SC = (45^2 + 8^2)^{1/2} = 45.7$  m:


$$\tan \alpha_{oC} = \frac{26}{45.7}, \quad \alpha_{oC} = 29.6^\circ$$

$$\tan \gamma_{oC} = \frac{8}{45}, \quad \gamma_{oC} = 10.1^\circ$$


Note again that since point  $C$  lies to the east of south,  $\gamma_{oC}$  is by convention negative.

The shading profile of the building can be approximated by joining  $A$  and  $C$  and  $A$  and  $B$  by straight lines. A more precise representation is obtained by calculating intermediate points on the shading profile to establish the curve. In this example, an object altitude angle of  $27.7^\circ$  is calculated for an object azimuth angle of  $25^\circ$ .

These coordinates are plotted and the outlines of the building are shown in the figure. The shaded area represents the existing building as seen from the proposed collector site. The dates and times when the collector would be shaded from direct sun by the building are evident.



Implicit in the preceding discussion is the idea that the solar position at a point in time can be represented for a point location. Collectors and receivers have finite size, and what one point on a large receiving surface “sees” may not be the same as what another point sees. The problem is often to determine the amount of beam radiation on a receiver. If



**Figure 1.9.2** (a) Cross section of a long overhang showing projection, gap, and height. (b) Section showing shading planes.

shading obstructions are far from the receiver relative to its size, so that shadows tend to move over the receiver rapidly and the receiver is either shaded or not shaded, the receiver can be thought of as a point. If a receiver is partially shaded, it can be considered to consist of a number of smaller areas, each of which is shaded or not shaded. Or integration over the receiver area may be performed to determine shading effects. These integrations have been done for special cases of overhangs and wingwalls.

Overhangs and wingwalls are architectural features that are applied to buildings to shade windows from beam radiation. The solar position charts can be used to determine when points on the receiver are shaded. The procedure is identical to that of Example 1.9.1; the obstruction in the case of an overhang and the times when the point is shaded from beam radiation are the times corresponding to areas above the line. This procedure can be used for overhangs of either finite or infinite length. The same concepts can be applied to wingwalls; the vertical edges of the object in Example 1.9.2 correspond to edges of wingwalls of finite height.


An overhang is shown in cross section in Figure 1.9.2(a) for the most common situation of a vertical window. The projection  $P$  is the horizontal distance from the plane of the window to the outer edge of the overhang. The gap  $G$  is the vertical distance from the top of the window to the horizontal plane that includes the outer edge of the overhang. The height  $H$  is the vertical dimension of the window.

The concept of shading planes was introduced by Jones (1980) as a useful way of considering shading by overhangs where end effects are negligible. Two shading planes are labeled in Figure 1.9.2(b). The angle of incidence of beam radiation on a shading plane can be calculated from its surface azimuth angle  $\gamma$  and its slope  $\beta = 90 + \psi$  by Equation 1.6.2 or equivalent. The angle  $\psi$  of shading plane 1 is  $\tan^{-1}[P/(G + H)]$  and that for shading plane 2 is  $\tan^{-1}(P/G)$ . Note that if the profile angle  $\alpha_p$  is less than  $90 - \psi$ , the outer surface of the shading plane will “see” the sun and beam radiation will reach the receiver.<sup>9</sup>

Shading calculations are needed when flat-plate collectors are arranged in rows.<sup>10</sup> Normally, the first row is unobstructed, but the second row may be partially shaded by the

<sup>9</sup>Use of the shading plane concept will be discussed in Chapters 2 and 14.

<sup>10</sup>See Figure 12.1.2(c) for an example.




**Figure 1.9.3** Section of two rows of a multirow collector array.

first, the third by the second, and so on. This arrangement of collectors is shown in cross section in Figure 1.9.3.

For the case where the collectors are long in extent so the end effects are negligible, the profile angle provides a useful means of determining shading. As long as the profile angle is greater than the angle  $CAB$ , no point on row  $N$  will be shaded by row  $M$ . If the profile angle at a point in time is  $CA'B'$  and is less than  $CAB$ , the portion of row  $N$  below point  $A'$  will be shaded from beam radiation.

### Example 1.9.3

A multiple-row array of collectors is arranged as shown in the figure. The collectors are 2.10 m from top to bottom and are sloped at  $60^\circ$  toward the south. At a time when the profile angle (given by Equation 1.6.12) is  $25^\circ$ , estimate the fraction of the area of the collector in row  $N$  that will be shaded by the collectors in row  $M$ . Assume that the rows are long so end effects are not significant.



### Solution

Referring to the figure, the angle  $BAC$  is  $\tan^{-1} [1.82 / (2.87 - 1.05)] = 45^\circ$ , and since  $\alpha_p$  is  $25^\circ$ , shading will occur.

The dimension  $AA'$  can be calculated:

$$AC = \frac{1.82}{\sin 45} = 2.57 \text{ m}$$

$$\angle CAA' = 180 - 45 - 60 = 75^\circ, \quad \angle CA'A = 180 - 75 - 20 = 85^\circ$$

From the law of sines,

$$AA' = \frac{2.57 \sin 20}{\sin 85} = 0.88 \text{ m}$$

The fraction of collector  $N$  that is shaded is  $0.88/2.10 = 0.42$ . ■

## 1.10 EXTRATERRESTRIAL RADIATION ON A HORIZONTAL SURFACE

Several types of radiation calculations are most conveniently done using normalized radiation levels, that is, the ratio of radiation level to the theoretically possible radiation that would be available if there were no atmosphere. For these calculations, which are discussed in Chapter 2, we need a method of calculating the extraterrestrial radiation.

At any point in time, the solar radiation incident on a horizontal plane outside of the atmosphere is the normal incident solar radiation as given by Equation 1.4.1 divided by  $R_b$ :

$$G_o = G_{sc} \left( 1 + 0.033 \cos \frac{360n}{365} \right) \cos \theta_z \quad (1.10.1)$$

where  $G_{sc}$  is the solar constant and  $n$  is the day of the year. Combining Equation 1.6.5 for  $\cos \theta_z$  with Equation 1.10.1 gives  $G_o$  for a horizontal surface at any time between sunrise and sunset:

$$G_o = G_{sc} \left( 1 + 0.033 \cos \frac{360n}{365} \right) (\cos \phi \cos \delta \cos \omega + \sin \phi \sin \delta) \quad (1.10.2)$$

It is often necessary for calculation of daily solar radiation to have the integrated daily extraterrestrial radiation on a horizontal surface,  $H_o$ . This is obtained by integrating Equation 1.10.2 over the period from sunrise to sunset. If  $G_{sc}$  is in watts per square meter,  $H_o$  in daily joules per square meter per day is


$$H_o = \frac{24 \times 3600 G_{sc}}{\pi} \left( 1 + 0.033 \cos \frac{360n}{365} \right) \times \left( \cos \phi \cos \delta \sin \omega_s + \frac{\pi \omega_s}{180} \sin \phi \sin \delta \right) \quad (1.10.3)$$

where  $\omega_s$  is the sunset hour angle, in degrees, from Equation 1.6.10.

The monthly mean<sup>11</sup> daily extraterrestrial radiation  $\overline{H_o}$  is a useful quantity. For latitudes in the range +60 to -60 it can be calculated with Equation 1.10.3 using  $n$  and  $\delta$  for the mean day of the month<sup>12</sup> from Table 1.6.1. Mean radiation  $H_o$  is plotted as a function of latitude for the northern and southern hemispheres in Figure 1.10.1. The curves are for dates that give the mean radiation for the month and thus show  $\overline{H_o}$ . Values of  $H_o$

<sup>11</sup>An overbar is used throughout the book to indicate a monthly average quantity.

<sup>12</sup>The mean day is the day having  $H_o$  closest to  $\overline{H_o}$ .



**Figure 1.10.1** Extraterrestrial daily radiation on a horizontal surface. The curves are for the mean days of the month from Table 1.6.1.



for any day can be estimated by interpolation. Exact values of  $\overline{H}_o$  for all latitudes are given in Table 1.10.1.

### Example 1.10.1

What is  $H_o$ , the day's solar radiation on a horizontal surface in the absence of the atmosphere, at latitude  $43^\circ$  N on April 15?

**Table 1.10.1** Monthly Average Daily Extraterrestrial Radiation, MJ/m<sup>2</sup>

$\phi$	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
90	0.0	0.0	1.2	19.3	37.2	44.8	41.2	26.5	5.4	0.0	0.0	0.0
85	0.0	0.0	2.2	19.2	37.0	44.7	41.0	26.4	6.4	0.0	0.0	0.0
80	0.0	0.0	4.7	19.6	36.6	44.2	40.5	26.1	9.0	0.6	0.0	0.0
75	0.0	0.7	7.8	21.0	35.9	43.3	39.8	26.3	11.9	2.2	0.0	0.0
70	0.1	2.7	10.9	23.1	35.3	42.1	38.7	27.5	14.8	4.9	0.3	0.0
65	1.2	5.4	13.9	25.4	35.7	41.0	38.3	29.2	17.7	7.8	2.0	0.4
60	3.5	8.3	16.9	27.6	36.6	41.0	38.8	30.9	20.5	10.8	4.5	2.3
55	6.2	11.3	19.8	29.6	37.6	41.3	39.4	32.6	23.1	13.8	7.3	4.8
50	9.1	14.4	22.5	31.5	38.5	41.5	40.0	34.1	25.5	16.7	10.3	7.7
45	12.2	17.4	25.1	33.2	39.2	41.7	40.4	35.3	27.8	19.6	13.3	10.7
40	15.3	20.3	27.4	34.6	39.7	41.7	40.6	36.4	29.8	22.4	16.4	13.7
35	18.3	23.1	29.6	35.8	40.0	41.5	40.6	37.3	31.7	25.0	19.3	16.8
30	21.3	25.7	31.5	36.8	40.0	41.1	40.4	37.8	33.2	27.4	22.2	19.9
25	24.2	28.2	33.2	37.5	39.8	40.4	40.0	38.2	34.6	29.6	25.0	22.9
20	27.0	30.5	34.7	37.9	39.3	39.5	39.3	38.2	35.6	31.6	27.7	25.8
15	29.6	32.6	35.9	38.0	38.5	38.4	38.3	38.0	36.4	33.4	30.1	28.5
10	32.0	34.4	36.8	37.9	37.5	37.0	37.1	37.5	37.0	35.0	32.4	31.1
5	34.2	36.0	37.5	37.4	36.3	35.3	35.6	36.7	37.2	36.3	34.5	33.5
0	36.2	37.4	37.8	36.7	34.8	33.5	34.0	35.7	37.2	37.3	36.3	35.7
-5	38.0	38.5	37.9	35.8	33.0	31.4	32.1	34.4	36.9	38.0	37.9	37.6
-10	39.5	39.3	37.7	34.5	31.1	29.2	29.9	32.9	36.3	38.5	39.3	39.4
-15	40.8	39.8	37.2	33.0	28.9	26.8	27.6	31.1	35.4	38.7	40.4	40.9
-20	41.8	40.0	36.4	31.3	26.6	24.2	25.2	29.1	34.3	38.6	41.2	42.1
-25	42.5	40.0	35.4	29.3	24.1	21.5	22.6	27.0	32.9	38.2	41.7	43.1
-30	43.0	39.7	34.0	27.2	21.4	18.7	19.9	24.6	31.2	37.6	42.0	43.8
-35	43.2	39.1	32.5	24.8	18.6	15.8	17.0	22.1	29.3	36.6	42.0	44.2
-40	43.1	38.2	30.6	22.3	15.8	12.9	14.2	19.4	27.2	35.5	41.7	44.5
-45	42.8	37.1	28.6	19.6	12.9	10.0	11.3	16.6	24.9	34.0	41.2	44.5
-50	42.3	35.7	26.3	16.8	10.0	7.2	8.4	13.8	22.4	32.4	40.5	44.3
-55	41.7	34.1	23.9	13.9	7.2	4.5	5.7	10.9	19.8	30.5	39.6	44.0
-60	41.0	32.4	21.2	10.9	4.5	2.2	3.1	8.0	17.0	28.4	38.7	43.7
-65	40.5	30.6	18.5	7.9	2.1	0.3	1.0	5.2	14.1	26.2	37.8	43.7
-70	40.8	28.8	15.6	5.0	0.4	0.0	0.0	2.6	11.1	24.0	37.4	44.9
-75	41.9	27.6	12.6	2.4	0.0	0.0	0.0	0.8	8.0	21.9	38.1	46.2
-80	42.7	27.4	9.7	0.6	0.0	0.0	0.0	0.0	5.0	20.6	38.8	47.1
-85	43.2	27.7	7.2	0.0	0.0	0.0	0.0	0.0	2.4	20.3	39.3	47.6
-90	43.3	27.8	6.2	0.0	0.0	0.0	0.0	0.0	1.4	20.4	39.4	47.8

**Solution**

For these circumstances,  $n = 105$  (from Table 1.6.1),  $\delta = 9.4^\circ$  (from Equation 1.6.1), and  $\phi = 43^\circ$ . From Equation 1.6.10

$$\cos \omega_s = -\tan 43 \tan 9.4 \text{ and } \omega_s = 98.9^\circ$$

Then from Equation 1.10.3, with  $G_{sc} = 1367 \text{ W/m}^2$ ,

$$\begin{aligned} H_o &= \frac{24 \times 3600 \times 1367}{\pi} \left( 1 + 0.033 \cos \frac{360 \times 105}{365} \right) \\ &\quad \times \left( \cos 43 \cos 9.4 \sin 98.9 + \frac{\pi \times 98.9}{180} \sin 43 \sin 9.4 \right) \\ &= 33.8 \text{ MJ/m}^2 \end{aligned}$$

From Figure 1.10.1(a), for the curve for April, we read  $H_o = 34.0 \text{ MJ/m}^2$ , and from Table 1.10.1 we obtain  $H_o = 33.8 \text{ MJ/m}^2$  by interpolation. ■

It is also of interest to calculate the extraterrestrial radiation on a horizontal surface for an hour period. Integrating Equation 1.10.2 for a period between hour angles  $\omega_1$  and  $\omega_2$  which define an hour (where  $\omega_2$  is the larger),

$$\begin{aligned} I_o &= \frac{12 \times 3600}{\pi} G_{sc} \left( 1 + 0.033 \cos \frac{360n}{365} \right) \\ &\quad \times \left[ \cos \phi \cos \delta (\sin \omega_2 - \sin \omega_1) + \frac{\pi(\omega_2 - \omega_1)}{180} \sin \phi \sin \delta \right] \end{aligned} \quad (1.10.4)$$

(The limits  $\omega_1$  and  $\omega_2$  may define a time other than an hour.)

**Example 1.10.2**

What is the solar radiation on a horizontal surface in the absence of the atmosphere at latitude  $43^\circ \text{ N}$  on April 15 between the hours of 10 and 11?

**Solution**

The declination is  $9.4^\circ$  (from the previous example). For April 15,  $n = 105$ . Using Equation 1.10.4 with  $\omega_1 = -30^\circ$  and  $\omega_2 = -15^\circ$ ,

$$\begin{aligned} I_o &= \frac{12 \times 3600 \times 1367}{\pi} \left( 1 + 0.033 \cos \frac{360 \times 105}{365} \right) \\ &\quad \times \left( \cos 43 \cos 9.4 [\sin (-15) - \sin (-30)] + \frac{\pi[-15 - (-30)]}{180} \sin 43 \sin 9.4 \right) \\ &= 3.79 \text{ MJ/m}^2 \end{aligned} \quad \blacksquare$$

The hourly extraterrestrial radiation can also be approximated by writing Equation 1.10.2 in terms of  $I$ , evaluating  $\omega$  at the midpoint of the hour. For the circumstances of Example 1.10.2, the hour's radiation so estimated is  $3.80 \text{ MJ/m}^2$ . Differences between the hourly radiation calculated by these two methods will be slightly larger at times near sunrise and sunset but are still small. For larger time spans, the differences become larger. For example, for the same circumstances as in Example 1.10.2 but for the 2-h span from 7:00 to 9:00, the use of Equation 1.10.4 gives  $4.58 \text{ MJ/m}^2$ , and Equation 1.10.2 for 8:00 gives  $4.61 \text{ MJ/m}^2$ .

## 1.11 SUMMARY

In this chapter we have outlined the basic characteristics of the sun and the radiation it emits, noting that the solar constant, the mean radiation flux density outside of the earth's atmosphere, is  $1367 \text{ W/m}^2$  (within  $\pm 1\%$ ), with most of the radiation in a wavelength range of  $0.3$  to  $3 \mu\text{m}$ . This radiation has directional characteristics that are defined by a set of angles that determine the angle of incidence of the radiation on a surface. We have included in this chapter those topics that are based on extraterrestrial radiation and the geometry of the earth and sun. This is background information for Chapter 2, which is concerned with effects of the atmosphere, radiation measurements, and data manipulation.

## REFERENCES

- American Society for Testing and Materials. E490-00a (2006). "Standard Solar Constant and Zero Air Mass Solar Spectral Irradiance Tables."
- Anderson, E. E., *Fundamentals of Solar Energy Conversion*, Addison-Wesley, Reading, MA (1982).
- Benford, F. and J. E. Bock, *Trans. Am. Illumin. Eng. Soc.*, **34**, 200 (1939). "A Time Analysis of Sunshine."
- Braun, J. E. and J. C. Mitchell, *Solar Energy*, **31**, 439 (1983). "Solar Geometry for Fixed and Tracking Surfaces."
- Cooper, P. I., *Solar Energy*, **12**, 3 (1969). "The Absorption of Solar Radiation in Solar Stills."
- Coulson, K. L., *Solar and Terrestrial Radiation*, Academic, New York (1975).
- Duncan, C. H., R. C. Willson, J. M. Kendall, R. G. Harrison, and J. R. Hickey, *Solar Energy*, **28**, 385 (1982). "Latest Rocket Measurements of the Solar Constant."
- Eibling, J. A., R. E. Thomas, and B. A. Landry, Report to the Office of Saline Water, U.S. Department of the Interior (1953). "An Investigation of Multiple-Effect Evaporation of Saline Waters by Steam from Solar Radiation."
- Frohlich, C., in *The Solar Output and Its Variation* (O. R. White, ed.), Colorado Associated University Press, Boulder (1977). "Contemporary Measures of the Solar Constant."
- Garg, H. P., *Treatise on Solar Energy*, Vol. **I**, Wiley-Interscience, Chichester (1982).
- Hickey, J. R., B. M. Alton, F. J. Griffin, H. Jacobowitz, P. Pelligrino, R. H. Maschhoff, E. A. Smith, and T. H. Vonder Haar, *Solar Energy*, **28**, 443 (1982). "Extraterrestrial Solar Irradiance Variability: Two and One-Half Years of Measurements from Nimbus 7."
- Hottel, H. C. and B. B. Woertz, *Trans. ASME*, **64**, 91 (1942). "Performance of Flat-Plate Solar Heat Collectors."
- Iqbal, M., *An Introduction to Solar Radiation*, Academic, Toronto (1983).
- Johnson, F. S., *J. Meteorol.*, **11**, 431 (1954). "The Solar Constant."
- Jones, R. E., *Solar Energy*, **24**, 305 (1980). "Effects of Overhang Shading of Windows Having Arbitrary Azimuth."

- Kasten, F., and A. Young, *Appl. Opt.*, **28**, 4735 (1989). "Revised Optical Air Mass Tables and Approximation Formula."
- Klein, S. A., *Solar Energy*, **19**, 325 (1977). "Calculation of Monthly Average Insolation on Tilted Surfaces."
- Kondratyev, K. Y., *Radiation in the Atmosphere*, Academic, New York (1969).
- Mazria, E., *The Passive Solar Energy Book*, Rondale, Emmaus, PA (1979).
- NASA SP-8055, National Aeronautics and Space Administration, May (1971). "Solar Electromagnetic Radiation."
- Robinson, N. (ed.), *Solar Radiation*, Elsevier, Amsterdam (1966).
- Spencer, J. W., *Search*, **2** (5), 172 (1971). "Fourier Series Representation of the Position of the Sun."
- Sun Angle Calculator, Libby-Owens-Ford Glass Company (1951).
- Thekaekara, M. P., *Solar Energy*, **18**, 309 (1976). "Solar Radiation Measurement: Techniques and Instrumentation."
- Thekaekara, M. P. and A. J. Drummond, *Natl. Phys. Sci.*, **229**, 6 (1971). "Standard Values for the Solar Constant and Its Spectral Components."
- Thomas, R. N., in *Transactions of the Conference on Use of Solar Energy* (E. F. Carpenter, ed.), Vol. 1, University of Arizona Press, Tucson, p. 1 (1958). "Features of the Solar Spectrum as Imposed by the Physics of the Sun."
- U.S. Hydrographic Office Publication No. 214 (1940). "Tables of Computed Altitude and Azimuth."
- Whillier, A., *Solar Energy*, **9**, 164 (1965). "Solar Radiation Graphs."
- Whillier, A., Personal communications (1975 and 1979).
- Willson, R. C., S. Gulkis, M. Janssen, H. S. Hudson, and G. A. Chapman, *Science*, **211**, 700 (1981). "Observations of Solar Irradiance Variability."

# Available Solar Radiation

In this chapter we describe instruments for solar radiation measurements, the solar radiation data that are available, and the calculation of needed information from the available data. It is generally not practical to base predictions or calculations of solar radiation on attenuation of the extraterrestrial radiation by the atmosphere, as adequate meteorological information is seldom available. Instead, to predict the performance of a solar process in the future, we use past measurements of solar radiation at the location in question or from a nearby similar location.

Solar radiation data are used in several forms and for a variety of purposes. The most detailed information available is beam and diffuse solar radiation on a horizontal surface, by hours, which is useful in simulations of solar processes. (A few measurements are available on inclined surfaces and for shorter time intervals.) Daily data are often available and hourly radiation can be estimated from daily data. Monthly total solar radiation on a horizontal surface can be used in some process design methods. However, as process performance is generally not linear with solar radiation, the use of averages may lead to serious errors if nonlinearities are not taken into account. It is also possible to reduce radiation data to more manageable forms by statistical methods.

## 2.1 DEFINITIONS


Figure 2.1.1 shows the primary radiation fluxes on a surface at or near the ground that are important in connection with solar thermal processes. It is convenient to consider radiation in two wavelength ranges.<sup>1</sup>

**Solar or short-wave radiation** is radiation originating from the sun, in the wavelength range of 0.3 to 3  $\mu\text{m}$ . In the terminology used throughout this book, solar radiation includes both beam and diffuse components unless otherwise specified.

**Long-wave radiation** is radiation originating from sources at temperatures near ordinary ambient temperatures and thus substantially all at wavelengths greater than 3  $\mu\text{m}$ . Long-wave radiation is emitted by the atmosphere, by a collector, or by any other body at ordinary temperatures. (This radiation, if originating from the ground, is referred to in some literature as “terrestrial” radiation.)

---

<sup>1</sup>We will see in Chapters 3, 4, and 6 that the wavelength ranges of incoming solar radiation and emitted radiation from flat-plate solar collectors overlap to a negligible extent, and for many purposes the distinction noted here is very useful. For collectors operating at high enough temperatures there is significant overlap and more precise distinctions are needed.



**Figure 2.1.1** The radiant energy fluxes of importance in solar thermal processes. Short-wave solar radiation is shown by  $\rightarrow$ . Longwave radiation is shown by  $\curvearrowright$ .

Instruments for measuring solar radiation are of two basic types:

A **pyrheliometer** is an instrument using a collimated detector for measuring solar radiation from the sun and from a small portion of the sky around the sun (i.e., beam radiation) at normal incidence.

A **pyranometer** is an instrument for measuring total hemispherical solar (beam plus diffuse) radiation, usually on a horizontal surface. If shaded from the beam radiation by a shade ring or disc, a pyranometer measures diffuse radiation.

In addition, the terms **solarimeter** and **actinometer** are encountered; a solarimeter can generally be interpreted to mean the same as a pyranometer, and an actinometer usually refers to a pyrheliometer.

In the following sections we discuss briefly the two basic radiation instruments and the pyrheliometric scales that are used in solar radiometry. More detailed discussions of instruments, their use, and the associated terminology are found in Robinson (1966), World Meteorological Organization (WMO, 1969), Kondratyev (1969), Coulson (1975), Thekaekara (1976), Yellott (1977), and Iqbal (1983). Stewart et al. (1985) review characteristics of pyranometers and pyrheliometers.


## 2.2 PYRHELIOMETERS AND PYRHELIOMETRIC SCALES

Standard and secondary standard solar radiation instruments are pyrheliometers. The water flow pyrheliometer, designed by Abbot in 1905, was an early standard instrument. This instrument uses a cylindrical blackbody cavity to absorb radiation that is admitted through a collimating tube. Water flows around and over the absorbing cavity, and measurements of its temperature and flow rate provide the means for determining the absorbed energy. The design was modified by Abbot in 1932 to include the use of two thermally identical chambers, dividing the cooling water between them and heating one chamber electrically while the other is heated by solar radiation; when the instrument is adjusted so as to make the heat produced in the two chambers identical, the electrical power input is a measure of the solar energy absorbed.

Standard pyrheliometers are not easy to use, and secondary standard instruments have been devised that are calibrated against the standard instruments. The secondary standards in turn are used to calibrate field instruments. Robinson (1966) and Coulson (1975) provide detailed discussion and bibliography on this topic. Two of these secondary standard instruments are of importance.

The Abbot silver disc pyrheliometer, first built by Abbot in 1902 and modified in 1909 and 1927, uses a silver disc 38 mm in diameter and 7 mm thick as the radiation receiver. The side exposed to radiation is blackened, and the bulb of a precision mercury thermometer is inserted in a hole in the side of the disc and is in good thermal contact with the disc. The silver disc is suspended on wires at the end of a collimating tube, which in later models has dimensions such that 0.0013 of the hemisphere is “seen” by the detector. Thus any point on the detector sees an aperture angle of  $5.7^\circ$ . The disc is mounted in a copper cylinder, which in turn is in a cylindrical wood box that insulates the copper and the disc from the surroundings. A shutter alternately admits radiation and shades the detector at regular intervals; the corresponding changes in disc temperature are measured and provide the means to calculate the absorbed radiation. A section drawing of the pyrheliometer is shown in Figure 2.2.1.

The other secondary standard of particular importance is the Ångström compensation pyrheliometer, first constructed by K. Ångström in 1893 and modified in several developments since then. In this instrument two identical blackened manganin strips are arranged so that either one can be exposed to radiation at the base of collimating tubes by moving a reversible shutter. Each strip can be electrically heated, and each is fitted with a thermocouple. With one strip shaded and one strip exposed to radiation, a current is passed through the shaded strip to heat it to the same temperature as the exposed strip. When there is no difference in temperature, the electrical energy to the shaded strip must equal the solar radiation absorbed by the exposed strip. Solar radiation is determined by equating the electrical energy to the product of incident solar radiation, strip area, and absorptance. After a determination is made, the position of the shutter is reversed to interchange the electrical and radiation heating, and a second determination is made. Alternating the shade and the functions of the two strips compensates for minor differences in the strips such as edge effects and lack of uniformity of electrical heating.



**Figure 2.2.1** Schematic section of the Abbot silver disc pyrheliometer.


The Ångström instrument serves, in principle, as an absolute or primary standard. However, there are difficulties in applying correction factors in its use, and in practice there are several primary standard Ångström instruments to which those in use as secondary standards are compared.

The Abbot and Ångström instruments are used as secondary standards for calibration of other instruments, and there is a **pyrheliometric scale** associated with each of them. The first scale, based on measurements with the Ångström instrument, was established in 1905 (the Ångström scale of 1905, or AS05). The second, based on the Abbot silver disc pyrheliometer (which was in turn calibrated with a standard water flow pyrheliometer) was established in 1913 (the Smithsonian scale of 1913, or SS13).

Reviews of the accuracy of these instruments and intercomparisons of them led to the conclusions that measurements made on SS13 were 3.5% higher than those on AS05, that SS13 was 2% too high, and that AS05 was 1.5% too low. As a result, the **International Pyrheliometric Scale 1956** (IPS56) was adopted, reflecting these differences. Measurements made before 1956 on the scale AS05 were increased by 1.5%, and those of SS13 were decreased by 2% to correct them to IPS56.

Beginning with the 1956 International Pyrheliometer Comparisons (IPC), which resulted in IPS56, new comparisons have been made at approximately five-year intervals, under WMO auspices, at Davos, Switzerland. As a result of the 1975 comparisons, a new pyrheliometric scale, the **World Radiometric Reference** (WRR) (also referred to as the **Solar Constant Reference Scale**, SCRS) was established; it is 2.2% higher than the IPS56 scale. (SS13 is very close to WRR.)

Operational or field instruments are calibrated against secondary standards and are the source of most of the data on which solar process engineering designs must be based. Brief descriptions of two of these, the Eppley normal-incidence pyrheliometer (NIP) and the Kipp & Zonen actinometer, are included here. The Eppley NIP is the instrument in most common use in the United States for measuring beam solar radiation, and the Kipp & Zonen instrument is in wide use in Europe. A cross section of a recent model of the Eppley is shown in Figure 2.2.2. The instrument mounted on a tracking mechanism is shown in



**Figure 2.2.2** Cross section of the Eppley NIP. Courtesy of The Eppley Laboratory.





**Figure 2.2.3** An Eppley NIP on an altazimuth tracking mount. Courtesy of The Eppley Laboratory.

Figure 2.2.3. The detector is at the end of the collimating tube, which contains several diaphragms and is blackened on the inside. The detector is a multijunction thermopile coated with Parson's optical black. Temperature compensation to minimize sensitivity to variations in ambient temperature is provided. The aperture angle of the instrument is  $5.7^\circ$ , so the detector receives radiation from the sun and from an area of the circumsolar sky two orders of magnitude larger than that of the sun.

The Kipp & Zonen actinometer is based on the Linke-Feussner design and uses a 40-junction constantan-manganin thermopile with hot junctions heated by radiation and cold junctions in good thermal contact with the case. In this instrument the assembly of copper diaphragms and case has very large thermal capacity, orders of magnitude more than the hot junctions. On exposure to solar radiation the hot junctions rise quickly to temperatures above the cold junction; the difference in the temperatures provides a measure of the radiation. Other pyrheliometers were designed by Moll-Gorczynski, Yanishevskiy, and Michelson.

The dimensions of the collimating systems are such that the detectors are exposed to radiation from the sun and from a portion of the sky around the sun. Since the detectors do not distinguish between forward-scattered radiation, which comes from the circumsolar sky, and beam radiation, the instruments are, in effect, defining beam radiation. An experimental study by Jeys and Vant-Hull (1976) which utilized several lengths of collimating tubes so that the aperture angles were reduced in step from  $5.72^\circ$  to  $2.02^\circ$  indicated that for cloudless conditions this reduction in aperture angle resulted in insignificant changes in the measurements of beam radiation. On a day of thin uniform cloud cover, however, with solar altitude angle of less than  $32^\circ$ , as much as 11% of the measured intensity was received from the circumsolar sky between aperture angles of  $5.72^\circ$  and  $2.02^\circ$ . It is difficult to generalize from the few data available, but it appears that thin clouds or haze can affect the angular distribution of radiation within the field of view of standard pyrheliometers.

The WMO recommends that calibration of pyrheliometers only be undertaken on days in which atmospheric clarity meets or exceeds a minimum value.

## 2.3 PYRANOMETERS

Instruments for measuring total (beam plus diffuse) radiation are referred to as pyranometers, and it is from these instruments that most of the available data on solar radiation are obtained. The detectors for these instruments must have a response independent of wavelength of radiation over the solar energy spectrum. In addition, they should have a response independent of the angle of incidence of the solar radiation. The detectors of most pyranometers are covered with one or two hemispherical glass covers to protect them from wind and other extraneous effects; the covers must be very uniform in thickness so as not to cause uneven distribution of radiation on the detectors. These factors are discussed in more detail by Coulson (1975).

Commonly used pyranometers in the United States are the Eppley and Spectrolab instruments, in Europe the Moll-Gorczynski, in Russia the Yanishevskiy, and in Australia the Trickett-Norris (Groiss) pyranometer.


The Eppley 180° pyranometer was the most common instrument in the United States. It used a detector consisting of two concentric silver rings; the outer ring was coated with magnesium oxide, which has a high reflectance for radiation in the solar energy spectrum, and the inner ring was coated with Parson's black, which has a very high absorptance for solar radiation. The temperature difference between these rings was detected by a thermopile and was a measure of absorbed solar radiation. The circular symmetry of the detector minimized the effects of the surface azimuth angle on instrument response. The detector assembly was placed in a nearly spherical glass bulb, which has a transmittance greater than 0.90 over most of the solar radiation spectrum, and the instrument response was nearly independent of wavelength except at the extremes of the spectrum. The response of this Eppley was dependent on ambient temperature, with sensitivity decreasing by 0.05 to 0.15%/°C (Coulson, 1975); much of the published data taken with these instruments was not corrected for temperature variations. It is possible to add temperature compensation to the external circuit and remove this source of error. It is estimated that carefully used Eppleys of this type could produce data with less than 5% errors but that errors of twice this could be expected from poorly maintained instruments. The theory of this instrument has been carefully studied by MacDonald (1951).

The Eppley 180° pyranometer is no longer manufactured and has been replaced by other instruments. The Eppley black-and-white pyranometer utilizes Parson's-black- and barium-sulfate-coated hot and cold thermopile junctions and has better angular (cosine) response. It uses an optically ground glass envelope and temperature compensation to maintain calibration within  $\pm 1.5\%$  over a temperature range of  $-20$  to  $+40^\circ\text{C}$ . It is shown in Figure 2.3.1.

The Eppley precision spectral pyranometer (PSP) utilizes a thermopile detector, two concentric hemispherical optically ground covers, and temperature compensation that results in temperature dependence of 0.5% from  $-20$  to  $+40^\circ\text{C}$ . [Measurements of irradiance in spectral bands can be made by use of bandpass filters; the PSP can be fitted with hemispherical domes of filter glass for this purpose. See Stewart et al. (1985) for information and references.] It is shown in Figure 2.3.2.



**Figure 2.3.1** The Eppley black-and-white pyranometer. Courtesy of The Eppley Laboratory.



**Figure 2.3.2** The Eppley PSP. Courtesy of The Eppley Laboratory.

The Moll-Gorczyński pyranometer uses a Moll thermopile to measure the temperature difference of the black detector surface and the housing of the instrument. The thermopile assembly is covered with two concentric glass hemispherical domes to protect it from weather and is rectangular in configuration with the thermocouples aligned in a row (which results in some sensitivity to the azimuth angle of the radiation).

Pyranometers are usually calibrated against standard pyrhemimeters. A standard method has been set forth in the *Annals of the International Geophysical Year (IGY, 1958)*, which requires that readings be taken at times of clear skies, with the pyranometer shaded and unshaded at the same time as readings are taken with the pyrhemimeter. It is recommended that shading be accomplished by means of a disc held 1 m from the

pyranometer with the disc just large enough to shade the glass envelope. The calibration constant is then the ratio of the difference in the output of the shaded and unshaded pyranometer to the output of the pyrhelimeter multiplied by the calibration constant of the pyrhelimeter and  $\cos \theta_z$ , the angle of incidence of beam radiation on the horizontal pyranometer. Care and precision are required in these calibrations.

It is also possible, as described by Norris (1973), to calibrate pyranometers against a secondary standard pyranometer such as the Eppley precision pyranometer. This secondary standard pyranometer is thought to be good to  $\pm 1\%$  when calibrated against a standard pyrhelimeter. Direct comparison of the precision Eppley and field instruments can be made to determine the calibration constant of the field instruments.

A pyranometer (or pyrhelimeter) produces a voltage from the thermopile detectors that is a function of the incident radiation. It is necessary to use a potentiometer to detect and record this output. Radiation data usually must be integrated over some period of time, such as an hour or a day. Integration can be done by means of planimetry or by electronic integrators. It has been estimated that with careful use and reasonably frequent pyranometer calibration, radiation measurements should be good within  $\pm 5\%$ ; integration errors would increase this number. Much of the available radiation data prior to 1975 is probably not this good, largely because of infrequent calibration and in some instances because of inadequate integration procedures.

Another class of pyranometers, originally designed by Robitzsch, utilizes detectors that are bimetallic elements heated by solar radiation; mechanical motion of the element is transferred by a linkage to an indicator or recorder pen. These instruments have the advantage of being entirely spring driven and thus require no electrical energy. Variations of the basic design are manufactured by several European firms (Fuess, Casella, and SIAP). They are widely used in isolated stations and are a major source of the solar radiation data that are available for locations outside of Europe, Australia, Japan, and North America. Data from these instruments are generally not as accurate as that from thermopile-type pyranometers.


Another type of pyranometer is based on photovoltaic (solar cell) detectors. Examples are the LI-COR LI-200SA pyranometer and the Yellott solarimeter. They are less precise instruments than the thermopile instruments and have some limitations on their use. They are also less expensive than thermopile instruments and are easy to use.

The main disadvantage of photovoltaic detectors is their spectrally selective response. Figure 2.3.3 shows a typical terrestrial solar spectrum and the spectral response of a silicon solar cell. If the spectral distribution of incident radiation was fixed, a calibration could be established that would remain constant; however, there are some variations in spectral distribution<sup>2</sup> with clouds and atmospheric water vapor. LI-COR estimates that the error introduced because of spectral response is  $\pm 5\%$  maximum under most conditions of natural daylight and is  $\pm 3\%$  under typical conditions.

Photovoltaic detectors have additional characteristics of interest. Their response to changing radiation levels is essentially instantaneous and is linear with radiation. The temperature dependence is  $\pm 0.15\%/^{\circ}\text{C}$  maximum. The LI-COR instrument is fitted with an acrylic diffuser that substantially removes the dependence of response on the angle of incidence of the radiation. The response of the detectors is independent of its orientation,

---

<sup>2</sup>This will be discussed in Section 2.6.




**Figure 2.3.3** Spectral distribution of extraterrestrial solar radiation and spectral response of a silicon solar cell. From Coulson (1975).

but reflected radiation from the ground or other surroundings will in general have a different spectral distribution than global horizontal radiation, and measurements on surfaces receiving significant amounts of reflected radiation will be subject to additional errors.


The preceding discussion dealt entirely with measurements of total radiation on a horizontal surface. Two additional kinds of measurements are made with pyranometers: measurements of diffuse radiation on horizontal surfaces and measurements of solar radiation on inclined surfaces.

Measurements of diffuse radiation can be made with pyranometers by shading the instrument from beam radiation. This is usually done by means of a shading ring, as shown in Figure 2.3.4. The ring is used to allow continuous recording of diffuse radiation without the necessity of continuous positioning of smaller shading devices; adjustments need to be made for changing declination only and can be made every few days. The ring shades the pyranometer from part of the diffuse radiation, and a correction for this shading must be estimated and applied to the observed diffuse radiation (Drummond, 1956, 1964; *IGY*, 1958; Coulson, 1975). The corrections are based on assumptions of the distribution of diffuse radiation over the sky and typically are factors of 1.05 to 1.2. An example of shade ring correction factors, to illustrate their trends and magnitudes, is shown in Figure 2.3.5.

Measurements of solar radiation on inclined planes are important in determining the input to solar collectors. There is evidence that the calibration of pyranometers changes if the instrument is inclined to the horizontal. The reason for this appears to be changes in the convection patterns inside the glass dome, which changes the manner in which heat is transferred from the hot junctions of the thermopiles to the cover and other parts of the instrument. The Eppley 180° pyranometer has been variously reported to show a decrease in sensitivity on inversion from 5.5% to no decrease. Norris (1974) measured the response at various inclinations of four pyranometers when subject to radiation from an incandescent lamp source and found correction factors at inclinations of 90° in the range of 1.04 to 1.10. Stewart et al. (1985) plot two sets of data of Latimer (1980) which show smaller correction




**Figure 2.3.4** Pyranometer with shading ring to eliminate beam radiation. Courtesy of The Eppley Laboratory.



**Figure 2.3.5** Typical shade ring correction factors to account for shading of the detector from diffuse radiation. Adapted from Coulson (1975).

factors. Figure 2.3.6 shows the set with the greater factors, with the Eppley PSP showing maximum positive effects at  $\beta = 90^\circ$  of 2.5% and smaller corrections for Kipp & Zonen instruments. There are thus disagreements of the magnitude of the corrections, but for the instruments shown, the corrections are of the order of 1 or 2%.

It is evident from these data and other published results that the calibration of pyranometers is to some degree dependent on inclination and that experimental information



**Figure 2.3.6** Effects of inclination of pyranometers on calibration. The instruments are the Eppley PSP, the Eppley 8–48, and the Kipp & Zonen CM6. Adapted from Stewart et al. (1985).

is needed on a particular pyranometer in any orientation to adequately interpret information from it.

The Bellani spherical distillation pyranometer is based on a different principle. It uses a spherical container of alcohol that absorbs solar radiation. The sphere is connected to a calibrated condenser receiver tube. The quantity of alcohol condensed is a measure of integrated solar energy on the spherical receiver. Data on the total energy received by a body, as represented by the sphere, are of interest in some biological processes.

## 2.4 MEASUREMENT OF DURATION OF SUNSHINE

The hours of bright sunshine, that is, the time in which the solar disc is visible, is of some use in estimating long-term averages of solar radiation.<sup>3</sup> Two instruments have been or are widely used. The Campbell-Stokes sunshine recorder uses a solid glass sphere of approximately 10 cm diameter as a lens that produces an image of the sun on the opposite surface of the sphere. A strip of standard treated paper is mounted around the appropriate part of the sphere, and the solar image burns a mark on the paper whenever the beam radiation is above a critical level. The lengths of the burned portions of the paper provide an index of the duration of “bright sunshine.” These measurements are uncertain on several counts: The interpretation of what constitutes a burned portion is uncertain, the instrument does not respond to low levels of radiation early and late in the day, and the condition of the paper may be dependent on humidity.

A photoelectric sunshine recorder, the Foster sunshine switch (Foster and Foskett, 1953), is now in use by the U.S. Weather Service. It incorporates two selenium photovoltaic cells, one of which is shaded from beam radiation and one exposed to it. In the absence of beam radiation, the two detectors indicate (nearly) the same radiation level. When beam radiation is incident on the unshaded cell, the output of that cell is higher than that of the shaded cell. The duration of a critical radiation difference detected by the two cells is a measure of the duration of bright sunshine.


<sup>3</sup>The relationship between sunshine hours and solar radiation is discussed in Section 2.7.

## 2.5 SOLAR RADIATION DATA

Solar radiation data are available in several forms. The following information about radiation data is important in their understanding and use: whether they are instantaneous measurements (irradiance) or values integrated over some period of time (irradiation) (usually hour or day); the time or time period of the measurements; whether the measurements are of beam, diffuse, or total radiation; the instruments used; the receiving surface orientation (usually horizontal, sometimes inclined at a fixed slope, or normal to the beam radiation); and, if averaged, the period over which they are averaged (e.g., monthly averages of daily radiation).

Most radiation data available are for horizontal surfaces, include both direct and diffuse radiation, and were measured with thermopile pyranometers (or in some cases Robitzsch-type instruments). Most of these instruments provide radiation records as a function of time and do not themselves provide a means of integrating the records. The data were usually recorded in a form similar to that shown in Figure 2.5.1 by recording potentiometers and were integrated graphically. Uncertainties in integration add to uncertainties in pyranometer response; electronic integration is now common.

Two types of solar radiation data are widely available. The first is monthly average daily total radiation on a horizontal surface,  $\overline{H}$ . The second is hourly total radiation on a horizontal surface,  $I$ , for each hour for extended periods such as one or more years. The  $\overline{H}$  data are widely available and are given for many stations in Appendix D. The



**Figure 2.5.1** Total (beam and diffuse) solar radiation on a horizontal surface versus time for clear and largely cloudy day, latitude  $43^\circ$ , for days near equinox.



traditional units have been calories per square centimeter; the data in Appendix D are in the more useful megajoules per square meter. These data are available from weather services (e.g., NSRDB, 1991–2005) and the literature [e.g., from the Commission of the European Communities (CEC) *European Solar Radiation Atlas* (1984) and Löf et al. (1966a,1966b)]. The WMO sponsors compilation of solar radiation data at the World Radiation Data Center; these are published in *Solar Radiation and Radiation Balance Data (The World Network)*, an annual publication.

The accuracy of some of the earlier (pre-1970) data is generally less than desirable, as standards of calibration and care in use of instruments and integration have not always been adequate.<sup>4</sup> Recent measurements and the averages based thereon are probably good to  $\pm 5\%$ . Most of the older average data are probably no better than  $\pm 10\%$ , and for some stations a better estimate may be  $\pm 20\%$ . Substantial inconsistencies are found in data from different sources for some locations.

A very extensive and carefully compiled monthly average daily solar radiation database is available for Europe and part of the Mediterranean basin. Volume 1 of the *European Solar Radiation Atlas* (CEC, 1984), is based on pyranometric data from 139 stations in 29 countries. It includes solar radiation derived from sunshine hour data for 315 stations (with 114 of the stations reporting both) for a total of 340 stations. Ten years of data were used for each station except for a few where data for shorter periods were available. The data and the instruments used to obtain them were carefully evaluated, corrections were made to compensate for instrumental errors, and all data are based on the WRR pyr heliometric scale. The *Atlas* includes<sup>5</sup> tables that show averages, maxima, minima, extraterrestrial radiation, and sunshine hours. Appendix D includes some data from the *Atlas*.

Average daily solar radiation data are also available from maps that indicate general trends. For example, a world map is shown in Figure 2.5.2 (Löf et al., 1966a,b).<sup>6</sup> In some geographical areas where climate does not change abruptly with distance (i.e., away from major influences such as mountains or large industrial cities), maps can be used as a source of average radiation if data are not available. However, large-scale maps must be used with care because they do not show local physical or climatological conditions that may greatly affect local solar energy availability.


For calculating the dynamic behavior of solar energy equipment and processes and for simulations of long-term process operation, more detailed solar radiation data (and related meteorological information) are needed. An example of this type of data (hourly integrated radiation, ambient temperature, and wind speed) is shown in Table 2.5.1 for a January week in Boulder, Colorado. Additional information may also be included in these records, such as wet bulb temperature and wind direction.

In the United States there has been a network of stations recording solar radiation on a horizontal surface and reporting it as daily values. Some of these stations also reported hourly radiation. In the 1970s, the U.S. National Oceanic and Atmospheric Administration (NOAA) undertook a program to upgrade the number and quality of the

<sup>4</sup>The *SOLMET* (1978) program of the U.S. Weather Service has addressed this problem by careful study of the history of individual instruments and their calibrations and subsequent “rehabilitation” of the data to correct for identifiable errors. The U.S. data in Appendix D have been processed in this way.

<sup>5</sup>Monthly average daily radiation on surfaces other than horizontal are in Volume II of the *Atlas*.

<sup>6</sup>Figure 2.5.2 is reproduced from deJong (1973), who redrew maps originally published by Löf et al. (1966a). deJong has compiled maps and radiation data from many sources.



**Figure 2.5.2** Average daily radiation on horizontal surfaces for December. Data are in cal/cm<sup>2</sup>, the traditional units. Adapted from deJong (1973) and Lóf et al. (1966a).

**Table 2.5.1** Hourly Radiation for Hour Ending at Indicated Time, Air Temperature, and Wind Speed Data for January Week, Boulder, Colorado (Latitude = 40 °N, Longitude = 105 W)

Day	Hour	$I$ (kJ/m <sup>2</sup> )	$T_a$ (°C)	$V$ (m/s)	Day	Hour	$I$ (kJ/m <sup>2</sup> )	$T_a$ (°C)	$V$ (m/s)
8	1	0	-1.7	3.1	8	13	1105	2.8	8.0
8	2	0	-3.3	3.1	8	14	1252	3.8	9.8
8	3	0	-2.8	3.1	8	15	641	3.3	9.8
8	4	0	-2.2	3.1	8	16	167	2.2	7.2
8	5	0	-2.8	4.0	8	17	46	0.6	7.6
8	6	0	-2.8	3.6	8	18	0	-0.6	7.2
8	7	0	-2.2	3.6	8	19	0	-1.1	8.0
8	8	17	-2.2	4.0	8	20	0	-1.7	5.8
8	9	134	-1.1	1.8	8	21	0	-1.7	5.8
8	10	331	1.1	3.6	8	22	0	-2.2	7.2
8	11	636	2.2	1.3	8	23	0	-2.2	6.3
8	12	758	2.8	2.2	8	24	0	-2.2	5.8
9	1	0	-2.8	7.2	9	13	1185	-2.2	2.2
9	2	0	-3.3	7.2	9	14	1009	-1.3	1.7
9	3	0	-3.3	6.3	9	15	796	-0.6	1.3
9	4	0	-3.3	5.8	9	16	389	-0.6	1.3
9	5	0	-3.9	4.0	9	17	134	-2.2	4.0
9	6	0	-3.9	4.5	9	18	0	-2.8	4.0
9	7	0	-3.9	1.8	9	19	0	-3.3	4.5
9	8	4	-3.9	2.2	9	20	0	-5.6	5.8
9	9	71	-3.9	2.2	9	21	0	-6.7	5.4
9	10	155	-3.3	4.0	9	22	0	-7.8	5.8
9	11	343	-2.8	4.0	9	23	0	-8.3	4.5
9	12	402	-2.2	4.0	9	24	0	-8.3	6.3
10	1	0	-9.4	5.8	10	13	1872	2.2	7.6
10	2	0	-10.0	6.3	10	14	1733	4.4	6.7
10	3	0	-8.9	5.8	10	15	1352	6.1	6.3
10	4	0	-10.6	6.3	10	16	775	6.7	4.0
10	5	0	-8.3	4.9	10	17	205	6.1	2.2
10	6	0	-8.3	7.2	10	18	4	3.3	4.5
10	7	0	-10.0	5.8	10	19	0	0.6	4.0
10	8	33	-8.9	5.8	10	20	0	0.6	3.1
10	9	419	-7.2	6.7	10	21	0	0.0	2.7
10	10	1047	-5.0	9.4	10	22	0	0.6	2.2
10	11	1570	-2.2	8.5	10	23	0	1.7	3.6
10	12	1805	-1.1	8.0	10	24	0	0.6	2.7
11	1	0	-1.7	8.9	11	13	138	-5.0	6.7
11	2	0	-2.2	4.9	11	14	96	-3.9	6.7
11	3	0	-2.2	4.5	11	15	84	-4.4	7.6
11	4	0	-2.8	5.8	11	16	42	-3.9	6.3
11	5	0	-4.4	5.4	11	17	4	-5.0	6.3

(Continued)

**Table 2.5.1** (Continued)

Day	Hour	$I$ (kJ/m <sup>2</sup> )	$T_a$ (°C)	$V$ (m/s)	Day	Hour	$I$ (kJ/m <sup>2</sup> )	$T_a$ (°C)	$V$ (m/s)
11	6	0	-5.0	4.5	11	18	0	-5.6	4.5
11	7	0	-5.6	3.6	11	19	0	-6.7	4.5
11	8	4	-6.1	5.8	11	20	0	-7.8	3.1
11	9	42	-5.6	5.4	11	21	0	-9.4	2.7
11	10	92	-5.6	5.4	11	22	0	-8.9	3.6
11	11	138	-5.6	9.4	11	23	0	-9.4	4.0
11	12	163	-5.6	8.0	11	24	0	-11.1	3.1
12	1	0	-11.7	4.0	12	13	389	-2.2	5.8
12	2	0	-12.8	3.1	12	14	477	-0.6	4.0
12	3	0	-15.6	7.2	12	15	532	2.8	2.2
12	4	0	-16.7	6.7	12	16	461	-0.6	2.2
12	5	0	-16.7	6.3	12	17	33	-1.7	3.1
12	6	0	-16.1	6.3	12	18	0	-4.4	1.3
12	7	0	-17.2	3.6	12	19	0	-7.8	2.7
12	8	17	-17.8	2.7	12	20	0	-7.8	4.0
12	9	71	-13.3	8.0	12	21	0	-8.9	4.9
12	10	180	-11.1	8.9	12	22	0	-10.6	4.9
12	11	247	-7.8	8.5	12	23	0	-12.8	4.9
12	12	331	-5.6	7.6	12	24	0	-11.7	5.4
13	1	0	-10.6	4.0	13	13	1926	5.6	5.4
13	2	0	-10.6	5.4	13	14	1750	7.2	4.5
13	3	0	-10.0	4.5	13	15	1340	8.3	4.9
13	4	0	-11.1	3.1	13	16	703	8.9	4.5
13	5	0	-10.6	3.6	13	17	59	6.7	5.4
13	6	0	-9.4	3.1	13	18	0	4.4	3.6
13	7	0	-7.2	3.6	13	19	0	1.1	3.6
13	8	17	-10.6	4.0	13	20	0	0.0	3.1
13	9	314	-8.3	5.8	13	21	0	-2.2	6.7
13	10	724	-1.7	6.7	13	22	0	2.8	7.2
13	11	1809	1.7	5.4	13	23	0	1.7	8.0
13	12	2299	3.3	6.3	13	24	0	1.7	5.8
14	1	0	-0.6	7.2	14	13	1968	6.7	1.8
14	2	0	-1.1	7.6	14	14	1733	6.7	2.7
14	3	0	-0.6	6.3	14	15	1331	7.2	3.1
14	4	0	-3.9	2.7	14	16	837	6.7	3.1
14	5	0	-1.7	4.9	14	17	96	7.2	2.7
14	6	0	-2.8	5.8	14	18	4	3.3	2.7
14	7	0	-2.8	4.0	14	19	0	0.0	3.6
14	8	38	-5.0	3.1	14	20	0	3.9	5.4
14	9	452	-5.0	4.9	14	21	0	-3.9	3.6
14	10	1110	-1.7	4.5	14	22	0	-3.9	5.8
14	11	1608	2.8	3.1	14	23	0	-6.1	5.4
14	12	1884	3.8	3.6	14	24	0	-6.7	6.3

radiation measuring stations, to rehabilitate past data (to account for sensor deterioration, calibration errors, and changes in pyrheliometric scales), and to make these data available (with related meteorological data) on magnetic tapes. In 1978, corrected data tapes of hourly meteorological information (including solar radiation on a horizontal surface based on the SCRC) for 26 stations over a period of 23 years became available. These tapes are referred to as the SOLMET tapes and are described in detail in the *SOLMET Manual* (1978).

In the late 1970s, the U.S. federal government funded the development and operation of a national solar radiation network (SOLRAD). Measurements of hourly total horizontal and direct normal radiation were made at the 38 stations that were part of the network. Eleven of the stations also measured diffuse radiation. Data for 1977 to 1980 were checked for quality and are available from the National Climatic Data Center. Funding for much of the program was reduced in 1981, and by 1985 the network was shut down. Since then, some additional funding has become available to upgrade the instrumentation at many of the stations to automate data acquisition and recalibrate pyranometers.

Many national weather services have produced typical meteorological year (TMY) data sets for specific locations that represent the average weather conditions over time periods such as 30 years. These data sets typically contain hourly values of solar radiation, ambient temperature, humidity, wind speed, wind direction, and other weather data. The data are intended to be used in the prediction of the long-term performance of solar systems. The data should not be used to predict performance under extreme conditions or the performance of wind systems. The monthly average data for the U.S. stations shown in Appendix D are derived from TMY2 data, a data set that was developed from weather data for the period 1961 to 1990 and is available from the National Renewable Energy Laboratory (NREL) website. TMY3 data for the period 1991 to 2005 is also available from the NREL website.

The time recorded for hourly weather data is not consistent among various databases. For example, the original TMY data set from the United States uses local solar time. Most new data sets, including TMY2 data, use local standard clock time (i.e., it does not account for daylight savings time). Consequently, in an office building energy simulation the occupancy schedule must be shifted by 1 h at the start and end of daylight savings time. Some computer programs do this shift automatically. Equation 1.5.2 can be used to convert between the recorded time and local solar time.

## 2.6 ATMOSPHERIC ATTENUATION OF SOLAR RADIATION

Solar radiation at normal incidence received at the surface of the earth is subject to variations due to change in the extraterrestrial radiation as noted in Chapter 1 and to two additional and more significant phenomena: (1) atmospheric scattering by air molecules, water, and dust and (2) atmospheric absorption by  $O_3$ ,  $H_2O$ , and  $CO_2$ . Iqbal (1983) reviews these matters in considerable detail.

**Scattering** of radiation as it passes through the atmosphere is caused by interaction of the radiation with air molecules, water (vapor and droplets), and dust. The degree to which scattering occurs is a function of the number of particles through which the radiation must pass and the size of the particles relative to  $\lambda$ , the wavelength of the radiation. The

pathlength of the radiation through air molecules is described by the air mass. The particles of water and dust encountered by the radiation depend on air mass and on the time- and location-dependent quantities of dust and moisture present in the atmosphere.

Air molecules are very small relative to the wavelength of the solar radiation, and scattering occurs in accordance with the theory of Rayleigh (i.e., the scattering coefficient varies with  $\lambda^{-4}$ ). Rayleigh scattering is significant only at short wavelengths; above  $\lambda = 0.6 \mu\text{m}$  it has little effect on atmospheric transmittance.

Dust and water in the atmosphere tend to be in larger particle sizes due to aggregation of water molecules and condensation of water on dust particles of various sizes. These effects are more difficult to treat than the effects of Rayleigh scattering by air molecules, as the nature and extent of dust and moisture particles in the atmosphere are highly variable with location and time. Two approaches have been used to treat this problem. Moon (1940) developed a transmission coefficient for precipitable water [the amount of water (vapor plus liquid) in the air column above the observer] that is a function of  $\lambda^{-2}$  and a coefficient for dust that is a function of  $\lambda^{-0.75}$ . Thus these transmittances are less sensitive to wavelength than is the Rayleigh scattering. The overall transmittance due to scattering is the product of three transmittances, which are three different functions of  $\lambda$ .

The second approach to estimation of effects of scattering by dust and water is by use of Ångström's turbidity equation. An equation for atmospheric transmittance due to aerosols, based on this equation, can be written as

$$\tau_{a,\lambda} = \exp(-\beta\lambda^{-\alpha}m) \quad (2.6.1)$$


where  $\beta$  is the Ångström turbidity coefficient,  $\alpha$  is a single lumped wavelength exponent,  $\lambda$  is the wavelength in micrometers, and  $m$  is the air mass along the path of interest. Thus there are two parameters,  $\beta$  and  $\alpha$ , that describe the atmospheric turbidity and its wavelength dependence;  $\beta$  varies from 0 to 0.4 for very clean to very turbid atmospheres,  $\alpha$  depends on the size distribution of the aerosols (a value of 1.3 is commonly used). Both  $\beta$  and  $\alpha$  vary with time as atmospheric conditions change.

More detailed discussions of scattering are provided by Fritz (1958), who included effects of clouds, by Thekaekara (1974) in a review, and by Iqbal (1983).


**Absorption** of radiation in the atmosphere in the solar energy spectrum is due largely to ozone in the ultraviolet and to water vapor and carbon dioxide in bands in the infrared. There is almost complete absorption of short-wave radiation by ozone in the upper atmosphere at wavelengths below  $0.29 \mu\text{m}$ . Ozone absorption decreases as  $\lambda$  increases above  $0.29 \mu\text{m}$ , until at  $0.35 \mu\text{m}$  there is no absorption. There is also a weak ozone absorption band near  $\lambda = 0.6 \mu\text{m}$ .

Water vapor absorbs strongly in bands in the infrared part of the solar spectrum, with strong absorption bands centered at 1.0, 1.4, and  $1.8 \mu\text{m}$ . Beyond  $2.5 \mu\text{m}$ , the transmission of the atmosphere is very low due to absorption by  $\text{H}_2\text{O}$  and  $\text{CO}_2$ . The energy in the extraterrestrial spectrum at  $\lambda > 2.5 \mu\text{m}$  is less than 5% of the total solar spectrum, and energy received at the ground at  $\lambda > 2.5 \mu\text{m}$  is very small.

The effects of Rayleigh scattering by air molecules and absorption by  $\text{O}_3$ ,  $\text{H}_2\text{O}$ , and  $\text{CO}_2$  on the spectral distribution of beam irradiance are shown in Figure 2.6.1 for an atmosphere with  $\beta = 0$  and 2 cm of precipitable water,  $w$ . The WRC extraterrestrial distribution is shown as a reference. The Rayleigh scattering is represented by the difference



**Figure 2.6.1** An example of the effects of Raleigh scattering and atmospheric absorption on the spectral distribution of beam irradiance. Adapted from Iqbal (1983).




**Figure 2.6.2** An example of spectral distribution of beam irradiance for air masses of 0, 1, 2, and 5. Adapted from Iqbal (1983).


between the extraterrestrial curve and the curve at the top of the shaded areas; its effect becomes small at wavelengths greater than about  $0.7 \mu m$ . The several absorption bands are shown by the shaded areas.

The effect of air mass is illustrated in Figure 2.6.2, which shows the spectral distribution of beam irradiance for air masses of 0 (the extraterrestrial curve), 1, 2, and 5 for an atmosphere of low turbidity.<sup>7</sup>

<sup>7</sup>The broadband (i.e., all wavelengths) transmittance of the atmosphere for beam normal radiation can be estimated by the method presented in Section 2.8.



**Figure 2.6.3** Relative energy distribution of total and diffuse radiation for a clear sky. Data from SMARTS.



**Figure 2.6.4** An example of calculated total, beam, and diffuse spectral irradiances on a horizontal surface for typical clear atmosphere. Adapted from Iqbal (1983).

The spectral distribution of total radiation depends also on the spectral distribution of the diffuse radiation. Some measurements are available in the ultraviolet and visible portions of the spectrum (Robinson, 1966; Kondratyev, 1969), which has led to the conclusion that in the wavelength range 0.35 to 0.80  $\mu\text{m}$  the distribution of the diffuse radiation is similar to that of the total beam radiation.<sup>8</sup> Figure 2.6.3 shows relative data on spectral distribution of total and diffuse radiation for a clear sky. The diffuse component has a distribution similar to the total but shifted toward the short-wave end of the spectrum; this is consistent with scattering theory, which indicates more scatter at shorter wavelengths. Fritz (1958) suggests that the spectrum of an overcast sky is similar to that for a clear sky. Iqbal (1983) uses calculated spectral distributions like that of Figure 2.6.4 to show that for typical atmospheric conditions most of the radiation at wavelengths longer than 1  $\mu\text{m}$

<sup>8</sup>Scattering theory predicts that shorter wavelengths are scattered most, and hence diffuse radiation tends to be at shorter wavelengths. Thus, clear skies are blue.



is beam, that scattering is more important at shorter wavelengths, and that the spectral distribution of diffuse is dependent on atmospheric conditions.

For most practical engineering purposes, the spectral distribution of solar radiation can be considered as approximately the same for the beam and diffuse components. It may also be observed that there is no practical alternative; data on atmospheric conditions on which to base any other model are seldom available.

For purposes of calculating properties of materials (absorptance, reflectance, and transmittance) that depend on the spectral distribution of solar radiation, it is convenient to have a representative distribution of terrestrial solar radiation in tabular form. Wiebelt and Henderson (1979) have prepared such tables for several air masses (zenith angles) and atmospheric conditions based on the National Aeronautics and Space Administration (NASA) spectral distribution curves and a solar constant of  $1353 \text{ W/m}^2$ . These can be used with little error for most engineering calculations with the more recent value of  $G_{sc}$  of  $1367 \text{ W/m}^2$ . Programs such as SMARTS (Gueymard, 2005) are available to calculate the spectral energy arriving at the earth's surface for various atmospheric conditions. Table 2.6.1 shows the terrestrial spectrum divided into 20 equal increments of energy, with a mean wavelength for each increment that divides that increment into two equal parts. This table is for a relatively clear atmosphere with air mass 1.5. It can be used as a typical distribution of terrestrial solar radiation.

**Table 2.6.1** ASTM G173-03 Air Mass 1.5 Reference Terrestrial Spectral Distribution of Beam Normal Plus Circumsolar Diffuse Radiation in Equal Increments of Energy<sup>a</sup>

Energy Band (%)	Wavelength Range (Nanometers)	Midpoint Wavelength (Nanometers)
0–5	280–416	385
5–10	416–458	439
10–15	458–492	475
15–20	492–525	508
20–25	525–559	542
25–30	559–592	575
30–35	592–627	609
35–40	627–662	644
40–45	662–700	680
45–50	700–741	719
50–55	741–786	764
55–60	786–835	808
60–65	835–885	859
65–70	885–970	917
70–75	970–1038	100
75–80	1038–1140	107
80–85	1140–1257	120
85–90	1257–1541	131
90–95	1541–1750	163
95–100	1750–4000	219

<sup>a</sup>Derived from SMARTS v 2.9.2.

In summary, the normal solar radiation incident on the earth's atmosphere has a spectral distribution indicated by Figure 1.3.1. The x-rays and other very short wave radiation of the solar spectrum are absorbed high in the ionosphere by nitrogen, oxygen, and other atmospheric components. Most of the ultraviolet is absorbed by ozone. At wavelengths longer than  $2.5\ \mu\text{m}$ , a combination of low extraterrestrial radiation and strong absorption by  $\text{CO}_2$  means that very little energy reaches the ground. Thus, from the viewpoint of terrestrial applications of solar energy, only radiation of wavelengths between 0.29 and  $2.5\ \mu\text{m}$  need be considered.

## 2.7 ESTIMATION OF AVERAGE SOLAR RADIATION

Radiation data are the best source of information for estimating average incident radiation. Lacking these or data from nearby locations of similar climate, it is possible to use empirical relationships to estimate radiation from hours of sunshine or cloudiness. Data on average hours of sunshine or average percentage of possible sunshine hours are widely available from many hundreds of stations in many countries and are usually based on data taken with Campbell-Stokes instruments. Examples are shown in Table 2.7.1. Cloud cover data (i.e., cloudiness) are also widely available but are based on visual estimates and are probably less useful than hours of sunshine data.

The original Ångström-type regression equation related monthly average daily radiation to clear-day radiation at the location in question and average fraction of possible sunshine hours:

$$\frac{\overline{H}}{\overline{H}_c} = a' + b' \frac{\overline{n}}{\overline{N}} \quad (2.7.1)$$

**Table 2.7.1** Examples of Monthly Average Hours per Day of Sunshine by Latitude and Altitude

Location	Hong Kong,	Paris,	Bombay,	Sokoto,	Perth,	Madison,
Latitude	22° N,	48° N,	India,	Nigeria,	Australia,	Wisconsin,
Altitude,	22° N,	48° N,	19° N,	13° N,	32° S,	43° N,
m	Sea Level	50 m	Sea Level	107 m	20 m	270 m
January	4.7	2.1	9.0	9.9	10.4	4.5
February	3.5	2.8	9.3	9.6	9.8	5.7
March	3.1	4.9	9.0	8.8	8.8	6.9
April	3.8	7.4	9.1	8.9	7.5	7.5
May	5.0	7.1	9.3	8.4	5.7	9.1
June	5.3	7.6	5.0	9.5	4.8	10.1
July	6.7	8.0	3.1	7.0	5.4	9.8
August	6.4	6.8	2.5	6.0	6.0	10.0
September	6.6	5.6	5.4	7.9	7.2	8.6
October	6.8	4.5	7.7	9.6	8.1	7.2
November	6.4	2.3	9.7	10.0	9.6	4.2
December	5.6	1.6	9.6	9.8	10.4	3.9
Annual	5.3	5.1	7.4	8.8	7.8	7.3

where  $\overline{H}$  = monthly average daily radiation on horizontal surface  
 $\overline{H}_c$  = average clear-sky daily radiation for location and month in question  
 $a', b'$  = empirical constants  
 $\overline{n}$  = monthly average daily hours of bright sunshine  
 $\overline{N}$  = monthly average of maximum possible daily hours of bright sunshine  
 (i.e., day length of average day of month)

A basic difficulty with Equation 2.7.1 lies in the ambiguity of the terms  $\overline{n}/\overline{N}$  and  $\overline{H}_c$ . The former is an instrumental problem (records from sunshine recorders are open to interpretation). The latter stems from uncertainty in the definition of a clear day. Page (1964) and others have modified the method to base it on extraterrestrial radiation on a horizontal surface rather than on clear-day radiation:

$$\frac{\overline{H}}{\overline{H}_o} = a + b \frac{\overline{n}}{\overline{N}} \quad (2.7.2)$$

where  $\overline{H}_o$  is the extraterrestrial radiation for the location averaged over the time period in question and  $a$  and  $b$  are constants depending on location. The ratio  $\overline{H}/\overline{H}_o$  is termed the monthly average clearness index and will be used frequently in later sections and chapters.

Values of  $\overline{H}_o$  can be calculated from Equation 1.10.3 using day numbers from Table 1.6.1 for the mean days of the month or it can be obtained from either Table 1.10.1 or Figure 1.10.1. The average day length  $\overline{N}$  can be calculated from Equation 1.6.11 or it can be obtained from Figure 1.6.3 for the mean day of the month as indicated in Table 1.6.1. Löff et al. (1966a) developed sets of constants  $a$  and  $b$  for various climate types and locations based on radiation data then available. These are given in Table 2.7.2.

The following example is based on Madison data (although the procedure is not recommended for a station where there are data) and includes comparisons of the estimated radiation with TMY3 data and estimates for Madison based on the Blue Hill constants (those which might have been used in the absence of constants for Madison)

### Example 2.7.1

Estimate the monthly averages of total solar radiation on a horizontal surface for Madison, Wisconsin, latitude  $43^\circ$ , based on the average duration of sunshine hour data of Table 2.7.1.

### Solution

The estimates are based on Equation 2.7.2 using constants  $a = 0.30$  and  $b = 0.34$  from Table 2.7.2. Values of  $\overline{H}_o$  are obtained from either Table or Figure 1.10.1 and day lengths from Equation 1.6.11, each for the mean days of the month. The desired estimates are obtained in the following table, which shows daily  $\overline{H}$  in MJ/m<sup>2</sup>. (For comparison, TMY3 data for Madison are shown, and in the last column estimates of Madison radiation determined by using constants  $a$  and  $b$  for Blue Hill.)

Month	$\overline{H}_o$ (MJ/m <sup>2</sup> )	$\overline{N}$ (h)	$\overline{n}/\overline{N}$	Estimated $\overline{H}$ (MJ/m <sup>2</sup> )	Measured $\overline{H}^a$ (MJ/m <sup>2</sup> )	Estimated $\overline{H}^b$ (MJ/m <sup>2</sup> )
January	13.36	9.2	0.49	6.3	6.9	6.2
February	18.80	10.3	0.55	9.2	9.7	9.3
March	26.01	11.7	0.59	13.0	13.1	13.4
April	33.75	13.2	0.57	16.6	16.9	17.0
May	39.39	14.5	0.63	20.2	21.0	21.0
June	41.74	15.2	0.67	22.0	23.4	23.1
July	40.52	14.0	0.66	21.2	22.2	22.2
August	35.88	13.8	0.73	19.6	19.6	20.9
September	28.77	12.3	0.70	15.5	14.5	16.4
October	20.89	19.8	0.67	11.0	9.7	11.6
November	14.61	9.5	0.44	6.6	6.2	6.4
December	11.90	8.8	0.44	5.4	5.6	5.3

<sup>a</sup>From TMY3 data.

<sup>b</sup>Using constants for Blue Hill.

The agreement between measured and calculated radiation is reasonably good, even though the constants  $a$  and  $b$  for Madison were derived from a different database from the measured data. If we did not have constants for Madison and had to choose a climate close to that of Madison, Blue Hill would be a reasonable choice. The estimated averages using the Blue Hill constants are shown in the last column. The trends are shown, but the agreement is not as good. This is the more typical situation in the use of Equation 2.7.2. ■

Data are also available on mean monthly cloud cover  $\overline{C}$ , expressed as tenths of the sky obscured by clouds. Empirical relationships have been derived to relate monthly average daily radiation  $\overline{H}$  to monthly average cloud cover  $\overline{C}$ . These are usually of the form

$$\frac{\overline{H}}{\overline{H}_o} = a'' + b''\overline{C} \quad (2.7.3)$$

Norris (1968) reviewed several attempts to develop such a correlation. Bennett (1965) compared correlations of  $\overline{H}/\overline{H}_o$  with  $\overline{C}$ , with  $\overline{n}/\overline{N}$ , and with a combination of the two variables and found the best correlation to be with  $\overline{n}/\overline{N}$ , that is, Equation 2.7.2. Cloud cover data are estimated visually, and there is not necessarily a direct relationship between the presence of partial cloud cover and solar radiation at any particular time. Thus there may not be as good a statistical relationship between  $\overline{H}/\overline{H}_o$  and  $\overline{C}$  as there is between  $\overline{H}/\overline{H}_o$  and  $\overline{n}/\overline{N}$ . Many surveys of solar radiation data (e.g., Bennett, 1965; Löf et al., 1966a,b) have been based on correlations of radiation with sunshine hour data. However, Paltridge and Proctor 1976 used cloud cover data to modify clear-sky data for Australia and derived from the data monthly averages of  $\overline{H}_o$  which are in good agreement with measured average data.

**Table 2.7.2** Climatic Constants for Use in Equation 2.7.2

Location	Climate <sup>a</sup>	Vegetation <sup>b</sup>	Sunshine Hours in Percentage of Possible		<i>a</i>	<i>b</i>
			Range	Average		
Albuquerque, NM	BS-BW	E	68–85	78	0.41	0.37
Atlanta, GA	Cf	M	45–71	59	0.38	0.26
Blue Hill, MA	Df	D	42–60	52	0.22	0.50
Brownsville, TX	BS	GDsp	47–80	62	0.35	0.31
Buenos Aires, Argentina	Cf	G	47–68	59	0.26	0.50
Charleston, SC	Cf	E	60–75	67	0.48	0.09
Darien, Manchuria	Dw	D	55–81	67	0.36	0.23
El Paso, TX	BW	Dsi	78–88	84	0.54	0.20
Ely, NV	BW	Bzi	61–89	77	0.54	0.18
Hamburg, Germany	Cf	D	11–49	36	0.22	0.57
Honolulu, HI	Af	G	57–77	65	0.14	0.73
Madison, WI	Df	M	40–72	58	0.30	0.34
Malange, Angola	Aw-BS	GD	41–84	58	0.34	0.34
Miami, FL	Aw	E-GD	56–71	65	0.42	0.22
Nice, France	Cs	SE	49–76	61	0.17	0.63
Poona, India	Am	S	25–49	37	0.30	0.51
Monsoon Dry			65–89	81	0.41	0.34
Kisangani, Zaire	Af	B	34–56	48	0.28	0.39
Tamanrasset, Algeria	BW	Dsp	76–88	83	0.30	0.43

<sup>a</sup>Climatic classification based on Trewartha's map (1954, 1961), where climate types are:

- Af Tropical forest climate, constantly moist; rainfall throughout the year
- Am Tropical forest climate, monsoon rain; short dry season, but total rainfall sufficient to support rain forest
- Aw Tropical forest climate, dry season in winter
- BS Steppe or semiarid climate
- BW Desert or arid climate
- Cf Mesothermal forest climate; constantly moist; rainfall throughout the year
- Cs Mesothermal forest climate; dry season in winter
- Df Microthermal snow forest climate; constantly moist; rainfall throughout the year
- Dw Microthermal snow forest climate; dry season in winter

<sup>b</sup>Vegetation classification based on Küchler's map, where vegetation types are:

- B Broadleaf evergreen trees
- Bzi Broadleaf evergreen, shrub form, minimum height 3 ft, growth singly or in groups or patches
- D Broadleaf deciduous trees
- Dsi Broadleaf deciduous, shrub form, minimum height 3 ft, plants sufficiently far apart that they frequently do not touch
- Dsp Broadleaf deciduous, shrub form, minimum height 3 ft, growth singly or in groups or patches
- E Needleleaf evergreen trees
- G Grass and other herbaceous plants
- GD Grass and other herbaceous plants; broadleaf deciduous trees
- GDsp Grass and other herbaceous plants; broadleaf deciduous, shrub forms, minimum height 3 ft, growth singly or in groups or patches
- M Mixed broadleaf deciduous and needleleaf evergreen trees
- S Semideciduous: broadleaf evergreen and broadleaf deciduous trees
- SE Semideciduous: broadleaf evergreen and broadleaf deciduous trees: needleleaf evergreen trees

*Note:* These constants are based on radiation data available before 1966 and do not reflect improvements in data processing and interpretation made since then. The results of estimations for U.S. stations will be at variance with TMY2 data. It is recommended that these correlations be used only when there are no radiation data available.

## 2.8 ESTIMATION OF CLEAR-SKY RADIATION

The effects of the atmosphere in scattering and absorbing radiation are variable with time as atmospheric conditions and air mass change. It is useful to define a standard “clear” sky and calculate the hourly and daily radiation which would be received on a horizontal surface under these standard conditions.

Hottel (1976) has presented a method for estimating the beam radiation transmitted through clear atmospheres which takes into account zenith angle and altitude for a standard atmosphere and for four climate types. The atmospheric transmittance for beam radiation  $\tau_b$  is  $G_{bn}/G_{on}$  (or  $G_{bT}/G_{oT}$ ) and is given in the form

$$\tau_b = a_0 + a_1 \exp\left(\frac{-k}{\cos \theta_z}\right) \quad (2.8.1a)$$

The constants  $a_0$ ,  $a_1$ , and  $k$  for the standard atmosphere with 23 km visibility are found from  $a_0^*$ ,  $a_1^*$ , and  $k^*$ , which are given for altitudes less than 2.5 km by

$$a_0^* = 0.4237 - 0.00821(6 - A)^2 \quad (2.8.1b)$$

$$a_1^* = 0.5055 + 0.00595(6.5 - A)^2 \quad (2.8.1c)$$

$$k^* = 0.2711 + 0.01858(2.5 - A)^2 \quad (2.8.1d)$$

where  $A$  is the altitude of the observer in kilometers. (Hottel also gives equations for  $a_0^*$ ,  $a_1^*$ , and  $k^*$  for a standard atmosphere with 5 km visibility.)

Correction factors are applied to  $a_0^*$ ,  $a_1^*$ , and  $k^*$  to allow for changes in climate types. The correction factors  $r_0 = a_0/a_0^*$ ,  $r_1 = a_1/a_1^*$ , and  $r_k = k/k^*$  are given in Table 2.8.1. Thus, the transmittance of this standard atmosphere for beam radiation can be determined for any zenith angle and any altitude up to 2.5 km. The clear-sky beam normal radiation is then

$$G_{cnb} = G_{on}\tau_b \quad (2.8.2)$$

where  $G_{on}$  is obtained from Equation 1.4.1. The clear-sky horizontal beam radiation is

$$G_{cb} = G_{on}\tau_b \cos \theta_z \quad (2.8.3)$$

For periods of an hour, the clear-sky horizontal beam radiation is

$$I_{cb} = I_{on}\tau_b \cos \theta_z \quad (2.8.4)$$

**Table 2.8.1** Correction Factors for Climate Types<sup>a</sup>

Climate Type	$r_0$	$r_1$	$r_k$
Tropical	0.95	0.98	1.02
Midlatitude summer	0.97	0.99	1.02
Subarctic summer	0.99	0.99	1.01
Midlatitude winter	1.03	1.01	1.00

<sup>a</sup>From Hottel (1976).

**Example 2.8.1**

Calculate the transmittance for beam radiation of the standard clear atmosphere at Madison (altitude 270 m) on August 22 at 11:30 AM solar time. Estimate the intensity of beam radiation at that time and its component on a horizontal surface.

**Solution**

On August 22,  $n = 234$ , the declination is  $11.4^\circ$ , and from Equation 1.6.5 the cosine of the zenith angle is 0.846.

The next step is to find the coefficients for Equation 2.8.1. First, the values for the standard atmosphere are obtained from Equations 2.8.1b to 2.8.1d for an altitude of 0.27 km:

$$a_0^* = 0.4237 - 0.00821(6 - 0.27)^2 = 0.154$$

$$a_1^* = 0.5055 + 0.00595(6.5 - 0.27)^2 = 0.736$$

$$k^* = 0.2711 + 0.01858(2.5 - 0.27)^2 = 0.363$$

The climate-type correction factors are obtained from Table 2.8.1 for midlatitude summer. Equation 2.8.1a becomes

$$\tau_b = 0.154 \times 0.97 + 0.736 \times 0.99 \exp\left(-0.363 \times \frac{1.02}{0.846}\right) = 0.62$$

The extraterrestrial radiation is  $1339 \text{ W/m}^2$  from Equation 1.4.1. The beam radiation is then

$$G_{cnb} = 1339 \times 0.62 = 830 \text{ W/m}^2$$

The component on a horizontal plane is

$$G_{cb} = 830 \times 0.846 = 702 \text{ W/m}^2$$

■

It is also necessary to estimate the clear-sky diffuse radiation on a horizontal surface to get the total radiation. Liu and Jordan (1960) developed an empirical relationship between the transmission coefficients for beam and diffuse radiation for clear days:

$$\tau_d = \frac{G_d}{G_o} = 0.271 - 0.294\tau_b \quad (2.8.5)$$

where  $\tau_d$  is  $G_d/G_o$  (or  $I_d/I_o$ ), the ratio of diffuse radiation to the extraterrestrial (beam) radiation on the horizontal plane. The equation is based on data for three stations. The data used by Liu and Jordan predated that used by Hottel (1976) and may not be entirely consistent with it; until better information becomes available, it is suggested that Equation 2.8.5 be used to estimate diffuse clear-sky radiation, which can be added to the beam radiation predicted by Hottel's method to obtain a clear hour's total. These

calculations can be repeated for each hour of the day, based on the midpoints of the hours, to obtain a standard clear day's radiation  $H_c$ .

### Example 2.8.2

Estimate the standard clear-day radiation on a horizontal surface for Madison on August 22.

#### Solution

For each hour, based on the midpoints of the hour, the transmittances of the atmosphere for beam and diffuse radiation are estimated. The calculation of  $\tau_b$  is illustrated for the hour 11 to 12 (i.e., at 11:30) in Example 2.8.1, and the beam radiation for a horizontal surface for the hour is  $2.53 \text{ MJ/m}^2$  ( $702 \text{ W/m}^2$  for the hour).

The calculation of  $\tau_d$  is based on Equation 2.8.5:

$$\tau_d = 0.271 - 0.294(0.62) = 0.089$$

Next  $G_{on}$ , calculated by Equation 1.4.1, is  $1339 \text{ W/m}^2$ . Then  $G_o$  is  $G_{on} \cos \theta_z$  so that

$$G_{cd} = 1339 \times 0.846 \times 0.089 = 101 \text{ W/m}^2$$


Then the diffuse radiation for the hour is  $0.36 \text{ MJ/m}^2$ . The total radiation on a horizontal plane for the hour is  $2.53 + 0.36 = 2.89 \text{ MJ/m}^2$ . These calculations are repeated for each hour of the day. The result is shown in the tabulation, where energy quantities are in megajoules per square meter. The beam for the day  $H_{cb}$  is twice the sum of column 4, giving  $19.0 \text{ MJ/m}^2$ . The day's total radiation  $H_c$  is twice the sum of column 7, or  $22.8 \text{ MJ/m}^2$ .

Hours	$\tau_b$	$I_{cb}$		$\tau_d$	$I_{cd}$	$I_c$
		Normal	Horizontal			
11–12, 12–1	0.620	2.99	2.52	0.089	0.36	2.89
10–11, 1–2	0.607	2.93	2.33	0.092	0.35	2.69
9–10, 2–3	0.580	2.79	1.97	0.100	0.34	2.31
8–9, 3–4	0.530	2.56	1.46	0.115	0.32	1.78
7–8, 4–5	0.444	2.14	0.88	0.140	0.28	1.15
6–7, 5–6	0.293	1.41	0.32	0.185	0.20	0.53
5–6, 6–7	0.150	0.72	0.03	0.227	0.05	0.07

■

A simpler method for estimating clear-sky radiation by hours is to use data for the ASHRAE standard atmosphere. Farber and Morrison (1977) provide tables of beam normal radiation and total radiation on a horizontal surface as a function of zenith angle. These are plotted in Figure 2.8.1. For a given day, hour-by-hour estimates of  $I$  can be made, based on midpoints of the hours.





**Figure 2.8.1** Total horizontal radiation and beam normal radiation for the ASHRAE standard atmosphere. Data from Farber and Morrison (1977).

This method estimates the “clear-sky” day’s radiation as 10% greater than the Hottel and Liu and Jordan “standard”-day method. The difference lies in the definition of a standard (clear) day. While the ASHRAE data are easier to use, the Hottel and Liu and Jordan method provides a means of taking into account climate type and altitude.

## 2.9 DISTRIBUTION OF CLEAR AND CLOUDY DAYS AND HOURS

The frequency of occurrence of periods of various radiation levels, for example, of good and bad days, is of interest in two contexts. First, information on the frequency distribution is the link between two kinds of correlations, that of the daily fraction of diffuse with daily radiation and that of the monthly average fraction of diffuse with monthly average radiation. Second, later in this chapter the concept of utilizability is developed; it depends on these frequency distributions.


The monthly average clearness index  $\overline{K}_T$  is the ratio<sup>9</sup> of monthly average daily radiation on a horizontal surface to the monthly average daily extraterrestrial radiation. In equation form,

$$\overline{K}_T = \frac{\overline{H}}{\overline{H}_o} \quad (2.9.1)$$

We can also define a daily clearness index  $K_T$  as the ratio of a particular day’s radiation to the extraterrestrial radiation for that day. In equation form,

$$K_T = \frac{H}{H_o} \quad (2.9.2)$$

<sup>9</sup>These ratios were originally referred to by Liu and Jordan (1960) as cloudiness indexes. As their values approach unity with increasing atmospheric clearness, they are also referred to as clearness indexes, the terminology used here.



**Figure 2.9.1** An example of the frequency of occurrence of days with various clearness indexes and cumulative frequency of occurrence of those days.

An hourly clearness index  $k_T$  can also be defined:

$$k_T = \frac{I}{I_o} \quad (2.9.3)$$


The data  $\overline{H}$ ,  $H$ , and  $I$  are from measurements of total solar radiation on a horizontal surface, that is, the commonly available pyranometer measurements. Values of  $\overline{H}_o$ ,  $H_o$ , and  $I_o$  can be calculated by the methods of Section 1.10.

If for locations with a particular value of  $\overline{K}_T$  the frequency of occurrence of days with various values of  $K_T$  is plotted as a function of  $K_T$ , the resulting distribution could appear like the solid curve of Figure 2.9.1. The shape of this curve depends on the average clearness index  $\overline{K}_T$ . For intermediate  $\overline{K}_T$  values, days with very low  $K_T$  or very high  $K_T$  occur relatively infrequently, and most of the days have  $K_T$  values intermediate between the extremes. If  $\overline{K}_T$  is high, the distribution must be skewed toward high  $K_T$  values, and if it is low, the curve must be skewed toward low  $K_T$  values. The distribution can be bimodal, as shown by Ibáñez et al. (2003).

The data used to construct the frequency distribution curve of Figure 2.9.1 can also be plotted as a cumulative distribution, that is, as the fraction  $f$  of the days that are less clear than  $K_T$  versus  $K_T$ . In practice, following the precedent of Whillier (1956), the plots are usually shown as  $K_T$  versus  $f$ . The result is shown as the dashed line in Figure 2.9.1.

Liu and Jordan (1960) found that the cumulative distribution curves are very nearly identical for locations having the same values of  $\overline{K}_T$ , even though the locations varied widely in latitude and elevation. On the basis of this information, they developed a set of generalized distribution curves of  $K_T$  versus  $f$  which are functions of  $\overline{K}_T$ , the monthly clearness index. These are shown in Figure 2.9.2. The coordinates of the curves are given in Table 2.9.1. Thus if a location has a  $\overline{K}_T$  of 0.6, 19% of the days will have  $K_T \leq 0.40$ .<sup>10</sup>

<sup>10</sup>Recent research indicates that there may be some seasonal dependence of these distributions in some locations.



**Figure 2.9.2** Generalized distribution of days with various values of  $K_T$  as a function of  $\bar{K}_T$ .

**Table 2.9.1** Coordinates of Liu and Jordan Generalized Monthly  $K_T$  Cumulative Distribution Curves

$K_T$	Value of $f(K_T)$				
	$\bar{K}_T = 0.3$	$\bar{K}_T = 0.4$	$\bar{K}_T = 0.5$	$\bar{K}_T = 0.6$	$\bar{K}_T = 0.7$
0.04	0.073	0.015	0.001	0.000	0.000
0.08	0.162	0.070	0.023	0.008	0.000
0.12	0.245	0.129	0.045	0.021	0.007
0.16	0.299	0.190	0.082	0.039	0.007
0.20	0.395	0.249	0.121	0.053	0.007
0.24	0.496	0.298	0.160	0.076	0.007
0.28	0.513	0.346	0.194	0.101	0.013
0.32	0.579	0.379	0.234	0.126	0.013
0.36	0.628	0.438	0.277	0.152	0.027
0.40	0.687	0.493	0.323	0.191	0.034
0.44	0.748	0.545	0.358	0.235	0.047
0.48	0.793	0.601	0.400	0.269	0.054
0.52	0.824	0.654	0.460	0.310	0.081
0.56	0.861	0.719	0.509	0.360	0.128
0.60	0.904	0.760	0.614	0.410	0.161
0.64	0.936	0.827	0.703	0.467	0.228
0.68	0.953	0.888	0.792	0.538	0.295
0.72	0.967	0.931	0.873	0.648	0.517
0.76	0.979	0.967	0.945	0.758	0.678
0.80	0.986	0.981	0.980	0.884	0.859
0.84	0.993	0.997	0.993	0.945	0.940
0.88	0.995	0.999	1.000	0.985	0.980
0.92	0.998	0.999	—	0.996	1.000
0.96	0.998	1.000	—	0.999	—
1.00	1.000	—	—	1.000	—

Bendt et al. (1981) have developed equations to represent the Liu and Jordan (1960) distributions based on 20 years of data from 90 locations in the United States. The correlation represents the Liu and Jordan curves very well for values of  $f(K_T)$  less than 0.9; above 0.9 the correlations overpredict the frequency for given values of the clearness index. The Bendt et al. (1981) equations are

$$f(K_T) = \frac{\exp(\gamma K_{T,\min}) - \exp(\gamma K_T)}{\exp(\gamma K_{T,\min}) - \exp(\gamma K_{T,\max})} \quad (2.9.4)$$

where  $\gamma$  is determined from the equation

$$\bar{K}_T = \frac{(K_{T,\min} - 1/\gamma) \exp(\gamma K_{T,\min}) - (K_{T,\max} - 1/\gamma) \exp(\gamma K_{T,\max})}{\exp(\gamma K_{T,\min}) - \exp(\gamma K_{T,\max})} \quad (2.9.5)$$

Solving for  $\gamma$  in this equation is not convenient, and Herzog (1985) gives an explicit equation for  $\gamma$  from a curve fit:

$$\gamma = -1.498 + \frac{1.184\xi - 27.182 \exp(-1.5\xi)}{K_{T,\max} - K_{T,\min}} \quad (2.9.6a)$$

and

$$\xi = \frac{K_{T,\max} - K_{T,\min}}{K_{T,\max} - \bar{K}_T} \quad (2.9.6b)$$

A value of  $K_{T,\min}$  of 0.05 was recommended by Bendt et al. (1981) and Hollands and Huget (1983) recommend that  $K_{T,\max}$  be estimated from


$$K_{T,\max} = 0.6313 + 0.267\bar{K}_T - 11.9(\bar{K}_T - 0.75)^8 \quad (2.9.6c)$$

The universality of the Liu and Jordan (1960) distributions has been questioned, particularly as applied to tropical climates. Saunier et al. (1987) propose an alternative expression for the distributions for tropical climates. A brief review of papers on the distributions is included in Knight et al. (1991).

Similar distribution functions have been developed for hourly radiation. Whillier (1953) observed that when the hourly and daily curves for a location are plotted, the curves are very similar. Thus the distribution curves of daily occurrences of  $K_T$  can also be applied to hourly clearness indexes. The ordinate in Figure 2.9.2 can be replaced by  $k_T$  and the curves will approximate the cumulative distribution of hourly clearness. Thus for a climate with  $\bar{K}_T = 0.4$ , 0.493 of the hours will have  $k_T \leq 0.40$ .

## 2.10 BEAM AND DIFFUSE COMPONENTS OF HOURLY RADIATION

In this and the following two sections we review methods for estimation of the fractions of total horizontal radiation that are diffuse and beam. The questions of the best methods




**Figure 2.10.1** A sample of diffuse fraction versus clearness index data from Cape Canaveral, FL. Adapted from Reindl (1988).

for doing these calculations are not fully settled. A broader database and improved understanding of the data will probably lead to improved methods. In each section we review methods that have been published and then suggest one for use. The suggested correlations are in substantial agreement with other correlations, and the set is mutually consistent.


The split of total solar radiation on a horizontal surface into its diffuse and beam components is of interest in two contexts. First, methods for calculating total radiation on surfaces of other orientation from data on a horizontal surface require separate treatments of beam and diffuse radiation (see Section 2.15). Second, estimates of the long-time performance of most concentrating collectors must be based on estimates of availability of beam radiation. The present methods for estimating the distribution are based on studies of available measured data; they are adequate for the first purpose but less than adequate for the second.

The usual approach is to correlate  $I_d/I$ , the fraction of the hourly radiation on a horizontal plane which is diffuse, with  $k_T$ , the hourly clearness index. Figure 2.10.1 shows a plot of diffuse fraction  $I_d/I$  versus  $k_T$  for Cape Canaveral, Florida. In order to obtain  $I_d/I$ -versus- $k_T$  correlations, data from many locations similar to that shown in Figure 2.10.1 are divided into “bins,” or ranges of values of  $k_T$ , and the data in each bin are averaged to obtain a point on the plot. A set of these points then is the basis of the correlation. Within each of the bins there is a distribution of points; a  $k_T$  of 0.5 may be produced by skies with thin cloud cover, resulting in a high diffuse fraction, or by skies that are clear for part of the hour and heavily clouded for part of the hour, leading to a low diffuse fraction. Thus the correlation may not represent a particular hour very closely, but over a large number of hours it adequately represents the diffuse fraction.

Orgill and Hollands (1977) have used data of this type from Canadian stations, Erbs et al. (1982) have used data from four U.S. and one Australian station, and Reindl et al. (1990a) have used an independent data set from the United States and Europe. The three



**Figure 2.10.2** The ratio  $I_d/I$  as function of hourly clearness index  $k_T$  showing the Orgill and Hollands (1977), Erbs et al. (1982), and Reindl et al. (1990a) correlations.



**Figure 2.10.3** The ratio  $I_d/I$  as a function of hourly clearness index  $k_T$ . From Erbs et al. (1982).

correlations are shown in Figure 2.10.2. They are essentially identical, although they were derived from three separate databases. The Erbs et al. correlation (Figure 2.10.3) is<sup>11</sup>

$$\frac{I_d}{I} = \begin{cases} 1.0 - 0.09k_T & \text{for } k_T \leq 0.22 \\ 0.9511 - 0.1604k_T + 4.388k_T^2 - 16.638k_T^3 + 12.336k_T^4 & \text{for } 0.22 < k_T \leq 0.80 \\ 0.165 & \text{for } k_T > 0.8 \end{cases} \quad (2.10.1)$$

<sup>11</sup>The Orgill and Hollands correlation has been widely used, produces results that are for practical purposes the same as those of Erbs et al., and is represented by the following equations:


$$\frac{I_d}{I} = \begin{cases} 1.0 - 0.249k_T & \text{for } 0 \leq k_T \leq 0.35 \\ 1.557 - 1.84k_T & \text{for } 0.35 < k_T < 0.75 \\ 0.177 & \text{for } k_T > 0.75 \end{cases}$$

For values of  $k_T$  greater than 0.8, there are very few data. Some of the data that are available show increasing diffuse fraction as  $k_T$  increases above 0.8. This apparent rise in the diffuse fraction is probably due to reflection of radiation from clouds during times when the sun is unobscured but when there are clouds near the path from the sun to the observer. The use of a diffuse fraction of 0.165 is recommended in this region.


In a related approach described by Boes (1975), values of  $I_d/I$  from correlations are modified by a restricted random number that adds a statistical variation to the correlation.

## 2.11 BEAM AND DIFFUSE COMPONENTS OF DAILY RADIATION

Studies of available daily radiation data have shown that the average fraction which is diffuse,  $H_d/H$ , is a function of  $K_T$ , the day's clearness index. The original correlation of Liu and Jordan (1960) is shown in Figure 2.11.1; the data were for Blue Hill, Massachusetts. Also shown on the graph are plots of data for Israel from Stanhill (1966), for New Delhi from Choudhury (1963), for Canadian stations from Ruth and Chant (1976) and Tuller (1976), for Highett (Melbourne), Australia, from Bannister (1969), and for four U.S. stations from Collares-Pereira and Rabl (1979a). There is some disagreement, with differences probably due in part to instrumental difficulties such as shading ring corrections and possibly in part due to air mass and/or seasonal effects. The correlation by Erbs (based on the same data set as is Figure 2.10.2) is shown in Figure 2.11.2. A seasonal dependence is shown; the spring, summer, and fall data are essentially the same, while the winter data show somewhat lower diffuse fractions for high values of  $K_T$ . The season is indicated by



**Figure 2.11.1** Correlations of daily diffuse fraction with daily clearness index. Adapted from Klein and Duffie (1978).



**Figure 2.11.2** Suggested correlation of daily diffuse fraction with  $K_T$ . From Erbs et al. (1982).

the sunset hour angle  $\omega_s$ . Equations representing this set of correlations are as follows<sup>12</sup>:  
For  $\omega_s \leq 81.4^\circ$

$$\frac{H_d}{H} = \begin{cases} 1.0 - 0.2727K_T + 2.4495K_T^2 - 11.9514K_T^3 + 9.3879K_T^4 & \text{for } K_T < 0.715 \\ 0.143 & \text{for } K_T \geq 0.715 \end{cases} \quad (2.11.1a)$$

and for  $\omega_s > 81.4^\circ$

$$\frac{H_d}{H} = \begin{cases} 1.0 + 0.2832K_T - 2.5557K_T^2 + 0.8448K_T^3 & \text{for } K_T < 0.722 \\ 0.175 & \text{for } K_T \geq 0.722 \end{cases} \quad (2.11.1b)$$

### Example 2.11.1

The day's total radiation on a horizontal surface for St. Louis, Missouri (latitude  $38.6^\circ$ ), on September 3 is  $23.0 \text{ MJ/m}^2$ . Estimate the fraction and amount that is diffuse.

#### Solution

For September 3, the declination is  $7^\circ$ . From Equation 1.6.10, the sunset hour angle is  $95.6^\circ$ . From Equation 1.10.3, the day's extraterrestrial radiation is  $33.3 \text{ MJ/m}^2$ . Then

$$K_T = \frac{H}{H_o} = \frac{23.0}{33.3} = 0.69$$

<sup>12</sup>The Collares-Pereira and Rabl correlation is

$$\frac{H_d}{H} = \begin{cases} 0.99 & \text{for } K_T \leq 0.17 \\ 1.188 - 2.272K_T + 9.473K_T^2 - 21.865K_T^3 + 14.648K_T^4 & \text{for } 0.17 < K_T < 0.75 \\ -0.54K_T + 0.632 & \text{for } 0.75 < K_T < 0.80 \\ 0.2 & \text{for } K_T \geq 0.80 \end{cases}$$




From Figure 2.11.2 or Equation 2.11.1b,  $H_d/H = 0.26$ , so an estimated 26% of the day's radiation is diffuse. The day's diffuse energy is  $0.26 \times 23.0 = 6.0 \text{ MJ/m}^2$ . ■


## 2.12 BEAM AND DIFFUSE COMPONENTS OF MONTHLY RADIATION

Charts similar to Figures 2.11.1 and 2.11.2 have been derived to show the distribution of monthly average daily radiation into its beam and diffuse components. In this case, the monthly fraction that is diffuse,  $\overline{H}_d/\overline{H}$ , is plotted as a function of monthly average clearness index,  $\overline{K}_T (= \overline{H}/\overline{H}_o)$ . The data for these plots can be obtained from daily data in either of two ways. First, monthly data can be plotted by summing the daily diffuse and total radiation data. Second, as shown by Liu and Jordan (1960), a generalized daily  $H_d/H$ -versus- $K_T$  curve can be used with a knowledge of the distribution of good and bad days (the cumulative distribution curves of Figure 2.9.2) to develop the monthly average relationships.

Figure 2.12.1 shows several correlations of  $\overline{H}_d/\overline{H}$  versus  $\overline{K}_T$ . The curves of Page (1964) and Collares-Pereira and Rabl (1979a) are based on summations of daily total and diffuse radiation. The original curve of Liu and Jordan (modified to correct for a small error in  $\overline{H}_d/\overline{H}$  at low  $\overline{K}_T$ ) and those labeled Highett, Stanhill, Choudhury, Ruth and Chant, and Tuller are based on daily correlations by the various authors (as in Figure 2.11.1) and on the distribution of days with various  $\overline{K}_T$  as shown in Figure 2.9.2. The Collares-Pereira and Rabl curve in Figure 2.12.1 is for their all-year correlation; they found a seasonal dependence of the relationship which they expressed in terms of the sunset hour angle of the mean day of the month. There is significant disagreement among the various correlations



**Figure 2.12.1** Correlations of average diffuse fractions with average clearness index. Adapted from Klein and Duffie (1978).



**Figure 2.12.2** Suggested correlation of  $\overline{H}_d/\overline{H}$  versus  $\overline{K}_T$  and  $\omega_s$ . Adapted from Erbs et al. (1982).

of Figure 2.12.1. Instrumental problems and atmospheric variables (air mass, season, or other) may contribute to the differences.

Erbs et al. (1982) developed monthly average diffuse fraction correlations from the daily diffuse correlations of Figure 2.11.2. As with the daily correlations, there is a seasonal dependence; the winter curve lies below the other, indicating lower moisture and dust in the winter sky with resulting lower fractions of diffuse. The dependence of  $\overline{H}_d/\overline{H}$  on  $\overline{K}_T$  is shown for winter and for the other seasons in Figure 2.12.2. Equations for these correlations are as follows<sup>13</sup>: For  $\omega_s \leq 81.4^\circ$  and  $0.3 \leq \overline{K}_T \leq 0.8$

$$\frac{\overline{H}_d}{\overline{H}} = 1.391 - 3.560\overline{K}_T + 4.189\overline{K}_T^2 - 2.137\overline{K}_T^3 \quad (2.12.1a)$$

and for  $\omega_s > 81.4^\circ$  and  $0.3 \leq \overline{K}_T \leq 0.8$

$$\frac{\overline{H}_d}{\overline{H}} = 1.311 - 3.022\overline{K}_T + 3.427\overline{K}_T^2 - 1.821\overline{K}_T^3 \quad (2.12.1b)$$

### Example 2.12.1

Estimate the fraction of the average June radiation on a horizontal surface that is diffuse in Madison, Wisconsin.

#### Solution

From Appendix D, the June average daily radiation  $\overline{H}$  for Madison is 23.0 MJ/m<sup>2</sup>. From Equation 1.10.3, for June 11 (the mean day of the month,  $n = 162$ , from Table 1.6.1), when the declination is  $23.1^\circ$ ,  $H_o = 41.8$  MJ/m<sup>2</sup>. Thus  $\overline{K}_T = 23.0/41.8 = 0.55$ . From Equation 1.6.10,  $\omega_s = 113.4^\circ$ . Then, using either Equation 2.12.1b or the upper curve from Figure 2.12.2,  $\overline{H}_d/\overline{H} = 0.38$ . ■

<sup>13</sup>The Collares-Pereira and Rabl correlation, with  $\omega_s$  in degrees, is

$$\frac{\overline{H}_d}{\overline{H}} = 0.775 + 0.00606 (\omega_s - 90) - [0.505 + 0.00455(\omega_s - 90)] \cos(115\overline{K}_T - 103)$$

## 2.13 ESTIMATION OF HOURLY RADIATION FROM DAILY DATA

When hour-by-hour (or other short-time base) performance calculations for a system are to be done, it may be necessary to start with daily data and estimate hourly values from daily numbers. As with the estimation of diffuse from total radiation, this is not an exact process. For example, daily total radiation values in the middle range between clear-day and completely cloudy day values can arise from various circumstances, such as intermittent heavy clouds, continuous light clouds, or heavy cloud cover for part of the day. There is no way to determine these circumstances from the daily totals. However, the methods presented here work best for clear days, and those are the days that produce most of the output of solar processes (particularly those processes that operate at temperatures significantly above ambient). Also, these methods tend to produce conservative estimates of long-time process performance.

Statistical studies of the time distribution of total radiation on horizontal surfaces through the day using monthly average data for a number of stations have led to generalized charts of  $r_t$ , the ratio of hourly total to daily total radiation, as a function of day length and the hour in question:

$$r_t = \frac{I}{H} \quad (2.13.1)$$

Figure 2.13.1 shows such a chart, adapted from Liu and Jordan (1960) and based on Whillier (1956, 1965) and Hottel and Whillier (1958). The hours are designated by the time for the midpoint of the hour, and days are assumed to be symmetrical about solar noon. A curve for the hour centered at noon is also shown. Day length can be calculated from Equation 1.6.11 or it can be estimated from Figure 1.6.3. Thus, knowing day length (a function of latitude  $\phi$  and declination  $\delta$ ) and daily total radiation, the hourly total radiation for symmetrical days can be estimated.

A study of New Zealand data by Benseman and Cook (1969) indicates that the curves of Figure 2.13.1 represent the New Zealand data in a satisfactory way. Iqbal (1979) used Canadian data to further substantiate these relationships. The figure is based on long-term averages and is intended for use in determining averages of hourly radiation. Whillier (1956) recommends that it be used for individual days only if they are clear days. Benseman and Cook (1969) suggest that it is adequate for individual days, with best results for clear days and increasingly uncertain results as daily total radiation decreases.

The curves of Figure 2.13.1 are represented by the following equation from Collares-Pereira and Rabl (1979a):


$$r_t = \frac{\pi}{24} (a + b \cos \omega) \frac{\cos \omega - \cos \omega_s}{\sin \omega_s - \frac{\pi \omega_s}{180} \cos \omega_s} \quad (2.13.2a)$$

The coefficients  $a$  and  $b$  are given by

$$a = 0.409 + 0.5016 \sin(\omega_s - 60) \quad (2.13.2b)$$

$$b = 0.6609 - 0.4767 \sin(\omega_s - 60) \quad (2.13.2c)$$

In these equations  $\omega$  is the hour angle in degrees for the time in question (i.e., the midpoint of the hour for which the calculation is made) and  $\omega_s$  is the sunset hour angle.



**Figure 2.13.1** Relationship between hourly and daily total radiation on a horizontal surface as a function of day length. Adapted from Liu and Jordan (1960).

### Example 2.13.1

What is the fraction of the average January daily radiation that is received at Melbourne, Australia, in the hour between 8:00 and 9:00?

#### Solution

For Melbourne,  $\phi = -38^\circ$ . From Table 1.6.1 the mean day for January is the 17th. From Equation 1.6.1 the declination is  $-20.9^\circ$ . From Equation 1.6.11 the day length is 14.3 h. From Figure 2.13.1, using the curve for 3.5 h from solar noon, at a day length of 14.3 h, approximately 7.8% of the day's radiation will be in that hour. Or Equation 2.13.2 can be used; with  $\omega_s = 107^\circ$  and  $\omega = -52.5^\circ$ , the result is  $r_t = 0.076$ . ■

**Example 2.13.2**

The total radiation for Madison on August 23 was  $31.4 \text{ MJ/m}^2$ . Estimate the radiation received between 1 and 2 PM.

**Solution**

For August 23,  $\delta = 11^\circ$  and  $\phi$  for Madison is  $43^\circ$ . From Figure 1.6.3, sunset is at 6:45 PM and day length is 13.4 h. Then from Figure 2.13.1, at day length of 13.4 h and mean of 1.5 h from solar noon, the ratio hourly total to daily total  $r_t = 0.118$ . The estimated radiation in the hour from 1 to 2 PM is then  $3.7 \text{ MJ/m}^2$ . (The measured value for that hour was  $3.47 \text{ MJ/m}^2$ .) ■

Figure 2.13.2 shows a related set of curves for  $r_d$ , the ratio of hourly diffuse to daily diffuse radiation, as a function of time and day length. In conjunction with Figure 2.11.2, it can be used to estimate hourly averages of diffuse radiation if the average daily total radiation is known:

$$r_d = \frac{I_d}{H_d} \quad (2.13.3)$$

These curves are based on the assumption that  $I_d/H_d$  is the same as  $I_o/H_o$  and are represented by the following equation from Liu and Jordan (1960):

$$r_d = \frac{\pi}{24} \frac{\cos \omega - \cos \omega_s}{\sin \omega_s - \frac{\pi \omega_s}{180} \cos \omega_s} \quad (2.13.4)$$


**Example 2.13.3**

From Appendix D, the average daily June total radiation on a horizontal plane in Madison is  $23.0 \text{ MJ/m}^2$ . Estimate the average diffuse, the average beam, and the average total radiation for the hours 10 to 11 and 1 to 2.

**Solution**

The mean daily extraterrestrial radiation  $\overline{H}_o$  for June for Madison is  $41.7 \text{ MJ/m}^2$  (from Table 1.10.1 or Equation 1.10.3 with  $n = 162$ ),  $\omega_s = 113^\circ$ , and the day length is 15.1 h (from Equation 1.6.11). Then (as in Example 2.12.1),  $\overline{K}_T = 0.55$ . From Equation 2.12.1,  $\overline{H}_d/\overline{H} = 0.38$ , and the average daily diffuse radiation is  $0.38 \times 23.0 = 8.74 \text{ MJ/m}^2$ . Entering Figure 2.13.2 for an average day length of 15.1 h and for 1.5 h from solar noon, we find  $r_d = 0.102$ . (Or Equation 2.13.4 can be used with  $\omega = 22.5^\circ$  and  $\omega_s = 113^\circ$  to obtain  $r_d = 0.102$ .) Thus the average diffuse for those hours is  $0.102 \times 8.74 = 0.89 \text{ MJ/m}^2$ .


From Figure 2.13.1 (or from Equations 2.13.1 and 2.13.2) from the curve for 1.5 h from solar noon, for an average day length of 15.1 h,  $r_t = 0.108$  and average hourly total radiation is  $0.108 \times 23.0 = 2.48 \text{ MJ/m}^2$ . The average beam radiation is the difference between the total and diffuse, or  $2.48 - 0.89 = 1.59 \text{ MJ/m}^2$ . ■



**Figure 2.13.2** Relationship between hourly diffuse and daily diffuse radiation on a horizontal surface as a function of day length. Adapted from Liu and Jordan (1960).

## 2.14 RADIATION ON SLOPED SURFACES

We turn next to the general problem of calculation of radiation on tilted surfaces when only the total radiation on a horizontal surface is known. For this we need the directions from which the beam and diffuse components reach the surface in question. Section 1.8 dealt with the geometric problem of the direction of beam radiation. The direction from which diffuse radiation is received, that is, its distribution over the sky dome, is a function of conditions of cloudiness and atmospheric clarity, which are highly variable. Some data are available, for example, from Kondratyev (1969) and Coulson (1975). Figure 2.14.1, from Coulson, shows profiles of diffuse radiation across the sky as a function of angular




**Figure 2.14.1** Relative intensity of solar radiation (at  $\lambda = 0.365 \mu\text{m}$ ) as a function of elevation angle in the principal plane that includes the sun, for Los Angeles, for clear sky and for smog. Adapted from Coulson (1975).

elevation from the horizon in a plane that includes the sun. The data are for clear-sky and smog conditions.

Clear-day data such as that in Figure 2.14.1 suggest a diffuse radiation model as being composed of three parts. The first is an **isotropic** part, received uniformly from the entire sky dome. The second is **circumsolar diffuse**, resulting from forward scattering of solar radiation and concentrated in the part of the sky around the sun. The third, referred to as **horizon brightening**, is concentrated near the horizon and is most pronounced in clear skies. Figure 2.14.2 shows schematically these three parts of the diffuse radiation.

The angular distribution of diffuse is to some degree a function of the reflectance  $\rho_g$  (the albedo) of the ground. A high reflectance (such as that of fresh snow, with  $\rho_g \sim 0.7$ ) results in reflection of solar radiation back to the sky, which in turn may be scattered to account for horizon brightening.

Sky models, in the context used here, are mathematical representations of the diffuse radiation. When beam and reflected radiation are added, they provide the means of calculating radiation on a tilted surface from measurements on the horizontal. Many sky models have been devised. A review of some of them is provided by Hay and McKay (1985). Since 1985, others have been developed. For purposes of this book, three of the most useful of these models are presented: the isotropic model in Section 2.15 and two anisotropic models in Section 2.16. The differences among them are in the way they treat the three parts of the diffuse radiation.



**Figure 2.14.2** Schematic of the distribution of diffuse radiation over the sky dome showing the circumsolar and horizon brightening components added to the isotropic component. Adapted from Perez et al. (1988).

It is necessary to know or to be able to estimate the solar radiation incident on tilted surfaces such as solar collectors, windows, or other passive system receivers. The incident solar radiation is the sum of a set of radiation streams including beam radiation, the three components of diffuse radiation from the sky, and radiation reflected from the various surfaces “seen” by the tilted surface. The total incident radiation on this surface can be written as<sup>14</sup>

$$I_T = I_{T,b} + I_{T,d,iso} + I_{T,d,cs} + I_{T,d,hz} + I_{T,refl} \quad (2.14.1)$$

where the subscripts iso, cs, hz, and refl refer to the isotropic, circumsolar, horizon, and reflected radiation streams.

For a surface (a collector) of area  $A_c$ , the total incident radiation can be expressed in terms of the beam and diffuse radiation on the horizontal surface and the total radiation on the surfaces that reflect to the tilted surface. The terms in Equation 2.14.1 become

$$A_c I_T = I_b R_b A_c + I_{d,iso} A_s F_{s-c} + I_{d,cs} R_b A_c + I_{d,hz} A_{hz} F_{hz-c} + \sum_i I_i \rho_i A_i F_{i-c} \quad (2.14.2)$$

The first term is the beam contribution. The second is the isotropic diffuse term, which includes the product of sky area  $A_s$  (an undefined area) and the radiation view factor from the sky to the collector  $F_{s-c}$ . The third is the circumsolar diffuse, which is treated as coming from the same direction as the beam. The fourth term is the contribution of the diffuse from the horizon from a band with another undefined area  $A_{hz}$ . The fifth term is the set of reflected radiation streams from the buildings, fields, and so on, to which the tilted surface is exposed. The symbol  $i$  refers to each of the reflected streams:  $I_i$  is the solar radiation incident on the  $i$ th surface,  $\rho_i$  is the diffuse reflectance of that surface, and  $F_{i-c}$  is the view factor from the  $i$ th surface to the tilted surface. It is assumed that the reflecting surfaces are diffuse reflectors; specular reflectors require a different treatment.

<sup>14</sup>This and following equations are written in terms of  $I$  for an hour. They could also be written in terms of  $G$ , the irradiance.



In general, it is not possible to calculate the reflected energy term in detail, to account for buildings, trees, and so on, the changing solar radiation incident on them, and their changing reflectances. Standard practice is to assume that there is one surface, a horizontal, diffusely reflecting ground, large in extent, contributing to this term. In this case,  $I_i$  is simply  $I$  and  $\rho_i$  becomes  $\rho_g$ , a composite “ground” reflectance.

Equation 2.14.2 can be rewritten in a useful form by interchanging areas and view factors (since the view factor reciprocity relation requires that, e.g.,  $A_s F_{s-c} = A_c F_{c-s}$ ). This eliminates the undefined areas  $A_s$  and  $A_{hz}$ . The area  $A_c$  appears in each term in the equation and cancels. The result is an equation that gives  $I_T$  in terms of parameters that can be determined either theoretically or empirically:

$$I_T = I_b R_b + I_{d,iso} F_{c-s} + I_{d,cs} R_b + I_{d,hz} F_{c-hz} + I \rho_g F_{c-g} \quad (2.14.3)$$

This equation, with variations, is the basis for methods of calculating  $I_T$  that are presented in the following sections.

When  $I_T$  has been determined, the ratio of total radiation on the tilted surface to that on the horizontal surface can be determined. By definition,

$$R = \frac{\text{total radiation on tilted surfaced}}{\text{total radiation on horizontal surface}} = \frac{I_T}{I} \quad (2.14.4)$$

Many models have been developed, of varying complexity, as the basis for calculating  $I_T$ . The differences are largely in the way that the diffuse terms are treated. The simplest model is based on the assumptions that the beam radiation predominates (when it matters) and that the diffuse (and ground-reflected radiation) is effectively concentrated in the area of the sun. Then  $R = R_b$  and all radiation is treated as beam. This leads to substantial overestimation of  $I_T$ , and the procedure is not recommended. Preferred methods are given in the following two sections and are based on various assumptions about the directional distribution of the diffuse radiation incident on the tilted surface.

For most hours the calculation of  $R_b$  in Equation 2.14.3 is straightforward, as shown in Section 1.8. However, problems can arise in calculating radiation on a tilted surface at times near sunrise and sunset. For example, solar radiation data may be recorded before sunrise or after sunset due to reflection from clouds and/or by refraction of the atmosphere. The usual practice is to either discard such measurements or treat the radiation as all diffuse as the impact on solar system performance is negligible. The time scale of most detailed radiation data is hourly where the reported value is the integrated energy over the previous hour; that is, the radiation for the hour 4 PM is the integrated radiation from 3 PM to 4 PM. Estimates of tilted surface radiation typically use the midpoint of the previous hour for all calculations. However, this practice can cause problems if the hour contains the actual sunrise or sunset.<sup>15</sup>

Consider the case when sunrise (or sunset) occurs at the midpoint of the hour; the cosine of the zenith angle is zero and  $R_b$  (Equation 1.8.1) evaluated at the midpoint of

<sup>15</sup>Sunrise or sunset on a surface that does not correspond to actual sunrise or sunset does not cause problems because the zenith angle is not 90° and therefore  $R_b$  does not approach infinity. And, since the incidence angles are large during this hour, ignoring the self-shading during part of the hour will not result in significant errors.

the hour is infinite. Under these circumstances the recorded radiation is not zero so the estimated beam radiation on the tilted surface can be very large. Arbitrarily limiting  $R_b$  to some value may not be the best general approach as large values of  $R_b$  do occur even at midday at high-latitude regions during the winter. The best approach is to extend Equation 1.8.1 from an instantaneous equation to one integrated over a time period  $\omega_1$  to  $\omega_2$ . The instantaneous beam radiation incident on a tilted surface is  $\tau_b G_o R_b$  and the instantaneous beam radiation on a horizontal surface is  $\tau_b G_o$ . These expressions cannot be integrated due to the unknown dependence of  $\tau_b$  on  $\omega$ , but if  $\tau_b$  is assumed to be a constant (a reasonable assumption), the average  $R_b$  is given by

$$R_{b,\text{ave}} = \frac{\int_{\omega_1}^{\omega_2} \tau_b G_o R_b d\omega}{\int_{\omega_1}^{\omega_2} \tau_b G_o d\omega} \approx \frac{\int_{\omega_1}^{\omega_2} G_o R_b d\omega}{\int_{\omega_1}^{\omega_2} G_o d\omega} = \frac{\int_{\omega_1}^{\omega_2} \cos \theta d\omega}{\int_{\omega_1}^{\omega_2} \cos \theta_z d\omega} \quad (2.14.5)$$

It is clear that when  $\omega_1$  and  $\omega_2$  represent two adjacent hours in a day away from sunrise or sunset  $R_{b,\text{ave}} \approx R_b$ . However, when either  $\omega_1$  or  $\omega_2$  represent sunrise or sunset  $R_b$  changes rapidly and integration is needed:

$$R_{b,\text{ave}} = \frac{a}{b} \quad (2.14.6)$$

where

$$\begin{aligned} a = & (\sin \delta \sin \phi \cos \beta - \sin \delta \cos \phi \sin \beta \cos \gamma) \times \frac{1}{180} (\omega_2 - \omega_1) \pi \\ & + (\cos \delta \cos \phi \cos \beta + \cos \delta \sin \phi \sin \beta \cos \gamma) \times (\sin \omega_2 - \sin \omega_1) \\ & - (\cos \delta \sin \beta \sin \gamma) \times (\cos \omega_2 - \cos \omega_1) \end{aligned}$$

and

$$b = (\cos \phi \cos \delta) \times (\sin \omega_2 - \sin \omega_1) + (\sin \phi \sin \delta) \times \frac{1}{180} (\omega_2 - \omega_1) \pi.$$

### Example 2.14.1

On March 4 at a latitude of  $45^\circ$  and a surface slope of  $60^\circ$  determine  $R_b$  at 6:30 AM and  $R_{b,\text{ave}}$  for the hour 6 to 7 AM.

#### Solution

From Equation 1.6.1 the declination is  $-7.15^\circ$ . The cosine of the incidence angle at 6:30 AM is found from Equation 1.6.7a with  $\omega = -82.5^\circ$ ,

$$\cos \theta = \cos(45 - 60) \cos(-7.15) \cos(-82.5) + \sin(45 - 60) \sin(-7.15) = 0.157$$

and the cosine of the zenith angle is found from Equation 1.6.5,

$$\cos \theta_z = \cos(45) \cos(-7.15) \cos(82.5) + \sin(45) \sin(-7.15) = 0.004$$

so that  $R_b = \cos \theta / \cos \theta_z = 0.157/0.004 = 39.3$ , a value that is much too high. If there is any significant beam radiation (measured or estimated), then multiplying it by 39.3 will probably produce a value that exceeds the solar constant. Clearly this is a situation to be avoided.

From Equation 1.6.10 sunrise occurs at  $-82.79^\circ/15 \text{ deg/h} = 5.52 \text{ h}$  before noon, or 6:29 AM. Consequently  $\omega_1 = -82.79^\circ$  and  $\omega_2 = 75.0^\circ$  for use in Equation 2.14.6:

$$\begin{aligned}
 a &= [\sin(-7.15) \sin 45 \cos 60 - \sin(-7.15) \cos 45 \sin 60 \cos 0] \\
 &\quad \times \frac{1}{180}[(-75) - (-82.79)]\pi \\
 &\quad + [\cos(-7.15) \cos 45 \cos 60 + \cos(-7.15) \sin 45 \sin 60 \cos 0] \\
 &\quad \times [\sin(-75) - \sin(-82.79)] \\
 &\quad - \{\cos(-7.15) \sin 60 \sin 0\} \times [\cos(-75) - \cos(-82.79)] = 0.0295 \\
 b &= [\cos 45 \cos(-7.15)] \times [\sin(-75) - \sin(-82.79)] \\
 &\quad + [\sin 45 \sin(-7.15)] \times \frac{1}{180}[(-75) - (-82.79)]\pi = 0.00639
 \end{aligned}$$

Therefore  $R_{b,\text{ave}} = 0.0295/0.00639 = 4.62$ , a much more reasonable value. An alternative is to neglect the hours that contain sunrise or sunset. ■

## 2.15 RADIATION ON SLOPED SURFACES: ISOTROPIC SKY

It can be assumed [as suggested by Hottel and Woertz (1942)] that the combination of diffuse and ground-reflected radiation is isotropic. With this assumption, the sum of the diffuse from the sky and the ground-reflected radiation on the tilted surface is the same regardless of orientation, and the total radiation on the tilted surface is the sum of the beam contribution calculated as  $I_b R_b$  and the diffuse on a horizontal surface,  $I_d$ . This represents an improvement over the assumption that all radiation can be treated as beam, but better methods are available.

An improvement on this model, the **isotropic diffuse** model, was derived by Liu and Jordan (1963). The radiation on the tilted surface was considered to include three components: beam, isotropic diffuse, and solar radiation diffusely reflected from the ground. The third and fourth terms in Equation 2.14.3 are taken as zero as all diffuse radiation is assumed to be isotropic. A surface tilted at slope  $\beta$  from the horizontal has a view factor to the sky  $F_{c-s} = (1 + \cos \beta)/2$ . (If the diffuse radiation is isotropic, this is also  $R_d$ , the ratio of diffuse on the tilted surface to that on the horizontal surface.) The tilted surface has a view factor to the ground  $F_{c-g} = (1 - \cos \beta)/2$ , and if the surroundings have a diffuse reflectance of  $\rho_g$  for the total solar radiation, the reflected radiation from the surroundings on the surface will be  $I \rho_g (1 - \cos \beta)/2$ . Thus Equation 2.14.3 is modified to give the total solar radiation on the tilted surface for an hour as the sum of three terms:

$$I_T = I_b R_b + I_d \left( \frac{1 + \cos \beta}{2} \right) + I \rho_g \left( \frac{1 - \cos \beta}{2} \right) \quad (2.15.1)$$

and by the definition of  $R$ ,

$$R = \frac{I_b}{I} R_b + \frac{I_d}{I} \left( \frac{1 + \cos \beta}{2} \right) + \rho_g \left( \frac{1 - \cos \beta}{2} \right) \quad (2.15.2)$$

### Example 2.15.1

Using the isotropic diffuse model, estimate the beam, diffuse, and ground-reflected components of solar radiation and the total radiation on a surface sloped  $60^\circ$  toward the south at a latitude of  $40^\circ$  N for the hour 9 to 10 AM on February 20. Here  $I = 1.04 \text{ MJ/m}^2$  and  $\rho_g = 0.60$ .

### Solution

For this hour,  $I_o = 2.34 \text{ MJ/m}^2$ , so  $k_T = 1.04/2.34 = 0.445$ . From the Erbs correlation (Equation 2.10.1)  $I_d/I = 0.766$ . Thus

$$I_d = 0.766 \times 1.04 = 0.796 \text{ MJ/m}^2$$

$$I_b = 0.234 \times 1.04 = 0.244 \text{ MJ/m}^2$$

The hour angle  $\omega$  for the midpoint of the hour is  $-37.5^\circ$ . The declination  $\delta = -11.6^\circ$ . Then for this south-facing surface

$$\begin{aligned} R_b &= \frac{\cos(40 - 60) \cos(-11.6) \cos(-37.5) + \sin(40 - 60) \sin(-11.6)}{\cos(40) \cos(-11.6) \cos(-37.5) + \sin(40) \sin(-11.6)} \\ &= \frac{0.799}{0.466} = 1.71 \end{aligned}$$

Equation 2.15.1 gives the three radiation streams and the total:

$$\begin{aligned} I_T &= 0.244 \times 1.71 + 0.796 \left( \frac{1 + \cos 60}{2} \right) + 1.04 \times 0.60 \left( \frac{1 - \cos 60}{2} \right) \\ &= 0.417 + 0.597 + 0.156 = 1.17 \text{ MJ/m}^2 \end{aligned}$$

Thus the beam contribution is  $0.417 \text{ MJ/m}^2$ , the diffuse is  $0.597 \text{ MJ/m}^2$ , and the ground reflected is  $0.156 \text{ MJ/m}^2$ . The total radiation on the surface for the hour is  $1.17 \text{ MJ/m}^2$ . There are uncertainties in these numbers, and while they are carried to 0.001 MJ in intermediate steps for purposes of comparing sky models, they are certainly no better than 0.01. ■

This example is for a surface with a surface azimuth angle of zero. The model (Equation 2.5.1) is applicable for surfaces of any orientation, provided the correct relationship for  $R_b$  is used.

## 2.16 RADIATION ON SLOPED SURFACES: ANISOTROPIC SKY


The isotropic diffuse model (Equation 2.15.1) is easy to understand, is conservative (i.e., it tends to underestimate  $I_T$ ), and makes calculation of radiation on tilted surfaces easy. However, improved models have been developed which take into account the circumsolar diffuse and/or horizon-brightening components on a tilted surface that are shown schematically in Figure 2.16.1. Hay and Davies (1980) estimate the fraction of the diffuse that is circumsolar and consider it to be all from the same direction as the beam radiation; they do not treat horizon brightening. Reindl et al. (1990b) add a horizon-brightening term to the Hay and Davies model, as proposed by Klucher (1979), giving a model to be referred to as the HDKR model. Skartveit and Olseth (1986, 1987) and Olseth and Skartveit (1987) develop methods for estimating the beam and diffuse distribution and radiation on sloped surfaces starting with monthly average radiation. Perez et al. (1987, 1988, 1990) treat both circumsolar diffuse and horizon brightening in some detail in a series of models. Neumann et al. (2002) propose a model for circumsolar radiation that is of particular importance in predicting the performance of concentrating systems where the angular distribution of energy near the sun's disc is important. The circumsolar ratio (CSR; defined as the ratio of the energy in the solar aureole to the energy in the solar disc plus the solar aureole) is used as a parameter to describe different atmospheric conditions.

The Hay-and-Davies model is based on the assumption that all of the diffuse can be represented by two parts, the isotropic and the circumsolar. Thus all but the fourth term in Equation 2.14.3 are used. The diffuse radiation on a tilted collector is written as

$$I_{d,T} = I_{T,d,iso} + I_{T,d,cs} \quad (2.16.1)$$

and

$$I_{d,T} = I_d \left[ (1 - A_i) \left( \frac{1 + \cos \beta}{2} \right) + A_i R_b \right] \quad (2.16.2)$$



**Figure 2.16.1** Beam, diffuse, and ground-reflected radiation on a tilted surface.

where  $A_i$  is an **anisotropy index** which is a function of the transmittance of the atmosphere for beam radiation,

$$A_i = \frac{I_{bn}}{I_{on}} = \frac{I_b}{I_o} \quad (2.16.3)$$

The anisotropy index determines a portion of the horizontal diffuse which is to be treated as forward scattered; it is considered to be incident at the same angle as the beam radiation. The balance of the diffuse is assumed to be isotropic. Under clear conditions, the  $A_i$  will be high, and most of the diffuse will be assumed to be forward scattered. When there is no beam,  $A_i$  will be zero, the calculated diffuse is completely isotropic, and the model becomes the same as Equation 2.15.1.

The total radiation on a tilted surface is then

$$I_T = (I_b + I_d A_i) R_b + I_d (1 - A_i) \left( \frac{1 + \cos \beta}{2} \right) + I \rho_g \left( \frac{1 - \cos \beta}{2} \right) \quad (2.16.4)$$

The Hay-and-Davies method for calculating  $I_T$  is not much more complex than the isotropic model and leads to slightly higher<sup>16</sup> estimates of radiation on the tilted surface. Reindl et al. (1990a) and others indicate that the results obtained with this model are an improvement over the isotropic model. However, it does not account for horizon brightening. Temps and Coulson (1977) account for horizon brightening on clear days by applying a correction factor of  $1 + \sin^3(\beta/2)$  to the isotropic diffuse. Klucher (1979) modified this correction factor by a modulating factor  $f$  so that it has the form  $1 + f \sin^3(\beta/2)$  to account for cloudiness.

Reindl et al. (1990b) have modified the Hay-and-Davies model by the addition of a term like that of Klucher. The diffuse on the tilted surface is

$$I_{d,T} = I_d \left\{ (1 - A_i) \left( \frac{1 + \cos \beta}{2} \right) \left[ 1 + f \sin^3 \left( \frac{\beta}{2} \right) \right] + A_i R_b \right\} \quad (2.16.5)$$

where  $A_i$  is as defined by Equation 2.16.3 and

$$f = \sqrt{\frac{I_b}{I}} \quad (2.16.6)$$

When the beam and ground-reflected terms are added, the HDKR model (the Hay, Davies, Klucher, Reindl model) results. The total radiation on the tilted surface is then

$$I_T = (I_b + I_d A_i) R_b + I_d (1 - A_i) \left( \frac{1 + \cos \beta}{2} \right) \left[ 1 + f \sin^3 \left( \frac{\beta}{2} \right) \right] + I \rho_g \left( \frac{1 - \cos \beta}{2} \right) \quad (2.16.7)$$

<sup>16</sup>Recalculation of Example 2.15.1 with Equation 2.16.4 leads to  $I_T = 1.26 \text{ MJ/m}^2$ , about 7% higher than the isotropic assumption.

**Example 2.16.1**

Do Example 2.15.1 using the HDKR model.

**Solution**

From Example 2.15.1,  $I = 1.04 \text{ MJ/m}^2$ ,  $I_b = 0.224 \text{ MJ/m}^2$ ,  $I_d = 0.796 \text{ MJ/m}^2$ ,  $I_o = 2.34 \text{ MJ/m}^2$ , and  $R_b = 1.71$ . From Equation 2.16.3,

$$A_i = \frac{0.244}{2.34} = 0.104$$

The modulating factor  $f$ , from Equation 2.16.6, is

$$f = \sqrt{\frac{0.244}{1.04}} = 0.484$$

Then from Equation 2.16.7,

$$\begin{aligned} I_T &= (0.244 + 0.796 \times 0.104)1.71 \\ &\quad + 0.796 (1 - 0.104) \left( \frac{1 + \cos 60}{2} \right) (1 + 0.484 \sin^3 30) \\ &\quad + 1.04 \times 0.60 \left( \frac{1 - \cos 60}{2} \right) \\ &= 0.559 + 0.567 + 0.156 = 1.28 \text{ MJ/m}^2 \end{aligned}$$

In this example, the correction factor to the diffuse to account for horizon brightening is 1.06, and the total estimated radiation on the tilted surface is 9% more than that estimated by the isotropic model.<sup>17</sup> ■

The Perez et al. (1990) model is based on a more detailed analysis of the three diffuse components. The diffuse on the tilted surface is given by

$$I_{d,T} = I_d \left[ (1 - F_1) \left( \frac{1 + \cos \beta}{2} \right) + F_1 \frac{a}{b} + F_2 \sin \beta \right] \quad (2.16.8)$$

where  $F_1$  and  $F_2$  are circumsolar and horizon brightness coefficients and  $a$  and  $b$  are terms that account for the angles of incidence of the cone of circumsolar radiation (Figure 2.16.1) on the tilted and horizontal surfaces. The circumsolar radiation is considered to be from a point source at the sun. The terms  $a$  and  $b$  are given as

$$a = \max(0, \cos \theta), \quad b = \max(\cos 85, \cos \theta_z) \quad (2.16.9)$$

---

<sup>17</sup>In Chapter 5 we will multiply each of the radiation streams by transmittance and absorptance factors which are functions of the angle of incidence of those streams on collectors. Thus it is generally necessary to calculate each stream independently. The differences among the various models may become more significant when these factors are applied.

With these definitions,  $a/b$  becomes  $R_b$  for most hours when collectors will have useful outputs.

The brightness coefficients  $F_1$  and  $F_2$  are functions of three parameters that describe the sky conditions, the zenith angle  $\theta_z$ , a clearness  $\varepsilon$ , and a brightness  $\Delta$ , where  $\varepsilon$  is a function of the hour's diffuse radiation  $I_d$  and normal incidence beam radiation  $I_{b,n}$ . The clearness parameter is given by

$$\varepsilon = \frac{\frac{I_d + I_{b,n}}{I_d} + 5.535 \times 10^{-6} \theta_z^3}{1 + 5.535 \times 10^{-6} \theta_z^3} \quad (2.16.10)$$

where  $\theta_z$  is in degrees and the brightness parameter is

$$\Delta = m \frac{I_d}{I_{on}} \quad (2.16.11)$$

where  $m$  is the air mass (Equation 1.5.1) and  $I_{on}$  is the extraterrestrial normal-incidence radiation (Equation 1.4.1), written in terms of  $I$ . Thus these parameters are all calculated from data on total and diffuse radiation (i.e., the data that are used in the computation of  $I_T$ ).

The brightness coefficients  $F_1$  and  $F_2$  are functions of statistically derived coefficients for ranges of values of  $\varepsilon$ ; a recommended set of these coefficients is shown in Table 2.16.1. The equations for calculating  $F_1$  and  $F_2$  are

$$F_1 = \max \left[ 0, \left( f_{11} + f_{12} \Delta + \frac{\pi \theta_z}{180} f_{13} \right) \right] \quad (2.16.12)$$

$$F_2 = \left( f_{21} + f_{22} \Delta + \frac{\pi \theta_z}{180} f_{23} \right) \quad (2.16.13)$$

This set of equations allows calculation of the three diffuse components on the tilted surface. It remains to add the beam and ground-reflected contributions. The total radiation on the tilted surface includes five terms: the beam, the isotropic diffuse, the circumsolar

**Table 2.16.1** Brightness Coefficients for Perez Anisotropic Sky<sup>a</sup>

Range of $\varepsilon$	$f_{11}$	$f_{12}$	$f_{13}$	$f_{21}$	$f_{22}$	$f_{23}$
1.000–1.065	−0.008	0.588	−0.062	−0.060	0.072	−0.022
1.065–1.230	0.130	0.683	−0.151	−0.019	0.066	−0.029
1.230–1.500	0.330	0.487	−0.221	0.055	−0.064	−0.026
1.500–1.950	0.568	0.187	−0.295	0.109	−0.152	0.014
1.950–2.800	0.873	−0.392	−0.362	0.226	−0.462	0.001
2.800–4.500	1.132	−1.237	−0.412	0.288	−0.823	0.056
4.500–6.200	1.060	−1.600	−0.359	0.264	−1.127	0.131
6.200– $\infty$	0.678	−0.327	−0.250	0.156	−1.377	0.251

<sup>a</sup>From Perez et al. (1990).



diffuse, the diffuse from the horizon, and the ground-reflected term (which parallel the terms in Equation 2.14.3):

$$I_T = I_b R_b + I_d (1 - F_1) \left( \frac{1 + \cos \beta}{2} \right) + I_d F_1 \frac{a}{b} + I_d F_2 \sin \beta + I \rho_g \left( \frac{1 - \cos \beta}{2} \right) \quad (2.16.14)$$

Equations 2.16.8 through 2.16.14, with Table 2.16.1, constitute a working version of the Perez model. Its use is illustrated in the following example.

### Example 2.16.2

Do Example 2.15.1 using the Perez method.

#### Solution

From Example 2.15.1,  $I_o = 2.34 \text{ MJ/m}^2$ ,  $I = 1.04 \text{ MJ/m}^2$ ,  $I_b = 0.244 \text{ MJ/m}^2$ ,  $I_d = 0.796 \text{ MJ/m}^2$ ,  $\cos \theta = 0.799$ ,  $\theta = 37.0^\circ$ ,  $\cos \theta_z = 0.466$ ,  $\theta_z = 62.2^\circ$ , and  $R_b = 1.71$ .

To use Equation 2.16.14, we need  $a$ ,  $b$ ,  $\varepsilon$ , and  $\Delta$  in addition to the quantities already calculated:

$$a = \max[0, \cos 37.0] = 0.799$$

$$b = \max[\cos 85, \cos 62.2] = 0.466$$

$$\frac{a}{b} = 0.799/0.466 = 1.71 \quad (\text{the same as } R_b \text{ in Example 2.15.1})$$

Next calculate  $\Delta$ . The air mass  $m$ , from Equation 1.5.1, is

$$m = \frac{1}{\cos 62.2} = \frac{1}{0.466} = 2.144$$

We also need  $I_{on}$ . Use Equation 1.4.1 with  $n = 51$ ,

$$I_{on} = 4.92(1 + 0.033 \cos(360 \times 51/365)) = 5.025$$

From the defining equation for  $\Delta$  (Equation 2.16.11),

$$\Delta = \frac{0.796 \times 2.144}{5.025} = 0.340$$

We next calculate  $\varepsilon$  from Equation 2.16.10. Thus  $I_{b,n} = I_b / \cos \theta_z = 0.244 / \cos 62.2 = 0.523 \text{ MJ/m}^2$ , and

$$\varepsilon = \frac{\frac{0.787 + 0.523}{0.787} + 5.535 \times 10^{-6}(62.2^3)}{1 + 5.535 \times 10^{-6}(62.2^3)} = 1.29$$

With this we can go to the table of coefficients needed in the calculation of  $F_1$  and  $F_2$ . These are, for the third  $\varepsilon$  range,

$$\begin{aligned} f_{11} &= 0.330, & f_{12} &= 0.487, & f_{13} &= -0.221 \\ f_{21} &= 0.055, & f_{22} &= -0.064, & f_{23} &= -0.026 \end{aligned}$$

So

$$\begin{aligned} F_1 &= \max \left[ 0, \left( 0.330 + 0.487 \times 0.340 + \frac{62.2\pi (-0.221)}{180} \right) \right] \\ &= 0.256 \\ F_2 &= 0.055 + (-0.064) \times 0.340 + \frac{62.2\pi (-0.026)}{180} \\ &= 0.005 \end{aligned}$$

We now have everything needed to use Equation 2.16.14 to get the total radiation on the sloped surface:

$$\begin{aligned} I_T &= 0.244 \times 1.71 + 0.796 (1 - 0.256) \left( \frac{1 + \cos 60}{2} \right) + 0.796 \times 0.256 \times 1.71 \\ &\quad + 0.005 \times 0.796 \sin 60 + 1.04 \times 0.60 \left( \frac{1 - \cos 60}{2} \right) \\ &= 0.417 + 0.444 + 0.348 + 0.003 + 0.156 \\ &= 1.37 \text{ MJ/m}^2 \end{aligned}$$

This is about 6% higher than the result of the HDKR model and about 17% higher than the isotropic model for this example. ■

The next question is which of these models for total radiation on the tilted surface should be used. The isotropic model is the simplest, gives the most conservative estimates of radiation on the tilted surface, and has been widely used. The HDKR model is almost as simple to use as the isotropic and produces results that are closer to measured values. For surfaces sloped toward the equator, the HDKR model is suggested. The Perez model is more complex to use and generally predicts slightly higher total radiation on the tilted surface; it is thus the least conservative of the three methods. It agrees the best by a small margin with measurements.<sup>18</sup> For surfaces with  $\gamma$  far from  $0^\circ$  in the northern hemisphere or  $180^\circ$  in the southern hemisphere, the Perez model is suggested. (In examples to be

---

<sup>18</sup>The HDKR method yields slightly better results than either the isotropic model or the Perez model in predicting utilizable radiation when the critical radiation levels are significant. See Sections 2.20 to 2.22 for notes on utilizable energy.

shown in later chapters, the isotropic and HDKR methods will be used, as they are more amenable to hand calculation.)

## 2.17 RADIATION AUGMENTATION


It is possible to increase the radiation incident on an absorber by use of planar reflectors. In the models discussed in Sections 2.15 and 2.16, ground-reflected radiation was taken into account in the last term, with the ground assumed to be a horizontal diffuse reflector infinite in extent, and there was only one term in the summation in Equation 2.15.2. With ground reflectance normally of the order of 0.2 and low collector slopes, the contributions of ground-reflected radiation are small. However, with ground reflectances of 0.6 to 0.7 typical of snow and with high slopes,<sup>19</sup> the contribution of reflected radiation of surfaces may be substantial. In this section we show a more general case of the effects of diffuse reflectors of finite size.

Consider the geometry sketched in Figure 2.17.1. Consider two intersecting planes, the receiving surface  $c$  (i.e., a solar collector or passive absorber) and a diffuse reflector  $r$ . The angle between the planes is  $\psi$ . The angle  $\psi = 180^\circ - \beta$  if the reflector is horizontal, but the analysis is not restricted to a horizontal reflector. The length of the assembly is  $m$ . The other dimensions of the collector and reflector are  $n$  and  $p$ , as shown.

If the reflector is horizontal, Equation 2.14.3 becomes




$$I_T = I_b R_b + I_d F_{c-s} + I_r \rho_r F_{c-r} + I \rho_g F_{c-g} \quad (2.17.1)$$

where  $F_{c-s}$  is again  $(1 + \cos \beta)/2$ . The view factor  $F_{r-c}$  is obtained from Figure 2.17.2,  $F_{c-r}$  is obtained from the reciprocity relationship  $A_c F_{c-r} = A_r F_{r-c}$ , and  $F_{c-g}$  can be obtained from the summation rule,  $F_{c-s} + F_{c-r} + F_{c-g} = 1$ . The view factor  $F_{r-c}$  is shown in Figure 2.17.2 as a function of the ratios  $n/m$  and  $p/m$  for  $\psi$  of  $90^\circ$ ,  $120^\circ$ , and  $150^\circ$ .



**Figure 2.17.1** Geometric relationship of an energy receiving surface  $c$  and reflecting surface  $r$ .

<sup>19</sup>At a slope of  $45^\circ$ , a flat surface sees 85% sky and 15% ground. At a slope of  $90^\circ$ , it sees 50% sky and 50% ground.



**Figure 2.17.2** View factor  $F_{r-c}$  as a function of the relative dimensions of the collecting and reflecting surfaces. Adapted from Hamilton and Morgan (1952).

**Example 2.17.1**

A vertical window receiver in a passive heating system is 3.0 m high and 6.0 m long. There is deployed in front of it a horizontal, diffuse reflector of the same length extending out 2.4 m. What is the view factor from the reflector to the window? What is the view factor from the window to the reflector? What is the view factor from the window to the ground beyond the reflector?

**Solution**

For the given dimensions,  $n/m = 3.0/6.0 = 0.5$ ,  $p/m = 2.4/6.0 = 0.4$ , and from Figure 2.17.2(a), the view factor  $F_{r-c} = 0.27$ .

The area of the window is 18.0 m<sup>2</sup>, and the area of the reflector is 14.4 m<sup>2</sup>. From the reciprocity relationship,  $F_{c-r} = (14.4 \times 0.27)/18.0 = 0.22$ .

The view factor from window to sky,  $F_{c-s}$ , is  $(1 + \cos 90)/2$ , or 0.50. The view factor from collector to ground is then  $1 - (0.50 + 0.22) = 0.28$ . ■

If the surfaces  $c$  and  $r$  are very long in extent (i.e.,  $m$  is large relative to  $n$  and  $p$ , as might be the case with long arrays of collectors for large-scale solar applications), Hottel's "crossed-string" method gives the view factor as

$$F_{r-c} = \frac{n + p - s}{2p} \quad (2.17.2)$$


where  $s$  is the distance from the upper edge of the collector to the outer edge of the reflector, measured in a plane perpendicular to planes  $c$  and  $r$ , as shown in Figure 2.17.3. This can be determined from

$$s = (n^2 + p^2 - 2np \cos \psi)^{1/2} \quad (2.17.3)$$

[For a collector array as in Example 2.17.1 but very long in extent,  $s = (3.0^2 + 2.4^2)^{0.5} = 3.84$  m and  $F_{r-c} = (3 + 2.4 - 3.84)/4.8 = 0.33$ .]

It is necessary to know the incident radiation on the plane of the reflector. The beam component is calculated by use of  $R_{br}$  for the orientation of the reflector surface. The diffuse component must be estimated from the view factor  $F_{r-s}$ . For any orientation of the surface  $r$ ,

$$F_{r-s} + F_{r-c} + F_{r-g} = 1 \quad (2.17.4)$$



**Figure 2.17.3** Section of reflector and collector surfaces.

where the view factors are from surface  $r$  to sky, to surface  $c$ , and to ground. The view factor  $F_{r-c}$  is determined as noted above and  $F_{r-g}$  will be zero for a horizontal reflector and will be small for collectors that are long in extent. Thus as a first approximation,  $F_{r-s} = 1 - F_{r-c}$  for many practical cases (where there are no other obstructions).

There remains the question of the angle of incidence of radiation reflected from surface  $r$  on surface  $c$ . As an approximation, an average angle of incidence can be taken as that of the radiation from the midpoint of surface  $r$  to the midpoint of surface  $c$ , as shown in Figure 2.17.3.<sup>20</sup> The average angle of incidence  $\theta_r$  is given by

$$\theta_r = \sin^{-1} \left( \frac{p \sin \psi}{s} \right) \quad (2.17.5)$$

The total radiation reflected from surface  $r$  with area  $A_r$  to surface  $c$  with area  $A_c$  if  $r$  has a diffuse reflectance of  $\rho_r$  is

$$A_c I_{r \rightarrow c} = [I_b R_{br} + (1 - F_{r-c}) I_d] \rho_r A_r F_{r-c} \quad (2.17.6)$$

### Example 2.17.2

A south-facing vertical surface is 4.5 m high and 12 m long. It has in front of it a horizontal diffuse reflector of the same length which extends out 4 m. The reflectance is 0.85. At solar noon, the total irradiance on a horizontal surface is 800 W/m<sup>2</sup> of which 200 is diffuse. The zenith angle of the sun is 50°. Estimate the total radiation on the vertical surface and the angle of incidence on that part of the total that is reflected from the diffuse reflector.

### Solution

Here we have irradiance, the instantaneous radiation, instead of the hourly values of the examples in Section 2.15, so the solution will be in terms of  $G$  rather than  $I$ .

First estimate  $F_{r-c}$  from Figure 2.17.2. At  $n/m = 4.5/12 = 0.38$  and  $p/m = 4/12 = 0.33$ ,  $F_{r-c} = 0.28$ . The total radiation on the reflector is the beam component, 600 W/m<sup>2</sup>, plus the diffuse component, which is  $G_d F_{r-s}$  or  $G_d(1 - F_{r-c})$ . The radiation reflected from the reflector that is incident on the vertical surface is estimated by Equation 2.17.6:

$$G_{r \rightarrow c} = [600 + 200(1 - 0.28)] \frac{0.85 \times 48 \times 0.28}{4.5 \times 12} = 160 \text{ W/m}^2$$

The beam component on the vertical surface is obtained with  $R_b$ , which is  $\cos 40^\circ / \cos 50^\circ = 1.19$ . Then  $G_{bT} = 600 \times 1.19 = 715 \text{ W/m}^2$ . The diffuse component from the sky on the vertical surface is estimated as

$$G_{dT} = 200 \frac{1 + \cos 90^\circ}{2} = 100 \text{ W/m}^2$$

<sup>20</sup>As the reflector area becomes very large, the angle of incidence becomes that given by the ground reflectance curve of Figure 5.4.1, where the angle  $\psi$  between the reflector and the collector is  $\psi$ , the abscissa on the figure.

The total radiation on the vertical surface (neglecting reflected radiation from ground areas beyond the reflector) is the sum of the three terms:

$$G_T = 160 + 715 + 100 = 975 \text{ W/m}^2$$

An average angle of incidence of the reflected radiation on the vertical surface is estimated with Equation 2.17.5:

$$s = (4.0^2 + 4.5^2)^{0.5} = 6.02 \text{ m}$$

and

$$\theta_r = \sin^{-1}(4.5 \sin 90/6.02) = 49^\circ$$

■

The contributions of diffuse reflectors may be significant, although they will not result in large increments in incident radiation. In the preceding example, the contribution is approximately  $160 \text{ W/m}^2$ . If the horizontal surface in front of the vertical plane were ground with  $\rho_g = 0.2$ , the contribution from ground-reflected radiation would have been  $0.2 \times 800(1 - \cos 90)/2$ , or  $80 \text{ W/m}^2$ .

It has been pointed out by McDaniels et al. (1975), Grassie and Sheridan (1977), Chiam (1981, 1982), and others that a specular reflector can have more effect in augmenting radiation on a collector than a diffuse reflector.<sup>21</sup> Hollands (1971) presents a method of analysis of some reflector-collector geometries, and Bannerot and Howell (1979) show effects of reflectors on average radiation on surfaces. The effects of reflectors that are partly specular and partly diffuse are treated by Grimmer et al. (1978). The practical problem is to maintain high specular reflectance, particularly on surfaces that are facing upward. Such surfaces are difficult to protect against weathering and will accumulate snow in cold climates.

## 2.18 BEAM RADIATION ON MOVING SURFACES

Sections 2.15 to 2.17 have dealt with estimation of total radiation on surfaces of fixed orientation, such as flat-plate collectors or windows. It is also of interest to estimate the radiation on surfaces that move in various prescribed ways. Most concentrating collectors utilize beam radiation only and move to “track” the sun. This section is concerned with the calculation of beam radiation on these planes, which move about one or two axes of rotation. The tracking motions of interest are described in Section 1.7, and for each the angle of incidence is given as a function of the latitude, declination, and hour angle.

At any time the beam radiation on a surface is a function of  $G_{bn}$ , the beam radiation on a plane normal to the direction of propagation of the radiation:

$$G_{bT} = G_{bn} \cos \theta \quad (2.18.1)$$

where  $\cos \theta$  is given by equations in Section 1.7 for various modes of tracking of the collector. If the data that are available are for beam normal radiation, this equation is the

---

<sup>21</sup> See Chapter 7 for a discussion of specular reflectors.

correct one to use. Note that as with other calculations of this type, Equation 2.18.1 can be written for an hour, in terms of  $I$  rather than  $G$ , and the angles calculated for the midpoint of the hour.

### Example 2.18.1

A concentrating collector is continuously rotated on a polar axis, that is, an axis that is parallel to the earth's axis of rotation. The declination is  $17.5^\circ$ , and the beam normal solar radiation for an hour is  $2.69 \text{ MJ/m}^2$ . What is  $I_{bT}$ , the beam radiation on the aperture of the collector?

#### Solution

For a collector continuously tracking on a polar axis,  $\cos \theta = \cos \delta$  (Equation 1.7.5a). Thus

$$I_{bT} = I_{bn} \cos \delta = 2.69 \cos 17.5 = 2.57 \text{ MJ/m}^2 \quad \blacksquare$$

If radiation data on a horizontal surface are used, the  $R_b$  concept must be applied. If the data are for hours (i.e.,  $I$ ), the methods of Section 2.10 are used to estimate  $I_b$ , and  $R_b$  is determined from its definition (Equation 1.8.1) using the appropriate equation for  $\cos \theta$ . If daily data are available (i.e.,  $H$ ), estimates of hourly beam must be made using the methods of Sections 2.10, 2.11, and 2.13. This is illustrated in the next example.

### Example 2.18.2

A cylindrical concentrating collector is to be oriented so that it rotates about a horizontal east–west axis so as to constantly minimize the angle of incidence and thus maximize the incident beam radiation. It is to be located at  $35^\circ \text{ N}$  latitude. On April 13, the day's total radiation on a horizontal surface is  $22.8 \text{ MJ/m}^2$ . Estimate the beam radiation on the aperture (the moving plane) of this collector for the hour 1 to 2 PM.

#### Solution

For this date,  $\delta = 8.67^\circ$ ,  $\omega_s = 96.13^\circ$ ,  $\omega = 22.5^\circ$ ,  $H_o = 35.1 \text{ MJ/m}^2$ ,  $K_T = 22.8/35.1 = 0.65$ , and from Figure 2.11.2,  $H_d/H$  is 0.34. Thus  $H_d = 7.75 \text{ MJ/m}^2$ . From Figure 2.13.1 or Equation 2.13.1,  $r_t = 0.121$ , and from Figure 2.13.2 or Equation 2.13.2,  $r_d = 0.115$ . Thus

$$I = 22.8 \times 0.121 = 2.76 \text{ MJ/m}^2$$

and

$$I_d = 7.75 \times 0.115 = 0.89 \text{ MJ/m}^2$$

and, by difference,  $I_b = 1.87 \text{ MJ/m}^2$ .

Next, calculate  $R_b$  from the ratio of Equations 1.7.2a and 1.6.5:

$$R_b = \frac{[1 - \cos^2(8.67) \sin^2(22.5)]^{1/2}}{\cos 35 \cos 8.67 \cos 22.5 + \sin 35 \sin 8.67} = \frac{0.926}{0.835} = 1.11$$



and

$$I_{bT} = I_b R_b = 1.87 \times 1.11 = 2.1 \text{ MJ/m}^2 \quad \blacksquare$$

The uncertainties in these estimations of beam radiation are greater than those associated with estimations of total radiation, and the use of pyrliometric data is preferred if they are available.

## 2.19 AVERAGE RADIATION ON SLOPED SURFACES: ISOTROPIC SKY

In Section 2.15, the calculation of total radiation on sloped surfaces from measurements on a horizontal surface was discussed. For use in solar process design procedures,<sup>22</sup> we also need the monthly average daily radiation on the tilted surface. The procedure for calculating  $\overline{H}_T$  is parallel to that for  $I_T$ , that is, by summing the contributions of the beam radiation, the components of the diffuse radiation, and the radiation reflected from the ground. The state of development of these calculation methods for  $\overline{H}_T$  is not as satisfactory as that for  $I_T$ .

The first method is that of Liu and Jordan (1962) as extended by Klein (1977), which has been widely used. If the diffuse and ground-reflected radiation are each assumed to be isotropic, then, in a manner analogous to Equation 2.15.1, the monthly mean solar radiation on an unshaded tilted surface can be expressed as

$$\overline{H}_T = \overline{H}_b \overline{R}_b + \overline{H}_d \left( \frac{1 + \cos \beta}{2} \right) + \overline{H} \rho_g \left( \frac{1 - \cos \beta}{2} \right) \quad (2.19.1)$$

and

$$\overline{R} = \frac{\overline{H}_T}{\overline{H}} = \left( 1 - \frac{\overline{H}_d}{\overline{H}} \right) \overline{R}_b + \frac{\overline{H}_d}{\overline{H}} \left( \frac{1 + \cos \beta}{2} \right) + \rho_g \left( \frac{1 - \cos \beta}{2} \right) \quad (2.19.2)$$

where  $\overline{H}_d/\overline{H}$  is a function of  $\overline{K}_T$ , as shown in Figure 2.12.2.

The ratio of the average daily beam radiation on the tilted surface to that on a horizontal surface for the month is  $\overline{R}_b$ , which is equal to  $\overline{H}_{bT}/\overline{H}_b$ . It is a function of transmittance of the atmosphere, but Liu and Jordan suggest that it can be estimated by assuming that it has the value which would be obtained if there were no atmosphere. For surfaces that are sloped toward the equator in the northern hemisphere, that is, for surfaces with  $\gamma = 0^\circ$ ,

$$\overline{R}_b = \frac{\cos(\phi - \beta) \cos \delta \sin \omega'_s + (\pi/180) \omega'_s \sin(\phi - \beta) \sin \delta}{\cos \phi \cos \delta \sin \omega_s + (\pi/180) \omega_s \sin \phi \sin \delta} \quad (2.19.3a)$$

where  $\omega'_s$  is the sunset hour angle for the tilted surface for the mean day of the month, which is given by

$$\omega'_s = \min \left[ \begin{array}{l} \cos^{-1}(-\tan \phi \tan \delta) \\ \cos^{-1}(-\tan(\phi - \beta) \tan \delta) \end{array} \right] \quad (2.19.3b)$$

where “min” means the smaller of the two items in the brackets.

---

<sup>22</sup>See Part III.


For surfaces in the southern hemisphere sloped toward the equator, with  $\gamma = 180^\circ$ , the equations are

$$\bar{R}_b = \frac{\cos(\phi + \beta) \cos \delta \sin \omega'_s + (\pi/180) \omega'_s \sin(\phi + \beta) \sin \delta}{\cos \phi \cos \delta \sin \omega_s + (\pi/180) \omega_s \sin \phi \sin \delta} \quad (2.19.4a)$$

and

$$\omega'_s = \min \left[ \begin{array}{l} \cos^{-1}(-\tan \phi \tan \delta) \\ \cos^{-1}(-\tan(\phi + \beta) \tan \delta) \end{array} \right] \quad (2.19.4b)$$

The numerator of Equation 2.19.3a or 2.19.4a is the extraterrestrial radiation on the tilted surface, and the denominator is that on the horizontal surface. Each of these is obtained by integration of Equation 1.6.2 over the appropriate time period, from true sunrise to sunset for the horizontal surface and from apparent sunrise to apparent sunset on the tilted surface. For convenience, plots of  $\bar{R}_b$  as a function of latitude for various slopes for  $\gamma = 0^\circ$  (or  $180^\circ$  in the southern hemisphere) are shown in Figure 2.19.1. A function for  $\bar{R}_b$  is available in the Engineering Equation Solver (EES) SETP library (available at [www.fchart.com](http://www.fchart.com)).



**Figure 2.19.1** Estimated  $\bar{R}_b$  for surfaces facing the equator as a function of latitude for various  $(\phi - \beta)$ , by months. (a)  $(\phi - \beta) = 15^\circ$ ; (b)  $(\phi - \beta) = 0^\circ$ ; (c)  $(\phi - \beta) = -15^\circ$ ; (d)  $\beta = 90^\circ$ . For the southern hemisphere, interchange months as shown on Figure 1.8.2, and use the absolute value of latitude. From Beckman et al. (1977).




Figure 2.19.1 (Continued)

The following example illustrates the kind of calculations that will be used in estimating monthly radiation on collectors as part of heating system design procedures.

### Example 2.19.1

A collector is to be installed in Madison, latitude  $43^\circ$ , at a slope of  $60^\circ$  to the south. Average daily radiation data are shown in Appendix D. The ground reflectance is 0.2 for all months except December and March ( $\rho_g = 0.4$ ) and January and February ( $\rho_g = 0.7$ ). Using the isotropic diffuse assumption, estimate the monthly average radiation incident on the collector.

### Solution

The calculation is detailed below for January, and the results for the year are indicated in a table. The basic equation to be used is Equation 2.19.1. The first steps are to obtain  $\bar{H}_d/\bar{H}$  and  $\bar{R}_b$ . The ratio  $\bar{H}_d/\bar{H}$  is a function of  $\bar{K}_T$  and can be obtained from Equation 2.12.1 or Figure 2.12.2.

For the mean January day, the 17th, from Table 1.6.1,  $n = 17$ ,  $\delta = -20.9^\circ$ . The sunset hour angle is calculated from Equation 1.6.10 and is  $69.1^\circ$ . With  $n = 17$  and

$\omega_s = 69.1^\circ$ , from Equation 1.10.3 (or Figure 1.10.1 or Table 1.10.1),  $\overline{H}_o = 13.36 \text{ MJ/m}^2$ . Then  $\overline{K}_T = 6.44/13.36 = 0.48$ .

The Erbs correlation (Equation 2.12.1a) is used to calculate  $\overline{H}_d/\overline{H}$  from  $\overline{K}_T$  and  $\omega_s$  gives  $\overline{H}_d/\overline{H} = 0.41$ . The calculation of  $\overline{R}_b$  requires the sunset hour angle on the sloped collector. From Equations 2.19.3

$$\cos^{-1}[-\tan(43 - 60) \tan(-20.8)] = 96.7^\circ$$

The angle  $\omega_s$  was calculated as  $69.1^\circ$  and is less than  $96.7^\circ$ , so  $\omega'_s = 69.1^\circ$ . Then

$$\begin{aligned}\overline{R}_b &= \frac{\cos(-17) \cos(-20.9) \sin 69.1 + (\pi \times 69.1/180) \sin(-17) \sin(-20.9)}{\cos 43 \cos(-20.9) \sin 69.1 + (\pi \times 69.1/180) \sin 43 \sin(-20.9)} \\ &= 2.79\end{aligned}$$

The equation for  $\overline{H}_T$  (Equation 2.19.1) can now be solved:

$$\begin{aligned}\overline{H}_T &= 6.44 (1 - 0.41)2.79 + 6.44 \times 0.41 \left( \frac{1 + \cos 60}{2} \right) \\ &\quad + 6.44 \times 0.7 \left( \frac{1 - \cos 60}{2} \right) \\ &= 10.60 + 1.98 + 1.13 = 13.7 \text{ MJ/m}^2\end{aligned}$$

The results for the 12 months are shown in the table below. Energy quantities are in megajoules per square meter. The effects of sloping the receiving plane  $60^\circ$  to the south on the average radiation (and thus on the total radiation through the winter season) are large indeed. The  $\overline{H}_T$  values are shown to a tenth of a megajoule per square meter. The last place is uncertain due to the combined uncertainties in the data and the correlations for  $\overline{H}_d/\overline{H}$  and  $\overline{R}$ . It is difficult to put limits of accuracy on them; they are probably no better than  $\pm 10\%$ .

Month	$\overline{H}$	$\overline{H}_o$	$\overline{K}_T$	$\overline{H}_d/\overline{H}$	$\overline{R}_b$	$\rho_s$	$\overline{H}_T$
January	6.44	13.37	0.48	0.41	2.79	0.7	13.7
February	9.89	18.81	0.53	0.37	2.04	0.7	17.2
March	12.86	26.03	0.49	0.43	1.42	0.4	15.8
April	16.05	33.78	0.48	0.45	0.96	0.2	14.7
May	21.36	39.42	0.54	0.39	0.71	0.2	16.6
June	23.04	41.78	0.55	0.38	0.62	0.2	16.5
July	22.58	40.56	0.56	0.38	0.66	0.2	16.8
August	20.33	35.92	0.57	0.37	0.84	0.2	17.5
September	14.59	28.80	0.51	0.42	1.21	0.2	15.6
October	10.48	20.90	0.50	0.39	1.81	0.2	15.2
November	6.37	14.62	0.44	0.46	2.56	0.2	11.4
December	5.74	11.91	0.48	0.41	3.06	0.4	12.7



## 2.20 AVERAGE RADIATION ON SLOPED SURFACES: KT METHOD

An alternative approach to calculation of average radiation on sloped surfaces has been developed by Klein and Theilacker (KT, 1981). It is a bit more cumbersome to use but shows improved results over the isotropic method when compared with hourly calculations based on many years of radiation data. The method is first outlined below in a form restricted to surfaces facing the equator and then in a general form for surfaces of any orientation. As with Equations 2.19.1 and 2.19.2, it is based on the assumption that both diffuse and ground-reflected radiation streams are isotropic.

The long-term value of  $\bar{R}$  can be calculated by integrating  $G_T$  and  $G$  from sunrise to sunset for all days over many years of data for a single month and summing (e.g., data for all days in January for 10 years should represent the long-term average for January):

$$\bar{R} = \frac{\sum_{\text{day}=1}^N \int_{t_{\text{sr}}}^{t_{\text{ss}}} G_T dt}{\sum_{\text{day}=1}^N \int_{t_{\text{sr}}}^{t_{\text{ss}}} G dt} \quad (2.20.1)$$

The denominator is  $N\bar{H}$ . To evaluate the numerator, it is convenient to replace  $G_T$  by  $I_T$  and exchange the order of the integration and summation. Using Equation 2.15.1, the radiation at any time of the day (i.e., for any hour) for  $N$  days is

$$N\bar{I}_T = N \left[ (\bar{I} - \bar{I}_d) R_b + \bar{I}_d \left( \frac{1 + \cos \beta}{2} \right) + \bar{I} \rho_g \left( \frac{1 - \cos \beta}{2} \right) \right] \quad (2.20.2)$$

where the  $\bar{I}$  and  $\bar{I}_d$  are long-term averages of the total and the diffuse radiation, obtained by summing the values of  $I$  and  $I_d$  over  $N$  days for each particular hour and dividing by  $N$ . Equation 2.20.1 then becomes<sup>23</sup>

$$\bar{R} = \frac{\int_{t_{\text{sr}}}^{t_{\text{ss}}} \left[ (\bar{I} - \bar{I}_d) R_b + \bar{I}_d \left( \frac{1 + \cos \beta}{2} \right) + \bar{I} \rho_g \left( \frac{1 - \cos \beta}{2} \right) \right] dt}{\bar{H}} \quad (2.20.3)$$

Equations 2.13.1 and 2.13.3 define the ratios of hourly to daily total and hourly to daily diffuse radiation, and Equations 2.13.2 and 2.13.4 relate  $r_t$  and  $r_d$  to time  $\omega$  and sunset hour angle  $\omega_s$ . Combining these with Equation 2.20.3 leads, for the case of south-facing surfaces in the northern hemisphere, to

$$\begin{aligned} \bar{R} = & \frac{\cos(\phi - \beta)}{d \cos} \left[ \left( a - \frac{\bar{H}_d}{\bar{H}} \right) \left( \sin \omega'_s - \frac{\pi \omega'_s}{180} \cos \omega''_s \right) \right. \\ & + \frac{b}{2} \left( \frac{\pi \omega'_s}{180} + \sin \omega'_s (\cos \omega'_s - 2 \cos \omega''_s) \right) \\ & \left. + \frac{\bar{H}_d}{\bar{H}} \left( \frac{1 + \cos \beta}{2} \right) + \rho_g \left( \frac{1 - \cos \beta}{2} \right) \right] \end{aligned} \quad (2.20.4a)$$

<sup>23</sup>The development of this equation assumes that the day length does not change during the month.

where  $\omega'_s$  is again given by

$$\omega'_s = \min \left[ \begin{array}{l} \cos^{-1}(-\tan \phi \tan \delta) \\ \cos^{-1}(-\tan(\phi - \beta) \tan \delta) \end{array} \right] \quad (2.20.4b)$$

and

$$\omega''_s = \cos^{-1}[-\tan(\phi - \beta) \tan \delta] \quad (2.20.4c)$$

Also,  $a$  and  $b$  are given by Equations 2.13.2b and 2.13.2c, and  $d$  is given by

$$d = \sin \omega_s - \frac{\pi \omega_s}{180} \cos \omega_s \quad (2.20.4d)$$

Equations 2.20.4 can be used in the southern hemisphere for north-facing surfaces by substituting  $\phi + \beta$  for  $\phi - \beta$ .

### Example 2.20.1

Redo Example 2.19.1 for the month of January using the KT method.

#### Solution

For January, from Example 2.19.1,  $\overline{H}_o = 13.37 \text{ MJ/m}^2$ ,  $\overline{H}_d/\overline{H} = 0.41$ , and for the mean day of the month ( $n = 17$ ),  $\omega_s = \omega'_s = 69.1^\circ$ . For the mean day,

$$a = 0.409 + 0.5016 \sin(69.1 - 60) = 0.488$$

$$b = 0.6609 - 0.4767 \sin(69.1 - 60) = 0.586$$

$$d = \sin 69.1 - \frac{\pi \times 69.1}{180} \cos 69.1 = 0.504$$

$$\omega''_s = \cos^{-1}[-\tan(43 - 60) \tan(-20.9)] = 96.7^\circ$$

Using Equation 2.20.4a,

$$\begin{aligned} \overline{R} &= \frac{\cos(43 - 60)}{0.504 \cos 43} \left[ (0.488 - 0.41) \left( \sin 69.1 - \frac{\pi \times 69.1}{180} \cos 96.7 \right) \right. \\ &\quad \left. + \frac{0.586}{2} \left( \frac{\pi \times 69.1}{180} + \sin 69.1 (\cos 69.1 - 2 \cos 96.7) \right) \right] \\ &\quad + 0.41 \left( \frac{1 + \cos 60}{2} \right) + 0.7 \left( \frac{1 - \cos 60}{2} \right) \\ &= 1.553 + 0.308 + 0.175 = 2.04 \end{aligned}$$

So the monthly average radiation on the collector would be

$$\overline{H}_T = \overline{H}\overline{R} = 6.44 \times 2.04 = 13.2 \text{ MJ/m}^2$$

■

**Table 2.20.1**  $\overline{H}_T$  and  $\overline{R}$  by Liu-Jordan and KT Methods from Examples 2.19.1 and 2.20.1 (Madison,  $\beta = 60^\circ$  and  $\gamma = 0^\circ$ )

Month	Liu and Jordan (1962)		Klein and Theilacker (1981)	
	$\overline{R}$	$\overline{H}_T$ , MJ/m <sup>2</sup>	$\overline{R}$	$\overline{H}_T$ , MJ/m <sup>2</sup>
January	2.13	13.71	2.04	13.16
February	1.74	17.25	1.69	16.69
March	1.23	15.79	1.21	15.56
April	0.91	14.69	0.93	14.88
May	0.78	16.58	0.80	17.04
June	0.72	16.53	0.74	17.07
July	0.74	16.76	0.76	17.27
August	0.86	17.47	0.88	17.82
September	1.07	15.58	1.06	15.53
October	1.45	15.18	1.41	14.73
November	1.78	11.36	1.70	10.85
December	2.22	12.72	2.12	12.19

Table 2.20.1 shows a comparison of the results of the monthly calculations for Examples 2.19.1 and 2.20.1. In the winter months, the Liu-and-Jordan method indicates the higher radiation than the KT method. The situation is reversed in the summer months.

Studies of calculation of average radiation on tilted surfaces have been done which account for anisotropic diffuse by other methods. Herzog (1985) has developed a correction factor to the KT method to account for anisotropic diffuse. Page (1986) presents a very detailed discussion of the method used in compiling the tables of radiation on inclined surface that are included in Volume II of the *European Solar Radiation Atlas*. These tables show radiation on surfaces of nine orientations, including surfaces facing all compass points; the tables and the method used to compute them are designed to provide useful information for daylighting and other building applications beyond those of immediate concern in this book.

Klein and Theilacker have also developed a more general form that is valid for any surface azimuth angle  $\gamma$ . If  $\gamma \neq 0^\circ$  (or  $180^\circ$ ), the times of sunrise and sunset on the sloped surface will not be symmetrical about solar noon, and the limits of integration for the numerator of Equations 2.20.1 and 2.20.3 will have different absolute values. The equation for  $\overline{R}$  is given as

$$\overline{R} = D + \frac{\overline{H}_d}{\overline{H}} \left( \frac{1 + \cos \beta}{2} \right) + \rho_g \left( \frac{1 - \cos \beta}{2} \right) \quad (2.20.5a)$$

where

$$D = \begin{cases} \max(0, G(\omega_{ss}, \omega_{sr})) & \text{if } \omega_{ss} \geq \omega_{sr} \\ \max(0, [G(\omega_{ss}, -\omega_s) + G(\omega_s, \omega_{sr})]) & \text{if } \omega_{sr} > \omega_{ss} \end{cases} \quad (2.20.5b)$$

$$\begin{aligned}
G(\omega_1, \omega_2) = & \frac{1}{2d} \left[ \left( \frac{bA}{2} - a'B \right) (\omega_1 - \omega_2) \frac{\pi}{180} \right. \\
& + (a'A - bB)(\sin \omega_1 - \sin \omega_2) - a'C(\cos \omega_1 - \cos \omega_2) \\
& + \left( \frac{bA}{2} \right) (\sin \omega_1 \cos \omega_1 - \sin \omega_2 \cos \omega_2) \\
& \left. + \left( \frac{bC}{2} \right) (\sin^2 \omega_1 - \sin^2 \omega_2) \right] \quad (2.20.5c)
\end{aligned}$$

$$a' = a - \frac{\overline{H}_d}{\overline{H}} \quad (2.20.5d)$$

The integration of Equation 2.20.3 starts at sunrise on the sloped surface or a horizontal plane, whichever is latest. The integration ends at sunset on the surface or the horizontal, whichever is earliest. For some orientations the sun can rise and set on the surface twice during a day, resulting in two terms in the second part of Equation 2.20.5b. The sunrise and sunset hour angles for the surface are determined by letting  $\theta = 90^\circ$  in Equation 1.6.2. This leads to a quadratic equation, giving two values of  $\omega$  (which must be within  $\pm\omega_s$ ). The signs on  $\omega_{sr}$  and  $\omega_{ss}$  depend on the surface orientation:

$$|\omega_{sr}| = \min \left[ \omega_s, \cos^{-1} \frac{AB + C\sqrt{A^2 - B^2 + C^2}}{A^2 + C^2} \right] \quad (2.20.5e)$$

$$\omega_{sr} = \begin{cases} -|\omega_{sr}| & \text{if } (A > 0 \text{ and } B > 0) \text{ or } (A \geq B) \\ +|\omega_{sr}| & \text{otherwise} \end{cases}$$

$$|\omega_{ss}| = \min \left[ \omega_s, \cos^{-1} \frac{AB - C\sqrt{A^2 - B^2 + C^2}}{A^2 + C^2} \right] \quad (2.20.5f)$$

$$\omega_{ss} = \begin{cases} +|\omega_{ss}| & \text{if } (A > 0 \text{ and } B > 0) \text{ or } (A \geq B) \\ -|\omega_{ss}| & \text{otherwise} \end{cases}$$

where

$$A = \cos \beta + \tan \phi \cos \gamma \sin \beta \quad (2.20.5g)$$

$$B = \cos \omega_s \cos \beta + \tan \delta \sin \beta \cos \gamma \quad (2.20.5h)$$

$$C = \frac{\sin \beta \sin \gamma}{\cos \phi} \quad (2.20.5i)$$

Calculating  $\overline{R}$  by Equations 2.20.5 works for all surface orientations and all latitudes (including negative latitudes for the southern hemisphere). It is valid whether the sun rises



or sets on the surface twice each day (e.g., on north-facing surfaces when  $d$  is positive) or not at all. Its use is illustrated in the next example.

### Example 2.20.2

What is  $\overline{H}_T$  for the collector of Example 2.19.1, but with  $\gamma = 30^\circ$ , for the month of January estimated by Equations 2.20.5?

#### Solution

A logical order of the calculation is to obtain  $A$ ,  $B$ , and  $C$ , then  $\omega_{sr}$  and  $\omega_{ss}$ , and then  $G$ ,  $D$ ,  $\overline{R}$ , and  $\overline{H}_T$  (i.e., work backward through Equations 2.20.5). Using data from the previous examples,

$$A = \cos 60 + \tan 43 \cos 30 \sin 60 = 1.199$$

$$B = \cos 69.1 \cos 60 + \tan(-20.9) \sin 60 \cos 30 = -0.108$$

$$C = \frac{\sin 60 \sin 30}{\cos 43} = 0.592$$

Next calculate  $\omega_{sr}$ , the sunrise hour angle with Equation 2.20.5e. It will be the minimum of  $69.1^\circ$  and

$$\cos^{-1} \frac{1.199(-0.108) + 0.592\sqrt{1.199^2 - (-0.108)^2 + 0.592^2}}{1.199^2 + 0.592^2} = 68.3^\circ$$

that is,

$$|\omega_{sr}| = \min(69.1, 68.3) = 68.3^\circ$$

Since  $A > B$ ,  $\omega_{sr} = -68.3^\circ$ .

The sunset hour angle is found next. From Equation 2.20.5f,

$$\cos^{-1} \frac{-0.129 - 0.789}{1.788} = 120.9^\circ$$

Then

$$|\omega_{ss}| = \min(69, 120.9) = 69.1^\circ$$

Since  $A > B$ ,  $\omega_{ss} = 69.1^\circ$ .

We next calculate  $G$ . Since  $\omega_{ss} > \omega_{sr}$ ,  $D = \max(0, G(\omega_{ss}, \omega_{sr}))$ . From Equation 2.20.5d, with  $a = 0.488$  (from Example 2.20.1),

$$a' = 0.488 - 0.410 = 0.078$$

From Equation 2.20.5c, with  $b = 0.586$  and  $d = 0.504$  and with  $\omega_1 = \omega_{ss} = 69.1^\circ$  and  $\omega_2 = \omega_{sr} = -68.3^\circ$ ,

$$\begin{aligned}
 G(\omega_{ss}, \omega_{sr}) = \frac{1}{2 \times 0.504} \left\{ \left( \frac{0.586 \times 1.199}{2} - 0.038(-0.108) \right) [69.1 - (-68.3)] \frac{\pi}{180} \right. \\
 + [0.078 \times 1.199 - 0.586(-0.108)][\sin 69.1 - \sin(-68.3)] \\
 - 0.078 \times 0.592[\cos 69.1 - \cos(-68.3)] \\
 + \left( \frac{0.586 \times 1.199}{2} \right) [\sin 69.1 \cos 69.1 - \sin(-68.3) \cos(-68.3)] \\
 \left. + \left( \frac{0.586 \times 0.592}{2} \right) [\sin^2 69.1 - \sin^2(-68.3)] \right\} = 1.39
 \end{aligned}$$

So  $D = \max(0, 1.39) = 1.39$  and, by Equation 2.20.5a,

$$\begin{aligned}
 \bar{R} &= 1.39 + 0.41 \left( \frac{1 + \cos 60}{2} \right) + 0.7 \left( \frac{1 - \cos 60}{2} \right) = 1.94 \\
 \bar{H}_T &= \bar{H}\bar{R} = 6.44 \times 1.94 = 12.5 \text{ MJ/m}^2
 \end{aligned}$$

■


The uncertainties in estimating radiation on surfaces sloped to the east or west of south are greater than those for south-facing surfaces. Greater contributions to the daily radiation totals occur early and late in the day when the air mass is large and the atmospheric transmission is less certain and when instrumental errors in measurements made on a horizontal plane may be larger than when the sun is nearer the zenith. For surfaces with surface azimuth angles more than  $15^\circ$  from south (or north in the southern hemisphere), the KT method illustrated in Example 2.20.2 is recommended.

The methods of Sections 2.19 and 2.20 are useful for calculating monthly average radiation on a tilted surface in one step. Monthly average radiation on a tilted surface can also be calculated by repeated use of the equations in Sections 2.14 to 2.16.

## 2.21 EFFECTS OF RECEIVING SURFACE ORIENTATION ON $\bar{H}_T$

The methods outlined in the previous sections for estimating average radiation on surfaces of various orientations can be used to show the effects of slope and azimuth angle on total energy received on a surface on a monthly, seasonal, or annual basis. (Optimization of collector orientation for any solar process that meets seasonally varying energy demands, such as space heating, must ultimately be done taking into account the time dependence of these demands. The surface orientation leading to maximum output of a solar energy system may be quite different from the orientation leading to maximum incident energy.)

To illustrate the effects of the receiving surface slope on monthly average daily radiation, the methods of Section 2.19 have been used to estimate  $\bar{H}_T$  for surfaces of several slopes for values of  $\phi = 45^\circ$ ,  $\gamma = 0^\circ$ , and ground reflectance 0.2. Here,  $\bar{H}_T$  is a




**Figure 2.21.1** Variation in estimated average daily radiation on surfaces of various slopes as a function of time of year for a latitude of  $45^\circ$ ,  $\overline{K}_T$  of 0.50, surface azimuth angle of  $0^\circ$ , and a ground reflectance of 0.20.

function of  $\overline{H}_d/\overline{H}$ , which in turn is a function of the average clearness index  $\overline{K}_T$ . The illustration is for  $\overline{K}_T = 0.50$ , constant through the year, a value typical of many temperate climates. Figure 2.21.1 shows the variations of  $\overline{H}_T$  (and  $\overline{H}$ ) through the year and shows the marked differences in energy received by surfaces of various slopes in summer and winter.

Figure 2.21.2(a) shows the total annual energy received as a function of slope and indicates a maximum at approximately  $\beta = \phi$ . The maximum is a broad one, and the changes in total annual energy are less than 5% for slopes of  $20^\circ$  more or less than the optimum. Figure 2.21.2(a) also shows total “winter” energy, taken as the total energy for the months of December, January, February, and March, which would represent the time of the year when most space heating loads would occur. The slope corresponding to the maximum estimated total winter energy is approximately  $60^\circ$ , or  $\phi + 15^\circ$ . A  $15^\circ$  change in the slope of the collector from the optimum means a reduction of approximately 5% in the incident radiation. The dashed portion of the winter total curve is estimated assuming that there is substantial snow cover in January and February that results in a mean ground reflectance of 0.6 for those two months. Under this assumption, the total winter energy is less sensitive to slope than with  $\rho_g = 0.2$ . The vertical surface receives 8% less energy than does the  $60^\circ$  surface if  $\rho_g = 0.6$  and 11% less if  $\rho_g = 0.2$ .

Calculations of total annual energy for  $\phi = 45^\circ$ ,  $\overline{K}_T = 0.50$ , and  $\rho_g = 0.20$  for surfaces of slopes  $30^\circ$  and  $60^\circ$  are shown as a function of surface azimuth angle in



**Figure 2.21.2** (a) Variation of total annual energy and total winter (December to March) energy as a function of surface slope for a latitude of  $45^\circ$ ,  $\bar{K}_T$  of 0.50, and surface azimuth angle of  $0^\circ$ . Ground reflectance is 0.20 except for the dashed curve where it is taken as 0.60 for January and February. (b) Variation of total annual energy with surface azimuth angle for slopes of  $30^\circ$  and  $60^\circ$ , latitude of  $45^\circ$ ,  $\bar{K}_T$  of 0.50, and ground reflectance of 0.20.

Figure 2.21.2(b). Note the expanded scale. The reduction in annual energy is small for these examples, and the generalization can be made that facing collectors  $10^\circ$  to  $20^\circ$  east or west of south should make little difference in the annual energy received. (Not shown by annual radiation figures is the effect of azimuth angle  $\gamma$  on the diurnal distribution of radiation on the surface. Each shift of  $\gamma$  of  $15^\circ$  will shift the daily maximum of available energy by roughly an hour toward morning if  $\gamma$  is negative and toward afternoon if  $\gamma$  is positive. This could affect the performance of a system for which there are regular diurnal variations in energy demands on the process.) Note that there is implicit in these calculations the assumption that the days are symmetrical about solar noon.

Similar conclusions have been reached by others, for example, Morse and Czarnecki (1958), who estimated the relative total annual beam radiation on surfaces of variable slope and azimuth angle.

From studies of this kind, general “rules of thumb” can be stated. For maximum annual energy availability, a surface slope equal to the latitude is best. For maximum summer availability, slope should be approximately  $10^\circ$  to  $15^\circ$  less than the latitude. For maximum winter energy availability, slope should be approximately  $10^\circ$  to  $15^\circ$  more than the latitude. The slopes are not critical; deviations of  $15^\circ$  result in reduction of the order of 5%. The expected presence of a reflective ground cover such as snow leads to higher slopes for maximizing wintertime energy availability. The best surface azimuth angles for maximum incident radiation are  $0^\circ$  in the northern hemisphere or  $180^\circ$  in the southern hemisphere, that is, the surfaces should face the equator. Deviations in azimuth angles of  $10^\circ$  or  $20^\circ$  have small effect on total annual energy availability. (Note that selection of surface orientation to maximize incident solar radiation may not lead to maximum solar energy collection or to maximum delivery of solar energy to an application. This will be treated in later chapters.)

## 2.22 UTILIZABILITY

In this and the following two sections the concepts of utilizability are developed. The basis is a simple one: If only radiation above a critical or threshold intensity is useful, then we can define a radiation statistic, called utilizability, as the fraction of the total radiation that is received at an intensity higher than the critical level. We can then multiply the average radiation for the period by this fraction to find the total utilizable energy. In these sections we define utilizability and show for any critical level how it can be calculated from radiation data or estimated from  $\bar{K}_T$ .

In this section we present the concept of monthly average hourly utilizability (the  $\phi$  concept) as developed by Whillier (1953) and Hottel and Whillier (1958). Then in Section 2.23 we show how Liu and Jordan (1963) generalized Whillier's  $\phi$  curves. In Section 2.24 we show an extension of the hourly utilizability to monthly average daily utilizability (the  $\bar{\phi}$  concept) by Klein (1978). Collares-Pereira and Rabl (1979a,b) independently extended hourly utilizability to daily utilizability. Evans et al. (1982) have developed a modified and somewhat simplified general method for calculating monthly average daily utilizability.

In Chapter 6 we develop in detail an energy balance equation to represent the performance of a solar collector. The energy balance says, in essence, that the useful gain at any time is the difference between the solar energy absorbed and the thermal losses from the collector. The losses depend on the difference in temperature between the collector plate and the ambient temperature and on a heat loss coefficient. Given a coefficient, a collector temperature, and an ambient temperature (i.e., a loss per unit area), there is a value of incident radiation that is just enough so that the absorbed radiation equals the losses. This value of incident radiation is the **critical radiation level**,  $I_{Tc}$  for that collector operating under those conditions.

If the incident radiation on the tilted surface of the collector,  $I_T$ , is equal to  $I_{Tc}$ , all of the absorbed energy will be lost and there will be no useful gain. If the incident radiation exceeds  $I_{Tc}$ , there will be useful gain and the collector should be operated. If  $I_T < I_{Tc}$ , no useful gain is possible and the collector should not be operated. The utilizable energy for any hour is thus  $(I_T - I_{Tc})^+$ , where the superscript + indicates that the utilizable energy can be zero or positive but not negative.


The fraction of an hour's total energy that is above the critical level is the utilizability for that particular hour:

$$\phi_h = \frac{(I_T - I_{Tc})^+}{I_T} \quad (2.22.1)$$

where  $\phi_h$  can have values from zero to unity. The hour's utilizability is the ratio of the shaded area  $(I_T - I_{Tc})$  to the total area  $(I_T)$  under the radiation curve for the hour as shown in Figure 2.22.1. (Utilizability could be defined on the basis of rates, i.e., using  $G_T$  and  $G_{Tc}$ , but as a practical matter, radiation data are available on an hourly basis and that is the basis in use.)

The utilizability for a single hour is not useful. However, utilizability for a particular hour for a month of  $N$  days (e.g., 10 to 11 in January) in which the hour's average radiation  $\bar{I}_T$  is useful. It can be found from


$$\phi = \frac{1}{N} \sum_1^N \frac{(I_T - I_{Tc})^+}{I_T} \quad (2.22.2)$$



**Figure 2.22.1**  $G_T$  versus time for a day. For the hour shown,  $I_T$  is the area under the  $G_T$  curve;  $I_{Tc}$  is the area under the constant critical radiation level curve.

The month's average utilizable energy for the hour is the product  $N\bar{I}_T\phi$ . The calculation can be done for individual hours (10 to 11, 11 to 12, etc.) for the month and the result summed to get the month's utilizable energy. If the application is such that the conditions of critical radiation level and incident radiation are symmetrical about solar noon, the calculations can be done for hour-pairs (e.g., 10 to 11 and 1 to 2 or 9 to 10 and 2 to 3) and the amount of calculations halved.

Given hourly average radiation data by months and a critical radiation level, the next step is to determine  $\phi$ . This is done by processing the hourly radiation data  $I_T$  [as outlined by Whillier (1953)] as follows: For a given location, hour, month, and collector orientation, plot a cumulative distribution curve of  $I_T/\bar{I}_T$ . An example for a vertical south-facing surface at Blue Hill, Massachusetts, for January is shown in Figure 2.22.2 for the hour-pair 11 to 12 and 12 to 1. This provides a picture of the frequency of occurrence of clear, partly cloudy, or cloudy skies in that hour for the month. For example, for the hour-pair of Figure 2.22.2, for  $f = 0.20$ , 20% of the days have radiation that is less than 10% of the average, and for  $f = 0.80$ , 20% of the days have radiation in that hour-pair that exceeds 200% of the average.



**Figure 2.22.2** Cumulative distribution curve for hourly radiation on a south-facing vertical surface in Blue Hill, MA. Adapted from Liu and Jordan (1963).

A dimensionless critical radiation is defined as

$$X_c = \frac{I_{Tc}}{\bar{I}_T} \quad (2.22.3)$$


An example is shown as the horizontal line in Figure 2.22.2, where  $X_c = 0.75$  and  $f_c = 0.49$ . The shaded area represents the monthly utilizability, that is, the fraction of the monthly energy for the hour-pair that is above the critical level. Integrating hourly utilizability over all values of  $f_c$  gives  $\phi$  for that critical radiation level:

$$\phi = \int_{f_c}^1 \phi_h df \quad (2.22.4)$$

As the critical radiation level is varied,  $\phi_c$  varies, and graphical integrations of the curve give utilizability  $\phi$  as a function of critical radiation ratio  $X_c$ . An example derived from Figure 2.22.2 is shown in Figure 2.22.3.

Whillier (1953) and later Liu and Jordan (1963) have shown that in a particular location for a one-month period  $\phi$  is essentially the same for all hours. Thus, although the curve of Figure 2.22.3 was derived for the hour-pair 11 to 12 and 12 to 1, it is useful for all hour-pairs for the vertical surface at Blue Hill.

The line labeled “limiting curve of identical days” in Figure 2.22.3 would result from a cumulative distribution curve that is a horizontal line at a value of the ordinate of 1.0 in Figure 2.22.2. In other words, every day of the month looks like the average day. The difference between the actual  $\phi$  curve and this limiting case represents the



**Figure 2.22.3** Utilizability curve derived by numerically integrating Figure 2.22.2. Adapted from Liu and Jordan (1963).

error in utilizable energy that would be made by using a single average day to represent a whole month.

### Example 2.22.1

Calculate the utilizable energy on a south-facing vertical solar collector in Blue Hill, Massachusetts, for the month of January when the critical radiation level on the collector is  $1.07 \text{ MJ/m}^2$ . The averages of January solar radiation on a vertical surface are 1.52, 1.15, and  $0.68 \text{ MJ/m}^2$  for the hour-pairs 0.5, 1.5, and 2.5 h from solar noon.

### Solution

For the hour-pair 11 to 12 and 12 to 1, the dimensionless critical radiation ratio  $X_c$  is given as

$$X_c = \frac{1.07}{1.52} = 0.70$$

and the utilizability, from Figure 2.22.3, is 0.54. The utilizable energy on the collector during this hour is

$$\bar{I}_T \phi = 1.52 \times 0.54 = 0.82 \text{ MJ/m}^2$$

For the hour-pair 10 to 11 and 1 to 2,  $X_c = 0.93$ ,  $\phi = 0.43$ , and  $\bar{I}_T \phi = 0.49$ . For the hour-pair 9 to 10 and 2 to 3,  $X_c = 1.57$ ,  $\phi = 0.15$ , and  $\bar{I}_T \phi = 0.10$ . The average utilizable energy for the month of January is then

$$N \sum_{\text{hours}} \bar{I}_T \phi = 31 \times 2 (0.82 + 0.49 + 0.10) = 87.5 \text{ MJ/m}^2$$

■

## 2.23 GENERALIZED UTILIZABILITY

We now have a way of calculating  $\phi$  for specific locations and specific orientations. For most locations the necessary data are not available, but it is possible to make use of the observed statistical nature of solar radiation to develop generalized  $\phi$  curves that depend only on  $\bar{K}_T$ , latitude, and collector slope. As noted above,  $\phi$  curves are nearly independent of the time of day (i.e., the curves for all hour-pairs are essentially the same). It was observed in early studies (e.g., Whillier, 1953) that  $\phi$  curves based on daily totals of solar radiation are also nearly identical to hourly  $\phi$  curves. It is possible to generate  $\phi$  curves from average hourly values of radiation using the methods of Section 2.13 to break daily total radiation into hourly radiation. However, it is easier to generate  $\phi$  curves from daily totals, and this is the procedure to be described here.

The radiation data most generally available are monthly average daily radiation on horizontal surfaces. Thus, with  $\bar{K}_T$  and the long-term distribution of days having particular values of  $K_T$  from Figure 2.9.2, it is possible to generate sequences of days that represent the long-term average distribution of daily total radiation. The order of occurrence of the days is unknown, but for  $\phi$  curves the order is irrelevant.



For each of these days, the daily total radiation on an inclined collector can be estimated by a procedure similar to that in Section 2.19 for monthly average radiation. For a particular day, the radiation on a tilted surface, using the Liu-Jordan<sup>24</sup> diffuse assumption, can be written as<sup>25</sup>

$$H_T = (H - H_d) \bar{R}_b + H_d \left( \frac{1 + \cos \beta}{2} \right) + H \rho_g \left( \frac{1 - \cos \beta}{2} \right) \quad (2.23.1)$$

where the monthly average conversion of daily beam radiation on a horizontal surface to daily beam radiation on an inclined surface,  $\bar{R}_b$ , is used rather than the value for the particular day since the exact date within the month is unknown. The value of  $\bar{R}_b$  is found from Equations 2.19.3a or its equivalent. If we divide by the monthly average extraterrestrial daily radiation  $\bar{H}_o$  and introduce  $K'_T$  based on  $\bar{H}_o$  (i.e.,  $K'_T = H/\bar{H}_o$ ), Equation 2.23.1 becomes

$$\frac{H_T}{\bar{H}_o} = K'_T \left[ \left( 1 - \frac{H_d}{H} \right) \bar{R}_b + \frac{H_d}{H} \left( \frac{1 + \cos \beta}{2} \right) + \rho_g \left( \frac{1 - \cos \beta}{2} \right) \right] \quad (2.23.2)$$

The ratio  $H_d/H$  is the daily fraction of diffuse radiation and can be found from Figure 2.11.2 (or Equation 2.11.1) as a function of  $K'_T$ . Therefore, for each of the days selected from the generalized distribution curve, Equation 2.23.2 can be used to estimate the radiation on a tilted surface. The average of all the days yields the long-term monthly average radiation on the tilted surface. The ratio  $H_T/\bar{H}_T$  can then be found for each day. The data for the whole month can then be plotted in the form of a cumulative distribution curve, as illustrated in Figure 2.22.2. The ordinate will be daily totals rather than hourly values, but as has been pointed out, the shape of the two curves are nearly the same. Finally, integration of the frequency distribution curve yields a utilizability curve as illustrated in Figure 2.22.3. The process is illustrated in the following example.

### Example 2.23.1

Calculate and plot utilizability as a function of the critical radiation ratio for a collector tilted  $40^\circ$  to the south at a latitude of  $40^\circ$ . The month is February and  $\bar{K}_T = 0.5$ .

### Solution

Since the only radiation information available is  $\bar{K}_T$ , it will be necessary to generate a  $\phi$  curve from the generalized  $\bar{K}_T$  frequency distribution curves. Twenty days, each represented by a  $k_T$  from Figure 2.9.2 at  $\bar{K}_T = 0.5$ , are given in the following table. (Twenty days from the generalized distribution curves are sufficient to represent a month.)

<sup>24</sup>Other assumptions for distribution of the diffuse could be used.

<sup>25</sup>Section 2.19 is concerned with monthly average daily radiation on a tilted surface. Here we want the average radiation on an inclined surface for all days having a particular value of  $K_T$ .



Day (1)	$K_T$ (2)	$H_d/H$ (3)	$H_T/\overline{H}_o$ (4)	$H_T/\overline{H}_T$ (5)
1	0.08	0.99	0.078	0.11
2	0.15	0.99	0.145	0.20
3	0.21	0.95	0.211	0.29
4	0.26	0.92	0.269	0.37
5	0.32	0.87	0.345	0.48
6	0.36	0.82	0.405	0.56
7	0.41	0.76	0.483	0.67
8	0.46	0.68	0.576	0.80
9	0.49	0.62	0.640	0.89
10	0.53	0.55	0.726	1.01
11	0.57	0.47	0.822	1.14
12	0.59	0.43	0.872	1.21
13	0.61	0.39	0.924	1.28
14	0.63	0.36	0.972	1.35
15	0.65	0.33	1.020	1.41
16	0.67	0.30	1.070	1.48
17	0.69	0.27	1.121	1.55
18	0.72	0.24	1.189	1.65
19	0.74	0.23	1.229	1.70
20	0.79	0.21	1.326	1.84
Average = 0.721				

For any day with daily total horizontal radiation  $H$  and daily diffuse horizontal radiation  $H_d$ , the ratio of daily radiation on a south-facing tilted surface to extraterrestrial horizontal radiation is found from Equation 2.23.2. For the condition of this problem,  $\overline{R}_b = 1.79$  from Equation 2.19.3a. The view factors from the collector to the sky and ground are  $(1 + \cos \beta)/2 = 0.88$  and  $(1 - \cos \beta)/2 = 0.12$ , respectively. The ground will be assumed to be covered with snow so that  $\rho_g = 0.7$ . Equation 2.23.2 reduces to

$$\frac{H_T}{\overline{H}_o} = K'_T \left( 1.87 - 0.91 \frac{H_d}{H} \right)$$

For each day in the table,  $H_d/H$  is found from Figure 2.11.1 (or Equation 2.11.1) using the corresponding value of  $k_T$ . The results of these calculations are given in columns 2 through 4. The average of column 4 is 0.721. Column 5, the ratio of daily total radiation on a tilted surface  $H_T$  to the monthly average value  $\overline{H}_T$ , is calculated by dividing each value in column 4 by the average value. Column 5 is plotted in the first figure that follows as a function of the day since the data are already in ascending order. The integration, as indicated in this figure, is used to determine the utilizability  $\phi$ . The area under the whole curve is 1.0. The area above a particular value of  $H_T/\overline{H}_T$  is the fraction of the month's radiation that is above this level. For  $H_T/\overline{H}_T = 1.2$ , 13% of the radiation is above this level. The utilizability is plotted in the second figure. Although daily totals were used to generate this figure, the hourly  $\phi$  curves will have nearly the same shape. Consequently, the

curve can be used in hourly calculations to determine collector performance as illustrated in Example 2.22.1.



In the preceding example, a  $\phi$  curve was generated from knowledge of the monthly average solar radiation and the known statistical behavior of solar radiation. For some purposes it is necessary to know monthly average hourly utilizability. If this information is needed, the method described in Section 2.13 and illustrated in Example 2.13.3 can be used to determine monthly average hourly radiation from knowledge of monthly average daily radiation (i.e.,  $\bar{K}_T$ ).

For each hour or hour-pair, the monthly average hourly radiation incident on the collector is given by

$$\bar{I}_T = (\bar{H}r_t - \bar{H}_d r_d) R_b + \bar{H}_d \left( \frac{1 + \cos \beta}{2} \right) + \bar{H} \rho_g r_t \left( \frac{1 - \cos \beta}{2} \right) \quad (2.23.3)$$

or by dividing by  $\bar{H}$  and introducing  $\bar{H} = \bar{K}_T \bar{H}_o$ ,

$$\bar{I}_T = \bar{K}_T \bar{H}_o \left[ \left( r_t - \frac{\bar{H}_d}{\bar{H}} r_d \right) R_b + \frac{\bar{H}_d}{\bar{H}} r_d \left( \frac{1 + \cos \beta}{2} \right) + \rho_g r_t \left( \frac{1 - \cos \beta}{2} \right) \right] \quad (2.23.4)$$

The ratios  $r_t$  and  $r_d$  are found from Figures 2.13.1 and 2.13.2 for each hour-pair.

### Example 2.23.2

Estimate the utilizability for the conditions of Example 2.23.1 for the hour-pair 11 to 12 and 12 to 1. The critical radiation level is  $1.28 \text{ MJ/m}^2$ . Ground reflectance is 0.7.

#### Solution

At a latitude of  $40^\circ \text{ N}$  in February the monthly average daily extraterrestrial radiation is  $20.5 \text{ MJ/m}^2$  and the declination for the average day of the month is  $-13.0^\circ$ . The sunset hour angle and the day length of February 16, the mean day of the month, are  $78.9^\circ$  and 10.5 h, respectively. The monthly average ratio  $\bar{H}_d/\bar{H} = 0.39$  from Figure 2.12.2 and  $\omega = 7.5^\circ$ . The ratios  $r_t$  and  $r_d$  from Figures 2.13.1 and 2.13.2 are 0.158 and 0.146. For the mean day in February and from Equation 1.8.2,  $R_b = 1.62$ . Then from Equation 2.23.4

$$\begin{aligned} \bar{I}_T &= 0.5 \times 20.5[(0.158 - 0.39 \times 0.146)1.62 + 0.39 \times 0.146 \times 0.88 \\ &\quad + 0.7 \times 0.158 \times 0.12] = 2.33 \text{ MJ/m}^2 \end{aligned}$$

The critical radiation rate for this hour-pair is


$$X_c = \frac{I_{Tc}}{\bar{I}_T} = \frac{1.28}{2.33} = 0.55$$

From the figure of Example 2.23.1,  $\phi = 0.50$ . The utilizable energy (UE) for the month for this hour-pair is

$$UE = 2.33 \times 0.50 \times 2 \times 28 = 65.2 \text{ MJ/m}^2 \quad \blacksquare$$

Liu and Jordan (1963) have generalized the calculations of Example 2.23.1. They found that the shape of the  $\phi$  curves was not strongly dependent on the ground reflectance or the view factors from the collector to the sky and ground. Consequently, they were able to construct a set of  $\phi$  curves for a fixed value of  $\bar{K}_T$ . The effect of tilt was taken into account by using the monthly average ratio of beam radiation on a tilted surface to

monthly average beam radiation on a horizontal surface  $\bar{R}_b$  as a parameter. The generalized  $\phi$  curves are shown in Figures 2.23.1 for values of  $\bar{K}_T$  of 0.3, 0.4, 0.5, 0.6, and 0.7. The method of constructing these curves is exactly like Example 2.23.1, except that the tilt used in their calculations was  $47^\circ$  and the ground reflectance was 0.2. A comparison of the  $\phi$  curve from Example 2.23.1, in which the tilt was  $40^\circ$  and the ground reflectance was 0.7 with the generalized  $\phi$  curve for  $\bar{K}_T = 0.5$  and  $\bar{R}_b = 1.79$ , shows that the two are nearly identical.



**Figure 2.23.1** Generalized  $\phi$  curves for south-facing surfaces. Adapted from Liu and Jordan (1963).




Figure 2.23.1 (Continued)

With the generalized  $\phi$  curves, it is possible to predict the utilizable energy at a constant critical level by knowing only the long-term average radiation. This procedure was illustrated (for one hour-pair) in Example 2.23.2. Rather than use the  $\phi$  curve calculated in Example 2.23.1, the generalized  $\phi$  curve could have been used. The only additional calculation is determining  $\bar{R}_b$  so that the proper curve can be selected. In Example 2.23.2,  $X_c = 0.55$ . From Equation 2.19.3a,  $\bar{R}_b = 1.79$ . Figure 2.23.1(c) is used to obtain  $\phi$ ; it is approximately 0.50.

It is convenient for computations to have an analytical representation of the utilizability function. Clark et al. (1983) have developed a simple algorithm to represent the generalized  $\phi$  functions. Curves of  $\phi$  versus  $X_c$  derived from long-term weather data are represented by

$$\phi = \begin{cases} 0 & \text{if } X_c \geq X_m \\ \left(1 - \frac{X_c}{X_m}\right)^2 & \text{if } X_m = 2 \\ \left| |g| - \left[ g^2 + (1 + 2g) \left(1 - \frac{X_c}{X_m}\right)^2 \right]^{1/2} \right| & \text{otherwise} \end{cases} \quad (2.23.5a)$$

where

$$g = \frac{X_m - 1}{2 - X_m} \quad (2.23.5b)$$

$$X_m = 1.85 + 0.169 \frac{\bar{R}_h}{\bar{k}_T^2} - 0.0696 \frac{\cos \beta}{\bar{k}_T^2} - 0.981 \frac{\bar{k}_T}{\cos^2 \delta} \quad (2.23.5c)$$

The monthly average hourly clearness index  $\bar{k}_T$  is defined as

$$\bar{k}_T = \frac{\bar{I}}{\bar{I}_o} \quad (2.23.6)$$

It can be estimated using Equations 2.13.2 and 2.13.4:

$$\bar{k}_T = \frac{\bar{I}}{\bar{I}_o} = \frac{r_t}{r_d} \frac{\bar{H}}{\bar{H}_o} = \frac{r_t}{r_d} \bar{K}_T = (a + b \cos \omega) \bar{K}_T \quad (2.23.7)$$

where  $a$  and  $b$  are given by Equations 2.13.2b and 2.13.2c.

The remaining term in Equation 2.23.5 is  $\bar{R}_h$ , the ratio of monthly average hourly radiation on the tilted surface to that on a horizontal surface:

$$\bar{R}_h = \frac{\bar{I}_T}{\bar{I}} = \frac{\bar{I}_T}{r_t \bar{H}} \quad (2.23.8)$$

### Example 2.23.3

Repeat Example 2.23.2 using the Clark et al. (1983) equations.

#### Solution

The calculations to be made are  $\bar{R}_h$ ,  $\bar{k}_T$ ,  $X_m$ ,  $X_c$ ,  $g$ , and finally  $\phi$ . Intermediate results from Example 2.23.2 that are useful here are  $\bar{I}_T = 2.33 \text{ MJ/m}^2$ ,  $r_t = 0.158$ ,  $\omega_s = 78.9^\circ$ ,  $\omega = 7.5^\circ$ ,  $X_c = 0.549$ :

$$\bar{R}_h = \frac{\bar{I}_T}{\bar{I}} = \frac{\bar{I}_T}{r_t \bar{H}} = \frac{2.33}{1.58 \times 20.3 \times 0.50} = 1.44$$

To calculate  $\bar{k}_T$ , we need the constants  $a$  and  $b$  in Equation 2.23.7:

$$a = 0.409 + 0.5016 \sin(78.9 - 60) = 0.571$$

$$b = 0.6609 - 0.4767 \sin(78.9 - 60) = 0.506$$

Thus

$$\bar{k}_T = 0.50 (0.571 + 0.506 \cos 7.5) = 0.536$$

Next calculate  $X_m$  with Equation 2.23.5c:

$$\begin{aligned} X_m &= 1.85 + 0.169 \frac{1.44}{0.536^2} - \frac{0.0696 \times \cos 40}{0.536^2} - \frac{0.981 \times 0.536}{\cos^2(-13)} \\ &= 1.942 \end{aligned}$$

The last steps are to calculate  $g$  and  $\phi$  with Equations 2.23.5b and 2.23.5a:

$$g = \frac{1.942 - 1}{2 - 1.942} = 16.24$$

Then

$$\phi = \left| 16.24 - \left[ 16.24^2 + (1 + 2 \times 16.24) \left( 1 - \frac{0.549}{1.942} \right)^2 \right]^{1/2} \right| = 0.52$$

This is nearly the same  $\phi$  as that from Example 2.23.2. ■

The  $\phi$  charts graphically illustrate why a single average day should not be used to predict system performance under most conditions. The difference in utilizability as indicated by the limiting curve of identical days and the appropriate  $\phi$  curve is the error that is incurred by basing performance on an average day. Only if  $\bar{K}_T$  is high or if the critical level is very low do all  $\phi$  curves approach the limiting curve. For many situations the error in using one average day to predict performance is substantial.

The  $\phi$  curves must be used hourly, even though a single  $\phi$  curve applies for a given collector orientation, critical level, and month. This means that three to six hourly calculations must be made per month if hour-pairs are used. For surfaces facing the equator, where hour-pairs can be used, the concept of monthly average daily utilizability  $\bar{\phi}$  provides a more convenient way of calculating useful energy. However, for processes that have critical radiation levels that vary in repeatable ways through the days of a month and for surfaces that do not face the equator, the generalized  $\phi$  curves must be used for each hour.

## 2.24 DAILY UTILIZABILITY

The amount of calculations in the use of  $\phi$  curves led Klein (1978) to develop the concept of monthly average daily utilizability  $\bar{\phi}$ . This daily utilizability is defined as the sum for a




month (over all hours and days) of the radiation on a tilted surface that is above a critical level divided by the monthly radiation. In equation form,

$$\bar{\phi} = \frac{\sum_{\text{days}} \sum_{\text{hours}} (I_T - I_{Tc})^+}{\bar{H}_T N} \quad (2.24.1)$$

where the critical level is similar to that used in the  $\phi$  concept.<sup>26</sup> The monthly utilizable energy is then the product  $\bar{H}_T N \bar{\phi}$ . The concept of daily utilizability is illustrated in Figure 2.24.1. Considering either of the two sequences of days,  $\bar{\phi}$  is the ratio of the sum of the shaded areas to the total areas under the curves.

The value of  $\bar{\phi}$  for a month depends on the distribution of hourly values of radiation in the month. If it is assumed that all days are symmetrical about solar noon and that the hourly distributions are as shown in Figures 2.13.1 and 2.13.2, then  $\bar{\phi}$  depends on the distribution of daily total radiation, that is, on the relative frequency of occurrence of below-average, average, and above-average daily radiation values.<sup>27</sup> Figure 2.24.1 illustrates this point. The days in the top sequence are all average days; for the low critical radiation level represented by the solid horizontal line, the shaded areas show utilizable energy, whereas



**Figure 2.24.1** Two sequences of days with the same average radiation levels on the plane of the collector. From Klein (1978).

<sup>26</sup>The critical level for  $\bar{\phi}$  is based on monthly average “optical efficiency” and temperatures rather than on values for particular hours. This will be discussed in Chapter 21.

<sup>27</sup>Klein assumed symmetrical days in his development of  $\bar{\phi}$ . It can be shown that departure from symmetry within days (e.g., if afternoons are brighter than mornings) will lead to increases in  $\bar{\phi}$ ; thus a  $\bar{\phi}$  calculated from the correlations of this section is somewhat conservative.

for the high critical level represented by the dotted line, there is no utilizable energy. The bottom sequence shows three days of varying radiation with the same average as before; utilizable energy for the low critical radiation level is nearly the same as for the first set, but there is utilizable energy above the high critical level for the nonuniform set of days and none for the uniform set. Thus the effect of increasing variability of days is to increase  $\bar{\phi}$ , particularly at high critical radiation levels.

The monthly distribution of daily total radiation is a unique function of  $\bar{K}_T$  as shown by Figure 2.9.2. Thus the effect of daily radiation distribution on  $\bar{\phi}$  is related to a single variable,  $\bar{K}_T$ .

Klein has developed correlations for  $\bar{\phi}$  as a function of  $\bar{K}_T$  and two variables, a geometric factor  $\bar{R}/R_n$  and a dimensionless critical radiation level  $\bar{X}_c$ . The symbol  $\bar{R}$  is the monthly ratio of radiation on a tilted surface to that on a horizontal surface,  $\bar{H}_T/\bar{H}$ , and is given by Equation 2.19.2, and  $R_n$  is the ratio for the hour centered at noon of radiation on the tilted surface to that on a horizontal surface for an average day of the month. Equation 2.15.2 can be rewritten for the noon hour, in terms of  $r_{d,n}H_d$  and  $r_{t,n}H$ , as

$$R_n = \left( \frac{I_T}{I} \right)_n = \left( 1 - \frac{r_{d,n}H_d}{r_{t,n}H} \right) R_{b,n} + \left( \frac{r_{d,n}H_d}{r_{t,n}H} \right) \left( \frac{1 + \cos \beta}{2} \right) + \rho_g \left( \frac{1 - \cos \beta}{2} \right) \quad (2.24.2)$$

where  $r_{d,n}$  and  $r_{t,n}$  are obtained from Figures 2.13.1 and 2.13.2 using the curves for solar noon or from Equations 2.13.2 and 2.13.4.

Note that  $R_n$  is calculated for a day that has the day's total radiation equal to the monthly average daily total radiation, that is, a day in which  $H = \bar{H}$  ( $R_n$  is *not* the monthly average value of  $R$  at noon). The calculation of  $R_n$  is illustrated in Example 2.24.1.

A monthly average critical radiation level  $\bar{X}_c$  is defined as the ratio of the critical radiation level to the noon radiation level on a day of the month in which the day's radiation is the same as the monthly average. In equation form,

$$\bar{X}_c = \frac{I_{Tc}}{r_{t,n}R_n\bar{H}} \quad (2.24.3)$$

Klein obtained  $\bar{\phi}$  as a function of  $X_c$  for various values of  $\bar{R}/R_n$  by the following process. For a given  $\bar{K}_T$ , a set of days was established that had the correct long-term average distribution of values of  $K_T$  (i.e., that match the distributions of Section 2.9). (This is the process illustrated in Example 2.23.1.) The radiation in each of the days in a sequence was divided into hours using the correlations of Section 2.13. These hourly values of beam and diffuse radiation were used to find the total hourly radiation on a tilted surface,  $I_T$ . Critical radiation levels were then subtracted from these  $I_T$  values and summed according to Equation 2.24.1 to arrive at values of  $\bar{\phi}$ .

The  $\bar{\phi}$  curves calculated in this manner are shown in Figures 2.24.2(a–e) for  $\bar{K}_T$  values of 0.3 to 0.7. These curves can be represented by the equation

$$\bar{\phi} = \exp \left\{ \left[ a + b \left( \frac{R_n}{\bar{R}} \right) \right] [\bar{X}_c + c\bar{X}_c^2] \right\} \quad (2.24.4a)$$





Figure 2.24.2 Monthly average daily utilizability as a function of  $\bar{X}_c$  and  $\bar{R}/R_n$ .





Figure 2.24.2 (Continued)




Figure 2.24.2 (Continued)

where

$$a = 2.943 - 9.271\bar{K}_T + 4.031\bar{K}_T^2 \quad (2.24.4b)$$

$$b = -4.345 + 8.853\bar{K}_T - 3.602\bar{K}_T^2 \quad (2.24.4c)$$

$$c = -0.170 - 0.306\bar{K}_T + 2.936\bar{K}_T^2 \quad (2.24.4d)$$

### Example 2.24.1

A surface in Madison, Wisconsin, has a slope of  $60^\circ$  and a surface azimuth angle of  $0^\circ$ . For the month of March, when  $\bar{K}_T = 0.49$ ,  $\bar{H} = 12.86 \text{ MJ/m}^2$ ,  $\rho_g = 0.4$ , and the critical radiation level is  $145 \text{ W/m}^2$ , calculate  $\bar{\phi}$  and the utilizable energy.

### Solution

For the mean day of March with  $n = 75$ , the sunset hour angle is  $87.7^\circ$  from Equation 1.6.10. Then from Equations 2.13.2 and 2.13.4,  $r_{t,n} = 0.146$  and  $r_{d,n} = 0.134$ . For  $K_T = 0.49$  (i.e., a day in which  $H = \bar{H}$ ),  $H_d/H$  from Figure 2.11.2 is 0.62. From Equation 1.8.2,  $R_{b,n} = 1.38$ . Then  $R_n$  can be calculated using Equation 2.24.2:

$$\begin{aligned} R_n &= \left(1 - \frac{0.134 \times 0.62}{0.146}\right) 1.38 + \frac{0.134 \times 0.62}{0.146} \left(\frac{1 + \cos 60^\circ}{2}\right) \\ &\quad + 0.4 \left(\frac{1 - \cos 60^\circ}{2}\right) = 1.12 \end{aligned}$$

Equation 2.19.2 is used to calculate  $\bar{R}$ . From Figure 2.19.1  $\bar{R}_b = 1.42$ . From Figure 2.12.2,  $\bar{H}_d/\bar{H} = 0.43$  at  $\bar{K}_T = 0.49$ . (See Example 2.19.1 for more details.) Then

$$\bar{R} = (1 - 0.43)1.42 + 0.43 \left( \frac{1 + \cos 60}{2} \right) + 0.4 \left( \frac{1 - \cos 60}{2} \right) = 1.23$$

and

$$\frac{R_n}{\bar{R}} = \frac{1.12}{1.23} = 0.91$$

From Equation 2.24.3 the dimensionless average critical radiation level is

$$\bar{X}_c = \frac{145 \times 3600}{0.146 \times 1.12 \times 12.86 \times 10^6} = 0.25$$

We can now get the utilizability  $\bar{\phi}$  from Figure 2.24.2(c) or from Equations 2.24.4. With  $\bar{K}_T = 0.49$ ,  $a = -0.632$ ,  $b = -0.872$ ,  $c = 0.385$ , and  $\bar{\phi} = 0.64$ , the month's utilizable energy is thus

$$\bar{H}_T N \bar{\phi} = \bar{H} \bar{R} N \bar{\phi} = 12.86 \times 1.23 \times 31 \times 0.64 = 314 \text{ MJ/m}^2$$

The  $\bar{\phi}$  depend on  $\bar{R}$  and  $R_n$ , which in turn depend on the division of total radiation into beam and diffuse components. As noted in Section 2.11, there are substantial uncertainties in determining this division. The correlation of  $\bar{H}_d/\bar{H}$  versus  $\bar{K}_T$  of Liu and Jordan (1960) was used by Klein (1978) to generate the  $\bar{\phi}$  charts. The correlation of Ruth and Chant (1976), which indicates significantly higher fractions of diffuse radiation, was also used to generate  $\bar{\phi}$  charts, and the results were not significantly different from those of Figure 2.24.2. A ground reflectance of 0.2 was used in generating the charts, but a value of 0.7 was also used and it made no significant difference. Consequently, even if the diffuse-to-total correlation is changed as a result of new experimental evidence, the  $\bar{\phi}$  curves will remain valid. Of course, using different correlations will change the predictions of radiation on a tilted surface, which will change the utilizable energy estimates.

Utilizability can be thought of as a radiation statistic that has built into it critical radiation levels. The  $\phi$  and  $\bar{\phi}$  concepts can be applied to a variety of design problems, for heating systems, combined solar energy-heat pump systems, and many others. The concept of utilizability has been extended to apply to passively heated buildings, where the excess energy (unutilizable energy) that cannot be stored in a building structure can be estimated. The unutilizability idea can also apply to photovoltaic systems with limited storage capacity.

## 2.25 SUMMARY

In this chapter we have described the instruments (pyrheliometers and pyranometers) used to measure solar radiation. Radiation data are available in several forms, with the most widely available being pyranometer measurements of total (beam-plus-diffuse) radiation

on horizontal surfaces. These data are available on an hourly basis from a limited number of stations and on a daily basis for many stations.

Solar radiation information is needed in several different forms, depending on the kinds of calculations that are to be done. These calculations fall into two major categories. First (and most detailed), we may wish to calculate on an hour-by-hour basis the longtime performance of a solar process system; for this we want hourly information of solar radiation and other meteorological measurements. Second, monthly average solar radiation is useful in estimating long-term performance of some kinds of solar processes. It is not possible to predict what solar radiation will be in the future, and recourse is made to use of past data to predict what solar processes will do.

We have presented methods (and commented on their limitations) for the estimation of solar radiation information in the desired format from the data that are available. This includes estimation of beam and diffuse radiation from total radiation, time distribution of radiation in a day, and radiation on surfaces other than horizontal. We introduced the concept of utilizability, a solar radiation statistic based on levels of radiation available above critical levels. Determination of critical radiation levels for collectors will be treated in Chapters 6 and 7, and the utilizability concepts will be the basis for most of Part III, on design of solar energy processes.

## REFERENCES

- Bannerot, R. B. and J. R. Howell, *Solar Energy*, **22**, 229 (1979). "Predicted Daily and Yearly Average Radiation Performance of Optimal Trapezoidal Groove Solar Energy Collectors."
- Bannister, J. W., Solar Radiation Records, Division of Mechanical Engineering, Commonwealth Scientific and Industrial Research Organization, Australia (1966–1969).
- Beckman, W. A., S. A. Klein, and J. A. Duffie, *Solar Heating Design by the f-Chart Method*, Wiley-Interscience, New York (1977).
- Bendt, P., M. Collares-Pereira, and A. Rabl, *Solar Energy*, **27**, 1 (1981). "The Frequency Distribution of Daily Radiation Values."
- Bennett, I., *Solar Energy*, **9**, 145 (1965). "Monthly Maps of Mean Daily Insolation for the United States."
- Benseman, R. F. and F. W. Cook, *New Zealand J. Sci.*, **12**, 696 (1969). "Solar Radiation in New Zealand—The Standard Year and Radiation on Inclined Slopes."
- Boes, E. C., Sandia Report SAND 75–0565 (1975). "Estimating the Direct Component of Solar Radiation."
- Chiam, H. F., *Solar Energy*, **26**, 503 (1981). "Planar Concentrators for Flat-Plate Collectors."
- Chiam, H. F., *Solar Energy*, **29**, 65 (1982). "Stationary Reflector-Augmented Flat-Plate Collectors."
- Choudhury, N. K. D., *Solar Energy*, **7**, 44 (1963). "Solar Radiation at New Delhi."
- Clark, D. R., S. A. Klein, and W. A. Beckman, *Trans. ASME J. Solar Energy Eng.*, **105**, 281 (1983). "Algorithm for Evaluating the Hourly Radiation Utilizability Function."
- Collares-Pereira, M. and A. Rabl, *Solar Energy*, **22**, 155 (1979a). "The Average Distribution of Solar Radiation—Correlations Between Diffuse and Hemispherical and Between Daily and Hourly Insolation Values."
- Collares-Pereira, M. and A. Rabl, *Solar Energy*, **23**, 235 (1979b). "Simple Procedure for Predicting Long Term Average Performance of Nonconcentrating and of Concentrating Solar Collectors."
- Commission of the European Communities, *European Solar Radiation Atlas*, Vol. 1, *Global Radiation on Horizontal Surfaces*, Vol. 2, *Inclined Surfaces* (W. Palz, ed.), Verlag TÜV Rheinland, Köln (1984).

- Coulson, K. L., *Solar and Terrestrial Radiation*, Academic, New York (1975).
- deJong, B., *Net Radiation Received by a Horizontal Surface at the Earth*, monograph, Delft University Press, Netherlands (1973).
- Drummond, A. J., *Arch. Meteorol. Geophys. Bioklimatol. Ser. B*, **7**, 413 (1956). "On the Measurement of Sky Radiation."
- Drummond, A. J., *J. Appl. Meteorol.*, **3**, 810 (1964). "Comments on Sky Radiation Measurement and Corrections."
- Erbs, D. G., S. A. Klein, and J. A. Duffie, *Solar Energy*, **28**, 293 (1982). "Estimation of the Diffuse Radiation Fraction for Hourly, Daily, and Monthly-Average Global Radiation."
- Evans, D. L., T. T. Rule, and B. D. Wood, *Solar Energy*, **28**, 13 (1982). "A New Look at Long Term Collector Performance and Utilizability."
- Farber, E. A. and C. A. Morrison, in *Applications of Solar Energy for Heating and Cooling of Buildings* (R. C. Jordan and B. Y. H. Liu, eds.) ASHRAE GRP-170, New York (1977). "Clear-Day Design Values."
- Foster, N. B. and L. W. Foskett, *Bull. Am. Meteorol. Soc.*, **34**, 212 (1953). "A Photoelectric Sunshine Recorder."
- Fritz, S., in *Transactions of the Conference on Use of Solar Energy* (E. F. Carpenter, ed.), Vol. **1**, University of Arizona Press, Tucson, p. 17 (1958). "Transmission of Solar Energy through the Earth's Clear and Cloudy Atmosphere."
- Grassie, S. L. and N. L. Sheridan, *Solar Energy*, **19**, 663 (1977). "The Use of Planar Reflectors for Increasing the Energy Yield of Flat-Plate Collectors."
- Grimmer, D. P., K. G. Zinn, K. C. Herr, and B. E. Wood, Report LA-7041 of Los Alamos Scientific Lab (1978). "Augmented Solar Energy Collection Using Various Planar Reflective Surfaces: Theoretical Calculations and Experimental Results."
- Gueymard, C., *Energy*, **30**, 1551 (2005). "Interdisciplinary Applications of a Versatile Spectral Solar Irradiance Model: A Review." See [www.nrel.gov/rredc/SMARTS](http://www.nrel.gov/rredc/SMARTS).
- Hamilton, D. C. and W. R. Morgan, National Advisory Committee for Aeronautics, Technical Note 2836 (1952). "Radiant Interchange Configuration Factors."
- Hay, J. E. and J. A. Davies, in *Proceedings of the First Canadian Solar Radiation Data Workshop* (J. E. Hay and T. K. Won, eds.), Ministry of Supply and Services, Toronto, Canada, p. 59 (1980). "Calculation of the Solar Radiation Incident on an Inclined Surface."
- Hay, J. E. and D. C. McKay, *Int. J. Solar Energy*, **3**, 203 (1985). "Estimating Solar Irradiance on Inclined Surfaces: A Review and Assessment of Methodologies."
- Herzog, M. E., M. S. Thesis, Trinity University (1985). "Estimation of Hourly and Monthly Average Daily Insolation on Tilted Surfaces."
- Hollands, K. G. T., *Solar Energy*, **13**, 149 (1971). "A Concentrator for Thin-Film Solar Cells."
- Hollands, K. G. T. and R. G. Huget, *Solar Energy*, **30**, 195 (1983). "A Probability Density Function for the Clearness Index, with Applications."
- Hottel, H. C., *Solar Energy*, **18**, 129 (1976). "A Simple Model for Estimating the Transmittance of Direct Solar Radiation Through Clear Atmospheres."
- Hottel, H. C. and A. Whillier, in *Transactions of the Conference on Use of Solar Energy* (E. F. Carpenter, ed.), Vol. **2**, University of Arizona Press, Tucson, p. 74 (1958). "Evaluation of Flat-Plate Solar Collector Performance."
- Hottel, H. C. and B. B. Woertz, *Trans. ASME*, **64**, 91 (1942). "Performance of Flat-Plate Solar Heat Collectors."
- Ibáñez, M., J. I. Rosell, and W. A. Beckman, *Solar Energy*, **75**, 73 (2003). "A Bi-variable Probability Density Function for the Daily Clearness Index."
- IGY Instruction Manual, Pergamon Press, London, Vol. **V**, Pt. **VI**, p. 426 (1958). "Radiation Instruments and Measurements."



- Iqbal, M., *Solar Energy*, **22**, 87 (1979). "A Study of Canadian Diffuse and Total Solar Radiation Data—II Monthly Average Hourly Radiation."
- Iqbal, M., *An Introduction to Solar Radiation*, Academic, Toronto (1983).
- Jeys, T. H. and L. L. Vant-Hull, *Solar Energy*, **18**, 343 (1976). "The Contribution of the Solar Aureole to the Measurements of Pyrheliometers."
- Klein, S. A., *Solar Energy*, **19**, 325 (1977). "Calculation of Monthly Average Insolation on Tilted Surfaces."
- Klein, S. A., *Solar Energy*, **21**, 393 (1978). "Calculations of Flat-Plate Collector Utilizability."
- Klein, S. A. and J. A. Duffie, in *Proceedings of 1978 Annual Meeting American Section* (K. W. Böer and G. E. Franta eds.), Vol. **2.2**, International Solar Energy Society, Denver, CO, p. 672 (1978). "Estimation of Monthly Average Diffuse Radiation."
- Klein, S. A. and J. C. Theilacker, *Trans. ASME J. Solar Energy Eng.*, **103**, 29 (1981). "An Algorithm for Calculating Monthly-Average Radiation on Inclined Surfaces."
- Klucher, T. M., *Solar Energy*, **23**, 111 (1979). "Evaluating Models to Predict Insolation on Tilted Surfaces."
- Knight, K. M., S. A. Klein, and J. A. Duffie, *Solar Energy*, **46**, 109 (1991). "A Methodology for the Synthesis of Hourly Weather Data."
- Kondratyev, K. Y., *Actinometry (translated from Russian)*, NASA TT F-9712 (1965); also *Radiation in the Atmosphere*, Academic, New York (1969).
- Latimer, J. R., in *Proceedings of the First Canadian Solar Radiation Data Workshop* (J. E. Hay and T. K. Won, eds.), Ministry of Supply and Services, Toronto, Canada, p. 81 (1980). "Canadian Procedures for Monitoring Solar Radiation."
- Liu, B. Y. H. and R. C. Jordan, *Solar Energy*, **4** (3), 1 (1960). "The Interrelationship and Characteristic Distribution of Direct, Diffuse and Total Solar Radiation."
- Liu, B. Y. H. and R. C. Jordan, *ASHRAE J.*, **3** (10), 53 (1962). "Daily Insolation on Surfaces Tilted Toward the Equator."
- Liu, B. Y. H. and R. C. Jordan, *Solar Energy*, **7**, 53 (1963). "The Long-Term Average Performance of Flat-Plate Solar Energy Collectors."
- Löf, G. O. G., J. A. Duffie, and C. O. Smith, Engineering Experiment Station Report 21, University of Wisconsin, Madison (July 1966a). "World Distribution of Solar Radiation."
- Löf, G. O. G., J. A. Duffie, and C. O. Smith, *Solar Energy*, **10**, 27 (1966b). "World Distribution of Solar Energy."
- McDaniels, D. K., D. H. Lowndes, H. Mathew, J. Reynolds, and R. Gray, *Solar Energy*, **17**, 277 (1975). "Enhanced Solar Energy Collection Using Reflector-Solar Thermal Collector Combinations."
- MacDonald, T. H., *Monthly Weather Rev.*, **79** (8), 153 (1951). "Some Characteristics of the Eppley Pyrheliometer."
- Moon, P., J. Franklin Institute, **230**, 583 (1940). "Proposed Standard Solar Radiation Curves for Engineering Use."
- Morse, R. N. and J. T. Czarnecki, Report E.E.6 of Engineering Section, Commonwealth Scientific and Industrial Research Organization, Melbourne, Australia (1958). "Flat-Plate Solar Absorbers: The Effect on Incident Radiation of Inclination and Orientation."
- Neumann, A., A. Witzke, S. A. Jones, and G. Schmitt, *J. Solar Energy Eng.*, **124**, 198 (2002). "Representative Terrestrial Solar Brightness Profiles."
- Norris, D. J., *Solar Energy*, **12**, 107 (1968). "Correlation of Solar Radiation with Clouds."
- Norris, D. J., *Solar Energy*, **14**, 99 (1973). "Calibration of Pyranometers."
- Norris, D. J., *Solar Energy*, **16**, 53 (1974). "Calibration of Pyranometers in Inclined and Inverted Positions."
- NSRDB National Solar Radiation Data Base. [redc.nrel.gov/solar/old-data/nsrdb/1991-2005/TMY3](http://redc.nrel.gov/solar/old-data/nsrdb/1991-2005/TMY3).

- Olseth, J. A. and A. Skartveit, *Solar Energy*, **339**, 343 (1987). "A Probability Density Model for Hourly Total and Beam Irradiance on Arbitrarily Oriented Planes."
- Orgill, J. F. and K. G. T. Hollands, *Solar Energy*, **19**, 357 (1977). "Correlation Equation for Hourly Diffuse Radiation on a Horizontal Surface."
- Page, J. K., *Proc. UN Conf. New Sources of Energy*, **4**, 378 (1964). "The Estimation of Monthly Mean Values of Daily Total Short-Wave Radiation of Vertical and Inclined Surfaces from Sunshine Records for Latitudes 40°N—40°S."
- Page, J. K., Prediction of Solar Radiation on Inclined Surfaces, *Reidel (for the Commission of the European Communities)*, Dordrecht, Holland (1986).
- Paltridge, G. W. and D. Proctor, *Solar Energy*, **18**, 235 (1976). "Monthly Mean Solar Radiation Statistics for Australia"
- Perez, R., R. Seals, P. Ineichen, R. Stewart, and D. Menicucci, *Solar Energy*, **39**, 221 (1987). "A New Simplified Version of the Perez Diffuse Irradiance Model for Tilted Surfaces."
- Perez, R., R. Stewart, R. Seals, and T. Guertin, Sandia National Laboratories Contractor Report SAND88-7030 (Oct. 1988). "The Development and Verification of the Perez Diffuse Radiation Model."
- Perez, R., P. Ineichen, R. Seals, J. Michalsky, and R. Stewart, *Solar Energy*, **44**, 271 (1990). "Modeling Daylight Availability and Irradiance Components from Direct and Global Irradiance."
- Reindl, D. T., M. S. Thesis, *Mechanical Engineering*, University of Wisconsin-Madison (1988). "Estimating Diffuse Radiation on Horizontal Surfaces and Total Radiation on Tilted Surfaces."
- Reindl, D. T., W. A. Beckman, and J. A. Duffie, *Solar Energy*, **45**, 1 (1990a). "Diffuse Fraction Correlations."
- Reindl, D. T., W. A. Beckman, and J. A. Duffie, *Solar Energy*, **45**, 9 (1990b). "Evaluation of Hourly Tilted Surface Radiation Models."
- Robinson, N. (ed.), *Solar Radiation*, Elsevier, Amsterdam (1966).
- Ruth, D. W. and R. E. Chant, *Solar Energy*, **18**, 153 (1976). "The Relationship of Diffuse Radiation to Total Radiation in Canada."
- Saunier, G. Y., T. A. Reddy, and S. Kumar, *Solar Energy*, **38**, 169 (1987). "A Monthly Probability Distribution Function of Daily Global Irradiation Values Appropriate for Both Tropical and Temperate Locations."
- Skartveit, A. and J. A. Olseth, *Solar Energy*, **36**, 333 (1986). "Modelling Sloped Irradiance at High Latitudes."
- Skartveit, A. and J. A. Olseth, *Solar Energy*, **38**, 271 (1987). "A Model for the Diffuse Fraction of Hourly Global Radiation."
- SOLMET Manual, Vols. 1 and 2, U.S. National Climatic Center, Ashville, NC (1978).
- Stanhill, G., *Solar Energy*, **10** (2), 69 (1966). "Diffuse Sky and Cloud Radiation in Israel."
- Stewart, R., D. W. Spencer, and R. Perez, in *Advances in Solar Energy*, Vol. 2 (K. Boer and J. A. Duffie, eds.), Plenum, NY, p. 1 (1985). "The Measurement of Solar Radiation."
- Temps, R. C. and K. L. Coulson, *Solar Energy*, **19**, 179 (1977). "Solar Radiation Incident Upon Slopes of Different Orientations."
- Thekaekara, M. P., in *Supplement to the Proceedings of the Twentieth Annual Meeting of the Institute for Environmental Science*, NASA Goddard Space Flight Center, Greenbelt, MD, p. 21 (1974). "Data on Incident Solar Energy."
- Thekaekara, M. P., *Solar Energy*, **28**, 309 (1976). "Solar Radiation Measurement: Techniques and Instrumentation."
- Trewartha, G. T., *An Introduction to Climate*, 3rd ed., McGraw-Hill, New York (1954).
- Trewartha, G. T., *The Earth's Problem Climates*, University of Wisconsin Press, Madison (1961).
- Tuller, S. E., *Solar Energy*, **18**, 259 (1976). "The Relationship Between Diffuse, Total and Extraterrestrial Solar Radiation."
- Whillier, A., Ph.D., Thesis, MIT, Cambridge, MA (1953). "Solar Energy Collection and Its Utilization for House Heating."

- Whillier, A., *Arch. Met. Geoph. Biokl. Ser. B*, **7**, 197 (1956). "The Determination of Hourly Values of Total Radiation from Daily Summations."
- Whillier, A., *Solar Energy*, **9**, 164 (1965). "Solar Radiation Graphs."
- Wiebelt, J. A. and J. B. Henderson, *Trans. ASME J. Heat Transfer*, **101**, 101 (1979). "Selected Ordinates for Total Solar Radiation Property Evaluation from Spectral Data."
- World Meteorological Organization, *Guide to Meteorological Instruments and Observing Practices*, 3rd ed., WMO and T.P.3, WMO, Geneva (1969).
- World Meteorological Organization, Solar Radiation and Radiation Balance Data (*The World Network*) (Annual data compilations, World Radiation Data Centre, Voeikov Main Geophysical Observatory, Leningrad).
- Yellott, J. I., in *Applications of Solar Energy for Heating and Cooling of Buildings* (R. C. Jordan and B. Y. H. Liu, eds.), ASHRAE, New York (1977). "Solar Radiation Measurement."

## Selected Heat Transfer Topics

This chapter is intended to review those aspects of heat transfer that are important in the design and analysis of solar collectors and systems. It begins with a review of radiation heat transfer, which is often given cursory treatment in standard heat transfer courses. The next sections review some convection correlations for internal flow and wind-induced flow.

The role of convection and conduction heat transfer in the performance of solar systems is obvious. Radiation heat transfer plays a role in bringing energy to the earth, but not so obvious is the significant role radiation heat transfer plays in the operation of solar collectors. In usual engineering practice radiation heat transfer is often negligible. In a solar collector the energy flux is often two orders of magnitude smaller than in conventional heat transfer equipment, and thermal radiation is a significant mode of heat transfer.

### 3.1 THE ELECTROMAGNETIC SPECTRUM

Thermal radiation is electromagnetic energy that is propagated through space at the speed of light. For most solar energy applications, only thermal radiation is important. Thermal radiation is emitted by bodies by virtue of their temperature; the atoms, molecules, or electrons are raised to excited states, return spontaneously to lower energy states, and in doing so emit energy in the form of electromagnetic radiation. Because the emission results from changes in electronic, rotational, and vibrational states of atoms and molecules, the emitted radiation is usually distributed over a range of wavelengths.

The spectrum of electromagnetic radiation is divided into wavelength bands. These bands and the wavelengths representing their approximate limits are shown in Figure 3.1.1. The wavelength limits associated with the various names and the mechanism producing the radiation are not sharply defined. There is no basic distinction between these ranges of radiation other than the wavelength  $\lambda$ ; they all travel with the speed of light  $C$  and have a frequency  $\nu$  such that

$$C = \frac{C_o}{n} = \lambda \nu \quad (3.1.1)$$

where  $C_o$  is the speed of light in a vacuum and  $n$  is the index of refraction.

The wavelengths of importance in solar energy and its applications are in the ultraviolet to near-infrared range, that is, from 0.29 to approximately 25  $\mu\text{m}$ . This includes the visible spectrum, light being a particular portion of the electromagnetic spectrum to which the




Figure 3.1.1 The spectrum of electromagnetic radiation.

human eye responds. Solar radiation outside the atmosphere has most of its energy in the range of  $0.25$  to  $3 \mu\text{m}$ , while solar energy received at the ground is substantially in the range of  $0.29$  to  $2.5 \mu\text{m}$  as noted in Chapters 1 and 2.

## 3.2 PHOTON RADIATION

For some purposes in solar energy applications, the classical electromagnetic wave view of radiation does not explain the observed phenomena. In this connection, it is necessary to consider the energy of a particle or photon, which can be thought of as an “energy unit” with zero mass and zero charge. The energy of the photon is given by

$$E = h\nu \quad (3.2.1)$$

where  $h$  is Planck’s constant ( $6.6256 \times 10^{-34}$  J s). It follows that as the frequency  $\nu$  increases (i.e., as the wavelength  $\lambda$  decreases), the photon energy increases. This fact is particularly significant where a minimum photon energy is needed to bring about a required change (e.g., the creation of a hole–electron pair in a photovoltaic device). There is thus an upper limit of wavelength of radiation that can cause the change.

## 3.3 THE BLACKBODY: PERFECT ABSORBER AND EMITTER

By definition, a blackbody is a perfect absorber of radiation. No matter what wavelengths or directions describe the radiation incident on a blackbody, all incident radiation will be absorbed. A blackbody is an ideal concept since all real substances will reflect some radiation.

Even though a true blackbody does not exist in nature, some materials approach a blackbody. For example, a thick layer of carbon black can absorb approximately 99% of all incident thermal radiation. This absence of reflected radiation is the reason for the name given to a blackbody. The eye would perceive a blackbody as being black. However, the eye is not a good indicator of the ability of a material to absorb radiation, since the eye is only sensitive to a small portion of the wavelength range of thermal radiation. White paints are good reflectors of visible radiation, but most are good absorbers of infrared radiation.

A blackbody is also a perfect emitter of thermal radiation. In fact, the definition of a blackbody could have been put in terms of a body that emits the maximum possible radiation. A simple thought experiment can be used to show that if a body is a perfect emitter of radiation, then it must also be a perfect absorber of radiation. Suppose a small blackbody and small nonblackbody are placed in a large evacuated enclosure made from a blackbody material. If the enclosure is isolated from the surroundings, then the blackbody, the real body, and the enclosure will in time come to the same equilibrium temperature. The blackbody must, by definition, absorb the entire radiation incident on it, and to maintain a constant temperature, the blackbody must also emit an equal amount of energy. The nonblackbody in the enclosure must absorb less radiation than the blackbody and will consequently emit less radiation than the blackbody. Thus a blackbody both absorbs and emits the maximum amount of radiation.

### 3.4 PLANCK'S LAW AND WIEN'S DISPLACEMENT LAW

Radiation in the region of the electromagnetic spectrum from approximately 0.2 to approximately 1000  $\mu\text{m}$  is called thermal radiation and is emitted by all substances by virtue of their temperature. The wavelength distribution of radiation emitted by a blackbody is given by Planck's law<sup>1</sup> (Richtmyer and Kennard, 1947):

$$E_{\lambda b} = \frac{2\pi h C_o^2}{\lambda^5 [\exp(h C_o / \lambda k T) - 1]} \quad (3.4.1)$$

where  $h$  is Planck's constant and  $k$  is Boltzmann's constant. The groups  $2\pi h C_o^2$  and  $h C_o / k$  are often called Planck's first and second radiation constants and given the symbols  $C_1$  and  $C_2$ , respectively.<sup>2</sup> Recommended values are  $C_1 = 3.7405 \times 10^8 \text{ W } \mu\text{m}^4/\text{m}^2$  and  $C_2 = 14,387.8 \text{ } \mu\text{m K}$ .

It is also of interest to know the wavelength corresponding to the maximum intensity of blackbody radiation. By differentiating Planck's distribution and equating to zero, the wavelength corresponding to the maximum of the distribution can be derived. This leads to Wien's displacement law, which can be written as

$$\lambda_{\max} T = 2897.8 \text{ } \mu\text{m K} \quad (3.4.2)$$

Planck's law and Wien's displacement law are illustrated in Figure 3.4.1, which shows spectral radiation distribution for blackbody radiation from sources at 6000, 1000, and 400 K. The shape of the distribution and the displacement of the wavelength of maximum intensity are clearly shown. Note that 6000 K represents an approximation of the surface temperature of the sun so the distribution shown for that temperature is an approximation of the distribution of solar radiation outside the earth's atmosphere. The other

<sup>1</sup>The symbol  $E_{\lambda b}$  represents energy per unit area per unit time per unit wavelength interval at wavelength  $\lambda$ . The subscript  $b$  represents blackbody.

<sup>2</sup>Sometimes the definition of  $C_1$  does not include the factor  $2\pi$ .




Figure 3.4.1 Spectral distribution of blackbody radiation.

two temperatures are representative of those encountered in low- and high-temperature solar-heated surfaces.


The same information shown in Figure 3.4.1 has been replotted on a normalized linear scale in Figure 3.4.2. The ordinate on this figure, which ranges from 0 to 1, is the ratio of the spectral emissive power to the maximum value at the same temperature. This clearly shows the wavelength division between a 6000 K source and lower temperature sources at 1000 and 400 K.

### 3.5 STEFAN-BOLTZMANN EQUATION

Planck's law gives the spectral distribution of radiation from a blackbody, but in engineering calculations the total energy is often of more interest. By integrating Planck's law over all wavelengths, the total energy emitted per unit area by a blackbody is found to be

$$E_b = \int_0^{\infty} E_{\lambda b} d\lambda = \sigma T^4 \quad (3.5.1)$$

where  $\sigma$  is the Stefan-Boltzmann constant and is equal to  $5.6697 \times 10^{-8} \text{ W/m}^2 \text{ K}^4$ . This constant appears in essentially all radiation equations.



**Figure 3.4.2** Normalized spectral distribution of blackbody radiation.

### 3.6 RADIATION TABLES

Starting with Planck's law (Equation 3.4.1) of the spectral distribution of blackbody radiation, Dunkle (1954) has presented a method for simplifying blackbody calculations. Planck's law can be written as

$$E_{\lambda b} = \frac{C_1}{\lambda^5 [\exp(C_2/\lambda T) - 1]} \quad (3.6.1)$$

Equation 3.6.1 can be integrated to give the radiation between any wavelength limits. The total emitted from zero to any wavelength  $\lambda$  is given by

$$E_{0-\lambda b} = \int_0^\lambda E_{\lambda b} d\lambda \quad (3.6.2)$$

Substituting Equation 3.6.1 into 3.6.2 and noting that by dividing by  $\sigma T^4$  the integral can be made to be only a function of  $\lambda T$ ,

$$f_{0-\lambda T} = \frac{E_{0-\lambda T}}{\sigma T^4} = \int_0^{\lambda T} \frac{C_1 d(\lambda T)}{\sigma (\lambda T)^5 [\exp(C_2/\lambda T) - 1]} \quad (3.6.3)$$

The value of this integral is the fraction of the blackbody energy between zero and  $\lambda T$ . Sargent (1972) has calculated values for convenient intervals and the results are given in Tables 3.6.1a and b. (Note that when the upper limit of integration of Equation 3.6.3 is infinity, the value of the integral is unity.)

For use in a computer, the following polynomial form of Equation 3.6.3 has been given by Siegel and Howell (2002):

$$f_{0-\lambda T} = \frac{15}{\pi^4} \sum_{n=1}^{\infty} \left[ \frac{e^{-n\gamma}}{n} \left( \gamma^3 + \frac{3\gamma^2}{n} + \frac{6\gamma}{n^2} + \frac{6}{n^3} \right) \right] \quad (3.6.4)$$

where  $\gamma = C_2/\lambda T$ . In practice the summation to 10 terms is sufficient.



**Table 3.6.1a** Fraction of Blackbody Radiant Energy between Zero and  $\lambda T$  for Even Increments of  $\lambda T$ 

$\lambda T, \mu m K$	$f_{0-\lambda T}$	$\lambda T, \mu m K$	$f_{0-\lambda T}$	$\lambda T, \mu m K$	$f_{0-\lambda T}$
1,000	0.0003	4,500	0.5643	8,000	0.8562
1,100	0.0009	4,600	0.5793	8,100	0.8601
1,200	0.0021	4,700	0.5937	8,200	0.8639
1,300	0.0043	4,800	0.6075	8,300	0.8676
1,400	0.0077	4,900	0.6209	8,400	0.8711
1,500	0.0128	5,000	0.6337	8,500	0.8745
1,600	0.0197	5,100	0.6461	8,600	0.8778
1,700	0.0285	5,200	0.6579	8,700	0.8810
1,800	0.0393	5,300	0.6693	8,800	0.8841
1,900	0.0521	5,400	0.6803	8,900	0.8871
2,000	0.0667	5,500	0.6909	9,000	0.8899
2,100	0.0830	5,600	0.7010	9,100	0.8927
2,200	0.1009	5,700	0.7107	9,200	0.8954
2,300	0.1200	5,800	0.7201	9,300	0.8980
2,400	0.1402	5,900	0.7291	9,400	0.9005
2,500	0.1613	6,000	0.7378	9,500	0.9030
2,600	0.1831	6,100	0.7461	9,600	0.9054
2,700	0.2053	6,200	0.7541	9,700	0.9076
2,800	0.2279	6,300	0.7618	9,800	0.9099
2,900	0.2506	6,400	0.7692	9,900	0.9120
3,000	0.2732	6,500	0.7763	10,000	0.9141
3,100	0.2958	6,600	0.7831	11,000	0.9318
3,200	0.3181	6,700	0.7897	12,000	0.9450
3,300	0.3401	6,800	0.7961	13,000	0.9550
3,400	0.3617	6,900	0.8022	14,000	0.9628
3,500	0.3829	7,000	0.8080	15,000	0.9689
3,600	0.4036	7,100	0.8137	16,000	0.9737
3,700	0.4238	7,200	0.8191	17,000	0.9776
3,800	0.4434	7,300	0.8244	18,000	0.9807
3,900	0.4624	7,400	0.8295	19,000	0.9833
4,000	0.4809	7,500	0.8343	20,000	0.9855
4,100	0.4987	7,600	0.8390	30,000	0.9952
4,200	0.5160	7,700	0.8436	40,000	0.9978
4,300	0.5327	7,800	0.8479	50,000	0.9988
4,400	0.5488	7,900	0.8521	$\infty$	1.

**Example 3.6.1**

Assume that the sun is a blackbody at 5777 K.

- a** What is the wavelength at which the maximum monochromatic emissive power occurs?
- b** What is the energy from this source that is in the visible part of the electromagnetic spectrum (0.38 to 0.78  $\mu m$ )?

**Table 3.6.1b** Fraction of Blackbody Radiation Energy between Zero and  $\lambda T$  for Even Fractional Increments

$f_{0-\lambda T}$	$\lambda T, \mu m K$	$\lambda T$ at Midpoint	$f_{0-\lambda T}$	$\lambda T, \mu m K$	$\lambda T$ at Midpoint
0.05	1,880	1,660	0.55	4,410	4,250
0.10	2,200	2,050	0.60	4,740	4,570
0.15	2,450	2,320	0.65	5,130	4,930
0.20	2,680	2,560	0.70	5,590	5,350
0.25	2,900	2,790	0.75	6,150	5,850
0.30	3,120	3,010	0.80	6,860	6,480
0.35	3,350	3,230	0.85	7,850	7,310
0.40	3,580	3,460	0.90	9,380	8,510
0.45	3,830	3,710	0.95	12,500	10,600
0.50	4,110	3,970	1.00	$\infty$	16,300

**Solution**

**a** The value of  $\lambda T$  at which the maximum monochromatic emissive power occurs is 2897.8  $\mu m K$ , so the desired wavelength is 2897.8/5777, or 0.502  $\mu m$ .

**b** From Table 3.6.1a the fraction of energy between zero and  $\lambda T = 0.78 \times 5777 = 4506 \mu m K$  is 56%, and the fraction of the energy between zero and  $\lambda T = 0.38 \times 5777 = 2195 \mu m K$  is 10%. The fraction of the energy in the visible is then 56% minus 10%, or 46%. These numbers are close to the values obtained from the actual distribution of energy from the sun as calculated in Example 3.6.1. ■

**3.7 RADIATION INTENSITY AND FLUX**

Thus far we have considered the radiation leaving a black surface in all directions; however, it is often necessary to describe the directional characteristics of a general radiation field in space. The radiation intensity is used for this purpose and is defined as the energy passing through an imaginary plane per unit area per unit time and per unit solid angle whose central direction is perpendicular to the imaginary plane. Thus, in Figure 3.7.1, if  $\Delta E$  represents the energy per unit time passing through  $\Delta A$  and remaining within  $\Delta \omega$ , then intensity is<sup>3</sup>

$$I = \lim_{\substack{\Delta A \rightarrow 0 \\ \Delta \omega \rightarrow 0}} \frac{\Delta E}{\Delta A \Delta \omega} \quad (3.7.1)$$

The intensity  $I$  has both a magnitude and a direction and can be considered as a vector quantity. For a given imaginary plane in space, we can consider two intensity vectors that are in opposite directions. These two vectors are often distinguished by the symbols  $I^+$  and  $I^-$ .

The radiation flux is closely related to the intensity and is defined as the energy passing through an imaginary plane per unit area per unit time and in all directions on one side of the imaginary plane. Note that the difference between intensity and flux is that the

<sup>3</sup>The symbol  $I$  is used for intensity when presenting basic radiation heat transfer ideas and for solar radiation integrated over an hour period when presenting solar radiation ideas. The two will seldom be used together.




Figure 3.7.1 Schematic of radiation intensity.

differential area for intensity is perpendicular to the direction of propagation, whereas the differential area for flux lies in a plane that forms the base of a hemisphere through which the radiation is passing.

The intensity can be used to determine the flux through any plane. Consider an elemental area  $\Delta A$  on an imaginary plane covered by a hemisphere of radius  $r$  as shown in Figure 3.7.2. The energy per unit time passing through an area  $\Delta A'$  on the surface of the hemisphere from the area  $\Delta A$  is equal to

$$\Delta Q = I \Delta A (\cos \theta) \frac{\Delta A'}{r^2} \quad (3.7.2)$$

Where  $\Delta A'/r^2$  is the solid angle between  $\Delta A$  and  $\Delta A'$  and  $\Delta A \cos \theta$  is the area perpendicular to the intensity vector. The energy flux per unit solid angle in the  $\theta, \phi$  direction can then be defined as

$$\Delta q = \lim_{\Delta A \rightarrow 0} \frac{\Delta Q}{\Delta A} = I (\cos \theta) \frac{\Delta A'}{r^2} \quad (3.7.3)$$

The radiation flux is then found by integrating over the hemisphere. The sphere incremental area can be expressed in terms of the angles  $\theta$  and  $\phi$  so that

$$q = \int_0^{2\pi} \int_0^{\pi/2} I \cos \theta \sin \theta \, d\theta \, d\phi \quad (3.7.4)$$

It is convenient to define  $\mu = \cos \theta$  so that

$$q = \int_0^{2\pi} \int_0^1 I \mu \, d\mu \, d\phi \quad (3.7.5)$$




Figure 3.7.2 Schematic of radiation flux.

Two important points concerning the radiation flux must be remembered. First, the radiation flux is, in general, a function of the orientation of the chosen imaginary plane. Second, the radiation flux will have two values corresponding to each of the two possible directions of the normal to the imaginary plane. When it is necessary to emphasize which of the two possible values of the radiation flux is being considered, the superscript + or – can be used along with a definition of the positive and negative directions.

Thus far, radiation flux and intensity have been defined at a general location in space. When it is desired to find the heat transfer between surfaces in a vacuum, or at least in radiative nonparticipating media, the most useful values of radiative flux and intensity occur at the surfaces. For the special case of a surface that has intensity independent of direction, the integration of Equation 3.7.5 yields

$$q = \pi I \quad (3.7.6)$$

Surfaces that have the intensity equal to a constant are called either Lambertian or diffuse surfaces. A blackbody emits in a diffuse manner, and therefore the blackbody emissive power is related to the blackbody intensity by

$$E_b = \pi I_b \quad (3.7.7)$$

The foregoing equations were written for total radiation but apply equally well to monochromatic radiation. For example, Equation 3.7.7 could be written in terms of a particular wavelength  $\lambda$ :

$$E_{\lambda b} = \pi I_{\lambda b} \quad (3.7.8)$$

### 3.8 INFRARED RADIATION EXCHANGE BETWEEN GRAY SURFACES

The general case of infrared radiation heat transfer between many gray surfaces having different temperatures is treated in a number of textbooks (e.g., Hottel and Sarofim, 1967; Siegel and Howell, 2002). The various methods all make the same basic assumptions, which for each surface can be summarized as follows:

1. The surface is gray. (Radiation properties are independent of wavelength.)
2. The surface is diffuse or specular diffuse (see Section 4.3).
3. The surface temperature is uniform.
4. The incident energy over the surface is uniform.

Beckman (1971) also utilized these basic assumptions and defined a total exchange factor between pairs of surfaces of an  $N$ -surface enclosure such that the net heat transfer to a typical surface  $i$  is<sup>4</sup>

$$Q_i = \sum_{j=1}^N \varepsilon_i \varepsilon_j A_i \hat{F}_{ij} \sigma (T_j^4 - T_i^4) \quad (3.8.1)$$

---

<sup>4</sup>The emittance  $\varepsilon$  is defined by Equation 4.1.8.

The factor  $\hat{F}_{ij}$  is the total exchange factor between surfaces  $i$  and  $j$  and is found from the matrix equation

$$[\hat{F}_{ij}] = [\delta_{ij} - \rho_i E_{ij}]^{-1} [E_{ij}] \quad (3.8.2)$$

where  $E_{ij}$ , the specular exchange factor, accounts for radiation going from surface  $i$  to surface  $j$  directly and by all possible specular (mirrorlike) reflections and  $\rho_j$  is the diffuse reflectance of surface  $j$ . Methods for calculating  $E_{ij}$  are given in advanced radiation texts. When the surfaces of the enclosure do not specularly reflect radiation, the specular exchange factors of Equation 3.8.2 reduce to the usual view factor (configuration factor)  $F_{ij}$ .

The majority of heat transfer problems in solar energy applications involve radiation between two surfaces. The solution of Equations 3.8.1 and 3.8.2 for diffuse surfaces with  $N = 2$  is

$$Q_1 = -Q_2 = \frac{\sigma(T_2^4 - T_1^4)}{\frac{1 - \varepsilon_1}{\varepsilon_1 A_1} + \frac{1}{A_1 F_{12}} + \frac{1 - \varepsilon_2}{\varepsilon_2 A_2}} \quad (3.8.3)$$

Two special cases of Equation 3.8.3 are of particular interest. For radiation between two infinite parallel plates (i.e., as in flat-plate collectors) the areas  $A_1$  and  $A_2$  are equal and the view factor  $F_{12}$  is unity. Under these conditions Equation 3.8.3 becomes

$$\frac{Q}{A} = \frac{\sigma(T_2^4 - T_1^4)}{\frac{1}{\varepsilon_1} + \frac{1}{\varepsilon_2} - 1} \quad (3.8.4)$$

The second special case is for a small convex object (surface 1) surrounded by a large enclosure (surface 2). Under these conditions, the area ratio  $A_1/A_2$  approaches zero, the view factor  $F_{12}$  is unity, and Equation 3.8.3 becomes

$$Q_1 = \varepsilon_1 A_1 \sigma(T_2^4 - T_1^4) \quad (3.8.5)$$

This result is independent of the surface properties of the large enclosure since virtually none of the radiation leaving the small object is reflected back from the large enclosure. In other words, the large enclosure absorbs all radiation from the small object and acts like a blackbody. Equation 3.8.5 also applies in the case of a flat plate radiating to the sky (i.e., a collector cover radiating to the surroundings).

### 3.9 SKY RADIATION

To predict the performance of solar collectors, it will be necessary to evaluate the radiation exchange between a surface and the sky. The sky can be considered as a blackbody at some equivalent sky temperature  $T_s$  so that the actual net radiation between a horizontal flat plate and the sky is given by Equation 3.8.5. The net radiation from a surface with emittance  $\varepsilon$  and temperature  $T$  to the sky at  $T_s$  is

$$Q = \varepsilon A \sigma (T^4 - T_s^4) \quad (3.9.1)$$

The equivalent blackbody sky temperature of Equation 3.9.1 accounts for the facts that the atmosphere is not at a uniform temperature and the atmosphere radiates only in certain wavelength bands. The atmosphere is essentially transparent in the wavelength region from 8 to 14  $\mu\text{m}$ , but outside of this “window” the atmosphere has absorbing bands covering much of the infrared spectrum. Several relations have been proposed to relate  $T_s$  for clear skies to measured meteorological variables. Swinbank (1963) relates sky temperature to the local air temperature, Brunt (1932) relates sky temperature to the water vapor pressure, and Bliss (1961) relates sky temperature to the dew point temperature. Berdahl and Martin (1984) used extensive data from the United States to relate the effective sky temperature to the dew point temperature, dry bulb temperature, and hour from midnight  $t$  by the following equation.

$$T_s = T_a[0.711 + 0.0056T_{dp} + 0.000073T_{dp}^2 + 0.013 \cos(15t)]^{1/4} \quad (3.9.2)$$

where  $T_s$  and  $T_a$  are in degrees Kelvin and  $T_{dp}$  is the dew point temperature in degrees Celsius. The experimental data covered a dew point range from  $-20^\circ\text{C}$  to  $30^\circ\text{C}$ . The range of the difference between sky and air temperatures is from  $5^\circ\text{C}$  in a hot, moist climate to  $30^\circ\text{C}$  in a cold, dry climate.

Clouds will tend to increase the sky temperature over that for a clear sky. It is fortunate that the sky temperature does not make much difference in evaluating collector performance. However, the sky temperature is critical in evaluating radiative cooling as a passive cooling method.

### 3.10 RADIATION HEAT TRANSFER COEFFICIENT

To retain the simplicity of linear equations, it is convenient to define a radiation heat transfer coefficient. The heat transfer by radiation between two arbitrary surfaces is found from Equation 3.8.3. If we define a heat transfer coefficient so that the radiation between the two surfaces is given by

$$Q = A_1 h_r (T_2 - T_1) \quad (3.10.1)$$

then it follows that

$$h_r = \frac{\sigma(T_2^2 + T_1^2)(T_2 + T_1)}{\frac{1 - \varepsilon_1}{\varepsilon_1} + \frac{1}{F_{12}} + \frac{(1 - \varepsilon_2)A_1}{\varepsilon_2 A_2}} \quad (3.10.2)$$

If the areas  $A_1$  and  $A_2$  are not equal, the numerical value of  $h_r$  depends on whether it is to be used with  $A_1$  or with  $A_2$ .

When  $T_1$  and  $T_2$  are close together, the numerator of Equation 3.10.2 can be expressed as  $4\sigma\bar{T}^3$ , where  $\bar{T}$  is the average temperature:

$$\bar{T}^3 = \frac{1}{4}(T_2^2 + T_1^2)(T_2 + T_1) \quad (3.10.3)$$

It is not difficult to estimate  $\bar{T}$  without actually knowing both  $T_1$  and  $T_2$ . Once  $\bar{T}$  is estimated, the equations of radiation heat transfer are reduced to linear equations that can be easily solved along with the linear equations of conduction and convection. If more accuracy is needed, a second or third iteration may be required. Most of the radiation calculations in this book use the linearized radiation coefficient.

### Example 3.10.1

The plate and cover of a flat-plate collector are large in extent, are parallel, and are spaced 25 mm apart. The emittance of the plate is 0.15 and its temperature is 70°C. The emittance of the glass cover is 0.88 and its temperature is 50°C. Calculate the radiation exchange between the surfaces and a radiation heat transfer coefficient for this situation.

### Solution

Exact and approximate solutions are possible for this problem. The exact solution is based on Equations 3.8.4 and 3.10.1. The radiation exchange is given by Equation 3.8.4:

$$\frac{Q}{A} = \frac{\sigma(343^4 - 323^4)}{\frac{1}{0.15} + \frac{1}{0.88} - 1} = 24.6 \text{ W/m}^2$$

Then from the defining equation for the radiation coefficient (Equation 3.10.1),

$$h_r = \frac{24.6}{70 - 50} = 1.232 \text{ W/m}^2 \text{ } ^\circ\text{C}$$

(The use of Equation 3.10.2 produces the identical result.)

We can also get an approximate solution using the average of the two plate temperatures, 60°C or 333 K, in Equation 3.10.3: Then

$$h_r = \frac{\sigma \times 4 \times 333^3}{\frac{1}{0.15} + \frac{1}{0.88} - 1} = 1.231 \text{ W/m}^2 \text{ } ^\circ\text{C}$$

This result is essentially the same as that calculated by the defining equation. ■

## 3.11 NATURAL CONVECTION BETWEEN FLAT PARALLEL PLATES AND BETWEEN CONCENTRIC CYLINDERS

The rate of heat transfer between two plates inclined at some angle to the horizon is of obvious importance in the performance of flat-plate collectors. Free-convection heat transfer data are usually correlated in terms of two or three dimensionless parameters: the Nusselt number  $Nu$ , the Rayleigh number  $Ra$ , and the Prandtl number  $Pr$ . Some authors correlate data in terms of the Grashof number, which is the ratio of the Rayleigh number to the Prandtl number.

The Nusselt, Rayleigh, and Prandtl numbers are given by<sup>5</sup>

$$\text{Nu} = \frac{hL}{k} \quad (3.11.1)$$

$$\text{Ra} = \frac{g\beta' \Delta T L^3}{\nu\alpha} \quad (3.11.2)$$

$$\text{Pr} = \frac{\nu}{\alpha} \quad (3.11.3)$$

Where  $h$  = heat transfer coefficient [ $\text{W}/\text{m}^2 \text{ K}$ ]

$L$  = plate spacing [m]

$k$  = thermal conductivity [ $\text{W}/\text{m K}$ ]

$g$  = gravitational constant [ $\text{m}/\text{s}^2$ ]

$\beta'$  = volumetric coefficient of expansion (for an ideal gas,  $\beta' = 1/T$ ) [ $1/\text{K}$ ]

$\Delta T$  = temperature difference between plates [ $\text{K}$ ]

$\nu$  = kinematic viscosity [ $\text{m}^2/\text{s}$ ]

$\alpha$  = thermal diffusivity [ $\text{m}^2/\text{s}$ ]

For parallel plates the Nusselt number is the ratio of a pure conduction resistance to a convection resistance [i.e.,  $\text{Nu} = (L/k)/(1/h)$ ] so that a Nusselt number of unity represents pure conduction.

Tabor (1958) examined the published results of a number of investigations and concluded that the most reliable data for use in solar collector calculations as of 1958 were contained in Report 32 published by the U.S. Home Finance Agency (1954).

In a more recent experimental study using air, Hollands et al. (1976) give the relationship between the Nusselt number and Rayleigh number for tilt angles from  $0$  to  $75^\circ$  as

$$\text{Nu} = 1 + 1.44 \left[ 1 - \frac{1708(\sin 1.8\beta)^{1.6}}{\text{Ra} \cos \beta} \right] \left[ 1 - \frac{1708}{\text{Ra} \cos \beta} \right]^+ + \left[ \left( \frac{\text{Ra} \cos \beta}{5830} \right)^{1/3} - 1 \right]^+ \quad (3.11.4)$$

where the meaning of the  $+$  exponent is that only positive values of the terms in the square brackets are to be used (i.e., use zero if the term is negative).


For horizontal surfaces, the results presented by Tabor compare favorably with the correlation of Equation 3.11.4. For vertical surfaces the data from Tabor approximate the  $75^\circ$  tilt data of Hollands et al. (1976). Actual collector performance will always differ from analysis, but a consistent set of data is necessary to predict the trends to be expected from design changes. Since a common purpose of this type of data is to evaluate collector design changes, the correlation of Hollands et al. (1976) is considered to be the most reliable.

Equation 3.11.4 is plotted in Figure 3.11.1. In addition to the Nusselt number, there is a second scale on the ordinate giving the value of the heat transfer coefficient times the plate spacing for a mean temperature of  $10^\circ\text{C}$ . The scale of this ordinate is not dimensionless but is  $\text{mm W}/\text{m}^2 \text{ }^\circ\text{C}$ . For temperatures other than  $10^\circ\text{C}$ , a factor  $F_2$ , the ratio of the


---

<sup>5</sup>Fluid properties in the convection relationships of this chapter should be evaluated at the mean temperature.





**Figure 3.11.1** Nusselt number as a function of Rayleigh number for free-convection heat transfer between parallel flat plates at various slopes.



**Figure 3.11.2** Air property corrections  $F_1$  and  $F_2$  for use with Figure 3.11.1. From Tabor (1958).

thermal conductivity of air at 10°C to that at any other temperature, has been plotted as a function of temperature in Figure 3.11.2. Thus to find  $hl$  at any temperature other than 10°C, it is only necessary to divide  $F_2 hl$  as read from the chart by  $F_2$  at the appropriate temperature.<sup>6</sup>

The abscissa also has an extra scale,  $F_1 \Delta T l^3$ . To find  $\Delta T l^3$  at temperatures other than 10°C, it is only necessary to divide  $F_1 \Delta T l^3$  by  $F_1$ , where  $F_1$  is the ratio of  $1/T\nu\alpha$  at the desired temperature to  $1/T\nu\alpha$  at 10°C. The ratio  $F_1$  is also plotted in Figure 3.11.2.

### Example 3.11.1

Find the convection heat transfer coefficient between two parallel plates separated by 25 mm with a 45° tilt. The lower plate is at 70°C and the upper plate is at 50°C.

#### Solution

At the mean air temperature of 60°C air properties are  $k = 0.029$  W/m K,  $T = 333$  K so  $\beta' = 1/333$ ,  $\nu = 1.88 \times 10^{-5}$  m<sup>2</sup>/s, and  $\alpha = 2.69 \times 10^{-5}$  m<sup>2</sup>/s. (Property data are from EES; www.fchart.com.) The Rayleigh number is

$$\text{Ra} = \frac{9.81 \times 20 \times (0.025)^3}{333 \times 1.88 \times 10^{-5} \times 2.69 \times 10^{-5}} = 1.82 \times 10^4$$

From Equation 3.11.4 or Figure 3.11.1 the Nusselt number is 2.4. The heat transfer coefficient is found from


$$h = \text{Nu} \frac{k}{L} = \frac{2.4 \times 0.029}{0.025} = 2.78 \text{ W/m}^2 \text{ K}$$

As an alternative, the dimensional scales of Figure 3.11.1 can be used with the property corrections from Figure 3.11.2. At 60°C,  $F_1 = 0.49$  and  $F_2 = 0.86$ . Therefore,  $F_1 \Delta T l^3 = 0.49 \times 20 \times 25^3 = 1.53 \times 10^5$  mm<sup>3</sup> °C. From the 45° curve in Figure 3.11.1,  $F_2 hl = 59$ . Finally,  $h = 59/(0.86 \times 25) = 2.74$  W/m<sup>2</sup> K.

Even with the substantially reduced radiation heat transfer resulting from the low emittance in Example 3.6.1, the radiation heat transfer is about one-half of the convection heat transfer. ■

It is recommended that the 75° correlation of Figure 3.11.1 be used for vertical surfaces. The correlation given by Equation 3.11.1 does not cover the range from 75 to 90°, but comparisons with other correlations suggest that the 75° represents the vertical case adequately. Raithby et al. (1977) have examined vertical surface convection data from a wide range of experimental investigations. They propose a correlation that includes the influence of aspect ratio  $A$ , that is, the ratio of plate height to spacing. Their correlation is plotted in Figure 3.11.3 for aspect ratios of 5, 60, and infinity. For comparison, other correlations that do not show an aspect ratio effect are also plotted on this figure and correspond approximately to the Raithby et al. correlation with an aspect ratio of between 10 and 20.

<sup>6</sup>The lowercase letter  $l$  is used as a reminder that the units are millimeters instead of meters.



**Figure 3.11.3** Nusselt number as a function of Rayleigh number for free-convection heat transfer between vertical flat plates.

Most of the experiments utilize a guarded hot-plate technique that measures the heat transfer only at the center of the test region. Consequently the end effects are largely excluded. However, Randall et al. (1977) used an interferometric technique that allowed determination of local heat transfer coefficients from which averages were determined; they could not find an aspect ratio effect, although a range of aspect ratios from 9 to 36 was covered. The Raithby et al. (1977) correlation also includes an angular correction for angles from  $70$  to  $110^\circ$  which shows a slight increase in Nusselt number over this range of tilt angles consistent with the trends of Figure 3.11.1 (Randall et al., 1977).

It is unusual to find a collector sloped at angles between  $75^\circ$  and  $90^\circ$ ; if they are to be that steep, they will probably be vertical. Windows and collector-storage walls are essentially always vertical. For vertical surfaces the four correlations shown in Figure 3.11.3 [with  $A \cong 15$  for the Raithby et al. (1977) result] agree within approximately 15% with the  $75^\circ$  correlation of Hollands et al. (1976) in Figure 3.11.1. Vertical solar collectors will have an aspect ratio on the order of 60, but at this aspect ratio the Raithby et al. result falls well below other correlations. Consequently, the  $75^\circ$  correlation of Figure 3.11.1 will give reasonable or conservative predictions for vertical surfaces.

Heat transfer between horizontal concentric cylinders is important in linear concentrating collectors (see Section 7.3). Raithby and Hollands (1975) [as reported by Incropera and DeWitt (2002)] propose the following correlation to account for the free convection:

$$\frac{k_{\text{eff}}}{k} = \max \left[ 1, 0.386 \left( \frac{\text{Pr} \times \text{Ra}^*}{0.861 + \text{Pr}} \right)^{1/4} \right] \quad (3.11.5)$$

where

$$\text{Ra}^* = \frac{[\ln(D_o/D_i)]^4}{L^3(D_i^{-3/5} + D_o^{-3/5})^5} \text{Ra}_L \quad (3.11.6)$$

and the Rayleigh and Prandtl numbers are defined by Equations 3.11.1 and 3.11.2. The characteristic length  $L$  is the distance between the inner and outer cylinders. The range of validity of this correlation is  $\text{Ra}^* \leq 10^7$ . At  $\text{Ra}^* \leq 100$  Equation 3.11.5 yields  $k_{\text{eff}} = k$ , indicating the free convection is suppressed and the heat transfer is by conduction.

As the pressure in the annulus is reduced, the conduction heat transfer is unaffected until the pressure is such that the mean free path of the molecules is on the order of the characteristic dimension of the annulus. The following equation from Ratzel et al. (1979) covers the range from pure conduction to free molecular heat transfer:

$$\frac{k_{\text{eff}}}{k} = \left[ 1 + \frac{(2-a)(9c_p/c_v - 5)\lambda}{a(c_p/c_v + 1) \ln(D_o/D_i)} \left( \frac{1}{D_o} + \frac{1}{D_i} \right) \right]^{-1} \quad (3.11.7)$$

where  $\lambda$  is the mean free path of the gas molecules given by

$$\lambda = \frac{kT}{\sqrt{2}\pi P\delta^2} \quad (3.11.8)$$

and where  $k$  is Boltzmann's constant ( $1.381 \times 10^{-23}$  J/K),  $P$  is the pressure in pascals, and  $\delta$  is the molecular diameter of the annulus gas ( $3.5 \times 10^{-10}$  m for air and  $2.4 \times 10^{-10}$  m for hydrogen). The parameter  $a$  is an accommodation coefficient that when set equal to 1 provides an upper bound on the free molecular heat transfer: The ratio of specific heats is close to 1.4 for both air and hydrogen.


A general expression for the effective gas conductivity in an annulus is to take the maximum value of either the part of Equation 3.11.5 that contains the Rayleigh number or 3.11.7.

### 3.12 CONVECTION SUPPRESSION

One of the objectives in designing solar collectors is to reduce the heat loss through the covers. This has led to studies of convection suppression by Hollands (1965), Edwards (1969), Buchberg et al. (1976), Arnold et al. (1977, 1978), Meyer et al. (1978), and others. In these studies the space between two plates, with one plate heated, is filled with a transparent or specularly reflecting honeycomb to suppress the onset of fluid motion. Without fluid motion the heat transfer between the plates is by conduction and radiation. Care must be exercised since improper design can lead to increased rather than decreased convection losses, as was first shown experimentally by Charters and Peterson (1972) and later verified by others.

For slats, as shown in Figure 3.12.1, the results of Meyer et al. (1978) can be expressed as the maximum of two numbers as

$$\text{Nu} = \max[1.1C_1C_2 \text{Ra}_L^{0.28}, 1] \quad (3.12.1)$$



**Figure 3.12.1** Slats for suppression of convection. From Meyer et al. (1978).

where  $C_1$  and  $C_2$  are given in Figure 3.12.2 and the subscript  $L$  indicates that the plate spacing  $L$  is the characteristic length. Note that the coefficient  $C_1$  has a maximum near an aspect ratio of 2.


To assess the magnitude of the convection suppression with slats, it is possible to compare Equation 3.12.1 with the correlation of Randall et al. (1977) obtained from data taken on the same equipment. Although the Randall correlation uses an exponent of 0.29 on the Rayleigh number, the correlation can be slightly modified to have an exponent of 0.28. The ratio of the two correlations is then

$$\frac{Nu_{\text{slats}}}{Nu_{\text{no slats}}} = \frac{\max[1.1C_1C_2 Ra_L^{0.28}, 1]}{\max[0.13 Ra_L^{0.28} [\cos(\beta - 45)]^{0.58}, 1]} \quad (3.12.2)$$

As long as fluid motion is not suppressed (i.e., as long as  $Nu > 1$ ), the ratio of the two Nusselt numbers is independent of the Rayleigh number.

At a collector angle of  $45^\circ$ , the addition of slats will reduce convection as long as the aspect ratio is less than approximately 0.5 (i.e.,  $C_1 = 0.12$ ,  $C_2 = 1.0$ ). At an aspect ratio of 0.25, the slats reduce convection by one-third. At a Rayleigh number of 5800 and a tilt of  $45^\circ$ , fluid movement is just beginning with an aspect ratio of 0.25, and the Nusselt number is 1.0. From Randall's correlation without slats and with a Rayleigh number of 5800, the Nusselt number is 1.47, a nearly 50% reduction in convection heat transfer.

Arnold et al. (1977, 1978) experimentally investigated cores with aspect ratios between 0.125 and 0.25 but with additional partitions that produced rectangular honeycombs having horizontal aspect ratios (width-to-plate spacing) ranging from 0.25 to 6.25. The results of these experiments, using silicone oil as the working fluid to suppress thermal radiation,



**Figure 3.12.2** Coefficients  $C_1$  and  $C_1$  for use in Equation 3.12.1. From Meyer et al. (1978).

can be correlated within  $\pm 15\%$  with the following equation:

$$Nu = 1 + 1.15 \left[ 1 - \frac{Ra_1}{Ra \cos \beta} \right]^+ + 1.25 \left[ 1 - \frac{Ra_2}{Ra \cos \beta} \right]^+ \quad (3.12.3)$$

for

$$0 \leq \beta \leq 60, \quad Ra \cos \beta \leq Ra_3, \quad 4 \leq L/H \leq 8, \quad 1 \leq W/H \leq 24$$

where

$$Ra_k = \frac{(a_k + b_k)^3}{a_k}$$

$$a_k = a_o + \frac{1}{2}b_k, \quad b_k = (k\pi + 0.85)^2, \quad k = 1, 2, 3$$

$$a_o = \left[ \frac{7}{1 + L/(7D)} + 18 \left( \frac{H}{W} \right)^2 \right] \left( \frac{L}{H} \right)^2$$

For vertical orientation ( $\beta = 90^\circ$ ), the results can be correlated by

$$\text{Nu} = 1 + \frac{10^{-4}(H/L)^{4.65}}{1 + 5(H/W)^4} \text{Ra}^{1/3} \quad (3.12.4)$$

for the same  $L/H$  and  $W/H$  limits as given for Equation 3.12.3.

These equations show little effect on heat transfer of horizontal aspect ratios beyond unity. Consequently, the results of Meyer et al. (1978) for slats should be directly comparable. At an angle of  $45^\circ$  and a Rayleigh number of  $4 \times 10^4$  both experiments give a Nusselt number of approximately 1.7, but the slope of the data on a Nusselt-Rayleigh plot from Arnold et al. (1977) is approximately 0.48 and the slope from Meyer et al. is 0.28. Since the Rayleigh number range of the two experiments was not large, these two very different correlations give similar Nusselt numbers, but extrapolation beyond the range of test data (i.e.,  $\text{Ra} > 10^5$ ) could lead to large differences.

This discrepancy points out a problem in estimating the effect of collector design options based on heat transfer data from two different experiments. It is the nature of heat transfer work that sometimes significant differences are observed in carefully controlled experiments using different equipment or techniques. Consequently, in evaluating an option such as the addition of honeycombs, heat transfer data with and without honeycombs measured in the same laboratory will probably be the most reliable.

The addition of a honeycomb in a solar collector will modify the collector's radiative characteristics. The honeycomb will certainly decrease the solar radiation reaching the absorbing plate of the collector. Hollands et al. (1978) have analyzed the solar transmittance<sup>7</sup> of a square-celled honeycomb and compared the results with measurements at normal incidence. For the particular polycarbonate plastic configuration tested, the honeycomb transmittance at normal incidence was 0.98. Its transmittance decreased in a nearly linear manner with incidence angle to approximately 0.90 at an angle of  $70^\circ$ .

The infrared radiation characteristics will also be affected in a manner largely dependent upon the honeycomb material. If the honeycomb is constructed of either an infrared transparent material or an infrared specularly reflective material, then the infrared radiative characteristics of the collector will not be significantly changed. If the honeycomb material is constructed of a material that is opaque in the infrared, then the radiative characteristics of the collector will approach that of a blackbody. As will be shown in the next two chapters, this is undesirable.

Transparent aerogels can be used to eliminate convection heat transfer. Properly made silica aerogels transmit most solar radiation. They consist of very fine silica particles and micropores that are smaller than the mean free path of air molecules; convection is

---

<sup>7</sup>Transmittance of cover systems is discussed in Chapter 5.

suppressed and conduction is less than that of still air. Thermal stability and weatherability may be problems.

### 3.13 VEE-CORRUGATED ENCLOSURES

Vee-corrugated absorber plates with the corrugations running horizontally have been proposed for solar collectors to improve the radiative characteristics of the absorber plate (see Section 4.9). Also, this configuration approximates the shape of some concentrating collectors (see Chapter 7). One problem with this configuration is that the improved radiative properties are, at least in part, offset by increased convection losses. Elsherbiny et al. (1977) state that free-convection losses from a vee-corrugated surface to a single plane above is as much as 50% greater than for two plane surfaces at the same temperatures and mean plate spacing.


Randall (1978) investigated vee-corrugated surfaces and correlated the data in terms of the Nusselt and Rayleigh numbers in the form

$$\text{Nu} = \max[(C \text{ Ra}^n), 1] \quad (3.13.1)$$

where the values of  $C$  and  $n$  are given in Table 3.13.1 as functions of the tilt angle  $\beta$  and the vee aspect ratio  $A'$ , the ratio of mean plate spacing  $l$  to vee height  $h$  shown in Figure 3.13.1.

**Table 3.13.1** Constants for Use in Equation 3.13.1

$\beta$	$A'$	$C$	$n$
0	0.75	0.060	0.41
	1	0.060	0.41
	2	0.043	0.41
45	0.75	0.075	0.36
	1	0.082	0.36
	2	0.037	0.41
60	0.75	0.162	0.30
	1	0.141	0.30
	2	0.027	0.42



**Figure 3.13.1** Section of vee-corrugated absorber and plane cover.



### 3.14 HEAT TRANSFER RELATIONS FOR INTERNAL FLOW

Heat transfer coefficients for common geometries are given in many heat transfer books (e.g., McAdams, 1954; Kays and Crawford, 1980; Incropera and DeWitt, 2002). For fully developed turbulent liquid flow inside tubes (i.e.,  $2300 < \text{Re} = \rho V D_h / \mu < 5 \times 10^6$  and  $0.5 < \text{Pr} < 2000$ ), Gnielinski, as reported in Kakaç et al. (1987), suggests

$$\text{Nu} = \frac{(f/8)(\text{Re} - 1000)\text{Pr}}{1.07 + 12.7\sqrt{f/8}(\text{Pr}^{2/3} - 1)} \left( \frac{\mu}{\mu_w} \right)^n \quad (3.14.1)$$

where  $n$  is 0.11 for heating and 0.25 for cooling and the Darcy friction factor  $f$  for smooth pipes is given by

$$f = (0.79 \ln \text{Re} - 1.64)^{-2} \quad (3.14.2)$$

For gases, the viscosity ratio in Equation 3.14.1 should be replaced by  $(T_w/T)^n$ . For noncircular tubes the hydraulic diameter can be used for the characteristic length in the preceding two equations. The hydraulic diameter is defined as

$$D_h = \frac{4(\text{flow area})}{\text{wetted perimeter}} \quad (3.14.3)$$

For short tubes with  $L/D > 1.0$  and a sharp-edged entry, McAdams (1954) recommends that the Nusselt number be calculated from

$$\frac{\text{Nu}_{\text{short}}}{\text{Nu}_{\text{long}}} = \left[ 1 + \left( \frac{D}{L} \right)^{0.7} \right] \quad (3.14.4)$$

For laminar flow in tubes the thermal boundary condition is important. With fully developed hydrodynamic and thermal profiles, the Nusselt number is 3.7 for constant wall temperature and 4.4 for constant heat flux. In a solar collector the thermal condition is closely represented by a constant resistance between the flowing fluid and the constant-temperature environment.<sup>8</sup> If this resistance is large, the thermal boundary condition approaches constant heat flux, and if this resistance is small, the thermal boundary condition approaches constant temperature. Consequently, the theoretical performance of a solar collector should lie between the results for constant heat flux and constant temperature. Since a constant-wall-temperature assumption yields somewhat lower heat transfer coefficients, this is the recommended assumption for conservative design.

For short tubes the developing thermal and hydrodynamic boundary layers will result in a significant increase in the heat transfer coefficient near the entrance. Heaton et al. (1964) present local Nusselt numbers for the case of constant heat rate. Their data are well represented by an equation of the form

$$\text{Nu} = \text{Nu}_{\infty} + \frac{a(\text{Re Pr } D_h/L)^m}{1 + b(\text{Re Pr } D_h/L)^n} \quad (3.14.5)$$

where the constants  $a$ ,  $b$ ,  $m$ , and  $n$  are given in Table 3.14.1.


---

<sup>8</sup>This will become apparent in Chapter 6.

**Table 3.14.1** Constants for Equation 3.14.5 for Calculation of Local Nu for Circular Tubes with Constant Heat Rate

Prandtl Number	$a$	$b$	$m$	$n$
0.7	0.00398	0.0114	1.66	1.12
10	0.00236	0.00857	1.66	1.13
$\infty$	0.00172	0.00281	1.66	1.29
$Nu_{\infty} = 4.4$				

Goldberg (1958), as reported by Rohsenow and Choi (1961), presents average Nusselt numbers for the case of constant wall temperature. The results for Prandtl numbers of 0.7, 5, and infinity are shown in Figure 3.14.1. The data of this figure can also be represented by an equation of the form of Equation 3.14.5 but with values of  $a$ ,  $b$ ,  $m$ ,  $n$ , and  $Nu_{\infty}$  given in Table 3.14.2.

**Figure 3.14.1** Average Nusselt numbers in short tubes for various Prandtl numbers.**Table 3.14.2** Constants for Equation 3.14.5 for Calculation of Average Nu for Circular Tubes with Constant Wall Temperature

Prandtl Number	$a$	$b$	$m$	$n$
0.7	0.0791	0.0331	1.15	0.82
5	0.0534	0.0335	1.15	0.82
$\infty$	0.0461	0.0316	1.15	0.84
$Nu_{\infty} = 3.7$				

**Example 3.14.1**

What is the heat transfer coefficient inside the tubes of a solar collector in which the tubes are 10 mm in diameter and separated by a distance of 100 mm? The collector is 1.5 m wide and 3 m long and has total flow rate of water of 0.075 kg/s. The water is at 80°C.

**Solution**

The collector has 15 tubes so that the flow rate per tube is 0.005 kg/s. The Reynolds number is

$$\frac{VD}{\nu} = \frac{4\dot{m}}{\pi D\mu} = \frac{4 \times 0.005}{\pi \times 0.01 \times 3.6 \times 10^{-4}} = 1800$$

which indicates laminar flow. The Prandtl number is 2.2 so that

$$\frac{\text{Re Pr } D_h}{L} = \frac{1800 \times 2.2 \times 0.01}{3} = 13$$

From Figure 3.14.1 the average Nusselt number is 4.6 so the average heat transfer coefficient is

$$h = \frac{\text{Nu } k}{D} = \frac{4.6 \times 0.67}{0.01} = 308 \text{ W/m}^2 \text{ } ^\circ\text{C}$$

■

In the study of solar air heaters and collector-storage walls it is necessary to know the forced-convection heat transfer coefficient between two flat plates. For air the following correlation can be derived from the data of Kays and Crawford (1980) for fully developed turbulent flow with one side heated and the other side insulated:

$$\text{Nu} = 0.0158 \text{ Re}^{0.8} \quad (3.14.6)$$

where the characteristic length is the hydraulic diameter (twice the plate spacing). For flow situations in which  $L/D_h$  is 10, Kays and Crawford indicates that the average Nusselt number is approximately 16% higher than that given by Equation 3.14.6. At  $L/D_h = 30$ , Equation 3.14.6 still underpredicts by 5%. At  $L/D_h = 100$ , the effect of the entrance region has largely disappeared.


Tan and Charters (1970) have experimentally studied flow of air between parallel plates with small aspect ratios for use in solar air heaters. Their results give higher heat transfer coefficients by about 10% than those given by Kays and Crawford with an infinite aspect ratio.

The local Nusselt number for laminar flow between two flat plates with one side insulated and the other subjected to a constant heat flux has been obtained by Heaton et al. (1964). The results have been correlated in the form of Equation 3.14.5 with the constants given in Table 3.14.3.

For the case of parallel plates with constant temperature on one side and insulated on the other side, Mercer et al. (1967) obtained the average Nusselt numbers shown in Figure 3.14.2. They also correlated these data into the form of Equation 3.14.7 for  $0.1 < \text{Pr} < 10$ :

**Table 3.14.3** Constants for Equation 3.14.5 for Calculation of Local Nu for Infinite Flat Plates: One Side Insulated and Constant Heat Flux on Other Side

Prandtl Number	<i>a</i>	<i>b</i>	<i>m</i>	<i>n</i>
0.7	0.00190	0.00563	1.71	1.17
10	0.00041	0.00156	2.12	1.59
∞	0.00021	0.00060	2.24	1.77
$Nu_{\infty} = 5.4$				

**Figure 3.14.2** Average Nusselt numbers in short ducts with one side insulated and one side at constant wall temperature for various Prandtl numbers.

$$Nu = 4.9 + \frac{0.0606(Re \, Pr \, D_h/L)^{1.2}}{1 + 0.0909(Re \, Pr \, D_h/L)^{0.7} Pr^{0.17}} \quad (3.14.7)$$

The results of Sparrow (1955) indicate that for  $Re \, Pr \, D_h/L < 1000$  and for  $Pr = 10$  the Nusselt numbers are essentially the same as for the case when the hydrodynamic profile is fully developed.

### Example 3.14.2

- a** Determine the convective heat transfer coefficient for airflow in a channel 1 m wide by 2 m long. The channel thickness is 15 mm and the air flow rate is 0.03 kg/s. The average air temperature is 35°C.
- b** If the channel thickness is halved, what is the heat transfer coefficient?
- c** If the flow rate is halved, what is the heat transfer coefficient?

**Solution**

**a** At a temperature of 35°C the viscosity is  $1.88 \times 10^{-5}$  m<sup>2</sup>/s and the thermal conductivity is 0.0268 W/m K. The hydraulic diameter  $D_h$  is twice the plate spacing  $t$ , and the Reynolds number can be expressed in terms of the flow rate per unit width  $\dot{m}/W$ . The Reynolds number is then

$$\text{Re} = \frac{\rho V D_h}{\mu} = \frac{\rho V 2tW}{W\mu} = \frac{2\dot{m}}{W\mu} = \frac{2 \times 0.03}{1 \times 1.88 \times 10^{-5}} = 3200$$

so that the flow is turbulent. From Equation 3.14.6 the Nusselt number is

$$\text{Nu} = 0.0158(3200)^{0.8} = 10.1$$

and the heat transfer coefficient is  $h = \text{Nu } k/D_h = 9$  W/m<sup>2</sup> K. Since  $L/D_h < 100$ , 9 W/m<sup>2</sup> °C is probably a few percent too low.

**b** If the channel thickness is halved, the Reynolds number remains the same but the heat transfer coefficient will double to 18 W/m<sup>2</sup> K.

**c** If the flow rate is halved, the Reynolds number will be 1600, indicating laminar flow. Equation 3.14.7 or Figure 13.14.2 should be used. The value of  $\text{Re } \text{Pr } D_h/L$  is  $1600 \times 0.7 \times 0.03/2 = 16.8$  so the Nusselt number is 6.0 and the heat transfer coefficient is 6.2 W/m<sup>2</sup> K. ■

### 3.15 WIND CONVECTION COEFFICIENTS

The heat loss from flat plates exposed to outside winds is important in the study of solar collectors. Sparrow et al. (1979) did wind tunnel studies on rectangular plates at various orientations and found the following correlation over the Reynolds number range of  $2 \times 10^4$  to  $9 \times 10^4$ :

$$\text{Nu} = 0.86 \text{Re}^{1/2} \text{Pr}^{1/3} \quad (3.15.1)$$

where the characteristic length is four times the plate area divided by the plate perimeter. For laminar flow (i.e.,  $\text{Re} < 10^6$ , the critical Reynolds number for flow over a flat plate) over a very wide flat plate at zero angle of attack, the analysis of Pohlhausen (Kays and Crawford, 1980) yields a coefficient for Equation 3.15.1 of 0.94.<sup>9</sup>

This agreement at low Reynolds numbers suggests that Equation 3.15.1 may be valid at Reynolds numbers up to  $10^6$  where direct experimental evidence is lacking. This extrapolation is necessary since a solar collector array 2 m × 5 m has a characteristic length of 2.9 m and Reynolds number of  $9.4 \times 10^5$  in a 5-m/s wind. From Equation 3.15.1, the heat transfer coefficient under these conditions is approximately 7 W/m<sup>2</sup> K.

McAdams (1954) reports the data of Jurgens for a 0.5-m<sup>2</sup> plate in which the convection coefficient is given by the dimensional equation

$$h = 5.7 + 3.8V \quad (3.15.2)$$

<sup>9</sup>To be consistent with Equation 3.15.1, the characteristic length in the Pohlhausen solution must be changed to twice the plate length. This changes the familiar coefficient of 0.664 to 0.94.

where  $V$  is the wind speed in m/s and  $h$  is in  $\text{W/m}^2 \text{K}$ . It is probable that the effects of free convection and radiation are included in this equation. For this reason Watmuff et al. (1977) report that this equation should be

$$h = 2.8 + 3.0V \quad (3.15.3)$$

For a  $0.5\text{-m}^2$  plate, Equation 3.15.1 yields a heat transfer coefficient of  $16 \text{ W/m}^2 \text{K}$  at  $5 \text{ m/s}$  wind speed and a temperature of  $25^\circ\text{C}$ . Equation 3.15.3 yields a value of  $18 \text{ W/m}^2 \text{K}$  at these conditions. Thus there is agreement between the two at a characteristic length of  $0.5 \text{ m}$ . It is not reasonable to assume that Equation 3.15.3 is valid at other plate lengths.

The flow over a collector mounted on a house is not always well represented by wind tunnel tests of isolated plates. The collectors will sometimes be exposed directly to the wind and other times will be in the wake region. The roof itself will certainly influence the flow patterns. Also, nearby trees and buildings will greatly affect local flow conditions. Mitchell (1976) investigated the heat transfer from various shapes (actually animal shapes) and showed that many shapes were well represented by a sphere when the equivalent sphere diameter is the cube root of the volume. The heat transfer obtained in this manner is an average that includes stagnation regions and wake regions. A similar situation might be anticipated to occur in solar systems. Mitchell suggests that the wind tunnel results of these animal tests should be increased by approximately 15% for outdoor conditions. Thus, assuming a house to be a sphere, the Nusselt number can be expressed as

$$\text{Nu} = 0.42 \text{Re}^{0.6} \quad (3.15.4)$$

where the characteristic length is the cube root of the house volume.

When the wind speed is very low, free-convection conditions may dominate. Free-convection data for hot inclined flat plates facing upward are not available. However, results are available for horizontal and vertical flat plates. For hot horizontal flat plates with aspect ratios up to 7:1, Lloyd and Moran (1974) give the following equations:

$$\text{Nu} \begin{cases} 0.76 \text{Ra}^{1/4} & \text{for } 10^4 < \text{Ra} < 10^7 \\ 0.15 \text{Ra}^{1/3} & \text{for } 10^7 < \text{Ra} < 3 \times 10^{10} \end{cases} \quad (3.15.5)$$

$$(3.15.6)$$

where the characteristic length is four times the area divided by the perimeter. (The original reference used  $A/P$ .) For vertical plates McAdams (1954) gives

$$\text{Nu} = \begin{cases} 0.59 \text{Ra}^{1/4} & \text{for } 10^4 < \text{Ra} < 10^9 \\ 0.13 \text{Ra}^{1/3} & \text{for } 10^9 < \text{Ra} < 10^{12} \end{cases} \quad (3.15.7)$$

$$(3.15.8)$$

where the characteristic length is the plate height.

For large Rayleigh numbers, as would be found in most solar collector systems, Equations 3.15.6 and 3.15.8 apply and the characteristic length drops out of the calculation of the heat transfer coefficient. The heat transfer coefficients from these two equations are

nearly the same since the coefficient on the Rayleigh numbers differ only slightly. This means that horizontal and vertical collectors have a minimum heat transfer coefficient (i.e., under free-convection conditions) of about  $5 \text{ W/m}^2 \text{ K}$  for a  $25^\circ\text{C}$  temperature difference and a value of about  $4 \text{ W/m}^2 \text{ K}$  at a temperature difference of  $10^\circ\text{C}$ .

From the preceding discussion it is apparent that the calculation of wind-induced heat transfer coefficients is not well established. Until additional experimental evidence becomes available, the following guidelines are recommended. When free and forced convection occur simultaneously, McAdams (1954) recommends that both values be calculated and the larger value used in calculations. Consequently, it appears that a minimum value of approximately  $5 \text{ W/m}^2 \text{ }^\circ\text{C}$  occurs in solar collectors under still-air conditions. For forced-convection conditions over buildings the results of Mitchell (1976) can be expressed as

$$h_w = \frac{8.6V^{0.6}}{L^{0.4}} \quad (3.15.9)$$

The heat transfer coefficient (in  $\text{W/m}^2 \text{ K}$ ) for flush-mounted collectors can then be expressed as

$$h_w = \max \left[ 5, \frac{8.6V^{0.6}}{L^{0.4}} \right] \quad (3.15.10)$$

where  $V$  is wind speed in meters per second and  $L$  is the cube root of the house volume in meters. At a wind speed of  $5 \text{ m/s}$  (which is close to the world average wind speed) and a characteristic length of  $8 \text{ m}$ , Equation 3.15.10 yields a heat transfer coefficient of  $10 \text{ W/m}^2 \text{ K}$ .

For flow of air across a single tube in an outdoor environment the equations recommended by McAdams (1954) have been modified to give<sup>10</sup>

$$\text{Nu} = \begin{cases} 0.40 + 0.54 \text{ Re}^{0.52} & \text{for } 0.1 < \text{Re} < 1000 \\ 0.30 \text{ Re}^{0.6} & \text{for } 1000 < \text{Re} < 50,000 \end{cases} \quad (3.15.11)$$

$$(3.15.12)$$

### 3.16 HEAT TRANSFER AND PRESSURE DROP IN PACKED BEDS AND PERFORATED PLATES

In solar air heating systems the usual energy storage media is a packed bed of small rocks or crushed gravel. The heat transfer and pressure drop characteristics of these storage devices are of considerable interest and have been extensively reviewed by Shewen et al. (1978). Although many correlations were found for both heat transfer coefficients and friction factors in packed beds, none of the correlations were entirely satisfactory in predicting the measured performance of their experimental packed bed. The following relationships are based on the recommendations of Shewen et al.

---

<sup>10</sup>To account for outdoor conditions, the original coefficients have been increased by 25%.

The physical characteristics of pebbles vary widely between samples. Three quantities have been used to describe pebbles, the average particle diameter  $D$ , the void fraction  $\varepsilon$ , and the surface area shape factor  $\alpha$ . The void fraction can be determined by weighing pebbles placed in a container of volume  $V$  before and after it is filled with water. The void fraction is then equal to

$$\varepsilon = \frac{m_w/\rho_w}{V} \quad (3.16.1)$$

where  $m_w$  is the mass of water and  $\rho_w$  is the density of water. The density of the rock material is then

$$\rho_r = \frac{m}{V(1 - \varepsilon)} \quad (3.16.2)$$

where  $m$  is the mass of the rocks alone. The average particle diameter is the diameter of a spherical particle having the same volume and can be calculated from

$$D = \left( \frac{6m}{\pi \rho_r N} \right)^{1/3} \quad (3.16.3)$$

where  $N$  is the number of pebbles in the sample. The surface area shape factor  $\alpha$  is the ratio of the surface area of the pebble to the surface area of the equivalent sphere and is difficult to evaluate. For smooth river gravel  $\alpha$  appears to be independent of pebble size and approximately equal to 1.5. For crushed gravel  $\alpha$  varies with the pebble size and decreases linearly from approximately 2.5 at very small sizes to approximately 1.5 for 50-mm-diameter particles. However, large scatter is observed.

The three pebble bed parameters  $D$ ,  $\varepsilon$ , and  $\alpha$  do not fully take into account all the observed behavior of packed-bed storage devices. However, exact predictions are not needed since the performance of a solar system is not a strong function of the storage unit design as long as certain criteria are met.<sup>11</sup> When measurements of the void fraction  $\varepsilon$  and the surface area shape factor  $\alpha$  are available, the pressure drop relationship recommended by Shewen et al. (1978) is that of McCorquodale et al. (1978):

$$\Delta p = \frac{LG_o^2}{\rho_{\text{air}} D} \frac{(1 - \varepsilon)\alpha}{\varepsilon^{3/2}} \left[ 4.74 + 166 \frac{(1 - \varepsilon)\alpha}{\varepsilon^{3/2}} \frac{\mu}{G_o D} \right] \quad (3.16.4)$$

where  $G_o$  is the mass velocity of the air (air mass flow rate divided by the bed frontal area) and  $L$  is the length of the bed in the flow direction. When measurements of  $\alpha$  and  $\varepsilon$  are not available, Shewen et al. (1978) recommend the equation of Dunkle and Ellul (1972):

$$\Delta p = \frac{LG_o^2}{\rho_{\text{air}} D} \left( 21 + 1750 \frac{\mu}{G_o D} \right) \quad (3.16.5)$$

---

<sup>11</sup>See Table 13.2.1 and Section 8.5.



For heat transfer Shewen et al. (1978) recommend the Löff and Hawley (1948) equation

$$h_v = 650 \left( \frac{G_o}{D} \right)^{0.7} \quad (3.16.6)$$

where  $h_v$  is the volumetric heat transfer coefficient in  $\text{W/m}^3 \text{ K}$ ,  $G_o$  is the mass velocity in  $\text{kg/m}^2 \text{ s}$ , and  $D$  is the particle diameter in meters. The relationship between volumetric heat transfer coefficient  $h_v$  and area heat transfer coefficient  $h$  is

$$h_v = 6h(1 - \varepsilon) \frac{\alpha}{D} \quad (3.16.7)$$

### Example 3.16.1

A pebble bed is used for energy storage in a solar heating system. Air is the working fluid and flows vertically through the bed. The bed has the following dimensions and characteristics: depth 2.10 m, length and width 4.0 and 3.7 m, equivalent diameter of pebbles 23.5 mm, and void fraction 0.41. The superficial air velocity is 0.143 m/s. The average air temperature is 40°C. Estimate the pressure drop through the bed and the volumetric heat transfer coefficient.

### Solution

Use Equation 3.16.5. From EES, for air at 40°C,  $\rho = 1.127 \text{ kg/m}^3$  and  $\mu = 1.90 \times 10^{-5} \text{ Pa s}$ . The mass velocity is then

$$G_o = 0.143 \times 1.127 = 0.161 \text{ kg/m}^2 \text{ s}$$

Using the Dunkle and Ellul (1972) correlation,

$$\Delta p = \frac{2.10(0.161)^2}{1.127 \times 0.0235} \left( 21 + 1750 \frac{1.90 \times 10^{-5}}{0.161 \times 0.0235} \right) = 61.2 \text{ Pa}$$

Use Equation 3.16.6 to estimate the volumetric heat transfer coefficient:

$$h_v = 650 \left( \frac{0.161}{0.0235} \right)^{0.7} = 2500 \text{ W/m}^3 \text{ K}$$

■

The heat transfer coefficient and pressure drop for air flowing through a perforated plate is of particular interest in the design of transpired solar collectors as described in Section 6.14. Kutscher (1994) developed the following correlation for air flowing through a close-packed array of holes (arranged as equilateral triangles):

$$\text{Nu}_D = 2.75 \left( \frac{P}{D} \right)^{-1.21} \text{Re}_D^{0.43} \quad (3.16.8)$$

where  $P$  is the hole pitch (the distance between the holes) and  $D$  is the hole diameter. The velocity in the Reynolds number is the average air velocity in the hole. The correlation was experimentally verified over the range of  $P/D$  from 5 to 40. The data used in developing the correlation covered the following range:

$$0.25 < \left(\frac{P}{D}\right)^{-1.21} \text{Re}_D^{0.43} < 1.4$$

The pressure drop through the holes was well correlated with the following:

$$\frac{\Delta p}{\rho V^2/2} = 6.82 \left(\frac{1-\sigma}{\sigma}\right)^2 \text{Re}_D^{-0.236} \quad (3.16.9)$$

where  $\sigma$  is the porosity defined as the hole area to the collector area. The correlation was tested over the range

$$0 < \left(\frac{1-\sigma}{\sigma}\right)^2 \text{Re}_D^{-0.236} < 0.52$$

### 3.17 EFFECTIVENESS-NTU CALCULATIONS FOR HEAT EXCHANGERS

It is convenient in solar process system calculations to use the effectiveness-NTU (number of transfer units) method of calculation of heat exchanger performance. A brief discussion of the method is provided here, based on the example of a countercurrent exchanger. The working equation is the same for other heat exchanger configurations; the expressions for effectiveness vary from one configuration to another (Kays and London, 1964).

A schematic of an adiabatic countercurrent exchanger with inlet and outlet temperatures and capacitance rates of the hot and cold fluids is shown in Figure 3.17.1. The overall heat transfer coefficient—area product is  $UA$ . The maximum possible temperature drop of the hot fluid is from  $T_{hi}$  to  $T_{ci}$ ; the heat transfer for this situation would be

$$Q_{\max} = (\dot{m}C_p)_h (T_{hi} - T_{ci}) \quad (3.17.1)$$

The maximum possible temperature rise of the cold fluid would be from  $T_{ci}$  to  $T_{hi}$ . The corresponding maximum heat exchange would be

$$Q_{\max} = (\dot{m}C_p)_c (T_{hi} - T_{ci}) \quad (3.17.2)$$

The maximum heat transfer that could occur in the exchanger is thus fixed by the lower of the two capacitance rates,  $(\dot{m}C_p)_{\min}$ , and

$$Q_{\max} = (\dot{m}C_p)_{\min} (T_{hi} - T_{ci}) \quad (3.17.3)$$

The actual heat exchange  $Q$  is given by

$$Q = (\dot{m}C_p)_c (T_{co} - T_{ci}) = (\dot{m}C_p)_h (T_{hi} - T_{ho}) \quad (3.17.4)$$



**Figure 3.17.1** Schematic of an adiabatic counterflow heat exchanger showing temperatures and capacitance rates of the hot and cold fluids.

Effectiveness  $\varepsilon$  is defined as the ratio of the actual heat exchange that occurs to the maximum possible,  $Q/Q_{\max}$ , so

$$\varepsilon = \frac{Q}{Q_{\max}} = \frac{(\dot{m}C_p)_h(T_{hi} - T_{ho})}{(\dot{m}C_p)_{\min}(T_{hi} - T_{ci})} = \frac{(\dot{m}C_p)_c(T_{co} - T_{ci})}{(\dot{m}C_p)_{\min}(T_{hi} - T_{ci})} \quad (3.17.5)$$

Since either the hot or cold fluid has the minimum capacitance rate, the effectiveness can always be expressed in terms of the temperatures only. The working equation for the heat exchanger is

$$Q = \varepsilon(\dot{m}C_p)_{\min}(T_{hi} - T_{ci}) \quad (3.17.6)$$

For a counterflow exchanger, the effectiveness is given by

$$\varepsilon = \begin{cases} \frac{1 - e^{-NTU(1-C^*)}}{1 - C^* e^{-NTU(1-C^*)}} & \text{if } C^* \neq 1 \\ \frac{NTU}{1 + NTU} & \text{if } C^* = 1 \end{cases} \quad (3.17.7a)$$

$$(3.17.7b)$$

where  $NTU$  is the number of transfer units, defined as

$$NTU = \frac{UA}{(\dot{m}C_p)_{\min}} \quad (3.17.8)$$

and the dimensionless capacitance rate is given by

$$C^* = \frac{(\dot{m}C_p)_{\min}}{(\dot{m}C_p)_{\max}} \quad (3.17.9)$$

Kays and London (1964) give equations and graphs for effectivenesses for many heat exchanger types.

The utility of this approach to heat exchanger calculations will be evident in Chapter 10, where the temperatures of streams entering exchangers between collectors and storage tanks and between storage tanks and loads are known.

### Example 3.17.1

A heat exchanger like that in Figure 3.17.1 is located between a collector and a storage tank. The fluid on the collector side is an antifreeze, a glycol-water mixture with

$C_p = 3850 \text{ J/kg K}$ . Its flow rate is  $1.25 \text{ kg/s}$ . The fluid on the tank side is water, and its flow rate is  $0.864 \text{ kg/s}$ . The  $UA$  of the heat exchanger is estimated to be  $6500 \text{ W/K}$ .

If the hot glycol from the collector enters the exchanger at  $62^\circ\text{C}$  and the cool water from the tank enters at  $35^\circ\text{C}$ , what is the heat exchange rate and what are the outlet temperatures?

### Solution

First calculate the capacitance rates on the hot (collector) and cold (tank) sides of the heat exchanger and  $C^*$ . Use the symbols  $C_h$  and  $C_c$  for the hot- and cold-side capacitance rates:

$$C_h = 1.25 \times 3850 = 4812 \text{ W/K}$$

$$C_c = 0.864 \times 4180 = 3610 \text{ W/K}$$

The cold-side capacitance rate is the minimum of the two, and from Equation 3.17.9,

$$C^* = \frac{3610}{4812} = 0.75$$

From Equation 3.17.8,

$$NTU = \frac{UA}{C_{\min}} = \frac{6500}{3610} = 1.80$$

The effectiveness is now calculated from Equation 3.17.7:

$$\varepsilon = \frac{1 - e^{-1.8(1-0.75)}}{1 - 0.75e^{-1.8(1-0.75)}} = 0.69$$

The heat transfer is now calculated from Equation 3.17.6:

$$Q = 0.69 \times 3610(62 - 35) = 67,300 \text{ W}$$

The temperatures of the fluids leaving the exchanger can also be calculated using Equation 3.17.4. The leaving-water temperature is

$$T_{co} = 35 + \frac{67,300}{3610} = 53.6^\circ\text{C}$$

and the leaving-glycol temperature is

$$T_{ho} = 62 - \frac{67,300}{4812} = 48.0^\circ\text{C}$$

■

## REFERENCES

- Arnold, J. N., D. K. Edwards, and I. Catton, *Trans. ASME J. Heat Transfer*, **99**, 120 (1977). "Effect of Tilt and Horizontal Aspect Ratio on Natural Convection in a Rectangular Honeycomb."
- Arnold, J. N., D. K. Edwards, and P. S. Wu, ASME Paper No. 78-WA/HT-5 (1978). "Effect of Cell Size on Natural Convection in High L/D Tilted Rectangular Cells Heated and Cooled on Opposite Faces."

- Beckman, W. A., *Solar Energy*, **13**, 3 (1971). "The Solution of Heat Transfer Problems on a Digital Computer."
- Berdahl, P., and M. Martin, *Solar Energy*, **32**, 5 663 (1984). "Emissivity of Clear Skies."
- Bliss, R. W., *Solar Energy*, **5**, 103 (1961). "Atmospheric Radiation Near the Surface of the Ground."
- Brunt, D., *Q. J. Roy. Meteorol. Soc.*, **58**, 389 (1932). "Notes on Radiation in the Atmosphere."
- Buchberg, H., I. Catton, and D. K. Edwards, *Trans. ASME J. Heat Transfer*, **98**, 182 (1976). "Natural Convection in Enclosed Spaces: A Review of Application to Solar Energy Collection."
- Charters, W. W. S. and L. J. Peterson, *Solar Energy*, **13**, 4 (1972). "Free Convection Suppression Using Honeycomb Cellular Materials."
- DeGraff, J. and E. Van Der Held, *Applied Science Research*, Sec. A, **3** (1952). "The Relation Between the Heat Transfer and the Convection Phenomena in Enclosed Plane Air Layers."
- Dunkle, R. V., *Trans. ASME*, **76**, 549 (1954). "Thermal Radiation Tables and Applications."
- Dunkle, R. V. and W. H. J. Ellul, *Trans. Inst. Eng. (Australia)*, **MC8**, 117 (1972). "Randomly Packed Particulate Bed Regenerators and Evaporative Coolers."
- Edwards, D. K., *Trans. ASME J. Heat Transfer*, **91**, 145 (1969). "Suppression of Cellular Convection by Lateral Walls."
- Elsherbiny, S. M., K. G. T. Hollands, and G. D. Raithby, in *Heat Transfer in Solar Energy Systems* (J. R. Howell and T. Min, eds.), American Society of Mechanical Engineers, New York (1977). "Free Convection Across Inclined Air Layers with One Surface V-Corrugated."
- Heaton, H. S., W. C. Reynolds, and W. M. Kays, *Int. J. Heat Mass Transfer*, **7**, 763 (1964). "Heat Transfer in Annular Passages. Simultaneous Development of Velocity and Temperature Fields in Laminar Flow."
- Hollands, K. G. T., *Solar Energy*, **9**, 159 (1965). "Honeycomb Devices in Flat-Plate Solar Collectors."
- Hollands, K. G. T., K. N. Marshall, and R. K. Wedel, *Solar Energy*, **21**, 231 (1978). "An Approximate Equation for Predicting the Solar Transmittance of Transparent Honeycombs."
- Hollands, K. G. T., T. E. Unny, G. D. Raithby, and L. Konicek, *Trans. ASME J. Heat Transfer*, **98**, 189 (1976). "Free Convection Heat Transfer Across Inclined Air Layers."
- Home Finance Agency Report No. 32, U.S. Government Printing Office, Washington, DC (1954). "The Thermal Insulating Value of Airspaces."
- Hottel, H. C. and A. F. Sarofim, *Radiative Transfer*, McGraw-Hill, New York (1967).
- Incropera, F. P. and D. P. DeWitt, *Introduction to Heat Transfer*, Wiley, New York (2002).
- Kakaç, S., R. K. Shah, and W. Aung (eds.), *Handbook of Single-Phase Convective Heat Transfer*, Wiley-Interscience, New York (1987).
- Kays, W. M. and M. E. Crawford, *Convective Heat and Mass Transfer*, 2nd ed, McGraw-Hill, New York (1980).
- Kays, W. M. and A. L. London, *Compact Heat Exchangers*, McGraw-Hill, New York (1964).
- Kutscher, C. F., *Trans ASME J. Solar Energy Eng.*, **116**, 391 (1994). "Heat Exchange Effectiveness and Pressure Drop for Air Flow through Perforated Plates with and without Crosswind."
- Lloyd, J. R. and W. P. Moran, *Trans. ASME J. Heat Transfer*, **96**, 443 (1974). "Natural Convection Adjacent to Horizontal Surface of Various Planforms."
- Löf, G. O. G. and R. W. Hawley, *Ind. Eng. Chem.*, **40**, 1061 (1948). "Unsteady State Heat Transfer between Air and Loose Solids."
- McAdams, W. H., *Heat Transmission*, 3rd ed, McGraw-Hill, New York (1954).
- McCorquodale, J. A., A. A. Hannourae, and M. S. Nasser, *J. Hydraul. Res.*, **16** (2), 123 (1978). "Hydraulic Conductivity of Rock Fill."
- Mercer, W. E., W. M. Pearce, and J. E. Hitchcock, *Trans. ASME J. Heat Transfer*, **89**, 251 (1967). "Laminar Forced Convection in the Entrance Region between Parallel Flat Plates."
- Meyer, B. A., M. M. El-Wakil, and J. W. Mitchell, in *Thermal Storage and Heat Transfer in Solar Energy Systems* (F. Kreith, R. Boehm, J. Mitchell, and R. Bannerot, eds.), American Society

- of Mechanical Engineers, New York (1978). "Natural Convection Heat Transfer in Small and Moderate Aspect Ratio Enclosures—An Application to Flat-Plate Collectors."
- Mitchell, J. W., *Biophys. J.*, **16**, 561 (1976). "Heat Transfer from Spheres and Other Animal Forms."
- Raithby, G. D., K. G. T. Hollands, and T. R. Unny, *Trans. ASME J. Heat Transfer*, **99**, 287 (1977). "Analysis of Heat Transfer by Natural Convection across Vertical Fluid Layers."
- Randall, K. R., Ph.D. Thesis, Department of Mechanical Engineering, University of Wisconsin-Madison (1978). "An Interferometric Study of Natural Convection Heat Transfer in Flat-Plate and Vee-Corrugated Enclosures."
- Randall, K. R., J. W. Mitchell, and M. M. El-Wakil, in *Heat Transfer in Solar Energy Systems* (J. R. Howell and T. Min, eds.), American Society of Mechanical Engineers, New York (1977). "Natural Convection Characteristics of Flat-Plate Collectors."
- Ratzel, A., C. Hickox, and D. Gartling, *Trans. ASME J. Heat Transfer*, **101**, 108 (1979). "Techniques for Reducing Thermal Conduction and Natural Convection Heat Losses in Annular Receiver Geometries."
- Richtmyer, F. K. and E. H. Kennard, *Introduction to Modern Physics*, 4th ed, McGraw-Hill, New York (1947).
- Rohsenow, W. M. and H. Choi, *Heat Mass and Momentum Transfer*, Prentice-Hall, Englewood Cliffs, NJ (1961).
- Sargent, S. L., *Bull. Am. Meteorol. Soc.*, **53**, 360 (Apr. 1972). "A Compact Table of Blackbody Radiation Functions."
- Shewen, E. C., H. F. Sullivan, K. G. T. Hollands, and A. R. Balakrishnan, Report STOR-6, Waterloo Research Institute, University of Waterloo (Aug., 1978). "A Heat Storage Subsystem for Solar Energy."
- Siegel, R. and J. R. Howell, *Thermal Radiation Heat Transfer*, 4th ed, Taylor & Francis, New York (2002).
- Sparrow, E. M., NACA Technical Note 3331 (1955). "Analysis of Laminar Forced-Convection Heat Transfer in Entrance Regions of Flat Rectangular Ducts."
- Sparrow, E. M., J. W. Ramsey, and E. A. Mass, *Trans. ASME J. Heat Transfer*, **101**, 2 (1979). "Effect of Finite Width on Heat Transfer and Fluid Flow about an Inclined Rectangular Plate."
- Swinbank, W. C., *Q. J. Roy. Meteorol. Soc.*, **89**, 339 (1963). "Long-Wave Radiation from Clear Skies."
- Tabor, H., *Bull. Res. Council Israel*, **6C**, 155 (1958). "Radiation Convection and Conduction Coefficients in Solar Collectors."
- Tan, H. M. and W. W. S. Charters, *Solar Energy*, **13**, 121 (1970). "Experimental Investigation of Forced-Convection Heat Transfer."
- Watmuff, J. H., W. W. S. Charters, and D. Proctor, *COMPLES*, No. 2, 56 (1977). "Solar and Wind Induced External Coefficients for Solar Collectors."

# Radiation Characteristics of Opaque Materials

This chapter begins with a detailed discussion of radiation characteristics of surfaces. For many solar energy calculations only two quantities are required, the solar absorptance and the long-wave or infrared emittance, usually referred to as just absorptance and emittance. Although values of these two quantities are often quoted, other radiation properties may be the only available information on a particular material. Since relationships exist between the various characteristics, it may be possible to calculate a desired quantity from available data. Consequently, it is necessary to understand exactly what is meant by the radiation terms found in the literature, to be familiar with the type of information available, and to know how to manipulate these data to get the desired information. The most common type of data manipulation is illustrated in the examples, and readers may wish to go directly to Section 4.5.

The names used for the radiation surface characteristics were chosen as the most descriptive of the many names found in the literature. In many cases, the names will seem to be cumbersome, but they are necessary to distinguish one characteristic from another. For example, both a monochromatic angular-hemispherical reflectance and a monochromatic hemispherical-angular reflectance will be defined. Under certain circumstances, these two quantities are identical, but in general they are different, and it is necessary to distinguish between them.

Both the name and the symbol should be aids for understanding the significance of the particular characteristic. The monochromatic directional absorptance  $\alpha_\lambda(\mu, \phi)$  is the fraction of the incident energy from the direction  $\mu, \phi$  at the wavelength  $\lambda$  that is absorbed.<sup>1</sup> The directional absorptance  $\alpha(\mu, \phi)$  includes all wavelengths, and the hemispherical absorptance  $\alpha$  includes all directions as well as all wavelengths. We will also have a monochromatic hemispherical absorptance  $\alpha_\lambda$  which is the fraction of the energy incident from all directions at a particular wavelength that is absorbed. Thus by careful study of the name the definition should be clear.

The middle sections of the chapter are concerned with calculation of broadband properties from spectral properties. The last part of the chapter is concerned with selective surfaces that have high absorptance in the solar energy spectrum and low emittance in the long-wave spectrum. Agnihotri and Gupta (1981) have reviewed this topic extensively, and Lampert (1990) provides an overall review of optical properties of materials for solar energy applications.

---

<sup>1</sup>The angles  $\theta$  and  $\phi$  are shown in Figure 3.7.2;  $\mu = \cos \theta$ .

## 4.1 ABSORPTANCE AND EMITTANCE

The monochromatic directional absorptance is a property of a surface and is defined as the fraction of the incident radiation of wavelength  $\lambda$  from the direction  $\mu, \phi$  (where  $\mu$  is the cosine of the polar angle and  $\phi$  is the azimuthal angle) that is absorbed by the surface. In equation form

$$\alpha_{\lambda}(\mu, \phi) = \frac{I_{\lambda,a}(\mu, \phi)}{I_{\lambda,i}(\mu, \phi)} \quad (4.1.1)$$

where subscripts  $a$  and  $i$  represent absorbed and incident.

The fraction of all the radiation (over all wavelengths) from the direction  $\mu, \phi$  that is absorbed by a surface is called the directional absorptance and is defined by the following equation:

$$\begin{aligned} \alpha(\mu, \phi) &= \frac{\int_0^{\infty} \alpha_{\lambda}(\mu, \phi) I_{\lambda,i}(\mu, \phi) d\lambda}{\int_0^{\infty} I_{\lambda,i} d\lambda} \\ &= \frac{1}{I_i(\mu, \phi)} \int_0^{\infty} \alpha_{\lambda}(\mu, \phi) I_{\lambda,i}(\mu, \phi) d\lambda \end{aligned} \quad (4.1.2)$$

Unlike the monochromatic directional absorptance, the directional absorptance is not a property of the surface since it is a function of the wavelength distribution of the incident radiation.<sup>2</sup>

The monochromatic directional emittance of a surface is defined as the ratio of the monochromatic intensity emitted by a surface in a particular direction to the monochromatic intensity that would be emitted by a blackbody at the same temperature:

$$\varepsilon_{\lambda}(\mu, \phi) = \frac{I_{\lambda}(\mu, \phi)}{I_{\lambda b}} \quad (4.1.3)$$

The monochromatic directional emittance is a property of a surface, as is the directional emittance, defined by<sup>3</sup>

$$\varepsilon(\mu, \phi) = \frac{\int_0^{\infty} \varepsilon(\mu, \phi) I_{\lambda b} d\lambda}{\int_0^{\infty} I_{\lambda b} d\lambda} = \frac{1}{I_b} \int_0^{\infty} \varepsilon(\mu, \phi) I_{\lambda b} d\lambda \quad (4.1.4)$$

In words, the directional emittance is defined as the ratio of the emitted total intensity in the direction  $\mu, \phi$  to the blackbody intensity. Note that  $\varepsilon(\mu, \phi)$  is a property, as its definition contains the intensity  $I_{\lambda b}$ , which is specified when the surface temperature is known. In

<sup>2</sup>Although  $\alpha(\mu, \phi)$  and some other absorptances are not properties in that they depend upon the wavelength distribution of the incoming radiation, we can consider them as properties if the incoming spectral distribution is known. As the spectral distribution of solar radiation is essentially fixed, we can consider solar absorptance as a property.

<sup>3</sup>Both the numerator and denominator could be multiplied by  $\pi$  so that the definition of  $\varepsilon(\mu, \phi)$  could have been in terms of  $\varepsilon_b$  and  $\varepsilon_{\lambda b}$ .



contrast, the definition of  $\alpha(\mu, \phi)$  contains the unspecified function  $I_{\lambda,i}(\mu, \phi)$  and is therefore not a property. It is important to note that these four quantities and the four to follow are all functions of surface conditions such as temperature, roughness, cleanliness, and so on.

From the definitions of the directional absorptance and emittance of a surface, the corresponding hemispherical properties can be defined. The monochromatic hemispherical absorptance and emittance are obtained by integrating over the enclosing hemisphere, as was done in Section 3.7:

$$\alpha_\lambda = \frac{\int_0^{2\pi} \int_0^1 \alpha_\lambda(\mu, \phi) I_{\lambda,i}(\mu, \phi) \mu \, d\mu \, d\phi}{\int_0^{2\pi} \int_0^1 I_{\lambda,i}(\mu, \phi) \mu \, d\mu \, d\phi} \quad (4.1.5)$$

$$\begin{aligned} \varepsilon_\lambda &= \frac{\int_0^{2\pi} \int_0^1 \varepsilon_\lambda(\mu, \phi) I_{\lambda,b}(\mu, \phi) \mu \, d\mu \, d\phi}{\int_0^{2\pi} \int_0^1 I_{\lambda,b}(\mu, \phi) \mu \, d\mu \, d\phi} \\ &= \frac{\int_0^{2\pi} \int_0^1 \varepsilon_\lambda(\mu, \phi) I_{\lambda,b}(\mu, \phi) \mu \, d\mu \, d\phi}{E_{\lambda,b}} \end{aligned} \quad (4.1.6)$$

The monochromatic hemispherical emittance is thus a property. The monochromatic hemispherical absorptance is not a property but is a function of the incident intensity.

The hemispherical absorptance and emittance are obtained by integrating over all wavelengths and are defined by

$$\alpha = \frac{\int_0^\infty \int_0^{2\pi} \int_0^1 \alpha_\lambda(\mu, \phi) I_{\lambda,i}(\mu, \phi) \mu \, d\mu \, d\phi \, d\lambda}{\int_0^\infty \int_0^{2\pi} \int_0^1 I_{\lambda,i}(\mu, \phi) \mu \, d\mu \, d\phi \, d\lambda} \quad (4.1.7)$$

$$\varepsilon = \frac{\int_0^\infty \int_0^{2\pi} \int_0^1 \varepsilon_\lambda(\mu, \phi) I_{\lambda,b}(\mu, \phi) \mu \, d\mu \, d\phi \, d\lambda}{\int_0^\infty \int_0^{2\pi} \int_0^1 I_{\lambda,b}(\mu, \phi) \mu \, d\mu \, d\phi \, d\lambda} = \frac{\int_0^\infty \varepsilon_\lambda E_{\lambda,b} \, d\lambda}{E_b} \quad (4.1.8)$$

Again the absorptance (in this case the hemispherical absorptance) is a function of the incident intensity whereas the hemispherical emittance is a surface property.

If the monochromatic directional absorptance is independent of direction [i.e.,  $\alpha_\lambda(\mu, \phi) = \alpha_\lambda$ ], then Equation 4.1.7 can be simplified by integrating over the hemisphere to yield

$$\alpha = \frac{\int_0^\infty \alpha_\lambda q_{\lambda,i} \, d\lambda}{\int_0^\infty q_{\lambda,i} \, d\lambda} \quad (4.1.9)$$

where  $q_{\lambda,i}$  is the incident monochromatic radiant energy. If the incident radiation in either Equation 4.1.7 or 4.1.9 is radiation from the sun, then the calculated absorptance is called the solar absorptance.

## 4.2 KIRCHHOFF'S LAW

A proof of Kirchhoff's law is beyond the scope of this book. [See Siegel and Howell (2002) for a complete discussion.] However, a satisfactory understanding can be obtained without a proof. Consider an evacuated isothermal enclosure at temperature  $T$ . If the enclosure is isolated from the surroundings, then the enclosure and any substance within the enclosure will be in thermodynamic equilibrium. In addition, the radiation field within the enclosure must be homogeneous and isotropic. If this were not so, we could have a directed flow of radiant energy at some location within the enclosure, but this is impossible since we could then extract work for an isolated and isothermal system.

If we now consider an arbitrary body within the enclosure, the body must absorb the same amount of energy as it emits. An energy balance on an element of the surface of the body yields

$$\alpha q = \varepsilon E_b \quad (4.2.1)$$

If we place a second body with different surface properties in the enclosure, the same energy balance must apply, and the ratio  $q/E_b$  must be constant:

$$\frac{q}{E_b} = \frac{\varepsilon_1}{\alpha_1} = \frac{\varepsilon_2}{\alpha_2} \quad (4.2.2)$$

Since this must also apply to a blackbody in which  $\varepsilon = 1$ , the ratio of  $\varepsilon$  to  $\alpha$  for any body in thermal equilibrium must be equal to unity. Therefore, for conditions of thermal equilibrium

$$\varepsilon = \alpha \quad (4.2.3)$$

It must be remembered that  $\alpha$  is not a property, and since this equation was developed for the condition of thermal equilibrium, it will not be valid if the incident radiation comes from a source at a different temperature (e.g., if the source of radiation is the sun). This distinction is very important in the performance of solar collectors.

Equation 4.2.3 is sometimes referred to as Kirchhoff's law, but his law is much more general. Within an enclosure the radiant flux is everywhere uniform and isotropic. The absorptance of a surface within the enclosure is then given by Equation 4.1.7 with  $I_{\lambda,i}(\mu, \phi)$  replaced by  $I_{\lambda b}$  and the emittance is given by Equation 4.1.8. Since the hemispherical absorptance and emittance are equal under conditions of thermal equilibrium, we can equate Equations 4.1.7 and 4.1.8 to obtain

$$\int_0^\infty I_{\lambda b} \int_0^{2\pi} \int_0^1 [\alpha_\lambda(\mu, \phi) - \varepsilon_\lambda(\mu, \phi)] \mu \, d\mu \, d\phi \, d\lambda = 0 \quad (4.2.4)$$

It is mathematically possible to have this integral equal to zero without  $\alpha_\lambda(\mu, \phi)$  being identical to  $\varepsilon_\lambda(\mu, \phi)$ , but this is a very unlikely situation in view of the very irregular behavior of  $\alpha_\lambda(\mu, \phi)$  exhibited by some substances. Thus we can say

$$\varepsilon_\lambda(\mu, \phi) = \alpha_\lambda(\mu, \phi) \quad (4.2.5)$$

This result is true for all conditions, not just thermal equilibrium, since both  $\alpha_\lambda(\mu, \phi)$  and  $\varepsilon_\lambda(\mu, \phi)$  are properties.<sup>4</sup>

If the surface does not exhibit a dependence on the azimuthal angle, then Equation 4.2.5 reduces to

$$\alpha_\lambda(\mu) = \varepsilon_\lambda(\mu) \quad (4.2.6)$$

and if the dependence on polar angle can also be neglected, then Kirchhoff's law further reduces to

$$\alpha_\lambda = \varepsilon_\lambda \quad (4.2.7)$$

Finally, if the surface does not exhibit a wavelength dependency, then the absorptance  $\alpha$  is equal to the emittance  $\varepsilon$ . This is the same result obtained for any surface when in thermal equilibrium, as given by Equation 4.2.3.

### 4.3 REFLECTANCE OF SURFACES

Consider the spatial distribution of radiation reflected by a surface. When the incident radiation is in the form of a narrow “pencil” (i.e., contained within a small solid angle), two limiting distributions of the reflected radiation exist. These two cases are called specular and diffuse. Specular reflection is mirrorlike, that is, the incident polar angle is equal to the reflected polar angle and the azimuthal angles differ by  $180^\circ$ . On the other hand, diffuse reflection obliterates all directional characteristics of the incident radiation by distributing the radiation uniformly in all directions. In practice, the reflection from a surface is neither all specular nor all diffuse. The general case along with the two limiting situations is shown in Figure 4.3.1.

In general, the magnitude of the reflected intensity in a particular direction for a given surface is a function of the wavelength and the spatial distribution of the incident radiation. The biangular reflectance or reflection function is used to relate the intensity of reflected radiation in a particular direction by the following equation:

$$\rho_\lambda(\mu_r, \phi_r, \mu_i, \phi_i) = \lim_{\Delta\omega_i \rightarrow 0} \frac{\pi I_{\lambda,r}(\mu_r, \phi_r)}{I_{\lambda,i} \mu_i \Delta\omega_i} \quad (4.3.1)$$

The numerator is  $\pi$  times the intensity reflected in the direction  $\mu_r, \phi_r$  when an energy flux of amount  $I_{\lambda,i} \mu_i \Delta\omega_i$  is incident on the surface from the direction  $\mu_i, \phi_i$ . The factor  $\pi$  has




Figure 4.3.1 Reflection from surfaces.

<sup>4</sup>Kirchhoff's law actually applied to each component of polarization and not to the sum of the two components as implied by Equation 4.2.5.




Figure 4.3.2 Coordinate system for the reflection function.

been included so that the numerator “looks like” an energy flux. The physical situation is shown schematically in Figure 4.3.2.

Since the energy incident in the solid angle  $\Delta\omega_i$  may be reflected in all directions, the reflected intensity in the direction  $\mu_r, \phi_r$  will be of infinitesimal size compared to the incident intensity. By multiplying the incident intensity by its solid angle (which must be finite in any real experiment) and the cosine of the polar angle, we obtain the incident radiation flux which will have values on the same order of magnitude as the reflected intensity. The biangular reflectance can have numerical values between zero and infinity; its values do not lie only between zero and 1.

From an experimental point of view, it is not practical to use the scheme depicted in Figure 4.3.2 since all the radiation quantities would be extremely small. An equivalent experiment is to irradiate the surface with a nearly monodirectional flux (i.e., with a small solid angle  $\Delta\omega_i$ ) as shown in Figure 4.3.3. The reflected energy in each direction is measured. This measured energy divided by the measurement instrument solid angle ( $\Delta\omega_r$ ) will be approximately equal to the reflected intensity. The incident flux will be on the same order and can be easily measured.

Two types of hemispherical reflectances exist. The angular-hemispherical reflectance is found when a narrow pencil of radiation is incident on a surface and all the reflected radiation is collected. The hemispherical-angular reflectance results from collecting reflected radiation in a particular direction when the surface is irradiated from all directions.

The monochromatic angular-hemispherical reflectance will be designated by  $\rho_\lambda(\mu_i, \phi_i)$ , where the subscript  $i$  indicates that the incident radiation has a specified direction. This reflectance is defined as the ratio of the monochromatic radiant energy reflected in all directions to the incident radiant flux within a small solid angle  $\Delta\omega_i$ . The incident energy  $I_{\lambda,i} \mu_i \Delta\omega_i$  that is reflected in all directions can be found using the reflection function:

$$q_{\lambda,r} = \frac{1}{\pi} \int_0^{2\pi} \int_0^1 \rho_\lambda(\mu_r, \phi_r, \mu_i, \phi_i) I_{\lambda,i} \mu_i \Delta\omega_i \mu_r d\mu_r d\phi_r \quad (4.3.2)$$




Figure 4.3.3 Schematic representation of an experiment for measuring the reflection function.

The monochromatic angular-hemispherical reflectance can then be expressed as

$$\rho_\lambda(\mu_i, \phi_i) = \frac{q_{\lambda,r}}{I_{\lambda,i} \mu_i \Delta\omega_i} = \frac{1}{\pi} \int_0^2 \int_0^1 \rho_\lambda(\mu_r, \phi_r, \mu_i, \phi_i) \mu_r d\mu_r d\phi_r \quad (4.3.3)$$

Examination of Equation 4.3.3 shows that  $\rho_\lambda(\mu_i, \phi_i)$  is a property of the surface. The angular-hemispherical reflectance,  $\rho(\mu_i, \phi_i)$ , can be found by integrating the incident and reflected fluxes over all wavelengths, but it is not a property as it depends upon the wavelength distribution of the incoming radiation.

The monochromatic hemispherical-angular reflectance is defined as the ratio of the reflected monochromatic intensity in the direction  $\mu_r, \phi_r$  to the monochromatic energy from all directions divided by  $\pi$  (which then looks like intensity). The incident energy can be written in terms of the incident intensity integrated over the hemisphere:

$$q_{\lambda,i} = \int_0^{2\pi} \int_0^1 I_{\lambda,i} \mu_i d\mu_i d\phi_i \quad (4.3.4)$$

and the monochromatic hemispherical-angular reflectance is then

$$\rho_\lambda(\mu_r, \phi_r) = \frac{I_{\lambda,r}(\mu_r, \phi_r)}{q_{\lambda,i}/\pi} \quad (4.3.5)$$

where the subscripts  $r$  in  $\rho_\lambda(\mu_r, \phi_r)$  are used to specify the reflected radiation as being in a specified direction. In terms of the reflectance function, Equation 4.3.5 can be written as

$$\rho_\lambda(\mu_r, \phi_r) = \frac{\int_0^{2\pi} \int_0^1 \rho_\lambda(\mu_r, \phi_r, \mu_i, \phi_i) I_{\lambda,i} \mu_i d\mu_i d\phi_i}{\int_0^{2\pi} \int_0^1 I_{\lambda,i} \mu_i d\mu_i d\phi_i} \quad (4.3.6)$$

Since  $\rho_\lambda(\mu_r, \phi_r)$  is dependent upon the angular distribution of the incident intensity, it is not a surface property. For the special case when the incident radiation is diffuse, the monochromatic hemispherical-angular reflectance is identical to the monochromatic angular-hemispherical reflectance. To prove the equality of  $\rho_\lambda(\mu_r, \phi_r)$  and  $\rho_\lambda(\mu_i, \phi_i)$  under the condition of constant  $I_{\lambda,i}$ , it is necessary to use the symmetry of the reflection function as given by

$$\rho_\lambda(\mu_i, \phi_i, \mu_r, \phi_r) = \rho_\lambda(\mu_r, \phi_r, \mu_i, \phi_i) \quad (4.3.7)$$

and compare Equation 4.3.6 (with  $I_{\lambda,i}$  independent of incident direction) with Equation 4.3.3. The proof of Equation 4.3.7 is beyond the scope of this book [see Siegel and Howell (2002)].

The equality of  $\rho_\lambda(\mu_i, \phi_i)$  and  $\rho_\lambda(\mu_r, \phi_r)$  when  $I_{\lambda,i}$  is uniform is of great importance since the measurement of  $\rho_\lambda(\mu_r, \phi_r)$  is much easier than  $\rho_\lambda(\mu_i, \phi_i)$ . This is discussed in Section 4.7.

Both  $\rho_\lambda(\mu_i, \phi_i)$  and  $\rho_\lambda(\mu_r, \phi_r)$  can be considered on a total basis by integration over all wavelengths. For the case of the angular-hemispherical reflectance, we have

$$\begin{aligned}\rho(\mu_i, \phi_i) &= \frac{\int_0^\infty q_{\lambda,r} d\lambda}{\int_0^\infty I_{\lambda,i} \mu_i \Delta\omega_i d\lambda} \\ &= \frac{1}{\pi I_i} \int_0^\infty \int_0^{2\pi} \int_0^1 \rho_\lambda(\mu_i, \phi_i, \mu_r, \phi_r) I_{\lambda,i} \mu_r d\mu_r d\phi_r d\lambda\end{aligned}\quad (4.3.8)$$

which, unlike the monochromatic angular-hemispherical reflectance, is not a property since it depends upon the nature of the incoming radiation.

When a surface element is irradiated from all directions and all the reflected radiation is measured, we characterize the process by the monochromatic hemispherical reflectance, defined as

$$\rho_\lambda = \frac{q_{\lambda,r}}{q_{\lambda,i}} \quad (4.3.9)$$

The reflected monochromatic energy can be expressed in terms of the reflection function and the incident intensity by

$$q_{\lambda,r} = \int_0^{2\pi} \int_0^1 \left[ \int_0^{2\pi} \int_0^1 \frac{\rho_\lambda(\mu_r, \phi_r, \mu_i, \phi_i)}{\pi} I_{\lambda,i} \mu_i d\mu_i d\phi_i \right] \mu_r d\mu_r d\phi_r \quad (4.3.10)$$

The incident energy, expressed in terms of the incident intensity, is

$$q_{\lambda,i} = \int_0^{2\pi} \int_0^1 I_{\lambda,i} \mu_i d\mu_i d\phi_i \quad (4.3.11)$$

Division of Equation 4.3.10 by 4.3.11 yields the monochromatic hemispherical reflectance. For the special case of a diffuse surface (i.e., the reflection function is a constant), the monochromatic hemispherical reflectance is numerically equal to the reflection function and is independent of the spatial distribution of the incident intensity.

The hemispherical reflectance is found by integration of Equations 4.3.10 and 4.3.11 over all wavelengths and finding the ratio

$$\rho = \frac{q_r}{q_i} = \frac{\int_0^\infty q_{\lambda,r} d\lambda}{\int_0^\infty q_{\lambda,i} d\lambda} \quad (4.3.12)$$

The hemispherical reflectance depends on both the angular distribution and wavelength distribution of the incident radiation.

For low-temperature applications that do not include solar radiation, a special form of the hemispherical reflectance (often the name is shortened to “reflectance”) will be found to be the most useful. The special form is Equation 4.3.12, which is based on the

assumption that the reflection function is independent of direction (diffuse approximation) and wavelength (gray approximation). The diffuse approximation for the hemispherical reflectance has already been discussed and was found to be equal to  $\rho_\lambda(\mu_i, \phi_i, \mu_r, \phi_r)$ . When the gray approximation is made in addition to the diffuse approximation, the surface reflectance becomes independent of everything except possibly the temperature of the surface, and even this is usually neglected.

#### 4.4 RELATIONSHIPS AMONG ABSORPTANCE, EMITTANCE, AND REFLECTANCE

It is now possible to show that it is necessary to know only one property, the monochromatic angular-hemispherical reflectance, and all absorptance and emittance properties for opaque surfaces can be found.

Consider a surface located in an isothermal enclosure maintained at temperature  $T$ . The monochromatic intensity in a direction  $\mu, \phi$  from an infinitesimal area of the surface consists of emitted and reflected radiation and must be equal to  $I_{\lambda b}$ :

$$I_{\lambda b} = I_{\lambda, \text{emitted}}(\mu, \phi) + I_{\lambda, \text{reflected}}(\mu, \phi) \quad (4.4.1)$$

The emitted and reflected intensities are

$$I_{\lambda, \text{emitted}}(\mu, \phi) = \varepsilon_\lambda(\mu, \phi) I_{\lambda b} \quad (4.4.2)$$

$$I_{\lambda, \text{reflected}}(\mu, \phi) = \rho_\lambda(\mu_r, \phi_r) I_{\lambda b} \quad (4.4.3)$$

but  $\rho_\lambda(\mu_r, \phi_r)$  is equal to the monochromatic angular-hemispherical reflectance,  $\rho_\lambda(\mu_i, \phi_i)$ , since the incident intensity is diffuse. Since  $I_{\lambda b}$  can be canceled from each term, we have

$$\varepsilon_\lambda(\mu, \phi) = 1 - \rho_\lambda(\mu_i, \phi_i) \quad (4.4.4)$$

But from Kirchhoff's law

$$\varepsilon_\lambda(\mu, \phi) = \alpha_\lambda(\mu, \phi) = 1 - \rho_\lambda(\mu_i, \phi_i) \quad (4.4.5)$$

Thus the monochromatic directional emittance and the monochromatic directional absorptance can both be calculated from knowledge of the monochromatic angular-hemispherical reflectance. Also, all emittance properties (Equations 4.1.4, 4.1.6, and 4.1.8) can be found once  $\rho_\lambda(\mu_i, \phi_i)$  is known. The absorptances (Equations 4.1.2, 4.1.5, and 4.1.7) can be found if the incident intensity is specified.

The relationship between the reflectance and absorptance<sup>5</sup> of Equation 4.4.5 can be considered as a statement of conservation of energy. The incident monochromatic energy

<sup>5</sup>There are no generally accepted names used in the literature except for the simple "absorptance," "emittance," and "reflectance," which, for clarity, were prefixed with the name hemispherical. In the remainder of this book, the modifier hemispherical will generally be omitted since most available data are hemispherical. If it is necessary to distinguish directional quantities, then the full name will be used.

from any direction is either reflected or absorbed. Similar arguments can be used to relate other absorptances to reflectances. For example, for an opaque surface, energy from all directions, either monochromatic or total, is either absorbed or reflected so that

$$\rho_\lambda + \alpha_\lambda = \rho_\lambda + \varepsilon_\lambda = 1 \quad (4.4.6)$$

and

$$\rho + \alpha = 1 \quad (4.4.7)$$

## 4.5 BROADBAND EMITTANCE AND ABSORPTANCE


The concepts and analyses of the previous sections are greatly simplified if it is assumed that there is no directional dependence of  $\varepsilon$  or  $\alpha$ . Figure 4.5.1 shows monochromatic emission as a function of wavelength for a blackbody and for a real surface, both at the same surface temperature. The monochromatic emittance at wavelength  $\lambda$  is  $E_\lambda/E_{\lambda b}$ , the ratio of the energy emitted at a wavelength to what it would be if it were a blackbody, that is, the ratio  $A/B$ .

The total emittance is found by integrating over wavelengths from zero to infinity:

$$\varepsilon = \frac{\int_0^\infty \varepsilon_\lambda E_{\lambda b} d\lambda}{\int_0^\infty E_{\lambda b} d\lambda} = \frac{\int_0^\infty \varepsilon_\lambda E_{\lambda b} d\lambda}{\sigma T^4} \quad (4.5.1)$$


This is the same as Equation 4.1.8. If the nature of the surface (i.e.,  $\varepsilon_\lambda$ ) and its temperature are known, the emittance  $\varepsilon$  can be determined. Since  $\varepsilon$  is not dependent on any external factors, it is a property of the surface.

Monochromatic absorptance is the fraction of the incident radiation at wavelength  $\lambda$  that is absorbed. This is shown in Figure 4.5.2, where the incident energy spectrum  $I_{\lambda,i}$  is shown as an arbitrary function of  $\lambda$ . The symbol  $\alpha_\lambda$  is the monochromatic absorptance at  $\lambda$ , the ratio  $C/D$ , or  $I_{\lambda,a}/I_{\lambda,i}$ . The total absorptance for this surface for the indicated



**Figure 4.5.1** Monochromatic emission  $E_\lambda$  versus wavelength for a black surface and a real surface, both at the same temperature.





**Figure 4.5.2** Monochromatic incident and absorbed energy.

incident spectrum is found by integration over wavelengths from zero to infinity:


$$\alpha = \frac{\int_0^{\infty} \alpha_{\lambda} I_{\lambda,i} d\lambda}{\int_0^{\infty} I_{\lambda,i} d\lambda} \quad (4.5.2)$$

This is the same as Equation 4.1.9. In contrast to emittance, which is specified by the nature of the surface and its temperature, absorptance depends on an external factor, the spectral distribution of incident radiation. A specification of  $\alpha$  is meaningless unless the incident radiation is described. In the context of solar energy we are usually interested in absorptance for solar radiation [as described by a terrestrial solar energy spectrum (Table 2.6.1), the extraterrestrial spectrum (Table 1.3.1), or an equivalent blackbody spectrum (described by a temperature and Table 3.6.1)]. For usual solar energy applications, the terrestrial solar spectrum of Table 2.6.1 provides a realistic basis for computation of  $\alpha$ , and henceforth in this book reference to absorptance without other specification of the incident radiation means absorptance for the terrestrial solar spectrum.

## 4.6 CALCULATION OF EMITTANCE AND ABSORPTANCE

The data that are generally available are measurements of monochromatic reflectance  $\rho_{\lambda}$ . This is related to  $\alpha_{\lambda}$  and  $\varepsilon_{\lambda}$  by Equation 4.4.6. With these data, we can conveniently divide the spectrum (the blackbody spectrum for emittance or the incident energy spectrum for absorptance) into segments and numerically integrate to obtain  $\alpha$  or  $\varepsilon$ .

Consider first the calculation of emittance. As shown in Figure 4.6.1, for a segment  $j$  of the blackbody spectrum at the surface temperature  $T$ , there is a “monochromatic” emittance  $\varepsilon_{\lambda,j}$  that is the ratio of the shaded area to the total area. The ratio  $E_{\lambda}/E_{\lambda b}$  at an appropriate wavelength in the segment (often its energy midpoint) is taken as characteristic of the segment. The energy increment  $\Delta f_j$  in the blackbody spectrum can be determined from Table 3.6.1 as the difference in  $f_{0-\lambda T}$  at the wavelengths defining the segment. The contribution of the  $j$ th increment to  $\varepsilon$  is  $\varepsilon_j \Delta f_j$ .



**Figure 4.6.1** The  $j$ th segment in the emission spectrum for which the monochromatic emittance is  $\varepsilon_{\lambda,j}$ .

Thus the emittance is

$$\varepsilon = \sum_{j=1}^n \varepsilon_j \Delta f_j \quad (4.6.1)$$

or in terms of reflectance

$$\varepsilon = \sum_{j=1}^n (1 - \rho_j) \Delta f_j = 1 - \sum_{j=1}^n \rho_j \Delta f_j \quad (4.6.2)$$

If the energy increments  $\Delta f_j$  are equal,

$$\varepsilon = \frac{1}{n} \sum_{j=1}^n \varepsilon_j = 1 - \frac{1}{n} \sum_{j=1}^n \rho_j \quad (4.6.3)$$

The calculation of absorptance is similar, except that the incident radiation must be specified. In general, it will not be blackbody radiation, and other information must be available on which to base the calculation. As our interest is in absorptance for solar radiation, Table 2.6.1 provides this information for calculation of  $\alpha$  for terrestrial applications.

The incident radiation is divided into increments, and the contributions of these increments are summed to obtain  $\alpha$  for that incident radiation. For an increment in incident radiation  $\Delta f_j$ , the contribution to  $\alpha$  is  $\alpha_j \Delta f_j$ . Summing,

$$\alpha = \sum_{j=1}^n \alpha_j \Delta f_j = \sum_{j=1}^n (1 - \rho_j) \Delta f_j = 1 - \sum_{j=1}^n \rho_j \Delta f_j \quad (4.6.4)$$


and if the energy increments  $\Delta f_j$  are equal,

$$\alpha = \frac{1}{n} \sum_{j=1}^n \alpha_j = \frac{1}{n} \sum_{j=1}^n (1 - \rho_j) = 1 - \frac{1}{n} \sum_{j=1}^n \rho_j \quad (4.6.5)$$

The calculations of  $\alpha$  and  $\varepsilon$  are illustrated in the following example, where the incident radiation is taken as the terrestrial solar spectrum of Table 2.6.1.

**Example 4.6.1**

Calculate the absorptance for the terrestrial solar spectrum and emittance at 177°C (450 K) of the surface having the monochromatic reflectance characteristics shown in the figure.

**Solution**

First calculate the emittance using five equal increments of blackbody radiation from Table 3.6.1b. For each increment,  $\lambda_j T$  at the midpoint is determined from the table, the midpoint wavelength  $\lambda_j$  for that increment is calculated from  $\lambda_j T/T$ , and  $\rho_{\lambda,j}$  is determined at  $\lambda_j$  from the figure. For the first increment, which has wavelength limits of 0 and  $2680/450 = 5.96 \mu\text{m}$ , the midpoint  $\lambda_j T = 2200 \mu\text{m K}$ ,  $\lambda_j = 2200/450 = 4.89 \mu\text{m}$ , and  $\rho_\lambda = 0.83$ . Tabulating for the five equal increments results in the following:

Increment, $\Delta f_j$	$\lambda_j T_{\text{mid}}, \mu\text{m K}$	$\lambda_{j,\text{mid}}, \mu\text{m}$	$\rho_{\lambda,j}$
0.0–0.2	2200	4.89	0.83
0.2–0.4	3120	6.93	0.87
0.4–0.6	4110	9.13	0.94
0.6–0.8	5590	12.42	0.94
0.8–1.0	9380	20.84	0.94
			$\Sigma = 4.52$

Using Equation 4.6.3, since all increments are equal,

$$\varepsilon = 1 - \frac{4.52}{5} = 0.10$$

Note that if 10 increments are used, the emittance is calculated to be 0.09. As there is no change of  $\rho_\lambda$  with  $\lambda$  at wavelengths beyond  $10 \mu\text{m}$ , smaller increments (perhaps  $\Delta f_j = 0.1$ ) could be used for  $\lambda < 10 \mu\text{m}$  and a single large increment for  $\lambda > 10 \mu\text{m}$ .

The calculation of absorptance for the terrestrial solar spectrum is similar. Taking 10 equal energy increments from Table 2.6.1, the results of these calculations are as follows:


Increment, $\Delta f_j$	$\lambda_{\text{mid}}, \mu\text{m}$	$\rho_\lambda$
0.0–0.1	0.426	0.04
0.1–0.2	0.508	0.05
0.2–0.3	0.581	0.06
0.3–0.4	0.653	0.06
0.4–0.5	0.732	0.06
0.5–0.6	0.822	0.07
0.6–0.7	0.929	0.08
0.7–0.8	1.080	0.10
0.8–0.9	1.300	0.14
0.9–1.0	1.974	0.55
		$\Sigma = 1.21$

And from Equation 4.6.5,  $\alpha = 1 - 1.21/10 = 0.88$ . ■

## 4.7 MEASUREMENT OF SURFACE RADIATION PROPERTIES

In the preceding discussion many radiation surface properties have been defined. Unfortunately, in much of the literature the exact nature of the surface being reported is not clearly specified. This situation requires that caution be exercised.

Many of the reflectance data reported in the literature have been measured by a method devised by Gier et al. (1954).<sup>6</sup> In this method a cool sample is exposed to blackbody radiation from a high-temperature source (a hohlraum), and the monochromatic radiation reflected from the surface is compared to monochromatic blackbody radiation from the cavity. The data are thus hemispherical-angular monochromatic reflectances (or angular-hemispherical monochromatic reflectances since they are equal for diffuse incident radiation). A hohlraum is shown schematically in Figure 4.7.1. In many systems the angle



**Figure 4.7.1** Schematic of a hohlraum for measurement of monochromatic hemispherical-angular reflectance. Radiation *A* is blackbody radiation reflected from the sample. Radiation *B* is blackbody radiation from the cavity. The ratio  $A_\lambda/B_\lambda$  is  $\rho_\lambda(\mu, \phi)$ .

<sup>6</sup>See Agnihotri and Gupta (1981) for a more extensive review of methods of measurement of absorptance and emittance.

between the surface normal and the measured radiation is often fixed at a small value so that measurements can be made at only one angle (approximately normal). In some designs the sample can be rotated so that all angles can be measured. With measurements of this type, emittance and absorptance values can be found from the equations of Section 4.6.

Table 4.7.1 gives data on surface properties for a few common materials. The data are total hemispherical or total normal emittances at various temperatures and normal solar absorptance at room temperature. Most of these data were calculated from monochromatic data as was done in Example 4.6.1. Table 4.7.1 was compiled from Volumes 7, 8, and

**Table 4.7.1** Radiation Properties

Material	Type <sup>a</sup>	Emittance			Absorptance <sup>c</sup>
		Temperature <sup>b</sup>			
Aluminum, pure	H	$\frac{0.102}{573}$	$\frac{0.130}{773}$	$\frac{0.113}{873}$	0.09–0.10
Aluminum, anodized	H	$\frac{0.842}{296}$	$\frac{0.720}{484}$	$\frac{0.669}{574}$	0.12–0.16
Aluminum, SiO <sub>2</sub> coated	H	$\frac{0.366}{263}$	$\frac{0.384}{293}$	$\frac{0.378}{324}$	0.11
Carbon black in acrylic binder	H	$\frac{0.83}{278}$			0.94
Chromium	N	$\frac{0.290}{722}$	$\frac{0.355}{905}$	$\frac{0.435}{1072}$	0.415
Copper, polished	H	$\frac{0.041}{338}$	$\frac{0.036}{463}$	$\frac{0.039}{803}$	0.35
Gold	H	$\frac{0.025}{275}$	$\frac{0.040}{468}$	$\frac{0.048}{668}$	0.20–0.23
Iron	H	$\frac{0.071}{199}$	$\frac{0.110}{468}$	$\frac{0.175}{668}$	0.44
Lampblack in epoxy	N	$\frac{0.89}{298}$			0.96
Magnesium oxide	H	$\frac{0.73}{380}$	$\frac{0.68}{491}$	$\frac{0.53}{755}$	0.14
Nickel	H	$\frac{0.10}{310}$	$\frac{0.10}{468}$	$\frac{0.12}{668}$	0.36–0.43
Paint					
Parson’s black	H	$\frac{0.981}{240}$	$\frac{0.981}{462}$		0.98
Acrylic white	H	$\frac{0.90}{298}$			0.26
White (ZnO)	H	$\frac{0.929}{295}$	$\frac{0.926}{478}$	$\frac{0.889}{646}$	0.12–0.18

<sup>a</sup>H is total hemispherical emittance; N is total normal emittance.

<sup>b</sup>The numerator is the emittance at the temperature (K) of the denominator.

<sup>c</sup>Normal solar absorptance.


9 of Touloukian et al. (1970, 1972, 1973). These three volumes are the most complete reference to radiation properties available today. In addition to total hemispherical and normal emittance, such properties as angular spectral reflectance, angular total reflectance, angular solar absorptance, and others are given in this extensive compilation.

## 4.8 SELECTIVE SURFACES

Solar collectors must have high absorptance for radiation in the solar energy spectrum. At the same time, they lose energy by a combination of mechanisms,<sup>7</sup> including thermal radiation from the absorbing surface, and it is desirable to have the long-wave emittance of the surface as low as possible to reduce losses. The temperature of this surface in most flat-plate collectors is less than 200°C (473 K), while the effective surface temperature of the sun is approximately 6000 K. Thus the wavelength range of the emitted radiation overlaps only slightly the solar spectrum. (Ninety-eight percent of the extraterrestrial solar radiation is at wavelengths less than 3.0  $\mu\text{m}$ , whereas less than 1% of the blackbody radiation from a 200°C surface is at wavelengths less than 3.0  $\mu\text{m}$ .) Under these circumstances, it is possible to devise surfaces having high solar absorptance and low long-wave emittance, that is, selective surfaces.<sup>8</sup>

The concept of a selective surface is illustrated in Figure 4.8.1. This idealized surface is called a semigray surface, since it can be considered gray in the solar spectrum (i.e., at wavelengths less than approximately 3.0  $\mu\text{m}$ ) and also gray, but with different properties, in the infrared spectrum (i.e., at wavelengths greater than approximately 3.0  $\mu\text{m}$ ). For this idealized surface, the reflectance below the cutoff wavelength is very low. For an opaque surface  $\alpha_\lambda = 1 - \rho_\lambda$ , so in this range  $\alpha_\lambda$  is very high. At wavelengths greater than  $\lambda_c$  the reflectance is nearly unity, and since  $\varepsilon_\lambda = \alpha_\lambda = 1 - \rho_\lambda$ , the emittance in this range is low.

The absorptance for solar energy and emittance for long-wave radiation are determined from the monochromatic reflectance data by integration over the appropriate spectral range. The absorptance for solar radiation, usually designated in the solar energy literature simply as  $\alpha$ , and the emittance, usually designated simply as  $\varepsilon$ , are calculated as shown in Section 4.6. For normal operation of flat-plate solar collectors, the temperatures



**Figure 4.8.1** A hypothetical selective surface with the cutoff wavelength at 3  $\mu\text{m}$ .

<sup>7</sup>This will be discussed in detail in Chapter 6.

<sup>8</sup>Agnihotri and Gupta (1981) provide a very extensive coverage of selective surfaces.

will be low enough that essentially all energy will be emitted at wavelengths greater than  $3\text{ }\mu\text{m}$ .

### Example 4.8.1

For the surface shown in Figure 4.8.1, calculate the absorptance for blackbody radiation from a source at 5777 K and the emittance at surface temperatures of 150 and 500°C.

### Solution

The absorptance for radiation from a blackbody source at 5777 K is found by Equation 4.6.4 with the incident radiation  $q_{\lambda,i}$  given by Planck's law, Equation 3.4.1.

For this problem,  $\alpha_\lambda$  has two values,  $\alpha_S$  in the short wavelengths below  $\lambda_c$  and  $\alpha_L$  in the long wavelengths:

$$\alpha = \alpha_S f_{0-\lambda T} + \alpha_L (1 - f_{0-\lambda T})$$

where  $f_{0-\lambda T}$  is the fraction of the incident blackbody radiation below the critical wavelength and is found from Table 3.6.1 at  $\lambda T = 3 \times 5777 = 17,331$ . Therefore the absorptance is

$$\alpha = (1 - 0.10)(0.979) + (1 - 0.95)(1 - 0.979) = 0.88$$

The emittances at 150 and 500°C are found with Equation 4.6.1. Again Table 3.6.1 is used in performing this integration. Equation 4.6.1 reduces to the following:

$$\varepsilon = \varepsilon_S f_{0-\lambda T} + \varepsilon_L (1 - f_{0-\lambda T})$$

where  $f_{0-\lambda T}$  is now the fraction of the blackbody energy that is below the critical wavelength but at the surface temperature rather than the source temperature, as was used in calculating the absorptance. For a surface temperature of 150°C (423 K),  $\lambda T = 1269$  and  $f_{0-\lambda T} = 0.004$ . The emittance at 150°C is then

$$\varepsilon_{150} = (1 - 0.10)(0.004) + (1 - 0.95)(0.996) = 0.05$$

at a surface temperature of 500°C,  $f_{0-\lambda T} = 0.124$  and the emittance at 500°C is

$$\varepsilon_{500} = (1 - 0.10)(0.124) + (1 - 0.95)(0.876) = 0.16 \quad \blacksquare$$

In practice, the wavelength dependence of  $\rho_\lambda$  does not approach the ideal curve of Figure 4.8.1. Examples of  $\rho_\lambda$  versus  $\lambda$  for several real surfaces are shown in Figures 4.8.2 and 4.8.3. Real selective surfaces do not have a well-defined critical wavelength  $\lambda_c$  or uniform properties in the short- and long-wavelength ranges. Values of emittance will be more sensitive to surface temperature than those of the ideal semigray surface of Figure 4.8.1. The integration procedure is the same as in Examples 4.6.1 and 4.8.1, but smaller spectral increments must be used.

### Example 4.8.2

Calculate the solar absorptance and the emittance at 100°C for the surface shown in curve C of Figure 4.8.2.




Figure 4.8.2 Spectral reflectance of several surfaces. From Edwards et al. (1960).




Figure 4.8.3 Spectral reflectance of black chrome on nickel before and after humidity tests. From Lin (1977).

### Solution

The solar absorptance  $\alpha$  should be calculated from Equation 4.6.5, with the incident radiation  $q_{\lambda,i}$  having the spectral distribution of solar radiation at the collector surface. Assume that the spectral distribution of Table 2.6.1 for air mass 2 represents the distribution of solar radiation. The table that follows gives the midpoints of the spectral bands that each contains 10% of the extraterrestrial solar radiation. The monochromatic reflectances of the selective surface corresponding to these midpoint wavelengths are shown. The monochromatic absorptances are just  $1 - \rho_\lambda$  and are assumed to hold over their wavelength intervals. Since the intervals are all the same, the solar absorptance is the sum of these




values divided by the number of intervals as in Equation 4.6.5. The result of the calculation is  $\alpha = 0.89$ .

The emittance at a temperature of  $100^\circ\text{C}$  is found in the same manner as described in Example 4.6.1, but here 10 increments are used rather than 5 increments. The midpoint  $\lambda T$  of each increment is found from Table 3.6.1b, the wavelength is determined from  $\lambda T$  with  $T = 373\text{ K}$ , and the monochromatic reflectance is read from the curve of Figure 4.8.2. The value of monochromatic emittance at wavelengths beyond  $25\text{ }\mu\text{m}$  is assumed to be 0.13. Using Equation 4.6.3, this procedure leads to an emittance of 0.16.

The details of the  $\alpha$  and  $\varepsilon$  calculations are shown in the following table:

Incident Spectrum				Emitted Spectrum		
Increment in Spectrum		$\lambda$ at Midpoint	$\alpha_\lambda = 1 - \rho_\lambda$	$\lambda T$ at Midpoint	$\lambda$ at $T = 373\text{ K}$	$\varepsilon_\lambda = 1 - \rho_\lambda$
0.0–0.1	0.05	0.43	0.95	1,880	5.0	0.43
0.1–0.2	0.15	0.51	0.93	2,450	6.6	0.24
0.2–0.3	0.25	0.58	0.91	2,900	7.8	0.16
0.3–0.4	0.35	0.65	0.96	3,350	9.0	0.14
0.4–0.5	0.45	0.73	0.96	3,830	10.3	0.11
0.5–0.6	0.55	0.82	0.93	4,410	11.8	0.10
0.6–0.7	0.65	0.93	0.86	5,130	13.8	0.09
0.7–0.8	0.75	1.08	0.78	6,150	16.5	0.08
0.8–0.9	0.85	1.30	0.72	7,850	21.0	0.10
0.9–1.0	0.95	1.97	<u>0.90</u>	12,500	33.5	<u>0.13</u>
		Average	0.89		Average	0.16

The reflectance of this surface for solar radiation is  $1 - \alpha = 0.11$ . The infrared emittance at a surface temperature of  $373\text{ K}$  is 0.16. The figure shows the infrared emittance for surface temperatures between  $300$  and  $800\text{ K}$ . For the range of normal flat-plate collector surface operating temperatures ( $275$  to  $375\text{ K}$ ) assuming the surface emittance to be 0.16 would be a reasonable approximation.



The potential utility of selective surfaces in solar collectors was inferred by Hottel and Woertz (1942) and noted by Gier and Dunkle (1958) and Tabor (1956, 1967) and Tabor et al. (1964). Interest in designing surfaces with a variety of  $\rho_\lambda$ -versus- $\lambda$  characteristics for applications to space vehicles and to solar energy applications resulted in considerable research and compilation of data (e.g., Martin and Bell, 1960; Edwards et al., 1960; Schmidt et al., 1964). Tabor (1967, 1977) reviewed selective surfaces and presents several methods for their preparation. Buhrman (1986) presents a review of the physics of these surfaces. Selective surfaces are in commercial use.

## 4.9 MECHANISMS OF SELECTIVITY

Several methods of preparing selective surfaces have been developed which depend on various mechanisms or combinations of mechanisms to achieve selectivity.

Coatings that have high absorptance for solar radiation and high transmittance for long-wave radiation can be applied to substrates with low emittance. The coating absorbs solar energy, and the substrate is the (poor) emitter of long-wave radiation. Coatings may be homogeneous or have particulate structure; their properties are then the inherent optical properties of either the coating material or the material properties and the coating structure. Many of the coating materials used are metal oxides and the substrates are metals. Examples are copper oxide on aluminum (e.g., Hottel and Unger, 1959) and copper oxide on copper (e.g., Close, 1962). A nickel—zinc sulfide coating can be applied to galvanized iron (Tabor, 1956).

Black chrome selective surfaces have been widely adopted for solar collectors. The substrate is usually nickel plating on a steel or copper base. The coatings are formed by electroplating in a bath of chromic acid and other agents.<sup>9</sup> In laboratory specimens, absorptances of 0.95 to 0.96 and emittances of 0.08 to 0.14 were obtained, while the average properties of samples of production run collector plates were  $\alpha = 0.94$  and  $\varepsilon = 0.08$  (Moore, 1976). Reflectance properties of these surfaces are described by McDonald (1974, 1975) and others. The surfaces appear to have good durability on exposure to humid atmospheres, as shown in Figure 4.8.3. Many references are available on preparation of chrome black surfaces, for example, Benning (1976), Pettit and Sowell (1976), and Sowell and Mattox (1976). The structure and properties of black chrome coatings have been examined by Lampert and Washburn (1979). They found the wavelengths of transition from low to high reflectance to be in the 1.5- to 5- $\mu\text{m}$  range, with increasing thickness of the coating shifting the transition to longer wavelengths. The coatings are aggregates of particles and voids, with particles of 0.05 to 0.30  $\mu\text{m}$  diameter that are combinations of very much smaller particles of chromium and an amorphous material that is probably chromium oxide.

Selective surfaces have been in use on Israeli solar water heaters since about 1950. A base of galvanized iron is carefully cleaned and a black nickel coating is applied by immersion of the plate as the cathode in an aqueous electroplating bath containing nickel sulfate, zinc sulfate, ammonium sulfate, ammonium thiocyanate, and citric acid. Details of this process are provided by Tabor (1967).

---

<sup>9</sup>Plating bath chemicals are available from Harshaw Chemical Co. (Chromonyx chromium process) and du Pont Company (Durimir BK black chromium process).

Copper oxide on copper selective blacks is formed on carefully degreased copper plates by treating the plates for various times in hot ( $140^{\circ}\text{C}$ ) solutions of sodium hydroxide and sodium chlorite, as described by Close (1962). Similar proprietary blackening processes have been used in the United States under the name Ebanol.

Absorptance of coatings can be enhanced by taking advantage of interference phenomena. Some coatings used on highly reflective (low- $\varepsilon$ ) substrates are semiconductors which have high absorptance in the solar energy spectrum but have high transmittance for long-wave radiation. Many of these materials also have a high index of refraction and thus reflect incident solar energy. This reflection loss can be reduced by secondary antireflective coatings. It has been shown by Martin and Bell (1960) that three-layer coatings such as  $\text{SiO}_2\text{-Al-SiO}_2$  on substrates such as aluminum could have absorptances for solar energy greater than 0.90 and long-wave emittances less than 0.10. The selectivity of surfaces using silicon and germanium with antireflecting coatings has been demonstrated by Seraphin (1975) and Meinel et al. (1973).


Vacuum sputtering processes for selective surfaces in evacuated tube collectors have been studied by Harding (1976) and Harding et al. (1976). The sputtering can be done in inert atmospheres (argon) to make metal coatings or in reactive atmospheres (argon plus 1 to 2% methane) to produce metal and metal carbide coatings. These coatings reportedly have extremely low emittances ( $\varepsilon = 0.03$ ) but moderate absorptance ( $\alpha \approx 0.8$ ); higher absorptances are optimum in most applications.

Sputtering processes are used in the application of cermet selective surfaces on the receivers of Luz concentrating collectors, which operate at temperatures between  $300$  and  $400^{\circ}\text{C}$  (Harats and Kearney, 1989). Four layers are deposited on the steel pipe receiving surface: an antidiffusing oxide layer to prevent diffusion of molecules of the steel substrate into the coatings, an infrared reflective layer (to provide low emittance), the cermet absorbing layer, and an antireflective oxide layer. These surfaces, which are used in vacuum jackets, have absorptance for solar radiation of 0.96 and design emittance for long-wave radiation of 0.16 at  $350^{\circ}\text{C}$ . The stability is excellent at temperatures well above  $400^{\circ}\text{C}$ . [The process used in making these surfaces is based on the work of Thornton and Lamb (1987).]


The surface structure of a metal of high reflectance can be designed to enhance its absorptance for solar radiation by grooving or pitting the surface to create cavities of dimensions near the desired cutoff wavelength of the surface. The surface acts as an array of cavity absorbers for solar radiation, thus having reduced reflectance in this part of the spectrum. The surface radiates as a flat surface in the long-wave spectrum and thus shows its usual low emittance. Desirable surface structures have been made by forming tungsten dendritic crystal in substrates by reduction of tungsten hexafluoride with hydrogen (Cuomo et al., 1976) or by chemical vapor deposition of dendritic nickel crystals from nickel carbonyl (Grimmer et al., 1976). Intermetallic compounds, such as  $\text{Fe}_2\text{Al}_5$ , can be formed with highly porous structures and show some selectivity (Santala, 1975). The degree of selectivity obtainable by this method is limited, and the emittances obtained to date have been 0.5 or more. However, roughening the substrate over which oxide (or other) coatings are applied can result in improved absorptance.

Directional selectivity can be obtained by proper arrangement of the surface on a large scale. Surfaces of deep V-grooves, large relative to all wavelengths of radiation concerned, can be arranged so that radiation from near-normal directions to the overall surface will be reflected several times in the grooves, each time absorbing a fraction of the

beam. This multiple absorption gives an increase in the solar absorptance but at the same time increases the long-wavelength emittance. However, as shown by Hollands (1963), a moderately selective surface can have its effective properties substantially improved by proper configuration. For example, a surface having nominal properties of  $\alpha = 0.60$  and  $\varepsilon = 0.05$ , used in a fixed optimally oriented flat-plate collector over a year, with  $55^\circ$  grooves, will have an average effective  $\alpha$  of 0.90 and an equivalent  $\varepsilon$  of 0.10. Figure 4.9.1 illustrates the multiple absorptions obtained for various angles of incidence of solar radiation on a  $30^\circ$  grooved surface. Figure 4.9.2 shows the variation of average yearly solar absorptance as a function of angle of the grooves and the absorptance of the plane surface.



**Figure 4.9.1** Absorption of radiation by successive reflections on folded metal sheets. Adapted from Trombe et al. (1964).



**Figure 4.9.2** Average yearly solar absorptance versus groove angle for several values of absorptance of plane surfaces. From Hollands (1963).

**Table 4.9.1** Properties of Some Selective Surfaces

Surface	$\alpha$	$\varepsilon$	Reference
Black chrome on Ni-plated steel	0.95	0.09	Mar et al. (1976), Lampert and Washburn (1979), and others
Sputtered cermet coating on steel	0.96	0.16	Harats and Kearney (1989)
“Nickel black” on galvanized steel	0.81	0.17	Tabor et al. (1964)
“Cu black” on Cu, by treating Cu with solution of NaOH and NaClO <sub>2</sub>	0.89	0.17	Close (1962)
Ebanol C on Cu; commercial Cu-blackening treatment giving coatings largely CuO	0.90	0.16	Edwards et al. (1962)

The physical structure of coatings on reflective substrates will affect the reflectance of the surface. Williams et al. (1963) showed that the reflectance of coatings of lead sulfide is a function of the structure of the coating and that finely divided particulate coatings of large void fraction have a low effective refractive index and a low reflectance in the solar spectrum. [The black chrome surfaces of Lampert and Washburn (1979) have a similar structure, in that they are particulates in voids.] This phenomenon is the basis for experimental studies of selective paints, in which binders transparent (insofar as is possible) to solar radiation are used to provide physical strength to the coatings. For example, PbS coatings of void fraction 0.8 to 0.9 on polished pure (99.99) aluminum substrates showed  $\alpha$  of 0.8 to 0.9 and  $\varepsilon$  of 0.2 to 0.3 without a binder and  $\varepsilon = 0.37$  with a silicone binder. Lin (1977) has reported studies of a range of pigments (mostly metal oxides) and binders on aluminum substrates and notes the best laboratory results obtained for an iron–manganese–copper oxide paint with a silicone binder are  $\alpha = 0.92$  and  $\varepsilon = 0.13$ . Quality control on application to substrates is a difficult problem (thickness of a coating has a strong effect on  $\alpha$  and  $\varepsilon$ ) that remains to be solved before these selective paints become practical for applications.


A critical consideration in the use of selective surfaces is their durability. Solar collectors must be designed to operate essentially without maintenance for many years, and the coatings and substrates must retain useful properties in humid, oxidizing atmospheres and at elevated temperatures. Data from Lin (1977) and Mar et al. (1976) and from other sources, plus experience with chrome black in other kinds of applications, suggest that this surface will retain its selective properties in a satisfactory way. Years of experience with Israeli nickel black, Australian copper oxide on copper coatings, and more recently chrome blacks have shown that these coatings can be durable.

Table 4.9.1 shows absorptance for solar radiation and emittance for long-wave radiation of surfaces that have been produced by commercial processes.

## 4.10 OPTIMUM PROPERTIES

In flat-plate collectors, it is generally more critical to have high absorptance than low emittance.<sup>10</sup> It is a characteristic of many surfaces that there is a relationship between  $\alpha$

<sup>10</sup>This will become evident in Chapter 6.



**Figure 4.10.1** Variations of  $\alpha$  and  $\varepsilon$  with the product of plating current density and time for chrome black. Adapted from Sowell and Mattox (1976).


and  $\varepsilon$  as typified by data shown in Figure 4.10.1. In the case of the chrome black surface, the optimum plating time (coating thickness) is obvious. For other selective surfaces the optimum mass per unit area or other measure of coating physical properties is not immediately obvious. The best combination must ultimately be selected on the basis of the effects of properties  $\alpha$  and  $\varepsilon$  on the annual operation of the complete solar energy system.<sup>11</sup> But the generalization can be made that  $\alpha$  should be near its maximum for best performance.

#### 4.11 ANGULAR DEPENDENCE OF SOLAR ABSORPTANCE

The angular dependence of solar absorptance of most surfaces used for solar collectors is not available. The directional absorptance for solar radiation of ordinary blackened surfaces (such as are used for solar collectors) is a function of the angle of incidence of the radiation on the surface. An example of this dependence of absorptance on angle of incidence is shown in Figure 4.11.1. The limited data available suggest that selective surfaces may exhibit similar behavior (Pettit and Sowell, 1976). A polynomial fit to the curve of Figure 4.11.1 is

$$\begin{aligned} \frac{\alpha}{\alpha_n} = & 1 - 1.5879 \times 10^{-3} \theta + 2.7314 \times 10^{-4} \theta^2 - 2.3026 \times 10^{-5} \theta^3 \\ & + 9.0244 \times 10^{-7} \theta^4 - 1.8000 \times 10^{-8} \theta^5 + 1.7734 \times 10^{-10} \theta^6 \\ & - 6.9937 \times 10^{-13} \theta^7 \end{aligned} \quad (4.11.1)$$

<sup>11</sup>Methods for this evaluation are in Chapter 14.



**Figure 4.11.1** Ratio of solar absorptance and solar absorptance at normal incidence for a flat black surface. From Beckman et al. (1977).

## 4.12 ABSORPTANCE OF CAVITY RECEIVERS

Some solar energy applications require that solar radiation be absorbed in cavities rather than on flat surfaces. The effective absorptance of a cavity without a cover on its aperture, that is, the fraction of incident radiation that is absorbed by the cavity,<sup>12</sup> is a function of the absorptance of the inner surfaces of the cavity and the ratio of the areas of the cavity aperture and inner surfaces. It is approximated by

$$\alpha_{\text{eff}} = \frac{\alpha_i}{\alpha_i + (1 - \alpha_i) A_a/A_i} \quad (4.12.1)$$

where  $\alpha_i$  is the absorptance of the inner surface of the cavity,  $A_a$  is the area of the aperture of the cavity, and  $A_i$  is the area of the inner surface. As an approximation,  $\alpha_i$  can be evaluated at the effective angle of incidence of diffuse radiation, about  $60^\circ$ .

### Example 4.12.1

A cylindrical cavity receiver has its length the same as its diameter. The aperture is in the end of the cylinder and has a diameter of two-thirds of that of the cylinder. The inner surface of the cavity has an absorptance at normal incidence of 0.60. Estimate the effective absorptance of the cavity.

<sup>12</sup>The presence of a transparent cover over the aperture of a cavity (such as a window in a room acting as a cavity receiver in passive heating) modifies Equation 4.12.1. See Section 5.11.

**Solution**

Assume that the angular dependence of  $\alpha_i$  is as shown in Figure 4.11.1. At an incident angle of  $60^\circ$ ,  $\alpha_i/\alpha_n = 0.93$  and  $\alpha_i = 0.93 \times 0.60 = 0.56$ .

The ratio  $A_a/A_i$ , if  $d$  is the diameter of the cavity, is

$$\frac{A_a}{A_i} = \frac{(0.667)^2 \pi d^2 / 4}{(2 - 0.667^2) \pi d^2 / 4 + \pi d^2} = \frac{(0.667)^2}{(2 - 0.667^2) + 4} = 0.080$$

The effective absorptance of the cavity is then

$$\alpha_{\text{eff}} = \frac{0.56}{0.56 + (1 - 0.56) 0.080} = 0.94 \quad \blacksquare$$

**4.13 SPECULARLY REFLECTING SURFACES**

Concentrating solar collectors require the use of reflecting materials (or possibly refracting materials) to direct the beam component of solar radiation onto a receiver. This requires surfaces of high specular reflectance for radiation in the solar spectrum.

Specular surfaces are usually metals or metallic coatings on smooth substrates. Opaque substrates must be front surfaced. Examples are anodized aluminum and rhodium-plated copper. The specular reflectivity of such surfaces is a function of the quality of the substrate and the plating.

Specular surfaces can also be applied to transparent substrates, including glass or plastic. If back-surface coatings are applied, the transparency of the substrate is important, as the radiation will pass through the equivalent of twice the thickness of the substrate and twice through the front surface-air interface. (See Chapter 5 for discussion of radiation transmission through partially transparent media.) If front-surface coatings are used on these substrates, the nature of the substrate, other than its smoothness and stability, is unimportant.

Specular reflectance is, in general, wavelength dependent, and in principle, monochromatic reflectances should be integrated for the particular spectral distribution of incident energy. Thus, the monochromatic specular reflectance is defined as

$$\rho_{\lambda s} = \frac{I_{\lambda s}}{I_{\lambda i}} \quad (4.13.1)$$

where  $I_{\lambda s}$  is the specularly reflected monochromatic intensity and  $I_{\lambda i}$  is the incident monochromatic intensity. Then the specular reflectance is

$$\rho_s = \frac{\int_0^\infty \rho_{\lambda s} I_{\lambda s} d\lambda}{\int_0^\infty I_{\lambda s} d\lambda} \quad (4.13.2)$$

Typical values of specular reflectance of surfaces for solar radiation are shown in Table 4.13.1. The table includes data on front-surface and second-surface reflectors.



**Table 4.13.1** Normal Specular Solar Reflectances of Surfaces

Surface	$\rho$
Back-silvered low-reflectance glass	0.94
Electroplated silver, new	0.96
High-purity Al, new clean	0.91
Sputtered aluminum optical reflector	0.89
Brytal processed aluminum, high purity	0.89
Back-silvered water white plate glass, new, clean	0.88
Al, SiO coating, clean	0.87
Aluminum foil, 99.5% pure	0.86
Back-aluminized 3M acrylic, new	0.86
Back-aluminized 3M acrylic <sup>a</sup>	0.85
Commercial Alzac process aluminum	0.85

<sup>a</sup>Exposed to equivalent of 1 yr solar radiation.

Back-silvered glass can have excellent specular reflectance, and if the reflective coatings are adequately protected, durability is excellent. The aluminized acrylic film is one of a number of aluminized polymeric films that have been evaluated for durability in weather, and it appears to be the best of those reported by the University of Minnesota and Honeywell (1973). Many other such materials have short lifetimes (on the order of weeks or months) under practical operating conditions.

Maintenance of high specular reflectance presents practical problems. Front-surface reflectors are subject to degradation by oxidation, abrasion, dirt, and so on. Back-surface reflectors may lose reflectance because of dirt or degradation of the overlying transparent medium or degradation of the reflecting coating.

Front-surface reflectors may be covered by thin layers of protective materials to increase their durability. For example, anodized aluminum is coated with a thin stable layer of aluminum oxide deposited by electrochemical means, and silicon monoxide has been applied to front-surface aluminum films. In general, each coating reduces the initial value of specular reflectance but may result in more satisfactory levels of reflectance over long periods of time.

## REFERENCES

- Agnihotri, O. P. and B. K. Gupta, *Solar Selective Surfaces*, Wiley, New York (1981).
- Beckman, W. A., S. A. Klein, and J. A. Duffie, *Solar Heating Design*, Wiley, New York (1977).
- Benning, A. C., in *AES Coatings for Solar Collectors Symposium*, American Electroplaters' Society (G. McDonald, ed.), Winter Park, FL, p. 57 (1976). "Black Chromium—A Solar Selective Coating."
- Buhrman, R. A., in *Advances in Solar Energy*, Vol. 3 (K. Böer, ed.), American Solar Energy Society, Boulder, CO, p. 207 (1986). "Physics of Solar Selective Surfaces."
- Close, D. J., Report E.D.7, Engineering Section, Commonwealth Scientific and Industrial Research Organization, Melbourne, Australia (1962). "Flat-Plate Solar Absorbers: The Production and Testing of a Selective Surface for Copper Absorber Plates."

- Cuomo, J. J., J. M. Woodall, and T. W. DiStefano, in *AES Coatings for Solar Collectors Symposium*, Electroplaters' Society (G. McDonald, ed.), Winter Park, FL (1976). "Dendritic Tungsten for Solar Thermal Conversion."
- Edwards, D. K., J. T. Gier, K. E. Nelson, and R. Roddick, *Solar Energy*, **6**, 1 (1962). "Spectral and Directional Thermal Radiation Characteristics of Selective Surfaces for Solar Collectors."
- Edwards, D. K., K. E. Nelson, R. D. Roddick, and J. T. Gier, Report No. 60-93, Department of Engineering, University of California at Los Angeles (Oct. 1960). "Basic Studies on the Use and Control of Solar Energy."
- Gier, J. T. and R. V. Dunkle, in *Transactions of the Conference of the Use of Solar Energy* (E. F. Carpenter, ed.), Vol. 2, Pt. I, University of Arizona Press, Tucson, p. 41 (1958). "Selective Spectral Characteristics as an Important Factor in the Efficiency of Solar Collectors."
- Gier, J. T., R. V. Dunkle, and J. T. Bevans, *J. Opt. Soc. Am.*, **44**, 558 (1954). "Measurements of Absolute Spectral Reflectivity from 1.0 to 15 Microns."
- Grimmer, C. P., K. C. Herr, and W. V. McCreary, in *AES Coatings for Solar Collectors Symposium*, American Electroplaters' Society (G. McDonald, ed.), Winter Park, FL, p. 79 (1976). "A Possible Selective Solar Photothermal Absorber: Ni Dendrites Formed on Al Surfaces by the CVD of  $\text{NiCO}_4$ ."
- Harats, Y. and D. Kearney, paper presented at ASME Meeting, San Diego (1989). "Advances in Parabolic Trough Technology in the SEGS Plants."
- Harding, G. L., *J. Vacuum Sci. Technol.*, **13**, 1070 (1976). "Sputtered Metal Carbide Solar-Selective Absorbing Surfaces."
- Harding, G. L., D. L. McKenzie, and B. Window, *J. Vacuum Sci. Technol.*, **13**, 1073 (1976). "The dc Sputter Coating of Solar-Selective Surfaces onto Tubes."
- Hollands, K. G. T., *Solar Energy*, **7**, 108 (1963). "Directional Selectivity, Emittance and Absorptance Properties of Vee Corrugated Specular Surfaces."
- Hottel, H. C. and T. A. Unger, *Solar Energy*, **3** (3), 10 (1959). "The Properties of a Copper Oxide-Aluminum Selective Black Surface Absorber of Solar Energy."
- Hottel, H. C. and B. B. Woertz, *Trans. ASME*, **14**, 91 (1942). "Performance of Flat-Plate Solar-Heat Exchangers."
- Lampert, C. M., in *Advances in Solar Energy*, Vol. 5 (K. Böer, ed.), American Solar Energy Society and Plenum Press, New York, p. 99 (1990). "Advances in Solar Optical Materials."
- Lampert, C. M. and J. Washburn, *Solar Energy Materials*, **1**, 81 (1979). "Microstructure of a Black Chrome Solar Selective Surface."
- Lin, R. J. H., Report C00/2930-4 to ERDA (Jan. 1977). "Optimization of Coatings for Flat-Plate Solar Collectors."
- Mar, H. Y. B., R. E. Peterson, and P. B. Zimmer, *Thin Solid Films*, **39**, 95 (1976). "Low Cost Coatings for Flat-Plate Solar Collectors."
- Martin, D. C. and R. Bell, in *Proceedings of the Conference on Coatings for the Aerospace Environment*, WADD-TR-60-TB, Wright Air Development Division, Dayton, OH (Nov. 1960). "The Use of Optical Interference to Obtain Selective Energy Absorption."
- McDonald, G. E., NASA Technical Memo NASA TMX 0171596 (1974). "Solar Reflectance Properties of Black Chrome for Use as a Solar Selective Coating."
- McDonald, G. E., *Solar Energy*, **17**, 119 (1975). "Spectral Reflectance Properties of Black Chrome for Use as a Solar Selective Coating."
- Meinel, A. B., M. P. Meinel, C. B. McDenney, and B. O. Seraphin, paper E13 presented at Paris Meeting of International Solar Energy Society (1973). "Photothermal Conversion of Solar Energy for Large-Scale Electrical Power Production."
- Moore, S. W., in *AES Coatings for Solar Collectors Symposium*, American Electroplaters' Society (G. McDonald, ed.), Winter Park, FL (1976). "Results Obtained from Black Chrome Production Run of Steel Collectors."

- Pettit, R. B. and R. P. Sowell, *J. Vacuum Sci. Technol.*, **13** (2), 596 (1976), "Solar Absorptance and Emittance Properties."
- Santala, T., in *Workshop in Solar Collectors for Heating and Cooling of Buildings*, Report, National Science Foundation RANN-75-919, p. 233 (May 1975). "Intermetallic Absorption Surface Material Systems for Collector Plates."
- Schmidt, R. N., K. C. Park, and E. Janssen, Tech. Doc. Report No. ML-TDR-64-250 from Honeywell Research Center to Air Force Materials Laboratory (Sept. 1964). "High Temperature Solar Absorber Coatings, Part II."
- Seraphin, B. O., Reports on National Science Foundation Grant GI-36731X of the Optical Sciences Center, University of Arizona (1975).
- Siegel, R. and J. R. Howell, *Thermal Radiation Heat Transfer*, 4th ed., Taylor & Francis, New York (2002).
- Sowell, R. R. and D. M. Mattox, in *AES Coatings for Solar Collectors Symposium*, American Electroplaters' Society (G. McDonald, ed.), Winter Park, FL, p. 21 (1976). "Properties and Composition of Electroplated Black Chrome."
- Tabor, H., *Bull. Res. Council Israel*, **5A** (2), 119 (Jan. 1956). "Selective Radiation."
- Tabor, H., in *Low Temperature Engineering Applications of Solar Energy* (R. C. Jordan, ed.), ASHRAE, New York (1967). "Selective Surfaces for Solar Collectors."
- Tabor, H., in *Applications of Solar Energy for Heating and Cooling of Buildings* (R. C. Jordan and B. Y. H. Liu, eds), ASHRAE GRP-170, New York (1977). "Selective Surfaces for Solar Collectors."
- Tabor, H., J. Harris, H. Weinberger, and B. Doron, *Proc. UN Conf. New Sources of Energy*, **4**, 618 (1964). "Further Studies on Selective Black Coatings."
- Thornton, J. A. and J. A. Lamb, Report SERI/STR-255-3040, Solar Energy Research Institute (1987). "Evaluation of Cermet Selective Absorber Coatings Deposited by Vacuum Sputtering."
- Touloukian, Y. S., et al., *Thermophysical Properties of Matter*, Plenum Data Corporation, New York, Vol. 7 (1970): "Thermal Radiative Properties—Metallic Elements and Alloys"; Vol. 8 (1972): "Thermal Radiative Properties—Nonmetallic Solids"; Vol. 9 (1973): "Thermal Radiative Properties—Coatings."
- Trombe, F., M. Foex, and M. LePhat Vinh, *Proc. UN Conf. New Sources of Energy*, **4**, 625, 638 (1964). "Research on Selective Surfaces for Air Conditioning Dwellings."
- University of Minnesota and Honeywell Corp. Progress Report No. 2 to the National Science Foundation, NSF/RANN/SE/GI-34871/PR/73/2 (1973). "Research Applied to Solar-Thermal Power Systems."
- Williams, D. A., T. A. Lappin, and J. A. Duffie, *Trans. ASME J. Eng. Power*, **85A**, 213 (1963). "Selective Radiation Properties of Particulate Coatings."

# Radiation Transmission through Glazing: Absorbed Radiation

The transmission, reflection, and absorption of solar radiation by the various parts of a solar collector are important in determining collector performance. The transmittance, reflectance, and absorptance are functions of the incoming radiation, thickness, refractive index, and extinction coefficient of the material. Generally, the refractive index  $n$  and the extinction coefficient  $K$  of the cover material are functions of the wavelength of the radiation. However, in this chapter, all properties initially will be assumed to be independent of wavelength. This is an excellent assumption for glass, the most common solar collector cover material. Some cover materials have significant optical property variations with wavelength, and spectral dependence of properties is considered in Section 5.7. Incident solar radiation is unpolarized (or only slightly polarized). However, polarization considerations are important as radiation becomes partially polarized as it passes through collector covers.

The last sections of this chapter treat the absorption of solar radiation by collectors, collector-storage walls, and rooms on an hourly and on a monthly average basis.

Reviews of important considerations of transmission of solar radiation have been presented by Dietz (1954, 1963) and by Siegel and Howell (2002).

## 5.1 REFLECTION OF RADIATION


For smooth surfaces Fresnel has derived expressions for the reflection of unpolarized radiation on passing from medium 1 with a refractive index  $n_1$  to medium 2 with refractive index  $n_2$ :

$$r_{\perp} = \frac{\sin^2 (\theta_2 - \theta_1)}{\sin^2 (\theta_2 + \theta_1)} \quad (5.1.1)$$

$$r_{\parallel} = \frac{\tan^2 (\theta_2 - \theta_1)}{\tan^2 (\theta_2 + \theta_1)} \quad (5.1.2)$$

$$r = \frac{I_r}{I_i} = \frac{r_{\perp} + r_{\parallel}}{2} \quad (5.1.3)$$

where  $\theta_1$  and  $\theta_2$  are the angles of incidence and refraction, as shown in Figure 5.1.1. Equation 5.1.1 represents the perpendicular component of unpolarized radiation  $r_{\perp}$ , and



**Figure 5.1.1** Angles of incidence and refraction in media with refractive indices  $n_1$  and  $n_2$ .

Equation 5.1.2 represents the parallel component of unpolarized radiation  $r_{\parallel}$ . (Parallel and perpendicular refer to the plane defined by the incident beam and the surface normal.) Equation 5.1.3 then gives the reflection of unpolarized radiation as the average of the two components. The angles  $\theta_1$  and  $\theta_2$  are related to the indices of refraction by Snell's law,

$$n_1 \sin \theta_1 = n_2 \sin \theta_2 \quad (5.1.4)$$

Thus if the angle of incidence and refractive indices are known, Equations 5.1.1 through 5.1.4 are sufficient to calculate the reflectance of the single interface.

For radiation at normal incidence both  $\theta_1$  and  $\theta_2$  are zero, and Equations 5.1.3 and 5.1.4 can be combined to yield

$$r(0) = \frac{I_r}{I_i} = \left( \frac{n_1 - n_2}{n_1 + n_2} \right)^2 \quad (5.1.5)$$

If one medium is air (i.e., a refractive index of nearly unity), Equation 5.1.5 becomes

$$r(0) = \left( \frac{n - 1}{n + 1} \right)^2 \quad (5.1.6)$$

### Example 5.1.1

Calculate the reflectance of one surface of glass at normal incidence and at  $60^\circ$ . The average index of refraction of glass for the solar spectrum is 1.526.

### Solution

At normal incidence, Equation 5.1.6 can be used:

$$r(0) = \left( \frac{0.526}{2.526} \right)^2 = 0.0434$$

At an incidence angle of  $60^\circ$ , Equation 5.1.4 gives the refraction angle  $\theta_2$ :

$$\theta_2 = \sin^{-1} \left( \frac{\sin 60}{1.526} \right) = 34.58$$

From Equation 5.1.3, the reflectance is

$$r(60) = \frac{1}{2} \left[ \frac{\sin^2(-25.42)}{\sin^2(94.58)} + \frac{\tan^2(-25.42)}{\tan^2(94.58)} \right] = \frac{1}{2} (0.185 + 0.001) = 0.093$$

In solar applications, the transmission of radiation is through a slab or film of material so there are two interfaces per cover to cause reflection losses. At off-normal incidence, the radiation reflected at an interface is different for each component of polarization, so the transmitted and reflected radiation becomes partially polarized. Consequently, it is necessary to treat each component of polarization separately.

Neglecting absorption in the cover material shown in Figure 5.1.2 and considering for the moment only the perpendicular component of polarization of the incoming radiation,  $(1 - r_{\perp})$  of the incident beam reaches the second interface. Of this,  $(1 - r_{\perp})^2$  passes through the interface and  $r_{\perp}(1 - r_{\perp})$  is reflected back to the first, and so on. Summing the transmitted terms, the transmittance for the perpendicular component of polarization is

$$\tau_{\perp} = (1 - r_{\perp})^2 \sum_{n=0}^{\infty} r_{\perp}^{2n} = \frac{(1 - r_{\perp})^2}{1 - r_{\perp}^2} = \frac{1 - r_{\perp}}{1 + r_{\perp}} \quad (5.1.7)$$


Exactly the same expansion results when the parallel component of polarization is considered. The components  $r_{\perp}$  and  $r_{\parallel}$  are not equal (except at normal incidence), and the transmittance of initially unpolarized radiation is the average transmittance of the two components,

$$\tau_r = \frac{1}{2} \left( \frac{1 - r_{\parallel}}{1 + r_{\parallel}} + \frac{1 - r_{\perp}}{1 + r_{\perp}} \right) \quad (5.1.8)$$

where the subscript  $r$  is a reminder that only reflection losses have been considered.

For a system of  $N$  covers all of the same materials, a similar analysis yields

$$\tau_{rN} = \frac{1}{2} \left( \frac{1 - r_{\parallel}}{1 + (2N - 1)r_{\parallel}} + \frac{1 - r_{\perp}}{1 + (2N - 1)r_{\perp}} \right) \quad (5.1.9)$$



**Figure 5.1.2** Transmission through one nonabsorbing cover.

**Example 5.1.2**

Calculate the transmittance of two covers of nonabsorbing glass at normal incidence and at  $60^\circ$ .

**Solution**

At normal incidence, the reflectance of one interface from Example 5.1.1 is 0.0434. From Equation 5.1.9, with both polarization components equal, the transmittance is


$$\tau_r(0) = \frac{1 - 0.0434}{1 + 3(0.0434)} = 0.85$$

Also from Example 5.1.1 but at a  $60^\circ$  incidence angle, the reflectances of one interface for each component of polarization are 0.185 and 0.001. From Equation 5.1.9, the transmittance is

$$\tau_r(60) = \frac{1}{2} \left[ \frac{1 - 0.185}{1 + 3(0.185)} + \frac{1 - 0.001}{1 + 3(0.001)} \right] = 0.76$$

The solar transmittance of *nonabsorbing* glass, having an average refractive index of 1.526 in the solar spectrum, has been calculated for all incidence angles in the same manner illustrated in Examples 5.1.1 and 5.1.2. The results for from one to four glass covers are given in Figure 5.1.3. This figure is a recalculation of the results presented by Hottel and Woertz (1942).

The index of refraction of materials that have been considered for solar collector covers are given in Table 5.1.1. The values correspond to the solar spectrum and can be used to calculate the angular dependence of reflection losses similar to Figure 5.1.3.



**Figure 5.1.3** Transmittance of 1, 2, 3, and 4 nonabsorbing covers having an index of refraction of 1.526.

**Table 5.1.1** Average Refractive Index  $n$  in Solar Spectrum of Some Cover Materials

Cover Material	Average $n$
Glass	1.526
Polymethyl methacrylate	1.49
Polyvinylfluoride	1.45
Polyfluorinated ethylene propylene	1.34
Polytetrafluoroethylene	1.37
Polycarbonate	1.60

## 5.2 ABSORPTION BY GLAZING

The absorption of radiation in a partially transparent medium is described by Bouguer's law, which is based on the assumption that the absorbed radiation is proportional to the local intensity in the medium and the distance  $x$  the radiation has traveled in the medium:

$$dI = -IK \, dx \quad (5.2.1)$$

where  $K$  is the proportionality constant, the extinction coefficient, which is assumed to be a constant in the solar spectrum. Integrating along the actual pathlength in the medium (i.e., from zero to  $L/\cos \theta_2$ ) yields

$$\tau_a = \frac{I_{\text{transmitted}}}{I_{\text{incident}}} = \exp\left(-\frac{KL}{\cos \theta_2}\right) \quad (5.2.2)$$

where the subscript  $a$  is a reminder that only absorption losses have been considered. For glass, the value of  $K$  varies from approximately  $4 \, \text{m}^{-1}$  for "water white" glass (which appears white when viewed on the edge) to approximately  $32 \, \text{m}^{-1}$  for high iron oxide content (greenish cast of edge) glass.

## 5.3 OPTICAL PROPERTIES OF COVER SYSTEMS

The transmittance, reflectance, and absorptance of a single cover, allowing for both reflection and absorption losses, can be determined either by ray-tracing techniques similar to that used to derive Equation 5.1.7 or by the net radiation method as described by Siegel and Howell (2002). For the perpendicular component of polarization, the transmittance  $\tau_{\perp}$ , reflectance  $\rho_{\perp}$ , and absorptance  $\alpha_{\perp}$  of the cover are

$$\tau_{\perp} = \frac{\tau_a(1-r_{\perp})^2}{1-(r_{\perp}\tau_a)^2} = \tau_a \frac{1-r_{\perp}}{1+r_{\perp}} \left[ \frac{1-r_{\perp}^2}{1-(r_{\perp}\tau_a)^2} \right] \quad (5.3.1)$$

$$\rho_{\perp} = r_{\perp} + r_{\perp} \frac{\tau_a^2(1-r_{\perp})^2}{1-(r_{\perp}\tau_a)^2} = r_{\perp} (1 + \tau_a \tau_{\perp}) \quad (5.3.2)$$

$$\alpha_{\perp} = (1 - \tau_a) \left( \frac{1 - r_{\perp}}{1 - r_{\perp}\tau_a} \right) \quad (5.3.3)$$



Similar results are found for the parallel component of polarization. For incident unpolarized radiation, the optical properties are found by the average of the two components.

The equation for the transmittance of a collector cover can be simplified by noting that the last term in Equation 5.3.1 (and its equivalent for the parallel component of polarization) is nearly unity, since  $\tau_a$  is seldom less than 0.9 and  $r$  is on the order of 0.1 for practical collector covers. With this simplification and with Equation 5.1.8, the transmittance of a single cover becomes

$$\tau \cong \tau_a \tau_r \quad (5.3.4)$$

This is a satisfactory relationship for solar collectors with cover materials and angles of practical interest.

The absorptance of a solar collector cover can be approximated by letting the last term in Equation 5.3.3 be unity so that

$$\alpha \cong 1 - \tau_a \quad (5.3.5)$$

Although the neglected term in Equation 5.3.3 is larger than the neglected term in Equation 5.3.1, the absorptance is much smaller than the transmittances so that the overall accuracy of the two approximations is essentially the same.

The reflectance of a single cover is then found from  $\rho = 1 - \alpha - \tau$ , so that

$$\rho \cong \tau_a(1 - \tau_r) = \tau_a - \tau \quad (5.3.6)$$

The advantage of Equations 5.3.4 through 5.3.6 over Equations 5.3.1 through 5.3.3 is that polarization is accounted for in the approximate equations through the single term  $\tau_r$  rather than by the more complicated expressions for each individual optical property. Example 5.3.1 shows a solution for transmittance by the exact equations and also by the approximate equations.

### Example 5.3.1

Calculate the transmittance, reflectance, and absorptance of a single glass cover 2.3 mm thick at an angle of  $60^\circ$ . The extinction coefficient of the glass is  $32 \text{ m}^{-1}$ .

#### Solution

At an incidence angle of  $60^\circ$ , the extinction coefficient—optical pathlength product is

$$\frac{KL}{\cos \theta_2} = \frac{32 \times 0.0023}{\cos 34.58} = 0.0894$$

where 34.58 is the refraction angle calculated in Example 5.1.1. The transmittance  $\tau_a$  from Equation 5.2.2 is then

$$\tau_a = \exp(-0.0894) = 0.915$$

Using the results of Example 5.1.1 and Equation 5.3.1, the transmittance is found by averaging the transmittances for the parallel and perpendicular components of polarization,

$$\begin{aligned}\tau &= \frac{0.915}{2} \left[ \frac{1 - 0.185}{1 + 0.185} \left( \frac{1 - 0.185^2}{1 - (0.185 \times 0.915)^2} \right) \right. \\ &\quad \left. + \frac{1 - 0.001}{1 + 0.001} \left( \frac{1 - 0.001^2}{1 - (0.001 \times 0.915)^2} \right) \right] \\ &= 0.5(0.625 + 0.912) = 0.768\end{aligned}$$

The reflectance is found using Equation 5.3.2 for each component of polarization and averaging:

$$\begin{aligned}\rho &= 0.5[0.185(1 + 0.915 \times 0.625) + 0.001(1 + 0.915 \times 0.912)] \\ &= 0.5(0.291 + 0.002) = 0.147\end{aligned}$$

In a similar manner, the absorptance is found using Equation 5.3.3:

$$\begin{aligned}\alpha &= \frac{1 - 0.915}{2} \left( \frac{1 - 0.185}{1 - 0.185 \times 0.915} + \frac{1 - 0.001}{1 - 0.001 \times 0.915} \right) \\ &= \frac{0.085}{2} (0.981 + 1.000) = 0.085\end{aligned}$$

### *Alternate Solution*

The approximate equations can also be used to find these properties. From Equations 5.3.4 and 5.1.8 the transmittance is

$$\tau = \frac{0.915}{2} \left( \frac{1 - 0.185}{1 + 0.185} + \frac{1 - 0.001}{1 + 0.001} \right) = 0.771$$

From Equation 5.3.5, the absorptance is

$$\alpha = 1 - 0.915 = 0.085$$

and the reflectance is then

$$\rho = 1 - 0.771 - 0.085 = 0.144$$

Note that even though the incidence angle was large and poor-quality glass was used in this example so that the approximate equations tend to be less accurate, the approximate method and the exact method are essentially in agreement. ■

Although Equations 5.3.4 through 5.3.6 were derived for a single cover, they apply equally well to identical multiple covers. The quantity  $\tau_r$  should be evaluated from Equation 5.1.9 and the quantity  $\tau_a$  from Equation 5.2.2 with  $L$  equal to the total cover system thickness.

**Example 5.3.2**

Calculate the solar transmittance at incidence angles of zero and  $60^\circ$  for two glass covers each 2.3 mm thick. The extinction coefficient of the glass is  $16.1 \text{ m}^{-1}$ , and the refractive index is 1.526.

**Solution**

For one sheet at normal incidence,

$$KL = 16.1 \times 2.3/1000 = 0.0370$$

The transmittance  $\tau_a$  is given as

$$\tau_a(0) = \exp[-2(0.0370)] = 0.93$$

The transmittance accounting for reflection, from Example 5.1.2, is 0.85. The total transmittance is then found from Equation 5.3.4:

$$\tau(0) = \tau_r(0)\tau_a(0) = 0.85(0.93) = 0.79$$

From Example 5.1.1, when  $\theta_1 = 60^\circ$ ,  $\theta_2 = 34.57^\circ$ , and

$$\tau_a(60) = \exp\left(-\frac{2(0.0370)}{\cos 34.57}\right) = 0.91$$

and the total transmittance (with  $\tau_r = 0.76$  from Example 5.1.2) becomes

$$\tau(60) = \tau_r(60)\tau_a(60) = 0.76(0.91) = 0.69 \quad \blacksquare$$


Figure 5.3.1 gives curves of transmittance as a function of angle of incidence for systems of one to four identical covers of three different kinds of glass. These curves were calculated from Equation 5.3.4 and have been checked by experiments (Hottel and Woertz, 1942).

In a multicover system, the ray-tracing technique used to develop Equation 5.1.7 can be used to derive the appropriate equations. Whillier (1953) has generalized the ray-tracing method to any number or type of covers, and modern radiation heat transfer calculation methods have also been applied to these complicated situations (e.g., Edwards, 1977; Siegel and Howell, 2002). If the covers are identical, the approximate method illustrated in Example 5.3.2 is recommended, although the following equations can also be used.

For a two-cover system with covers not necessarily identical the following equations are for transmittance and reflectance, where subscript 1 refers to the top cover and subscript 2 to the inner cover:

$$\tau = \frac{1}{2} (\tau_\perp + \tau_\parallel) = \frac{1}{2} \left[ \left( \frac{\tau_1 \tau_2}{1 - \rho_1 \rho_2} \right)_\perp + \left( \frac{\tau_1 \tau_2}{1 - \rho_1 \rho_2} \right)_\parallel \right] \quad (5.3.7)$$

$$\rho = \frac{1}{2} (\rho_\perp + \rho_\parallel) = \frac{1}{2} \left[ \left( \rho_1 + \frac{\tau \rho_2 \tau_1}{\tau_2} \right)_\perp + \left( \rho_1 + \frac{\tau \rho_2 \tau_1}{\tau_2} \right)_\parallel \right] \quad (5.3.8)$$



**Figure 5.3.1** Transmittance (considering absorption and reflection) of one, two, three, and four covers for three types of glass.

The reflectance of a cover system depends upon which cover is on top. In these equations the subscripts  $\perp$  and  $\parallel$  apply to all terms in the corresponding parentheses.

### Example 5.3.3

Calculate the optical properties of a two-cover solar collector at an angle of  $60^\circ$ . The outer cover is glass with  $K = 16.1 \text{ m}^{-1}$  and thickness of 2.3 mm. The inner cover is

polyvinyl fluoride with refractive index equal to 1.45. The plastic film is thin enough so that absorption within the plastic can be neglected.

### Solution

The optical properties of the glass and plastic covers alone, as calculated from Equations 5.3.1 through 5.3.3, are

Glass:	$\tau_{\parallel} = 0.953,$	$\tau_{\perp} = 0.655$
	$\rho_{\parallel} = 0.002,$	$\rho_{\perp} = 0.302$
	$\alpha_{\parallel} = 0.044,$	$\alpha_{\perp} = 0.044$
Plastic:	$\tau_{\parallel} = 0.995,$	$\tau_{\perp} = 0.726$
	$\rho_{\parallel} = 0.005,$	$\rho_{\perp} = 0.274$
	$\alpha_{\parallel} = 0.000,$	$\alpha_{\perp} = 0.000$

Equations 5.3.4 through 5.3.6 could have been used with each component of polarization to simplify the calculation of the preceding properties.

The transmittance of the combination is found from Equation 5.3.7:

$$\begin{aligned}\tau &= \frac{1}{2} \left( \frac{0.655 \times 0.726}{1 - 0.302 \times 0.274} + \frac{0.953 \times 0.995}{1 - 0.002 \times 0.005} \right) \\ &= 0.5(0.518 + 0.948) = 0.733\end{aligned}$$

The reflectance, with the glass first, is found from Equation 5.3.8:

$$\begin{aligned}\rho &= \frac{1}{2} \left( 0.302 + \frac{0.518 \times 0.274 \times 0.655}{0.726} + 0.002 + \frac{0.948 \times 0.005 \times 0.953}{0.995} \right) \\ &= 0.5(0.430 + 0.007) = 0.219\end{aligned}$$

The absorptance is then

$$\alpha = 1 - 0.219 - 0.733 = 0.048 \quad \blacksquare$$

Equations 5.3.7 and 5.3.8 can be used to calculate the transmittance of any number of covers by repeated application. If subscript 1 refers to the properties of a cover system and subscript 2 to the properties of an additional cover placed under the stack, then these equations yield the appropriate transmittance and reflectance of the new system. The reflectance  $\rho_1$  in Equation 5.3.7 is the reflectance of the original cover system from the bottom side. If any of the covers exhibit strong wavelength-dependent properties, integration over the wavelength spectrum is necessary (see Section 5.6).


## 5.4 TRANSMITTANCE FOR DIFFUSE RADIATION

The preceding analysis applies only to the beam component of solar radiation. Radiation incident on a collector also consists of scattered solar radiation from the sky and possibly reflected solar radiation from the ground. In principle, the amount of this radiation that passes through a cover system can be calculated by integrating the transmitted radiation over all angles. However, the angular distribution of this radiation is generally unknown.

For incident isotropic radiation (i.e., independent of angle), the integration can be performed. The presentation of the results can be simplified by defining an equivalent angle for beam radiation that gives the same transmittance as for diffuse radiation. For a wide range of conditions encountered in solar collector applications, this equivalent angle is essentially  $60^\circ$ . In other words, a cover has the same transmittance for isotropic diffuse radiation as it does for beam radiation incident at an angle of  $60^\circ$ .

Circumsolar diffuse radiation can be considered as having the same angle of incidence as the beam radiation. Diffuse radiation from the horizon is usually a small contribution to the total and as an approximation can be taken as having the same angle of incidence as the isotropic diffuse radiation.

Solar collectors are usually oriented so that they “see” both the sky and the ground. If the diffuse radiation from the sky and the radiation reflected from the ground are both isotropic, then the transmittance of the glazing systems can be found by integrating the beam transmittance over the appropriate incidence angles. This integration has been done by Brandemuehl and Beckman (1980); the results are presented in Figure 5.4.1 in terms



**Figure 5.4.1** Effective incidence angle of isotropic diffuse radiation and isotropic ground-reflected radiation on sloped surfaces. From Brandemuehl and Beckman (1980).

of a single effective incidence angle. Thus all of the diffuse radiation can be treated as having a single equivalent angle of incidence, and all of the ground-reflected radiation can be considered as having another equivalent angle of incidence. The shaded region includes a wide range of glazings. The upper curve is for a one-cover polyfluorinated ethylene propylene glazing with no internal absorption, whereas the lower curve represents a two-cover glass glazing with extinction length  $KL = 0.0524$ . All one- and two-cover systems with indices of refraction between 1.34 and 1.526 and extinction lengths less than 0.0524 lie in the shaded region.

The dashed lines shown in Figure 5.4.1 are given for ground-reflected radiation by

$$\theta_{e,g} = 90 - 0.5788\beta + 0.002693\beta^2 \quad (5.4.1)$$


and for diffuse radiation by

$$\theta_{e,d} = 59.7 - 0.1388\beta + 0.001497\beta^2 \quad (5.4.2)$$

## 5.5 TRANSMITTANCE-ABSORPTANCE PRODUCT

To use the analysis of the next chapter, it is necessary to evaluate the transmittance-absorptance product  $(\tau\alpha)$ .<sup>1</sup> Of the radiation passing through the cover system and incident on the plate, some is reflected back to the cover system. However, all this radiation is not lost since some of it is, in turn, reflected back to the plate.

The situation is illustrated in Figure 5.5.1, where  $\tau$  is the transmittance of the cover system at the desired angle and  $\alpha$  is the angular absorptance of the absorber plate. Of the incident energy,  $\tau\alpha$  is absorbed by the absorber plate and  $(1 - \alpha)\tau$  is reflected back to the cover system. The reflection from the absorber plate is assumed to be diffuse (and unpolarized) so the fraction  $(1 - \alpha)\tau$  that strikes the cover system is diffuse radiation and  $(1 - \alpha)\tau\rho_d$  is reflected back to the absorber plate. The quantity  $\rho_d$  refers to the reflectance of the cover system for diffuse radiation incident from the bottom side and can be estimated from Equation 5.3.6 as the difference between  $\tau_a$  and  $\tau$  at an angle of  $60^\circ$ .<sup>2</sup>



**Figure 5.5.1** Absorption of solar radiation by absorber plate under a cover system.

<sup>1</sup>The transmittance-absorptance product  $(\tau\alpha)$  should be thought of as a property of a cover-absorber combination rather than the product of two properties.

<sup>2</sup>For single covers of the three kinds of glass of Figure 5.3.1,  $\rho_d$  at  $60^\circ$  is 0.16 (for  $KL = 0.0125$ ), 0.15 (for  $KL = 0.0370$ ), and 0.15 (for  $KL = 0.0524$ ). For two covers, the corresponding values are 0.23, 0.22, and 0.21.

If the cover system consists of two (or more) covers of dissimilar materials,  $\rho_d$  will be different (slightly) from the diffuse reflectance of the incident solar radiation (see Equation 5.3.8). The multiple reflection of diffuse radiation continues so that the fraction of the incident energy ultimately absorbed is<sup>3</sup>

$$(\tau\alpha) = \tau\alpha \sum_{n=0}^{\infty} [(1 - \alpha)\rho_d]^n = \frac{\tau\alpha}{1 - (1 - \alpha)\rho_d} \quad (5.5.1)$$

### Example 5.5.1

For a two-cover collector using glass with  $KL = 0.0370$  per plate and an absorber plate with  $\alpha = 0.90$  (independent of direction), find the transmittance-absorptance product at an angle of  $50^\circ$ .

#### Solution

From Figure 5.3.1,  $\tau$  at  $50^\circ$  is 0.75 and  $\tau$  at  $60^\circ$  (the effective angle of incidence of radiation reflected back to the cover) is 0.69. From Equation 5.2.2 with  $\theta_2 = 34.58^\circ$ ,  $\tau_a = 0.91$ . From Equation 5.3.6,  $\rho_d = 0.91 - 0.69 = 0.22$ . From Equation 5.5.1

$$(\tau\alpha) = \frac{0.75 \times 0.90}{1 - (1 - 0.90) 0.22} = 0.69$$

Note that it is also possible to estimate  $\rho_d = 1 - \tau_r$ , where  $\tau_r$  can be estimated from Figure 5.1.3 at  $60^\circ$ . For two covers,  $\tau_r = 0.77$ , so  $\rho_d = 0.23$ . ■

The value of  $(\tau\alpha)$  in this example is very nearly equal to 1.01 times the product of  $\tau$  times  $\alpha$ . This is a reasonable approximation for most practical solar collectors. Thus,

$$(\tau\alpha) \cong 1.01\tau\alpha \quad (5.5.2)$$


can be used as an estimate of  $(\tau\alpha)$  in place of Equation 5.5.1.

## 5.6 ANGULAR DEPENDENCE OF $(\tau\alpha)$

The dependence of absorptance and transmittance on the angle of incidence of the incident radiation has been shown in Sections 4.11 and 5.1 to 5.4. For ease in determining  $(\tau\alpha)$  as a function of angle of incidence  $\theta$ , Klein (1979) developed a relationship between  $(\tau\alpha)/(\tau\alpha)_n$  and  $\theta$  based on the angular dependence of  $\alpha$  shown in Figure 4.11.1 and on the angular dependence of  $\tau$  for glass covers with  $KL = 0.04$ . The result is not sensitive to  $KL$  and can be applied to all covers having a refractive index close to that of glass. Klein's curves are shown in Figure 5.6.1. The results obtained by using this figure are essentially the same as those obtained by independently finding the angular dependence of  $\tau$  and  $\alpha$  as illustrated in examples to follow in this chapter.

<sup>3</sup>The absorptance  $\alpha$  of the absorber plate for the reflected radiation should be the absorptance for diffuse radiation. Also, the reflected radiation may not all be diffuse, and it may be partially polarized. However, the resulting errors should be negligible in that the difference between  $\tau\alpha$  and  $(\tau\alpha)$  is small.






**Figure 5.6.1** Typical  $(\tau\alpha)/(\tau\alpha)_n$  curves for one to four covers. Adapted from Klein (1979).

## 5.7 SPECTRAL DEPENDENCE OF TRANSMITTANCE

Most transparent media transmit selectively; that is, transmittance is a function of wavelength of the incident radiation. Glass, the material most commonly used as a cover material in solar collectors, may absorb little of the solar energy spectrum if its  $\text{Fe}_2\text{O}_3$  content is low. If its  $\text{Fe}_2\text{O}_3$  content is high, it will absorb in the infrared portion of the solar spectrum. The transmittance (including reflection losses) of several glasses of varying iron content is shown in Figure 5.7.1. These show clearly that “water white” (low-iron) glass has the best transmission; glass with high  $\text{Fe}_2\text{O}_3$  content has a greenish appearance and is a relatively poor transmitter. Note that the transmission is not a strong function of wavelength in the solar spectrum except for the “heat-absorbing” glass. Glass becomes substantially opaque at wavelengths longer than approximately  $3\ \mu\text{m}$  and can be considered as opaque to long-wave radiation.

Some collector cover materials may have transmittances that are more wavelength dependent than low-iron glass, and it may be necessary to obtain their transmittance for monochromatic radiation and then integrate over the entire spectrum. If there is no significant angular dependence of monochromatic transmittance, the transmittance for incident radiation of a given spectral distribution is calculated by an equation analogous to Equation 4.6.4:

$$\tau = \sum_{j=1}^n \tau_{\lambda,j} \Delta f_i \quad (5.7.1)$$



**Figure 5.7.1** Spectral transmittance of 6-mm-thick glass with various iron oxide contents for incident radiation at normal incidence. From Dietz (1954).

If there is an angular dependence of  $\tau_\lambda$ , the total transmittance at angle  $\theta$  can be written as

$$\tau(\theta) = \frac{\int_0^\infty \tau_\lambda(\theta) I_{\lambda i}(\theta) d\lambda}{\int_0^\infty I_{\lambda i}(\theta) d\lambda} \quad (5.7.2)$$

where  $\tau_\lambda(\theta)$  is calculated by the equations of the preceding section using monochromatic values of the index of refraction and absorption coefficient and  $I_{\lambda i}(\theta)$  is the incident monochromatic intensity arriving at the cover system from angle  $\theta$ .

### Example 5.7.1

For the glass of Figure 5.7.1, having an iron oxide content of 0.50%, estimate the transmittance at normal incidence for terrestrial solar radiation.

#### Solution

Use Table 2.6.1 to represent the spectral distribution of the incident radiation and Equation 5.7.1 to calculate  $\tau$ . Dividing the spectrum into 10 equal increments, the increments, the wavelength at the energy midpoints of the increments, and  $\tau_\lambda$  at the midpoints of the increments are shown in the table below. The sum of the third and sixth

columns is 3.89. Since 10 equal increments were chosen, the transmittance is the average of the  $\tau_\lambda$ . Thus the transmittance of the glass at normal incidence is 0.39.

Increment	$\lambda_{\text{mid}}, \mu\text{m}$	$\tau_{\lambda, \text{mid}}$	Increment	$\lambda_{\text{mid}}, \mu\text{m}$	$\tau_{\lambda, \text{mid}}$
0.0–0.1	0.416	0.76	0.5–0.6	0.786	0.19
0.1–0.2	0.492	0.80	0.6–0.7	0.885	0.11
0.2–0.3	0.559	0.74	0.7–0.8	1.140	0.05
0.3–0.4	0.627	0.60	0.8–0.9	1.257	0.07
0.4–0.5	0.700	0.38	0.9–1.0	1.750	0.19

■

If the absorptance of solar radiation by an absorber plate is independent of wavelength, then Equation 5.5.1 can be used to find the transmittance-absorptance product with the transmittance as calculated from Equation 5.7.1 or 5.7.2. However, if both the solar transmittance of the cover system and the solar absorptance of the absorber plate are functions of wavelength and angle of incidence, the fraction absorbed by an absorber plate is given by


$$\tau\alpha(\theta) = \frac{\int_0^\infty \tau_\lambda(\theta) \alpha_\lambda(\theta) I_{\lambda i}(\theta) d\lambda}{\int_0^\infty I_{\lambda i}(\theta) d\lambda} \quad (5.7.3)$$

To account for multiple reflections in a manner analogous to Equation 5.5.1, it would be necessary to evaluate the spectral distribution of each reflection and integrate over all wavelengths. It is unlikely that such a calculation would ever be necessary for solar collector systems, since the error involved by directly using Equation 5.7.3 with Equation 5.5.1 would be small if  $\alpha$  is near unity.

In a multicover system in which the covers have significant wavelength-dependent properties, the spectral distribution of the solar radiation changes as it passes through each cover. Consequently, if all covers are identical, the transmittance of individual covers increases in the direction of propagation of the incoming radiation. If the covers are not all identical, the transmittance of a particular cover may be greater or less than other similar covers in the system. Equations 5.7.1 to 5.7.3 account for this phenomenon. At any wavelength  $\lambda$ , the transmittance is the product of the monochromatic transmittances of the individual covers. Thus for  $N$  covers

$$\tau\alpha(\theta) = \frac{\int_0^\infty \tau_{\lambda,1}(\theta) \tau_{\lambda,2}(\theta) \cdots \tau_{\lambda,N}(\theta) \alpha_\lambda(\theta) I_{\lambda i}(\theta) d\lambda}{\int_0^\infty I_{\lambda i}(\theta) d\lambda} \quad (5.7.4)$$

If a cover system has one cover with wavelength-independent properties (e.g., glass) and one cover with wavelength-dependent properties (e.g., some plastics), then a simplified procedure can be used. The transmittance and reflectance of each cover can be obtained



**Figure 5.7.2** Infrared spectral transmittance of Tedlar film. Courtesy of du Pont.

separately, and the combined system transmittance and reflectance can be obtained from Equations 5.3.7 and 5.3.8.


For most plastics, the transmittance will also be significant in the infrared spectrum at  $\lambda > 3 \mu\text{m}$ . Figure 5.7.2 shows the transmittance curve for a polyvinyl fluoride (Tedlar) film for wavelengths longer than  $2.5 \mu\text{m}$ . Whillier (1963) calculated the transmittance of a similar film using Equation 5.7.2. The incident radiation  $I_{\lambda i}$  was for radiation from blackbody sources at temperatures from 0 to  $200^\circ\text{C}$ . He found that transmittance was 0.32 for radiation from the blackbody source at  $0^\circ\text{C}$ , 0.29 for the source at  $100^\circ\text{C}$ , and 0.32 for the source at  $200^\circ\text{C}$ .

## 5.8 EFFECTS OF SURFACE LAYERS ON TRANSMITTANCE

If a film of low refractive index is deposited at an optical thickness of  $\lambda/4$  onto a transparent slab, radiation of wavelength  $\lambda$  reflected from the upper and lower surfaces of the film will have a phase difference of  $\pi$  and will cancel. The reflectance will be decreased, and the transmittance will be increased relative to the uncoated material. This is the principal type of coating used on camera lenses, binoculars, and other expensive optical equipment.

Inexpensive and durable processes have been developed for treating glass to reduce its reflectance by the addition of films having a refractive index between that of air and the transparent medium (e.g., Thomsen, 1951). The solar reflectance of a single pane of untreated glass is approximately 8%. Surface treatment, by dipping glass in a silica-saturated fluosilic acid solution, can reduce the reflection losses to 2%, and a double-layer coating can, as shown by Mar et al. (1975), reduce reflection losses to less than 1%. Such an increase in solar transmittance can make a very significant improvement in the thermal performance of flat-plate collectors. Figure 5.8.1 shows typical monochromatic reflectance data before and after etching. Note that unlike unetched glass, it is necessary to integrate monochromatic reflectance over the solar spectrum to obtain the reflectance for solar radiation.

Experimental values for the angular dependence of solar transmission for unetched and etched glass are given in Table 5.8.1. Not only does the etched sample exhibit higher transmittance than the unetched sample at all incidence angles, but also the transmittance degrades less at high incidence angles.



**Figure 5.8.1** Monochromatic reflectance of one sheet of etched and unetched glass. From Mar et al. (1975).

**Table 5.8.1** Solar Transmittance for Etched and Unetched Glass as Function of Incidence Angle<sup>a</sup>

Type of Glass	Transmittance by Incidence Angle						
	0°	20°	40°	50°	60°	70°	80°
Etched	0.941	0.947	0.945	0.938	0.916	0.808	0.562
Unetched	0.888	0.894	0.903	0.886	0.854	0.736	0.468

<sup>a</sup>From Mar et al. (1975).

Glass is treated by other means to decrease its emittance for use as transparent insulation for glazing applications. These treatments also change the transmittance, in many cases decreasing it substantially.

## 5.9 ABSORBED SOLAR RADIATION

The prediction of collector performance requires information on the solar energy absorbed by the collector absorber plate. The solar energy incident on a tilted collector can be found by the methods of Chapter 2. This incident radiation has three different spatial distributions: beam radiation, diffuse radiation, and ground-reflected radiation, and each must be treated separately. The details of the calculation depend on which diffuse-sky model (Sections 2.14 to 2.16) is used. Using the isotropic diffuse concept on an hourly basis, Equation 2.15.1 can be modified to give the absorbed radiation  $S$  by multiplying each term

by the appropriate transmittance-absorptance product:

$$S = I_b R_b (\tau\alpha)_b + I_d (\tau\alpha)_d \left( \frac{1 + \cos \beta}{2} \right) + \rho_g I (\tau\alpha)_g \left( \frac{1 - \cos \beta}{2} \right) \quad (5.9.1)$$

where  $(1 + \cos \beta)/2$  and  $(1 - \cos \beta)/2$  are the view factors from the collector to the sky and from the collector to the ground, respectively. The subscripts  $b$ ,  $d$ , and  $g$  represent beam, diffuse, and ground. For a given collector tilt, Figure 5.4.1 gives the effective angle of incidence of the diffuse and ground-reflected radiation, and Figures 4.11.1 and 5.4 can be used to find the proper absorptance and transmittance values. Equation 5.5.1 or 5.5.2 can then be used to find  $(\tau\alpha)_d$  and  $(\tau\alpha)_g$ . The angle  $\theta$  for the beam radiation, which is needed in evaluating  $R_b$ , is used to find  $(\tau\alpha)_b$ . Alternatively,  $(\tau\alpha)_n$  can be found from the properties of the cover and absorber and Figure 5.6.1 can be used at the appropriate angles of incidence for each radiation stream to determine the three transmittance-absorptance products.

The results of the preceding sections are summarized in the following example in which the solar radiation absorbed by a collector is calculated.

### Example 5.9.1

For an hour 11 to 12 AM on a clear winter day,  $I = 1.79 \text{ MJ/m}^2$ ,  $I_b = 1.38 \text{ MJ/m}^2$ , and  $I_d = 0.41 \text{ MJ/m}^2$ . Ground reflectance is 0.6. For this hour,  $\theta$  for the beam radiation is  $7^\circ$  and  $R_b = 2.11$ . A collector with one glass cover is sloped  $60^\circ$  to the south. The glass has  $KL = 0.0370$ , and the absorptance of the plate at normal incidence,  $\alpha_n$ , is 0.93. Using the isotropic diffuse model (Equation 5.9.1), calculate the absorbed radiation per unit area of absorber.

### Solution

Two approaches to the solution are possible. The angular dependence of  $\tau$  and  $\alpha$  can be individually determined or the angular dependence of  $(\tau\alpha)$  can be determined.

In the first method, use Figure 4.11.1 to get angular dependence of  $\alpha$  and Figure 5.3.1 to get angular dependence of  $\tau$ . For the  $60^\circ$  slope, from Figure 5.4.1, the effective angle of incidence of the diffuse radiation is  $57^\circ$  and that of the ground-reflected radiation is  $65^\circ$ :

For the beam radiation, at  $\theta = 7^\circ$ :

From Figure 4.11.1,  $\alpha/\alpha_n = 0.99$

From Figure 5.3.1,  $\tau = 0.88$

$$(\tau\alpha)_b = 1.01 \times 0.88 \times 0.99 \times 0.93 = 0.82$$

For the (isotropic) diffuse radiation, at  $\theta = 57^\circ$ :

From Figure 4.11.1,  $\alpha/\alpha_n = 0.94$

From Figure 5.3.1,  $\tau = 0.83$

$$(\tau\alpha)_d = 1.01 \times 0.83 \times 0.94 \times 0.93 = 0.73$$

For the ground-reflected radiation, at  $\theta = 65^\circ$ :

From Figure 4.11.1,  $\alpha/\alpha_n = 0.88$

From Figure 5.3.1,  $\tau = 0.76$

$$(\tau\alpha)_g = 1.01 \times 0.76 \times 0.88 \times 0.93 = 0.63$$

Equation 5.9.1 is now used to calculate  $S$ :

$$\begin{aligned} S &= 1.38 \times 2.11 \times 0.82 + 0.41 \times 0.73 \left( \frac{1 + \cos 60}{2} \right) \\ &\quad + 1.79 \times 0.6 \times 0.63 \left( \frac{1 - \cos 60}{2} \right) \\ &= 2.39 + 0.22 + 0.17 = 2.78 \text{ MJ/m}^2 \end{aligned}$$

In the second method, use Figure 5.6.1 to get the angular dependence of  $(\tau\alpha)/(\tau\alpha)_n$ . The effective angles of incidence of the diffuse and ground-reflected radiation are  $57^\circ$  and  $65^\circ$ , as before. From Figure 5.3.1,  $\tau_n = 0.88$ ,  $\alpha_n = 0.93$  (given), so

$$(\tau\alpha)_n = 1.01 \times 0.88 \times 0.93 = 0.83$$

From Figure 5.6.1 with the beam radiation at  $\theta = 7^\circ$ ,  $(\tau\alpha)/(\tau\alpha)_n = 0.99$  and

$$(\tau\alpha)_b = 0.83 \times 0.99 = 0.82$$

From Figure 5.6.1 with the diffuse radiation at  $\theta = 57^\circ$ ,  $(\tau\alpha)/(\tau\alpha)_n = 0.87$  and

$$(\tau\alpha)_d = 0.83 \times 0.87 = 0.72$$

From Figure 5.6.1 with the ground-reflected radiation at  $\theta = 65^\circ$ ,  $(\tau\alpha)/(\tau\alpha)_n = 0.76$  and

$$(\tau\alpha)_g = 0.83 \times 0.76 = 0.63$$

These are essentially identical to the results of the first solution. ■

The calculation of absorbed radiation using the HDKR model of diffuse radiation (Equation 2.16.7) is similar to that based on the isotropic model except that the circumsolar diffuse is treated as an increment to the beam radiation, horizon brightening is considered, and the diffuse component is correspondingly reduced. It is assumed that the angle of incidence of the circumsolar diffuse is the same as that of the beam and that the angle of incidence of the diffuse from the horizon is the same as the isotropic. The energy absorbed by the absorbing surface is given by

$$\begin{aligned} S &= (I_b + I_d A_i) R_b (\tau\alpha)_b + I_d (1 - A_i) (\tau\alpha)_d \left( \frac{1 + \cos \beta}{2} \right) \left[ 1 + f \sin^3 \left( \frac{\beta}{2} \right) \right] \\ &\quad + I \rho_g (\tau\alpha)_g \left( \frac{1 - \cos \beta}{2} \right) \end{aligned} \quad (5.9.2)$$

**Example 5.9.2**

Redo Example 5.9.1 using the HDKR model. For this hour  $I_o = 2.40 \text{ MJ/m}^2$ .

**Solution**

The calculations of the transmittance-absorptance products are the same as in Example 5.9.1. The anisotropy index is calculated from Equation 2.16.3:

$$A_i = \frac{1.38}{2.40} = 0.58$$

Using Equation 2.16.6,

$$f = \sqrt{\frac{I_b}{I}} = \sqrt{\frac{1.38}{1.79}} = 0.88$$

Then using Equation 5.9.2,  $S$  can be calculated:

$$\begin{aligned} S &= (1.38 + 0.41 \times 0.58) \times 2.11 \times 0.82 \\ &\quad + 0.41 \times (1 - 0.58) \left( \frac{1 + \cos 60}{2} \right) \left[ 1 + 0.88 \sin^3 \left( \frac{60}{2} \right) \right] \times 0.73 \\ &\quad + 1.79 \times 0.6 \left( \frac{1 - \cos 60}{2} \right) \times 0.63 \\ &= 2.80 + 0.10 + 0.17 = 3.07 \text{ MJ/m}^2 \end{aligned} \quad \blacksquare$$

Under the clear-sky conditions of these two examples, the HDKR sky model leads to substantially higher estimates of absorbed radiation, as much of the diffuse radiation is taken as circumsolar and added to the beam radiation.

In these two examples, each radiation stream on the collector is treated separately. At times it is convenient to define an average transmittance-absorptance product as the ratio of the absorbed solar radiation  $S$  to the incident solar radiation  $I_T$ . Thus,

$$S = (\tau\alpha)_{\text{av}} I_T \quad (5.9.3)$$

This is convenient when direct measurements are available for  $I_T$ . In Example 5.9.2,  $S$ , the solar radiation absorbed by the collector for the hour 11 to 12, is  $3.07 \text{ MJ/m}^2$ , and  $I_T = 3.81 \text{ MJ/m}^2$ . The average transmittance-absorptance product for this hour is then 0.80, which is slightly less than the value of  $(\tau\alpha)_b = 0.82$ . When the beam fraction is high, as in these examples,  $(\tau\alpha)_{\text{av}}$  is close to  $(\tau\alpha)_b$ . When the diffuse fraction is high, using the value of  $(\tau\alpha)_d$  for  $(\tau\alpha)_{\text{av}}$  may be a reasonable assumption. As will be seen in Chapter 6, useful energy gain by the collector is highest when beam radiation is high, and as an approximation when  $I_T$  data are available, the following can be assumed:

$$(\tau\alpha)_{\text{av}} \cong 0.96(\tau\alpha)_b \quad (5.9.4)$$

(Comparisons of the measured and calculated operation of solar processes are often made, with the incident solar radiation measured on the plane of the collector,  $I_T$ . Equation 5.9.4



provides a convenient way to estimate the absorbed radiation  $S$  under these circumstances. This  $S$  is then used in the performance calculations.)

As will be seen in Sections 6.16 and 6.17, the concept of an **incidence angle modifier** (called variously the IAM or  $K_{\tau\alpha}$ ) is useful in describing collector test data. Here,  $K_{\tau\alpha}$  is defined for each solar radiation stream (i.e., beam, sky, and ground-reflected solar radiation) as the ratio of the transmittance-absorptance product at some angle to the transmittance-absorptance product at normal incidence.

## 5.10 MONTHLY AVERAGE ABSORBED RADIATION

Methods for the evaluation of long-term solar system performance<sup>4</sup> require that the average radiation absorbed by a collector be evaluated for monthly periods. The solar transmittance and absorptance are both functions of the angle at which solar radiation is incident on the collector. Example 5.9.1 illustrated how to calculate the absorbed solar radiation for an hour. This calculation can be repeated for each hour of each day of the month, from which the monthly average absorbed solar radiation can be found. Klein (1979) calculated the monthly average absorbed solar radiation in this manner using many years of data. He defined a monthly average transmittance-absorptance product<sup>5</sup> which when multiplied by the monthly average radiation incident on a collector yields the monthly average absorbed radiation  $\bar{S}$ :

$$(\overline{\tau\alpha}) = \frac{\bar{S}}{\bar{H}_T} = \frac{\bar{S}}{\bar{H} \bar{R}} \quad (5.10.1)$$

The following methods, analogous to the hourly evaluations of  $S$ , can be used to find  $\bar{S}$ .

Using the isotropic diffuse assumption, Equation 2.19.1 becomes

$$\bar{S} = \bar{H}_b \bar{R}_b (\overline{\tau\alpha})_b + \bar{H}_d (\overline{\tau\alpha})_d \left( \frac{1 + \cos \beta}{2} \right) + \bar{H} \rho_g (\overline{\tau\alpha})_g \left( \frac{1 - \cos \beta}{2} \right) \quad (5.10.2)$$


For the diffuse and ground-reflected terms,  $(\overline{\tau\alpha})_d$  and  $(\overline{\tau\alpha})_g$  can be evaluated using the effective incidence angles given in Figure 5.4.1. These are functions of the properties of the cover and absorber and  $\beta$ , the collector slope, and so do not change with time for collectors mounted at fixed  $\beta$ . The hourly and monthly values are thus the same, and they can be written with or without the overbars.

For the monthly average beam radiation, Klein (1979) has worked out the monthly average (equivalent) beam incident angle  $\bar{\theta}_b$  as a function of collector slope, month, latitude, and azimuth angle. These are shown in Figures 5.10.1(a–f). These values of  $\bar{\theta}_b$  were evaluated using the angular distribution of  $(\tau\alpha)/(\tau\alpha)_n$  shown in Figure 5.6.1.

The Klein and Theilacker equations can also be used to calculate  $\bar{S}$ , the product  $(\overline{\tau\alpha})\bar{R}\bar{H}$ . Each of the  $\bar{R}$  equations 2.20.4a and 2.20.5a includes three terms: the first

<sup>4</sup>See Chapters 20 to 22.

<sup>5</sup>This could be designated as  $(\overline{\tau\alpha})_{av}$ , as it is a time-weighted and energy-weighted average. Common usage is to designate it as  $(\overline{\tau\alpha})$ .



**Figure 5.10.1** Monthly average beam incidence angle for various surface locations and orientations. For southern hemisphere interchange months as shown in Figure 1.8.2. From Klein (1979).

is multiplied by  $(\overline{\tau\alpha})_b$ , the second by  $(\overline{\tau\alpha})_d$ , and the third by  $(\overline{\tau\alpha})_g$ , as was shown in Equation 5.10.2. For surfaces with surface azimuth angles other than zero (or  $180^\circ$  in the southern hemisphere), the use of the modified Equation 2.20.5a is recommended.

Calculation of  $\bar{S}$  is illustrated in the following example.

### Example 5.10.1

Estimate  $\bar{S}$  for a south-facing vertical collector-storage wall at Springfield, Illinois,  $40^\circ$  N latitude. The wall consists of double glazing with a black-finished absorbing surface behind the glass with  $\alpha$  at normal incidence of 0.90. The monthly average daily radiation on a horizontal surface  $\bar{H}$ , in megajoules per square meter, is shown in the table that follows. The ground reflectance is assumed to be 0.3 for all months. The angular dependence of  $(\tau\alpha)$  for the two-cover glazing is as shown in Figure 5.6.1. The glass has  $KL = 0.0125$ . Calculate the monthly radiation on the wall  $\bar{H}_T$ , the monthly absorbed radiation  $\bar{S}$ , and the monthly average  $(\overline{\tau\alpha})$ .




Figure 5.10.1 (Continued)

**Solution**

The calculations are shown in detail for January, and the results for all months are shown in the table.

For these two covers, from Figure 5.3.1 at normal incidence, the transmittance is 0.83. With the absorber normal-incidence absorptance of 0.90,  $(\bar{\tau}\alpha)_n = 1.01 \times 0.83 \times 0.90 = 0.754$ . For the vertical collector the effective incidence angle of both the diffuse and the ground-reflected radiation is  $59^\circ$  from Figure 5.4.1. From Figure 5.6.1 at  $59^\circ$ ,  $(\bar{\tau}\alpha)/(\tau\alpha)_n = 0.83$  so that  $(\bar{\tau}\alpha)_d = (\bar{\tau}\alpha)_g = 0.83 \times 0.754 = 0.626$ . These values apply to all months.

For January, from Figure 5.10.1(b), at  $40^\circ$  latitude and  $90^\circ$  slope,  $\bar{\theta}_b = 41^\circ$ . From Figure 5.6.1,  $(\bar{\tau}\alpha)_b/(\tau\alpha)_n = 0.96$  for the two-cover system. Thus  $(\bar{\tau}\alpha)_b = 0.96 \times 0.754 = 0.724$ .

For January,  $\bar{H}_o = 15.21 \text{ MJ/m}^2$ , so  $\bar{K}_T = 6.63/15.21 = 0.436$ . For the mean day of the month, from Table 1.6.1,  $\delta = -20.9^\circ$ . Thus

$$\omega_s = \cos^{-1}[-\tan(-20.9) \tan 40] = 71.3^\circ$$




Figure 5.10.1 (Continued)

Equation 2.12.1 is used to calculate the diffuse fraction. For January this gives  $\bar{H}_d/\bar{H} = 0.458$ . Then

$$\bar{H}_d = 6.63 \times 0.458 = 3.04 \text{ MJ/m}^2$$

and

$$\bar{H}_b = 3.59 \text{ MJ/m}^2$$

From Equation 2.19.3,  $\bar{R}_b = 2.32$ .

We can now calculate  $\bar{H}_T$  with Equation 2.19.1 based on the isotropic diffuse assumption:

$$\begin{aligned} \bar{H}_T &= 3.59 \times 2.32 + 3.04 \left( \frac{1 + \cos 90}{2} \right) + 6.63 \times 0.3 \left( \frac{1 - \cos 90}{2} \right) \\ &= 8.33 + 1.52 + 0.99 = 10.84 \text{ MJ/m}^2 \end{aligned}$$

With the transmittance-absorptance products determined above, again using the isotropic assumption (Equation 5.10.2),

$$\begin{aligned}\bar{S} &= 3.59 \times 2.32 \times 0.724 + 3.04 \times 0.626 \left( \frac{1 + \cos 90}{2} \right) \\ &\quad + 6.63 \times 0.3 \times 0.626 \left( \frac{1 - \cos 90}{2} \right) \\ &= 6.03 + 0.95 + 0.62 = 7.60 \text{ MJ/m}^2\end{aligned}$$

The average transmittance-absorptance product for the month is then


$$(\bar{\tau}\alpha) = \frac{\bar{S}}{\bar{H}_T} = \frac{7.60}{10.84} = 0.70$$

The monthly results are as follows:

Month	$\bar{H}$	$\bar{K}_T$	$\bar{H}_T$	$(\bar{\tau}\alpha)_b$	Absorbed Radiation, MJ/m <sup>2</sup>			$\bar{S}$	$(\bar{\tau}\alpha)$
					Beam	Diffuse	Gr. Refl.		
Jan.	6.63	0.44	10.84	0.72	6.03	0.95	0.62	7.60	0.70
Feb.	9.77	0.48	12.59	0.69	6.28	1.27	0.92	8.47	0.67
Mar.	12.97	0.47	11.65	0.63	4.25	1.85	1.22	7.32	0.63
Apr.	17.20	0.50	11.03	0.51	2.41	2.33	1.62	6.36	0.58
May	21.17	0.53	10.59	0.38	1.22	2.64	1.99	5.84	0.55
June	23.80	0.57	10.52	0.26	0.68	2.72	2.23	5.63	0.54
July	23.36	0.57	10.79	0.27	0.83	2.64	2.19	5.66	0.53
Aug.	20.50	0.56	11.69	0.44	2.11	2.39	1.92	6.42	0.55
Sep.	16.50	0.55	13.18	0.59	4.45	1.98	1.55	7.98	0.61
Oct.	12.13	0.54	14.23	0.67	6.72	1.49	1.14	9.35	0.66
Nov.	7.68	0.47	12.09	0.72	6.70	1.02	0.72	8.44	0.70
Dec.	5.57	0.40	9.46	0.72	5.22	0.86	0.52	6.61	0.70

The Klein and Theilacker equations could have been used for this calculation. ■

For collectors that face the equator, Klein (1976) found that  $(\bar{\tau}\alpha)_b$  could be approximated by  $(\bar{\tau}\alpha)$  evaluated at the incidence angle that occurs 2.5 h from solar noon on the average day of the month. This angle can be calculated from Equation 1.6.7a (or Equation 1.6.7b for the southern hemisphere) or obtained from Figure 5.10.2. This rule leads to acceptable results for solar space heating systems for which it was derived, but inaccurate results are obtained for other types of systems. Klein also found that the value of  $(\bar{\tau}\alpha)/(\tau\alpha)_n$  during the winter months is nearly constant and equal to 0.96 for a one-cover



**Figure 5.10.2** Monthly mean incidence angle for beam radiation for surfaces facing the equator in the northern hemisphere for space heating systems. For the southern hemisphere, interchange the two inequality signs. From Klein (1979).

collector and suggests using this constant value for collectors tilted toward the equator with a slope approximately equal to the latitude plus  $15^\circ$  in heating system analysis. For two-cover collectors a constant value of 0.94 was suggested.

It is useful to be able to calculate  $(\overline{\tau\alpha})$  from  $(\tau\alpha)_n$  and the information on  $(\tau\alpha)/(\tau\alpha)_n$  in Figure 5.6.1, where  $(\overline{\tau\alpha})$  is defined by Equation 5.10.1. Dividing by  $(\tau\alpha)_n$ , we have

$$\frac{(\overline{\tau\alpha})}{(\tau\alpha)_n} = \frac{\overline{S}}{H_T (\tau\alpha)_n} \quad (5.10.3)$$

The appropriate equation for  $\bar{S}$  is substituted in this relationship to provide a useful working equation. If the isotropic model is used, Equation 5.10.3 becomes

$$\frac{(\bar{\tau}\alpha)}{(\tau\alpha)_n} = \frac{\bar{H}_b \bar{R}_b}{\bar{H}_T} \frac{(\bar{\tau}\alpha)_b}{(\tau\alpha)_n} + \frac{\bar{H}_d}{\bar{H}_T} \frac{(\bar{\tau}\alpha)_d}{(\tau\alpha)_n} \left( \frac{1 + \cos \beta}{2} \right) + \frac{\bar{H} \rho_g}{\bar{H}_T} \frac{(\bar{\tau}\alpha)_g}{(\tau\alpha)_n} \left( \frac{1 - \cos \beta}{2} \right) \quad (5.10.4)$$

In Equation 5.10.4, the  $(\bar{\tau}\alpha)/(\tau\alpha)_n$  ratios are obtained from Figure 5.6.1 for the beam component at the effective angle of incidence  $\bar{\theta}_b$  from Figure 5.10.1 and for the diffuse and ground-reflected components at the effective angles of incidence at  $\beta$  from Figure 5.3.1.

The Klein and Theilacker equations can be used in a similar manner.

## 5.11 ABSORPTANCE OF ROOMS

Direct-gain passive solar heating depends on absorption of solar radiation in rooms or sunspaces which are cavity receivers with apertures (windows) covered with one or more glazings. Equation 4.12.1 can be modified to give the fraction of the incident solar energy on the glazing that is absorbed by such a receiver,

$$\tau_c \alpha_{\text{eff}} = \tau_c \frac{\alpha_i}{\alpha_i + (1 - \alpha_i) \tau_d A_a + A_i} \quad (5.11.1)$$

Here  $\tau_c$  is the transmittance of the glazing for the incident solar radiation;  $\tau_d$  is the transmittance of the glazing for isotropic diffuse solar radiation (the solar radiation reflected from the inner walls of the cavity), which is at an effective angle of incidence of about  $60^\circ$ ;  $A_a$  is the area of the aperture (the window);  $A_i$  is the area of the inside of the room; and  $\alpha_i$  is the absorptance for diffuse radiation of the inner surface of the cavity. A room may have various surfaces on floor, walls, ceiling, and furnishings, and a mean value of  $\alpha_i$  can be used.

### Example 5.11.1

Calculate  $\tau_c \alpha_{\text{eff}}$ , the fraction of solar radiation incident on a window which is absorbed in a room that has dimensions  $5 \times 4 \times 2.5$  m. The double glazed window is  $1.5 \times 3$  m. The mean absorptance of the surfaces in the room is 0.45. The transmittance of the glazing for incident radiation  $\tau_c = 0.87$ . The glass has  $KL = 0.0125$  per glazing.

### Solution

The area of the window,  $A_a$ , is  $1.5 \times 3 = 4.5 \text{ m}^2$ . The area of the room,  $A_i$  (not including the window), is  $2(5 \times 4 + 5 \times 2.5 + 4 \times 2.5) - 4.5 = 80.5 \text{ m}^2$ . From Figure 5.3.1, the transmittance of the glazing for diffuse radiation  $\tau_d$  at an effective angle of incidence of  $60^\circ$  is 0.74. Therefore,

$$\tau_c \alpha_{\text{eff}} = 0.87 \frac{0.45}{0.45 + (1 - 0.45) 0.74 (4.5/80.5)} = 0.87 \times 0.95 = 0.83$$

Thus this room will absorb 0.83 of the incident solar radiation (and 0.95 of the solar energy that is transmitted into it by the glazing). ■

**Example 5.11.2**

A direct-gain passive heating system is to be located in Springfield, Illinois ( $\phi = 40^\circ$ ). The receiver (the window) and the space in which solar radiation is to be absorbed have dimensions and characteristics described in the previous example (i.e., an effective absorptance of 0.95). For January, calculate  $\bar{S}$ , the absorbed radiation per unit area of window, if the window is not shaded. (This problem is the same as Example 5.10.1, except that the energy is absorbed in the room rather than on the black surface of an absorbing wall behind the glazing.)

**Solution**

For the cavity receiver the calculations are similar to those of Example 5.10.1, but the absorptance is constant and the transmittance-absorptance product is given by  $\tau\alpha$ . (The correction factor of 1.01 from Equation 5.5.2 is not used, as the radiation reflected back into the cavity from the cover is accounted for in the calculation of  $\alpha$ .) From Example 5.10.1, the month's average beam radiation incidence angle is  $41^\circ$  and the mean incidence angle of both the diffuse and the ground-reflected radiation is  $59^\circ$ .

For the beam radiation, from Figure 5.3.1 at  $\theta = 41^\circ$ , the transmittance is 0.82. Then

$$(\tau\alpha)_b = 0.82 \times 0.95 = 0.78$$

For the diffuse and ground-reflected radiation, from Figure 5.3.1 at  $\theta = 59^\circ$ , the transmittance is 0.74, and

$$(\tau\alpha)_d = (\tau\alpha)_g = 0.74 \times 0.95 = 0.70$$

Again assuming isotropic diffuse and using monthly average radiation calculations from Example 5.10.1,

$$\begin{aligned}\bar{S} &= 3.59 \times 2.32 \times 0.78 + 3.04 \times 0.70 \left( \frac{1 + \cos 90}{2} \right) \\ &\quad + 6.63 \times 0.7 \times 0.70 \left( \frac{1 - \cos 90}{2} \right) \\ &= 6.50 + 1.06 + 1.62 = 9.18 \text{ MJ/m}^2\end{aligned}$$

We can calculate a month's average  $(\tau\alpha)$  as  $\bar{S}/\bar{H}_T$ . Thus for January, with  $\bar{H}_T = 12.2 \text{ MJ/m}^2$ ,

$$(\tau\alpha) = \frac{9.18}{12.2} = 0.75$$

So 75% of the radiation incident on this window in January is absorbed in this room. Calculations for other months are done the same way as those for January. ■

Examples 5.10.1 and 5.11.2 will be the basis of passive system performance calculations to be shown in Chapter 22. Many receivers (windows) of passive heating systems are partially shaded by overhangs or wingwalls, and these shading devices must be taken into account in estimating the incident radiation.



## 5.12 ABSORPTANCE OF PHOTOVOLTAIC CELLS

As shown in Chapter 23, the major factor affecting the power output from a photovoltaic (PV) device is the solar radiation absorbed on the cell surface,  $S$ , which is a function of the incident radiation, air mass, and incidence angle. Similar to the situation with thermal collectors the needed radiation data are not normally known on the plane of the PV panel, so it is necessary to estimate the absorbed solar radiation using horizontal data and incidence angle information. The effective absorbed solar radiation  $S$  for a PV system consists of beam, diffuse, and ground-reflected components and a spectral effect. Equation 5.12.1 (which is identical to Equation 5.9.1 with the exception of the factor  $M$ ) provides a method of estimating  $S$  assuming that both diffuse and ground-reflected radiation are isotropic<sup>6</sup>:

$$\begin{aligned} S &= M \left( G_b R_b (\tau\alpha)_b + G_d (\tau\alpha)_d \frac{1 + \cos \beta}{2} + G \rho_g (\tau\alpha)_g \frac{1 - \cos \beta}{2} \right) \\ &= (\tau\alpha)_n M \left( G_b R_b K_{\tau\alpha,b} + G_d K_{\tau\alpha,d} \frac{1 + \cos \beta}{2} + G \rho_g K_{\tau\alpha,g} \frac{1 - \cos \beta}{2} \right) \end{aligned} \quad (5.12.1)$$

where  $K_{\tau\alpha,b} = (\tau\alpha)_b / (\tau\alpha)_n$  is the incidence angle modifier at the beam incidence angle,  $K_{\tau\alpha,d}$  and  $K_{\tau\alpha,g}$  are the incidence angle modifiers at effective incidence angles for isotropic diffuse and ground-reflected radiation, and  $M$  is an air mass modifier. Selective absorption by species in the atmosphere causes the spectral content of the solar radiation to change, altering the spectral distribution of the radiation incident on the PV panel and thus the generated electricity. King et al. (2004) developed an empirical relation to account for changes in the spectral distribution resulting from changes in air mass from the reference air mass value of 1.5 (i.e., at sea-level reference conditions the air mass is equal to 1.5 and  $M_{\text{ref}} \equiv 1$ ):

$$M = \sum_0^4 a_i (AM)^i \quad (5.12.2)$$

where  $AM$  is the air mass and the  $a_i$  are constants for different PV materials. However, as reported by DeSoto et al. (2006), if one set of constants is chosen and used for all cell types, the difference in the results obtained is small for zenith angles less than about  $70^\circ$ . For monocrystalline silicon cells, as reported by Fanney et al. (2002), the values of  $a_0, \dots, a_4$  are 0.935823, 0.054289,  $-0.008677$ , 0.000527,  $-0.000011$ .

As discussed in Section 23.2, the ratio of the absorbed radiation  $S$  to the absorbed radiation at a reference radiation,  $S_{\text{ref}} = M_{\text{ref}} G_{\text{ref}} (\tau\alpha)_n$ , is needed and is conveniently represented as

$$\frac{S}{S_{\text{ref}}} = M \left( \frac{G_b}{G_{\text{ref}}} R_{\text{beam}} K_{\tau\alpha,b} + \frac{G_d}{G_{\text{ref}}} K_{\tau\alpha,d} \frac{1 + \cos \beta}{2} + \frac{G}{G_{\text{ref}}} \rho K_{\tau\alpha,g} \frac{1 - \cos \beta}{2} \right) \quad (5.12.3)$$

<sup>6</sup>Here the isotropic sky (Liu and Jordan) method is used but any of the anisotropic methods of Section 2.16 could have been used.

where  $G_{\text{ref}}$  is the solar radiation at a reference condition ( $1000 \text{ W/m}^2$  for most PV systems) at normal incidence so that  $(\tau\alpha)_n$  cancels out and  $M_{\text{ref}} = 1$ .

The incidence angle modifier for a PV panel differs somewhat from that of a flat-plate solar collector in that the glazing is bonded to the cell surface, thereby eliminating one air-glazing interface and the glazing surface may be treated so as to reduce reflection losses. Sjerps-Koomen et al. (1996) have shown that the transmission of a PV cover system is well represented by a simple air-glazing model. Snell's, Fresnel's, and Bouguer's laws (Section 5.1) are used to calculate the radiation absorbed by a cell with a glass cover as

$$\tau\alpha(\theta) = e^{-(KL/\cos\theta_r)} \left[ 1 - \frac{1}{2} \left( \frac{\sin^2(\theta_r - \theta)}{\sin^2(\theta_r + \theta)} + \frac{\tan^2(\theta_r - \theta)}{\tan^2(\theta_r + \theta)} \right) \right] \quad (5.12.4)$$

where  $\theta$  and  $\theta_r$  are the incidence and refraction angles (called  $\theta_1$  and  $\theta_2$  in Section 5.2),  $K$  is the glazing extinction coefficient, and  $L$  is the glazing thickness. For most PV systems a typical value for  $K$  is  $4 \text{ m}^{-1}$ , the value for "water white" glass, a typical value for the glazing thickness is 2 mm, and the refractive index is set to 1.526, the value for glass.

To obtain the incidence angle modifier ( $K_{\tau\alpha}$ ), Equation 5.12.3 needs be evaluated for incidence angles of  $0^\circ$  and  $\theta$ . The ratio of these two transmittances yields the incidence angle modifier:

$$K_{\tau\alpha}(\theta) = \frac{\tau\alpha(\theta)}{\tau\alpha(0)} \quad (5.12.5)$$


Separate incidence angle modifiers are needed for beam, diffuse, and ground-reflected radiation, but each can be calculated in the same way. Average angles for isotropic diffuse and ground-reflected radiation are provided as a function of the slope of the surface by Figure 5.4.1. Although these average angles for diffuse radiation were obtained for thermal collectors, they were found to yield reasonable results for PV systems.

A plot of the incidence angle modifier calculated using Equation 5.12.4 as a function of incidence angle is shown in Figure 5.12.1. Incidence angle modifiers in the form of fourth-order polynomial fits provided by Fanney et al. (2002) [following the recommendation of King et al. (2004)] for four different cell types are shown in the figure with dotted lines. The plots are all similar out to about  $70^\circ$  to  $75^\circ$  with the curve-fit nature of four of the curves clearly visible. Differences are apparent at high incidence angles, but the incident radiation is often low at these high angles and the uncertainty in the experimental values of the incidence angle modifier is large at these conditions.

When the beam and diffuse components of the horizontal radiation are known, the evaluation of Equation 5.12.2 is straightforward. However, the usual circumstance is to know only the total horizontal radiation  $G$  so it is necessary to estimate the beam and diffuse components. Erb's hourly diffuse fraction correlation (Equation 2.10.1) can be used to estimate  $G_d/G$  as a function of the clearness index. Sometimes the radiation is known on the inclined surface and a more complicated process is needed; this process is illustrated in the following example.

### Example 5.12.1

The instantaneous measured radiation on a south-facing surface at a tilt of  $45^\circ$  at sea level and at latitude  $39.22^\circ$  on June 1 is  $648.3 \text{ W/m}^2$ . Photovoltaic cells with a typical glass



**Figure 5.12.1** Incidence angle modifier  $k_{\tau\alpha}$ , as a function of incidence angle  $\theta$  calculated using Equation 5.12.4 (solid line). The dotted lines are curve fits to experimentally determined incidence angle modifiers for four different cell types.

cover are mounted at the same orientation. Estimate the ratio of absorbed radiation  $S$  to the absorbed radiation for a reference condition of  $1000 \text{ W/m}^2$  at normal incidence.

### Solution

Since the total radiation  $G_T$  is known on an inclined surface, it is first necessary to estimate the beam and diffuse components of the horizontal radiation. The zenith angle is  $17.24^\circ$  from Equation 1.6.5 and the incidence angle is  $27.87^\circ$  from Equation 1.6.2. From Equation 1.8.1,  $R_b = \cos 27.87 / \cos 17.24 = 0.9256$ . The extraterrestrial radiation  $G_o = 1268 \text{ W/m}^2$  from Equation 1.10.1. For an assumed ground reflectance of 0.2 the radiation on an inclined surface is found from Equation 2.15.1 in terms of the beam and diffuse components of horizontal radiation as

$$648.3 = G_b 0.9256 + G_d 0.854 + (G_b + G_d) 0.029$$

From the definition of  $k_T$ ,

$$k_T = \frac{G_b + G_d}{1268}$$

For radiation on a horizontal surface the beam and diffuse breakup can be estimated using Equation 2.10.1:

$$\frac{G_d}{G_d + G_b} = 0.9511 - 0.1604k_T + 4.388k_T^2 - 16.638k_T^3 + 12.336k_T^4$$

where it is assumed (and later checked and found to be true) that  $k_T$  is between 0.22 and 0.80. Solving the above three equations simultaneously results in  $k_T = 0.5776$ ,  $G_d = 377.8 \text{ W/m}^2$ ,  $G_b = 329.6 \text{ W/m}^2$ , and  $G = 707.4 \text{ W/m}^2$ .

The next step is to evaluate Equation 5.12.5 at three different angles:  $27.87^\circ$  for the beam radiation,  $69.45^\circ$  for the ground-reflected radiation (from Equation 5.4.1), and  $56.49^\circ$  for the diffuse radiation (from Equation 5.4.2). The incident angle modifier for the beam radiation will be used to illustrate the calculations. At an incidence angle of  $27.87^\circ$  the refraction angle is  $17.84^\circ$  from Equation 5.1.4. With  $K = 4 \text{ m}^{-1}$  and  $L = 0.002 \text{ m}$  we have

$$(\tau\alpha)_b = e^{-(0.008/\cos 17.84)} \left[ 1 - \frac{1}{2} \left( \frac{\sin^2 (17.84 - 28.87)}{\sin^2 (17.84 + 28.87)} + \frac{\tan^2 (17.84 - 28.87)}{\tan^2 (17.84 + 28.87)} \right) \right]$$

$$= 0.9475$$

At normal incidence

$$(\tau\alpha)_n = e^{-0.008} \left[ 1 - \left( \frac{1.526 - 1}{1.526 + 1} \right)^2 \right] = 0.9490$$

so that  $K_{\tau\alpha,b} = 0.9475/0.9490 = 0.998$ . In the same manner  $K_{\tau\alpha,d} = 0.962$  and  $K_{\tau\alpha,g} = 0.867$ . The air mass  $AM = 1/\cos 17.24 = 1.047$  so the air mass modifier  $M$  is equal to 0.9837 from Equation 5.12.2. The desired result is found from Equation 5.12.1:

$$\frac{S}{S_{\text{ref}}} = 0.9837 \left( \frac{329.6}{1000} 0.926 \times 0.998 + \frac{377.8}{1000} 0.962 \times 0.854 \right. \\ \left. + \frac{707.4}{1000} 0.2 \times 0.867 \times 0.146 \right)$$

$$= 0.622$$

■

## 5.13 SUMMARY

This chapter includes several alternative methods for calculating important parameters. For purposes of calculating radiation absorbed on surfaces that face toward the equator or nearly so, it is suggested that the hourly absorbed radiation is adequately estimated by Equation 5.9.1 and the monthly absorbed radiation by Equation 5.10.2 (both based on the isotropic model). (The HDKR model for  $S$  is almost as easy to use as the isotropic, leads to less conservative estimates of  $S$ , and is a useful alternative.) For surfaces that face other than toward the equator (e.g., for calculating winter radiation on north-facing windows), anisotropic models should be used.

## REFERENCES

- Brandemuehl, M. J. and W. A. Beckman, *Solar Energy*, **24**, 511 (1980). "Transmission of Diffuse Radiation through CPC and Flat-Plate Collector Glazings."
- DeSoto, W., S. A. Klein, and W. A. Beckman, *Solar Energy*, **80**, 78 (2006). "Improvement and Validation of a Model for Photovoltaic Array Performance."

- Dietz, A. G. H., in *Space Heating with Solar Energy* (R. W. Hamilton, ed.), Massachusetts Institute of Technology Press, Cambridge, MA (1954). “Diathermanous Materials and Properties of Surfaces.”
- Dietz, A. G. H., in *Introduction to the Utilization of Solar Energy* (A. M. Zarem and D. D. Erway, eds.), McGraw-Hill, New York (1963). “Diathermanous Materials and Properties of Surfaces.”
- Edwards, D. K., *Solar Energy*, **19**, 401 (1977). “Solar Absorption of Each Element in an Absorber-Coverglass Array.”
- Fanney, A. H., B. P. Dougherty, and M. W. Davis, in *Proceedings of the Twenty-Ninth IEEE Photovoltaic Specialists Conference (PVSC)*, New Orleans, LA (May 20–24, 2002), “Evaluating Building Integrated Photovoltaic Performance Models.”
- Hottel, H. C. and B. B. Woertz, *Trans. ASME*, **64**, 91 (1942). “The Performance of Flat-Plate Solar-Heat Collectors.”
- King, D. L., W. E. Boyson, and J. E. Kratochvil, Sandia National Laboratories Report SAND 2004–3535 (Aug. 2004). “Photovoltaic Array Performance Model.”
- Klein, S. A., Ph.D. Thesis, University of Wisconsin—Madison (1976). “A Design Procedure for Solar Heating Systems.”
- Klein, S. A., *Solar Energy*, **23**, 547 (1979). “Calculation of the Monthly-Average Transmittance-Absorptance Product.”
- Mar, H. Y. B., J. H. Lin, P. P. Zimmer, R. E. Peterson, and J. S. Gross, Report to ERDA under Contract No. NSF-C-957 (Sept. 1975). “Optical Coatings for Flat-Plate Solar Collectors.”
- Siegel, R. and J. R. Howell. *Thermal Radiation Heat Transfer*, 4th ed, Taylor & Francis, New York (2002).
- Sjerps-Koomen, E. A., E. A. Alsema, and W. C. Turkemburg, *Solar Energy*, **57**, 421 (1996). “A Simple Model for PV Module Reflection Losses under Field Conditions.”
- Thomsen, S. M., *RCA Rev.*, **12**, 143 (1951). “Low-Reflection Films Produced on Glass in a Liquid Fluosilicic Acid Bath.”
- Whillier, A., ScD. Thesis, MIT, Cambridge, MA (1953). “Solar Energy Collection and Its Utilization for House Heating.”
- Whillier, A., *Solar Energy*, **7**, 148 (1963). “Plastic Covers for Solar Collectors.”

## Flat-Plate Collectors

A solar collector is a special kind of heat exchanger that transforms solar radiant energy into heat. A solar collector differs in several respects from more conventional heat exchangers. The latter usually accomplish a fluid-to-fluid exchange with high heat transfer rates and with radiation as an unimportant factor. In the solar collector, energy transfer is from a distant source of radiant energy to a fluid. The flux of incident radiation is, at best, approximately  $1100 \text{ W/m}^2$  (without optical concentration), and it is variable. The wavelength range is from  $0.3$  to  $3 \mu\text{m}$ , which is considerably shorter than that of the emitted radiation from most energy-absorbing surfaces. Thus, the analysis of solar collectors presents unique problems of low and variable energy fluxes and the relatively large importance of radiation.


Flat-plate collectors can be designed for applications requiring energy delivery at moderate temperatures, up to perhaps  $100^\circ\text{C}$  above ambient temperature. They use both beam and diffuse solar radiation, do not require tracking of the sun, and require little maintenance. They are mechanically simpler than concentrating collectors. The major applications of these units are in solar water heating, building heating, air conditioning, and industrial process heat. Passively heated buildings can be viewed as special cases of flat-plate collectors with the room or storage wall as the absorber. Passive systems are discussed in Chapter 14.

The importance of flat-plate collectors in thermal processes is such that their thermal performance is treated in considerable detail. This is done to develop an understanding of how the component functions. In many practical cases of design calculations, the equations for collector performance are reduced to relatively simple forms.

The last sections of this chapter treat testing of collectors, the use of test data, and some practical aspects of manufacture and use of these heat exchangers. Costs will be considered in chapters on applications.

### 6.1 DESCRIPTION OF FLAT-PLATE COLLECTORS

The important parts of a typical liquid heating flat-plate solar collector, as shown in Figure 6.1.1, are the “black” solar energy-absorbing surface with means for transferring the absorbed energy to a fluid, envelopes transparent to solar radiation over the solar absorber surface that reduce convection and radiation losses to the atmosphere, and back insulation to reduce conduction losses. Figure 6.1.1 depicts a water heater, and most of the analysis of this chapter is concerned with this geometry. Air heaters are fundamentally the same except that the fluid tubes are replaced by ducts. Flat-plate collectors are almost



**Figure 6.1.1** Cross section of a basic flat-plate solar collector.

always mounted in a stationary position (e.g., as an integral part of a wall or roof structure) with an orientation optimized for the particular location in question for the time of year in which the solar device is intended to operate.

## 6.2 BASIC FLAT-PLATE ENERGY BALANCE EQUATION

In steady state, the performance of a solar collector is described by an energy balance that indicates the distribution of incident solar energy into useful energy gain, thermal losses, and optical losses. The solar radiation absorbed by a collector per unit area of absorber  $S$  is equal to the difference between the incident solar radiation and the optical losses as defined by Equation 5.9.1. The thermal energy lost from the collector to the surroundings by conduction, convection, and infrared radiation can be represented as the product of a heat transfer coefficient  $U_L$  times the difference between the mean absorber plate temperature  $T_{pm}$  and the ambient temperature  $T_a$ . In steady state the useful energy output of a collector of area  $A_c$  is the difference between the absorbed solar radiation and the thermal loss:

$$Q_u = A_c[S - U_L(T_{pm} - T_a)] \quad (6.2.1)$$

The problem with this equation is that the mean absorber plate temperature is difficult to calculate or measure since it is a function of the collector design, the incident solar radiation, and the entering fluid conditions. Part of this chapter is devoted to reformulating Equation 6.2.1 so that the useful energy gain can be expressed in terms of the inlet fluid temperature and a parameter called the collector heat removal factor, which can be evaluated analytically from basic principles or measured experimentally.

Equation 6.2.1 is an energy rate equation and, in SI units, yields the useful energy gain in watts (J/s) when  $S$  is expressed in  $\text{W/m}^2$  and  $U_L$  in  $\text{W/m}^2 \text{ K}$ . The most convenient time base for solar radiation is hours rather than seconds since this is the normal period for reporting of meteorological data. (For example, Table 2.5.2 gives solar radiation in  $\text{J/m}^2$  for 1-h time periods.) This is the time basis for  $S$  in Equation 5.9.1 since the meaning of  $I$  is hourly  $\text{J/m}^2$ . We can consider  $S$  to be an average energy rate over a 1-h period with units of  $\text{J/m}^2 \text{ h}$ , in which case the thermal loss term  $U_L(T_{pm} - T_a)$  must be multiplied by 3600 s/h to obtain numerical values of the useful energy gain in J/h. The hour time base is not a proper use of SI units, but this interpretation is often convenient. Alternatively, we can integrate Equation 6.2.1 over a 1-h period. Since we seldom have data over time

periods less than 1 h, this integration can be performed only by assuming that  $S$ ,  $T_{pm}$ , and  $T_a$  remain constant over the hour. The resulting form of Equation 6.2.1 is unchanged except that both sides are multiplied by 3600 s/h. To avoid including this constant in expressions for useful energy gain on an hourly basis, we could have used different symbols for rates and for hourly integrated quantities (e.g.,  $\dot{Q}_u$  and  $Q_u$ ). However, the intended meaning is always clear from the use of either  $G$  or  $I$  in the evaluation of  $S$ , and we have found it unnecessary to use different symbols for collector useful energy gain on an instantaneous basis or an hourly integrated basis. From a calculation standpoint the 3600 must still be included since  $S$  will be known for an hour time period but the loss coefficient will be in SI units.

A measure of collector performance is the collection efficiency, defined as the ratio of the useful gain over some specified time period to the incident solar energy over the same time period:

$$\eta = \frac{\int \dot{Q}_u \, dt}{A_c \int G_T \, dt} \quad (6.2.2a)$$

If conditions are constant over a time period, the efficiency reduces to

$$\eta = \frac{Q_u}{I_T A_C} \quad (6.2.2b)$$

The design of a solar energy system is concerned with obtaining minimum-cost energy. Thus, it may be desirable to design a collector with an efficiency lower than is technologically possible if the cost is significantly reduced. In any event, it is necessary to be able to predict the performance of a collector, and that is the basic aim of this chapter.

### 6.3 TEMPERATURE DISTRIBUTIONS IN FLAT-PLATE COLLECTORS

The detailed analysis of a solar collector is a complicated problem. Fortunately, a relatively simple analysis will yield very useful results. These results show the important variables, how they are related, and how they affect the performance of a solar collector. To illustrate these basic principles, a liquid heating collector, as shown in Figure 6.3.1, will be examined first. The analysis presented follows the basic derivation by Whillier (1953, 1977) and Hottel and Whillier (1958).

To appreciate the development that follows, it is desirable to have an understanding of the temperature distribution that exists in a solar collector constructed as shown in Figure 6.3.1. Figure 6.3.2(a) shows a region between two tubes. Some of the solar energy absorbed by the plate must be conducted along the plate to the region of the tubes. Thus the temperature midway between the tubes will be higher than the temperature in the vicinity of the tubes. The temperature above the tubes will be nearly uniform because of the presence of the tube and weld metal.

The energy transferred to the fluid will heat the fluid, causing a temperature gradient to exist in the direction of flow. Since in any region of the collector the general temperature level is governed by the local temperature level of the fluid, a situation as shown in






Figure 6.3.1 Sheet-and-tube solar collector.




Figure 6.3.2 Temperature distribution on an absorber plate. From Duffie and Beckman (1974).

Figure 6.3.2(b) is expected. At any location  $y$ , the general temperature distribution in the  $x$  direction is as shown in Figure 6.3.2(c), and at any location  $x$ , the temperature distribution in the  $y$  direction will look like Figure 6.3.2(d).

To model the situation shown in Figure 6.3.2, a number of simplifying assumptions can be made to lay the foundations without obscuring the basic physical situation. These assumptions are as follows:

1. Performance is steady state.
2. Construction is of sheet and parallel tube type.
3. The headers cover a small area of collector and can be neglected.
4. The headers provide uniform flow to tubes.
5. There is no absorption of solar energy by a cover insofar as it affects losses from the collector.

6. Heat flow through a cover is one dimensional.
7. There is a negligible temperature drop through a cover.
8. The covers are opaque to infrared radiation.
9. There is one-dimensional heat flow through back insulation.
10. The sky can be considered as a blackbody for long-wavelength radiation at an equivalent sky temperature.
11. Temperature gradients around tubes can be neglected.
12. The temperature gradients in the direction of flow and between the tubes can be treated independently.
13. Properties are independent of temperature.
14. Loss through front and back are to the same ambient temperature.
15. Dust and dirt on the collector are negligible.
16. Shading of the collector absorber plate is negligible.

In later sections of this chapter many of these assumptions will be relaxed.

## 6.4 COLLECTOR OVERALL HEAT LOSS COEFFICIENT


The equations developed in the remainder of this text are often coupled nonlinear algebraic and/or differential equations. The equations are presented in a manner that is convenient for solving by hand or by programming in structured languages such as FORTRAN, Pascal, or C. Typically this means nonlinear equations are linearized, differential equations are discretized, and iterative solutions are required. A number of computer programs are available that can solve systems of algebraic and differential equations; it is only necessary to write the equations in a natural form and let the program organize the solution. The authors use Engineering Equation Solver (EES)<sup>1</sup> to check solutions to the example problems, to solve the homework problems in Appendix A, and to carry on research with their colleagues and graduate students.

It is useful to develop the concept of an overall loss coefficient for a solar collector to simplify the mathematics. Consider the thermal network for a two-cover system shown in Figure 6.4.1. At some typical location on the plate where the temperature is  $T_p$ , solar energy of amount  $S$  is absorbed by the plate, where  $S$  is equal to the incident solar radiation reduced by optical losses as shown in Section 5.9. This absorbed energy  $S$  is distributed to thermal losses through the top and bottom and to useful energy gain. The purpose of this section is to convert the thermal network of Figure 6.4.1 to the thermal network of Figure 6.4.2.


The energy loss through the top is the result of convection and radiation between parallel plates. The steady-state energy transfer between the plate at  $T_p$  and the first cover at  $T_{c1}$  is the same as between any other two adjacent covers and is also equal to the energy lost to the surroundings from the top cover. The loss through the top per-unit area is then

---

<sup>1</sup>Engineering Equation Solver information is available at [www.fchart.com](http://www.fchart.com).



**Figure 6.4.1** Thermal network for a two-cover flat-plate collector: (a) in terms of conduction, convection, and radiation resistances; (b) in terms of resistances between plates.



**Figure 6.4.2** Equivalent thermal network for flat-plate solar collector.

equal to the heat transfer from the absorber plate to the first cover:

$$q_{\text{loss, top}} = h_{c, p-c1}(T_p - T_{c1}) + \frac{\sigma(T_p^4 - T_{c1}^4)}{\frac{1}{\varepsilon_p} + \frac{1}{\varepsilon_{c1}} - 1} \quad (6.4.1)$$

where  $h_{c, p-c1}$  is the convection heat transfer coefficient between two inclined parallel plates from Chapter 3. If the definition of the radiation heat transfer coefficient (Equation 3.10.1) is used, the heat loss becomes

$$q_{\text{loss, top}} = (h_{c, p-c1} + h_{r, p-c1})(T_p - T_{c1}) \quad (6.4.2)$$

where

$$h_{r, p-c1} = \frac{\sigma(T_p + T_{c1})(T_p^2 + T_{c1}^2)}{\frac{1}{\varepsilon_p} + \frac{1}{\varepsilon_{c1}} - 1} \quad (6.4.3)$$

The resistance  $R_3$  can then be expressed as

$$R_3 = \frac{1}{h_{c, p-c1} + h_{r, p-c1}} \quad (6.4.4)$$

A similar expression can be written for  $R_2$ , the resistance between the covers. In general, we can have as many covers as desired, but the practical limit is two and most collectors use one.

The resistance from the top cover to the surroundings has the same form as Equation 6.4.4, but the convection heat transfer coefficient  $h_w$  is given in Section 3.15. The radiation resistance from the top cover accounts for radiation exchange with the sky at  $T_s$ . For convenience, we reference this resistance to the ambient temperature  $T_a$ , so that the radiation heat transfer coefficient can be written as

$$h_{r, c2-a} = \frac{\sigma \varepsilon_c (T_{c2} + T_s)(T_{c2}^2 + T_s^2)(T_{c2} - T_s)}{T_{c2} - T_a} \quad (6.4.5)$$

The resistance to the surroundings  $R_1$  is then given by

$$R_1 = \frac{1}{h_w + h_{r, c2-a}} \quad (6.4.6)$$

For this two-cover system, the top loss coefficient from the collector plate to the ambient is

$$U_t = \frac{1}{R_1 + R_2 + R_3} \quad (6.4.7)$$

The procedure for solving for the top loss coefficient using Equations 6.4.1 through 6.4.7 is necessarily an iterative process. First a guess is made of the unknown cover temperatures, from which the convective and radiative heat transfer coefficients between parallel surfaces are calculated. With these estimates, Equation 6.4.7 can be solved for

the top loss coefficient. The top heat loss is the top loss coefficient times the overall temperature difference, and since the energy exchange between plates must be equal to the overall heat loss, a new set of cover temperatures can be calculated. Beginning at the absorber plate, a new temperature is calculated for the first cover. This new first cover temperature is used to find the next cover temperature, and so on. For any two adjacent covers or plate, the new temperature of plate or cover  $j$  can be expressed in terms of the temperature of plate or cover  $i$  as

$$T_j = T_i - \frac{U_t(T_i - T_a)}{h_{c,i-j} + h_{r,i-j}} \quad (6.4.8)$$

The process is repeated until the cover temperatures do not change significantly between successive iterations. The following example illustrates the process.

#### Example 6.4.1

Calculate the top loss coefficient for an absorber with a single glass cover having the following specifications:

Plate-to-cover spacing	25 mm
Plate emittance	0.95
Ambient air and sky temperature	10°C
Wind heat transfer coefficient	10 W/m <sup>2</sup> °C
Mean plate temperature	100°C
Collector tilt	45°
Glass emittance	0.88

#### Solution

For this single-glass-cover system, Equation 6.4.7 becomes

$$U_t = \left( \frac{1}{h_{c,p-c} + h_{r,p-c}} + \frac{1}{h_w + h_{r,c-a}} \right)^{-1}$$

The convection coefficient between the plate and the cover  $h_{c,p-c}$  can be found using the methods of Section 3.11. The radiation coefficient from the plate to the cover  $h_{r,p-c}$  is

$$h_{r,p-c} = \frac{\sigma(T_p^2 + T_c^2)(T_p - T_c)}{\frac{1}{\varepsilon_p} + \frac{1}{\varepsilon_c} - 1}$$

The radiation coefficient for the cover to the air  $h_{r,c-a}$  is given as

$$h_{r,c-a} = \varepsilon_c \sigma (T_c^2 + T_s^2)(T_c + T_s)$$

The equation for the cover glass temperature is based on Equation 6.4.8:

$$T_c = T_p - \frac{U_t(T_p - T_a)}{h_{c,p-c} + h_{r,p-c}}$$

The procedure is to estimate the cover temperature, from which  $h_{c,p-c}$ ,  $h_{r,p-c}$  and  $h_{r,c-a}$  are calculated. With these heat transfer coefficients and  $h_w$ , the top loss coefficient is calculated. These results are then used to calculate  $T_c$  from the preceding equation. If  $T_c$  is close to the initial guess, no further calculations are necessary. Otherwise, the newly calculated  $T_c$  is used and the process is repeated.

With an assumed value of the cover temperature of  $35^\circ\text{C}$ , the two radiation coefficients become

$$h_{r,p-c} = 7.60 \text{ W/m}^2 \text{ }^\circ\text{C}, \quad h_{r,c-a} = 5.16 \text{ W/m}^2 \text{ }^\circ\text{C}$$

Equation 3.11.4 is used to calculate the convection coefficient between the plate and the cover. The mean temperature between the plate and the cover is  $67.5^\circ\text{C}$  so the air properties are  $\nu = 1.96 \times 10^{-5} \text{ m}^2/\text{s}$ ,  $k = 0.0293 \text{ W/m }^\circ\text{C}$ ,  $T = 340.5 \text{ K}$ , and  $\text{Pr} = 0.7$ . The Rayleigh number is

$$\text{Ra} = \frac{9.81(100 - 35)(0.025)^3(0.7)}{340.5(1.96 \times 10^{-5})^2} = 5.33 \times 10^4$$

and from Equation 3.11.4 the Nusselt number is 3.19. The convective heat transfer coefficient is

$$h = \text{Nu} \frac{k}{L} = 3.19 \frac{0.0293}{0.025} = 3.73 \text{ W/m}^2 \text{ }^\circ\text{C}$$

(The same result is obtained from Figures 3.11.1 and 3.11.2. From Figure 3.11.2,  $F_1 = 0.46$  and  $F_2 = 0.84$ . The value of  $F_1 \Delta T l^3$  is  $4.7 \times 10^5$ . From Figure 3.11.1,  $F_2 hl = 78$ . Then  $h = 3.7 \text{ W/m}^2 \text{ }^\circ\text{C}$ .) The first estimate of  $U_t$  is then

$$U_t = \left( \frac{1}{3.73 + 7.60} + \frac{1}{5.16 + 10.0} \right)^{-1} = 6.49 \text{ W/m}^2 \text{ }^\circ\text{C}$$

The cover temperature is

$$T_c = 100 - \frac{6.49 \times 90}{3.73 + 7.60} = 48.5^\circ\text{C}$$

With this new estimate of the cover temperature, the various heat transfer coefficients become

$$h_{r,p-c} = 8.03 \text{ W/m}^2 \text{ }^\circ\text{C}, \quad h_{r,c-a} = 5.53 \text{ W/m}^2 \text{ }^\circ\text{C}, \quad h_{c,p-c} = 3.52 \text{ W/m}^2 \text{ }^\circ\text{C}$$

and the second estimate of  $U_t$  is

$$U_t = 6.62 \text{ W/m}^2 \text{ }^\circ\text{C}$$

When the cover glass temperature is calculated with this new top loss coefficient, it is found to be  $48.4^\circ\text{C}$ , which is essentially equal to the estimate of  $48.5^\circ\text{C}$ .

The following shows the solution to this example using EES. The small difference between  $U_t$  obtained by EES and  $U_t$  in the above solution is due only to property differences (the EES solution properties being more accurate).

**Equations**

Knowns – units set to J, K, kPa, and degrees

$$L = 0.025 \text{ [m]}; \varepsilon_p = 0.95; T_a = 283 \text{ [K]}; h_w = 10 \text{ [W/m}^2 \text{ K]}; P_{\text{atm}} = 101.3 \text{ [kPa]}$$

$$T_p = 373 \text{ [K]}; \beta = 45[\text{deg}]; \varepsilon_g = 0.88; \sigma = \text{sigma\#}; g = g\#$$

Definition of top loss coefficient and rate equations:

$$q = U_t(T_p - T_a)$$

$$q = h_c(T_p - T_c) + \frac{\sigma(T_p^4 - T_c^4)}{1/\varepsilon_p + 1/\varepsilon_c - 1}$$

$$q = h_w(T_c - T_a) + \sigma\varepsilon_p(T_c^4 - T_a^4)$$

Get properties at  $T_m$

$$T_m = \frac{T_p + T_c}{2}$$

$$\mu = \text{viscosity}(\text{air}, T = T_m); k = \text{conductivity}(\text{air}, T = T_m)$$

$$C_p = \text{specheat}(\text{air}, T = T_m); \rho = \text{density}(\text{air}, T = T_m)$$

$$\nu = \mu/\rho; \alpha = k/(\rho C_p)$$

Rayleigh and Nusselt numbers

$$\text{Ra\#} = \frac{g(T_p - T_c)L^3}{T_m \nu \alpha}; \text{Nu\#} = \frac{h_c L}{k}$$

$$\text{Nu\#} = 1 + 1.44 \left[ 1 - \frac{1708(\sin 1.8\beta)^{1.6}}{\text{Ra\#} \cos \beta} \right] \left[ 1 - \frac{1708}{\text{Ra\#} \cos \beta} \right]^+ \\ + \left[ \left( \frac{\text{Ra\#} \cos \beta}{5830} \right)^{1/3} - 1 \right]^+$$

$$T_{\text{cover}} = \text{ConvrtTemp}(\text{K}, C, T_c)$$

**Solution**

$$\alpha = 0.0000284 \text{ [m}^2/\text{s]}$$

$$C_p = 1008 \text{ [J/kg K]}$$

$$h_c = 3.44 \text{ [W/m}^2 \text{ K]}$$

$$k = 0.0291 \text{ [W/m K]}$$

$$\mu = 0.0000207 \text{ [kg/m s]}$$

$$\nu = 0.00002035 \text{ [m}^2/\text{s]}$$

$$\text{Nu\#} = 2.96$$

$$q = 593.5 \text{ [W/m}^2 \text{]}$$

$$\text{Ra\#} = 39542$$

$$\rho = 1.017 \text{ [kg/m}^3 \text{]}$$

$$T_c = 321.1 \text{ [K]}$$

$$T_{\text{cover}} = 48.1 \text{ [C]}$$

$$T_m = 347.1 \text{ [K]}$$

$$U_t = 6.59 \text{ [W/m}^2 \text{ K]}$$




The results of heat loss calculations for four different solar collectors, all with the same plate and ambient temperatures, are shown in Figure 6.4.3. The cover temperatures and the heat flux by convection and radiation are shown for one and two glass covers and for selective and nonselective absorber plates. Note that radiation between plates is the dominant mode of heat transfer in the absence of a selective surface. When a selective surface having an emittance of 0.10 is used, convection is the dominant heat transfer mode between the selective surface and the cover, but radiation is still the largest term between the two cover glasses in the two-cover system.

For most conditions the use of a blackbody radiation sky temperature that is not equal to the air temperature will not greatly affect the top loss coefficient or the top heat loss. For example, the top loss coefficient based on the plate-to-ambient-temperature difference for condition (a) of Figure 6.4.3 is increased from 6.62 to 6.76  $\text{W/m}^2 \text{ } ^\circ\text{C}$  when the sky temperature is reduced from 10 to  $0^\circ\text{C}$ . For condition (b) the top loss coefficient is increased from 3.58 to 3.67  $\text{W/m}^2 \text{ } ^\circ\text{C}$ .

As illustrated by Example 6.4.1, the calculation of the top loss coefficient is a tedious process. To simplify calculations of collector performance, Figures 6.4.4(a–f) have been prepared. These figures give the top loss coefficient for one, two, and three glass covers spaced 25 mm apart; ambient temperatures of 40, 10, and  $-20^\circ\text{C}$ ; wind heat transfer coefficients of 5, 10, and 20  $\text{W/m}^2 \text{ } ^\circ\text{C}$ ; plates having an emittance of 0.95 and 0.10, a slope of  $45^\circ$ , and a range of plate temperatures.

Even though the top loss coefficients of Figures 6.4.4 are for a plate spacing of 25 mm, they can be used for other plate spacings with little error as long as the spacing is



**Figure 6.4.3** Cover temperature and upward heat loss for flat-plate collectors operating at  $100^\circ\text{C}$  with ambient and sky temperature of  $10^\circ\text{C}$ , plate spacing of 25 mm, tilt of  $45^\circ$ , and wind heat transfer coefficient of 10  $\text{W/m}^2 \text{ } ^\circ\text{C}$ : (a) one cover, plate emittance 0.95,  $U_t = 6.6 \text{ W/m}^2 \text{ } ^\circ\text{C}$ ; (b) one cover, plate emittance 0.10,  $U_t = 3.6 \text{ W/m}^2 \text{ } ^\circ\text{C}$ ; (c) two covers, plate emittance 0.95,  $U_t = 3.9 \text{ W/m}^2 \text{ } ^\circ\text{C}$ ; (d) two covers, plate emittance 0.10,  $U_t = 2.4 \text{ W/m}^2 \text{ } ^\circ\text{C}$ . All heat flux terms in watts per square meter.







Figure 6.4.4 Top loss coefficient for slope of 45° and a plate spacing of 25 mm.





Figure 6.4.4 (Continued)






Figure 6.4.4 (Continued)

greater than about 15 mm. Figure 6.4.5 illustrates the dependence of the top loss coefficient on plate spacing for selective and nonselective one- and two-cover collectors. For very small plate spacings convection is suppressed and the heat transfer mechanism through the gap is by conduction and radiation. In this range the top loss coefficient decreases rapidly as the plate spacing increases until a minimum is reached at about 10- to 15-mm plate spacing. When fluid motion first begins to contribute to the heat transfer process, the top loss coefficient increases until a maximum is reached at approximately 20 mm. Further increase in the plate spacing causes a small reduction in the top loss coefficient. Similar behavior occurs at other conditions and for other collector designs.


Figure 6.4.4 was prepared using a slope  $\beta$  of  $45^\circ$ . In Figure 6.4.6 the ratio of the top loss coefficient at any tilt angle to that of  $45^\circ$  has been plotted as a function of slope.

The graphs for  $U_t$  are convenient for hand calculations but they are difficult to use on computers. An empirical equation for  $U_t$  that is useful for both hand and computer calculations was developed by Klein (1979) following the basic procedure of Hottel and Woertz (1942) and Klein (1975). This relationship fits the graphs for  $U_t$  for mean plate temperatures<sup>2</sup> between ambient and  $200^\circ\text{C}$  to within  $\pm 0.3 \text{ W/m}^2 \text{ }^\circ\text{C}$ :



**Figure 6.4.5** Typical variation of top loss coefficient with plate spacing.

<sup>2</sup>A method for estimating  $T_{pm}$  is given in Section 6.9.



**Figure 6.4.6** Dependence of top loss coefficient on slope.

$$U_t = \left( \frac{N}{\frac{C}{T_{pm}} \left[ \frac{(T_{pm} - T_a)}{(N + f)} \right]^e + \frac{1}{h_w}} \right)^{-1} + \frac{\sigma(T_{pm} + T_a)(T_{pm}^2 + T_a^2)}{\frac{1}{\varepsilon_p + 0.00591N h_w} + \frac{2N + f - 1 + 0.133\varepsilon_p}{\varepsilon_g} - N} \quad (6.4.9)$$

where  $N$  = number of glass covers

$$f = (1 + 0.089h_w - 0.1166h_w\varepsilon_p)(1 + 0.07866N)$$

$C = 520(1 - 0.000051\beta^2)$  for  $0^\circ < \beta < 70^\circ$ ; for  $70^\circ < \beta < 90^\circ$ , use  $\beta = 70^\circ$

$$e = 0.430(1 - 100/T_{pm})$$

$\beta$  = collector tilt (deg)

$\varepsilon_g$  = emittance of glass (0.88)

$\varepsilon_p$  = emittance plate

$T_a$  = ambient temperature (K)

$T_{pm}$  = mean plate temperature (K)

$h_w$  = wind heat transfer coefficient ( $\text{W/m}^2 \text{ } ^\circ\text{C}$ )

#### Example 6.4.2

Determine the collector top loss coefficient for a single glass cover with the following specifications:

Plate-to-cover spacing	25 mm
Plate emittance	0.95
Ambient temperature	$10^\circ\text{C}$
Mean plate temperature	$100^\circ\text{C}$
Collector tilt	$45^\circ$
Wind heat transfer coefficient	$10 \text{ W/m}^2 \text{ } ^\circ\text{C}$

**Solution**

From the definitions of  $f$ ,  $C$ , and  $e$  in Equation 6.4.9

$$f = [1.0 + 0.089(10) - 0.1166(10)(0.95)](1 + 0.07866) = 0.844$$

$$C = 520[1 - 0.000051(45)^2] = 466$$

$$e = 0.430 \left(1 - \frac{100}{373}\right) = 0.315$$

From Equation 6.4.9

$$\begin{aligned} U_t &= \left[ \frac{1}{\frac{466}{373} \left( \frac{373 - 283}{1 + 0.844} \right)^{0.315} + \frac{1}{10}} \right]^{-1} \\ &\quad + \frac{5.67 \times 10^{-8} (373 + 283)(373^2 + 283^2)}{\frac{1}{0.95 + 0.00591 \times 1 \times 10} + \frac{2 + 0.844 - 1 + 0.133 \times 0.95}{0.88} - 1} \\ &= 2.98 + 3.65 = 6.6 \text{ W/m}^2 \text{ } ^\circ\text{C} \end{aligned}$$

which is very nearly the same as found in Example 6.4.1. ■

The energy loss through the bottom of the collector is represented by two series resistors,  $R_4$  and  $R_5$ , in Figure 6.4.1, where  $R_4$  represents the resistance to heat flow through the insulation and  $R_5$  represents the convection and radiation resistance to the environment. The magnitudes of  $R_4$  and  $R_5$  are such that it is usually possible to assume  $R_5$  is zero and all resistance to heat flow is due to the insulation. Thus, the back loss coefficient  $U_b$  is approximately<sup>3</sup>

$$U_b = \frac{1}{R_4} = \frac{k}{L} \quad (6.4.10)$$

where  $k$  and  $L$  are the insulation thermal conductivity and thickness, respectively.

For most collectors the evaluation of edge losses is complicated. However, in a well-designed system, the edge loss should be small so that it is not necessary to predict it with great accuracy. Tabor (1958) recommends edge insulation of about the same thickness as bottom insulation. The edge losses are then estimated by assuming one-dimensional sideways heat flow around the perimeter of the collector system. The losses through the edge should be referenced to the collector area. If the edge loss coefficient–area product is  $(U/A)_{\text{edge}}$ , then the edge loss coefficient, based on the collector area  $A_c$ , is

$$U_e = \frac{(UA)_{\text{edge}}}{A_c} \quad (6.4.11)$$

---

<sup>3</sup>It is often assumed that the back losses are to a sink at the same temperature as the front losses. This may not be the case.

If it is assumed that all losses occur to a common sink temperature  $T_a$ , the collector overall loss coefficient  $U_L$  is the sum of the top, bottom, and edge loss coefficients:

$$U_L = U_t + U_b + U_e \quad (6.4.12)$$

### Example 6.4.3

For the collector of Example 6.4.2 with a top loss coefficient of  $6.6 \text{ W/m}^2 \text{ }^\circ\text{C}$ , calculate the overall loss coefficient with the following additional specifications:

Back-insulation thickness	50 mm
Insulation conductivity	$0.045 \text{ W/m }^\circ\text{C}$
Collector bank length	10 m
Collector bank width	3 m
Collector thickness	75 mm
Edge insulation thickness	25 mm

### Solution

The bottom loss coefficient is found from Equation 6.4.10:

$$U_b = \frac{k}{L} = \frac{0.045}{0.050} = 0.9 \text{ W/m}^2 \text{ }^\circ\text{C}$$

The edge loss coefficient for the 26-m perimeter is found from Equation 6.4.11:

$$U_e = \frac{(0.045/0.025) \times 26 \times 0.075}{30} = 0.12 \text{ W/m}^2 \text{ }^\circ\text{C}$$

The collector overall loss coefficient is then

$$U_L = 6.6 + 0.9 + 0.1 = 7.6 \text{ W/m}^2 \text{ }^\circ\text{C} \quad \blacksquare$$

The edge loss for this  $30\text{-m}^2$  collector array is a little over 1% of the total losses. Note, however, that if this collector were  $1 \times 2 \text{ m}$ , the edge losses would increase to over 5%. Thus, edge losses for well-constructed large collector arrays are usually negligible, but for small arrays or individual modules the edge losses may be significant. Also note that only the exterior perimeter was used to estimate edge losses. If the individual collectors are not packed tightly together, significant heat loss may occur from the edge of each module.

The preceding discussion of top loss coefficients, including Equation 6.4.9, is based on covers like glass that are opaque to long-wavelength radiation. If a plastic material is used to replace one or more covers, the equation for  $U_t$  must be modified to account for some infrared radiation passing directly through the cover. For a single cover that is partially transparent to infrared radiation, the net radiant energy transfer directly between the collector plate and the sky is

$$q_{r,p-s} = \frac{\tau_c \varepsilon_p \sigma (T_p^4 - T_s^4)}{1 - \rho_p \rho_c} \quad (6.4.13)$$

where  $\tau_c$  and  $\rho_c$  are the transmittance and reflectance of the cover for radiation from  $T_p$  and from  $T_s$  (assuming that the transmittance is independent of source temperature or that  $T_p$  and  $T_s$  are nearly the same) and  $\varepsilon_p$  and  $\rho_p$  are the emittance and reflectance of the plate for long-wave radiation. The top loss coefficient then becomes

$$U_t = \frac{q_{r,p-s}}{T_p - T_a} + \left( \frac{1}{h_{c,p-c} + h_{r,p-c}} + \frac{1}{h_w + h_{r,c-s}} \right)^{-1} \quad (6.4.14)$$

The evaluation of the radiation heat transfer coefficients in Equation 6.4.14 must take into account that the cover is partially transparent. The net radiation between the opaque plate and the partially transparent cover is given by

$$q = \frac{\sigma \varepsilon_p \varepsilon_c (T_p^4 - T_c^4)}{1 - \rho_p \rho_c} \quad (6.4.15)$$

The radiation heat transfer coefficient between the plate and cover is just the net heat transfer divided by the temperature difference:

$$h_{r,p-c} = \frac{\sigma \varepsilon_p \varepsilon_c (T_p + T_c)(T_p^2 + T_c^2)}{1 - \rho_p \rho_c} \quad (6.4.16)$$

Whillier (1977) presents top loss coefficients for collector cover systems of one glass cover over one plastic cover, two plastic covers, and one glass cover over two plastic covers.

## 6.5 TEMPERATURE DISTRIBUTION BETWEEN TUBES AND THE COLLECTOR EFFICIENCY FACTOR

The temperature distribution between two tubes can be derived if we temporarily assume the temperature gradient in the flow direction is negligible. Consider the sheet-tube configuration shown in Figure 6.5.1. The distance between the tubes is  $W$ , the tube diameter is  $D$ , and the sheet is thin with a thickness  $\delta$ . Because the sheet material is a good conductor, the temperature gradient through the sheet is negligible. We will assume the sheet above the bond is at some local base temperature  $T_b$ . The region between the centerline separating the tubes and the tube base can then be considered as a classical fin problem.

The fin, shown in Figure 6.5.2(a), is of length  $(W - D)/2$ . An elemental region of width  $\Delta x$  and unit length in the flow direction is shown in Figure 6.5.2(b). An energy balance on this element yields

$$S \Delta x - U_L \Delta x (T - T_a) + \left( -k\delta \frac{dT}{dx} \right) \Big|_x - \left( -k\delta \frac{dT}{dx} \right) \Big|_{x+\Delta x} = 0 \quad (6.5.1)$$

where  $S$  is the absorbed solar energy defined by Equation 5.9.1. Dividing through by  $\Delta x$  and finding the limit as  $\Delta x$  approaches zero yield

$$\frac{d^2 T}{dx^2} = \frac{U_L}{k\delta} \left( T - T_a - \frac{S}{U_L} \right) \quad (6.5.2)$$






Figure 6.5.1 Sheet and tube dimensions.




Figure 6.5.2 Energy balance on fin element.

The two boundary conditions necessary to solve this second-order differential equation are symmetry at the centerline and the known base temperature:

$$\left. \frac{dT}{dx} \right|_{x=0} = 0, \quad T|_{x=(W-D)/2} = T_b \quad (6.5.3)$$

For convenience, we can define two variables,  $m$  and  $\Psi$  :

$$m = \sqrt{\frac{U_L}{k\delta}} \quad (6.5.4a)$$

$$\psi = T - T_a - \frac{S}{U_L} \quad (6.5.4b)$$

and Equation 6.5.2 becomes

$$\frac{d^2\psi}{dx^2} - m^2\psi = 0 \quad (6.5.5)$$

which has the boundary conditions

$$\left. \frac{d\psi}{dx} \right|_{x=0} = 0, \quad \psi|_{x=(W-D)/2} = T_b - T_a - \frac{S}{U_L} \quad (6.5.6)$$

The general solution is

$$\psi = C_1 \sinh mx + C_2 \cosh mx \quad (6.5.7)$$

The constants  $C_1$  and  $C_2$  can be found by substituting the boundary conditions into the general solution. The result is

$$\frac{T - T_a - S/U_L}{T_b - T_a - S/U_L} = \frac{\cosh mx}{\cosh m(W - D)/2} \quad (6.5.8)$$

The energy conducted to the region of the tube per unit of length in the flow direction can now be found by evaluating Fourier's law at the fin base:

$$q'_{\text{fin}} = -k \delta \left. \frac{dT}{dx} \right|_{x=(W-D)/2} = \left( \frac{k \delta m}{U_L} \right) [S - U_L(T_b - T_a)] \tanh \frac{m(W - D)}{2} \quad (6.5.9)$$

but  $k \delta m/U_L$  is just  $1/m$ . Equation 6.5.9 accounts for the energy collected on only one side of a tube; for both sides, the energy collection is

$$q'_{\text{fin}} = (W - D)[S - U_L(T_b - T_a)] \frac{\tanh m(W - D)/2}{m(W - D)/2} \quad (6.5.10)$$

It is convenient to use the concept of a fin efficiency to rewrite Equation 6.5.10 as

$$q'_{\text{fin}} = (W - D)F[S - U_L(T_b - T_a)] \quad (6.5.11)$$

where

$$F = \frac{\tanh[m(W - D)/2]}{m(W - D)/2} \quad (6.5.12)$$

The function  $F$  is the standard fin efficiency for straight fins with rectangular profile and is plotted in Figure 6.5.3.

The useful gain of the collector also includes the energy collected above the tube region. The energy gain for this region is

$$q'_{\text{tube}} = D[S - U_L(T_b - T_a)] \quad (6.5.13)$$


and the useful gain for the tube and fin per unit of length in the flow direction is the sum of Equations 6.5.11 and 6.5.13:

$$q'_u = [(W - D)F + D][S - U_L(T_b - T_a)] \quad (6.5.14)$$

Ultimately, the useful gain from Equation 6.5.14 must be transferred to the fluid. The resistance to heat flow to the fluid results from the bond and the tube-to-fluid resistance. The useful gain can be expressed in terms of the two resistances as

$$q'_u = \frac{T_b - T_f}{\frac{1}{h_{fi}\pi D_i} + \frac{1}{C_b}} \quad (6.5.15)$$

where  $D_i$  is the inside tube diameter and  $h_{fi}$  is the heat transfer coefficient between the fluid and the tube wall. The bond conductance  $C_b$  can be estimated from knowledge of the



**Figure 6.5.3** Fin efficiency for tube-and-sheet solar collectors.

bond thermal conductivity  $k_b$ , the average bond thickness  $\gamma$ , and the bond width  $b$ . On a per-unit-length basis,

$$C_b = \frac{k_b b}{\gamma} \quad (6.5.16)$$

The bond conductance can be very important in accurately describing collector performance. Whillier and Saluja (1965) have shown by experiments that simple wiring or clamping of the tubes to the sheet results in low bond conductance and significant loss of performance. They conclude that it is necessary to have good metal-to-metal contact so that the bond conductance is greater than 30 W/m °C.

We now wish to eliminate  $T_b$  from the equations and obtain an expression for the useful gain in terms of known dimensions, physical parameters, and the local fluid temperature. Solving Equation 6.5.15 for  $T_b$ , substituting it into Equation 6.5.14, and solving the result for the useful gain, we obtain

$$q'_u = W F' [S - U_L (T_f - T_a)] \quad (6.5.17)$$

where the collector efficiency factor  $F'$  is given as

$$F' = \frac{1/U_L}{W \left[ \frac{1}{U_L [D + (W - D) F]} + \frac{1}{C_b} + \frac{1}{\pi D_i h_{fi}} \right]} \quad (6.5.18)$$

A physical interpretation for  $F'$  results from examining Equation 6.5.17. At a particular location,  $F'$  represents the ratio of the actual useful energy gain to the useful gain that would result if the collector absorbing surface had been at the local fluid temperature. For this and most (but not all) geometries, another interpretation for the parameter  $F'$  becomes clear when it is recognized that the denominator of Equation 6.5.18 is the heat transfer resistance from the fluid to the ambient air. This resistance will be given the symbol  $1/U_o$ . The numerator is the heat transfer resistance from the absorber plate to the ambient air. Thus  $F'$  is the ratio of these two heat transfer coefficients:

$$F' = \frac{U_o}{U_L} \quad (6.5.19)$$


The collector efficiency factor is essentially a constant for any collector design and fluid flow rate. The ratio of  $U_L$  to  $C_b$ , the ratio of  $U_L$  to  $h_{fi}$ , and the fin efficiency parameter  $F$  are the only variables appearing in Equation 6.5.18 that may be functions of temperature. For most collector designs  $F$  is the most important of these variables in determining  $F'$ . The factor  $F'$  is a function of  $U_L$  and  $h_{fi}$ , each of which has some temperature dependence, but it is not a strong function of temperature.

The evaluation of  $F'$  is not a difficult task. However, to illustrate the effects of various design parameters on the magnitude of  $F'$ , Figure 6.5.4 has been prepared. Three values of the overall heat transfer coefficient  $U_L$  were chosen (2, 4, and 8 W/m<sup>2</sup> °C) which cover the range of collector designs from a one-cover nonselective to a two-cover selective. (See Figure 6.4.4 for other combinations that yield these same overall loss coefficients.) Instead of selecting various plate materials, the curves were prepared for various values of  $k\delta$ , the product of the plate thermal conductivity and plate thickness. For a copper plate 1 mm thick,  $k\delta = 0.4$  W/°C; for a steel plate 0.1 mm thick,  $k\delta = 0.005$  W/°C. Thus, the probable range of  $k\delta$  is from 0.005 to 0.4. The bond conductance was assumed to be very large (i.e.,  $1/C_b = 0$ ) and the tube diameter was selected as 0.01 m. Three values were chosen for the heat transfer coefficient inside the tube to cover a range from laminar flow to highly turbulent flow: 100, 300, and 1000 W/m<sup>2</sup> °C. Note that increasing  $h_{fi}$  beyond 1000 W/m<sup>2</sup> °C for this diameter tube does not result in significant increases in  $F'$ . As expected, the collector efficiency factor decreases with increased tube center-to-center distances and increases with increases in both material thickness and thermal conductivity. Increasing the overall loss coefficient decreases  $F'$ .

### Example 6.5.1

Calculate the collector efficiency factor for the following specifications:

Overall loss coefficient	8.0 W/m <sup>2</sup> °C
Tube spacing	150 mm
Tube diameter (inside)	10 mm
Plate thickness	0.5 mm
Plate thermal conductivity (copper)	385 W/m °C
Heat transfer coefficient inside tubes	300 W/m <sup>2</sup> °C
Bond conductance	∞ W/m °C



**Figure 6.5.4** Collector efficiency factor  $F'$  versus tube spacing for 10-mm-diameter tubes: (a)  $h_{fi} = 100 \text{ W/m}^2 \text{ }^\circ\text{C}$ ; (b)  $h_{fi} = 300 \text{ W/m}^2 \text{ }^\circ\text{C}$ ; (c)  $h_{fi} = 1000 \text{ W/m}^2 \text{ }^\circ\text{C}$ .

### Solution

The fin efficiency factor  $F$ , from Equations 6.5.4a and 6.5.12, is determined as follows:

$$m = \left( \frac{8}{385 \times 5 \times 10^{-4}} \right)^{1/2} = 6.45 \text{ [1/m]}$$

$$F = \frac{\tanh[6.45(0.15 - 0.01)/2]}{6.45(0.15 - 0.01)/2} = 0.937$$




Figure 6.5.4 (Continued)

The collector efficiency factor  $F'$  is found from Equation 6.5.18:

$$F' = \frac{1/8}{0.15 \left[ \frac{1}{8 [0.01 + (0.15 - 0.01) 0.937]} + \frac{1}{\infty} + \frac{1}{\pi \times 0.01 \times 300} \right]} = 0.841$$

The same result is obtained from Figure 6.5.4(b). ■





Figure 6.5.4 (Continued)

## 6.6 TEMPERATURE DISTRIBUTION IN FLOW DIRECTION

The useful gain per unit flow length as calculated from Equation 6.5.17 is ultimately transferred to the fluid. The fluid enters the collector at temperature  $T_{fi}$  and increases in temperature until at the exit it is  $T_{fo}$ . Referring to Figure 6.6.1, we can express an energy balance on the fluid flowing through a single tube of length  $\Delta y$  as

$$\left(\frac{\dot{m}}{n}\right) C_p T_f|_y - \left(\frac{\dot{m}}{n}\right) C_p T_f|_{y+\Delta y} + \Delta y q'_u = 0 \quad (6.6.1)$$



**Figure 6.6.1** Energy balance on fluid element.

where  $\dot{m}$  is the total collector flow rate and  $n$  is the number of parallel tubes. Dividing through by  $\Delta y$ , finding the limit as  $\Delta y$  approaches zero, and substituting Equation 6.5.17 for  $q'_{u'}$ , we obtain

$$\dot{m}C_p \frac{dT_f}{dy} - nWF'[S - U_L(T_f - T_a)] = 0 \quad (6.6.2)$$

If we assume that  $F'$  and  $U_L$  are independent of position,<sup>4</sup> then the solution for the fluid temperature at any position  $y$  (subject to the condition that the inlet fluid temperature is  $T_{fi}$ ) is

$$\frac{T_f - T_a - S/U_L}{T_{fi} - T_a - S/U_L} = \exp\left(-\frac{U_L nWF'y}{\dot{m}C_p}\right) \quad (6.6.3)$$

If the collector has a length  $L$  in the flow direction, then the outlet fluid temperature  $T_{fo}$  is found by substituting  $L$  for  $y$  in Equation 6.6.3. The quantity  $nWL$  is the collector area:

$$\frac{T_{fo} - T_a - S/U_L}{T_{fi} - T_a - S/U_L} = \exp\left(-\frac{U_L A_c F'}{\dot{m}C_p}\right) \quad (6.6.4)$$

## 6.7 COLLECTOR HEAT REMOVAL FACTOR AND FLOW FACTOR

It is convenient to define a quantity that relates the actual useful energy gain of a collector to the useful gain if the whole collector surface were at the fluid inlet temperature. This quantity is called the collector heat removal factor  $F_R$ . In equation form it is

$$F_R = \frac{\dot{m}C_p(T_{fo} - T_{fi})}{A_c[S - U_L(T_{fi} - T_a)]} \quad (6.7.1)$$

The collector heat removal factor can be expressed as

$$\begin{aligned} F_R &= \frac{\dot{m}C_p}{A_c U_L} \left[ \frac{T_{fo} - T_{fi}}{S/U_L - (T_{fi} - T_a)} \right] \\ &= \frac{\dot{m}C_p}{A_c U_L} \left[ \frac{[S/U_L - (T_{fi} - T_a)] - [S/U_L - (T_{fo} - T_a)]}{S/U_L - (T_{fi} - T_a)} \right] \end{aligned} \quad (6.7.2)$$

<sup>4</sup>Dunkle and Cooper (1975) have assumed  $U_L$  is a linear function of  $T_f - T_a$ .



or

$$F_R = \frac{\dot{m}C_p}{A_c U_L} \left[ 1 - \frac{S/U_L - (T_{fo} - T_a)}{S/U_L - (T_{fi} - T_a)} \right] \quad (6.7.3)$$

which from Equation 6.6.4 can be expressed as

$$F_R = \frac{\dot{m}C_p}{A_c U_L} \left[ 1 - \exp \left( -\frac{A_c U_L F'}{\dot{m}C_p} \right) \right] \quad (6.7.4)$$


To present Equation 6.7.4 graphically, it is convenient to define the collector flow factor  $F''$  as the ratio of  $F_R$  to  $F'$ . Thus

$$F'' = \frac{F_R}{F'} = \frac{\dot{m}C_p}{A_c U_L F'} \left[ 1 - \exp \left( -\frac{A_c U_L F'}{\dot{m}C_p} \right) \right] \quad (6.7.5)$$

This collector flow factor is a function of the single variable, the dimensionless collector capacitance rate  $\dot{m}C_p/A_c U_L F'$ , and is shown in Figure 6.7.1.

The quantity  $F_R$  is equivalent to the effectiveness of a conventional heat exchanger, which is defined as the ratio of the actual heat transfer to the maximum possible heat transfer. The maximum possible useful energy gain (heat transfer) in a solar collector occurs when the whole collector is at the inlet fluid temperature; heat losses to the surroundings are then at a minimum. The collector heat removal factor times this maximum possible useful energy gain is equal to the actual useful energy gain  $Q_u$  :

$$Q_u = A_c F_R [S - U_L (T_i - T_a)] \quad (6.7.6)$$



**Figure 6.7.1** Collector flow factor  $F''$  as a function of  $\dot{m}C_p/A_c U_L F'$ .

This is an extremely useful equation<sup>5</sup> and applies to essentially all flat-plate collectors. With it, the useful energy gain is calculated as a function of the inlet fluid temperature. This is a convenient representation when analyzing solar energy systems, since the inlet fluid temperature is usually known. However, losses based on the inlet fluid temperature are too small since losses occur all along the collector from the plate and the plate has an ever-increasing temperature in the flow direction. The effect of the multiplier  $F_R$  is to reduce the useful energy gain from what it would have been had the whole collector absorber plate been at the inlet fluid temperature to what actually occurs. As the mass flow rate through the collector increases, the temperature rise through the collector decreases. This causes lower losses since the average collector temperature is lower and there is a corresponding increase in the useful energy gain. This increase is reflected by an increase in the collector heat removal factor  $F_R$  as the mass flow rate increases. Note that  $F_R$  can never exceed the collector efficiency factor  $F'$ . As the flow rate becomes very large, the temperature rise from inlet to outlet decreases toward zero but the temperature of the absorbing surface will still be higher than the fluid temperature. This temperature difference is accounted for by the collector efficiency factor  $F'$ .

Many of the equations of Sections 6.6 and 6.7 contain the ratio of the collector mass flow rate to collector area. This ratio is a convenient way to express flow rate when collector area is a design variable since increasing both in proportion will maintain a nearly constant value of  $F_R$ .

### Example 6.7.1

Calculate the daily useful gain and efficiency of an array of 10 solar collector modules installed in parallel near Boulder, Colorado, at a slope of  $60^\circ$  and a surface azimuth of  $0^\circ$ . The hourly radiation on the plane of the collector  $I_T$ , the hourly radiation absorbed by the absorber plate  $S$ , and the hourly ambient temperature  $T_a$  are given in the table at the end of this example. The methods of Sections 2.15, 2.16, and 5.9 can be used to find  $I_T$  and  $S$  knowing the hourly horizontal radiation, the collector orientation, and the collector optical properties. For the collector assume the overall loss coefficient  $U_L$  to be  $8.0 \text{ W/m}^2 \text{ }^\circ\text{C}$  and the plate efficiency factor  $F'$  to be 0.841 (from Example 6.5.1). The water flow rate through each  $1 \times 2\text{-m}$  collector panel is  $0.03 \text{ kg/s}$  and the inlet water temperature remains constant at  $40^\circ\text{C}$ . Assume a controller turns off the water flow whenever the outlet temperature is less than the inlet temperature.

### Solution

The dimensionless collector mass flow rate is

$$\frac{\dot{m}C_p}{A_c U_L F'} = \frac{0.03 \times 4190}{2 \times 8 \times 0.841} = 9.35$$

so that the collector flow factor, from Equation 6.7.5 (or Figure 6.7.1), is

$$F'' = 9.35 \left[ 1 - \exp\left(-\frac{1}{9.35}\right) \right] = 0.948$$

<sup>5</sup>This is the most important equation in the book. The subscript  $f$  on the fluid inlet temperature has been dropped; whenever the meaning is not clear, it will be reintroduced.

and the heat removal factor is

$$F_R = F' F'' = 0.841 \times 0.948 = 0.797$$

The average loss rate for the hour 10 to 11, based on an inlet temperature of 40°C, is

$$U_L(T_i - T_a) = 8(40 - 2) \times 3600 = 1.09 \text{ MJ/m}^2 \text{ h}$$

and the average useful energy gain per unit of collector area is

$$q_u = \frac{Q_u}{A_c} = 0.797(3.29 - 1.09) \times 10^6 = 1.76 \text{ MJ/m}^2 \text{ h}$$

The collector efficiency for this hour is found from Equation 6.2.2:

$$\eta = \frac{Q_u}{I_T A_c} = \frac{q_u}{I_T} = \frac{1.76}{3.92} = 0.45$$

and the day-long collector efficiency is

$$\eta_{\text{day}} = \frac{\sum q_u}{\sum I_T} = \frac{7.57}{19.79} = 0.38$$

The daily useful energy gain of the 10 collector modules in the array is

$$\sum Q_u = 10 \times 2 \times 7.57 \times 10^6 = 150 \text{ MJ}$$

Time	$T_a$ (°C)	$I_T$ (MJ/m <sup>2</sup> h)	$S$ (MJ/m <sup>2</sup> h)	$U_L(T_i - T_a)$ (MJ/m <sup>2</sup> h)	$q_u$ (MJ/m <sup>2</sup> h)	$\eta$
7–8	–11	0.02	0.01	1.46	0.00	0.00
8–9	–8	0.43	0.35	1.38	0.00	0.00
9–10	–2	0.99	0.82	1.21	0.00	0.00
10–11	2	3.92	3.29	1.09	1.76	0.45
11–12	3	3.36	2.84	1.07	1.42	0.42
12–1	6	4.01	3.39	0.98	1.93	0.48
1–2	7	3.84	3.21	0.95	1.81	0.47
2–3	8	1.96	1.63	0.92	0.57	0.29
3–4	9	1.21	0.99	0.89	0.08	0.07
4–5	7	<u>0.05</u>	0.04	0.95	<u>0.00</u>	0.00
Sum		19.79			7.57	



A number of general observations can be made from the results of Example 6.7.1. The estimated performance is typical of a one-cover nonselective collector, although in

most systems the inlet temperatures will vary throughout the day.<sup>6</sup> The losses are both thermal and optical, and during the early morning and late afternoon the radiation level was not sufficient to overcome the losses. The collector should not be operated during these periods.

Daily efficiency may also be based on the period while the collector is operating. The efficiency calculated in this manner is  $7.57/18.39$ , or 41%. Reporting in this manner gives a higher value for collector efficiency. As the collector inlet temperature is reduced, these two day-long efficiencies will approach one another. Collector efficiency is a single parameter that combines collector and system characteristics and generally is not reliable for making comparisons.

The fluid temperature rise through the collector (from  $\Delta T = Q_u/\dot{m}C_p$ ) varies from a high of  $8.5^\circ\text{C}$  between 12 and 1 to a low of  $2.5^\circ\text{C}$  between 2 and 3. This relatively modest temperature rise is typical of liquid heating collectors. The temperature rise can be increased by reducing the flow rate, but this will reduce the useful energy gain (if the inlet fluid temperature stays the same). If the flow rate were halved and if  $F'$  remained the same (in fact,  $h_{fi}$  would decrease, which would reduce  $F'$ ), then  $F_R$  would decrease to 0.76 and the temperature rise during the hour 12 to 1 would be  $16.2^\circ\text{C}$ , which is less than twice the original temperature rise. The efficiency during this hour would be reduced from 48 to 46%.<sup>7</sup>

## 6.8 CRITICAL RADIATION LEVEL

In Chapter 2, the concept of utilizability was developed without concern for how critical radiation levels were defined. With Equation 6.7.6 established, we can now determine the critical radiation level  $G_{Tc}$  for flat-plate collectors. It is convenient to rewrite Equation 6.7.6 in the following form:

$$Q_u = A_c[F_R(\tau\alpha)_{av} G_T - F_R U_L(T_i - T_a)] \quad (6.8.1)$$

The critical radiation level is that value of  $G_T$  that makes the term in the brackets identically zero, that is, where the absorbed radiation and loss terms are equal:

$$G_{Tc} = \frac{F_R U_L(T_i - T_a)}{F_R(\tau\alpha)} \quad (6.8.2)$$

It is convenient to retain  $F_R$  in the equation for reasons that will be clear in later sections. The collector output can now be written in terms of the critical radiation level:

$$Q_u = A_c F_R(\tau\alpha)_{av}(G_T - G_{Tc})^+ \quad (6.8.3)$$

The equations for  $Q_u$  indicate that for the collector to produce useful output, that is, for  $Q_u > 0$ , the absorbed radiation must exceed the thermal losses and  $G_T$  must be greater

<sup>6</sup>Temperature fluctuations are considered in Chapter 10.

<sup>7</sup>It will be seen in later chapters that when a *system* with a thermally stratified tank is considered, a reduction in flow rate may lead to reduced  $T_{fi}$  and thus to increased  $Q_u$  even though  $F_R$  is decreased.

than  $G_{Tc}$ . In Equations 6.7.6 and 6.8.3, only positive values of the terms in parentheses are considered. This implies that there is a controller on the collector that shuts off the flow of fluid when the value in parentheses is not positive.

## 6.9 MEAN FLUID AND PLATE TEMPERATURES

To evaluate collector performance, it is necessary to know the overall loss coefficient and the internal fluid heat transfer coefficients. However, both  $U_L$  and  $h_{fi}$  are to some degree functions of temperature. The mean fluid temperature can be found by integrating Equation 6.6.3 from zero to  $L$  :

$$T_{fm} = \frac{1}{L} \int_0^L T_f(y) dy \quad (6.9.1)$$

Performing this integration and substituting  $F_R$  from Equation 6.7.4 and  $Q_u$  from Equation 6.7.6, the mean fluid temperature was shown by Klein et al. (1974) to be

$$T_{fm} = T_{fi} + \frac{Q_u/A_c}{F_R U_L} (1 - F'') \quad (6.9.2)$$

This is the proper temperature for evaluating fluid properties.

When a collector is producing useful energy, the mean plate temperature will always be greater than the mean fluid temperature due to the heat transfer resistance between the absorbing surface and the fluid. This temperature difference is usually small for liquid heating collectors but may be significant for air collectors.

The mean plate temperature can be used to calculate the useful gain of a collector,

$$Q_u = A_c [S - U_L (T_{pm} - T_a)] \quad (6.9.3)$$

If we equate Equations 6.9.3 and 6.7.6 and solve for the mean plate temperature, we have

$$T_{pm} = T_{fi} + \frac{Q_u/A_c}{F_R U_L} (1 - F_R) \quad (6.9.4)$$

Equation 6.9.4 can be solved in an iterative manner with Equation 6.4.9. First an estimate of the mean plate temperature is made from which  $U_L$  is calculated. With approximate values of  $F_R$ ,  $F''$ , and  $Q_u$ , a new mean plate temperature is obtained from Equation 6.9.4 and used to find a new value for the top loss coefficient. The new value of  $U_L$  is used to refine  $F_R$  and  $F''$ , and the process is repeated. With a reasonable initial guess, a second iteration is seldom necessary. A reasonable first guess for  $T_{pm}$  for liquid heating collectors operated at typical flow rates of 0.01 to 0.02 kg/m<sup>2</sup> s is  $T_{fi} + 10^\circ\text{C}$ . For air heaters a reasonable first estimate is  $T_{fi} + 20^\circ\text{C}$ .

### Example 6.9.1

Find the mean fluid and plate temperatures for the hour 11 to 12 of Example 6.7.1.

**Solution**

Assume  $U_L = 8.0 \text{ W/m}^2 \text{ }^\circ\text{C}$ ,  $F'' = 0.948$ ,  $F_R = 0.797$ , and  $q_u = 1.42 \text{ MJ/m}^2 \text{ h}$ . We have from Equation 6.9.2

$$T_{fm} = 40 + \frac{1.42 \times 10^6 / 3600}{8 \times 0.797} (1 - 0.948) = 43^\circ\text{C}$$

The mean plate temperature is found from Equation 6.9.4:


$$T_{pm} = 40 + \frac{1.42 \times 10^6 / 3600}{8 \times 0.797} (1 - 0.797) = 53^\circ\text{C}$$

In this example  $U_L$  was assumed to be independent of temperature. If the temperature dependence of  $U_L$  is considered, an iterative process would have been necessary. ■

**6.10 EFFECTIVE TRANSMITTANCE-ABSORPTANCE PRODUCT**

In Section 5.5, the product of cover transmittance times plate solar absorptance was discussed. In Section 6.4 the expressions for  $U_L$  were derived assuming that the glazing did not absorb solar radiation. To maintain the simplicity of Equation 6.7.6 and account for the reduced thermal losses due to absorption of solar radiation by the glass, an effective transmittance-absorptance product  $(\tau\alpha)_e$  will be introduced. It will be shown that  $(\tau\alpha)_e$  is slightly greater than  $(\tau\alpha)$ .

All of the solar radiation that is absorbed by a cover system is not lost, since this absorbed energy tends to increase the cover temperature and consequently reduce the thermal losses from the plate. Consider the thermal network of a single-cover system shown in Figure 6.10.1. Solar energy absorbed by the cover is  $G_T \alpha_c$ , where  $\alpha_c$  is the cover



**Figure 6.10.1** Thermal network for top losses for a single-cover collector with and without absorptance in the cover.

absorptance and  $G_T$  is the incident radiation. From Equation 5.3.5 the cover absorptance can be replaced by  $1 - \tau_a$ . The loss for (a), without absorption, is  $U_{p-c}(T_p - T_c)$ , and the loss for (b), with absorption, is  $U_{p-c}(T_p - T'_c)$ . Here we have assumed that the small amount of absorption in the cover and consequent increased cover temperature do not change the values of  $U_{p-c}$  and  $U_{c-a}$ . The difference  $D$  in the two loss terms is

$$D = U_{p-c}[(T_p - T_c) - (T_p - T'_c)] \quad (6.10.1)$$

The temperature difference  $T_p - T_c$  can be expressed as

$$T_p - T_c = \frac{U_t(T_p - T_a)}{U_{p-c}} \quad (6.10.2)$$

where  $U_t$  is the top loss coefficient and is equal to  $U_{p-c}U_{c-a}/(U_{p-c} + U_{c-a})$ .

The temperature difference  $T_p - T'_c$  can be expressed as

$$T_p - T'_c = \frac{U_{c-a}(T_p - T_a) - G_T\alpha_c}{U_{p-c} + U_{c-a}} \quad (6.10.3)$$

Therefore

$$D = U_t(T_p - T_a) - \frac{U_{p-c}U_{c-a}(T_p - T_a)}{U_{p-c} + U_{c-a}} + \frac{G_T U_{p-c}(1 - \tau_a)}{U_{p-c} + U_{c-a}} \quad (6.10.4)$$

or

$$D = \frac{G_T U_t(1 - \tau_a)}{U_{c-a}} \quad (6.10.5)$$

The quantity  $D$  represents the reduction in collector losses due to absorption in the cover but can be considered an additional input in the collector equation. The useful gain of a collector is then

$$q_u = F_R \left[ S + \frac{G_T U_t(1 - \tau_a)}{U_{c-a}} - U_L(T_i - T_a) \right] \quad (6.10.6)$$

In general the quantity  $G_T$  has three components, beam, diffuse, and ground-reflected radiation. Each of these terms is multiplied by a separate value of  $(\tau\alpha)$  to determine  $S$  [i.e.,  $(\tau\alpha)_b$ ,  $(\tau\alpha)_d$ , or  $(\tau\alpha)_g$ , as shown in Section 5.8]. We can divide the radiation absorbed in the cover into these same three components. By defining the quantity  $(\tau\alpha) + (1 - \tau_a) U_t/U_{c-a}$  as the effective transmittance-absorptance product for each of the three components, the simplicity of Equation 6.7.6 can be maintained. For this one-cover system

$$(\tau\alpha)_e = (\tau\alpha) + (1 - \tau_a) \frac{U_t}{U_{c-a}} \quad (6.10.7)$$

When evaluating  $S$ , the appropriate value of  $(\tau\alpha)_e$  should be used in place of  $(\tau\alpha)$ . As noted below,  $(\tau\alpha)_e$  is on the order of 1% greater than  $(\tau\alpha)$  for a typical single-cover

collector with normal glass. For a collector with low-iron (water-white) glass,  $(\tau\alpha)_e$  and  $(\tau\alpha)$  are nearly identical.

A general analysis for a cover system of  $n$  identical plates yields

$$(\tau\alpha)_e = (\tau\alpha) + (1 - \tau_a) \sum_{i=1}^n a_i \tau^{i-1} \quad (6.10.8)$$

where  $a_i$  is the ratio of the top loss coefficient to the loss coefficient from the  $i$ th cover to the surroundings and  $\tau_a$  is the transmittance of a single cover from Equation 5.2.2. This equation was derived assuming that the transmittance to the  $i$ th cover could be approximated by the transmittance of a single cover raised to the  $i - 1$  power.

For a cover system composed of different materials (e.g., a combination of glass and plastic) the effective transmittance-absorptance product is

$$(\tau\alpha)_e = (\tau\alpha) + (1 - \tau_{a,1})a_1 + (1 - \tau_{a,2})a_2\tau_1 + (1 - \tau_{a,3})a_3\tau_2 + \cdots \quad (6.10.9)$$

where  $\tau_i$  is the transmittance of the cover system above the  $i + 1$  cover and  $\tau_{a,i}$  is the transmittance due to absorption for the  $i$ th cover. The angular dependence of  $(\tau\alpha)_e$  can be evaluated using the proper angular dependency of  $(\tau\alpha)$ ,  $\tau\alpha$  and  $\tau_a$ .

The values of  $a_i$  actually depend upon the plate temperature, ambient temperature, plate emittance, and wind speed. Table 6.10.1 gives values of  $a_i$  for one, two, and three covers and for plate emittances of 0.95, 0.50, and 0.10. These values were calculated using a wind heat transfer coefficient of  $24 \text{ W/m}^2 \text{ }^\circ\text{C}$ , a plate temperature of  $100^\circ\text{C}$ , and an ambient air and sky temperature of  $10^\circ\text{C}$ . The dependence of  $a_i$  on wind speed may be significant. However, lower wind heat transfer coefficients will increase the  $a_i$  values, leading to slightly higher useful energy gains. Since the total amount absorbed by the glass is small, relatively large errors in  $a_i$  will not cause a significant error in the calculation of  $Q_u$ .

Although the value of  $(\tau\alpha)_e$  can be calculated from Equation 6.10.9 with some precision,  $(\tau\alpha)_e$  is seldom more than 1 to 2% greater than  $(\tau\alpha)$ . For a one-cover nonselective collector,  $a_1 = 0.27$ . If the cover absorbs 4% of the incident radiation, that is, the cover is ordinary glass with  $KL$  of about 0.03, then  $(\tau\alpha)_e$  is 1% greater than  $(\tau\alpha)$ . For a one-cover selective collector with this glass, the difference is 0.5%. For a one-cover selective collector with low-iron glass with  $KL$  about 0.01,  $(\tau\alpha)_e$  is about 0.1% greater than  $(\tau\alpha)$ . For a two-cover nonselective system  $(\tau\alpha)_e$  is almost 2% greater

**Table 6.10.1** Constants for Use in Equations 6.10.8 and 6.10.9

Number of Covers	$a_i$	$\varepsilon_p = 0.95$	$\varepsilon_p = 0.50$	$\varepsilon_p = 0.10$
1	$a_1$	0.27	0.21	0.13
2	$a_1$	0.15	0.12	0.09
	$a_2$	0.62	0.53	0.40
3	$a_1$	0.14	0.08	0.06
	$a_2$	0.45	0.40	0.31
	$a_3$	0.75	0.67	0.53



than  $(\tau\alpha)$ . As discussed in Section 5.5,  $(\tau\alpha)$  is approximately 1% greater than the product of  $\tau$  and  $\alpha$ . Since surface radiation properties are seldom known to within 1%, the effective transmittance-absorptance product can be approximated for collectors with ordinary glass by

$$(\tau\alpha)_e \cong 1.02\tau\alpha \quad (6.10.10a)$$

and for collectors with covers with negligible absorption by

$$(\tau\alpha)_e \cong 1.01\tau\alpha \quad (6.10.10b)$$

## 6.11 EFFECTS OF DUST AND SHADING

The effects of dust and shading are difficult to generalize. Data reported by Dietz (1963) show that at the angles of incidence of interest (0 to 50°) the maximum reduction of transmittance of covers due to dirt was 2.7%. From long-term experiments on collectors in the Boston area, Hottel and Woertz (1942) found that collector performance decreased approximately 1% due to dirty glass. In a rainless 30-day experiment in India, Garg (1974) found that dust reduced the transmittance by an average of 8% for glass tilted at 45°. To account for dust in temperate climates, it is suggested that radiation absorbed by the plate be reduced by 1%; in dry and dusty climates, absorbed radiation can be reduced by 2%.

Shading effects can also be significant. Whenever the angle of incidence is off normal, some of the collector structure will intercept solar radiation. Some of this radiation will be reflected to the absorbing plate if the sidewalls are of a high-reflectance material. Hottel and Woertz (1942), based on experiments with two-cover collectors, recommend that the radiation absorbed by the plate be reduced by 3% to account for shading effects if the net (unobstructed) glass area is used in all calculations. The net glass area accounts for the blockage by the supports for the glass. Most modern collectors use one cover, and module areas are larger, both of which reduce shading effects. A reduction of  $S$  of 1% may be a more appropriate correction for these collectors.

### Example 6.11.1

In Example 6.7.1, the effects of dust, shading, and absorption by the cover were all neglected. Reevaluate the daily performance taking these quantities into account. The single glass cover has  $KL = 0.037$  and the plate has a flat-black (nonselective) absorbing surface.

### Solution

This glass ( $KL = 0.037$ ) absorbs approximately 4% of the incident radiation and, according to Table 6.10.1 and Equation 6.10.8, 27% of this is not lost. Thus  $(\tau\alpha)_e$  is  $1.01 \times (\tau\alpha)$ . The effects of dust and shading each reduce the absorbed radiation by 1%; the net effect is to decrease  $S$  by 1%. The table that follows gives new values for  $S$  and the hourly energy gains with  $F_R = 0.8$  and  $U_L = 8.0 \text{ W/m}^2 \text{ }^\circ\text{C}$ . The daily efficiency is reduced from 38 to 37%.

Time	$I_T$ (MJ/m <sup>2</sup> )	$S$ (MJ/m <sup>2</sup> )	$T$ (°C)	$q_u$ (MJ/m <sup>2</sup> )	$\eta$
7–8	0.02	0.00	–11	0.00	0.00
8–9	0.43	0.34	–8	0.00	0.00
9–10	0.99	0.80	–2	0.00	0.00
10–11	3.92	3.22	2	1.70	0.43
11–12	3.36	2.78	3	1.37	0.41
12–1	4.01	3.32	6	1.87	0.47
1–2	3.84	3.15	7	1.76	0.46
2–3	1.96	1.60	8	0.54	0.27
3–4	1.21	0.97	9	0.06	0.05
4–5	<u>0.05</u>	0.00	7	<u>0.00</u>	0.00
	19.79			7.30	
$\eta_{\text{day}} = \frac{7.30}{19.79} = 0.37$					

■

## 6.12 HEAT CAPACITY EFFECTS IN FLAT-PLATE COLLECTORS

The operation of most solar energy systems is inherently transient; there is no such thing as steady-state operation when one considers the transient nature of the driving forces. This observation has led to numerical studies by Klein et al. (1974), Wijesundera (1978), and others on the effects of collector heat capacity on collector performance. The effects can be regarded in two distinct parts. One part is due to the heating of the collector from its early morning low temperature to its final operating temperature in the afternoon. The second part is due to intermittent behavior during the day whenever the driving forces such as solar radiation and wind change rapidly.

Klein et al. (1974) showed that the daily morning heating of the collector results in a loss that can be significant but is negligible for many situations. For example, the radiation on the collector of Example 6.11.1 before 10 AM was 1.44 MJ/m<sup>2</sup>. The calculated losses exceeded this value during this time period because these calculated losses assumed that the fluid entering the collector was at 40°C. In reality, no fluid would be circulating and the absorbed solar energy would heat the collector without reducing the useful energy gain.

The amount of preheating that will occur in a given collector can be estimated by solving the transient energy balance equations for the various parts of the collector. Even though these equations can be developed to almost any desired degree of accuracy, the driving forces such as solar radiation, wind speed, and ambient temperature are usually known only at hour intervals. This means that any predicted transient behavior between the hourly intervals can only be approximate, even with detailed analysis. Consequently, a simplified analysis is warranted to determine if more detailed analysis is desirable.

To illustrate the method, consider a single-cover collector. Assume the absorber plate, the water in the tubes, and one-half of the back insulation are all at the same temperature. Also assume that the cover is at a uniform temperature that is different from the plate

temperature. An energy balance on the absorber plate, water, and one-half of the back insulation yields

$$(mC)_p \frac{dT_p}{dt} = A_c[S - U_{p-c}(T_p - T_c)] \quad (6.12.1)$$

The subscripts  $c$  and  $p$  represent cover and plate;  $U_{p-c}$  is the loss coefficient from the plate to the cover and  $t$  is time. An energy balance on the cover yields

$$(mC)_c \frac{dT_c}{dt} = A_c[U_{p-c}(T_p - T_c) + U_{c-a}(T_a - T_c)] \quad (6.12.2)$$

where  $U_{c-a}$  is the loss coefficient from the cover to the ambient air and  $T_a$  is the ambient temperature. It is possible to solve these two equations simultaneously; however, a great simplification occurs if we assume  $(T_c - T_a)/(T_p - T_a)$  remains constant at its steady-state value. In other words, we must assume that the following relationship holds<sup>8</sup>:

$$U_{c-a}(T_c - T_a) = U_L(T_p - T_a) \quad (6.12.3)$$

Differentiating Equation 6.12.3, assuming  $T_a$  is a constant, we have

$$\frac{dT_c}{dt} = \frac{U_L}{U_{c-a}} \frac{dT_p}{dt} \quad (6.12.4)$$

Adding Equation 6.12.1 to 6.12.2 and using Equation 6.12.4, we obtain the following differential equation for the plate temperature:

$$\left[ (mC)_p + \frac{U_L}{U_{c-a}} (mC)_c \right] \frac{dT_p}{dt} = A_c[S - U_L(T_p - T_a)] \quad (6.12.5)$$

The term in square brackets on the left-hand side represents an effective heat capacity of the collector and is written as  $(mC)_e$ . By the same reasoning, the effective heat capacity of a collector with  $n$  covers would be

$$(mC)_e = (mC)_p + \sum_{i=1}^n a_i (mC)_{c,i} \quad (6.12.6)$$

where  $a_i$  is the ratio of the overall loss coefficient to the loss coefficient from the cover in question to the surroundings. This is the same quantity presented in Table 6.10.1.

If we assume that  $S$  and  $T_a$  remain constant for some period  $t$ , the solution to Equation 6.12.5 is

$$\frac{S - U_L(T_p - T_a)}{S - U_L(T_{p,\text{initial}} - T_a)} = \exp\left(\frac{A_c U_L t}{(mC)_e}\right) \quad (6.12.7)$$

The simplification introduced through the use of Equation 6.12.3 is significant in that the problem of determining heat capacity effects has been reduced to solving one

---

<sup>8</sup>The back and edge losses are assumed to be small.

differential equation. The error introduced by this simplification is difficult to assess for all conditions without solving the set of differential equations. Wijesundera (1978) compared this one-node approximation against a two-node solution and experimental data and found good agreement for single-cover collectors. For two- and three-cover collectors the predicted fractional temperature rise was less than 15% in error.

The collector plate temperature  $T_p$  can be evaluated at the end of each time period by knowing  $S$ ,  $U_L$ ,  $T_a$ , and the collector plate temperature at the beginning of the time period. Repeated application of Equation 6.12.7 for each hour before the collector actually operates serves to estimate the collector temperature as a function of time. An estimate of the reduction in useful gain can then be obtained by multiplying the collector effective heat capacity by the temperature rise necessary to bring the collector to its initial operating temperature.

A similar loss occurs due to collector heat capacity whenever the final average collector temperature in the afternoon exceeds the initial average temperature. This loss can be easily estimated by multiplying collector effective heat capacity times this temperature difference.

Finally, Klein et al. (1974) showed that the effects of intermittent sunshine, wind speed, and ambient air temperature were always negligible for normal collector construction.

### Example 6.12.1

For the collector described in Example 6.11.1, estimate the reduction in useful energy gain due to heat capacity effects. The plate and tubes are copper. The collector has the following specifications:

Plate thickness	0.5 mm
Tube inside diameter	10.0 mm
Tube spacing	150.0 mm
Glass cover thickness	3.5 mm
Back-insulation thickness	50.0 mm

The collector materials have the following properties:

	$C, \text{ kJ/kg } ^\circ\text{C}$	$\rho, \text{ kg/m}^3$
Copper	0.48	8800
Glass	0.80	2500
Insulation	0.80	50

### Solution

Since the collector operates with a constant inlet temperature, only the early morning heating will influence the useful gain. The collector heat capacity includes the glass, plate, tubes, water in tubes, and insulation. The heat capacity of the glass is

$$0.0035 \text{ m} \times 2500 \text{ kg/m}^3 \times 0.8 \text{ kJ/kg } ^\circ\text{C} = 7 \text{ kJ/m}^2 ^\circ\text{C}$$

For the plate, tubes, water in tubes, and insulation, the heat capacities are 2, 1, 2, and 2 kJ/m<sup>2</sup> °C, respectively. The insulation exposed to the ambient remains near ambient

temperature so that the effective insulation heat capacitance is one-half of its actual value. The effective collector capacity is thus  $2 + 1 + 2 + 1 + 0.27 \times 7 = 8 \text{ kJ/m}^2 \text{ }^\circ\text{C}$ . From Equation 6.12.7, the collector temperature at the end of the period from 8 to 9, assuming that the initial collector temperature is equal to the ambient temperature, is

$$\begin{aligned} T_p^+ &= T_a + \frac{S}{U_L} \left[ 1 - \exp \left( -\frac{A_c U_L t}{(mC)_e} \right) \right] \\ &= -8 + \frac{0.34 \times 10^6 / 3600}{8} \left[ 1 - \exp \left( -\frac{8 \times 3600}{8000} \right) \right] = 3^\circ\text{C} \end{aligned}$$

For the second-hour period, the initial temperature is  $3^\circ\text{C}$  and the temperature at 10:00 AM becomes

$$\begin{aligned} T_p^+ &= T_a + \frac{S}{U_L} - \left[ \frac{S}{U_L} - (T_i - T_a) \right] \exp \left( -\frac{A_c U_L t}{(mC)_e} \right) \\ &= -2 + \frac{0.79 \times 10^6 / 3600}{8} - \left[ \frac{0.79 \times 10^6 / 3600}{8} - (3 + 2) \right] \exp \left( -\frac{8 \times 3600}{8000} \right) \\ &= 25^\circ\text{C} \end{aligned}$$

By 10:00 AM, the collector has been heated to within  $15^\circ\text{C}$  of its operating temperature at  $40^\circ\text{C}$ . The reduction in useful gain is the energy required to heat the collector the last  $15^\circ\text{C}$ , or  $120 \text{ kJ/m}^2$ . Thus the useful energy gain from 10 to 11 should be reduced from  $1.65$  to  $1.53 \text{ MJ/m}^2$ . Note that this collector responds quickly to the various changes as the exponential term in the preceding calculation was small. [The collector “time constant” is  $(mC)_e / A_c U_L$ , which is approximately 15 min. The time constant with liquid flowing is on the order of 1 to 2 min, as shown in Section 6.17.1] ■

## 6.13 LIQUID HEATER PLATE GEOMETRIES

In the preceding sections, we have considered only one basic collector design: a sheet-and-tube solar water heater with parallel tubes on the back of the plate. There are many different designs of flat-plate collectors, but fortunately it is not necessary to develop a completely new analysis for each situation. Hottel and Whillier (1958), Whillier (1977), and Bliss (1959) have shown that the generalized relationships developed for the tube-and-sheet case apply to most collector designs. It is necessary to derive the appropriate form of the collector efficiency factor  $F'$ , and Equations 6.7.5 and 6.7.6 then can be used to predict the thermal performance. Under some circumstances, the loss coefficient  $U_L$  will have to be modified slightly. In this and the next section the analyses of the basic design are applied to other configurations.

Figure 6.13.1 shows seven different liquid heater designs. The first three have parallel tubes (risers) thermally fastened to a plate and connected at the top and bottom by headers to admit and remove the liquid. The first of these is the basic design discussed in the previous sections; the important equations for  $F$ ,  $F'$ , and  $U_L$  are shown. The design shown in (b) is the same, except that the tubes are mounted on top of the plate rather than under it.




Figure 6.13.1 (a–g) Liquid heater designs and collector efficiency factor equations.




Figure 6.13.1 (a–g) (Continued)

A design shown in (c) has the tubes centered in the plane of the plate forming an integral part of the plate structure.

In types (d), (e), and (f), long, narrow, flat absorbers are mounted inside evacuated glass tubes.<sup>9</sup> Convective heat losses from collectors are usually significant, but they can be reduced or eliminated by evacuating the space between the absorber and the cover. As the pressure is reduced to a moderately low level, convection ceases but conduction through the gas remains constant until the mean free path of the molecules is on the order of the characteristic spacing. There are flat-plate collectors built with seals at the edges, posts to support the cover, and evacuated spaces above (and below) the absorber plate. However, most practical designs have been based on evacuated tubes, which provide the structural strength to withstand the pressure differences.

The collector type shown in (d) is constructed with a single fin and tube with glass-to-metal seals at both ends; with this configuration, bellows are used to accommodate differential expansion of the glass envelope and the metal fin and tube. This configuration is similar to type (a) with a single riser tube.

Liquid flow in the type (e) collector is “down and back,” with a U-tube joining the two conduits. Two glass-to-metal seals are provided at the same end of the tube. The two flow conduits down and back are in close proximity; with this arrangement, it is necessary that the thermal resistance between the two conduits be high, that is, that the two streams be thermally decoupled. If the resistance were zero, the two conduits would be at the same temperature, and collection would be zero. Ortabasi and Buehl (1975) constructed such a collector with the plate split into two parts to avoid the coupling problem. If coupling is not significant, the analysis of type (e) collectors is basically the same as for the types (a), (b), or (c) even though the inlet and outlet manifolds are at the same end of the tubes.

Heat pipes can be used to extract energy from evacuated collectors, as shown in Figure 6.13.1(f). In the arrangement shown, the portion of the heat pipe in contact with the fin is the boiler portion. The condenser is a short section in good thermal contact with the pipe or duct through which the fluid to be heated is pumped; the condenser is shown

<sup>9</sup>The first evacuated tubular collector was built by Speyer (1965). The design shown in Figure 6.13.1(e) is similar to Speyer’s.

fastened with a conducting clamp to the pipe carrying the fluid to be heated. These designs have the advantage that they have only one seal, at one end of the tube, and the fin and heat pipe are free to expand inside the evacuated space. In contrast to most other flat-plate collectors, the temperature gradients along the length of the heat pipe will be small, but there will be gradients along the header from one heat pipe connector to the next.

There are important differences between flat-plate collectors with flat covers such as types (a) to (c) and cylindrical covers such as types (d) to (f). The fin width (or diameter) must be less than the tube diameter, so the absorbing surface will have projected areas less than that of the tube. The tubes are usually closely packed. The planes of the absorbers may be different from the plane of the tube arrays. The angular dependence of solar transmittance will be different from that of a flat cover.<sup>10</sup> Manifold designs vary widely, and manifold losses may be important. And metal-to-glass seals must be provided.

Other important collector geometries exist for which  $F'$  and  $F_R$  cannot easily be expressed in a simple form. The risers in (a), (b), and (c) are all parallel tubes; an alternative design is the serpentine tube arrangement shown in Figure 6.13.1(g). If a thermal break is made midway between the tubes, for example, by cutting through the absorber plate, then the collector can be analyzed as a conventional collector. If a break is not provided, reduced performance can be expected and a more complicated analysis is necessary.

Abdel-Khalik (1976) analytically solved the case of a single bend, and Zhang and Lavan (1985) obtained solutions for three and four bends. For a single bend, Zhang and Lavan show that the solution for  $F_R$  is given by Equation 6.13.1 in terms of three dimensionless parameters  $F_1$ ,  $F_2$ , and  $F_3$  (the parameters  $F_4$ ,  $F_5$ , and  $F_6$  are functions of  $F_2$  only):

$$F_R = F_1 F_3 F_5 \left[ \frac{2F_4}{F_6 \exp \left[ -\sqrt{1 - F_2^2/F_3} \right] + F_5} - 1 \right] \quad (6.13.1)$$

The parameters  $F_1$  through  $F_6$  are given by

$$F_1 = \frac{\kappa}{U_L W} \frac{\kappa R(1 + \gamma)^2 - 1 - \gamma - \kappa R}{[\kappa R(1 + \gamma) - 1]^2 - (\kappa R)^2} \quad (6.13.2a)$$

$$F_2 = \frac{1}{\kappa R(1 + \gamma)^2 - 1 - \gamma - \kappa R} \quad (6.13.2b)$$

$$F_3 = \frac{\dot{m} C_p}{F_1 U_L A_c} \quad (6.13.2c)$$

$$F_4 = \left( \frac{1 - F_2^2}{F_2^2} \right)^{1/2} \quad (6.13.2d)$$

$$F_5 = \frac{1}{F_2} + F_4 - 1 \quad (6.13.2e)$$

<sup>10</sup>See Section 6.19 for further information on angular dependence of  $(\tau\alpha)$  of evacuated-tube collectors.



$$F_6 = 1 - \frac{1}{F_2} + F_4 \quad (6.13.2f)$$

and

$$\kappa = \frac{(k\delta U_L)^{1/2}}{\sinh[(W - D)(U_L/k\delta)^{1/2}]} \quad (6.13.2g)$$

$$\gamma = -2 \cosh \left[ (W - D) \left( \frac{U_L}{k\delta} \right)^{1/2} \right] - \frac{DU_L}{\kappa} \quad (6.13.2h)$$

$$R = \frac{1}{C_b} + \frac{1}{\pi D_i h_{fi}} \quad (6.13.2i)$$

Zhang and Lavan (1985) point out that Equation 6.13.1 is valid for any number of bends if the group  $\dot{m}C_p/F_1U_LA_c$  is greater than about 1.0. For smaller values of this group, their paper should be consulted.

### Example 6.13.1

Determine the heat removal factor for a collector with a serpentine tube having the following specifications [see Figure 6.13.1(g)]:

Length of one serpentine segment $L$	1.2 m
Distance between tubes $W$	0.1 m
Number of segments $N$	6
Plate thickness $\delta$	1.5 mm
Tube outside diameter $D$	7.5 mm
Tube inside diameter $D_i$	6.5 mm
Plate thermal conductivity $k$	211 W/m °C
Overall loss coefficient $U_L$	5 W/m <sup>2</sup> °C
Fluid mass flow rate $\dot{m}$	0.014 kg/s
Fluid specific heat $C_p$	3352 J/kg °C
Fluid-to-tube heat transfer coefficient $h_{fi}$	1500 W/m <sup>2</sup> °C
Bond conductance $C_b$	$\infty$ W/m °C

### Solution

From Equation 6.13.2(g):

$$\kappa = \frac{(211 \times 0.0015 \times 5)^{1/2}}{\sinh \left[ (0.1 - 0.0075) \left( \frac{5}{211 \times 0.0015} \right)^{1/2} \right]} = 3.346 \text{ W/m } ^\circ\text{C}$$

From Equation 6.13.2(h):

$$\gamma = -2 \cosh \left[ (0.1 - 0.0075) \left( \frac{5}{211 \times 0.0015} \right)^{1/2} \right] - \frac{0.0075 \times 5}{3.346} = -2.148$$

From Equation 6.13.2(i):

$$R = \frac{1}{\pi \times 0.0065 \times 1500} = 0.0326 \text{ m } ^\circ\text{C/W}$$

Then  $kR = 3.346 \times 0.0326 = 0.1091$ . From Equation 6.13.2(a):

$$F_1 = \frac{3.346}{5 \times 0.1} \frac{0.1091(1 - 2.148)^2 - 1 + 2.148 - 0.1091}{[0.1091(1 - 2.148) - 1]^2 - (0.109)^2} = 6.310$$

From Equation 6.13.2(b):

$$F_2 = \frac{1}{1.1827} = 0.846$$

The collector area  $NWL = 6 \times 0.1 \times 1.2 = 0.72 \text{ m}^2$ . From Equation 6.13.2(c) the dimensionless capacitance rate is

$$F_3 = \frac{0.014 \times 3352}{6.309 \times 5 \times 0.72} = 2.066$$

From Equations 6.13.2(d) to 6.13.2(f),  $F_4 = 0.631$ ,  $F_5 = 0.814$ , and  $F_6 = 0.449$ . Finally from Equation 6.13.1,


$$\frac{F_R}{F_1} = 0.148 \quad \text{and} \quad F_R = 0.148 \times 6.310 = 0.93 \quad \blacksquare$$

The most common liquid solar heater is uncovered and used for low-temperature applications such as swimming pool heating. These collectors are typically made from plastics such as stabilized polyolefin. The parallel-flow channels either are in direct contact with one another or are connected by very short fins. The short fins are necessary due to the low thermal conductivity of the plastic material. The same basic equations apply for these collectors, but the lack of a cover means that estimating the collector loss coefficient is very uncertain.

## 6.14 AIR HEATERS

Figure 6.14.1 shows six designs for air heating collectors. Also on this figure are equations for the collector efficiency factors that have been derived for these geometries. For (e) and (f), the L f overlapped glass plates and the matrix air heater, the analyses to date have not put the results in a generalized form. For these two situations, it is necessary to resort to numerical techniques for analysis. Selcuk (1971) has analyzed the overlapped glass plate system. Chiou et al. (1965), Hamid and Beckman (1971), and Neeper (1979) have studied the matrix-type air heaters. Hollands and Shewen (1981) have analyzed the effects of flow passage geometry on  $h_{fi}$  and  $F'$ .


To illustrate the procedure for deriving  $F'$  and  $U_L$  for an air heater, we derive the equation for type (a) of Figure 6.14.1. Although type (b) is the more common design for an air heater, type (a) is somewhat more complicated to analyze. Also, type (a) is similar



$$U_L = \frac{(U_b + U_t)(h_1 h_2 + h_1 h_r + h_2 h_r) + U_b U_t (h_1 + h_2)}{h_1 h_r + h_2 U_t + h_2 h_r + h_1 h_2}$$

$$F' = \frac{h_r h_1 + h_2 U_t + h_2 h_r + h_1 h_2}{(U_t + h_r + h_1)(U_b + h_2 + h_r) - h_r^2}$$


$$h_r = \frac{\sigma(T_1^2 + T_2^2)(T_1 + T_2)}{\frac{1}{\epsilon_1} + \frac{1}{\epsilon_2} - 1}$$



$$U_L = U_t + U_b$$

$$F' = \frac{1}{1 + \frac{U_L}{h_1 + \frac{1}{\frac{1}{h_2} + \frac{1}{h_r}}}}$$


$h_r = \text{same as (a)}$



$$F'_0 = F' \text{ of (b)}$$

$$F' = F'_0 \left[ 1 + \frac{1 - F'_0}{\frac{F'_0}{F_p} + \frac{W h_1}{2 W_2 h_2 F_F}} \right]$$


$F_p = \text{fin efficiency of plate}$   
 $F_F = \text{fin efficiency of fin}$




$$U_L = U_t + U_b$$

$U_t$  is based on projected area

$F' = \text{same as (b) with } h_1 \text{ replaced by } h_1 / \sin \phi/2$



See Selcuk (1971)



See Hamid & Beckman (1971)

**Figure 6.14.1 (a–f)** Air heater designs and efficiency factors. In (b), (c), and (d) it is assumed that back losses are from a source at the same temperature as top losses.

to a collector-storage wall in a passive heating system. A schematic of the collector and thermal network is shown in Figure 6.14.2. The derivation follows that suggested by Jones (1979).

At some location along the flow direction the absorbed solar energy heats up the plate to a temperature  $T_p$ . Energy is transferred from the plate to the ambient air at  $T_a$  through the back loss coefficient  $U_b$ , to the fluid at  $T_f$  through the convection heat transfer coefficient  $h_2$ , and to the bottom of the cover glass through the linearized radiation heat transfer coefficient  $h_r$ . Energy is transferred to the cover glass from the fluid through the heat transfer coefficient  $h_1$ . Energy is lost to the ambient air through the combined convection and radiation coefficient  $U_t$ . Note that  $U_t$  can account for multiple covers.

Energy balances on the cover, the plate, and the fluid yield the following equations:

$$U_t(T_a - T_c) + h_r(T_p - T_c) + h_1(T_f - T_c) = 0 \quad (6.14.1)$$

$$S + U_b(T_a - T_p) + h_2(T_f - T_p) + h_r(T_c - T_p) = 0 \quad (6.14.2)$$

$$h_1(T_c - T_f) + h_2(T_p - T_f) = q_u \quad (6.14.3)$$

These three equations are solved so that the useful gain is expressed as a function of  $U_t$ ,  $h_1h_2$ ,  $h_r$ ,  $T_f$ , and  $T_a$ . In other words,  $T_p$  and  $T_c$  must be eliminated. The algebra is somewhat tedious and only a few of the intermediate steps are given. Solving the first two equations for  $T_p - T_f$  and  $T_c - T_f$ ,

$$T_p - T_f = \frac{S(U_t + h_r + h_1) - (T_f - T_a)(U_t h_r + U_t U_b + U_b h_r + U_b h_1)}{(U_t + h_r + h_1)(U_b + h_2 + h_r) - h_r^2} \quad (6.14.4)$$

$$T_c - T_f = \frac{Sh_r - (T_f - T_a)(U_t h_2 + U_t U_b + U_t h_r + U_b h_r)}{(U_t + h_r + h_1)(U_b + h_2 + h_r) - h_r^2} \quad (6.14.5)$$

Substituting these into the equation for  $q_u$  and rearranging, we obtain

$$q_u = F'[S - U_L(T_f - T_a)] \quad (6.14.6)$$




Figure 6.14.2 Type (a) solar air heater and thermal network.

where

$$F' = \frac{h_r h_1 + U_t h_2 + h_2 h_r + h_1 h_2}{(U_t + h_r + h_1)(U_b + h_2 + h_r) - h_r^2} \quad (6.14.7)$$

and

$$U_L = \frac{(U_b + U_t)(h_r h_1 + h_2 h_r + h_1 h_2) + U_b U_t (h_1 + h_2)}{h_r h_1 + U_t h_2 + h_2 h_r + h_1 h_2} \quad (6.14.8)$$

Note that  $U_L$  for this collector is not just the top loss coefficient in the absence of back losses but also accounts for heat transfer between the absorbing surface and the bottom of the cover. Whenever the heat removal fluid is in contact with a transparent cover,  $U_L$  will be modified in a similar fashion.

The equations for type (b) air heaters are derived in a similar manner, but the working fluid does not contact the cover system. For simplicity, back losses are assumed to occur from the absorber plate temperature. The following example shows calculation of the performance of a type (b) air heater.

### Example 6.14.1

Calculate the outlet temperature and efficiency of a single-cover type (b) air heater of Figure 6.14.1 at a  $45^\circ$  slope when the radiation incident on the collector is  $900 \text{ W/m}^2$ . The plate-to-cover spacing is 20 mm and the air channel depth is 10 mm. The collector is 1 m wide by 4 m long. The absorber plate is selective with an emittance of 0.1 and the effective transmittance-absorptance product is 0.82. The inlet air temperature is  $60^\circ\text{C}$ , the ambient air temperature is  $10^\circ\text{C}$ , and the mass flow rate of the air is  $0.056 \text{ kg/s}$ . The wind heat transfer coefficient is  $10 \text{ W/m}^2 \text{ }^\circ\text{C}$  and the sum of the back and edge loss coefficients is  $1.0 \text{ W/m}^2 \text{ }^\circ\text{C}$  (see Example 6.4.3). The emittances of the surfaces of the inside of the duct,  $\varepsilon_1$  and  $\varepsilon_2$ , are both 0.95.

### Solution

From Figure 6.4.4(e) with an assumed average plate temperature of  $70^\circ\text{C}$ , the top loss coefficient is  $3.3 \text{ W/m}^2 \text{ }^\circ\text{C}$ , and with the back and edge loss coefficient of  $1.0 \text{ W/m}^2 \text{ }^\circ\text{C}$ , the overall loss coefficient is  $4.3 \text{ W/m}^2 \text{ }^\circ\text{C}$ . The radiation coefficient between the two air duct surfaces is estimated by assuming a mean radiant temperature equal to the mean fluid temperature. With an estimated mean fluid temperature of  $70^\circ\text{C}$ ,<sup>11</sup> we have, from Equations 3.10.2 and 3.10.3,

$$h_r = \frac{4\sigma \bar{T}^3}{1/\varepsilon_1 + 1/\varepsilon_2 - 1} = \frac{4 \times 5.67 \times 10^{-8} \times 343^3}{2/0.95 - 1} = 8.3 \text{ W/m}^2 \text{ }^\circ\text{C}$$

The heat transfer coefficients between the air and two duct walls will be assumed to be equal. The characteristic length is the hydraulic diameter, which for flat plates is twice the

<sup>11</sup>Section 6.9 suggests a first estimate of the mean fluid temperature as  $20^\circ\text{C}$  above the inlet fluid temperature. Here we have used a smaller increment to illustrate the iterative solution to the problem.

plate spacing. The Reynolds number, at an assumed average fluid temperature of 70°C, is

$$\text{Re} = \frac{\rho V D_h}{\mu} = \frac{\dot{m} D_h}{A_f \mu} = \frac{0.056(2 \times 0.01)}{(0.01 \times 1)2.04 \times 10^{-5}} = 5490$$

The length-to-diameter ratio is

$$\frac{L}{D_h} = \frac{4}{2 \times 0.01} = 200$$

Since  $\text{Re} > 2100$  and  $L/D_h$  is large, the flow is turbulent and fully developed. From Equation 3.14.6

$$\text{Nu} = 0.0158(5490)^{0.8} = 15.5$$

The heat transfer coefficients inside the duct,  $h_1$  and  $h_2$ , are then

$$h = 15.5 \frac{k}{D_h} = \frac{15.5 \times 0.029}{2 \times 0.01} = 22 \text{ W/m}^2 \text{ } ^\circ\text{C}$$

From Figure 6.14.1(b), with  $h_1 = h_2 = h$ ,

$$F' = \left[ 1 + \frac{U_L}{h + [(1/h) + (1/h_r)]^{-1}} \right]^{-1} = \left[ 1 + \frac{4.3}{22 + \left( \frac{1}{22} + \frac{1}{8.3} \right)} \right]^{-1} = 0.87$$

The dimensionless capacitance rate is

$$\frac{\dot{m} C_p}{A_c U_L F'} = \frac{0.056 \times 1009}{4 \times 4.3 \times 0.87} = 3.78$$

From Equation 6.7.5 or Figure 6.7.1,

$$F'' = 3.78[1 - e^{-1/3.78}] = 0.88$$

or

$$F_R = F'' F' = 0.88 \times 0.87 = 0.77$$

The useful gain, from Equation 6.7.6, is

$$Q_u = 4 \times 0.77[900 \times 0.82 - 4.3(60 - 10)] = 1610 \text{ W}$$

The outlet temperature is

$$T_o = T_i + \frac{Q_u}{\dot{m} C_p} = 60 + \frac{1610}{0.056 \times 1009} = 89^\circ\text{C}$$

It is now necessary to check the assumed mean fluid and absorber plate temperatures. The mean plate temperature is found from Equation 6.9.4,

$$T_{pm} = 60 + \frac{1610/4}{4.3 \times 0.77} (1 - 0.77) = 88^\circ\text{C}$$

and the mean fluid temperature is found from Equation 6.9.2,

$$T_{fm} = 60 + \frac{1610/4}{4.3 \times 0.77} (1 - 0.88) = 74^\circ\text{C}$$

Since the initial guess of the plate and fluid temperatures was  $70^\circ\text{C}$ , another iteration is necessary. With a new assumed average plate temperature of  $88^\circ\text{C}$ ,  $U_t = 3.4 \text{ W/m}^2 \text{ }^\circ\text{C}$  and  $U_L = 4.4 \text{ W/m}^2 \text{ }^\circ\text{C}$ . The radiation heat transfer coefficient between the two duct surfaces is  $8.7 \text{ W/m}^2 \text{ }^\circ\text{C}$  (with  $\bar{T}$  assumed to be the same as  $T_{fm}$ , or  $348 \text{ K}$ ), the Reynolds number is 5400, and the heat transfer coefficient is  $23 \text{ W/m}^2 \text{ }^\circ\text{C}$ . The parameters  $F'$ ,  $F''$ , and  $F_R$  are unchanged so that the useful energy gain remains at  $1610 \text{ W}$ . Note that even though the first iteration used an estimate of the plate temperature that was  $18^\circ\text{C}$  in error, only minor changes resulted from the second iteration.

The efficiency is

$$\eta = \frac{Q_u}{A_c G_T} = \frac{1610}{4 \times 900} = 0.45, 45\% \quad \blacksquare$$

A novel uncovered air heating collector has been studied both analytically and experimentally by Kutscher et al. (1993), Kutscher (1994), and Summers (1995). These transpired systems consist of a dark (solar-absorbing) building façade that is perforated and sealed around the edges. A fan draws outside air in through the perforations and into the space between the absorber and the building wall. The air is heated as it passes over the front surface, through the holes, and along the backside of the collector. The heated air is then ducted into a building or into another heater to bring the temperature to the desired level. These systems are often very large, and as a result the convection loss from the surface is very small (if the suction flow rate per unit area is sufficiently large, convection losses only occur at the edges). Consequently, the collector losses consist primarily of radiation to the surroundings. The collector useful gain is the difference between the absorbed radiation and the radiation losses:

$$Q_u = A_c [S - \varepsilon \sigma F_{c-g} (T_c^4 - T_a^4) - \varepsilon \sigma (1 - F_{c-g}) (T_c^4 - T_{\text{sky}}^4)] \quad (6.14.9)$$

where  $F_{c-g}$  is the view factors from collector to ground (equal to  $\frac{1}{2}$  for a vertical collector) and  $\varepsilon$  is the collector infrared emittance. The collector temperature is found from an effectiveness relating the collector useful energy gain to the maximum possible energy gain:

$$\frac{Q_u}{\dot{m} c_p (T_c - T_a)} = 1 - \exp(-NTU) = 1 - \exp \left[ -\frac{h (A_c - A_{\text{holes}})}{\dot{m} C_p} \right] \quad (6.14.10)$$

where  $\dot{m}$  is the mass flow rate through the collector holes,  $A_{\text{holes}}$  is the area of the holes, and  $h$  is the heat transfer coefficient found from Equation 3.16.8. The collector useful energy gain  $Q_u$  can be eliminated between Equations 6.14.9 and 6.14.10, resulting in a single nonlinear equation for the collector temperature  $T_c$ . With  $T_c$  known the useful energy gain

can be determined from either Equation 6.14.9 or 6.14.10 and the outlet temperature can be calculated from

$$Q_u = \dot{m} c_p (T_o - T_a) \quad (6.14.11)$$

### Example 6.14.2

Determine the useful energy gain, the collector efficiency, the outlet temperature, and the pressure drop of a transpired collector 10 m wide by 3 m high. The holes are close packed (equilateral triangles) with a spacing between holes of 18 mm and a hole diameter of 1.6 mm. The mass flow rate through the collector per unit of collector area is 0.05 kg/m<sup>2</sup> s. The collector surface is painted with a nonselective paint with an infrared emittance and a solar absorptance of 0.90. The ambient temperature is 300 K and the sky temperature is 292 K. The solar energy incident on the surface is 800 W/m<sup>2</sup>.

### Solution

At a temperature of 300 K,  $\rho = 1.176 \text{ kg/m}^3$ ,  $k = 0.0257 \text{ W/m K}$ ,  $c_p = 1007 \text{ J/kg K}$ , and  $\mu = 1.857 \times 10^{-5} \text{ kg/m s}$ . For equilateral triangles with holes at the corners one-half of a hole is associated with each triangle. The porosity  $\sigma_p$ , the ratio of hole area to triangle area (which is the same as the area of all holes to the collector area), is then

$$\sigma_p = \frac{A_{\text{hole}}}{A_{\text{triangle}}} = \frac{A_{\text{holes}}}{A_c} = \frac{\pi}{2\sqrt{3}} \left( \frac{D}{P} \right)^2 = 0.907 \left( \frac{0.0016}{0.018} \right)^2 = 0.00717$$

resulting in  $A_{\text{holes}} = 0.215 \text{ m}^2$ . The velocity through the holes is then

$$V_{\text{holes}} = \frac{0.05 \times A_c}{\rho A_{\text{holes}}} = \frac{0.05 \times 30}{1.176 \times 0.215} = 5.93 \text{ m/s}$$

and the Reynolds number is

$$\text{Re}_D = \frac{\rho V_{\text{holes}} D}{\mu} = \frac{1.176 \times 5.93 \times 0.0016}{0.00001857} = 601$$

The heat transfer coefficient is found from Equation 3.16.8:

$$h = \frac{0.0257}{0.0016} 2.75 \left( \frac{0.018}{0.0016} \right)^{-1.2} 601^{0.43} = 37.9 \text{ W/m}^2 \text{ K}$$

resulting in

$$\text{NTU} = \frac{h(A_c - A_{\text{holes}})}{\dot{m} c_p} = \frac{37.9(30 - 0.215)}{0.05 \times 30 \times 1007} = 0.747$$

The view factor from the collector to the ground is 0.5. From Equations 6.14.9 and 6.14.10 a nonlinear equation for the collector temperature is

$$S - \epsilon \sigma \left[ T_c^4 - \frac{(T_a^4 + T_{\text{sky}}^4)}{2} \right] = \frac{\dot{m}}{A_c} c_p (T_c - T_a) (1 - e^{-\text{NTU}})$$



Everything but  $T_c$  is known. Solving,  $T_c = 321.4$  K. The useful gain from Equation 6.14.9 is

$$\begin{aligned} Q_u &= A_c \left[ S - \varepsilon \sigma \left( T_c^4 - \frac{T_a^4 + T_{\text{sky}}^4}{2} \right) \right] \\ &= 30 \left[ 0.9 \times 800 - 0.90 \times 5.67 \times 10^{-8} \left( 321.4^4 - \frac{300^4 + 292^4}{2} \right) \right] = 17,000 \text{ W} \end{aligned}$$

and the outlet temperature from Equation 6.14.11 is

$$T_o = T_a + \frac{Q_u}{\dot{m} c_p} = 300 + \frac{17,000}{0.05 \times 30 \times 1007} = 311.3 \text{ K} = 38^\circ\text{C}$$

The collector efficiency is the useful energy gain divided by the incident solar, or

$$\eta = \frac{17,000}{30 \times 800} = 0.71$$

The approach velocity is  $V_{\text{app}} = \dot{m}/(\rho A_c) = 0.05/1.176 = 0.0425$  m/s. The pressure drop across the plate is found from Equation 3.16.9:

$$\begin{aligned} \Delta p &= \frac{\rho V_{\text{app}}^2}{2} 6.82 \left( \frac{1 - \sigma_p}{\sigma_p} \right)^2 \text{Re}_D^{-0.236} \\ &= \frac{1.176 \times 0.0425^2}{2} 6.82 \left( \frac{1 - 0.00717}{0.00717} \right)^2 601^{-0.236} = 307 \text{ Pa} \end{aligned}$$

This pressure drop and other pressure losses in the flow path must be made up by the system fan to produce the desired airflow rate. ■

Transpired collectors have some operating characteristics that are generally opposite to those of conventional collectors. Kutscher (1994) shows that wind will increase the heat transfer coefficient somewhat leading to increased collector performance. Kutscher also provides a correlation for the heat transfer coefficient that includes the effect of wind. The plate thermal conductivity has little influence on the collector performance so that the plate could be made from metal or plastic. And finally, as the ambient temperature decreases, the heat loss by radiation decreases, resulting in an increase of the collector efficiency (a conventional air heater heating outside air will also exhibit an increase in efficiency with decreasing ambient temperature).

Kutscher (2005) suggests the following design guidelines for transpired solar collectors: The minimum approach velocity should be 0.020 m/s and the minimum hole pressure drop should be 25 Pa.

## 6.15 MEASUREMENTS OF COLLECTOR PERFORMANCE

The first detailed experimental study of the performance of flat-plate collectors, by Hottel and Woertz (1942), was based on energy balance measurements on an array of collectors

on an experimental solar-heated building. The analysis was basically similar to that of the previous sections, but with performance calculations based on mean plate temperature rather than on inlet temperature and  $F_R$ . They developed a correlation for thermal losses which was a forerunner of Equation 6.4.9. Their experimental data were for time periods of many days, and calculated and measured performance agreed within approximately 13% before effects of dust and shading were taken into account.

Tabor (1958) modified the Hottel and Woertz loss calculation by use of new correlations for convection transfer between parallel planes and values of emittance of glass lower than those used by Hottel and Woertz. These modifications permitted estimation of loss coefficients for collectors with selective surfaces. Tabor found equilibrium (no fluid flow) temperatures from experiment and theory for a particular collector to be 172 and 176°C, indicating satisfactory agreement. He also recalculated the results of Hottel and Woertz using his modified heat loss coefficients and found calculated and measured losses for two sets of conditions to be 326 versus 329 W/m<sup>2</sup> °C and 264 versus 262 W/m<sup>2</sup> °C, again indicating excellent agreement. Moore et al. (1974) made extensive comparisons of the performance of a flat-plate liquid heating collector with results predicted by use of the original Hottel and Woertz method. The operating conditions were similar to those of Hottel and Woertz, and agreement was good.

As shown by these examples and by many other measurements, there is substantial experimental evidence that the energy balance calculation methods developed in this chapter are very satisfactory representations of the performance of most flat-plate collectors.

## 6.16 COLLECTOR CHARACTERIZATIONS

Based on the theory outlined in the previous sections and the laboratory measurements that support the theory, several methods for characterizing collectors can be noted. These characterizations, or models, have various numbers of parameters and are thus of varying complexity, and they serve different purposes. At one extreme very detailed models include all of the design features of the collector (plate thickness, tube spacing, number of covers and cover material, back and edge insulation dimensions, etc.). At the other extreme is a model that includes only two parameters, one that shows how the collector absorbs radiation and the other how it loses heat. (The simplest model would be a one-parameter model, a single efficiency; this is essentially useless as the efficiency is dependent on the collector operating temperature and ambient temperature, so that in most collector applications the efficiency changes with time.)

For collector design (i.e., specification of the details of the design, such as plate thickness, tube spacing, etc.) and for detailed understanding of how collectors function, detailed models are appropriate. The most complete steady-state model includes all of the design parameters entering the terms in Equation 6.7.6, that is, those that determine  $F_R$ ,  $U_L$ , and  $(\tau\alpha)_{av}$ . To this can be added an analysis of transient behavior, which can be a single lumped-capacitance analysis (like that of Section 6.12) or a multinode analysis. For most flat-plate collectors, the single-capacitance model is adequate, and for many it may not be necessary to consider thermal capacitance at all.

For use in simulations of thermal processes, less complex models are usually adequate. Several of these have been used [e.g., in the simulation program *TRNSYS* (2012) and by Wirsum (1988)]; in these models, one, two, or all of the three major terms in Equation 6.7.6

may be considered as variables<sup>12</sup>: an angular-dependent  $(\tau\alpha)_{av}$ , a temperature-dependent  $U_L$ , and a temperature-dependent  $F_R$ .

The definition of instantaneous efficiency, combined with Equation 6.7.6, provides the basis for simulation models:

$$\eta_i = \frac{Q_u}{A_c G_T} = \frac{F_R [G_T (\tau\alpha)_{av} - U_L (T_i - T_a)]}{G_T} \quad (6.16.1)$$

If most of the radiation is beam radiation that is nearly normal to the collector and if  $F_R$  and  $U_L$  do not vary greatly in the range of operation of the collector,  $F_R(\tau\alpha)_n$  and  $F_R U_L$  are two parameters that describe how the collector works, where  $F_R(\tau\alpha)_n$  is an indication of how energy is absorbed and  $F_R U_L$  is an indication of how energy is lost. These two parameters constitute the simplest practical collector model.

A third parameter describes the effects of the angle of incidence of the radiation. An **incidence angle modifier** for beam radiation can be defined as the ratio  $(\tau\alpha)_b/(\tau\alpha)_n$ ; it is a function of  $\theta_b$ . As shown in the next section, the incidence angle modifier can be approximately represented in terms of a single coefficient  $b_o$ , the third parameter in this simple collector model.

We now have a three-parameter model [ $F_R(\tau\alpha)_n$ ,  $F_R U_L$ , and  $b_o$ ] for a flat-plate collector which takes into account the major phenomena associated with collector operation. This model will be utilized in Part III of this book on design of systems.

Other models can be written which account for temperature dependence of  $U_L$  and  $F_R$  and for complex angular relationships for  $(\tau\alpha)_{av}$ . Thus there is a range of collector thermal performance models that vary in their level of detail. The selection of a model depends on the purposes at hand. If the collector operates over restricted ranges of conditions, which is true of many space and water heating applications, then the simplest model is quite adequate. If operating conditions are highly variable, more complex models may be needed.

## 6.17 COLLECTOR TESTS: EFFICIENCY, INCIDENCE ANGLE MODIFIER, AND TIME CONSTANT

This section is concerned with how collector tests are done and how test data are presented in useful ways. In the next section, test data are presented for typical flat-plate collectors of the types shown in Sections 6.13 and 6.14. The following two sections discuss methods for manipulating test data to get them in forms that are needed for designing solar energy systems.

In the mid-1970s many new collector designs appeared on the commercial market. Needs developed for standard tests to provide collector operating data. Information was needed on how a collector absorbs energy, how it loses heat, the effects of angle of incidence of solar radiation, and the significant heat capacity effects. In response to this need in the United States, the National Bureau of Standards (NBS; Hill and Kusuda, 1974) devised a test procedure [see also Hill and Streed (1976, 1977) and Hill et al. (1979)]<sup>13</sup>

<sup>12</sup>In Equation 6.7.6  $S$  can be written as  $G_T(\tau\alpha)_{av}$ .

<sup>13</sup>European test practices are discussed in detail by Gillett and Moon (1985).

which has been modified by ASHRAE. The ASHRAE/ANSI 93–2003 (2003) standard procedure is the basis for this section. A standard test procedure has been adopted by the European Union (EU; EN 12975–1:2000 and EN 12975–1:2001). Other countries have either developed their own test standard or adopted either the ASHRAE or the EU standard.

Collector thermal performance tests can be considered in three parts. The first is determination of instantaneous efficiency with beam radiation nearly normal to the absorber surface. The second is determination of effects of angle of incidence of the solar radiation. The third is determination of collector time constant, a measure of effective heat capacity.

The basic method of measuring collector performance is to expose the operating collector to solar radiation and measure the fluid inlet and outlet temperatures and the fluid flow rate. The useful gain is then

$$Q_u = \dot{m}C_p(T_o - T_i) \quad (6.17.1)$$

In addition, radiation on the collector, ambient temperature, and wind speed are also recorded. Thus two types of information are available: data on the thermal output and data on the conditions producing that thermal performance. These data permit the characterization of a collector by parameters that indicate how the collector absorbs energy and how it loses energy to the surroundings.

Equation 6.7.6, which describes the thermal performance of a collector operating under steady conditions, can be written in terms of the incident radiation:

$$Q_u = A_c F_R [G_T (\tau\alpha)_{av} - U_L (T_i - T_a)] \quad (6.17.2)$$

Here  $(\tau\alpha)_{av}$  is a transmittance-absorptance product that is weighted according to the proportions of beam, diffuse, and ground-reflected radiation on the collector, as discussed in Section 5.9. Testing standards generally require that during a collector test the beam normal radiation be high and the diffuse fraction be low. Consequently, the  $(\tau\alpha)$  determined under test conditions is for conditions under which a collector provides most of its useful output, that is, when radiation is high and most of the incident radiation is beam radiation. It is customary to drop the subscript *av* from Equation 6.17.2 and treat the resulting  $(\tau\alpha)$  as representative of the beam component.

Equations 6.17.1 and 6.17.2 can be used to define an instantaneous efficiency:

$$\eta_i = \frac{Q_u}{A_c G_T} = F_R (\tau\alpha) - \frac{F_R U_L (T_i - T_a)}{G_T} \quad (6.17.3)$$

and

$$\eta_i = \frac{\dot{m}C_p (T_o - T_i)}{A_c G_T} \quad (6.17.4)$$

These equations are the basis of the standard test methods outlined in this section.

Other equations are also used. European practice is to base collector test results on  $T_{f,av}$ , the arithmetic average of the fluid inlet and outlet temperatures.<sup>14</sup> Thus

$$\eta_i = F_{av} (\tau\alpha) - \frac{F_{av} U_L (T_{f,av} - T_a)}{G_T} \quad (6.17.5)$$

---

<sup>14</sup>Methods for converting between  $F_R$  and  $F_{av}$  are given in Section 6.19.

ASHRAE 93–2003 sets forth three standard test procedures for liquid heaters and one for air heaters. A schematic of one of these, a closed-loop system for liquid heating collectors, is shown in Figure 6.17.1. Although details differ, the essential features of all of the procedures can be summarized as follows:

1. Means are provided to feed the collector with fluid at a controlled inlet temperature; tests are made over a range of inlet temperatures.
2. Solar radiation is measured by a pyranometer on the plane of the collector.
3. Means of measuring flow rate, inlet and outlet fluid temperatures, and ambient conditions are provided.
4. Means are provided for measurements of pressure and pressure drop across the collector.


The ASHRAE method for air collectors includes the essential features of those for liquid heaters, with the addition of detailed specifications of conditions relating to airflow, air mixing, air temperature measurements, and pressure drop measurements.

Measurements may be made either outdoors or indoors. Indoor tests are made using a solar simulator, that is, a source producing radiant energy that has spectral distribution, intensity, uniformity in intensity, and direction closely resembling that of solar radiation. Means must also be provided to move air to produce wind. [See Vernon and Simon (1974), Simon (1976), and Gillett (1980).] There are not many test facilities of this kind available, the results are not always comparable to those of outdoor tests, and most collector tests are done outdoors. Gillett (1980) has compared the results of outdoor tests with those of mixed indoor and outdoor tests and notes that diffuse-fraction and longwave radiation exchange (which are not the same indoors and outdoors) can affect the relative results of the tests.


The general test procedure is to operate the collector in the test facility under nearly steady conditions, measure the data to determine  $Q_u$  from Equation 6.17.1, and measure  $G_T$ ,  $T_i$ , and  $T_a$ , which are needed for analysis based on Equation 6.17.3. Of necessity, this means outdoor tests are done in the midday hours on clear days when the beam radiation is high and usually with the beam radiation nearly normal to the collector. Thus the transmittance-absorptance product for these test conditions is approximately the normal-incidence value and is written as  $(\tau\alpha)_n$ .

Tests are made with a range of inlet temperature conditions. To minimize effects of heat capacity of collectors, tests are usually made in nearly symmetrical pairs, one before and one after solar noon, with results of the pairs averaged. Instantaneous efficiencies are determined from  $\eta = \dot{m}C_p(T_o - T_i)/A_c G_T$  for the averaged pairs and are plotted as a function of  $(T_i - T_a)/G_T$ . A sample plot of data taken at five test sites under conditions meeting ASHRAE specifications is shown in Figure 6.17.2.

If  $U_L$ ,  $F_R$ , and  $(\tau\alpha)_n$  were all constant, the plots of  $\eta_i$ , versus  $(T_i - T_a)/G_T$  would be straight lines with intercept  $F_R(\tau\alpha)_n$  and slope  $-F_R U_L$ . However, they are not, and the data scatter. From Section 6.4 it is clear that  $U_L$  is a function of temperature and wind speed, with decreasing dependence as the number of covers increases. Also,  $F_R$  is a weak function of temperature. And some variations of the relative proportions of beam, diffuse, and ground-reflected components of solar radiation will occur. Thus scatter in the data are to be expected, because of temperature dependence, wind effects, and angle-of-incidence



**Figure 6.17.1** Closed-loop test setup for liquid heating flat-plate collectors. From ASHRAE Standard 93–2003 (2003), with permission.



**Figure 6.17.2** Experimental collector efficiency data measured for a liquid heating flat-plate collector with one cover and a selective absorber. Sixteen points are shown for each of five test sites. The curve represents the theoretical characteristic derived from points calculated for the test conditions. Adapted from Streed et al. (1979).

variations. In spite of these difficulties, long-time performance estimates of many solar heating systems, collectors can be characterized by the intercept and slope [i.e., by  $F_R(\tau\alpha)_n$  and  $F_R U_L$ ].

### Example 6.17.1

A water heating collector with an aperture area of  $4.10 \text{ m}^2$  is tested by the ASHRAE method, with beam radiation nearly normal to the plane of the collector. The following information comes from the test:

$Q_u \text{ (MJ/h)}$	$G_T \text{ (W/m}^2\text{)}$	$T_i \text{ (}^\circ\text{C)}$	$T_a \text{ (}^\circ\text{C)}$
9.05	864	18.2	10.0
1.98	894	84.1	10.0

What are  $F_R(\tau\alpha)_n$  and  $F_R U_L$  for this collector based on aperture area?

### Solution


For the first data set,

$$\eta_i = \frac{9.05 \times 1000}{864 \times 3.6 \times 4.10} = 0.71$$

and

$$\frac{T_i - T_a}{G_T} = \frac{18.2 - 10.0}{864} = 0.0095 \text{ m}^2\text{C/W}$$

For the second data set,  $\eta_i = 0.15$  and  $(T_i - T_a)/G_T = 0.083 \text{ m}^2\text{C/W}$ . These two points are shown on the plot.



The slope is

$$\frac{0.71 - 0.15}{0.0095 - 0.083} = 7.62 \text{ W/m}^2 \text{ } ^\circ\text{C}$$

Then  $F_R U_L = -\text{slope} = 7.62 \text{ W/m}^2\text{C}$ . The intercept of the line of the  $\eta_i$  axis is 0.78, which is  $F_R(\tau\alpha)_n$ . (In practice, tests produce multiple data points and a least-squares fit would be used to find the best constants.) ■

The collector area appears in the denominator of the definition of  $\eta_i$ . Various areas have been used: gross area, glass area, aperture area, unshaded absorber plate area, and so on. Gross collector area is defined as the total area occupied by a collector module, that is, the total area of a collector array divided by the number of modules in the array. Aperture area is defined as the unobstructed cover area or the total cover area less the area of cover supports. The unshaded absorber plate area is also sometimes used. ASHRAE 93–2003 uses the gross collector area while European practice is to use the aperture area. It does not matter which area is used as long as it is specified clearly so that the same area basis can be used in subsequent design calculations.

In Example 6.17.1, if the collector has a gross area of  $4.37 \text{ m}^2$ ,  $F_R(\tau\alpha)_n$  and  $F_R U_L$  based on the gross area would be the numbers based on the aperture area multiplied by  $4.10/4.37$ .

Additional methods of treating test data may be encountered. For example, Cooper and Dunkle (1981) assume a linear temperature dependence of the overall loss coefficient of the form

$$U_L F' = a + b(T - T_a) \quad (6.17.6)$$

resulting in the following expression for the instantaneous efficiency:

$$\eta_i = F'(\tau\alpha) - a \frac{\Delta T_m}{G_T} - b \frac{\Delta T_m^2}{G_T} \quad (6.17.7)$$

where  $\Delta T_m$  is the true mean fluid temperature difference.<sup>15</sup> Cooper and Dunkle show that replacing the true mean fluid temperature with the arithmetic average of inlet and

<sup>15</sup>The symbols  $\eta_o$ ,  $a_1$ , and  $a_2$  are sometimes used in place of  $F'(\tau\alpha)$ ,  $a$ , and  $b$ .



outlet temperature,  $(T_i + T_o)/2 - T_a$ , results in very small errors for practical collector designs.<sup>16</sup> This formulation assumes  $a$  and  $b$  are constants at a particular wind speed; wind speed variations can dominate the temperature effect for one-cover collectors. Additional parameters are needed if wind speed dependence is considered. For plotting, a convenient form of Equation 6.17.7 is obtained if  $b$  is replaced by a new (assumed to be constant) parameter,  $b' = bG_T$ , so that the instantaneous efficiency is a second-order function of  $\Delta T_m/G_T$ . The value of  $G_T$  in the parameter  $b'$  is typically assigned a value of  $800 \text{ W/m}^2$ . In the United States common practice when using Equation 6.17.7 is to replace  $\Delta T_m$  by  $T_{in} - T_a$  and to replace  $F'$  by  $F_R$ . The values of the parameters  $a$  and  $b$  are different in this representation.<sup>17</sup>

Proctor (1984) and Perers (1993) propose empirical efficiency equations that take into account a wide range of conditions such as wind speed, temperature-dependent loss coefficient, beam and diffuse fractions, radiation sink temperature, and thermal capacitance.

The second important aspect of collector testing is the determination of effects of angle of incidence of the incident radiation. An **incidence angle modifier**  $K_{\tau\alpha}$  can be introduced into Equation 6.17.2. The dependence of  $(\tau\alpha)$  on the angle of incidence of radiation on the collector varies from one collector to another, and the standard test methods include experimental estimation of this effect. In the discussion leading to Equation 6.17.3 it was noted that the requirement of a clear test day means that the experimental value of  $(\tau\alpha)$  will be essentially the same as  $(\tau\alpha)_b$ . The incidence angle modifier for beam radiation incident at angle  $\theta_b$  is written as

$$K_{\tau\alpha}(\theta_b) = \frac{(\tau\alpha)_b}{(\tau\alpha)_n} \quad (6.17.8)$$

Then for clear days

$$Q_u = A_c F_R [G_T K_{\tau\alpha}(\tau\alpha)_n - U_L(T_i - T_a)] \quad (6.17.9)$$


A general expression has been suggested by Souka and Safwat (1966) for angular dependence of  $K_{\tau\alpha}$  for collectors with flat covers as

$$K_{\tau\alpha} = 1 - b_o \left( \frac{1}{\cos \theta} - 1 \right) \quad (6.17.10)$$

where  $b_o$  is a constant called the **incidence angle modifier coefficient**. (Note that this equation follows the ASHRAE 93–2003 convention and  $b_o$  is generally a positive number, which is opposite to the older ASHRAE standard.) Figure 6.17.3 shows an incidence angle modifier  $K_{\tau\alpha}$  for a typical single-cover collector plotted as a function of both  $\theta$  and  $1/\cos \theta - 1$ . Also shown is the fit using Equation 6.17.10 where  $b_o = 0.136$ . At incidence angles less than about  $60^\circ$ , Equation 6.17.10 is a useful approximation to account for

<sup>16</sup>Cooper and Dunkle (1981) provide exact analytical equations for the instantaneous efficiency. The use of the average fluid temperature is discussed further in Section 6.19. Also note that the last term in Equation 6.17.7 is  $\Delta T_m^2/G_T$  and not  $(\Delta T_m/G_T)^2$ .

<sup>17</sup>See Section 6.19 for converting between the two representations.



**Figure 6.17.3** Incidence angle modifier as function of  $\theta$  and  $1/\cos \theta - 1$  for a collector with a flat cover.

angle-of-incidence effects. At large angles of incidence, the linear relationship no longer applies, but most of the useful energy absorbed in a collector system will be at times when  $\theta < 60^\circ$ .

ASHRAE 93–2003 recommends that experimental determination of  $K_{\tau\alpha}$  be done by positioning a collector in indoor tests so that  $\theta$  is  $0^\circ$ ,  $30^\circ$ ,  $45^\circ$ , and  $60^\circ$ . For outdoor tests it is recommended that pairs of tests symmetrical about solar noon be done early and late in the day, when angles of incidence of beam radiation are approximately  $30^\circ$ ,  $45^\circ$ , and  $60^\circ$ . The European standard suggests that the single angle of  $50^\circ$  be used.

Tesfamichael and Wäckelgård (2000) show that adding an exponent  $n$  to the term in brackets [i.e.,  $K_{\tau\alpha} = 1 - b_o(1/\cos \theta - 1)^n$ ] and determining both  $b_o$  and  $n$ , the fit can be significantly improved and the range of validity can be greater than  $60^\circ$ .

When predicting the performance of a collector with Equation 6.7.6, it is necessary to consider separately the beam, diffuse, and ground-reflected radiation components. The beam radiation is treated as outlined in this section. The diffuse and ground-reflected radiation are considered to be at the appropriate angles of incidence from Figure 5.4.1. The incidence angle modifier function determined for the beam component is used for the diffuse and ground-reflected radiation at their effective angles. This approach is appropriate since collector tests are made under clear-sky conditions when the fraction of beam is high so the data are indicative of the effects of the angle of incidence of beam radiation. The  $S$  in Equation 6.7.6, written in terms of the beam, diffuse, and ground-reflected incidence

angle modifiers, is then


$$S = I_b R_b K_{\tau\alpha,b}(\tau\alpha)_n + I_d K_{\tau\alpha,d}(\tau\alpha)_n \left( \frac{1 + \cos \beta}{2} \right) + \rho_g I K_{\tau\alpha,g}(\tau\alpha)_n \left( \frac{1 - \cos \beta}{2} \right) \quad (6.17.11)$$

Evacuated tubular collectors of the types shown in Figure 6.13.1(d–f) have covers that are optically nonsymmetrical. As recommended by McIntire and Read (1983), biaxial incidence angle modifiers are used. Figure 6.17.4 shows the two planes of the modifiers, the transverse and the longitudinal planes. An overall incidence angle modifier is taken as the product of the two:


$$K_{\tau\alpha} = (K_{\tau\alpha})_t (K_{\tau\alpha})_l \quad (6.17.12)$$

The third aspect of collector testing is the determination of the heat capacity of a collector in terms of a **time constant**. The time constant is defined as the time required for a fluid leaving a collector to change through  $(1 - 1/e) = (0.632)$  of the total change from its initial to its ultimate steady value after a step change in incident radiation or inlet fluid temperature. The ASHRAE standard test procedure outlines two procedures for estimating the time constant. The first is to operate a collector at nearly steady conditions with inlet fluid temperature controlled at or very near ambient temperature. The solar radiation is abruptly shut off by shading or repositioning the collector and the decrease in outlet temperature (with the pump running) is noted as a function of time. The time  $t$  at which the equality for Equation 6.17.12 is reached is the time constant of the collector:

$$\frac{T_{o,t} - T_i}{T_{o,\text{init}} - T_i} = \frac{1}{e} = 0.368 \quad (6.17.13)$$



**Figure 6.17.4** The planes of the evacuated tube incidence angle modifiers. From Theunissen and Beckman (1985).



**Figure 6.17.5** Time-temperature plot for a flat-plate air heater showing temperature drop on sudden reduction of the solar radiation on the collector to zero. The time constant is the time for the temperature to drop to  $1/e$  of the total potential drop, that is, for  $B/A$  to reach 0.368. Adapted from Hill et al. (1979).

where  $T_{o,t}$  is the outlet temperature at time  $t$  and  $T_{o,init}$  is the outlet temperature when the solar radiation is interrupted. A typical time-temperature history is shown in Figure 6.17.5.

An alternative method for measuring a collector time constant is to test a collector not exposed to radiation (i.e., at night, indoors, or shaded) and impose a step change in the temperature of the inlet fluid from a value well above ambient (e.g., 30°C) to a value very near ambient. Equation 6.17.13 also applies to this method (which may not give results identical with the first method).

There are other test procedures and analyses which produce more detailed information about collectors. Proctor (1984) provides a detailed discussion of evaluation of instruments used in tests and the sensitivity of test results to instrumental errors. He shows that uncertainties in radiation measurements dominate the uncertainties. He develops collector efficiency equations based on a mean fluid temperature  $T_{f,m}$  that includes nonlinearities in  $\Delta T$  and separately accounts for ambient and sky temperatures. The result is a six-constant model with various combinations of the constants applicable to various types of collectors.

Gillett and Moon (1985) review European practices and standards for collector testing. Proctor and James (1985) note that there can be as much as  $\pm 10\%$  variations in the measured values of  $F_R(\tau\alpha)_n$  in production runs of collectors with selective surfaces.


## 6.18 TEST DATA

For purposes of illustrating the kinds of data that are available and the differences that exist among collectors, test results for several flat-plate collectors are shown.<sup>18</sup> These data are based on the ASHRAE 93–2003 standard procedures. Figure 6.18.1 shows test points and correlations for a double-glazed liquid heater. The points and solid curve are based on the aperture area of the collector, that is, the unobstructed glass area. The dashed curve shows the correlation based on the gross area of the collector. In some of the tests the intensity of incident radiation  $G_T$  was reduced by a shading screen to obtain points over a range of values of  $(T_i - T_a)/G_T$ .

Figure 6.18.2 shows a set of five curves for different collector designs. There are obvious differences in these collector characteristics. The selection of one or another of these collectors would depend on the operating conditions, that is, on the range of values of  $(T_i - T_a)/G_T$  that are expected in an application, and on costs. The fact that one collector may be more efficient than another in part or all of its range of operating conditions does not mean that it necessarily is a better collector in an economic context; as will be pointed out later, collectors must be evaluated in terms of their performance in systems and ultimately in terms of costs.


Hill et al. (1979) have measured the effects of angle of incidence of radiation on the collector of Figure 6.18.1; these are shown in Figure 6.18.3.

Figure 6.18.4. shows characteristic curves for two air heating flat-plate collectors, one of them operating at two different airflow rates. These curves are based on gross collector area. It is characteristic of most air heaters that they are operated at relatively




**Figure 6.18.1** Test points for a liquid heater based on collector aperture area. Also shown is the correlation based on gross collector area. The collector is double glazed with antireflective coatings on three glass surfaces and has a black chrome selective surface. Gross collector area is  $1.66 \text{ m}^2$  and aperture area is  $1.40 \text{ m}^2$ . Adapted from Hill et al. (1979).


<sup>18</sup>Solar collector performance test data are available on the World Wide Web. For example, in the United States see the Solar Rating and Certification Corporation and its Directory of SRCC Certified Solar Collector Ratings (updated periodically) at [www.solar-rating.org](http://www.solar-rating.org).



**Figure 6.18.2** Characteristics of five collectors: (a) one-cover liquid heater with selective absorber; (b) one-cover liquid heater with moderately selective black paint absorber; (c) one-cover air heater with black nickel absorber; (d) glass vacuum tube liquid heater with sputtered aluminum nitride absorber; (e) unglazed liquid heater with flat-black absorber. Details of plate thickness, tube spacing, etc., vary among these collectors. The slope of (e) will be very sensitive to wind speed. Data from *Directory of SRCC Certified Solar Collector Ratings*.




**Figure 6.18.3** Data on incidence angle modifier for a double-glazed water heating collector. The conditions of operation were collector tilted  $25^\circ$  to south, ambient temperature  $34^\circ\text{C}$ , wind speed  $4.5\text{ m/s}$ , and insolation  $230$  to  $830\text{ W/m}^2$  of which an estimated 20% was diffuse. Adapted from Hill et al. (1979).



**Figure 6.18.4** Characteristic curves for two air heaters: (a) one-cover, selective absorber, operated at 25 liters/m<sup>2</sup> s; (b) same collector, operated at 10 liters/m<sup>2</sup> s; (c) one-cover selective black chrome absorber, operated at 20 liters/m<sup>2</sup> s.

low capacitance rates, have low heat transfer coefficients between absorber surface and fluid, and show relatively low values of  $F_R$ . The low flow rates are used to minimize pressure drop in the collectors. The collector represented by (a) is operated at higher than normal airflow rates. (Also, low airflow rates through pebble bed storage units used with air heaters in space heating applications result in high thermal stratification, which has operating advantages. See Chapters 9 and 13.)

Test data for flat-plate collectors in evacuated tubes are not as neatly categorized as those for collectors with flat covers, as there is more variability in their design and they may operate in higher temperature ranges where temperature dependence of losses is more important. Figure 6.18.5 shows  $\eta_i$ -versus- $(T_i - T_a)/G_T$  data for an evacuated-tube



**Figure 6.18.5** Test curves, operating points, and straight-line fit to the operating points for a Sanyo evacuated tube collector of the type shown in Figure 6.13.1(d), with tubes close packed, flat absorbers, and tubes oriented on horizontal axis. Adapted from International Energy Agency (1986).

collector with flat absorbers and close-packed tubes. There is a spread of the data and a dependence on radiation level that is not evident in ordinary flat-plate collectors.

As noted, the presence of cylindrical covers dictates that the optical properties of these collectors will not be symmetrical. For collectors with tubes on the sloped axis, if the slope is approximately the same as the latitude, the component of the angle of incidence in the longitudinal plane will vary with declination, but not greatly, and the major angle-of-incidence effects will be in the transverse plane.

## 6.19 THERMAL TEST DATA CONVERSION

Data from collector tests in the United States are usually expressed in terms of  $\eta_i$  and  $(T_i - T_a)/G_T$  as shown in Figures 6.18.2. Practice in some other countries is to express  $\eta_i$  as a function of  $(T_{av} - T_a)/G_T$ . Test data for air systems are sometimes expressed as  $\eta_i$  as a function of  $(T_o - T_a)/G_T$ . In this section, methods are presented for converting test results from one format to another.

If test data are plotted as  $\eta_i$  versus  $(T_{av} - T_a)/G_T$ , where  $T_{av}$  is the arithmetic average of inlet and outlet fluid temperatures, the equation of the straight line is<sup>19</sup>

$$\eta_i = F_{av}(\tau\alpha)_n - F_{av}U_L \frac{T_{av} - T_a}{G_T} \quad (6.19.1)$$

If the flow rate of the fluid is known, the intercept  $F_{av}(\tau\alpha)_n$  and slope  $-F_{av}U_L$  of the curve of Equation 6.19.1 are related to  $F_R U_L$  and  $F_R(\tau\alpha)_n$ . Eliminating  $\eta$  and  $T_o$  from Equations 6.17.3 to 6.17.5 (Beckman et al., 1977), these relationships are found to be

$$F_R(\tau\alpha)_n = F_{av}(\tau\alpha)_n \left( 1 + \frac{A_c F_{av} U_L}{2\dot{m} C_p} \right)^{-1} \quad (6.19.2a)$$

$$F_{av}(\tau\alpha)_n = F_R(\tau\alpha)_n \left( 1 - \frac{A_c F_R U_L}{2\dot{m} C_p} \right)^{-1} \quad (6.19.2b)$$

and

$$F_R U_L = F_{av} U_L \left( 1 + \frac{A_c F_{av} U_L}{2\dot{m} C_p} \right)^{-1} \quad (6.19.3a)$$

$$F_{av} U_L = F_R U_L \left( 1 - \frac{A_c F_R U_L}{2\dot{m} C_p} \right)^{-1} \quad (6.19.3b)$$

For air heater test data that are presented as plots of  $\eta_i$ , versus  $(T_o - T_a)/G_T$ , the intercept  $F_o(\tau\alpha)_n$  and slope  $-F_o U_L$  of these curves can be converted to  $F_R U_L$  and

---

<sup>19</sup>When the fluid flow rate is high,  $F_{av}$ ,  $F'$ , and  $F_R$  are nearly the same.



$F_R(\tau\alpha)_n$  by the following:

$$F_R(\tau\alpha)_n = F_o(\tau\alpha)_n \left( \frac{1 + A_c F_o U_L}{\dot{m} C_p} \right)^{-1} \quad (6.19.4a)$$

$$F_o(\tau\alpha)_n = F_R(\tau\alpha)_n \left( 1 - \frac{A_c F_R U_L}{\dot{m} C_p} \right)^{-1} \quad (6.19.4b)$$

$$F_R U_L = F_o U_L \left( 1 + \frac{A_c F_o U_L}{\dot{m} C_p} \right)^{-1} \quad (6.19.5a)$$

$$F_o U_L = F_R U_L \left( 1 - \frac{A_c F_R U_L}{\dot{m} C_p} \right)^{-1} \quad (6.19.5b)$$

### Example 6.19.1

What are  $F_R U_L$  and  $F_R(\tau\alpha)_n$  for the two-cover air heater having  $F_o U_L = 3.70 \text{ W/m}^2 \text{ }^\circ\text{C}$  and  $F_o(\tau\alpha)_n = 0.64$ ? The volumetric flow rate per unit area is  $10.1 \text{ liters/m}^2 \text{ s}$ .

### Solution

For air at  $20^\circ\text{C}$ ,  $C_p = 1006 \text{ J/kg}$  and  $\rho = 1.204 \text{ kg/m}^3$  or  $0.001204 \text{ kg/liter}$ . Then

$$\frac{A_c F_o U_L}{\dot{m} C_p} = \frac{3.7}{10.1 \times 0.001204 \times 1006} = 0.302$$

Then from Equations 6.19.4a and 6.19.5a,


$$F_R(\tau\alpha)_n = \frac{0.64}{1 + 0.302} = 0.49$$

$$F_R U_L = \frac{3.7}{1 + 0.302} = 2.84 \text{ W/m}^2 \text{ }^\circ\text{C}$$

■

Figure 6.19.1 shows linear test results for an air heating collector plotted in all three of the common formats. The three curves have a common intercept at  $\eta_i = 0$ . For air heaters the differences in the three methods of plotting are substantial; for liquid heaters operating at normal to high flow rates, the differences among the three are less.

The collector area that is used to define the measured efficiency with Equation 6.17.4 is not the same in all standards. In the United States the convention is to use the gross collector area—the area that takes space on a roof. In some standards the aperture area or absorber area or other defined areas are used. For example in a collector panel consisting of a number of separated evacuated tubes without a back reflector, one standard uses the area inside the glass tubes. It is not difficult to change the performance parameters from one area to another since all that is required is to know the area used in the test and the desired (usually gross) area. The parameters in Equations 6.7.6 or 6.17.7 are then converted by a simple area ratio.



**Figure 6.19.1** Efficiency curves for an air heating flat-plate collector plotted as functions of  $T_i$ ,  $T_{av}$ , and  $T_o$ .

Sometimes a second-order collector equation is known but a linear equation is desired. The simplest way to perform this conversion is numerically and is illustrated in Example 6.19.2.

### Example 6.19.2

A collector manufacturer supplies the following data based upon Equation 6.17.7 when used with the aperture area:  $F'(\tau\alpha)_n = 0.736$ ,  $a = 4.32 \text{ W/m}^2 \text{ K}$ ;  $b = 0.0062 \text{ W/m}^2 \text{ K}^2$ ; test volumetric flow rate 150 liters/h of 33.3% glycol-water mixture; aperture area  $1.395 \text{ m}^2$ ; length 2.15 m and width 0.935 m. Convert these test data to the linear collector equation (Equation 6.7.6) based upon the gross collector area (the  $f$ -chart design method of Chapter 20 uses Equation 6.7.6).

### Solution

The gross area is  $2.15 \times 0.935 = 2.010 \text{ m}^2$  so that the ratio of aperture to gross area is  $1.395/2.010 = 0.694$ . The collector parameters based upon the gross area are then  $F'(\tau\alpha)_n = 0.736 \times 0.694 = 0.511$ ,  $a = 4.32 \times 0.694 = 3.00 \text{ W/m}^2 \text{ K}$ ,  $b = 0.0062 \times 0.694 = 0.0043 \text{ W/m}^2 \text{ K}^2$ . The linear fit and the second-order fit can have the same efficiency and  $\Delta T/G$  at only two conditions so it is necessary to choose two values of  $\Delta T/G$  where the two curves intersect. It is also necessary to choose a value of the incident radiation so that the second-order collector equation is a function of  $\Delta T/G$ . Values of  $\Delta T/G$  of 0.05 and 0.12 and  $G = 800 \text{ W/m}^2$  are reasonable choices, leading to two equations with two unknowns:

$$F'(\tau\alpha)_n - F'U_L \times 0.05 = 0.511 - 3.00 \times 0.05 - 0.0043 \times 800 \times 0.05^2$$

$$F'(\tau\alpha)_n - F'U_L \times 0.12 = 0.511 - 3.00 \times 0.12 - 0.0043 \times 800 \times 0.12^2$$

which leads to  $F'(\tau\alpha)_n = 0.531$  and  $F'U_L = 3.58 \text{ W/m}^2 \text{ }^\circ\text{C}$ . Equations 6.19.2a and 6.19.3a are used to convert to the desired parameters of  $F_R(\tau\alpha)_n$  and  $F_R U_L$ . The density and specific heat of the collector fluid are  $1.027 \text{ kg/liter}$  and  $3771 \text{ J/kg } ^\circ\text{C}$  so that

$$F_R(\tau\alpha)_n = 0.531 \times \left(1 + \frac{2.010 \times 3.58}{2 \times 150 \times 1.027 \times 3771/3600}\right)^{-1} = 0.519$$

$$F_R U_L = 3.58 \times \left(1 + \frac{2.010 \times 3.58}{2 \times 150 \times 1.027 \times 3771/3600}\right)^{-1} = 3.50 \text{ W/m}^2 \text{ }^\circ\text{C}$$

■

## 6.20 FLOW RATE CORRECTIONS TO $F_R(\tau\alpha)_n$ AND $F_R U_L$

Ideally, test data should be measured at flow rates corresponding to those to be used in applications. If a collector is to be used at a flow rate other than that of the test conditions, an approximate analytical correction to  $F_R(\tau\alpha)_n$  and  $F_R U_L$  can be obtained from the ratios of values of  $F_R$  determined by use of Equation 6.7.4 or 6.7.5. Assume that the only effect of changing flow rate is to change the temperature gradient in the flow direction and that changes in  $F'$  due to changes of  $h_{fi}$  with flow rate are small (reasonable assumptions for liquid heating collectors operating at normal flow rates). The ratio  $r$  by which  $F_R U_L$  and  $F_R(\tau\alpha)_n$  are to be corrected is then given by

$$r = \frac{F_R U_L|_{\text{use}}}{F_R U_L|_{\text{test}}} = \frac{F_R(\tau\alpha)_n|_{\text{use}}}{F_R(\tau\alpha)_n|_{\text{test}}} \quad (6.20.1)$$

$$r = \frac{\frac{\dot{m}C_p}{A_c F' U_L} [1 - \exp(-A_c F' U_L / \dot{m}C_p)]|_{\text{use}}}{\frac{\dot{m}C_p}{A_c F' U_L} [1 - \exp(-A_c F' U_L / \dot{m}C_p)]|_{\text{test}}} \quad (6.20.2)$$

or

$$r = \frac{\frac{\dot{m}C_p}{A_c} [1 - \exp(-A_c F' U_L / \dot{m}C_p)]|_{\text{use}}}{F_R U_L|_{\text{test}}} \quad (6.20.3)$$

To use these equations, it is necessary to know or estimate  $F' U_L$ . For the test conditions, it can be calculated from  $F_R U_L$ . Rearranging Equation 6.7.4 and solving for  $F' U_L$  yields

$$F' U_L = -\frac{\dot{m}C_p}{A_c} \ln \left(1 - \frac{F_R U_L A_c}{\dot{m}C_p}\right) \quad (6.20.4)$$

For liquid collectors,  $F' U_L$  calculated for the test conditions is approximately equal to  $F' U_L$  at use conditions and can be used in both numerator and denominator of Equation 6.20.2.

**Example 6.20.1**

The water heating collector of Example 6.17.1 is to be used at a flow rate of 0.020 kg/s rather than at the 0.040 kg/s at which the test data were obtained. Estimate the effect of reducing the flow rate on  $F_R(\tau\alpha)_n$  and  $F_R U_L$ .

**Solution**

Equation 6.20.2 will be used but Equation 6.20.3 could have been used. First, calculate  $F'U_L$  for the test conditions from Equation 6.20.4:

$$F'U_L = -\frac{0.040 \times 4187}{4.10} \ln \left( 1 - \frac{7.62 \times 4.10}{0.040 \times 4187} \right) = 8.43 \text{ W/m}^2 \text{ } ^\circ\text{C}$$

Then  $r$  is obtained with Equation 6.20.2. For use conditions,

$$\frac{\dot{m}C_p}{A_c F'U_L} = \frac{0.020 \times 4187}{4.10 \times 8.43} = 2.42$$

For test conditions

$$\frac{\dot{m}C_p}{A_c F'U_L} = \frac{0.040 \times 4187}{4.10 \times 8.43} = 4.85$$

So

$$r = \frac{2.42[1 - \exp(-1/2.42)]}{4.85[1 - \exp(-1/4.85)]} = 0.91$$

Then at the reduced flow rate

$$F_R(\tau\alpha)_n = 0.78 \times 0.91 = 0.71$$

$$F_R U_L = 7.62 \times 0.91 = 6.91 \text{ W/m}^2 \text{ } ^\circ\text{C}$$

■

The procedure used in Example 6.20.1 should not be used for air heating collectors or for liquid heating collectors where there is a strong dependence of  $h_{fi}$  and thus  $F'$  on flow rate. The defining equation for  $F'$  (Equation 6.5.18 or its equivalent from Figure 6.13.1 or 6.14.1) must be used at both use and test flow rates to estimate the effect of flow rate on  $F'$ . The collector tests do not provide adequate information with which to do this calculation, and theory must be used to estimate  $F'$  at use and test conditions.

**Example 6.20.2**

Test evaluations of the air heater of Example 6.14.1 give  $F_R(\tau\alpha)_n = 0.63$  and  $F_R U_L = 3.20 \text{ W/m}^2 \text{ } ^\circ\text{C}$  when the flow rate is 0.056 kg/s through the 4.00-m<sup>2</sup> collector. The conditions of the tests and of anticipated use (other than flow rate) are as outlined in Example 6.14.1. What are  $F_R(\tau\alpha)_n$  and  $F_R U_L$  if the flow rate through the collector is reduced to 0.028 kg/s?

**Solution**

The effects of flow rate on  $F'$  need to be checked for this situation, since the convection coefficient from duct to air will change significantly. This requires calculation of the convection and radiation coefficients  $h_{fi}$  and  $h_r$  as was done in Example 6.14.1 and recalculation for the reduced flow rate. The details of that example are not repeated here. It will be assumed that  $h_r$  and  $U_L$  are not greatly changed from the test to the use conditions, so  $h_r = 8.3 \text{ W/m}^2 \text{ }^\circ\text{C}$  and  $U_L = 4.3 \text{ W/m}^2 \text{ }^\circ\text{C}$ .

When the flow rate is reduced, the Reynolds number becomes

$$\text{Re} = \frac{0.028(2 \times 0.01)}{(0.01 \times 1)2.04 \times 10^{-5}} = 2740$$

This is still in the turbulent (transition) range, so

$$\text{Nu} = 0.0158(2740)^{0.8} = 8.9$$

and

$$h_{fi} = \frac{8.09 \times 0.029}{2 \times 0.01} = 12.9 \text{ W/m}^2 \text{ }^\circ\text{C}$$

The value of  $F'$  is calculated at the reduced flow rate in the same way it was calculated in Example 6.14.1 for the test conditions:

$$F' = \left[ 1 + \frac{4.3}{12.9 + (1/12.9 + 1/8.3)^{-1}} \right]^{-1} = 0.81$$

With the test condition calculation of  $F' = 0.87$  and the use condition  $F' = 0.81$ , we can use Equation 6.20.2. For test conditions,

$$\frac{\dot{m}C_p}{A_c F' U_L} = 3.69$$

For use conditions,

$$\frac{\dot{m}C_p}{A_c F' U_L} = \frac{0.028 \times 1009}{4.00 \times 0.81 \times 4.3} = 2.03$$

So

$$r = \frac{2.03[1 - \exp(-1/2.03)]}{3.69[1 - \exp(-1/3.69)]} = 0.90$$

Then for use conditions,

$$F_R(\tau\alpha)_n = 0.90 \times 0.63 = 0.57$$

and

$$F_R U_L = 0.90 \times 3.20 = 2.89 \text{ W/m}^2 \text{ }^\circ\text{C}$$




## 6.21 FLOW DISTRIBUTION IN COLLECTORS

Performance calculations of collectors are based on an implicit assumption of uniform flow distribution in all of the risers in single- or multiple-collector units. If flow is not uniform, the parts of the collectors with low flow through risers will have lower  $F_R$  than parts with higher flow rates. Thus the design of both headers and risers is important in obtaining good collector performance. This problem has been studied analytically and experimentally by Dunkle and Davey (1970). It is of particular significance in large forced-circulation systems; natural-circulation systems tend to be self-correcting and the problem is not as critical. Weitbrecht et al. (2002) reviewed some earlier studies and presented an analytical approach to the flow distribution problem with experimental verification.


Dunkle and Davey (1970) calculated the pressure drop along the headers for the common situation of water entering the bottom header at one side of the collector and leaving the top header at the other side. Their analysis is based on the assumptions that flow is turbulent in headers and laminar in risers (assumptions logical for Australian and many other water heaters). An example of calculated pressure distributions in top and bottom headers is shown in Figure 6.21.1. The implications of these pressure distributions are obvious; the pressure drops from bottom to top are greater at the ends than at the center portion, leading to high flows in the end risers and low flows in the center risers.

This situation is found experimentally. Temperatures of absorber plates are measures of how effectively energy is removed, and thus differences among temperatures measured at the same relative location on individual collectors in banks is a measure of the lack of uniformity of flow in risers. Figure 6.21.2 shows measured temperatures for a bank of 12 collectors connected in parallel. The data show temperature differentials of 22°C from center to ends. Connecting the units in either a series–parallel or a parallel–series arrangement, such as shown in Figure 6.21.3, results in more uniform flow distribution and temperatures.


Manufacturers of collectors have worked out recommended practices for piping collectors to avoid maldistribution of flow and minimize pressure drops, and the designer of a system should refer to those recommendations. Otherwise, standard references on design of piping networks should be consulted.



**Figure 6.21.1** Pressure distribution in headers of an isothermal absorber bank. Adapted from Dunkle and Davey (1970).



**Figure 6.21.2** Experimental temperature measurements on plates in a bank of collectors connected in parallel. Adapted from Dunkle and Davey (1970).



**Figure 6.21.3** Examples of alternative methods of connecting arrays in (a) series-parallel and (b) parallel-series arrangements, as recommended by Dunkle and Davey (1970).

## 6.22 IN SITU COLLECTOR PERFORMANCE

There is no fundamental reason why a collector would not operate as well installed in an application as it does on a test stand. However, there are some practical considerations that can influence measured performance on-site. Differences between predicted and measured performance may arise from several sources:

1. Flow of fluid through the collector may not be uniform through all parts of the collector array. Parts of a collector array receiving reduced fluid flow will have lower  $F_R$  and poorer performance, resulting in degradation of array performance.

2. Flow rates may not be those at which collectors were tested. The parameter  $F_R$  is a function of flow rate for both liquid and air heaters (particularly so for air heating collectors), and changes in flow rate can make significant differences in collector performance.
3. Leaks in air collectors may also introduce differences between predicted and measured performance. Collectors are usually operated at slightly less than atmospheric pressure, resulting in leakage of cool ambient air in and reduced collector outlet temperatures (Close and Yusoff, 1978).
4. Edge and back losses may be different in tests and applications. Edge losses may be reduced in large arrays resulting in smaller  $U_L$  than is obtained from measurements on a single module.
5. Duct and pipe losses may be more significant in applications than in tests, as runs may be longer and ducts and pipes may not be as well insulated.

## 6.23 PRACTICAL CONSIDERATIONS FOR FLAT-PLATE COLLECTORS

In this chapter we have discussed the thermal performance of collectors in theory, in tests, and installed in systems. There are many other practical considerations in the design, manufacture, shipment, installation, and long-term use of flat-plate collectors. In this section we briefly illustrate some of these considerations and show two commercial designs (one liquid and one air). The industry has advanced to the point that manufacturers have developed installation and service manuals (see these manuals for more details). The discussion here is based largely on the concept of factory-manufactured, modular collectors that are assembled in large arrays on a job; the same practical considerations hold for site-built collectors. Discussions of many aspects of installation and operation of large collector arrays are given by the International Energy Agency (IEA, 1985).

Equilibrium temperatures (sometimes called stagnation temperatures), encountered under conditions of high radiation with no fluid flowing through the collector, are substantially higher than ordinary operating temperatures, and collectors must be designed to withstand these temperatures. It is inevitable that at some time power failure, control problems, servicing, summer shutdown, or other causes will lead to no-flow conditions. (They may be encountered first during installation of the collectors.) The fluid and plate temperatures are the same for the no-flow condition. The equilibrium temperatures of other parts of the collector can be estimated from the ratios of thermal resistances between those parts and ambient to that of the plate to ambient. These maximum equilibrium temperatures place constraints on the materials, which must retain their important properties during and after exposure to these temperatures, and on mechanical design to accommodate thermal expansion. The maximum equilibrium temperature, a function of the ambient temperature and the incident solar radiation, can be estimated by evaluating the fluid temperature in Equation 6.7.6 with  $Q_u = 0$ :

$$T_{\max} = T_a + \frac{S}{U_L} \quad (6.23.1)$$



At an ambient temperature of  $30^{\circ}\text{C}$ , absorbed solar radiation of  $1000\text{ W/m}^2$ , and  $U_L$  in the range of  $8.33$  to  $3.70\text{ W/m}^2\text{ }^{\circ}\text{C}$  for single-cover flat-plate collectors (nonselective to highly selective absorbers), the maximum equilibrium temperature ranges from  $150$  to  $300^{\circ}\text{C}$ .

Extremely low temperatures must also be considered. This is particularly important for liquid heating collectors where freeze protection must be provided. This may be done by use of antifreeze fluids or by arranging the system so that the collector will drain during periods when it is not operating. Corrosion is an important consideration with collectors containing antifreeze solutions. Methods of freeze protection are in part system considerations and will be treated in later chapters.

Materials of wide variety are used in collectors, including structural materials (such as metal used in boxes), glazing (which is usually glass), insulation, caulking materials, and so on. Skoda and Masters (1977) have compiled a survey of practical experience with a range of materials and illustrate many problems that can arise if materials are not carefully selected for withstanding weather, temperature extremes, temperature cycling, and compatibility. A series of articles in *Solar Age* (1977) deals with fabrication and corrosion prevention problems in the use of copper, steel, and aluminum absorber plates.

Covers and absorbers are particularly critical; their properties determine  $(\tau\alpha)$  and  $\varepsilon_p$  and thus strongly affect thermal performance. Degradation of these properties can seriously affect long-term performance, and materials should be selected that have stable properties. Condensation of moisture sometimes occurs under covers or between covers, and this imparts an increased reflectance to covers; energy is required to evaporate the condensate on start-up and collector performance is diminished, although the effect on long-term performance may be small. Some collectors use sealed spaces under the top cover, and some use breathing tubes containing desiccants to dry the air in the space under the top cover. Covers and supports should be designed so that dirt will not get under the cover. Materials used in the collector should not contain volatiles that can be evaporated during periods of high collector temperatures; these volatiles condense on the underside of covers and reduce transmittance.

Mechanical design affects thermal performance. It is important in that structural strength of collectors must be adequate to withstand handling and installation and the conditions to be expected over the lifetime of the units. Collectors must be water tight or provided with drains to avoid rain damage and in high latitudes should be mounted so as to allow snow to slide off. Wind loads may be high and tie-downs must be adequate to withstand these loads. Some collectors may be designed to provide structural strength or serve as the water-tight envelope of a building; these functions may impose additional requirements on collector design and manufacture.

Hail damage to collectors has been a matter of concern. Löff (1980) reports the effects on collectors of a hail storm in Colorado in 1979. Hail averaging  $2$  to  $3\text{ cm}$  in diameter fell for a period of several minutes, followed by a lull and then  $1$  or  $2\text{ min}$  of hail with sizes in the  $3\text{- to }10\text{-cm}$  range. Eleven solar heating systems were in the path of the storms; the slopes were  $32^{\circ}$  to  $56^{\circ}$ , and most of the collector panels were about  $1 \times 2\text{ m}$  in size. Of the  $1010$  collector modules on these systems,  $11$  suffered broken glass. In the same storm, a greenhouse had about a third of its roof glass broken by the hail. Löff concludes that


“the risk of hail damage to collectors glazed with 3 mm tempered glass mounted on slopes greater than  $30^\circ$  is negligibly small.”

Installation costs can be an important item of cost of solar collectors. These are largely determined by three factors: handling, tie-down, and manifolding. Moving and positioning of collector modules may be done by hand if modules are light enough or may be done by machine for heavy modules or inaccessible mountings. Tie-downs must be adequate to withstand wind loads; tie-down and weatherproofing should be accomplished with a minimum of labor. Manifolding, connecting the inlets and outlets of many collectors in an array to obtain the desired flow distribution, can be a very time-consuming and expensive operation, and module design should be such as to minimize the labor and materials needed for this operation.


Safety must also be considered in two contexts. First, it must be possible to handle and install modules with a minimum of hazards. Second, materials used in collectors must be capable of withstanding the maximum equilibrium temperatures without hazard of fire or without evolution of toxic or flammable gases.

All of these considerations are important and must be viewed in the light of the many years of low-maintenance service that should be expected of a well-designed collector. In later chapters on economic calculations it will be noted that lifetimes of decades are used in economic calculations, and collectors in most applications should be designed to last 10 to 30 years with minimum degradation in thermal performance or mechanical properties.


Here we illustrate two collectors that have been commercially manufactured. These collectors are selected as typical of good design. Figure 6.23.1 shows a cross-sectional view of two modules of an air heating collector. Manifolds are built into the structure of the



**Figure 6.23.1** Cross-sectional view of two modules of a solar air heater. Air flows from one module to another through side ports and manifold area. Courtesy Solaron Corp.



**Figure 6.23.2** Arrangement of collector array for a solar air heater. Courtesy Solaron Corp.



**Figure 6.23.3** Construction details of a flat-plate liquid heater. Courtesy Lennox Industries.

collectors, and matching openings are provided on the sides of the manifold to interconnect units placed side by side in an array. Figure 6.23.2 shows a schematic of a typical collector array assembly; one pair of openings in the back of the array will serve as entrance and exit ports for multiple modules.

Figure 6.23.3 shows details of a liquid heating collector. The absorber plate is steel with bright nickel plating and a chrome black absorbing surface.

## 6.24 PUTTING IT ALL TOGETHER

The first six chapters of this book have covered many subjects all of which contribute to the ability to predict the performance of flat-plate collectors. In order to illustrate the analytical process, two example problems are solved. The first problem models a typical flat-plate collector in detail and uses simulated test conditions to determine the usual test parameters. The second problem uses the same collector operating over a typical winter day. The thermal performance is estimated using the detailed model and the two simplified models found in the first example. Koo (1999) used this material to develop & Collector Design Program (CoDePro) for flat-plate collectors.

**Example 6.24.1**

Consider a flat-plate collector with the following characteristics:

Number of glass covers	1
Cover $KL$ product	0.121
Cover refractive index	1.526
Wind heat transfer coefficient	$10 \pm 5 \text{ W/m}^2 \text{ K}$
Back-insulation thickness	0.007 m
Back-insulation thermal conductivity	0.0245 W/m K
Edge loss coefficient	$0.098 \text{ W/m}^2 \text{ K}$
Plate-to-cover spacing	0.028 m
Circulating fluid	Water
Flow (based on gross area)	$0.02 \text{ kg/s m}^2$
Number of tubes in parallel	8
Distance between tubes	0.115 m
Tube length (neglect headers)	2.46 m
Tube diameter (thin walled)	0.015 m
Collector gross length	2.5 m
Collector gross width	1.0 m
Bond conductance between tubes and absorber	$10^6 \text{ W/m}^2 \text{ K}$
Absorber plate thickness	0.0005 m
Absorber plate material	Copper
Absorber plate solar absorptance (Example 4.8.2)	0.89
Plate emittance (curve fit from Example 4.8.2)	$-0.00443 + 0.0003451 \times T$ $+ (2.6186 \times 10^{-7})T^2$

The ISO 9806–1 test procedure requires a minimum total solar radiation of  $800 \text{ W/m}^2$  on the collector aperture with less than 20% diffuse solar radiation (ground reflected plus sky), a mass flow rate of  $0.02 \text{ kg/s m}^2$ , and a wind speed between 2 and 4 m/s. The collector is operated in Madison, Wisconsin (latitude  $43.1^\circ$ , longitude  $89.4^\circ$ ), on June 16 at a slope of  $19.75^\circ$  (so that at noon the incidence angle is  $0^\circ$ ) on a clear day with  $k_T = 0.7$  (all day), an ambient temperature of  $20^\circ\text{C}$  in a climate with a relative humidity of 70%. The inlet temperature varies from 20 to  $130^\circ\text{C}$  (at a pressure of 3 atm to avoid boiling). The wind speed over the collector and its mounting is 2.7 m/s. The characteristic length of the collector mounting is 3 m (see Equation 3.15.10). The ground reflectance is estimated to be 0.4. Generate a plot of collector efficiency as a function of  $(T_{in} - T_a)/I_T$  and determine values for the linear parameters given by Equation 6.17.3 and values for the second-order parameters given by Equation 6.17.7 but with the U.S. custom of using  $T_{in} - T_a$  rather than  $T_{av} - T_a$ . Also determine the incident angle modifier coefficient,  $b_o$ .

**Solution**


The simultaneous solution to the system of equations was accomplished using EES (see Example 6.4.1). As with all systems of nonlinear equations reasonable initial guesses are required. For this problem for all inlet fluid temperatures only initial guesses for the mean plate ( $50^\circ\text{C}$ ) and mean fluid temperature ( $40^\circ\text{C}$ ) are needed; all other variables had an initial guess value of 1.0. Most variables are set to have a lower limit of zero. Once a

solution is found, the initial guess values of all variables are set to the most recent solution values. In this simulated test all measurements are assumed to occur very close to noon. In reality it is necessary to make adjustments and then wait for steady-state conditions between each test point.

The collector aperture area is  $8 \times 0.115 \times 2.46 = 2.3 \text{ m}^2$  and the gross area is  $2.5 \text{ m}^2$ . It does not matter which area is used as long as the value used is reported with the results. Converting between the two areas is a simple matter of multiplying or dividing by the area ratio. Since the gross area is important in laying out collectors on a building roof, the gross area will be used here.


An inlet temperature of the water of  $50^\circ\text{C}$  is used to illustrate the values of variables. Water properties (at the mean fluid temperature  $\bar{T}_{\text{fluid}} = 50.3^\circ\text{C}$ :  $k = 0.631 \text{ W/m K}$ ,  $c = 4181 \text{ J/kg K}$ ,  $\mu = 0.00054 \text{ Pa s}$ ) are from EES. The heat transfer coefficient inside the tube ( $163 \text{ W/m}^2 \text{ K}$ ) is from Equations 3.14.1 through 3.14.5 (with Table 3.14.1). The mean plate temperature ( $52.6^\circ\text{C}$ ) and fluid temperature ( $50.3^\circ\text{C}$ ) are from Equations 6.9.2 and 6.9.4. The effective temperature of  $3.5^\circ\text{C}$  is found from Equation 3.9.2. The top loss coefficient ( $3.78 \text{ W/m}^2 \text{ }^\circ\text{C}$ ), back loss coefficient ( $0.35 \text{ W/m}^2 \text{ }^\circ\text{C}$ ), and overall loss coefficient ( $4.23 \text{ W/m}^2 \text{ }^\circ\text{C}$ ) are found using the methods of Example 6.4.1. The values  $F' = 0.927$ ,  $F'' = 0.997$ , and  $F_R = 0.924$  are found using the methods of Example 6.7.1. The incident radiation on a horizontal surface is  $872 \text{ W/m}^2$  ( $k_T = 0.7$ ), which, using the HDKR method of Example 2.16.1, leads to an incident radiation on the sloped collector of  $928 \text{ W/m}^2$  when the ground reflectance is 0.4 (from the ISO standards the minimum incident radiation is  $800 \text{ W/m}^2$  with less than 20% diffuse solar). The absorbed solar radiation ( $663 \text{ W/m}^2$ ) is found using the HDKR method of Example 5.9.2. The useful energy gain ( $4.03 \text{ MJ/h}$  for the  $2.5\text{-m}^2$  collector) is found using Equation 6.7.6. The collector efficiency (0.483 based on gross area) is found using Equation 6.2.2 where the time period was 1 h. The wind heat transfer coefficient ( $10 \text{ W/m}^2 \text{ K}$ ) is found using Equation 3.15.10. Since the wind heat transfer coefficient is the variable with the least certainty, the analysis is performed using the EES uncertainty propagation with the wind heat transfer coefficient set to  $10 \pm 5 \text{ W/m}^2 \text{ K}$ . The following figure shows the estimated performance with error bars to indicate the uncertainty due to the wind heat transfer coefficient. A linear fit (using the gross collector area) yields  $\eta = 0.610 - 4.06 \Delta T/I$  and a second order fit (with  $I = 800 \text{ W/m}^2$ ) yields  $\eta = 0.594 - 3.21 \Delta T/I - 0.0090 \Delta T^2/I$ , where  $\Delta T = T_{\text{in}} - T_a$ .

The incidence angle modifier is found with the inlet temperature fixed at  $20^\circ\text{C}$  and with beam incident angles of  $0^\circ$ ,  $45^\circ$ , and  $60^\circ$ . In Madison at noon in June at a slope of  $19.75^\circ$  it is not possible to cover the range of beam incident angles from  $0^\circ$  to  $60^\circ$ ; even with the collector facing due north at noon the beam incidence angle is only  $40^\circ$ . Therefore it is necessary to either change the slope to reach beam incident angles of  $45^\circ$  and  $60^\circ$  or perform the test at a time other than noon. The problem with changing the slope of this typical flat-plate collector is that changing the slope will impact the convection between the absorber plate and the cover and will also affect the spatial distribution of ground-reflected and diffuse-sky radiation, both of which will impact the incidence angle modifier. For some collector designs (e.g., evacuated tubular collectors with heat pipe absorbers) changing the slope can dramatically change the performance. Consequently, the test is performed with the collector facing south at a slope of  $19.75^\circ$  at times when the beam incident angle is  $45^\circ$  (15:17) and  $60^\circ$  (18 : 24). In an actual test the collector is typically mounted on a platform



that rotates about a vertical axis to maintain the incidence angle at the desired value over the test period.

The ratio of the efficiency at an inlet temperature of  $20^{\circ}\text{C}$  and at zero incidence angle (0.593) to the efficiency at incidence angle  $\theta$  is  $K_{\tau\alpha}(\theta)$ . At  $45^{\circ}$  the efficiency is 0.557 and at  $60^{\circ}$  the efficiency is 0.493. The results evaluating  $K_{\tau\alpha}(\theta)$  at every degree are shown in the figure below where  $K_{\tau\alpha}(\theta)$  is plotted as a function of  $1/\cos \theta - 1$ . The slope of the dotted line ( $-0.161$ ) is the incidence angle modifier coefficient,  $b_o$ .



The use of the collector test equations (rather than the complete equations as described in Example 6.24.1) in a simulation can yield reasonable results. Example 6.24.2 illustrates, for one day, the agreement that can be expected. The time of the year, the collector slope, and the reasonably high temperature difference between the inlet temperature and the ambient temperature are all chosen to maximize the differences.

### Example 6.24.2

The collector of Example 6.24.1 is operated in Madison, Wisconsin, on February 2 when  $k_T = 0.7$ , relative humidity is 50%, and the ambient temperature is constant at  $0^\circ\text{C}$ . The inlet temperature is  $35^\circ\text{C}$ , and the collector slope is  $60^\circ$  with a zero surface azimuth angle. The ground reflectance is 0.7 due to snow cover. Simulate the day's performance using the detailed equations and the two collector test equations of Example 6.24.1.

### Solution

The useful energy gains from the two collector test equations applied to the situations of this example are

$$Q_{u1} = 2.5[0.610I_T \bar{K}_{\tau\alpha} - 4.06(35 - 0)]$$

$$Q_{u2} = 2.5[0.594I_T \bar{K}_{\tau\alpha} - 3.21(35 - 0) - 0.0090(35 - 0)^2]$$

where the average value of the incidence angle modifier is found from the equations of Section 5.9 using the Liu-and-Jordan method. Note that in Example 6.24.1 the absorbed radiation was estimated using the HDKR method, which is expected to yield the most accurate estimate. The Liu-and-Jordan method is often used in simulations and will be used here. Therefore

$$I_T \bar{K}_{\tau\alpha} = I_b R_b K_{\tau\alpha,b} + I_d K_{\tau\alpha,d} \left( \frac{1 + \cos \beta}{2} \right) + I_{\rho_g} K_{\tau\alpha,g} \left( \frac{1 - \cos \beta}{2} \right)$$

where each  $K_{\tau\alpha}$  is evaluated using the incidence angle modifier equation

$$K_{\tau\alpha} = 1 - 0.161 \left( \frac{1}{\cos \theta} - 1 \right)$$


at the appropriate angle ( $\theta$  for the beam radiation and for the diffuse-sky and ground-reflected radiation  $\theta_{e,d} = 57^\circ$  and  $\theta_{e,g} = 65^\circ$  from Figure 5.4.1). Even though the ground-reflected equivalent angle is greater than  $60^\circ$ , the maximum angle for Equation 6.17.10, there is no available alternative when using typical test results.

The useful energy gain for the day using the linear collector equation is then

$$Q_1 = \frac{2.5}{15} \int_{\omega_{\text{sunrise}}}^{\omega_{\text{sunset}}} \max\{[0.610I_T \bar{K}_{\tau\alpha} - 4.06(35 - 0)], 0\} d\omega$$

The 15 deg/h converts the hourly gain to the gain per hour angle. The second-order collector is treated in a similar manner. The “actual” energy gain (assuming the detailed collector analysis of Example 6.24.1 represents reality) is also found by integrating over

the day. The results shown in the figure were all obtained using EES. The “actual” value for the day’s energy is 27.6 MJ; the linear model predicts 25.2 MJ and the second-order model predicts 25.8 MJ. The linear and second-order collector models predict essentially the same results but both are considerably below the result of the detailed model.



There are a number of reasons to explain the differences. The collector test in the previous example was carried out at a slope of about  $20^\circ$  whereas the slope for this example was  $60^\circ$ . As can be seen from Figure 3.11.1, the slope of the collector can have a significant impact on the convection heat loss from the absorber plate to the cover. This convection heat loss is also impacted by the temperature level of the collector operation. That is, when the ambient temperature is, say,  $20^\circ\text{C}$  and the inlet minus ambient temperature is, for example,  $25^\circ\text{C}$ , the top heat loss coefficient will not be the same with a different ambient temperature even though the temperature rise remains at  $25^\circ\text{C}$ . The effective sky temperature for Example 24.6.1 is  $3.5^\circ\text{C}$ , whereas for this example it is  $-26.5^\circ\text{C}$ . These very different surrounding temperatures impact the heat loss. Another difference is the collector cover’s view of the sky and ground in the two examples due to the different slopes. Finally, the detailed model uses the HDKR method for radiation processing and the incidence angle modifiers estimated from fundamentals whereas the collector test equations uses the Liu-and-Jordan method for radiation processing and the  $b_o$  method for estimating absorbed radiation. When a similar comparison is done where the test is “performed” in June and the daylong simulation is done for a clear day in June, the detailed model predicts a daily gain of 33.3 MJ and the linear and second-order models predict 32.6 and 32.7 MJ, respectively. ■

## 6.25 SUMMARY

In this chapter, we have gone through the theory of flat-plate collectors, shown performance measurements on them, outlined methods of testing these units, and shown standard



methods of presenting the thermal characteristics. The thermal performance data taken on a test stand provide valuable information that will be used later in process design calculations. Performance of a collector in an application will depend on the design of the particular installation and also on the skill with which the equipment is assembled and installed.

## REFERENCES

- Abdel-Khalik, S. I., *Solar Energy*, **18**, 59 (1976). "Heat Removal Factor for a Flat-Plate Solar Collector with a Serpentine Tube."
- ASHRAE/ANSI Standard 93-2003, *Methods of Testing to Determine the Thermal Performance of Solar Collectors*, American Society of Heating, Refrigeration, and Air Conditioning Engineers, Atlanta, GA (2003).
- Beckman, W. A., S. A. Klein, and J. A. Duffie, *Solar Heating Design by the f-Chart Method*, Wiley, New York (1977).
- Bliss, R. W., *Solar Energy*, **3** (4), 55 (1959). "The Derivations of Several 'Plate Efficiency Factors' Useful in the Design of Flat-Plate Solar-Heat Collectors."
- Chiou, J. P., M. M. El-Wakil, and J. A. Duffie, *Solar Energy*, **9**, 73 (1965). "A Slit-and-Expanded Aluminum-Foil Matrix Solar Collector."
- Close, D. J. and M. B. Yusoff, *Solar Energy*, **20**, 459 (1978). "Effects of Air Leaks on Solar Air Collector Behavior."
- Cooper, P. I. and R. V. Dunkle, *Solar Energy*, **26**, 133 (1981). "A Non-Linear Flat-Plate Collector Model."
- Dietz, A. G. H., in *Introduction to the Utilization of Solar Energy* (A. M. Zarem and D. D. Erway, eds.), McGraw-Hill, New York (1963). "Diathermanous Materials and Properties of Materials."
- Directory of SRCC Certified Solar Collectors Ratings* (updated periodically). Solar Rating and Certification Corporation, % FSEC, Coca, FL.
- Duffie, J. A., and W. A. Beckman, *Solar Energy Thermal Processes*, Wiley-Interscience, New York (1974).
- Dunkle, R. V. and P. I. Cooper, paper presented at the Los Angeles Meeting of the International Solar Energy Society (1975). "A Proposed Method for the Evaluation of Performance Parameters of Flat-Plate Solar Collectors."
- Dunkle, R. V. and E. T. Davey, paper presented at Melbourne International Solar Energy Society Conference (1970). "Flow Distribution in Absorber Banks."
- EN 12975-1:2000, "Thermal Solar Systems and Components—Solar Collectors—Part 1: General Requirements," CEN—European Committee for Standardization, Brussels (2000).
- EN 12975-2:2001, "Thermal Solar Systems and Components—Solar Collectors—Part 2: Test Methods," CEN—European Committee for Standardization, Brussels (2001).
- Garg, H. P., *Solar Energy*, **15**, 299 (1974). "Effect of Dirt on Transparent Covers in Flat-Plate Solar Energy Collectors."
- Gillett, W. B., *Solar Energy*, **25**, 543 (1980). "The Equivalence of Outdoor and Mixed Indoor/Outdoor Solar Collector Testing."
- Gillett, W. B. and J. E. Moon, *Solar Collectors. Test Methods and Design Guidelines*. Reidel (for the Commission of the European Communities), Dordrecht (1985).
- Hamid, Y. H. and W. A. Beckman, *Trans. ASME J. Eng. Power*, **93**, 221 (1971). "Performance of Air-Cooled, Radiatively Heated Screen Matrices."
- Hill, J. E. and T. Kusuda, *National Bureau of Standards Interim Report NBSIR 74-635 to NSF/ERDA* (1974). "Proposed Standard Method of Testing for Rating Solar Collectors Based on Thermal Performance."

- Hill, J. E. and E. R. Streed, *Solar Energy*, **18**, 421 (1976). "Method of Testing for Rating Solar Collectors Based on Thermal Performance."
- Hill, J. E. and E. R. Streed, in *Application of Solar Energy of Heating and Cooling of Buildings* (R. Jordan and B. Y. Liu, eds.), ASHRAE GRP 170, New York, (1977). "Testing and Rating of Solar Collectors."
- Hill, J. E., J. P. Jenkins, and D. E. Jones, *ASHRAE Trans.*, **84**, 2 (1978). "Testing of Solar Collectors According to ASHRAE Standard 93-77."
- Hill, J. E., J. P. Jenkins, and D. E. Jones, *NBS Building Science Series 117*, U.S. Department of Commerce (1979). "Experimental Verification of a Standard Test Procedure for Solar Collectors."
- Hollands, K. G. T. and E. C. Shewen, *Trans. ASME J. Solar Energy Eng.*, **103**, 323 (1981). "Optimization of Flow Passage Geometry for Air Heating Plate-Type Solar Collectors."
- Hottel, H. C. and A. Whillier, in *Transactions of the Conference on the Use of Solar Energy* (E. F. Carpenter, ed.), Vol. 2, P. I, University of Arizona Press, Tucson, p. 74 (1958). "Evaluation of Flat-Plate Collector Performance."
- Hottel, H. C. and B. B. Woertz, *Trans. ASME*, **64**, 91 (1942). "Performance of Flat-Plate Solar-Heat Collectors."
- International Energy Agency (IEA), in *Proceedings of the IEA Workshop*, San Diego, CA (1985). "Design and Performance of Large Solar Thermal Collector Arrays" (C. A. Bankston, Ed.).
- International Energy Agency (IEA), Report IEA-SHAC-TIV-4 (1986). "Results from Eleven Evacuated Collector Installations."
- Jones, D. E., personal communication (1979).
- Klein, S. A., *Solar Energy*, **17**, 79 (1975). "Calculation of Flat-Plate Loss Coefficients."
- Klein, S. A., personal communication (1979).
- Klein, S. A., J. A. Duffie, and W. A. Beckman, *Trans. ASME J. Eng. Power*, **96A**, 109 (1974). "Transient Considerations of Flat-Plate Solar Collectors."
- Koo, J. M., *MS thesis*, University of Wisconsin-Madison (1999). "Development of a Flat-Plate Solar Collector Design Program."
- Kutscher, C. F., personal communication (2005).
- Kutscher, C. F., *Trans ASME J. Solar Energy Eng.*, **116**, 391 (1994). "Heat Exchange Effectiveness and Pressure Drop for Air Flow through Perforated Plates with and without Crosswind."
- Kutscher, C. F., C. B. Christensen, and G. M. Barker, *Trans ASME J. Solar Energy Eng.*, **115**, 182 (1993). "Un glazed Transpired Solar Collectors: Heat Loss Theory."
- Löf, G. O. G., *Solar Energy*, **25**, 555 (1980). "Hail Resistance of Solar Collectors with Tempered Glass Covers."
- McIntire, W. R. and K. A. Read, *Solar Energy*, **31**, 405 (1983). "Orientational Relationships for Optically Non-Symmetric Solar Collectors."
- Moore, S. W., J. D. Balcomb, and J. C. Hedstrom, *paper presented at Ft. Collins ISES Meeting* (Aug. 1974). "Design and Testing of a Structurally Integrated Steel Solar Collector Unit Based on Expanded Flat Metal Plates."
- Neeper, D. A., in *Proceedings of the ISES Congress*, Atlanta (K. W. Böer and B. H. Glenn, eds.), Vol. 1, Pergamon, Elmsford, NY, p. 298 (1979). "Analysis of Matrix Air Heaters."
- Ortabasi, U. and W. M. Buehl, *Paper presented at the ISES Conference*, Los Angeles (1975). "Analysis and Performance of an Evacuated Tubular Collector."
- Perers, B., *Solar Energy*, **50**, 517 (1993). "Dynamic Method for Solar Corrector Array Testing and Evaluation with Standard Database and Simulation Programs."
- Proctor, D., *Solar Energy*, **32**, 377 (1984). "A Generalized Method for Testing All Classes of Solar Collectors. I. Attainable Accuracy. II. Evaluation of Collector Thermal Constants. III. Linearized Efficiency Equations."
- Proctor, D. and S. R. James, *Solar Energy*, **35**, 387 (1985). "Analysis of the Sanyo Evacuated Tube Solar Collector Test Results from the IEA Task III Programme."

- Selcuk, K., *Solar Energy*, **13**, 165 (1971). "Thermal and Economic Analysis of the Overlapped-Glass Plate Solar-Air Heaters."
- Simon, F. F. *Solar Energy*, **18**, 451 (1976). "Flat-Plate Solar Collector Performance Evaluation with a Solar Simulation as a Basis for Collector Selection and Performance Prediction."
- Skoda, L. F. and L. W. Masters, *Report NBSIR 77-1314 of the National Bureau of Standards* (1977). "Solar Energy Systems—Survey of Materials Performance."
- Solar Age*, **2** (1977), a series of articles including: Butt, S. H. and J. W. Popplewell, "Absorbers: Questions and Answers"; Lyman, W. S. and P. Anderson, "Absorbers: Copper"; Kruger, P., "Absorbers: Steel"; Byrne, S. C. "Absorbers: Aluminum."
- Souka, A. F. and H. H. Safwat, *Solar Energy*, **10**, 170 (1966). "Optimum Orientations for the Double Exposure Flat-Plate Collector and Its Reflectors."
- Speyer, E., *Trans. ASME J. Eng. Power*, **86**, 270 (1965). "Solar Energy Collection with Evacuated Tubes."
- Streed, E. R., J. E. Hill, W. C. Thomas, A. G. Dawson, and B. D. Wood, *Solar Energy*, **22**, 235 (1979). "Results and Analysis of a Round Robin Test Program for Liquid-Heating Flat-Plate Solar Collectors."
- Summers, D. N. M. S. *Thesis in Mechanical Engineering*, University of Wisconsin-Madison (1995). "Thermal Simulation and Economic Assessment of Unglazed Transpired Collector Systems."
- Tabor, H., *Bull. Res. Council Israel*, **6C**, 155 (1958). "Radiation, Convection and Conduction Coefficients in Solar Collectors."
- Tesfamichael, T. and E. Wäckelgård, *Solar Energy*, **68**, 335 (2000). "Angular Solar Absorptance and Incident Angle Modifier of Selective Absorbers for Solar Thermal Collectors."
- Theunissen, P-H. and W. A. Beckman, *Solar Energy*, **35**, 311 (1985). "Solar Transmittance Characteristics of Evacuated Tubular Collectors with Diffuse Back Reflectors."
- TRNSYS Users Manual, Version 16, University of Wisconsin Solar Energy Laboratory (2012). [The first public version was 7 (1976).]
- Vernon, R. W. and F. F. Simon, *paper presented at Ft. Collins ISES Meeting*, Aug. 1974, and NASA TMX-71602. "Flat-Plate Collector Performance Determined Experimentally with a Solar Simulator."
- Weitbrecht, V. D. Lehmann, and A. Richter, *Solar Energy*, **73**, 433 (2002). "Flow Distribution in Solar Collectors with Laminar Flow Conditions."
- Whillier, A., Sc. D. *Thesis*, MIT, Cambridge, MA (1953). "Solar Energy Collection and Its Utilization for House Heating."
- Whillier, A., in *Applications of Solar Energy for Heating and Cooling of Buildings* (R. C. Jordan and B. Y. H. Liu, eds.), ASHRAE, New York, (1977). "Prediction of Performance of Solar Collectors."
- Whillier, A. and G. Saluja, *Solar Energy*, **9**, 21 (1965). "Effects of Materials and of Construction Details on the Thermal Performance of Solar Water Heaters."
- Wijesundera, N. E., *Solar Energy*, **21**, 517 (1978). "Comparison of Transient Heat Transfer Models for Flat-Plate Collectors."
- Wirsum, M. C. M. S. *Thesis*, University of Wisconsin-Madison (1988). "Simulation Study of a Large Solar Air Heating System."
- Zhang, H-F. and Z. Lavan, *Solar Energy*, **34**, 175 (1985). "Thermal Performance of a Serpentine Absorber Plate."

## Concentrating Collectors

For many applications it is desirable to deliver energy at temperatures higher than those possible with flat-plate collectors. Energy delivery temperatures can be increased by decreasing the area from which heat losses occur. This is done by interposing an optical device between the source of radiation and the energy-absorbing surface. The small absorber will have smaller heat losses compared to a flat-plate collector at the same absorber temperature. In this chapter we discuss two related approaches: the use of nonimaging concentrators and the use of imaging concentrators.

Many designs have been set forth for concentrating collectors. Concentrators can be reflectors or refractors, can be cylindrical or surfaces of revolution, and can be continuous or segmented. Receivers can be convex, flat, or concave and can be covered or uncovered. Many modes of tracking are possible. Concentration ratios (the ratios of collector aperture area to absorber area, which are approximately the factors by which radiation flux on the energy-absorbing surface is increased) can vary over several orders of magnitude. With this wide range of designs, it is difficult to develop general analyses applicable to all concentrators. Thus concentrators are treated in two groups: nonimaging collectors with low concentration ratio and linear imaging collectors with intermediate concentration ratios. We also note some basic considerations of three-dimensional concentrators that can operate at the high end of the concentration ratio scale.

Concentrators can have concentration ratios from low values less than unity to high values of the order of  $10^5$ . Increasing ratios mean increasing temperatures at which energy can be delivered and increasing requirements for precision in optical quality and positioning of the optical system. Thus the cost of delivered energy from a concentrating collector is a function of the temperature at which it is available. At the highest range of concentration and correspondingly highest precision of optics, concentrating collectors are termed **solar furnaces**; these are laboratory tools for studying properties of materials at high temperatures and other high-temperature processes. Laszlo (1965) and the *Proceedings of the 1957 Solar Furnace Symposium* (1957) include extensive discussions of solar furnaces. The main concerns in this chapter are with energy delivery systems operating at low or intermediate concentrations.

From an engineering point of view, concentrating collectors present problems in addition to those of flat-plate collectors. They must (except at the very low end of the concentration ratio scale) be oriented to “track” the sun so that beam radiation will be directed onto the absorbing surface. However, the designer has available a range of configurations that allow new sets of design parameters to be manipulated. There are also new requirements for maintenance, particularly to retain the quality of optical systems for long periods of time in the presence of dirt, weather, and oxidizing or other corrosive

atmospheric components. The combination of operating problems and collector cost has restricted the utility of concentrating collectors. New materials and better engineering of systems have now led to large-scale applications, as will be noted in Chapter 17.


To avoid confusion of terminology, the word **collector** will be applied to the total system, including the receiver and the concentrator. The **receiver** is that element of the system where the radiation is absorbed and converted to some other energy form; it includes the **absorber**, its associated covers, and insulation. The **concentrator**, or **optical system**, is the part of the collector that directs radiation onto the receiver. The **aperture** of the concentrator is the opening through which the solar radiation enters the concentrator.

The first four sections in this chapter deal with general information on optical principles and heat transfer that is important in concentrating collectors. The next is concerned with arrays of cylindrical absorbers over diffuse reflectors. The following three treat the performance of compound parabolic concentrator (CPC) collectors. The balance of the chapter is concerned with imaging collectors and discusses linear collectors of types being used in experimental industrial process heat and pumping applications and multiple heliostat “central-receiver” collectors.

## 7.1 COLLECTOR CONFIGURATIONS

Many concentrator types are possible for increasing the flux of radiation on receivers. They can be reflectors or refractors. They can be cylindrical to focus on a “line” or circular to focus on a “point.” Receivers can be concave, flat, or convex. Examples of six configurations are shown in Figure 7.1.1.

The first two are arrays of evacuated tubes with cylindrical absorbers spaced apart, with back reflectors to direct radiation on the area between the tubes to the absorbers. The first uses a flat diffuse back reflector and the second cusp-shaped specular reflectors. The



**Figure 7.1.1** Possible concentrating collector configurations: (a) tubular absorbers with diffuse back reflector; (b) tubular absorbers with specular cusp reflectors; (c) plane receiver with plane reflectors; (d) parabolic concentrator; (e) Fresnel reflector; (f) array of heliostats with central receiver.

configuration shown in Figure 7.1.1(c) has a plane receiver with plane reflectors at the edges to reflect additional radiation onto the receiver. The concentration ratios of this type are low, with a maximum value of less than 4. Some of the diffuse components of radiation incident on the reflectors would be absorbed at the receiver. These collectors can be viewed as flat-plate collectors with augmented radiation. Analyses of these concentrators have been presented by Hollands (1971), Selcuk (1979), and others. Figure 7.1.1(d) shows a reflector of a parabolic section, which could be a cylindrical surface (with a tubular receiver) or a surface of revolution (with a spherical or hemispherical receiver). Cylindrical collectors of this type have been studied in some detail and are being applied.

The continuous parabolic reflector can be replaced by a Fresnel reflector, a set of flat reflectors on a moving array as shown in Figure 7.1.1(e), or its refracting equivalent. The facets of the reflector can also be individually mounted and adjusted in position, as shown in Figure 7.1.1(f). Large arrays of heliostats of this type, with receivers mounted on a tower, are the basis of designs of central-receiver collectors.

For the concentrators shown in Figures 7.1.1(c–f), single-sided flat receivers may be used (if the receiver is not “inside” the reflector). Cylindrical, hemispherical, or other convex shapes may also be possible, and cavity receivers may also be used.

In general, concentrators with receivers much smaller than the aperture are effective only on beam radiation. It is evident also that the angle of incidence of the beam radiation on the concentrator is important and that sun tracking will be required for these collectors. A variety of orienting mechanisms have been designed to move focusing collectors so that the incident beam radiation will be reflected to the receiver. The motions required to accomplish tracking vary with the design of the optical system, and a particular resultant motion may be accomplished by more than one system of component motions.

Linear (cylindrical) optical systems will focus beam radiation to the receiver if the sun is in the central plane of the concentrator (the plane including the focal axis and the vertex line of the reflector). These collectors can be rotated about a single axis of rotation, which may be north-south, east-west, or inclined and parallel to the earth’s axis (in which case the rate of rotation is  $15^\circ/\text{h}$ ). There are significant differences in quantity of incident beam radiation, its time dependence, and the image quality obtained with these three modes of orientation.

Reflectors that are surfaces of revolution (circular concentrators) generally must be oriented so that the axis and sun are in line and thus must be able to move about two axes. These axes may be horizontal and vertical or one axis of rotation may be inclined so that it is parallel to the earth’s axis of rotation (i.e., a polar axis) and the other perpendicular to it. The angle of incidence of beam radiation on a moving plane is indicated for the most probable modes of orientation of that plane by the equations in Section 1.7.

Orientation systems can provide continuous or nearly continuous adjustments, with movement of the collector to compensate for the changing position of the sun. For some low-concentration linear collectors it is possible to adjust their position intermittently, with weekly, monthly, or seasonal changes possible for some designs. Continuous orientation systems may be based on manual or mechanized operation. Manual systems depend on the observations of operators and their skill at making the necessary corrections and may be adequate for some purposes if concentration ratios are not too high and labor costs are not prohibitive; they have been suggested for use in areas of very low labor cost.

Mechanized orienting systems can be sun-seeking systems or programmed systems. Sun-seeking systems use detectors to determine system misalignment and through controls make the necessary corrections to realign the assembly. Programmed systems, on the other hand, cause the collector to be moved in a predetermined manner (e.g.,  $15^\circ/\text{h}$  about a polar axis) and may need only occasional checking to assure alignment. It may also be advantageous to use a combination of these tracking methods, for example, by superimposing small corrections by a sun-seeking mechanism on a programmed “rough positioning” system. Any mechanized system must have the capability of adjusting the position of the collector from end-of-day position to that for operation early the next day, adjusting for intermittent clouds, and adjusting to a stowed position where it can best withstand very high winds without damage.


## 7.2 CONCENTRATION RATIO

The most common definition of concentration ratio, and that used here, is an **area concentration ratio**,<sup>1</sup> the ratio of the area of aperture to the area of the receiver. (A **flux concentration ratio** is defined as the ratio of the average energy flux on the receiver to that on the aperture, but generally there are substantial variations in energy flux over the surface of a receiver. A **local flux concentration ratio** can also be defined as the ratio of the flux at any point on the receiver to that on the aperture, which will vary across the receiver.)

The area concentration ratio is

$$C = \frac{A_a}{A_r} \quad (7.2.1)$$

This ratio has an upper limit that depends on whether the concentration is a three-dimensional (circular) concentrator such as a paraboloid or a two-dimensional (linear) concentrator such as a cylindrical parabolic concentrator. The following development of the maximum concentration ratio, from Rabl (1976a), is based on the second law of thermodynamics applied to radiative heat exchange between the sun and the receiver. Consider the circular concentrator with aperture area  $A_a$  and receiver area  $A_r$ , viewing the sun of radius  $r$  at distance  $R$ , as shown in Figure 7.2.1. The half-angle subtended by the



**Figure 7.2.1** Schematic of sun at  $T_s$  at distance  $R$  from a concentrator with aperture area  $A_a$  and receiver area  $A_r$ . Adapted from Rabl (1976a).

<sup>1</sup>Usually termed simply concentration ratio.



sun is  $\theta_s$ . (The receiver is shown beyond the aperture for clarity; the argument is the same if it is on the same side of the aperture as the sun.)

If the concentrator is perfect, the radiation from the sun on the aperture (and thus also on the receiver) is the fraction of the radiation emitted by the sun which is intercepted by the aperture. Although the sun is not a blackbody, for purposes of an approximate analysis it can be assumed to be a blackbody at  $T_s$ :

$$Q_{s \rightarrow r} = A_a \frac{r^2}{R^2} \sigma T_s^4 \quad (7.2.2)$$

A perfect receiver (i.e., blackbody) radiates energy equal to  $A_r T_r^4$ , and a fraction of this,  $E_{r \rightarrow s}$ , reaches the sun<sup>2</sup>:

$$Q_{r \rightarrow s} = A_r \sigma T_r^4 E_{r \rightarrow s} \quad (7.2.3)$$

When  $T_r$  and  $T_s$  are the same, the second law of thermodynamics requires that  $Q_{s \rightarrow r}$  be equal to  $Q_{r \rightarrow s}$ . So from Equations 7.2.2 and 7.2.3

$$\frac{A_a}{A_r} = \frac{R^2}{r^2} E_{r \rightarrow s} \quad (7.2.4)$$

and since the maximum value of  $E_{r \rightarrow s}$  is unity, the maximum concentration ratio for circular concentrators is

$$\left( \frac{A_a}{A_r} \right)_{\text{circular, max}} = \frac{R^2}{r^2} = \frac{1}{\sin^2 \theta_s} \quad (7.2.5)$$

A similar development for linear concentrators leads to

$$\left( \frac{A_a}{A_r} \right)_{\text{linear, max}} = \frac{1}{\sin \theta_s} \quad (7.2.6)$$

Thus with  $\theta_s = 0.27^\circ$ , the maximum possible concentration ratio for circular concentrators is 45,000, and for linear concentrators the maximum is 212.


The higher the temperature at which energy is to be delivered, the higher must be the concentration ratio and the more precise must be the optics of both the concentrator and the orientation system. Figure 7.2.2 shows practical ranges of concentration ratios and types of optical systems needed to deliver energy at various temperatures.

Concentrators can be divided into two categories: nonimaging and imaging. Nonimaging concentrators, as the name implies, do not produce clearly defined images of the sun on the absorber but rather distribute radiation from all parts of the solar disk onto all parts of the absorber. The concentration ratios of linear nonimaging collectors are in the low range and are generally below 10. Imaging concentrators, in contrast, are analogous to camera lenses in that they form images (usually of very low quality by ordinary optical standards) on the absorber.

---

<sup>2</sup> $E_{r \rightarrow s}$  is an exchange factor as used in Equation 3.8.2.





**Figure 7.2.2** Relationship between concentration ratio and temperature of receiver operation. The “lower limit” curve represents concentration ratios at which the thermal losses will equal the absorbed energy; higher ratios will then result in useful gain. The shaded range corresponds to collection efficiencies of 40 to 60% and represents a probable range of operation. Also shown are approximate ranges in which several types of reflectors might be used. (This figure is not to be used for design. It is based on an assumed set of conditions determining the absorbed radiation and the thermal losses and on reasonable design practice at various temperatures. The positions of these curves would shift under conditions other than those assumed.) From Duffie and Löff (1962).

### 7.3 THERMAL PERFORMANCE OF CONCENTRATING COLLECTORS

Calculation of the performance of concentrating collectors follows the same general outlines as for flat-plate collectors (for example, see Forristall, 2003). The absorbed radiation per unit area of aperture  $S$  must be estimated from the radiation and the optical characteristics of the concentrator and receiver. Estimation of  $S$  is discussed in sections to follow. Thermal losses from the receiver must be estimated, usually in terms of a loss coefficient  $U_L$ , which is based on the area of the receiver. In principle, temperature gradients along the receiver can be accounted for by a flow factor  $F_R$  to allow the use of inlet fluid temperatures in energy balance calculations. This section is concerned with the estimation of  $U_L$  and  $F_R$ .

The methods for calculating thermal losses from receivers are not as easily summarized as in the case of flat-plate collectors. The shapes and designs are widely variable, the temperatures are higher, the edge effects are more significant, conduction terms may be

quite high, and the problems may be compounded by nonuniformity of radiation flux on receivers which can result in substantial temperature gradients across the energy-absorbing surfaces. It is difficult to present a single general method of estimating thermal losses, and ultimately each receiver geometry must be analyzed as a special case.

The nature of the thermal losses for receivers of concentrating collectors is the same as for flat-plate exchangers. Receivers may have covers transparent to solar radiation. If so, the outward losses from the absorber by convection and radiation to the atmosphere are correspondingly modified and equations similar to those of Chapter 6 can be used to estimate their magnitude. As with flat-plate systems, the losses can be estimated as being independent of the intensity of incident radiation (although this may not be strictly true if a transparent cover absorbs appreciable solar radiation). In any event, an effective transmittance-absorptance product can also be defined for focusing systems. Furthermore, with focusing systems the radiation flux at the receiver is generally such that only cover materials with very low absorptance for solar radiation can be used without thermal damage to the cover. Conduction losses occur through the supporting structure and through insulation on parts of the receiver that are not irradiated.

The generalized thermal analysis of a concentrating collector is similar to that of a flat-plate collector. Although not necessary, it is convenient to derive appropriate expressions for the collector efficiency factor  $F'$ , the loss coefficient  $U_L$ , and the collector heat removal factor  $F_R$ . With  $F_R$  and  $U_L$  known, the collector useful gain can be calculated from an expression that is similar to that for a flat-plate collector. One significant difference between a concentrating collector and a flat-plate collector is the high temperatures encountered in the concentrating collector. High temperatures mean that thermal radiation is important, leading to the loss coefficient being temperature dependent.

As an example of calculating the thermal losses and the loss coefficient  $U_L$ , consider an uncovered cylindrical absorbing tube used as a receiver with a linear concentrator. Assume that there are no temperature gradients around the receiver tube. The loss and loss coefficient considering convection and radiation from the surface and conduction through the support structure are

$$\begin{aligned}\frac{Q_{\text{loss}}}{A_r} &= h_w (T_r - T_a) + \varepsilon \sigma (T_r^4 - T_{\text{sky}}^4) + U_{\text{cond}} (T_r - T_a) \\ &= (h_w + h_r + U_{\text{cond}}) (T_r - T_a) \\ &= U_L (T_r - T_a)\end{aligned}\tag{7.3.1}$$

The linearized radiation coefficient can be calculated from

$$h_r = \frac{\varepsilon \sigma (T_r^4 - T_{\text{sky}}^4)}{T_r - T_a}\tag{7.3.2}$$

If a single value of  $U_L$  is not acceptable due to large temperature gradients in the flow direction, the collector can be considered as divided into segments each with constant  $U_L$ , as was done by Stuetzle et al. (2004). The estimation of  $h_w$  for cylinders is noted in Section 3.15. Estimation of conductive losses must be based on knowledge of the construction details or on measurements on a particular collector.

Linear concentrators may be fitted with cylindrical absorbers surrounded by transparent tubular covers. For a collector of length  $L$  the heat transfer from the receiver at  $T_r$  to the inside of the cover at  $T_{ci}$  through the cover to  $T_{co}$  and then to the surroundings at  $T_a$  and  $T_{sky}$  is given by

$$Q_{\text{loss}} = \frac{2\pi k_{\text{eff}} L}{\ln(D_{ci}/D_r)} (T_r - T_{ci}) + \frac{\pi D_r L \sigma (T_r^4 - T_{ci}^4)}{\frac{1}{\varepsilon_r} + \frac{1 - \varepsilon_c}{\varepsilon_c} \left(\frac{D_r}{D_{ci}}\right)} \quad (7.3.3)$$

$$Q_{\text{loss}} = \frac{2\pi k_c L (T_{ci} - T_{co})}{\ln(D_{co}/D_{ci})} \quad (7.3.4)$$

$$Q_{\text{loss}} = \pi D_{co} L h_w (T_{co} - T_a) + \varepsilon_c \pi D_{co} L \sigma (T_{co}^4 - T_{sky}^4) \quad (7.3.5)$$

where the subscript  $r$  represents the receiver and subscripts  $ci$  and  $co$  represent the cover inside and outside. The cover thermal conductivity is  $k_c$  and  $k_{\text{eff}}$  is an effective conductivity for convection between the receiver and the cover and is found from Equation 3.11.5. If the annulus is evacuated so that convection is suppressed,  $k_{\text{eff}}$  can be zero at very low pressures.<sup>3</sup> The outside convective coefficient  $h_w$  is calculated with Equation 3.15.12.

The procedure used to solve Equations 7.3.3 to 7.3.5 by hand is to estimate  $T_{co}$  (which will be much closer to  $T_a$  than  $T_r$ ), calculate  $Q_{\text{loss}}$  from Equation 7.3.5, and substitute these quantities into Equation 7.3.4 to find an estimate of  $T_{ci}$ . Equation 7.3.3 is used to check the initial guess of  $T_{co}$  by comparing  $Q_{\text{loss}}$  from Equation 7.3.5 with that calculated from Equation 7.3.3.

It may be necessary to account for absorption of solar radiation by the cover. If so, the absorbed energy can be added to the left-hand side of Equation 7.3.5, which assumes all of the energy is absorbed on the outside of the cover. The principles are identical with those shown in Chapter 6 for flat-plate collectors. If there is significant heat loss through supports to the surroundings, a suitable heat loss equation of the form  $Q_{\text{supp}} = (UA)_{\text{supp}} \Delta T$  can be included with Equations 7.7.3 to 7.7.5. The total heat loss is then the sum of  $Q_{\text{loss}}$  and  $Q_{\text{supp}}$ .

### Example 7.3.1

Calculate the loss coefficient  $U_L$  for a 60-mm cylindrical receiver at 200°C. The absorber surface has an emittance of 0.31. The absorber is covered by a glass tubular cover 90 mm in outer diameter and 4 mm thick. The space between the absorber and cover is evacuated. The wind speed is 5 m/s and the sky and air temperatures are 2 and 10°C, respectively.

### Solution

The equations describing the losses can be solved by various equation-solving programs. Here we will illustrate an iterative hand calculation. For the first guess, assume the cover temperature is 290 K. To estimate the wind heat transfer coefficient, it is necessary to find

<sup>3</sup>With the space initially evacuated over time the space can become filled with hydrogen. A getter is often used to remove hydrogen from the annulus.

the Reynolds number for an air temperature that is the average of the cover and ambient temperatures, or 286.5 K:

$$\text{Re} = \frac{\rho V D}{\mu} = \frac{1.232 \times 5 \times 0.090}{1.794 \times 10^{-5}} = 30,900$$

The wind heat transfer coefficient is then found from Equation 3.15.12:

$$\text{Nu} = \frac{h_w D_{co}}{k} = 0.30(30900)^{0.6} = 148$$

$$h_w = 148 \times \frac{0.2046}{0.090} = 40.5 \text{ W/m}^2 \text{ } ^\circ\text{C}$$

Substituting  $h_w$  into Equation 7.3.5 with a 1-m length provides the first estimate of the loss:

$$\begin{aligned} Q_{\text{loss}} &= \pi \times 0.090 \times 1 [40.5 \times (290 - 283) + 0.88 \times 5.67 \times 10^{-8} (290^4 - 275^4)] \\ &= 99.5 \text{ W} \end{aligned}$$

The inside cover temperature is found from Equation 7.3.4:

$$T_{ci} = 290 + \frac{99.5 \times \ln(0.090/0.082)}{2 \times \pi \times 1.4 \times 1} = 291.1 \text{ K}$$

Equation 7.3.3 is used to find the heat loss, which is compared with the original heat loss. If they are not equal, it is necessary to make another guess of the outside cover temperature. From Equation 7.3.3

$$Q_{\text{loss}} = \frac{\pi \times 0.06 \times 1 \times 5.67 \times 10^{-8} (473^4 - 291.5^4)}{\frac{1}{0.31} + \frac{1 - 0.88}{0.88} \left( \frac{0.060}{0.082} \right)} = 137.8 \text{ W}$$


Since 137.8 is not equal to 99.5 (the difference is +38.3), our initial guess of the outside cover temperature was too low. A second guess of the outside cover temperature of 295 K has an error of  $-27.8$  W. Linear interpolation to find the temperature where the error is zero yields a cover temperature of 292.9 K. With this new cover temperature the loss calculated from Equations 7.3.3 and 7.3.5 are virtually identical and equal to 136.7 W. The loss coefficient (based on receiver area) is found from the definition given by Equation 7.3.1 as

$$U_L = \frac{136.7}{\pi \times 0.06 \times 1 \times (473.0 - 283.0)} = 3.82 \text{ W/m}^2 \text{ } ^\circ\text{C}$$

The large variation of the loss coefficient with receiver temperature is shown in the following figure. A collector that has a significant temperature change in the flow direction should be divided into a number of small sections.<sup>4</sup>

---

<sup>4</sup>The treatment of two or more collectors in series is the subject of Section 10.5.



In Example 7.3.1 the annulus is assumed to be evacuated. If this space is not evacuated, then the heat transfer through the gas must be included. Equations 3.11.5 and 3.11.7 can be used to estimate the gas heat transfer which can be very significant. For example, if air at a pressure of 100 Pa is present in the collector annulus, the loss coefficient at a receiver temperature of 473 K is 6.68 W/m<sup>2</sup> K.

Next consider the factors which account for temperature gradients in the flow direction. The development is analogous to that for flat-plate collectors, but the different geometries require modified procedures. Again treating linear concentrating systems with cylindrical receivers, the heat transfer resistance from the outer surface of the receiving tube to the fluid in the tube should include the tube wall as the heat flux in a concentrating system may be high. The overall heat transfer coefficient (based on the outside receiver tube diameter) between the surroundings and the fluid is

$$U_o = \left( \frac{1}{U_L} + \frac{D_o}{h_f D_i} + \frac{D_o \ln(D_o/D_i)}{2k} \right)^{-1} \quad (7.3.6)$$

where  $D_i$  and  $D_o$  are the inside and outside tube diameters,  $h_f$  is the heat transfer coefficient inside the tube, and  $k$  is the thermal conductivity of the tube.

The useful energy gain per unit of collector length  $q'_u$ , expressed in terms of the local receiver temperature  $T_r$  and the absorbed solar radiation per unit of aperture area  $S$ , is

$$q'_u = \frac{A_a S}{L} - \frac{A_r U_L}{L} (T_r - T_a) \quad (7.3.7)$$

where  $A_a$  is the unshaded area of the concentrator aperture and  $A_r$  is the area of the receiver ( $\pi D_o L$  for the cylindrical absorber). In terms of the energy transfer to the fluid at local fluid temperature  $T_f$ ,

$$q'_u = \frac{(A_r/L)(T_r - T_f)}{\frac{D_o}{h_f D_i} + \left( \frac{D_o}{2k} \ln \frac{D_o}{D_i} \right)} \quad (7.3.8)$$

If  $T_r$  is eliminated from Equations 7.3.7 and 7.3.8, we have

$$q'_u = F' \frac{A_a}{L} \left[ S - \frac{A_r}{A_a} U_L (T_f - T_a) \right] \quad (7.3.9)$$

where the collector efficiency factor  $F'$  is given as

$$F' = \frac{1/U_L}{\frac{1}{U_L} + \frac{D_o}{h_f D_i} + \left( \frac{D_o}{2k} \ln \frac{D_o}{D_i} \right)} \quad (7.3.10)$$

or

$$F' = \frac{U_o}{U_L} \quad (7.3.11)$$

The form of Equations 7.3.9 to 7.3.11 is identical to that of Equations 6.5.16 to 6.5.19. If the same procedure is followed as was used to derive Equation 6.7.6, the following equation results:

$$Q_u = F_R A_a \left[ S - \frac{A_r}{A_a} U_L (T_i - T_a) \right] \quad (7.3.12)$$

In a manner analogous to that for a flat-plate collector, the collector flow factor  $F''$  is given as

$$F'' = \frac{F_R}{F'} = \frac{\dot{m} C_p}{A_r U_L F'} \left[ 1 - \exp \left( - \frac{A_r U_L F'}{\dot{m} C_p} \right) \right] \quad (7.3.13)$$

The differences between covered and uncovered receivers are in the calculations of  $S$  and  $U_L$ .

If a receiver of this type serves as a boiler,  $F'$  is given by Equation 7.3.10, but  $F_R$  is then identically equal to  $F'$  as there is no temperature gradient in the flow direction. If a part of the receiver serves as a boiler and other parts as fluid heaters, the two or three segments of the receiver must be treated separately.

### Example 7.3.2

A cylindrical parabolic concentrator with width 2.5 m and length 10 m has an absorbed radiation per unit area of aperture of 430 W/m<sup>2</sup>. The receiver is a cylinder with an emittance of 0.31 and is surrounded by an evacuated glass cylindrical envelope. The absorber has a diameter of 60 mm, and the transparent envelope has an outer diameter of 90 mm with a thickness of 4 mm. The collector is designed to heat a fluid entering the absorber at 155.2°C at a flow rate of 0.0537 kg/s. The fluid has  $C_p = 3.26$  kJ/kg°C. The heat transfer coefficient inside the tube is 300 W/m<sup>2</sup> °C and the overall loss coefficient is 3.82 W/m<sup>2</sup> °C (from Example 7.3.1). The tube is made of stainless steel ( $k = 16$  W/m °C) with a wall thickness of 5 mm. If the ambient temperature is 10°C, calculate the useful gain and exit fluid temperature.

### Solution

The solution is based on Equation 7.3.12. The area of the receiver is

$$A_r = \pi D L = \pi \times 0.06 \times 10 = 1.88 \text{ m}^2$$

Taking into account shading of the central part of the collector by the receiver,

$$A_a = (2.5 - 0.09) 10 = 24.1 \text{ m}^2$$

To calculate  $F_R$  we first calculate  $F'$  for this situation from Equation 7.3.10:

$$F' = \frac{1/3.82}{\frac{1}{3.82} + \frac{0.060}{300 \times 0.050} + \frac{0.060 \ln(0.060/0.050)}{2 \times 16}} = 0.984$$

Then  $F_R$  from Equation 7.3.13 is calculated as follows:

$$\begin{aligned} \frac{\dot{m}C_p}{A_r U_L F'} &= \frac{0.0537 \times 3260}{1.88 \times 3.82 \times 0.984} = 24.77 \\ F'' &= 24.77 [1 - \exp(-1/24.77)] = 0.980 \\ F_R &= F'' \times F' = 0.980 \times 0.984 = 0.964 \end{aligned}$$

The useful gain from Equation 7.13.12 is

$$Q_u = 24.1 \times 0.964 \left[ 430 - \frac{1.88 \times 3.82}{24.1} (200 - 10) \right] = 8675 \text{ W}$$

The fluid temperature rise is

$$\Delta T = \frac{Q_u}{\dot{m}C_p} = \frac{8675}{0.0537 \times 3260} = 49.6^\circ\text{C}$$

and the exit fluid temperature is  $155.2 + 49.6 = 204.8^\circ\text{C}$ . The average temperature drop from the outside of the receiver to the fluid is

$$\begin{aligned} \bar{T}_{ro} - \bar{T}_f &= Q_u \left[ \frac{1}{\pi D_{ri} L h_{fi}} + \frac{\ln(D_{ro}/D_{ri})}{2\pi k_{\text{rec}} L} \right] \\ &= 8675 \left[ \frac{1}{\pi \times 0.05 \times 10 \times 300} + \frac{\ln(0.060/0.050)}{2 \times \pi \times 16 \times 10} \right] = 20.0^\circ\text{C} \end{aligned}$$

so that the average receiver temperature is  $(155.2 + 204.8)/2 + 20.0 = 200^\circ\text{C}$ , which was the assumed value in Example 7.3.1. Under typical circumstances the average receiver surface temperature would not be known and it would be necessary to solve the equations of Examples 7.3.1 and 7.3.2 simultaneously. See Problem 7.2. ■

Control problems can arise for collectors that are very long in the flow direction. Parabolic trough collectors can be more than 1000 m long so that the heat transfer fluid may take one-half hour or more to traverse from inlet to outlet. If the desire is to maintain a constant outlet temperature, the only available control variable is the fluid flow rate. An adjustment of the flow rate will continue to have an impact on the outlet temperature for the duration of the fluid transit time. Stuetzle et al. (2004) used a model predictive control strategy to control the flow rate in an optimal manner. A mathematical model of the collector was developed that includes the transit time and was used with a predicted weather pattern to predict future outlet temperatures. An optimum time-dependent flow rate was determined with the model and predicted weather and used to control the real fluid flow rate for a short

period of time. At the end of the short time period another time-dependent optimal flow rate was determined and the processes repeated. Although the process was not tested in a real system, it was tested by simulation with good results.

## 7.4 OPTICAL PERFORMANCE OF CONCENTRATING COLLECTORS

Concentrating collectors have optical properties that vary substantially with the geometry of the device. The following general concepts can be applied to all concentrators, although the ways in which they are applied vary with configuration. An equation for  $S$ , the absorbed radiation per unit area of unshaded aperture, can be written as

$$S = I_b \rho (\gamma \tau \alpha)_n K_{\gamma \tau \alpha} \quad (7.4.1)$$

The terms in this equation have implications that are different from those for flat-plate collectors, and the treatment of them depends on collector geometry.

The effective incident radiation measured on the plane of the aperture  $I_b$  includes only beam radiation for all concentrators except those of low concentration ratio (i.e., perhaps 10 or below). For systems of low concentration ratio, part of the diffuse radiation will be reflected to the receiver, with the amount depending on the acceptance angle of the concentrator.

Generally  $\rho$  is the specular reflectance of the concentrator. For diffuse reflectors used with cylindrical absorbers, it will be the diffuse reflectance. If the concentrator is a refractor, it will be the transmittance of the refractor.

The next three factors,  $\gamma$ ,  $\tau$ , and  $\alpha$ , are functions of the angle of incidence of radiation on the aperture. The effects of angle of incidence on these characteristics may be considered individually or they may, as implied by Equation 7.4.1, be combined in an incidence angle modifier.

The **intercept factor**  $\gamma$  is defined as the fraction of the reflected radiation that is incident on the absorbing surface of the receiver. This concept is particularly useful in describing imaging concentrators. An example of an image formed in the focal plane of a linear concentrator is shown in Figure 7.4.1; if a receiver extends from  $A$  to  $B$ , the intercept factor will be


$$\gamma = \frac{\int_A^B I(w) dw}{\int_{-\infty}^{+\infty} I(w) dw} \quad (7.4.2)$$

The objective in using concentrating systems is to reduce heat losses from the absorber by reducing its area. Most imaging collectors are built with receivers large enough to intercept a large fraction of the reflected radiation but not large enough to intercept the low-intensity fringes of the images. Values of  $\gamma$  greater than 0.9 are common.

Here  $\tau$  is the transmittance of any cover system on the receiver. Its calculation may be difficult as the angles of incidence of the radiation from the reflector on the cover may be uncertain. The absorptance of the absorber for the reflected (and transmitted) solar radiation,  $\alpha$ , may be difficult to determine for the same reason as that of  $\tau$ .

An incidence angle modifier  $K_{\gamma \tau \alpha}$  can be used to account for deviations from the normal of the angle of incidence of the radiation on the aperture. For cylindrical systems,





**Figure 7.4.1** An example of a flux distribution in the focal plane of a linear imaging concentrator. The receiver extends from A to B.

biaxial incidence modifiers are required, with separate treatment for the longitudinal and transverse planes. However, the transverse incidence angle modifier would only be used for tracking errors and may not be needed in practice. For circular systems that are fully symmetric, a single modifier will be adequate. If the system is not fully symmetric,<sup>5</sup> biaxial or possibly more complex modifiers will be needed. As written in Equation 7.4.1,  $K_{\gamma\tau\alpha}$  includes the effects of angle of incidence on the intercept factor; in general, as the angle of incidence of radiation increases, the size of the image will increase and the fraction of the reflected radiation intercepted by the receiver will decrease. With cylindrical (linear) systems there may be end effects if the collector is not long compared to its focal length; this effect can be included in  $K_{\gamma\tau\alpha}$ .


These optical terms will be discussed for two classes of concentrators, nonimaging and imaging, in the following sections.

## 7.5 CYLINDRICAL ABSORBER ARRAYS


In Chapter 6, we discussed collectors with selective flat absorbers placed in evacuated tubes and noted that low loss coefficients can be obtained. Another type of evacuated tubular collector is the Dewar type in which the vacuum is maintained between two concentric glass tubes; a cylindrical absorbing surface is on the outside of the inner of the two tubes or on a cylindrical fin inside of the inner tube. Two important configurations of these tubes are shown in Figures 7.5.1(a) and (b).

In type (a), the selective absorbing surface is on the outside of the inner glass tube of the vacuum jacket, in the evacuated space. A third tube, the delivery tube, is used to move fluid into (or out of) the end of the Dewar and thus move the fluid past the solar-heated inner tube of the jacket. The working fluid fills the space inside of the Dewar. The delivery tube should be designed to reduce thermal coupling between the in and out streams. Figure 7.5.1(b) shows a design with a fin-and-tube absorber inserted in the Dewar. The fin is rolled into a cylindrical form to provide a “spring” fit when inserted. The absorbing

<sup>5</sup>The central-receiver collectors described in Sections 7.15 and 17.5 are examples of unsymmetrical circular systems.



**Figure 7.5.1** Two types of evacuated Dewar tubes with cylindrical absorbers: (a) Dewar with delivery tube; (b) Dewar with inserted fin and tube. Adapted from International Energy Agency (1986).




**Figure 7.5.2** Section of a collector with an array of cylindrical absorbers and a diffuse back reflector.


surface is on the fin. In this design, the quantity of fluid in the Dewar is very much less, and breakage of a tube does not result in loss of fluid and failure of an array.

Figure 7.5.2 shows a cross section of an array of cylindrical absorbers spaced approximately a diameter apart and a diameter above a diffuse back reflector. Some of the incident radiation is absorbed directly by the cylinders. Some that is incident on the back reflector is reflected to the cylinders, and some is reflected back to the sky and lost. The optical properties of these reflectors and tube arrays are nonsymmetrical (as are those of flat absorbers with cylindrical covers) and biaxial incidence angle modifiers are used. Theunissen and Beckman (1985) have computed the optical properties of arrays of tubes for incident beam, diffuse, and reflected radiation, for arrays sloped toward the south with tube axes north-south, and with the diffuse reflectance of the back reflector equal to 0.8.

Values of  $F_R(\gamma\tau\alpha)_n$  for these collectors with flat diffuse back reflectors are typically 0.65 to 0.70. Transverse plane incidence angle modifiers for a collector of this type are shown in Figure 7.5.3. Data are from Chow et al. (1984), who also did ray-trace studies to derive theoretical incidence angle modifier (IAM) curves; they found that the measured curves agreed with the theoretical within the experimental errors. Mather (1980) notes similar experimental results.



**Figure 7.5.3** Measured transverse incidence angle modifiers for 30-mm-diameter cover tubes and 22-mm absorber tubes over white diffuse back reflectors. Curve *a*: tube-to-tube spacing  $s = 60$  mm and height  $h = 40$  mm. Curve *b*: tube-to-tube spacing is 45 mm and height is 32 mm. Data from Chow et al. (1984).



**Figure 7.5.4** Calculated loss coefficients for evacuated tubular collectors of the type shown in Figure 7.5.1(a) considering (a) radiation transfer only across the evacuated space and (b) adding an estimate of 50% to allow for manifold losses. The  $U$  values are based on aperture area of an array with tubes spaced a tube diameter apart. Based on Rabl (1985).

Loss coefficients for these collectors are more temperature dependent than those for flat-plate collectors. Radiation, the major mechanism for heat transfer across the evacuated space, is dependent on the difference of the fourth power of the temperatures, and the collectors in many applications run at higher temperatures than flat-plate collectors. Rabl (1985) shows calculations of overall loss coefficients for the tubes based on the absorber area. For typical spacing of tubes with a tube diameter space between them, the results based on aperture area  $U_{ap}$  are shown as curve (a) in Figure 7.5.4. Rabl suggests that losses in manifolds can be as much as 50% of those from the tubes. Curve (b) reflects this increase and can be considered as an overall loss coefficient  $U_L$  from an array of tubes and its associated manifold.


## 7.6 OPTICAL CHARACTERISTICS OF NONIMAGING CONCENTRATORS

It is possible to construct concentrating collectors that can function seasonally or annually with minimum requirements for tracking (with its attendant mechanical complications).

These nonimaging concentrators have the capability of reflecting to the receiver all of the incident radiation on the aperture over ranges of incidence angles within wide limits. The limits define the **acceptance angle** of the concentrator. As all radiation incident within the acceptance angle is reflected to the receiver, the diffuse radiation within these angles is also useful input to the collector.


Most of this section is devoted to **compound parabolic concentrators**.<sup>6</sup> These concentrators had their origins in instruments for detection of Cherenkov radiation in high-energy physics experiments, a development noted by Hinterberger and Winston (1966). An independent and parallel development occurred in the USSR (Baranov and Melnikov, 1966). Their potential as concentrators for solar energy collectors was pointed out by Winston (1974), and they have been the basis of detailed study since then by Welford and Winston (1978), Rabl (1976a,b), and many others.

The basic concept of the CPC is shown in Figure 7.6.1. These concentrators are potentially most useful as linear or trough-type concentrators (although the analysis has also been done for three-dimensional concentrators), and the following is based on the two-dimensional CPC. Each side of the CPC is a parabola; the focus and axis of only the right-hand parabola are indicated. Each parabola extends until its surface is parallel with the CPC axis. The angle between the axis of the CPC and the line connecting the focus of one of the parabolas with the opposite edge of the aperture is the acceptance half-angle  $\theta_c$ . If the reflector is perfect, any radiation entering the aperture at angles between  $\pm\theta_c$  will be reflected to a receiver at the base of the concentrator by specularly reflecting parabolic reflectors.



**Figure 7.6.1** Cross section of a symmetrical nontruncated CPC.

<sup>6</sup>The term CPC is applied to many nonimaging concentrators even though their geometry differs from parabolic.




**Figure 7.6.2** Fraction of radiation incident on the aperture of a CPC at angle  $\theta$  which reaches the absorber surface if  $\rho = 1$ :  $\theta_c$  = acceptance half-angle,  $\Delta$  = angular surface error. (—) Full CPC with no surface errors; (-----) truncated CPC with no surface errors; (.....) full CPC with surface errors. Adapted from Rabl (1976b).

Concentrators of the type of Figure 7.6.1 have area concentration ratios which are functions of the acceptance half-angle  $\theta_c$ . For an ideal two-dimensional system the relationship is<sup>7</sup>

$$C_i = \frac{1}{\sin \theta_c} \quad (7.6.1)$$


An ideal CPC in this context is one which has parabolas with no errors. Thus an ideal CPC with an acceptance half-angle of  $23.5^\circ$  will have  $C_i = 2.51$ , and one with an acceptance half-angle of  $11.75^\circ$  will have  $C_i = 4.91$ . Figure 7.6.2 shows the fraction of radiation incident on the aperture at angle  $\theta$  which reaches the absorber as a function of  $\theta$ . For the ideal CPC, the fraction is unity out to  $\theta_c$  and zero beyond. For a real CPC with surface errors, some radiation incident at angles less than  $\theta_c$  does not reach the absorber, and some at angles greater than  $\theta_c$  does reach it.

At the upper end points of the parabolas in a CPC, the surfaces are parallel to the central plane of symmetry of the concentrator. The upper ends of the reflectors thus contribute little to the radiation reaching the absorber, and the CPC can be truncated to reduce its height from  $h$  to  $h'$  with a resulting saving in reflector area but little sacrifice in performance. A truncated CPC is shown in Figure 7.6.3. The dashed plot in Figure 7.6.2 shows the spread



**Figure 7.6.3** A CPC truncated so its height-aperture ratio is about one-half of the full CPC.

<sup>7</sup>This can be shown by the same arguments that led to Equations 7.2.6.




**Figure 7.6.4** Ratio of height to aperture for full and truncated CPCs as a function of  $C$  and  $\theta_c$ . Adapted from Rabl (1976b).

of the image for the truncated concentrator. Limited truncation affects the acceptance angle very little, but it does change the height-to-aperture ratio, the concentration ratio, and the average number of reflections undergone by radiation before it reaches the absorber surface. The effects of truncation are shown for otherwise ideal CPCs in Figures 7.6.4 to 7.6.6. Figure 7.6.4 shows the height-to-aperture ratio and Figure 7.6.5 shows the ratio of reflector area to aperture area. Figure 7.6.6 shows the average number of reflections undergone by radiation entering the aperture before it reaches the absorber. If the truncation is such that the average number of reflections is below the  $(N)_{\min}$  curve, that average number is at least  $1 - 1/C$ .


The use of these plots can be illustrated as follows. An ideal full CPC has an acceptance half-angle  $\theta_c$  of  $12^\circ$ . From Figure 7.6.4 the height-to-aperture ratio is 2.8 and the concentration ratio is 4.8. From Figure 7.6.5, the area of reflector required is 5.6 times the aperture. The average number of reflections undergone by radiation before reaching the absorber surface is 0.97 from Figure 7.6.6. If this CPC is truncated so that its height-to-aperture ratio is 1.4, from Figure 7.6.4 the concentration ratio will drop to 4.2. Then from Figure 7.6.5 the reflector area–aperture area ratio is 3.0 and from Figure 7.6.6 the average number of reflections will be at least  $1 - 1/4.2 = 0.76$ .

Figures 7.6.4 to 7.6.6 are sometimes difficult to read to the desired accuracy. The following equations were used to generate these plots.<sup>8</sup> Equations 7.6.2 to 7.6.4 for a

<sup>8</sup>These equations can have multiple solutions. Like most nonlinear systems of equations good guesses are often needed to find the appropriate solution. Valid solutions will have  $h_r/h \leq 1$  and  $\phi \geq 2\theta$ .



**Figure 7.6.5** Ratio of reflector area to aperture area for full and truncated CPCs. Adapted from Rabl (1976b).



**Figure 7.6.6** The average number of reflections undergone by radiation within the acceptance angle reaching the absorber surface of full and truncated CPCs. Adapted from Rabl (1976b).

full CPC and 7.6.5 to 7.6.8 for a truncated CPC (with subscript  $T$ ) are from Welford and Winston (1978). Equation 7.6.9, the average number of reflections for either a full or truncated CPC, is from Rabl (1976a):

$$f = a'(1 + \sin \theta_c) \quad (7.6.2)$$

$$a = \frac{a'}{\sin \theta_c} \quad (7.6.3)$$

$$h = \frac{f \cos \theta_c}{\sin^2 \theta_c} \quad (7.6.4)$$

$$a_T = \frac{f \sin(\phi_T - \theta_c)}{\sin^2(\phi_T/2)} - a' \quad (7.6.5)$$

$$h_T = \frac{f \cos(\phi_T - \theta_c)}{\sin^2(\phi_T/2)} \quad (7.6.6)$$

$$C = \frac{a_T}{a'} \quad \text{or for a full CPC} \quad C = \frac{a}{a'} = \frac{1}{\sin \theta_c} \quad (7.6.7)$$

$$\frac{A_{RT}}{2a_T} = \frac{f}{2} \left[ \frac{\cos(\phi/2)}{\sin^2(\phi/2)} + \ln \cot\left(\frac{\phi}{4}\right) \right] \Big|_{\theta_c+\pi/2}^{\phi_T} \quad (7.6.8)$$

$$n_i = \max \left[ C \frac{A_{RT}}{4a_T} - \frac{x^2 - \cos^2 \theta}{2(1 + \sin \theta)}, 1 - \frac{1}{C} \right] \quad (7.6.9a)$$

$$x = \left( \frac{1 + \sin \theta}{\cos \theta} \right) \left( -\sin \theta + \left( 1 + \frac{h_T}{h} \cot^2 \theta \right)^{1/2} \right) \quad (7.6.9b)$$

where  $A_{RT}$  is the reflector area per unit depth of a truncated CPC (if  $\phi_T = 2\theta_c$ , then  $A_{RT} = A_R$ ),  $n_i$  is the average number of reflections, and the other variables are shown in Figure 7.6.3.

### Example 7.6.1

A CPC is to be designed with a concentration ratio of 2.0. Prepare plots of  $\theta_c$ ,  $\phi$ ,  $A_{RT}$ ,  $h_T$ , and  $n_i$  as functions of the ratio of the truncated height to the full CPC height.


### Solution

In order to prepare the plots, we need to solve the CPC equations 7.6.2 to 7.6.9 since it is difficult to read the graphs with sufficient accuracy. From any of the three plots it is clear that a full CPC with an acceptance angle of about  $30^\circ$  or a truncated CPC with a smaller acceptance angle will satisfy the requirement of the problem. From Equation 7.6.7 a full CPC with  $C = 2$  has  $\theta_c = \sin^{-1}(\frac{1}{2}) = 30^\circ$ . We will assume the absorber area  $a'$  is equal to unity so that from Equation 7.6.2 the focal length  $f = (1 + \sin \theta_c) = 1.5$ . The aperture area  $a = 2$  from Equation 7.6.3 and the height  $h = 2.60$  from Equation 7.6.4. For this full



CPC the angle  $\phi$  is equal to the angle  $2\theta_c$  so that, from Equation 7.6.8,  $A_R = 2.67$ . The average number of reflections from Equation 7.6.9 is 0.67.


For a truncated CPC with, for example, a known value of  $h/h_T$  we need to solve simultaneously for  $\theta_c$ ,  $\phi$ ,  $f$ ,  $h$ , and  $h_T$  from Equations 7.6.2, 7.6.4, 7.6.5, and 7.6.6. Solving systems of algebraic equations is EESy with appropriate software. With  $h/h_T = 0.5$  we find  $\theta_c = 27.02$ ,  $\phi = 70.73$ ,  $f = 0.727$ ,  $h = 3.14$ , and  $h_T = 1.57$ . The truncated receiver area  $A_{RT}$  is then 1.66 and the average number of reflections is 0.5. Choosing a range of values for  $h/h_T$  from 0 to 1 the following plot can be constructed.




Compound parabolic concentrators with flat receivers should have a gap between the receiver and the reflector to prevent the reflector from acting as a fin conducting heat from the receiver. The gap results in a loss of reflector area and a corresponding loss in performance and should be kept small (Rabl, 1985).

The preceding discussion has been based on flat receivers occupying the plane between the two foci (Figure 7.6.3). Other receiver shapes can be used; Winston and Hinterberger (1975) showed that a CPC can be developed with aperture  $l$  which will concentrate incident radiation with incidence angles between  $\pm\theta_c$  onto any convex absorber with circumference  $l \sin \theta_c$ . The method of generation of the shape of the CPC is illustrated by Figure 7.6.7, which shows a special case of interest, a cylindrical absorber. Parts  $AB$  and  $AC$  of the reflector are convolutes of parts  $AF$  and  $AG$  of the absorber. The requirement for the rest of the reflector is that at any point  $P$  the normal to the reflector  $NP$  must bisect the angle between the tangent to the absorber  $PT$  and the line  $QP$ , which is at an angle  $\theta_c$  to the axis of the CPC. This CPC is used with evacuated tubular receivers. They can be truncated in the same way as other CPCs. An example is shown in Figure 7.6.8.


This method can be used to generate a reflector for any convex receiver shape. Thus a set of CPC-type concentrators (not necessarily parabolas) can be evolved that permit



**Figure 7.6.7** A CPC for a tubular receiver. Adapted from Rabl (1978).



**Figure 7.6.8** An array of truncated CPC reflectors with evacuated tubular receivers with a glass cover over the array. Courtesy of Energy Design Corporation.



**Figure 7.6.9** Involute reflector for use with cylindrical absorber. Adapted from O'Gallagher et al. (1980).

a range of choices of receiver shape. The CPCs can be used in series; the receiver for a primary concentrator can be the aperture of a secondary concentrator. The concentrators need not be symmetrical.

Tubular absorbers are often used with CPC reflectors. O'Gallagher et al. (1980) have shown that the reflector shape leading to maximum absorption of radiation by cylindrical absorbers is an involute, shown in Figure 7.6.9.

## 7.7 ORIENTATION AND ABSORBED ENERGY FOR CPC COLLECTORS

The advantages of CPCs are that they can function without continuous tracking and still achieve some concentration. However, they must be properly oriented to maximize the absorbed radiation when output from the collector is needed. To determine the operation at any time (which is a step to finding the best orientation), it is necessary to calculate the absorbed radiation. A particularly critical question is whether or not the beam radiation will be absorbed.

A logical orientation for such a collector is along a horizontal east-west axis, sloped toward the equator, and more or less adjustable about that axis. The CPC is arranged so that the pseudo-incidence angle<sup>9</sup> of beam radiation (the projection of the angle of incidence on the north-south vertical plane) lies within the limits  $\pm \theta_c$  during the times when output is needed from the collector. In practice, compromises are necessary between frequency of movement of the collector and concentration ratio, with high ratios associated with small acceptance angles and relatively frequent positioning.

To estimate the radiation absorbed by the receiver of a CPC, it is necessary to determine if the angle of incidence of the beam radiation is within the acceptance angle  $2\theta_c$  and then estimate the contributions of the beam and diffuse radiation plus the ground-reflected radiation if it is within the acceptance angle. The absorbed radiation can be estimated as

$$S = G_{b,CPC} \tau_{c,b} \tau_{CPC,b} \alpha_b + G_{d,CPC} \tau_{c,d} \tau_{CPC,d} \alpha_d + G_{g,CPC} \tau_{c,g} \tau_{CPC,g} \alpha_g \quad (7.7.1a)$$

$$G_{b,CPC} = F G_{bn} \cos \theta \quad (7.7.1b)$$


$$G_{d,CPC} = \begin{cases} \frac{G_d}{C} & \text{if } (\beta + \theta_c) < 90^\circ \\ \frac{G_d}{2} \left( \frac{1}{C} + \cos \beta \right) & \text{if } (\beta + \theta_c) > 90^\circ \end{cases} \quad (7.7.1c)$$

$$G_{g,CPC} = \begin{cases} 0 & \text{if } (\beta + \theta_c) < 90^\circ \\ \frac{G_d}{2} \left( \frac{1}{C} - \cos \beta \right) & \text{if } (\beta + \theta_c) > 90^\circ \end{cases} \quad (7.7.1d)$$

The first term in Equation 7.7.1a is the beam contribution to  $S$ , the second is the contribution of the diffuse, and the third is the contribution of the ground-reflected radiation. In the first term,  $G_{b,CPC}$  is the beam radiation on the aperture that is within the acceptance angle,  $\tau_{c,b}$  is the transmittance for beam radiation of any cover which may be placed over the concentrator array, and  $\alpha_b$  is the absorptance of the receiver for the beam radiation. The factor  $\tau_{CPC,b}$  is a “transmittance” of the CPC which accounts for reflection losses and is a function of the average number of reflections. The factors in the terms for diffuse and ground-reflected radiation are analogous to those for the beam radiation.

The ground-reflected radiation is only effective if  $\beta + \theta_c > 90^\circ$ , that is, if the receiver “sees” the ground. The angles are shown in Figure 7.7.1. Equations 7.7.1c and 7.7.1d

<sup>9</sup>This angle is referred to in architectural literature as the solar profile angle and by Hollands (1971) as the east-west vertical (EWV) angle.



**Figure 7.7.1** Projection on a north-south plane of CPC acceptance angles and slope for a CPC on an east-west axis.

account for the contribution or lack thereof of the ground-reflected radiation. Here the diffuse radiation is assumed to be isotropic.<sup>10</sup>

Figure 7.7.1 shows the acceptance angle of a CPC on a vertical north-south plane for a CPC oriented east-west. Two angles,  $\beta - \theta_c$  and  $\beta + \theta_c$ , are the angles from the vertical in this plane to the two limits describing the acceptance angle. Mitchell (1979) has shown that the following condition must be met in order for the beam radiation to be effective:

$$(\beta - \theta_c) \leq \tan^{-1}(\tan \theta_z \cos \gamma_s) \leq (\beta + \theta_c) \quad (7.7.2)$$

It is convenient to introduce the **control function**  $F$  in Equation 7.7.1b, which is 1 if the criterion of Equation 7.7.2 is met and 0 otherwise. If beam radiation is incident on the aperture within the acceptance angle,  $F = 1$  and the beam radiation term will be included in the calculation of  $S$ .


A CPC collector will probably have a transparent cover over the array of reflectors. This serves both to protect the reflecting and absorbing surfaces and to reduce thermal losses from the absorber. Then beam and diffuse radiation effectively entering the CPC are reduced by the transmittance of the cover  $\tau_c$ .

Only part of the incident diffuse radiation effectively enters the CPC, and that part is a function of the acceptance angle. A relationship between the mean angle of incidence of effective diffuse radiation from the sky and the acceptance half-angle  $\theta_c$  is shown in Figure 7.7.2. This is based on the assumption that the diffuse radiation is isotropic. The relationship depends on the nature of the cover system, and the figure shows a band of solutions including one and two covers, refractive indices from 1.34 to 1.526, and  $KL$  per cover up to 0.0524. An equation for the equivalent angle of incidence  $\theta_e$  (the dashed line) is

$$\theta_e = 44.86 - 0.0716\theta_c + 0.00512\theta_c^2 - 0.00002798\theta_c^3 \quad (7.7.3)$$

Thus for a CPC with  $\theta_c = 20^\circ$ , the mean angle of incidence of effective diffuse radiation is  $45^\circ$  and the transmittance of the cover for this radiation is that of beam radiation at  $45^\circ$ . In general, CPCs are orientated such that they do not utilize any ground-reflected radiation. If the CPC can see the ground, then the effective incidence angle for ground-reflected radiation and diffuse radiation can be assumed to be equal.

<sup>10</sup>If the diffuse has a significant circumsolar contribution, the method described in this section will underestimate the effective diffuse radiation.



**Figure 7.7.2** Equivalent incidence angle for isotropic diffuse radiation for a CPC as a function of acceptance half-angle. From Brandemuehl and Beckman (1980).

The terms  $\tau_{CPC,b}$ ,  $\tau_{CPC,d}$ , and  $\tau_{CPC,g}$  in Equation 7.7.1a are transmittances of the CPC that account for the specular reflectance of the concentrator and the average number of reflections. The terms are usually treated as the same, and an appropriate value to be applied to all three of them is estimated from the number of reflections  $n_i$  from Figure 7.6.6 and the reflectance  $\rho$  by the equation

$$\tau_{CPC} = \rho^{n_i} \quad (7.7.4)$$

Here it is assumed that end effects are negligible or that the ends are highly reflective.

The absorptances  $\alpha_b$ ,  $\alpha_d$ , and  $\alpha_g$  of the receiver surface depend on the angles of incidence of the radiation on the surface. The angles of incidence vary depending on the angle of incidence of the radiation on the aperture of the CPC, the number of reflections undergone by the radiation, and the shape of the reflecting and receiving surfaces. If the average number of reflections is small, as it will be for large acceptance angles, then as a first approximation the absorptance can be taken as that corresponding to the angle of incidence of the effective radiation on the aperture of the CPC; however, this will generally result in overestimation of  $\alpha$ . Due to lack of design information, there may be no alternative.

### Example 7.7.1

An uncovered full CPC collector array is mounted on a horizontal east-west axis and oriented at a slope of  $25^\circ$  from the horizontal. The latitude is  $35^\circ$  N. The acceptance angle  $2\theta_c = 24^\circ$ . At 10 AM on August 1, the beam normal radiation  $G_{bn} = 805 \text{ W/m}^2$ . Estimate the beam radiation incident on the CPC per square meter of aperture area.

**Solution**

The first step is to see if the criterion of Equation 7.7.2 is met, that is, whether  $F$  is 0 or 1. For this date,  $n = 213$ ,  $\omega = -30^\circ$ , and  $\delta = 17.9^\circ$ . From Equation 1.6.5,  $\theta_z = 31.6^\circ$ . From Equations 1.6.6

$$\gamma_s = (-1) \left| \cos^{-1} \left( \frac{\cos 31.6 \sin 35 - \sin 17.9}{\sin 31.6 \cos 35} \right) \right| = -65.2^\circ$$

For this collector,  $\beta - \theta_c = 25 - 12 = 13^\circ$  and  $\beta + \theta_c = 25 + 12 = 37^\circ$ . From Equation 7.7.2,  $\tan^{-1} [\tan 31.6 \cos(-65.2)] = 14.5^\circ$ . Since  $14.5^\circ$  lies between  $13^\circ$  and  $37^\circ$ ,  $F = 1$ . The angle of incidence of the beam radiation on the aperture can be obtained with Equation 1.6.7a:

$$\cos \theta = \cos(35 - 25) \cos 17.9 \cos 30 + \sin(35 - 25) \sin 17.9 = 0.865$$

The effective beam radiation incident on the aperture of the CPC is

$$G_{b,CPC} = 1 \times 805 \times 0.865 = 700 \text{ W/m}^2 \quad \blacksquare$$

**Example 7.7.2**

At the location and time of Example 7.7.1 the diffuse radiation on a horizontal surface is  $320 \text{ W/m}^2$ . The CPC of Example 7.7.1 is truncated and has a concentration ratio of 4.5. The reflectance of the CPC reflector is 0.89 and the absorptance of the receiver is 0.94. Estimate the total radiation absorbed by the receiver per unit receiver area if the CPC array has a glass cover with  $KL = 0.0125$ .

**Solution**

For these circumstances  $\beta + \theta_c = 37^\circ$ , so there is no contribution of ground-reflected radiation. Equation 7.7.1c is used to estimate the effective diffuse radiation:

$$G_{d,CPC} = \frac{320}{4.5} = 71 \text{ W/m}^2$$

The angle of incidence of the beam radiation on the cover is  $\cos^{-1}(0.865)$ , or  $30^\circ$ . The transmittance of the cover for this radiation, from Figure 5.3.1, is 0.90. The mean angle of incidence for the diffuse radiation from Figure 7.7.2 is  $45^\circ$ . From Figure 5.3.1 the transmittance for this radiation is 0.89. From Figure 7.6.6 the average number of reflections is 0.81. The radiation absorbed by the receiver per unit area of the receiver is then the contribution of the beam and diffuse components times the concentration ratio:

$$S = 4.5 \times 0.94 \times (700 \times 0.90 + 71 \times 0.89) 0.89^{0.81} = 2668 \text{ W/m}^2 \quad \blacksquare$$

**Example 7.7.3**

What is the diffuse and ground-reflected radiation incident on the receiver surface for a full CPC collector with an acceptance half-angle of  $18^\circ$  sloped at  $80^\circ$  to south at latitude  $35^\circ$ ? The horizontal total radiation is  $530 \text{ W/m}^2$ , the diffuse is  $175 \text{ W/m}^2$ , and the ground reflectance is 0.7.

**Solution**

In this case the ground-reflected radiation must be considered, as  $\beta + \theta_c > 90^\circ$ . Equations 7.7.1c and 7.7.1d are used with  $C$  replaced by  $1/\sin \theta_c$  for this full CPC:

$$G_{d,CPC} = \frac{175}{2}(\sin 18 + \cos 80) = 42.2 \text{ W/m}^2$$


$$G_{g,CPC} = \frac{530 \times 0.7}{2}(\sin 18 - \cos 80) = 25.1 \text{ W/m}^2$$

There are a variety of CPC geometries that require special treatment. For example, a common form of CPC uses evacuated tubular receivers with cylindrical absorbing surfaces, interposing an additional cover that must be considered. Evacuated tubes with flat receivers can also be used with cusp reflectors similar to those shown in Figure 7.6.9. With the procedures outlined in this section, it is possible to estimate the energy absorbed by many CPC collectors. In the next section, the absorbed energy is combined with the thermal performance analysis of Section 7.2 to show how collector performance can be estimated for any set of operating conditions.

## 7.8 PERFORMANCE OF CPC COLLECTORS

The basic equation summarizing the performance of a CPC collector is Equation 7.3.12, where  $S$  is calculated by Equations 7.7.1. The remaining question is the calculation of the appropriate thermal loss coefficient  $U_L$ . Losses from CPCs will include losses from the receivers (which are calculated by methods that are basically the same as for other collectors) plus losses from manifolds, as shown in Figure 7.5.4.

Rabl (1976b) presents a discussion of calculation of loss coefficients for a CPC collector geometry using a flat absorber. Figure 7.8.1 shows his estimations of overall



**Figure 7.8.1** Estimated loss coefficients for CPC collectors with flat absorbers. From Rabl (1976b).

loss coefficients per unit area of absorber for use in Equation 7.3.12. The coefficients are functions of concentration ratio; the method used in their estimation assumed fixed conduction losses independent of concentration ratio, and both radiation and convection from plate to cover are to some degree functions of the concentration ratio. Estimates are shown for two plate emittances and two plate temperatures.

With estimates of  $U_L$  from Figure 7.8.1, from measurements, or from calculations and with knowledge of the meteorological conditions and inlet fluid temperature, the procedure for calculating collector output is the same as for a flat-plate collector. Then  $F_R$  is calculated from  $F'$ ,  $U_L$ , and the fluid flow rate  $\dot{m}$  and  $F''$  is calculated by Equation 7.3.13;  $Q_u$  is calculated with Equation 7.3.12, and the average plate temperature is calculated as the basis for a check of the assumed  $T_p$  (and  $U_L$ ).

### Example 7.8.1

The CPC collector of Example 7.7.2 has a flat receiver with  $\varepsilon_p = 0.10$ . Under the conditions of its use, it is expected that  $F' = 0.87$ . The inlet fluid temperature is  $130^\circ\text{C}$  and the ambient temperature is  $28^\circ\text{C}$ . The collector array of  $10\text{ m}^2$  total aperture area has 10 concentrators each with an aperture width of  $0.30\text{ m}$ , with flow in parallel through the 10 receivers. The total flow rate is  $0.135\text{ kg/s}$  and the fluid heat capacity is  $3560\text{ J/kg }^\circ\text{C}$ . Estimate the useful gain from the collector when the absorbed radiation  $S = 590\text{ W/m}^2$ . Base  $U_L$  on Rabl's estimates as indicated in Figure 7.8.1.

### Solution

Assume the absorber temperature  $T_p = 140^\circ\text{C}$ . From Figure 7.8.1 the overall loss coefficient  $U_L$  is approximately  $6.1\text{ W/m}^2\text{ }^\circ\text{C}$  for this CPC with a concentration ratio of 4.5. The flow rate per unit area of aperture is  $\dot{m}/A_a = 0.135/10 = 0.0135\text{ kg/m}^2\text{ s}$ . With these,  $F_R$  can be calculated from Equation 7.3.13:

$$F_R = \frac{0.0135 \times 3560}{6.1} \left[ 1 - \exp \left( - \frac{6.1 \times 0.87}{0.0135 \times 3560} \right) \right] = 0.82$$

The total useful gain can be estimated from Equation 7.3.12:

$$Q_u = 10 \times 0.82 \left[ 590 - \frac{6.1 (130 - 28)}{4.5} \right] = 3.7\text{ kW}$$

The temperature rise through the collector is

$$\Delta T = \frac{3700}{0.135 \times 3560} = 7.7^\circ\text{C}$$

Equation 6.8.4 could be used to estimate the mean receiver temperature of  $134^\circ\text{C}$  and a new  $U_L$  estimated based on the revised mean absorber temperature  $T_p$ . It will be close to the  $140^\circ\text{C}$  assumed, and it is not possible to improve significantly on the estimate already made. ■

Rabl et al. (1980) have measured the performance of several experimental CPC collectors. A collector with a cylindrical absorber, a concentration ratio of 5.2, an acceptance half-angle of  $6.5^\circ$ , and a flat cover over the array had  $F_{av}(\tau\alpha)_n = 0.68$  and



$F_{\text{av}}U_L = 0.185 \text{ W/m}^2 \text{ } ^\circ\text{C}$ . Operating data from some CPC arrays with evacuated tubular receivers have been reported to be similar to that shown in Figure 6.18.5, which indicates a more complex dependence of efficiency on incident radiation and operating temperature than is indicated by the two-parameter model.

## 7.9 LINEAR IMAGING CONCENTRATORS: GEOMETRY


Linear concentrators with parabolic cross section have been studied extensively both analytically and experimentally and have been proposed and used for applications requiring intermediate concentration ratios and temperatures in the range of 100 to 500°C. Figure 7.9.1 shows a collector of this type which is part of a power generation system in California. The receiver used with this concentrator is cylindrical and is enclosed in an evacuated tubular cover; flat receivers have also been used with reflectors of this type.

To understand how these collectors operate, it is necessary to describe the optical properties of the concentrators and the images (the distribution of solar radiation flux across the focus) they produce. This section treats the geometry of reflectors and the width of the images they produce. The next section is concerned with the distribution of flux in images from perfect reflectors. Section 7.11 then treats images produced by imperfect reflectors. The final section in this series is on energy balances on these collectors.


For collectors of this type, the absorbed radiation per unit area of unshaded aperture is given by Equation 7.4.1. In order to evaluate  $S$ , it is necessary to know the characteristics of the images produced by reflectors. Theoretical images, that is, those produced by perfect concentrators that are perfectly aligned, depend on concentrator geometry. Cross sections of a linear parabolic concentrator are shown in Figures 7.9.2 and 7.9.3. The equation of the parabola, in terms of the coordinate system shown, is

$$y^2 = 4fx \quad (7.9.1)$$


The aperture is  $a$  and the focal length (the distance from the focal point to the vertex) is  $f$ .



**Figure 7.9.1** Collector with linear parabolic concentrator used in a power generation installation. Photo courtesy of Luz Corporation.



**Figure 7.9.2** Section of a linear parabolic concentrator showing major dimensions and the  $x, y, z$  coordinates.



**Figure 7.9.3** Image dimensions for a linear concentrator.


The radiation beam shown in Figure 7.9.3 is incident on the reflector at point  $B$  at the rim where the **mirror radius** is a maximum at  $r_r$ . The angle  $\phi_r$  is the rim angle, described by  $AFB$ , and is given by

$$\varphi_r = \tan^{-1} \left[ \frac{8(f/a)}{16(f/a)^2 - 1} \right] = \sin^{-1} \left( \frac{a}{2r_r} \right) \quad (7.9.2)$$

For convenience,  $\phi_r$  is plotted as a function of  $f/a$  in Figure 7.9.4.

For any point of the parabolic reflector the **local mirror radius** is

$$r = \frac{2f}{1 + \cos \phi} \quad (7.9.3)$$




**Figure 7.9.4** Rim angle  $\phi_r$  as a function of focal length–aperture ratio.

An incident beam of solar radiation is a cone with an angular width of  $0.53^\circ$  (i.e., a half-angle  $\theta_s$  of  $0.267^\circ$  or  $16'$ ). For present purposes, assume that the concentrator is symmetrical and that the beam radiation is normal to the aperture. Thus the beam radiation is incident on the concentrator in a direction parallel to the central plane of the parabola (the  $x$ - $z$  plane described by the axis and focus of the parabola). (The effects of alignment errors will be noted in Section 7.11.)

Figure 7.9.5 shows schematically how the reflected radiation from the rim of the parabola determines the width of the focal zone. The width of the solar image in the focal plane increases with increasing rim angle. The minimum sizes of flat, circular, and semicircular receivers centered at the focal point to intercept all of the reflected radiation are shown. It is clear from this diagram that the angle of incidence of radiation on the surface of any of these receiver shapes is variable.

For specular parabolic reflectors of perfect shape and alignment, the size of the receiver to intercept all of the solar image can be calculated. The diameter  $D$  of a cylindrical receiver is given as

$$D = 2r_r \sin 0.267 = \frac{a \sin 0.267}{\sin \phi_r} \quad (7.9.4)$$



**Figure 7.9.5** Schematic of reflected radiation from center and rim of a (half) parabolic reflector, with minimum plane, circular, and semicircular receivers to intercept all reflected radiation from a full parabola.

For a flat receiver in the focal plane of the parabola (the  $y$ - $z$  plane through  $F$ , as shown in Figure 7.9.3) the width  $W$  is given as

$$W = \frac{2r_r \sin 0.267}{\cos(\phi_r + 0.267)} = \frac{a \sin 0.267}{\sin \phi_r \cos(\phi_r + 0.267)} \quad (7.9.5)$$

Note that  $W$  is also the diameter of a semicircular receiver.

For a flat receiver, as  $\phi$  varies from zero to  $\phi_r$ ,  $r$  increases from  $f$  to  $r_r$  and the theoretical image size in the focal plane increases from  $D$  (evaluated with  $r_r$  equal to  $f$ ) to  $W$ . The focal length is a determining factor in image size, and the aperture is the determining factor in total energy; thus the image brightness or energy flux concentration at the receiver of a focusing system will be a function of the ratio  $a/f$ .

## 7.10 IMAGES FORMED BY PERFECT LINEAR CONCENTRATORS

We turn now to a more detailed consideration of the theoretical images produced by perfectly oriented cylindrical parabolic reflectors.<sup>11</sup> Only images formed on planes perpendicular to the axis of the parabola will be considered; these examples provide the basis for an appreciation of the important factors in the operation of concentrators.


The radiation incident on a differential element of area of a reflector can be thought of as a cone having an apex angle of  $32'$ , or a half-angle of  $16'$ . The reflected radiation from the element will be a similar cone and will have the same apex angle if the reflector is perfect. The intersection of this cone with the receiver surface determines the image size and shape for that element, and the total image is the sum of the images for all of the elements of the reflector.

Consider a flat receiver perpendicular to the axis of a perfect parabola at its focal point, with beam radiation normal to the aperture. The intersection of the focal plane and a cone of reflected radiation from an element is an ellipse, with minor axis of  $2r \sin 16'$  and major axis of  $y_1 - y_2$ , where  $y_1 = r \sin 16' / \cos(\phi - 16')$  and  $y_2 = r \sin 16' / \cos(\phi + 16')$ . The total image is the sum of the ellipses for all of the elements of the reflector.


Evans (1977) has determined the distribution of energy flux in the integrated images on the focal plane for three models of the sun, including a nonuniform solar disk with an intensity distribution suggested by Lose (1957) based on data of Abetti (1938). The nonuniform disk model takes into account the fact that the sun radiates more from its central portion than it does from the limb, or edge. Figures 7.10.1(a), 7.10.2, and 7.10.3 show the distribution of energy across images for several perfect concentrators for the nonuniform solar disk.

The local concentration ratio  $C_l = I(y)/I_{b,ap}$  is the ratio of intensity at any position  $y$  in the image to the intensity on the aperture of the concentrator. Local concentration ratios are shown in Figure 7.10.1(a). The abscissa is the distance from the image center,


<sup>11</sup>This and the following sections are based on numerical integrations of images formed by parabolic cylinder reflectors on focal planes and draws on the work of Evans (1977). An alternative approach extensively developed by Rabl (1985) is based on the concept that images can be described as Gaussian in character. Many concentrators use cylindrical receivers, which require modifications of the analyses. Ray-trace methods are often used in the analysis and design of these collectors.



**Figure 7.10.1** (a) Image distributions for perfect concentrators for the nonuniform solar disk. From Evans (1977). (b) Intercept factors for images from perfect concentrators obtained by integrating areas under curves of (a).



**Figure 7.10.2** Image distributions for the nonuniform solar disk for several pointing errors in the  $x$ - $y$  plane. From Evans (1977).



**Figure 7.10.3** Image distributions for 30° rim angle reflectors for several displacements of the plane of the image from the focal plane. The dashed curve shows the effect of shading of the reflector by the absorber. From Evans (1977).

expressed in dimensionless form as  $y/f$ . A reflectance of 1 was assumed in these calculations. Distributions are shown for five rim angles of the reflector. As rim angle increases, the local concentration ratio increases, as does the size of the image. (If a uniform solar disk is assumed, the distributions show lower concentration ratios in the center of the image and higher ratios in the outer portions of the images than for the nonuniform model.)

The distributions of Figure 7.10.1(a) can be integrated from zero to  $y/f$  to show the intercept factor  $\gamma$ , the fraction of the total image that is intercepted by the flat receiver in the focal plane. Intercept factors are shown in Figure 7.10.1(b).

### Example 7.10.1

A perfect cylindrical parabolic reflector has an aperture of 7.00 m and a focal length of 6.53 m. It is long in the  $z$  direction so that end effects are negligible. The incident beam radiation normal to the aperture is 805 W/m<sup>2</sup>. The specular reflectance of the concentrator is 0.85.

What is the image width? What is the radiation intensity at the center of the image for the nonuniform solar disk? What is the intensity of the image at a point in the focal plane 26 mm from the axis, and how much of the total solar energy is incident on a symmetrical receiver 52 mm wide?

### Solution

The  $f/a$  ratio of this concentrator is  $6.53/7.00 = 0.933$ . From Equation 7.9.2 the rim angle for a concentrator of these dimensions is

$$\phi_r = \tan^{-1} \left( \frac{8 \times 0.933}{16 \times 0.933^2 - 1} \right) = 30^\circ$$

From Equation 7.9.5 the image width is

$$W = \frac{7.00 \sin 0.267}{\sin 30 \cos(30 + 0.267)} = 0.076 \text{ m}$$

From Figure 7.10.1(a), for the nonuniform solar disk, the local concentration ratio  $C_l$  at the axis is 149. Thus the flux in the image at the axis is

$$I(y = 0) = I_{b,ap} \rho C_l = 805 \times 0.85 \times 149 = 102 \text{ kW/m}^2$$

At a distance 0.026 m from the axis,  $(y/f)10^3 = 0.026 \times 10^3/6.53 = 4.0$ . Again from Figure 7.10.1(a), at  $\phi_r = 30^\circ$ ,  $C_l = 69$  and

$$I(y = 0.026) = 805 \times 0.85 \times 69 = 47 \text{ kW/m}^2$$

From Figure 7.10.1(b), at  $(y/f)10^3 = 4.0$ , the intercept factor is 0.92, so the energy per unit length on a receiver of width of 52 mm, neglecting shading by the receiver, is

$$7.00 \times 805 \times 0.85 \times 0.92 = 4.41 \text{ kW/m}$$

■

To this point, orientation of the collector has been considered to be perfect, that is, with the beam radiation normal to the aperture. Two kinds of variation from this situation arise. The first is pointing errors in the  $x$ - $y$  plane. The second is variation of the angle of incidence in the  $x$ - $z$  plane that results from the mode of tracking.

Calculations similar to those resulting in Figure 7.10.1(a) have been done by Evans (1977) for perfect reflectors with alignment errors in the  $x$ - $y$  plane. The results are shown in Figure 7.10.2 for two rim angles and three alignment errors. Figure 7.10.3 shows the effects of displacement  $L$  of the image plane from the focal plane for a perfect reflector with a rim angle of  $30^\circ$  with the radiation normal to the aperture. The dashed lines show the effect of shading of the reflector by the receiver for receiver widths of  $0.05f$ ,  $0.1f$ ,  $0.2f$ , and  $0.3f$ . It is clear that significant displacements of a receiver from the focal plane (or gross reflector distortions that lead to variation in focal length) lead to major changes in the nature of the image. The effect increases as rim angle increases.

Linear parabolic concentrators may be oriented in several ways to track the beam radiation. In general, the beam radiation will be in the principal plane (the  $x$ - $z$  plane) of the collector as described by the focus and vertex of the parabola but will not be normal to the aperture. Rabl (1985) shows that under these circumstances a parabolic trough collector can be analyzed by projections in the  $x$ - $y$  plane. Common modes of orientation are adjustment about horizontal axes, aligned either east-west or north-south; rotation about a polar axis is occasionally used. In these situations the angle of incidence  $\theta$  of beam radiation on the aperture of the collector, if it is parallel to the central plane of the reflector, is described by Equation 1.7.2a, 1.7.3a, or 1.7.5a.

As the angle of incidence in the  $x$ - $z$  plane increases, the apparent half-angle subtended by the sun (the projection on the  $x$ - $y$  plane of the  $0.267^\circ$  half-angle) increases as  $1/\cos \theta$ . The effect on image width  $W$  is obtained from Equation 7.9.5 by substituting  $0.267/\cos \theta$  for 0.267:

$$W = \frac{2r_r \sin(0.267/\cos \theta)}{\cos(\phi_r + 0.267/\cos \theta)} \quad (7.10.1)$$

The effect of  $\theta$  on image width is best illustrated by  $W/W_0$ , the ratio of image width at incidence angle  $\theta$  to the width at  $\theta = 0$ :

$$\frac{W}{W_0} = \frac{\sin(0.267/\cos \theta)}{\sin 0.267} \frac{\cos(\phi_r + 0.267)}{\cos(\phi_r + 0.267/\cos \theta)} \approx \frac{1}{\cos \theta} \quad (7.10.2)$$

This ratio does not change significantly with  $\theta$  until the rim angle exceeds about  $80^\circ$ . Until  $\theta$  becomes large, the second fraction varies little with  $\theta$  and the dominant effect is that of the first fraction. Also, the sine of a small angle is nearly equal to the angle, so  $W/W_0$  is very nearly equal to  $1/\cos \theta$ .

The result of this image widening is that a linear parabolic concentrator oriented on a horizontal east-west axis would have an image on the receiver very much enlarged in the early and late hours of a day and of minimum size at noon. A collector oriented on a north-south horizontal axis would have an image size that would be less variable through the day. The effects of  $\theta$  on image size are in addition to the effect of reduction of energy in the image (for a given  $I_{bn}$ ) by the factor  $\cos \theta$ .

### Example 7.10.2

The concentrator of Example 7.10.1 is oriented with its  $z$  axis horizontal in the east-west direction, and it is rotated continuously to minimize the angle of incidence of the beam radiation. Assume that there is no pointing error in the  $x$ - $y$  plane. At 3 PM on June 11, what is the image width? What is the image intensity in the focal plane at the axis? What will the image intensity be at a point 0.026 m from the axis? What is the fraction of the specularly reflected radiation that is intercepted by a symmetrical receiver in the focal plane that is 0.052 m wide?

#### Solution

On June 11 at 3 PM,  $\delta = 23.1^\circ$  and  $\omega = 45^\circ$ . From Equation 1.7.2a

$$\cos \theta = (1 - \cos^2 23.1^\circ \times \sin^2 45^\circ)^{1/2} = 0.760$$

$$\theta = 40.6^\circ$$

From Example 7.10.1  $\phi_r = 30^\circ$  and  $f = 6.53$  m, so from Equation 7.9.3

$$r_r = \frac{2 \times 6.53}{1 + \cos 30} = 7.00 \text{ m}$$

The image width is found from Equation 7.10.1,

$$W = \frac{2 \times 7.00 \sin(0.267/0.760)}{\cos(30 + 0.267/0.760)} = 0.099 \text{ m}$$

(The same information can be obtained from Equation 7.10.2, where  $W_0$  is the width calculated in Example 7.10.1. The width  $W = 0.076/\cos 40.6 = 0.099$  m.)

The intensity at the center will be reduced by two effects, the reduced radiation incident on the aperture resulting from off-normal solar radiation and the image spread due to the apparent increase in the sun's half-angle  $\theta_s$ . From Example 7.10.1 the intensity at the center is  $102 \text{ kW/m}^2$ . For the off-normal condition of this example,

$$I(y = 0, \theta = 40.6) = I(y = 0, \theta = 0)(\cos 40.6) \frac{W_0}{W}$$

$$= 102 \times 0.759 \times \frac{0.076}{0.099} = 59 \text{ kW/m}^2$$



The area under a  $C_l$ -versus- $y/f$  curve is fixed, so at a given  $y/f$ , as the image widens, the local intensity diminishes. In Figure 7.10.1(a) the ordinate becomes  $C_l / \cos \theta$  and the abscissa becomes  $(y/f) \times 10^3 \times \cos \theta$ . The value of  $(y/f) \times 10^3$  of 4.0 of Example 7.10.1 is equivalent to a value of  $4.0 \cos 40.6 = 3.0$  for this example. From Figure 7.10.1(a), at an abscissa of 3.0, the ordinate  $C_l / \cos \theta = 105$ , so the local concentration ratio  $C_l = 80$ . The intensity is

$$I(y) = 0.026, \theta = 40.6) = 805(\cos 40.5)0.85 \times 80 = 42 \text{ kW/m}^2$$

From Figure 7.10.1(b) at an abscissa of 3.0, the intercept factor is 0.78 and the energy per unit length on a receiving surface of width 0.052 m, neglecting receiver shading, is

$$7.00 \times 805(\cos 40.6) 0.85 \times 0.78 = 2.8 \text{ kW/m} \quad \blacksquare$$

Comparing the results of the two examples (at the same  $I_{bn}$ ), when the angle of incidence in the  $x$ - $z$  plane went from  $0^\circ$  to  $40.6^\circ$ , the image width increased from 76 to 99 mm, the intensity at the center of the image dropped from 102 to  $59 \text{ kW/m}^2$ , the intensity at  $y = 26 \text{ mm}$  decreased from 47 to  $42 \text{ kW/m}^2$ , and the energy per unit length incident on the receiving surface 52 mm wide dropped from 4.4 to 2.8 kW/m.

## 7.11 IMAGES FROM IMPERFECT LINEAR CONCENTRATORS

The distributions shown in Figures 7.10.1 to 7.10.3 are for perfect parabolic cylinders. If a reflector has small, two-dimensional surface slope errors that are normally distributed, the images in the focal plane created by these reflectors for perfect alignment will be as shown in Figure 7.11.1. Distributions for reflectors with rim angles of  $30^\circ$  and  $75^\circ$  are shown for various values of the standard deviation of the normally distributed slope errors. Imperfect reflectors will, as is intuitively obvious, produce larger images than the theoretical.


A second method of accounting for imperfections in the shape of a parabola is to consider the reflected beam as having an angular width of  $(0.53 + \delta)$  degrees, where  $\delta$  is a **dispersion angle**, as shown in Figure 7.11.2. Here  $\delta$  is a measure of the limits of angular errors of the reflector surface. With  $\delta$ , equations can be written for the size of images produced on cylinders or planes at the focus. The diameter of a cylindrical receiver that would intercept all of the image would be

$$D = 2r_r \sin(0.267 + \delta/2) = \frac{a \sin(0.267 + \delta/2)}{\sin \phi_r} \quad (7.11.1)$$


The image width on the focal plane, if the incident radiation were normal to the aperture, would be

$$W = \frac{2r_r \sin(0.267 + \delta/2)}{\cos(\phi_r + 0.267 + \delta/2)} = \frac{a \sin(0.267 + \delta/2)}{\sin \phi_r \cos(\phi_r + 0.267 + \delta/2)} \quad (7.11.2)$$

It may be possible to estimate  $\delta$  from flux distribution measurements, by ray-trace methods if the distribution of angular errors is known, or by knowledge of the distribution of angular errors to be expected from the process used in manufacturing a reflector. An assumption of normally distributed angular errors may be closer to reality.



**Figure 7.11.1** (a) Image distributions for imperfect reflectors for  $30^\circ$  rim angle for various standard deviations of normally distributed reflector slope errors, (b) Image distributions for imperfect reflectors for  $75^\circ$  rim angle for various standard deviations of normally distributed reflector slope errors. From Evans (1977).



**Figure 7.11.2** Schematic of a portion of a concentrator with a dispersion angle  $\delta$  added to the  $0.53^\circ$  solar intercept angle.

Equations 7.11.1 and 7.11.2 give the diameter and width of images of imperfect parabolic troughs that can be described by the dispersion angle  $\delta$ . (Equations 7.9.4 and 7.9.5 give the same information for perfect reflectors.) The ratio  $(a/W)_{\gamma=1}$  is defined as the ratio of the area of the aperture to the total area of the receiver when the receiver is just large enough to intercept all of the specularly reflected radiation (i.e., when  $\gamma = 1$ ). From  $(a/W)_{\gamma=1}$  we can get  $C_{\max}$ , the maximum area concentration ratio that leads to interception

of the total image. For a concentrator producing an image with well-defined boundaries and without pointing errors or mispositioning of the receiver, for a flat receiver of width  $W$  with a shadow  $W$  wide, the maximum area concentration ratio for  $\gamma = 1$  is  $(a/W)_{\gamma=1} - 1$ . Then

$$C_{\max} = \frac{\sin \phi_r \cos(\phi_r + 0.267 + \delta/2)}{\sin(0.267 + \delta/2)} - 1 \quad (7.11.3)$$


## 7.12 RAY-TRACE METHODS FOR EVALUATING CONCENTRATORS

Analysis of concentrating collectors (and other optical systems) is commonly done by ray-trace methods. This is the process of following the paths of a large number of rays of incident radiation through the optical system (the set of refracting and reflecting surfaces) to determine the distribution of the processed rays on the surface of interest. Thus for a concentrating collector, the ray trace starts with the assembly of rays of incident radiation on the aperture and determines the distribution and intensity of those rays on the receiver. This subject is treated in detail in many books on optics; a useful summary in the solar energy context is provided by Welford and Winston (1981). Spencer and Murty (1962) present a useful general treatment of the method, and Bendt et al. (1979) show application of ray tracing to linear parabolic concentrators.

Ray tracing in solar collector systems is done with vectors. For a reflecting surface, the direction and point of intersection of an incident ray with the reflecting surface are determined. The normal to the surface is also determined from its shape, and the direction of the reflected ray then follows from the principle that the angle of reflection equals the angle of incidence. This is done in an appropriate set of coordinates. Refracting surfaces are similarly treated using Snell's law. Figure 7.12.1 shows an example of a ray-trace analysis of a CPC; the sizes and shapes of receivers can be shown on the diagram to determine the distribution and angles of incidence of radiation on those receivers.

## 7.13 INCIDENCE ANGLE MODIFIERS AND ENERGY BALANCES

In practice, images often do not have well-defined boundaries, and it usually is best to use a receiver that will intercept less than all of the specularly reflected radiation. A trade-off between increasing thermal losses with increasing area and increasing optical losses with decreasing area is necessary to optimize long-term collector performance. This optimization problem has been studied by Löf et al. (1962) and Löf and Duffie (1963), with a result that for a wide range of conditions the optimum-size receiver will intercept 90 to 95% of the possible radiation. Thus an optical loss, often in a range of 5 to 10%, will be



**Figure 7.12.1** A ray-trace diagram for a CPC reflector.

incurred in this type of collector. This has been expressed in terms of the intercept factor  $\gamma$ , the fraction of the specularly reflected radiation which is intercepted by the receiver. Figure 7.10.1(b) shows intercept factors as a function of receiver width in the focal plane for symmetrical collectors with perfect concentrators.

Errors in concentrator contours, tracking (pointing) errors, and errors in displacement of receivers from the focus all lead to enlarged or shifted images and consequently affect  $\gamma$ . These errors can also affect the transmittance of a cover system and the absorptance of a receiver. In addition, a spread of the image at the receiver of a linear concentrator depends on the angle of incidence of beam radiation  $\theta$  as indicated in Section 7.10. These effects can be represented by biaxial incidence angle modifiers, in the transverse ( $x$ - $y$ ) and longitudinal ( $x$ - $z$ ) planes.


In the transverse plane,  $\gamma$  will drop off sharply as the transverse component of the angle of incidence increases. This effect can be determined from information in curves like those of Figure 7.10.2.

In the longitudinal plane, the two major effects will be that of image spread as a function of  $\theta$  (as noted in Section 7.10) and variation with  $\theta$  of the reflectance, transmittance, and absorptance. It is not practical to generalize these effects, and experimental data are most useful to determine their magnitude. Figure 7.13.1 shows an example of measured incidence angle modifiers as a function of  $\theta$ . In addition, if the trough is not long in extent, there will be end effects as the image from the end of the trough is formed beyond the end of the receiver. Rabl (1985) gives an example of an end-effect correction for receivers that are the same length  $l$  as the reflector and placed symmetrically over it:

$$\kappa(\theta) = 1 - \frac{f}{l} \left( 1 + \frac{a^2}{48f^2} \right) \tan \theta \quad (7.13.1)$$

As a first approximation the overall incidence angle modifier can be taken as the product of the transverse and longitudinal components. These factors are in general not simply expressed as analytic functions, and it is not now possible to write general equations for overall effects of the angles of incidence in the longitudinal and transverse planes.

In order to estimate the useful output of the collector, it is necessary to estimate  $F_R$  and  $U_L$ . Methods for calculating  $F_R$  are basically the same as for flat-plate collectors, except



**Figure 7.13.1** Incidence angle modifier as a function of angle of incidence in the  $x$ - $z$  plane for a Hexcel linear parabolic collector. Adapted from Gaul and Rabl (1980).


that fin and bond conductance terms generally will not appear in  $F'$ ; these considerations are outlined in Section 7.3.

Values of  $U_L$  may be difficult to determine. [For examples of calculation methods for uncovered cylinders and cylinders with cylindrical covers, see Section 7.3, Tabor (1955, 1958) and Forristall (2003).] An additional complication arises in that conduction losses through supporting structures are highly variable with design and are dependent on temperature. Some experimental data are available on loss coefficients for several receiver designs. Table 7.13.1 provides a brief description of three receivers, and Figure 7.13.2 shows measured loss coefficients as a function of the difference between receiver temperature and ambient temperature. These loss coefficients are based on receiver area.

**Table 7.13.1** Receiver Design and Collector Characteristics<sup>a</sup>

Type	Description	$C$	$a$ , m	$f$ , m
A. Hexcel	Steel pipe, black chrome coated. Back side insulated. On absorbing side, cover is glass semicylinder. Space not evacuated.	67	2.6	0.914
B. Solar Kinetics	Steel tube, black chrome plated, inside a borosilicate glass tube, not evacuated.	41	1.3	0.267
C. Suntec Systems	Two parallel steel pipes, black chrome plated, with down- and back-flow path. Back insulated, front covered with flat glass.	35	3.5	3.05


<sup>a</sup>From Leonard (1978).



**Figure 7.13.2** Loss coefficients per unit of area of receiver as a function of the difference between average receiver temperature and ambient temperature for three receivers described in Table 7.13.1. Data from Leonard (1978).

**Example 7.13.1**

A linear parabolic concentrator with  $a = 2.50$  m and  $f = 1.00$  m is continuously adjusted about a horizontal east-west axis. It is to be fitted with a liquid heating receiver very similar to type C in Table 7.13.1. The unit is 10.5 m long. A strip of the reflector 0.21 m wide is shaded by the receiver. The receiver is designed to be just large enough to intercept all of the specularly reflected beam radiation when the incident beam radiation is normal to the aperture, and under those conditions the distribution of radiation in the focal plane can be approximated as shown by the solid line on the figure below. The loss coefficient per unit area of receiver is found from curve C in Figure 7.13.2.



The normal beam radiation  $G_{bn}$  at noon on April 20 is  $975 \text{ W/m}^2$ , and at 3 PM it is  $810 \text{ W/m}^2$ . Here  $(\tau\alpha)$  for the receiver is estimated at 0.78 with radiation normal to the aperture and  $\rho = 0.86$ . The inlet fluid temperature is  $170^\circ\text{C}$ , the ambient temperature is  $25^\circ\text{C}$ , and  $F_R$  is estimated to be 0.85.

What will be the output of the collector at noon and at 3 PM?

**Solution**

The basic equation to be used for the estimation of useful gain is Equation 7.3.9. The first step is to estimate an optical efficiency, then  $S$ , and then  $Q_u$ . At noon, the radiation will be normal to the aperture, and according to design specifications  $\gamma = 1$ . A fraction of the reflector of  $0.21/2.50$ , or 0.084, is shaded by the receiver, so  $1 - 0.084$ , or 0.916, of the reflector is effective. The product  $\rho\gamma\tau\alpha$  is calculated by

$$\rho\gamma\tau\alpha = 0.86 \times 1.00 \times 0.78 \times 0.916 = 0.61$$

Based on the area of the unshaded aperture,

$$S = 975 \times 0.61 = 600 \text{ W/m}^2$$

At an estimated mean receiver surface temperature of  $200^\circ\text{C}$ ,  $U_L$  from Figure 7.13.2 is  $13.7 \text{ W/m}^2 \cdot ^\circ\text{C}$ . Then from Equation 7.3.9, at a concentration ratio  $A_a/A_r$  of  $(2.5 - 0.21)/0.21 = 10.9$ ,

$$Q_u = 0.85 \times 10.5 \times 2.5 \left[ 600 - \frac{13.7}{10.9} (170 - 25) \right] = 9.3 \text{ kW}$$

At 3 PM the angle of incidence of beam radiation on the aperture is  $43.9^\circ$  (from Equation 1.7.2a). This leads to significant image spread and changes in  $\gamma$ ,  $\tau$ , and  $\alpha$ . The dashed line in the figure shows how the image will spread, with its width  $(1/\cos 43.9)$  greater than at

noon. An approximate integration between the limits of the receiver dimensions indicates  $\gamma = 0.80$ . From Figures 4.11.1 and 5.3.1,  $\alpha$  and  $\tau$  will be reduced by approximately 3% each, so an approximation to  $(\tau\alpha)$  is  $0.78(0.97)^2 = 0.73$ . Then  $\rho\gamma\tau\alpha = 0.86 \times 0.80 \times 0.73 \times 0.916 = 0.46$ .

At 3 PM, based on the unshaded aperture,

$$S = 810 \times 0.46 \cos 43.9 = 268 \text{ W/m}^2$$


The useful gain is

$$Q_u = 0.85 \times 10.5 \times 2.5 \left[ 268 - \frac{13.7}{10.9} (170 - 25) \right] = 1.91 \text{ kW}$$


In this example, some shortcuts have been taken. The mean angles of incidence of the radiation on the receiver are not known when  $\gamma$  is significantly less than unity, and only simple corrections accounting for incidence angles on the plane of the receiver have been made. The integration to find  $\gamma$  is approximate. More detailed knowledge of the optical characteristics of reflector orienting systems and receivers would have to be combined with ray-trace techniques to improve on these calculations.

An experimental study of energy balances on a linear parabolic collector was reported by Löf et al. (1962). While it is a special case, and while the concentrator  $f/a$  was smaller than optimum, it provides an illustration of the importance of several factors affecting performance of collectors of this type. The collector consisted of a parabolic cylinder reflector of aperture 1.89 m, length 3.66 m, and focal length 0.305 m, with bare tubular receivers of three sizes coated with nonselective black paint having an absorptance of 0.95. The collector was mounted so as to rotate on a polar axis at  $15^\circ/\text{h}$ . It was operated over a range of temperatures from near ambient to approximately  $180^\circ\text{C}$  with each of the three receivers.

The intercept factors for various receiver sizes were determined from measurements of the flux distribution at many locations on the focal tube. These distributions were averaged, and the resulting mean distribution is shown in Figure 7.13.3. This distribution is similar



**Figure 7.13.3** Experimental mean flux distribution for a parabolic cylinder reflector. From Löf et al. (1962).




**Figure 7.13.4** Intercept factors for tubes centered at position zero of the reflector of Figure 7.13.3. From Löff et al. (1962).

to a Gaussian distribution and is displaced from the position of the theoretical focus. The intercept factors that resulted from this distribution are shown in Figure 7.13.4.

The results of many energy balance measurements are summarized in Figure 7.13.5, which shows the distribution of incident beam solar energy (during operation at steady state in clear weather) into useful gain and various losses for a tube diameter of 60 mm. The relative magnitudes of the losses are evident.

From these figures it is possible to estimate the effects of design changes. For example, for this collector, the use of selective surface of emittance 0.2 would reduce the



**Figure 7.13.5** Distribution of incident energy for the 1.89-m reflector with 60-mm-diameter receiver as a function of receiver temperature. From Löff et al. (1962).



radiation loss by 79% of the values shown. However, radiation loss is not the dominant loss [a generalization made by Edwards and Nelson (1961)]. The most obvious initial improvements for this exchange would be in reduction of optical losses by using surfaces of high reflectance and by intercept factor improvements.

In this study, the reflector and receiver tubes were supported by plates at each end; these result in heat loss by conduction from the tubes. These losses were estimated from temperature measurements along the supporting plates. Although not shown in the figures, they were estimated at 3, 6, and 10% of the incident clear-sky radiation for receiver-surface temperatures of 100, 135, and 175°C, respectively, for the conditions of these experiments.

## 7.14 PARABOLOIDAL CONCENTRATORS

In the previous sections methods were outlined for calculation of absorbed radiation for collectors with linear parabolic concentrators. A similar analysis can be done for collectors with three-dimensional parabolic reflectors, that is, concentrators that are surfaces of revolution. Rabl (1976a, 1985) summarizes important optical aspects of these collectors. In a section through the axis of the paraboloid these collectors are represented by Figures 7.9.2 and 7.9.3, and the rim angle  $\phi_r$  and mirror radius  $r$  are analogous to those for the linear concentrator. Dispersion also occurs in paraboloidal concentrators, and equations analogous to Equation 7.11.2 can be written for collectors without tracking errors. For spherical receivers (allowing for minimum shading by the receiver)

$$C_{\max} = \frac{\sin^2 \phi_r}{4 \sin^2(0.267 + \delta/2)} - 1 \quad (7.14.1)$$

For flat receivers

$$C_{\max} = \frac{\sin^2 \phi_r \cos^2(\phi_r + 0.267 + \delta/2)}{4 \sin^2(0.267 + \delta/2)} - 1 \quad (7.14.2)$$

where  $C_{\max}$  is again defined as the maximum that can be obtained, based on interception of all of the specularly reflected radiation which is within the cone of angular width  $(0.534 + \delta)$ .

Cavity receivers may be used with paraboloidal concentrators to increase absorptance and to reduce convective losses from the absorbing surface. The equations for optical properties of systems with flat receivers will also apply to cavity receivers if appropriate absorptances of the cavities are used.

Absorbed energy for a paraboloidal collector depends on properties in the same way as linear parabolic collectors. However, at the higher concentration ratios achieved by these collectors, any absorption of solar radiation in the cover material would lead to heating of the cover, and as a result covers are usually not used. In the absence of a cover, the absorbed energy for the unshaded aperture area of the collector is then

$$S = I_{b,a} \rho(\gamma\alpha)_n K_{\gamma\alpha} \quad (7.14.3)$$

where the factors have the same meaning as in Equation 7.4.1. The incidence angle modifier may be circularly symmetrical; if the optical system is not symmetrical, biaxial or other

modifiers may have to be used. The modifier accounts for pointing errors in the alignment of the collector.

Calculation of thermal losses is very much a function of receiver geometry and may be complicated by the existence of temperature gradients on the surface of a receiver. For examples of these estimations, see reports of Boeing, Martin Marietta, and McDonnell-Douglas (1977) on the receiver subsystems of central-receiver solar thermal power systems.

## 7.15 CENTRAL-RECEIVER COLLECTORS

The central-receiver, or “power tower,” concept for generation of electrical energy from solar energy is based on the use of very large concentrating collectors. The optical system consists of a field of a large number of heliostats, each reflecting beam radiation onto a central receiver. The result is a Fresnel-type concentrator, a parabolic reflector broken up into small segments, as shown in Figure 7.1.1(f). Several additional optical phenomena must be taken into account. Shading and blocking can occur (shading of incident beam radiation from a heliostat by another heliostat and blocking of reflected radiation from a heliostat by another which prevents that radiation from reaching the receiver). As a result of these considerations, the heliostats are spaced apart, and only a fraction of the ground area  $\psi$  is covered by mirrors. A  $\psi$  of about 0.3 to 0.5 has been suggested as a practical value.

The maximum concentration ratio for a three-dimensional concentrator system with radiation incident at an angle  $\theta_i$  on the plane of the heliostat array ( $\theta_i = \theta_z$  for a horizontal array), a rim angle of  $\phi_r$ , and a dispersion angle of  $\delta$ , if all reflected beam radiation is to be intercepted by a spherical receiver, is

$$C_{\max} = \frac{\psi \sin^2 \phi_r}{4 \sin^2(0.267 + \delta/2)} - 1 \quad (7.15.1)$$

For a flat receiver, the concentration ratio is

$$C_{\max} = \psi \left[ \frac{\sin \phi_r \cos(\phi_r + 0.267 + \phi/2)}{\sin(0.267 + \delta/2)} \right]^2 - 1 \quad (7.15.2)$$

As with linear concentrators, the optimum performance may be obtained with intercept factors less than unity. The designer of these collectors has additional considerations to take into account. The heliostat field need not be symmetrical, the ground cover  $\psi$  does not have to be uniform, and the heliostat array is not necessarily all in one plane. These collectors operate with high concentration ratios and at relatively high receiver temperatures.

There has been considerable work done on the design and performance of collectors of this type in the 1970s, and a large body of literature is available. For example, see the University of Houston-Sandia *Proceedings of ERDA Workshops on Central Receiver Systems* (1977). Also, many papers have appeared in journals, and as a starting point the reader could go to Hildebrandt and Vant-Hull (1977) or Vant-Hull (1977). The *Proceedings of the IEA Workshop on Design and Performance of Large Solar Thermal*



**Figure 7.15.1** Solar One, a central receiver collector system. Photo courtesy of Sandia Laboratories.

*Collector Arrays* (IEA, 1984) includes performance reports on several central-receiver collectors and components thereof. The *ASME Transactions, Journal of Solar Energy Engineering*, volume 106, number 1 (1984), was devoted entirely to papers on central-receiver systems. Radosevich and Skinrood (1989) review experience with Solar One, a power-generating facility based on a central-receiver collector. A photograph of this facility is shown in Figure 7.15.1. Solar One ceased operation in 1988 and was rebuilt and restarted in 1996 as Solar Two (see Chapter 17).

## 7.16 PRACTICAL CONSIDERATIONS

Many of the practical considerations for flat-plate collectors also apply to concentrators; the necessity to move the collectors and the higher temperature ranges over which they operate impose additional requirements on focusing collectors. For more information on these topics,<sup>12</sup> see Radosevich and Skinrood (1989) for a report on Solar One and Harats and Kearney (1989) for a description of experience with the large-scale Luz linear concentrator systems used in power generation in California.

For acceptable performance, all of the terms in the optical efficiency  $\rho\gamma\tau\alpha$  must be maintained at acceptably high levels over the years of the system operating life. To maintain high specular reflectance, mechanized methods of cleaning reflectors have been developed for heliostats for central-receiver systems and for reflectors of linear concentrators, and plant layout has to be arranged to allow access to the reflectors by the cleaning machinery. Protection of the coatings on the back-silvered glass reflectors is necessary to reduce corrosion of the reflecting surfaces to very low values.

The intercept factor is a function of quality of construction and also of collector orientation. Control systems of precision appropriate to the quality of the optics of the collector are needed. Each of the individual heliostats is controlled in Solar One. The Luz systems have a controller and tracking drive for each solar collector assembly (235 m<sup>2</sup> area each for LS-2 and 545 m<sup>2</sup> area each for LS-3). There are obvious advantages to using fewer controllers and drives, each controlling larger areas, but stiffness of the structures becomes a limiting factor.

<sup>12</sup>See Chapter 17 for more information on these two systems.

Receivers of concentrators operate at elevated temperatures, and absorbing surfaces must be capable of prolonged exposure to the surrounding atmospheres at elevated temperature while maintaining acceptable absorptance and emittance.

Tracking collectors are by nature not rigidly mounted on buildings or other structures and are subject to wind loads that dictate structural requirements. Concentrators are typically designed to operate in winds up to 15 to 20 m/s; above that speed the reflectors are usually moved to a stowed position in which they are capable of withstanding the forces imposed by the maximum anticipated winds. Wind forces on outer collectors in very large arrays are higher than those in interior rows, and the structures and tracking drives must be designed to cope with these higher forces.

Concentrating collectors operate at temperatures that can range from 150 to 800°C and cycle on and off at least once each operating day. This means that receivers, fluid circulation pumps, flexible connections, piping runs, heat exchangers, and other equipment in the hot-fluid loops will cycle through substantial temperature excursions at least once a day.

Concentrating collectors must, as is obvious, be carefully designed and constructed if they are to provide reliable energy delivery over periods of many years.

## REFERENCES

- Abetti, G., *The Sun*, Van Nostrand, Princeton, NJ (1938).
- Baranov, V. K. and G. K. Melnikov, *Sov. J. Opt. Technol.* **33**, 408 (1966) "Study of the Illumination Characteristics of Hollow Focons."
- Bendt, P., A. Rabl, H. W. Gaul, and K. A. Reed, Report SERI/TR-34-092 of the Solar Energy Research Institute, Golden, CO (1979). "Optical Analysis and Optimization of Line Focus Solar Collectors."
- Boeing Engineering and Construction Co. (Contract No. EY-76-C-03-1111), Martin Marietta Corp. (Contract EY-77-C-03-1110), and McDonnell Douglas Astronautics Co. (Contract EY-76-C-03-1108) to the U.S. Department of Energy (1977) on "Central Receiver Solar Thermal Power System."
- Brandemuehl, M. J. and W. A. Beckman, *Solar Energy*, **24**, 511 (1980). "Transmission of Diffuse Radiation through CPC and Flat-Plate Collector Glazings."
- Chow, S. P., G. L. Harding, B. Window, and K. J. Cathro, *Solar Energy*, **32**, 251 (1984). "Effects of Collector Components on the Collection Efficiency of Tubular Evacuated Collectors with Diffuse Reflectors."
- Duffie, J. A. and G. O. G. Löf, Paper 207 III.7/5, presented at the World Power Conference, Melbourne (1962). "Focusing Solar Collectors for Power Generation."
- Edwards, D. E. and K. E. Nelson, Paper 61-WA-158, presented at the New York ASME Meeting (1961). "Radiation Characteristics in the Optimization of Solar-Heat Power Conversion Systems."
- Evans, D. L., *Solar Energy*, **19**, 379 (1977). "On the Performance of Cylindrical Parabolic Solar Concentrators with Flat Absorbers."
- Forristal, R., Report NREL/TP-550-34169, National Renewable Energy Laboratory, Golden, CO (2003). "Heat Transfer Analysis and Modeling of a Parabolic Trough Solar Receiver Implemented in Engineering Equation Solver."
- Gaul, H. and A. Rabl, *Trans. ASME J. Solar Energy Eng.*, **102**, 16 (1980). "Incidence-Angle Modifier and Average Optical Efficiency of Parabolic Trough Collectors."
- Harats, Y. and D. Kearney, paper presented at the ASME Meeting, San Diego, CA (1989). "Advances in Parabolic Trough Technology in the SEGS Plants."

- Hildebrandt, A. F. and L. L. Vant-Hull, *Science*, **198**, 1139 (1977). "Power with Heliostats."
- Hinterberger, H. and R. Winston, *Rev. Sci. Instrum.*, **37**, 1094 (1966).
- Hollands, K. G. T., *Solar Energy*, **13**, 149 (1971). "A Concentrator for Thin-Film Solar Cells."
- International Energy Agency (IEA), in *Proceedings of the IEA Workshop on Design and Performance of Large Solar Thermal Collector Arrays* (C. A. Bankston, ed.), San Diego, CA (1984). Available from National Technical Information Services, U.S. Department of Commerce.
- International Energy Agency (IEA), Report IEA-SHAC-TIV-4 (1986). "Results from Eleven Evacuated Collector Installations."
- Laszlo, T. S., *Image Furnace Techniques*, Interscience, New York (1965).
- Leonard, J. A., paper presented at the Solar Thermal Concentrating Collector Technology Symposium, Denver, June (1978). "Linear Concentrating Solar Collectors—Current Technology and Applications."
- Löf, G. O. G. and J. A. Duffie, *Trans ASME J. Eng. Power*, **85A**, 221 (1963). "Optimization of Focusing Solar-Collector Design."
- Löf, G. O. G., D. A. Fester, and J. A. Duffie, *Trans. ASME J. Eng. Power*, **84A**, 24 (1962). "Energy Balance on a Parabolic Cylinder Solar Reflector."
- Lose, P. D., *Solar Energy*, **1** (2, 3), 1 (1957). "The Flux Distribution through the Focal Spot of a Solar Furnace."
- Mather, G. R. Jr., *Trans. ASME J. Solar Energy Eng.* **102**, 294 (1980). "ASHRAE 93–77 Instantaneous and All-Day Tests of the Sunpak Evacuated Tube Collector."
- Mitchell, J. C. Personal communication (1979).
- O’Gallagher, J. J., A. Rabl, and R. Winston, *Solar Energy*, **24**, 323 (1980). "Absorption Enhancement in Solar Collectors by Multiple Reflections."
- Proceedings of the 1957 Solar Furnace Symposium*, *Solar Energy*, **1** (2, 3) (1957).
- Rabl, A., *Solar Energy*, **18**, 93 (1976a). "Comparison of Solar Concentrators."
- Rabl, A., *Solar Energy*, **18**, 497 (1976b). "Optical and Thermal Properties of Compound Parabolic Concentrators."
- Rabl, A., paper presented at the Solar Thermal Concentrating Collector Technology Symposium, Denver, June (1978). "Optical and Thermal Analysis of Concentrators."
- Rabl, A., *Active Solar Collectors and Their Applications*, Oxford University Press, New York and Oxford (1985).
- Rabl, A., J. J. O’Gallagher, and R. Winston, *Solar Energy*, **25** 335 (1980). "Design and Test of Non-Evacuated Solar Collectors with Compound Parabolic Concentrators."
- Radosevich, L. G. and A. C. Skinrood, *Trans ASME J. Solar Energy Eng.*, **111**, 144 (1989). "The Power Production Operation of Solar One, the IOMWe Solar Thermal Central Receiver Power Plant."
- Selcuk, M. K., *Solar Energy*, **22**, 413 (1979), "Analysis, Development and Testing of a Fixed Tilt Solar Collector Employing Reversible Vee-Trough Reflectors and Vacuum Tube Receivers."
- Spencer, G. H. and M. V. R. K. Murty, *J. Opt. Soc. Am.*, **52**, 672 (1962). "General Ray-Tracing Procedure."
- Stuetzle, T., N. J. Blair, J. W. Mitchell, and W. A. Beckman, *Solar Energy*, **76**, 187 (2004). "Automatic Control of a 30 MWe SEGS VI Parabolic Trough Plant."
- Tabor, H., *Bull. Res. Council Israel*, **5C**, 5 (1955). "Solar Energy Collector Design."
- Tabor, H., *Solar Energy*, **2** (1), 3 (1958). "Solar Energy Research: Program in the New Desert Research Institute in Beersheba."
- Theunissen, P-H. and W. A. Beckman, *Solar Energy*, **35**, 311 (1985). "Solar Transmittance Characteristics of Evacuated Tubular Collectors with Diffuse Back Reflectors."
- University of Houston-Sandia Laboratories, *Proceedings of the ERDA Solar Workshop on Methods for Optical Analysis of Central Receiver Systems* (1977). Available from National Technical Information Services, U.S. Department of Commerce.

- Vant-Hull, L. L., *Opt. Eng.*, **16**, 497 (1977). “An Educated Ray-Trace Approach to Solar Tower Optics.”
- Welford, W. T. and R. Winston, *The Optics of Nonimaging Concentrators*, Academic, New York (1978).
- Welford, W. T. and R. Winston, in *Solar Energy Handbook* (J. Kreider and R. Kreith, eds.), McGraw-Hill, New York (1981). “Principles of Optics Applied to Solar Energy Concentrators.”
- Winston, R., *Solar Energy*, **16**, 89 (1974). “Solar Concentrations of Novel Design.”
- Winston, R. and H. Hinterberger, *Solar Energy*, **17**, 255 (1975). “Principles of Cylindrical Concentrators for Solar Energy.”

# Energy Storage

Solar energy is a time-dependent energy resource. Energy needs for a very wide variety of applications are also time dependent but in a different fashion than the solar energy supply. Consequently, the storage of energy or other product of a solar process is necessary if solar energy is to meet substantial portions of these energy needs.

Energy (or product) storage must be considered in the light of a solar process system, the major components of which are the solar collector, storage units, conversion devices (such as air conditioners or engines), loads, auxiliary (supplemental) energy supplies, and control systems. The performance of each of these components is related to that of the others. The dependence of the collector performance on temperature makes the whole system performance sensitive to temperature. For example, in a solar-thermal power system, a thermal energy storage system which is characterized by high drop in temperature between input and output will lead to unnecessarily high collector temperature and/or low heat engine inlet temperature, both of which lead to poor system performance.


In passive solar heating, collector and storage components are integrated into the building structure. The performance of storage media in passive heating systems is interdependent with the absorption of energy, and we reserve discussion of part of this aspect of solar energy storage for Chapter 14.

The optimum capacity of an energy storage system depends on the expected time dependence of solar radiation availability, the nature of loads to be expected on the process, the degree of reliability needed for the process, the manner in which auxiliary energy is supplied, and an economic analysis that determines how much of the annual load should be carried by solar and how much by the auxiliary energy source.

In this chapter we set forth the principles of several energy storage methods and show how their capacities and rates of energy input and output can be calculated. In the example problems, as in the collector examples, we arbitrarily assume temperatures or energy quantities. In reality these must be found by simultaneous solutions of the equations representing all of the system components. These matters are taken up in Chapter 10; we will see there that the differential equations for storage are the key equations for most systems, with time the independent variable and storage (and other) temperatures the dependent variables.

## 8.1 PROCESS LOADS AND SOLAR COLLECTOR OUTPUTS

Consider an idealized solar process in which the time dependence of the load  $\dot{L}$  and gain from the collector  $Q_u$  are shown in Figure 8.1.1(a). During part of the time, available



**Figure 8.1.1** A solar energy process with storage. (a) Incident solar energy  $\dot{G}_T$ , collector useful gain  $\dot{Q}_u$ , and loads  $\dot{L}$  as functions of time for a three-day period. Vertical shaded areas show times of excess energy to be added to storage. Horizontal shaded areas show energy withdrawn from storage to meet loads. Dotted areas show energy supplied to load from collector during collector operation. (b) Energy added to or removed from storage, taking time  $t = 0$  as a base. (c) Integrated values of the useful gain from collector, the load, and the auxiliary energy for the same three-day period. In this example solar energy collected is slightly more than half the integrated load.

energy exceeds the load on the process, and at other times it is less. A storage subsystem can be added to store the excess collector output and return it when needed. Figure 8.1.1(b) shows the energy stored as a function of time. Energy storage is clearly important in determining system output. If there were no storage, the useful solar gain would be reduced on the first and third days by the amount of energy added to storage on those days. This would represent a major drop in solar contribution to meeting the load.

In most applications it is not practical to meet all of the loads  $\dot{L}$  on a process from solar energy over long periods of time, and an auxiliary energy source must be used. The total load  $\dot{L}$  is met by a combination of solar energy  $\dot{L}_S$  (which in practice will be somewhat less than  $\dot{Q}_u$  because of losses) and  $\dot{L}_A$  (the auxiliary energy supplied).

It is also useful to show the integrated values of the major parameters  $\dot{Q}_u$  (i.e., approximately  $\dot{L}_S$ ),  $\dot{L}$ , and  $\dot{L}_A$ . Examples of these are shown in Figure 8.1.1(c). A major objective of system performance analysis is a determination of long-term values of  $\dot{L}_A$ , the amount of energy that must be purchased; this is needed to assess the cost of delivering energy or product from the solar energy process and to estimate the fraction of total



energy or product needs met from solar and auxiliary energy sources. In practice, these integrations must be done over long periods (typically a year), and both collector area and storage capacity are variables to be considered.

## 8.2 ENERGY STORAGE IN SOLAR PROCESS SYSTEMS

Energy storage may be in the form of sensible heat of a liquid or solid medium, as heat of fusion in chemical systems, or as chemical energy of products in a reversible chemical reaction. Mechanical energy can be converted to potential energy and stored in elevated fluids. Products of solar processes other than energy may be stored; for example, distilled water from a solar still may be stored in tanks until needed, and electrical energy can be stored as chemical energy in batteries.


The choice of storage media depends on the nature of the process. For water heating, energy storage as sensible heat of stored water is logical. If air heating collectors are used, storage in sensible or latent heat effects in particulate storage units is indicated, such as sensible heat in a pebble bed heat exchanger. In passive heating, storage is provided as sensible heat in building elements. If photovoltaic or photochemical processes are used, storage is logically in the form of chemical energy.

The major characteristics of a thermal energy storage system are (a) its capacity per unit volume; (b) the temperature range over which it operates, that is, the temperature at which heat is added to and removed from the system; (c) the means of addition or removal of heat and the temperature differences associated therewith; (d) temperature stratification in the storage unit; (e) the power requirements for addition or removal of heat; (f) the containers, tanks, or other structural elements associated with the storage system; (g) the means of controlling thermal losses from the storage system; and (h) its cost.

Of particular significance in any storage system are those factors affecting the operation of the solar collector. The useful gain from a collector decreases as its average plate temperature increases. A relationship between the average collector temperature and the temperature at which heat is delivered to the load can be written as

$$\begin{aligned}
 T(\text{collector}) - T(\text{delivery}) = & \Delta T \text{ (transport from collector to storage)} \\
 & + \Delta T \text{ (into storage)} \\
 & + \Delta T \text{ (storage loss)} \\
 & + \Delta T \text{ (out of storage)} \\
 & + \Delta T \text{ (transport from storage to application)} \\
 & + \Delta T \text{ (into application)}
 \end{aligned}$$

Thus, the temperature of the collector, which determines the useful gain for the collector, is higher than the temperature at which the heat is finally used by the sum of a series of temperature difference driving forces. An objective of system design, and particularly of storage unit design, is to minimize or eliminate these temperature drops within economic constraints.




**Figure 8.2.1** Schematic of alternative storage location at *A* or *B*.

A solar process designer may have alternatives in locating the energy storage component. As an example, consider a process in which a heat engine converts solar energy into electrical energy. In such a system storage can be provided as thermal storage between the solar collector and the engine, as mechanical energy storage between the engine and generator, or as chemical storage in a battery between the generator and the end application. Solar cooling with an absorption air conditioner provides another example. Thermal energy from the collector can be stored to be used when needed by the air conditioner, or alternatively, the “cooling” produced by the air conditioner can be stored in a low-temperature (below-ambient) thermal storage unit. These are illustrated schematically in Figure 8.2.1.

These two alternatives are not equivalent in capacity, costs, or effects on overall system design and performance. The storage capacity required of a storage unit in position *B* is less than that required in position *A* by (approximately) the efficiency of the intervening converter. Thus if the conversion process is operating at 25% efficiency, the capacity of storage at *B* must be approximately 25% of the capacity of *A*. Thermal energy storage at *A* has the advantage that the converter can be designed to operate at a more nearly constant rate, leading to better conversion efficiency and higher use factor on the converter; it can lower converter capacity requirements by removing the need for operation at peak capacities corresponding to direct solar input. Storage at *B* may be energy of a different form than that at *A*. The choice between energy storage at *A* or at *B* may have very different effects on the operating temperature of the solar collector, collector size, and ultimately cost. These arguments may be substantially modified by requirements for use of auxiliary energy.

### 8.3 WATER STORAGE

For many solar systems water is the ideal material in which to store usable heat. Energy is added to and removed from this type of storage unit by transport of the storage medium itself, thus eliminating the temperature drop between transport fluid and storage medium. A typical system in which a water tank is used is shown in Figure 8.3.1. A forced-circulation



**Figure 8.3.1** A typical system using water tank storage, with water circulation through collector to add energy and through the load to remove energy.

(pumped) system is shown, but it could be natural circulation. Energy delivery to the load could be across a heat exchanger. Implicit in the following discussion is the idea that flow rates into and out of the tanks, to collector and load, can be determined.

The energy storage capacity of a water (or other liquid) storage unit at uniform temperature (i.e., fully mixed, or unstratified) operating over a finite temperature difference is given by

$$Q_s = (mC_p)_s \Delta T_s \quad (8.3.1)$$

where  $Q_s$  is the total heat capacity for a cycle operating through the temperature range  $\Delta T_s$  and  $m$  is the mass of water in the unit. The temperature range over which such a unit can operate is limited at the lower extreme for most applications by the requirements of the process. The upper limit may be determined by the process, the vapor pressure of the liquid, or the collector heat loss.

An energy balance on the unstratified tank shown in Figure 8.3.2 is


$$(mC_p)_s \frac{dT_s}{dt} = Q_u - \dot{L}_s - (UA)_s(T_s - T'_a) \quad (8.3.2)$$

where  $Q_u$  and  $\dot{L}_s$  are rates of addition or removal of energy from the collector and to the load and  $T'_a$  is the ambient temperature for the tank (which may not be the same as that for a collector supplying energy to the tank).

Equation 8.3.2 is to be integrated over time to determine the long-term performance of the storage unit and the solar process. Useful long-term analytical solutions are not possible due to the complex time dependence of some of the terms. There are many possible numerical integration methods. Using simple Euler integration is usually satisfactory [i.e., rewriting the temperature derivative as  $(T_s^+ - T_s)/\Delta t$  and solving for the tank temperature at the end of a time increment],

$$T_s^+ = T_s + \frac{\Delta t}{(mC_p)_s} [Q_u - L_s - (UA)_s(T_s - T'_a)] \quad (8.3.3)$$

Thus the temperature at the end of an hour is calculated from that at the beginning, assuming that  $Q_u$ ,  $L_s$ , and the tank losses do not change during the hour. The terms in



**Figure 8.3.2** Unstratified storage of mass  $m$  operating at time-dependent temperature  $T_s$  in ambient temperature  $T'_a$ .

Equation 8.3.2 are rates; in Equation 8.3.3 they are integrated quantities for the hour.<sup>1</sup> (By convention, the symbol  $Q_u$  is used for both the rate and the hourly integrated useful energy from the collector. Hourly radiation data are generally available, hence the use of a 1-h time base.)

Example 8.3.1 illustrates how the energy balance on a storage tank can be used to predict its temperature as a function of time. Once the tank temperature is known, other temperature-dependent quantities can be estimated. Solutions to the governing system equations when integrated over long periods (usually a year) provide information on how much solar energy is delivered to meet a load. As will be shown in Chapter 10, this is essential information in assessing the economic feasibility of a solar process.

### Example 8.3.1

A fully mixed water tank storage containing 1500 kg of water has a loss coefficient–area product of 11.1 W/°C and is located in a room at 20°C. At the beginning of a particular hour the tank temperature is 45.0°C. During the hour energy  $Q_u$  is added to the tank from a solar collector, and energy  $L_s$  is removed from the tank and delivered to a load as indicated in the table. A calculation of the solar gain  $Q_u$  using Equation 6.7.6 shows that no energy is delivered during the first hour. A calculation of the load energy  $L_s$  shows 12 MJ is extracted from the tank during the first hour. Using Euler integration, calculate the temperature of the tank at the end of each of 12 h.

Hour	$Q_u$ , MJ	$L_s$ , MJ	$T_s$ , C	$T_s^+$ , C
1	0	12	45	42.9
2	0	12	42.9	40.9
3	0	11	40.9	39.0
4	0	11	39.0	37.1
5	0	13	37.1	35.0
6	0	14	35.0	32.6
7	0	18	32.6	29.7
8	0	21	29.7	26.3
9	21	20	26.3	26.4
10	41	20	26.4	29.7
11	60	18	29.7	36.3
12	75	16	36.3	45.6

### Solution

The energy balance on the tank in finite-difference form is Equation 8.3.3. Inserting the appropriate constants, with a time increment of 1 h, yields

$$T_s^+ = T_s + \frac{1}{1500 \times 4190} [Q_u - L_s - 11.1 \times 3600(T_s - 20)]$$

With the initial tank temperature  $T_s$  of 45.0°C and  $Q_u$  and  $L_s$  of 0 and 12 MJ, respectively, the estimated tank temperature at the end of the hour  $T_s^+ = 42.9^\circ\text{C}$ . The starting temperature

<sup>1</sup>The dot over  $L_s$  (the load supplied by storage) has been left off as a reminder that  $L_s$  is an average rate over the time interval  $\Delta t$ .


for the next hour is thus  $42.9^\circ\text{C}$ . For the next hour new estimates of  $Q_u$  and  $L_s$  are obtained using  $T_s = 42.9^\circ\text{C}$  and any other time-dependent variables such as the incident solar radiation and ambient temperature. Tank losses, the last term in the brackets, are also easily assessed; for the first hour of this example they are 1.0 MJ. By setting up the calculation in the manner shown in this example, it is easy to integrate (i.e., add)  $Q_u$ ,  $L_s$ , and tank losses over time. ■

## 8.4 STRATIFICATION IN STORAGE TANKS


Water tanks may operate with significant degrees of stratification, that is, with the top of the tank hotter than the bottom. Many stratified tank models have been developed; they fall into either of two categories. In the first, the **multinode** approach, a tank is modeled as divided into  $N$  nodes (sections), with energy balances written for each section of the tank; the result is a set of  $N$  differential equations that can be solved for the temperatures of the  $N$  nodes as functions of time. In the second, the **plug flow** approach, segments of liquid at various temperatures are assumed to move through the tank in plug flow, and the models are essentially bookkeeping methods to keep track of the size, temperature, and position of the segments. Each of these approaches has many variations, and the selection of a model depends on the use to which it will be put. Examples of each approach are discussed. None of them lend themselves to hand calculations.

The degree of stratification in a real tank will depend on the design of the tank; the size, location, and design of the inlets and outlets; and flow rates of the entering and leaving streams. It is possible to design tanks with low inlet and outlet velocities that will be highly stratified (Gari and Loehrke, 1982; Van Koppen et al., 1979). The effects of stratification on solar process performance can be bracketed by calculating performance with fully mixed tanks and with highly stratified tanks.

To formulate the equations for a multinode tank, it is necessary to make assumptions about how the water entering the tank is distributed to the various nodes. For example, for the five-node tank shown in Figure 8.4.1, water from the collector enters at a temperature  $T_{co}$ , which lies between  $T_{s,2}$  and  $T_{s,3}$ . It can be assumed that it all finds its way down inside the tank to node 3, where its density nearly matches that of the water in the tank. (That this can be done is clearly illustrated in Figure 8.4.2, which shows dyed water entering



**Figure 8.4.1** A hypothetical five-node tank with  $T_{s,2} > T_{co} > T_{s,3}$ . Water can be considered to enter at node 3 or be distributed among nodes 1, 2, and 3.



**Figure 8.4.2** Dyed water entering a stratified tank through a low-velocity manifold. From Gari and Loehrke (1982).

a tank from a carefully designed inlet manifold.) Alternatively, it can be assumed that the incoming water distributes itself in some way to nodes 1, 2, and 3. In the following discussion, a model is developed that can represent a high degree of stratification; it is assumed that the water in Figure 8.4.1 finds its way into node 3.

Stratification is difficult to evaluate without considering the end use. If the load can use energy at the same efficiency without regard to its temperature level (that is, thermodynamic availability), then maximum stratification would provide the lowest possible temperature near the bottom of the tank and this would maximize collector output. On the other hand, if the quality of the energy to the load is important, then minimizing the destruction of available energy may be the proper criteria for defining maximum stratification (although all parts of the system should be considered simultaneously in such an analysis). The following analysis is intended to provide a limiting case in which the bottom of the tank is maintained at a minimum temperature, but other criteria could be used.

For a three-node tank, as shown in Figure 8.4.3, the flow to the collector always leaves from the bottom, node 3, and the flow to the load always leaves from the top, node 1. The flow returning from the collector will return to the node that is closest to but less than the collector outlet temperature. Suppose the three node temperatures are 45, 35, and 25°C, with, of course, the hottest at the top. Return water from the collector lower than 35°C will go to node 3 and between 35 and 45°C would go to node 2.

A collector control function  $F_i^c$  can be defined to determine which node receives water from the collector:

$$F_i^c = \begin{cases} 1 & \text{if } i = 1 \text{ and } T_{c,o} > T_{s,1} \\ 1 & \text{if } T_{s,i-1} \geq T_{c,o} > T_{s,i} \\ 0 & \text{if } i = 0 \text{ or if } i = N + 1 \\ 0 & \text{otherwise} \end{cases} \quad (8.4.1)$$




Figure 8.4.3 Three-node stratified liquid storage tank.

Note that if the collector is operating, then one and only one control function can be nonzero. Also, a fictitious temperature  $T_{s,0}$  of the nonexistent node zero is assumed to be a large number. The three branches of the collector return water are controlled by this collector return control function, as shown in Figure 8.4.3. For the three-node tank of the previous paragraph with return water between 45 and 35°C,  $F_1^c = 0$ ,  $F_2^c = 1$ ,  $F_3^c = 0$ .

The liquid returning from the load can be controlled in a similar manner with a load return control function  $F_i^L$ .

$$F_i^L = \begin{cases} 1 & \text{if } i = N \text{ and } T_{L,r} < T_{s,N} \\ 1 & \text{if } T_{s,i-1} \geq T_{L,r} > T_{s,i} \\ 0 & \text{if } i = 0 \text{ or if } i = N + 1 \\ 0 & \text{otherwise} \end{cases} \quad (8.4.2)$$

The net flow between nodes can be either up or down depending upon the magnitudes of the collector and load flow rates and the values of the two control functions at any particular instant. It is convenient to define a mixed-flow rate that represents the net flow into node  $i$  from node  $i - 1$ , excluding the effects of flow, if any, directly into the node from the load:

$$\dot{m}_{m,1} = 0 \quad (8.4.3a)$$

$$\dot{m}_{m,i} = \dot{m}_c \sum_{j=1}^{i-1} F_j^c - \dot{m}_L \sum_{j=i+1}^N F_j^L \quad (8.4.3b)$$

$$\dot{m}_{m,N+1} = 0 \quad (8.4.3c)$$

With these control functions, an energy balance on node  $i$  can be expressed as

$$m_i \frac{dT_{s,i}}{dt} = \left( \frac{UA}{C_p} \right)_i (T'_a - T_{s,i}) + F_i^c \dot{m}_c (T_{c,o} - T_{s,i}) + F_i^L \dot{m}_L (T_{L,r} - T_{s,i}) \\ + \begin{cases} \dot{m}_{m,i} (T_{s,i-1} - T_{s,i}) & \text{if } \dot{m}_{m,i} > 0 \\ \dot{m}_{m,i+1} (T_{s,i} - T_{s,i+1}) & \text{if } \dot{m}_{m,i+1} < 0 \end{cases} \quad (8.4.4)$$

where a term has been added to account for losses from node  $i$  to an environment at  $T'_a$ .

With a large number of nodes, the tank model given by Equation 8.4.4 represents a high level of stratification that may not be achievable in actual experiments. There is very little experimental evidence to support the use of this model to represent high stratification, but the model is based on first principles.

As a practical matter, many tanks show some degree of stratification, and it is suggested that three or four nodes may represent a reasonable compromise between conservative design (represented by systems with one-node tanks) and the limiting situation of carefully maintained high degrees of stratification.

Two other factors may be significant. First, stratified tanks will have some tendency to destratify over time due to diffusion and wall conduction. This has been experimentally studied by Lavan and Thompson (1977). Second, some tanks have sources of energy in addition to that in fluids pumped into or out of the tank. If, for example, an auxiliary heater coil were present in one of the nodes, an additional term could be added to Equation 8.4.4 to account for its effect.


Numerical integration of Equations 8.3.2 or 8.4.4 can be accomplished by several techniques that are discussed in texts on numerical methods. The explicit Euler, implicit Crank-Nicholson, predictor-corrector, and Runge-Kutta methods are the most common. Because of the complicated nature of the tank equations when coupled to a load and a collector, particularly with the stratified tank model, a computer must be used to obtain solutions.

An alternative approach suggested by Kuhn et al. (1980) for modeling a stratified storage tank is based on the assumption of plug flow of the fluid up or down in the tank. [The resulting model is not amenable to the step-by-step solutions of a differential equation as in Example 8.3.1 and is useful only in programs such as TRNSYS (2012).] Increments of volume (segments) of fluid from either the collector (or other heat source) or load enter the tank at an appropriate location, shifting the position of all existing segments in the tank between the inlet and the return. The size of a segment depends on the flow rate and the time increment used in the computation.

The point at which heated fluid is considered to enter the tank can be at a fixed position or at a variable position. If the fluid is considered to enter at a fixed position, it may be necessary to combine nodes above or below the entry to avoid temperature inversions. If the inlet is considered to be at a variable position (in a manner analogous to that shown in Figure 8.4.1), the position is selected so as to avoid temperature inversions.

Figure 8.4.4 illustrates the concept of the plug flow tank model. In this example, the tank is initially divided into four segments of volume  $V_i$  (represented on the figure by segments of the horizontal axis) and temperatures  $T_i$  without temperature inversions. In one time step, the collector delivers a volume of liquid,  $V_c$ , equal to  $\dot{m}_c \Delta t / \rho$  at a





**Figure 8.4.4** An example of the plug flow algebraic tank model. Adapted from Kuhn et al. (1980).

temperature  $T_c$ . Assuming that  $T_c > T_L$ , a new segment is added at the top of the tank and the existing profile is shifted down. At the same time, a volume of fluid  $V_L$  returns from the load, with  $V_L = \dot{m}_L \Delta t / \rho$  at a temperature of  $T_L$ . (These steps are shown sequentially, although they occur simultaneously.) If  $T_L < T_4$ , then a segment is added at the bottom of the tank and the whole profile is shifted upward. The net shift of the profile in the tank is volume  $V_c - V_L$  or  $(\dot{m}_c - \dot{m}_L) \Delta t / \rho$ . The segments and/or fractions of segments whose positions fall outside the bounds of the tank are returned to the collector and/or load. The average temperature of the fluid delivered to the load for the example of Figure 8.4.4 is

$$T_D = \frac{V_c T_c + (V_L - V_c) T_1}{V_L} \quad (8.4.5)$$

and the average heat source return temperature  $T_R = T_L$ .

The plug flow model, in contrast to the differential equations of the type of Equation 8.4.5, is algebraic. Its use in simulations is primarily a matter of bookkeeping.


This model can represent a somewhat higher degree of stratification than that of multinode differential equation models (*TRNSYS*, 2012; Kuhn et al., 1980).

The number of nodes needed to adequately predict the performance of a solar storage tank depends upon the application. If the goal is to predict the thermocline (i.e., the temperature distribution) during laboratory testing of tanks with specified periods of charging, discharging, and stand-by, Drück [as reported by Oberndorfer et al. (1999)] needed more than 100 nodes to reproduce the measured exit temperatures. Kleinbach et al. (1993) compared experimental data (for domestic hot-water-sized systems) with model predictions and found that 10 or fewer nodes were satisfactory in predicting measured performance. Oberndorfer et al. (1999) modeled a number of different systems using from 1 to 100 tank nodes and concluded that for annual predictions no more than 10 nodes are necessary and 3 to 5 nodes are usually sufficient. The general conclusion from these studies is that a 1-node tank model (i.e., a fully mixed tank) provides a conservative estimate of annual performance and a 10-node model provides essentially the same system performance estimate as a 100-node model.

## 8.5 PACKED-BED STORAGE

A packed-bed (also called a pebble bed or rock pile) storage unit uses the heat capacity of a bed of loosely packed particulate material to store energy. A fluid, usually air, is circulated through the bed to add or remove energy. A variety of solids may be used, rock being the most widely used material.

A packed-bed storage unit is shown in Figure 8.5.1. Essential features include a container, a screen to support the bed, support for the screen, and inlet and outlet ducts. In operation, flow is maintained through the bed in one direction during addition of heat (usually downward) and in the opposite direction during removal of heat. Note that heat



**Figure 8.5.1** A packed-bed storage unit. Courtesy of Solaron Corp.

cannot be added and removed at the same time; this is in contrast to water storage systems, where simultaneous addition to and removal from storage is possible.


Well-designed packed beds using rocks have several characteristics that are desirable for solar energy applications: The heat transfer coefficient between the air and solid is high, which promotes thermal stratification; the costs of the storage material and container are low; the conductivity of the bed is low when there is no airflow; and the pressure drop through the bed can be low.

A major advantage of a packed-bed storage unit is its high degree of stratification. This can be visualized by consideration of a hypothetical situation of a bed initially at a fixed temperature, which has air blown into it at a higher fixed temperature. The temperature profiles in the bed during heating are shown in Figure 8.5.2. The high heat transfer coefficient–area product between the air and pebbles means that high-temperature air entering the bed quickly loses its energy to the pebbles. The pebbles near the entrance are heated, but the temperature of the pebbles near the exit remains unchanged and the exit air temperature remains very close to the initial bed temperature. As time progresses a temperature front passes through the bed. By hour 5 the front reaches the end of the bed and the exit air temperature begins to rise.


When the bed is fully charged, its temperature is uniform. Reversing the flow with a new reduced inlet temperature results in a constant outlet temperature at the original inlet temperature for 5 h and then a steadily decreasing temperature until the bed is fully discharged.

If the heat transfer coefficient between air and pebbles were infinitely large, the temperature front during charging or discharging would be square. The finite heat transfer coefficient produces a “smeared” front that becomes less distinct as time progresses.

A packed bed in a solar heating system does not normally operate with constant inlet temperature. During the day the variable solar radiation, ambient temperature, collector



**Figure 8.5.2** Temperature distributions in a pebble bed while charging with inlet air at constant temperature.



**Figure 8.5.3** Temperature profiles in the Colorado State University House II pebble bed during charging and discharging. From Karaki et al. (1977).

inlet temperature, load requirements, and other time-dependent conditions result in a variable collector outlet temperature. A set of typical measured temperature profiles in an operating bed is shown in Figure 8.5.3. This bed was heated during the day with air from collectors flowing down, and energy was removed during the evening and night by air at temperatures near 20°C flowing upward.

Many studies are available on the heating and cooling of packed beds. The first analytical study was by Schumann (1929), and the following equations describing a packed bed are often referred to as the Schumann model. The basic assumptions leading to this model are one-dimensional plug flow, no axial conduction or dispersion, constant properties, no mass transfer, no heat loss to the environment, and no temperature gradients within the solid particles. The differential equations for the fluid and bed temperatures are

$$(\rho C_p)_{f\varepsilon} \frac{\partial T_f}{\partial t} = -\frac{(\dot{m}C_p)_f}{A} \frac{\partial T_f}{\partial x} + h_v(T_b - T_f) \quad (8.5.1)$$

$$(\rho C_p)_b(1 - \varepsilon) \frac{\partial T_b}{\partial t} = h_v(T_f - T_b) \quad (8.5.2)$$

where  $\varepsilon$  is the bed void fraction,  $h_v$  is the volumetric heat transfer coefficient between the bed and the fluid (i.e., the usual area heat transfer coefficient times the bed particulate surface area per unit bed volume), and other terms have their usual meanings. A correlation relating  $h_v$  to the bed characteristics and to the fluid flow conditions is given in Section 3.16.

For an air-based system, the first term on the left-hand side of Equation 8.5.1 can be neglected and the equations can be written as

$$\frac{\partial T_f}{\partial (x/L)} = NTU(T_b - T_f) \quad (8.5.3)$$

$$\frac{\partial T_b}{\partial \theta} = NTU(T_f - T_b) \quad (8.5.4)$$

$$NTU = \frac{h_v AL}{(\dot{m}C_p)_f} \quad (8.5.5)$$


and the dimensionless time is

$$\theta = \frac{t(\dot{m}C_p)_f}{(\rho C_p)_b(1 - \varepsilon)AL} \quad (8.5.6)$$

where  $A$  is bed cross-sectional area and  $L$  is bed length. Analytical solutions to these equations exist for a step change in inlet conditions and for cyclic operation.

For the long-term study of solar energy systems, these analytical solutions are not useful and numerical techniques must be employed. Kuhn et al. (1980) investigated a large number of finite-difference schemes to numerically solve Equations 8.5.3 and 8.5.4 and concluded that the “complicated effectiveness- $NTU$ ” method of Hughes (1975) was best suited for solar system simulation. The following development follows the simpler “effectiveness- $NTU$ ” method of Hughes, which is the same as the method proposed by Mumma and Marvin (1976). For practical designs the two Hughes models give essentially the same results, and the simpler one is recommended.

Over a length of bed  $\Delta x$  as shown in Figure 8.5.4, the bed temperature can be considered to be uniform. (The more complicated Hughes equations assumed the bed



**Figure 8.5.4** Packed bed divided into  $N$  segments.

temperature to have a linear variation over  $\Delta x$ .) The air temperature has an exponential profile and the air temperature leaving bed element  $i$  is found from

$$\frac{T_{f,i+1} - T_{b,i}}{T_{f,i} - T_{b,i}} = e^{NTU(\Delta x/L)} \quad (8.5.7)$$

This equation is analogous to a heat exchanger operating as an evaporator. The energy removed from the air and transferred to the bed in length  $\Delta x$  is then

$$(\dot{m}C_p)_f(T_{f,i} - T_{f,i+1}) = (\dot{m}C_p)_f(T_{f,i} - T_{b,i})\eta \quad (8.5.8)$$

where  $\eta$  is a constant equal to  $1 - e^{-NTU/N}$  and  $N = L/\Delta x$ .

With Equation 8.5.8, an energy balance on the rock within region  $\Delta x$  can then be expressed as

$$\frac{dT_{b,i}}{d\theta} = \eta N(T_{f,i} - T_{b,i}), \quad i = 1, \dots, N \quad (8.5.9)$$

Equation 8.5.9 represents  $N$  ordinary differential equations for the  $N$  bed temperatures. Fluid temperatures are found from Equation 8.5.8. An extension to Equation 8.5.9 permits energy loss to an environment at  $T'_a$  to be included. Then

$$\frac{dT_{b,i}}{d\theta} = \eta N(T_{f,i} - T_{b,i}) + \frac{(U \Delta A)_i}{(\dot{m}C_p)_f} (T'_a - T_{b,i}) \quad (8.5.10)$$

where  $(U \Delta A)_i$  is the loss area–loss coefficient product for node  $i$ .


Hughes suggests that a Crank-Nicholson approach be used to solve Equation 8.5.10. The time derivative is replaced by  $(T'_a - T_{b,i})/\Delta\theta$  and the bed temperatures on the right-hand side of Equation 8.5.10 are replaced by  $(T_{b,i}^+ + T_{b,i})/2$ . With all bed temperatures known, the process starts at node 1 so that the inlet fluid temperature is known. A new bed temperature is calculated from Equation 8.5.10 and an outlet fluid temperature from Equation 8.5.8. This new fluid temperature becomes the inlet fluid temperature for node 2.

The repetitive solution of the Schumann model, even in the form of Equation 8.5.10, is time consuming for year-long solar process calculations. This observation led Hughes et al. (1976) to investigate an infinite  $NTU$  model. When the complete Schumann equations are solved for various values of  $NTU$ , the long-term performance of a solar air heating system with  $NTU = 25$  is virtually the same as that with  $NTU = \infty$ .

For infinite  $NTU$ , Equations 8.5.3 and 8.5.4 can be combined into a single partial differential equation since the bed and fluid temperatures are everywhere equal. With the addition of a container heat loss term the result is

$$\frac{\partial T}{\partial \theta} = -L \frac{\partial T}{\partial x} + \frac{(UA)_b}{(\dot{m}C_p)_f} (T'_a - T) \quad (8.5.11)$$

This is a single partial differential equation instead of the two coupled partial differential equations of the Schumann model. The single equation represents both the bed and air temperatures since the infinite  $NTU$  model assumes the two are identical.



**Figure 8.5.5** Long-term performance on a pebble bed as a function of  $NTU$ . The band represents different values of collector and bed characteristics for solar heating systems. From Hughes et al. (1976).

Figure 8.5.5 shows the ratio of the predicted long-term fraction of a heating load met by solar energy for a system with a bed having a finite  $NTU$  to the solar fraction with an infinite  $NTU$  bed. At  $NTU$  greater than 25 the ratio is unity, but at values as low as 10 the ratio is above 0.95. Consequently, the infinite  $NTU$  model can be used for long-term performance predictions even if  $NTU$  is as low as 10. Short-term predictions of bed temperature profiles should be based on the full Schumann equations unless the bed  $NTU$  is large.

The Schumann model is based on the assumption that the temperature gradients within the particles of the packed bed are not significant; this assumption can be relaxed by defining a corrected value of  $NTU$ . Jeffreson (1972) has shown that temperature gradients within the rocks can be accommodated by defining a corrected  $NTU$ :

$$NTU_c = \frac{NTU}{1 + Bi/5} \quad (8.5.12)$$

where  $Bi$  is the rock Biot number defined as  $hR/k$ , where  $R$  is an equivalent spherical rock radius,  $k$  is the rock conductivity, and  $h$  is the fluid-to-rock heat transfer coefficient. The  $NTU_c$  can be used in any of the equations of this section instead of  $NTU$  to include the effects of temperature gradients in the rock. If the Biot number is less than 0.1, the temperature gradients within the pebbles can be neglected.

### Example 8.5.1

A pebble bed has the following characteristics: length in flow direction 1.80 m; cross-sectional area 14.8 m<sup>2</sup>; air velocity 0.053 m/s, equivalent diameter of pebbles 12.5 mm, void fraction 0.47, density of pebble material 1350 kg/m<sup>3</sup>, specific heat of pebbles 0.90 kJ/kg °C, thermal conductivity of pebble material 0.85 W/m °C, and surface area of pebbles per unit volume 255 m<sup>2</sup>/m<sup>3</sup>. For this pebble bed, calculate the Biot number and  $NTU$ . Will there be significant temperature gradients in the pebbles? Can the infinite  $NTU$  model be used to calculate the performance of this storage unit?

**Solution**

The temperature of the air is unknown. If we use a low temperature to evaluate properties (e.g., 20°C), the Biot number and  $NTU$  criteria will be more severe than if a high temperature were used. The volumetric heat transfer coefficient from fluid to pebbles is estimated from the L f and Hawley equation of Section 3.16:

$$h_v = 650(G/D)^{0.7}$$

$$G = 0.053 \times 1.204 = 0.0638 \text{ kg/m}^2 \text{ s}$$

so

$$h_v = 650(0.0638/0.0125)^{0.7} = 2030 \text{ W/m}^3 \text{ }^\circ\text{C}$$

and

$$h = 2030/255 = 8.0 \text{ W/m}^2 \text{ }^\circ\text{C}$$

$$\text{Bi} = \frac{hR}{k} = \frac{8.0 \times 0.0125/2}{0.85} = 0.059$$

Since the Biot number is less than 0.1,  $NTU_c$  is nearly the same as  $NTU$ . From the definition of  $NTU$  (Equation 8.5.5),

$$NTU = \frac{h_v AL}{(\dot{m}C_p)_f} = \frac{2030 \times 14.8 \times 1.80}{0.053 \times 14.8 \times 1.004 \times 1010} = 68$$

Thus the number of transfer units is much larger than 10, and the infinite  $NTU$  model is appropriate. ■

**Example 8.5.2**

For the pebble bed of Example 8.5.1 compute the bed air outlet temperature over a 16-h time span as a function of time if the bed is initially at 25°C and the air inlet temperature varies sinusoidally from 25 to 65°C and back to 25°C over a 16-h period. Assume that the heat loss from the side of the pebble bed is small.

**Solution**

Since Example 8.5.1 shows that the pebble Biot number is less than 0.1 and that  $NTU > 25$ , Equation 8.5.11 can be used to find the outlet temperature. There is an analytic solution for this situation, but a numerical solution is generally more versatile. The bed is divided into  $N$  sections, as shown in Figure 8.5.4. Equation 8.5.11 is converted into  $N$  ordinary differential equations. The space derivative is approximated as

$$\frac{\partial T}{\partial x} \approx 0.5 \left[ \left( \frac{T_i - T_{i-1}}{\Delta x} \right) + \left( \frac{T_{i+1} - T_i}{\Delta x} \right) \right] = \frac{T_{i+1} - T_{i-1}}{2\Delta x}$$

With this approximation and the small bed losses the  $N$  equations are

$$\frac{dT_i}{d\theta} = -L \left( \frac{T_{i+1} - T_{i-1}}{2\Delta x} \right), \quad i = 1, \dots, N$$



The inlet air temperature is given by

$$T_0 = 25 + 40 \sin \left( \frac{360}{2\pi} \frac{\pi}{16} \frac{t}{3600} \right) = 25 + 40 \sin \left( \frac{t}{320} \right)$$


where  $t$  is the time in seconds. The outlet air temperature is the same as the exit bed temperature, so  $T_{N+1} = T_N$ . This set of equations can be solved by packaged software (e.g., EES), by programs written in a high-level language such as FORTRAN or Pascal, or by a spreadsheet. The set of ordinary differential equations can be discretized to form a set of explicit algebraic equations of the form

$$T_i^+ = T_i - \frac{\Delta\theta L}{2 \Delta x} (T_{i+1} - T_i), \quad i = 1, \dots, N$$

where at time zero all temperatures are 25°C.

The solution is straightforward. For node 1 everything is known (either from the initial conditions or from the boundary condition) so the new temperature of node 1 can be calculated. Once the new temperature of node 1 is known the new temperature of node 2 can be evaluated. The solution proceeds by marching through the bed length. The processes repeated for each new time.

The inlet and outlet air temperatures are shown in the figure. For this example the outlet temperature lags the inlet temperature by about 5 h. As with all numerical solutions of differential equations, care must be exercised in choosing appropriate time and/or space intervals. The line shown in the figure for the outlet temperature was obtained by dividing the bed into 100 nodes and used a  $\frac{1}{32}$ -h time step. Also shown by the use of different symbols are solutions with a variety of time and distance increments. For this example the use of 10 nodes and  $\frac{1}{4}$ -h time steps is probably a reasonable compromise between accuracy and computational speed. When the airflow is reversed to extract energy from the bed, the same equations can be used but the distance  $x$  must be measured from what was the bed outlet.



## 8.6 STORAGE WALLS

In passive heating systems, storage of thermal energy is provided in the walls and roofs of the buildings. A case of particular interest is the collector-storage wall, which is arranged so that solar radiation transmitted through glazing is absorbed on one side of the wall. The temperature of the wall increases as energy is absorbed, and time-dependent temperature gradients are established in the wall. Energy is lost through the glazing and is transferred from the room side of the wall to the room by radiation and convection. Some of these walls may be vented, that is, have openings in the top and bottom through which air can circulate from and to the room by natural convection, providing an additional mechanism for transfer of energy to the room. Figure 8.6.1 shows a section of such a wall.


A solid storage wall [e.g., a wall of concrete as used by Trombe et al. (1977)] can be considered as a set of nodes connected together by a thermal network, each with a temperature and capacitance. The network used in *TRNSYS* (2012), which is similar to that used by Balcomb et al. (1977), Ohanessian and Charters (1978), and others, is shown in Figure 8.6.2. The wall is shown divided into  $N$  nodes across its thickness, with the surface nodes having half of the mass of the interior nodes. A loss coefficient  $U_l$  is based on the inner glazing temperature, as it is in Figure 6.14.1(a). Heat is transferred by radiation across the gap and by convection between air flowing in the gap and the absorbing surface and the inner glazing. (The glazing will at times be colder than the air, and at those times the convective transfer will be from air to glazing.) If there is no air flow, heat transfer will occur across the gap by convection in the enclosed gap space and by radiation.

Energy balances are written for each node of thickness  $\Delta x$ , resulting in a set of ordinary differential equations with terms that represent its time-dependent temperature and energy flows to all adjacent nodes. The general energy balance for any node in the wall is


$$\frac{dT_i}{dt} = \frac{k}{\rho C \Delta x^2} (T_{i-1} + T_{i+1} - 2T_i), \quad i = 2, \dots, N-1 \quad (8.6.1)$$

Equations for nodes 1 and  $N$  must take into account the node half thickness and the convection and radiation heat transfer. The set of  $N$  equations are simultaneously solved for the time-dependent temperatures at each of the nodes, and from this the energy stored in the wall (relative to a base temperature  $T_{\text{room}}$ ) can be calculated.

If there is airflow through vents and to the room, the energy added to the room by this mechanism will be  $(\dot{m}C_p)_a(T_o - T_r)$ . Air may circulate by either natural or forced



**Figure 8.6.1** Section of a storage wall with glazing and energy-absorbing surface on one surface.



**Figure 8.6.2** A thermal circuit diagram for a collector storage wall with double glazing. From *TRNSYS* (2012).

convection, and in either case it is necessary to estimate flow rates and convection coefficients. Flow by natural convection is difficult to estimate. Trombe et al. (1977) have published measurements that indicate that most of the pressure drop is through the vents. Analyses have been done for laminar flow (e.g., Fender and Dunn, 1978) but have not included pressure drops through vents. It is probable that flow will be turbulent due to entrance and exit effects.

A solution of Bernoulli's equation can be used to estimate the mean velocity in the gap based on the assumption that density and air temperature in the gap vary linearly with height. The average velocity in the gap is

$$\bar{V} = \left[ \frac{2gh}{\left[ C_1 (A_g/A_v)^2 + C_2 \right]} \frac{T_m - T_r}{T_m} \right]^{1/2} \quad (8.6.2)$$

The term  $[C_1 (A_g/A_v)^2 + C_2]$  represents the pressure drop in the gap and vents, and  $C_1$  and  $C_2$  are dimensionless empirical constants. The wall height is  $h$  and  $T_m$  is the mean air temperature in the gap. From data in Trombe et al. (1977), values of  $C_1$  and  $C_2$  have been determined by Utzinger (1979) to be 8.0 and 2.0, respectively.

The heat transfer coefficient between air in the gap and the wall and glazing depends on whether the vents are open. If the vents are closed, the methods of Sections 3.8 and 3.11 for vertical collectors can be used. If the vents are open and there is flow through the gap, Equation 3.14.6 can be used for flow in the turbulent region and Equation 3.14.7 can be used for the laminar region. The loss coefficient  $U_t$  can be estimated by the standard

methods of Chapter 6. Heat transfer from the room side of the wall to the room is calculated by conventional methods.


This analysis for collector-storage walls can be simplified to apply to walls that are not vented or that are not glazed.

## 8.7 SEASONAL STORAGE


Large-scale solar heating systems that supply energy to district heating systems for building and water heating require large-scale storage facilities. These are in most cases in the ground, as there is no other feasible way to gain the necessary capacity. The objective of very large scale storage is to store summer energy for winter use. Thus the time span over which losses from storage occur is of the order of a year, and losses occur in summer months when they would not occur in systems with storage capacities of the order of days. The volume of a storage unit increases (roughly) as the cube of the characteristic dimension, and its area for heat loss increases as the square, so increasing the size reduces the loss-to-capacity ratio. Figure 8.7.1 shows how annual solar fraction can vary with storage capacity (on a log scale) for building heating. There are two ‘knees’ in the curve; the first is where sufficient energy is stored in a day to carry the loads through the night and the second is where energy is stored in the summer to carry loads in the next winter. Storage capacity per unit collector area must be two to three orders of magnitude larger for seasonal storage than for overnight storage. These factors have led to consideration of very large thermal energy storage systems.

Bankston (1988) provides a review of seasonal storage solar heating systems, much of which is concerned with design and performance of the storage units. Several ground storage methods have been explored and/or used, including water-filled tanks, pits, and caverns underground; storage in the ground itself; and storage in aquifers.

Large underground water storage tanks or caverns, or water-filled pits in the ground that are roofed over, are the same in their principles of operation as the tanks discussed in Sections 8.3 and 8.4. Energy is added to or removed from the store by pumping water into or out of the storage unit. Their larger capacity makes stratification more likely. The major difference will be in the mechanisms for heat loss and possible thermal coupling with the ground. Units that have been built and operated vary widely in design and characteristics,



**Figure 8.7.1** Variation of annual fraction of heating loads carried by solar energy in a space heating application with storage capacity per unit collector area. Adapted from Braun (1980).



**Figure 8.7.2** Temperature profiles in the Lyckebo store during the second year of operation. From Brunstrom and Larsson (1986).

and the calculation of performance of each is based on the particular circumstances of its design. A brief description follows of one such system, at Lyckebo, Sweden, with note of the important factors in its operation.

The Lyckebo system (e.g., Brunstrom and Larsson, 1986) is a cavern of  $10^5 \text{ m}^3$  capacity cut out of bedrock using standard mining methods of cylindrical shape with a central column of rock left to support the overhead rock. The cavern is about 30 m high and its top is about 30 m below ground level. It is water filled, and inlet and outlet pipes can be moved up and down to inject and remove water from controlled levels. The water is highly stratified with top-to-bottom temperatures of about 80 to  $30^\circ\text{C}$ . Figure 8.7.2 shows temperature profiles in the store at various dates in the second year of operation; the high degree of stratification is evident. No thermal insulation is used, and there is a degree of coupling with surrounding rock which adds some effective capacity to the system. Losses occur to a semi-infinite solid and can be estimated by standard methods. Observed losses from this system are higher than those calculated; this is attributed to small but significant thermal circulation of water through the tunnel used in cavern construction and back through fissures in the rock. It takes several years of cycling through the annual weather variations for a storage system of this size to reach a “steady periodic” operation. In the second year of its operation, while it was still in a “warm-up” stage, 74% of the energy added to the store was recovered.

Ground (e.g., the soil, sand, rocks, clay) can be used for thermal energy storage. Means must be provided to add energy to and remove it from the medium. This is done by pumping heat transfer fluids through pipe arrays in the ground. The pipes may be vertical U-tubes inserted in wells that are spaced at appropriate intervals in the storage field or they may be horizontal pipes buried in trenches. The rates of charging and discharging are limited by the area of the pipe arrays and the rates of heat transfer through the ground surrounding the pipes. If the storage medium is porous, energy transport may occur by evaporation and condensation and by movement of water through the medium, and a complete analysis of such a store must include consideration of both heat and mass transfer. These storage systems are usually not insulated, although insulation may be provided at the ground

surface. These storage units usually operate over smaller temperature ranges than the water stores noted previously.

A borehole storage system at Lulea, Sweden, provides an example of ground storage (Bankston, 1988). It consists of 120 boreholes drilled to a depth of 65 m into bedrock which lies under 2 to 6 m of soil. The holes are on a square pattern 4 m apart. The total volume of rock in the active store is about  $10^5 \text{ m}^3$ . A tube that delivers the fluid to the bottom of the hole is inserted into each of the holes; the fluid then passes up through the annulus in contact with the rock. Flow patterns are so arranged as to have the central part of the store the hottest, achieving a degree of stratification. This store, which is heated to  $80^\circ\text{C}$  by wastewater from an industrial process rather than solar energy, shows maximum and minimum temperatures in the center of the array of  $60^\circ\text{C}$  and  $40^\circ\text{C}$ ; the far-field rock temperature is  $5^\circ\text{C}$ . About 60% of the energy that is added to the store is usefully extracted to provide heat for buildings.

Aquifer storage is closely related to ground storage, except that the primary storage medium is water which flows at low rates through the ground. Water is pumped out of and into the ground to heat it and extract energy from it. Water flow also provides a mechanism for heat exchange with the ground itself. As a practical matter, aquifers cannot be insulated. Only aquifers that have low natural flow rates through the storage field can be used. A further limitation may be in chemical reactions of heated water with the ground materials. Aquifers, as with ground storage, operate over smaller temperature ranges than water stores.

## 8.8 PHASE CHANGE ENERGY STORAGE


Materials that undergo a change of phase in a suitable temperature range may be useful for energy storage if several criteria can be satisfied. The phase change must be accompanied by a high latent heat effect, and it must be reversible over a very large number of cycles without serious degradation. The phase change must occur with limited supercooling or superheating, and means must be available to contain the material and transfer heat in and out. Finally, the cost of the material and its containers must be reasonable. If these criteria can be met, phase change energy storage systems can operate over small temperature ranges, have relatively low volume and mass, and have high storage capacities (relative to energy storage in specific-heat-type systems).

The storage capacity of a phase change material heated from  $T_1$  to  $T_2$ , if it undergoes a phase transition at  $T^*$ , is the sum of the sensible heat change of the solid (the lower temperature phase) from  $T_1$  to  $T^*$ , the latent heat at  $T^*$ , and the sensible heat of the liquid (the melt, or higher temperature phase) from  $T^*$  to  $T_2$  :

$$Q_s = m[C_s(T^* - T_1) + \lambda + C_l(T_2 - T^*)] \quad (8.8.1)$$

where  $m$  is the mass of material,  $C_s$  and  $C_l$  are the heat capacities of the solid and liquid phases, and  $\lambda$  is the latent heat of phase transition. Glauber's salt ( $\text{Na}_2\text{SO}_4 \cdot 10\text{H}_2\text{O}$ ) has  $C_s \sim 1950 \text{ J/kg } ^\circ\text{C}$ ,  $\lambda = 2.43 \times 10^5 \text{ J/kg}$  at  $34^\circ\text{C}$ , and  $C_l \sim 3550 \text{ J/kg } ^\circ\text{C}$ ; on heating 1 kg of this medium from  $25$  to  $50^\circ\text{C}$  the energy stored would be  $1950(34 - 25) + 2.43 \times 10^5 + 3350(50 - 34) = 0.315 \text{ MJ}$ .

Glauber's salt was the earliest phase change storage material to be studied experimentally for house heating applications (Telkes, 1955). On heating at approximately  $34^{\circ}\text{C}$  it gives a solution and solid  $\text{Na}_2\text{SO}_4$  :



Energy storage is accomplished by the reaction proceeding from left to right on addition of heat. The total energy added depends on the temperature range over which the material is heated since it will include sensible heat to heat the salt to the transition temperature, heat of fusion to cause the phase change, and sensible heat to heat the  $\text{Na}_2\text{SO}_4$  and solution to the final temperature. Energy extraction from storage is the reverse procedure, with the reaction proceeding from right to left and the thermal effects reversed.

Practical difficulties have been encountered with this material. It has been found that performance degrades on repeated cycling, with the thermal capacity of the system reduced. As shown in Figure 8.8.1,  $\text{Na}_2\text{SO}_4 \cdot 10\text{H}_2\text{O}$  has an incongruent melting point, and as its temperature increases beyond the melting point, it separates into a liquid (solution) phase and solid  $\text{Na}_2\text{SO}_4$ . Since the density of the salt is higher than the density of the solution, phase separation occurs. Many studies have been done to develop means to avoid phase separation: through the use of containers of thin cross section; through the use of gels, thickeners, and other agents; or by mechanically agitating the melt mix.

Johnson (1977) has applied phase change storage to a passively heated building, where operation over small temperature ranges is needed. The melting point of  $\text{Na}_2\text{SO}_4 \cdot 10\text{H}_2\text{O}$  is too high for this application; the addition of 9%  $\text{NaCl}$  to the Glauber's salt reduced the melting point to about  $23^{\circ}\text{C}$ . In addition, borax, a thickener, and surfactants were added. Laboratory tests showed no noticeable phase separation after 500 cycles. This phase change material is designed to be used in thin layers in ceiling tiles in passively heated buildings.

Other possibilities for phase change storage media for temperatures in ranges of interest in comfort heating include, for example,  $\text{Na}_2\text{SO}_4 \cdot 12\text{H}_2\text{O}$  and  $\text{Fe}(\text{NO}_3)_2 \cdot 6\text{H}_2\text{O}$  (which has a congruent melting point). Paraffin waxes have also been studied for this use; they can be obtained with various melting points and as mixtures with ranges of melting points. Eutectic mixtures have also been studied (Kauffman and Gruntfest, 1973), such as  $\text{CaCl}_2 \cdot \text{MgCl}_2 \cdot \text{H}_2\text{O}$ ,  $\text{urea} \cdot \text{NH}_4\text{NO}_3$ , and others. Phase change materials studied




Figure 8.8.1 Phase diagram for sodium sulfate decahydrate, with incongruent melting point.

for application at higher temperatures include  $\text{AlSO}_4 \cdot 10\text{H}_2\text{O}$  (melting point  $112^\circ\text{C}$ ),  $\text{MgCl}_2 \cdot 6\text{H}_2\text{O}$  (melting point  $115^\circ\text{C}$ ), and  $\text{NaNO}_3 + \text{NaOH}$  (melting point  $245^\circ\text{C}$ ).

A further consideration with phase change materials lies in the possibility of supercooling on energy recovery. If the material supercools, the latent heat of fusion may not be recovered or it may be recovered at a temperature significantly below the melting point. This question has been approached from three standpoints: by selection of materials that do not have a strong tendency to supercool, by addition of nucleating agents, and by ultrasonic means of nucleation. These considerations are reviewed by Belton and Ajami (1973), who note that the viscosity at the melting point of a material is a major factor in determining the glass-forming ability of a melt and thus its tendency to supercool.

Carlsson et al. (1978) have carried out an extensive experimental study of the use of  $\text{CaCl}_2 \cdot 6\text{H}_2\text{O}$ , including consideration of heat transfer through the storage medium, supercooling, temperature stratification, and the use of  $\text{SrCl}_2 \cdot 6\text{H}_2\text{O}$  to avoid the formation of a stable tetrahydrate that interferes with hydration and dehydration reactions.

Phase change storage media are usually contained in small containers or shallow trays to provide a large heat transfer area. The general principles of packed-bed storage units outlined in Section 8.5 will apply to these units. The heat transfer fluid is usually air, although water has been used. Two additional phenomena must be considered. First, the latent heat must be taken into account; it is in effect a high specific heat over a very small temperature range. Second, the thermal resistance to heat transfer within the material is variable depending on the degree of solidification and whether heating or cooling of the material is occurring. [Heat transfer in situations of this type has been studied, for example, by Hodgins and Hoffman (1955), Murray and Landis (1959), and Smith et al. (1980).] As heat is extracted from a phase change material, crystallization will occur at the walls and then progressively inward into the material; at the end of the crystallization, heat must be transferred across layers of solid to the container walls. As a solidified material is heated, melting occurs first at the walls and then inward toward the center of the container. These effects can be minimized by design of the containers to give very short pathlengths for internal heat transfer, and the following development assumes the internal gradients to be small.


Morrison and Abdel-Khalik (1978) developed a model applicable to phase change materials in such containers, where the length in flow direction is  $L$ , the cross-sectional area of the material is  $A$ , and the wetted perimeter is  $P$ . The heat transfer fluid passes through the storage unit in the  $x$  direction at the rate  $\dot{m}$  and with inlet temperature  $T_{fi}$  as shown in Figure 8.8.2.

A model can be based on three assumptions: (a) During flow, axial conduction in the fluid is negligible; (b) the Biot number is low enough that temperature gradients normal to the flow can be neglected; and (c) heat losses from the bed are negligible. An energy balance on the material gives

$$\frac{\partial u}{\partial t} = \frac{k}{\rho} \frac{\partial^2 T}{\partial x^2} + \frac{UP}{\rho A} (T_f - T) \quad (8.8.2)$$

where  $u$ ,  $T$ ,  $K$ , and  $\rho$  are the specific internal energy, temperature, thermal conductivity, and density of the phase change material;  $T_f$  and  $U$  are the circulating fluid temperature and overall heat transfer coefficient between the fluid and phase change material; and  $t$  is time.





**Figure 8.8.2** Schematic of a phase change storage unit. From Morrison and Abdel-Khalik (1978).

An energy balance on the fluid is

$$\frac{\partial T_f}{\partial t} + \frac{\dot{m}}{\rho_f A_f} \frac{\partial T_f}{\partial x} = \frac{UP}{\rho_f A_f C_f} (T - T_f) \quad (8.8.3)$$

where  $\rho_f$ ,  $A_f$ , and  $C_f$  are the density, flow area, and specific heat of the fluid.

The specific internal energy is related to temperature  $T$ , liquid fraction  $\chi$ , and the specific heats of the liquid and solid phases  $C_l$  and  $C_s$  by

$$u = \begin{cases} C_s (T - T_{\text{ref}}) & \text{if } T < T^* \\ C_s (T^* - T_{\text{ref}}) + \chi \lambda & \text{if } T = T^* \\ C_s (T^* - T_{\text{ref}}) + \lambda + C_l (T - T^*) & \text{if } T > T^* \end{cases} \quad (8.8.4)$$

where  $T^*$  is the melting temperature and  $T_{\text{ref}}$  is the reference temperature at which the internal energy is taken as zero.

The equation and boundary conditions for phase change energy storage can be simplified for particular cases [see Morrison and Abdel-Khalik (1978) for details]. It has been shown that axial conduction during flow is negligible, and if the fluid capacitance is small, Equations 8.8.2 and 8.8.3 become

$$\frac{\partial u}{\partial t} = \frac{UP}{\rho A} (T_f - T) \quad (8.8.5)$$

$$\frac{\partial T_f}{\partial x} = \frac{UP}{(\dot{m} C_p)_f} (T - T_f) \quad (8.8.6)$$

These two equations can be rewritten in terms of  $NTU$  as

$$\frac{\partial u}{\partial \theta} = NTU (T_f - T) \quad (8.8.7)$$

$$\frac{\partial T_f}{\partial (x/L)} = NTU (T - T_f) \quad (8.8.8)$$

where  $\theta = t(\dot{m} C_p)_f / \rho A L$  and  $NTU = UPL / (\dot{m} C_p)_f$ .

Equations 8.8.7 and 8.8.8 are essentially the same as Equations 8.5.2 and 8.5.3 for air and rock beds. Morrison and Abdel-Khalik have developed these models, explored the effects of assumptions made in their development, and used them in simulation studies of solar heating systems with ideal phase change energy storage that has no superheating or supercooling and complete reversibility (see Section 13.10). They showed that the infinite *NTU* model is a good approximation for practical systems.

Jurinak and Abdel-Khalik (1979) have shown that for building heating operations where the melting point is between an optimum value (usually 5 to 10°C above room temperature) and 50°C, an empirical equation for equivalent heat capacity can be written as

$$C_{p,e} = \frac{18.3}{T^{*2}} \lambda + \left(1 - \frac{18.3}{T^{*2}}\right) C_s + \frac{18.3}{T^{*2}} C_l \quad (8.8.9)$$

where all temperatures are in degrees Celsius and  $\lambda$  is in kilojoules per kilogram.

Other practical considerations include corrosion, reactions of the phase change material with containers or other side reactions, vapor pressure, and toxicity. Cost is a major factor in many applications and rules out all but the least expensive materials.

Comparisons of sensible heat storage and phase change storage can only be made in the context of systems in particular applications. The system analysis methods outlined in the following chapters can be used to evaluate the relative merits of the several possible methods. In doing so, it should be kept in mind that the formulations for sensible heat storage are reliable (in the sense that temperature changes of sensible heat media are very predictably related to quantities of heat added to or removed), whereas those for phase change materials may be more uncertain because of possible (and unpredictable) superheating, supercooling, and lack of complete reversibility of the phase change.

## 8.9 CHEMICAL ENERGY STORAGE

The previous section dealt with storage of thermal energy in materials undergoing phase transitions. In this section we consider chemical reactions that might be used to store energy. None of these possibilities have yet been used in practical applications, and both technical and economic questions are yet to be answered for all of the possibilities. A review of chemical storage is presented by Offenhartz (1976).


An ideal thermochemical reaction for energy storage is an endothermic reaction in which the reaction products are easily separable and do not undergo further reactions. For example, decomposition reactions of the type  $AB + \text{heat} \rightarrow A + B$  are candidates if the reaction can be reversed to permit recovery of the stored energy. The products A and B can be stored separately, and thermal losses from the storage units are restricted to sensible heat effects, which are usually small compared to heats of reaction. Unfortunately, there are not very obvious candidates of this type useful for low-temperature solar applications. Reactions in which water vapor is a product have the difficulty that the heat of condensation is usually lost. Reactions in which products such as atomic chlorine are produced lose energy on formation of the dimer  $\text{Cl}_2$ .

Thermal decomposition of metal oxides for energy storage has been considered by Simmons (1976). These reactions may have the advantage that the oxygen evolved can be

used for other purposes or discarded and oxygen from the atmosphere used in the reverse reactions. Two examples are the decomposition of potassium oxide,



which occurs over a temperature range of 300 to 800°C with a heat of decomposition of 2.1 MJ/kg, and lead oxide,



which occurs over a temperature range of 300 to 350°C with a heat of decomposition of 0.26 MJ/kg. There are many practical problems yet to be faced in the use of these reactions.

Energy storage by thermal decomposition of  $\text{Ca}(\text{OH})_2$  has been extensively studied by Fujii et al. (1985, 1989). The reaction is  $\text{Ca}(\text{OH})_2 \leftrightarrow \text{CaO} + \text{H}_2\text{O}$ . The forward reaction will proceed at temperatures above about 450°C; the rates of reaction can be enhanced by the addition of zinc or aluminum. The product CaO is stored in the absence of water. The reverse exothermic reaction proceeds easily; in experiments reported in Fujii et al. (1985) energy was recovered at temperatures in the 100 to 200°C range, and temperature rises to 300°C were mentioned.

Another reaction of possible interest in higher temperature ranges is the dehydration of mixtures of  $\text{MgO}/\text{Mg}(\text{OH})_2$  [see Bauerle et al. (1976), who also considered  $\text{CaO}/\text{Ca}(\text{OH})_2$ ]. The storage reaction proceeds at temperatures of 350 to 550°C. The reverse reactions occur at lower temperatures on the addition of water or steam. The system sulfuric acid—water has also been proposed [e.g., by Huxtable and Poole (1976)], with condensed water and acid stored until needed. There are obvious practical problems with these systems.

An example of a photochemical decomposition reaction is the decomposition of nitrosyl chloride, which can be written as



The atomic chlorine produced forms chlorine gas,  $\text{Cl}_2$ , with the release of a substantial part of the energy added to the NOCl in decomposition. Thus the overall reaction is



The reverse reaction can be carried out to recover part of the energy of the photons entering the reaction (Marcus and Wohlers, 1961).

Processes that produce electrical energy may have storage provided as chemical energy in electrical storage batteries or their equivalent as described in the next section. Several types of battery systems can be considered for these applications, including lead-acid, nickel-iron, and nickel-cadmium batteries. For low discharge rates and moderate charge rates the efficiencies of these systems range from 60 to 80% (ratio of watt-hour output to watt-hour input). It is also possible to electrolyze water with solar-generated electrical energy, to store oxygen and hydrogen, and to recombine in a fuel cell to regain electrical energy (Bacon, 1964). These storage systems are characterized by the relatively high cost

per kilowatt-hour of storage capacity and can now be considered for low-capacity special applications such as auxiliary power supply for space vehicles, isolated telephone repeater power supplies, instrument power supplies, and so on.

## 8.10 BATTERY STORAGE

The previous section dealt with the storage of thermal energy by means of chemical reactions. In this section we consider chemical reactions that are specifically designed to store electricity. Although this material could have been included in the previous section, the subject is of sufficient importance to warrant a separate section. In recent years there has been considerable work on improving batteries for hybrid electric vehicles. This work is directly applicable to batteries used for energy storage for wind and photovoltaic systems. A detailed discussion of batteries is presented by Bode (1977).

The Shepard (1965) model is the basis of a number of different battery models. Here we discuss the Shepard model as implemented by Eckstein (1990) in the *TRNSYS* (2012) simulation program (see Section 19.4). One problem with all battery models is that a large number of parameters are needed to predict the performance of a specific battery and the only way to accurately obtain values for these parameters is to test the battery. Here we supply typical values for many of the parameters so that a reasonable electrical storage system model can be developed.

The model for each cell requires two equations, one for charging and one for discharging. For charging (when the current  $I > 0$ )

$$V = V_{oc} + \frac{1}{k_z} \ln \left( \frac{|I|}{I_z} + 1 \right) - g_d H + I r_{qd} \left( 1 + \frac{m_d H}{Q_d / Q_m - H} \right) \quad (8.10.1)$$

and for discharging (when the current  $I < 0$ )

$$V = V_{oc} - \frac{1}{k_z} \ln \left( \frac{|I|}{I_z} + 1 \right) - g_c H + I r_{qc} \left( 1 + \frac{m_c H}{Q_c / Q_m - H} \right) \quad (8.10.2)$$

The subscripts  $c$  and  $d$  represent charging and discharging, respectively. The subscript  $oc$  is open circuit and  $z$  is a correction for small currents. The parameter  $H$  is the fractional depth of discharge and is equal to  $1 - F$ , where  $F$  is the fractional state of charge and is equal to  $Q / Q_m$ . The battery capacity is  $Q_m$  (at  $F = 1$  obtainable from the manufacturer) and  $Q$  is the actual battery capacity. The cell capacity parameters for charge and discharge are  $Q_c$  and  $Q_d$ . The internal resistance of the battery is a resistance parameter  $r_{qc}$  or  $r_{qd}$  times the dimensionless term in the brackets in either Equation 8.10.1 or 8.10.2.

For lead-acid batteries there are some known values and approximate relationships between some of the parameters, thus reducing the number of needed parameters:

$$Q_c = -0.035 Q_m \quad (\text{Ah}) \quad (8.10.3a)$$

$$Q_d = \frac{Q_m}{0.85} \quad (\text{Ah}) \quad (8.10.3b)$$

$$r_{qd} = \frac{0.5}{Q_m} \quad (\Omega) \quad (8.10.3c)$$

$$r_{qc} = \frac{3.0}{Q_m} \quad (\Omega) \quad (8.10.3d)$$

$$g_c = g_d = 0.08 \quad (V) \quad (8.10.3e)$$

$$m_d = 1 \quad (8.10.3f)$$

$$m_c = 0.864 \quad (8.10.3g)$$

$$V_{oc} = 2.175 \quad (V) \quad (8.10.3h)$$

$$k_z = 29.3 \quad (8.10.3i)$$

$$I_z = 2.5 \quad (A) \quad (8.10.3j)$$

Substituting these relationships into Equations 8.10.1 (for charging) results in

$$V = 2.175 + \frac{1}{29.3} \ln \left( \frac{|I|}{2.5} + 1 \right) - 0.08H + I \frac{0.5}{Q_m} \left( 1 + \frac{H}{1.18 - H} \right) \quad (8.10.4)$$

and into Equation 8.10.2 (for discharging) results in

$$V = 2.175 - \frac{1}{29.3} \ln \left( \frac{|I|}{2.5} + 1 \right) - 0.08H + I \frac{3.0}{Q_m} \left( 1 - \frac{0.864H}{0.035 + H} \right) \quad (8.10.5)$$

Equations 8.10.4 and 8.10.5 (and also Equations 8.10.1 and 8.10.2) are for a single battery cell. For  $N_s$  cells in series and  $N_p$  cells in parallel the battery current and battery voltage are

$$V_{\text{batt}} = N_s V \quad (8.10.6)$$

and


$$I_{\text{batt}} = N_p I \quad (8.10.7)$$

The battery capacity at any time, given an initial capacity of  $Q_o$ , is found by integrating over time:

$$Q = Q_o + \int_{\text{time}} \eta I \, dt$$

The charging efficiency  $\eta$  takes into account the generation of gas and various other losses during charging. A value of the charging efficiency of 0.9 is reasonable. During discharging  $\eta = 1.0$ .

Figure 8.10.1 shows the current–voltage and state-of-charge characteristics of a typical 50-A-h lead-acid battery. The curves were generated with  $N_s = 6$  and  $N_p = 1$ . Also shown on the figure are voltage and current limits that are maintained to avoid damage to the battery and are set by the battery manufacturer. In practice this is done with a charge controller as the battery model is without limits. For this battery the maximum current is 11 A on both charge and discharge. The battery should not be charged above  $F = 1$  or discharged below  $F = 0.2$ . The limiting voltages are 12.3 and 14 V.



**Figure 8.10.1** Characteristics of a typical 50 A-h lead-acid battery.

### Example 8.10.1

Consider the 50-Ah nominal 12-V lead-acid battery shown in Figure 8.10.1. The battery has a charging efficiency of 0.95. The initial state of charge of the battery is 0.2. The battery is to be charged at a constant voltage of 16.6 V until the state of charge reaches 1.0. The maximum charging current is 11 A. The battery is to be discharged to a load of  $1\ \Omega$ . How long does it take to charge the battery? How long can this fully charged battery supply the resistive load before the state of charge reaches 0.2? Show a plot of state of charge versus time. How much energy was put into the battery and how much was removed? What is the battery efficiency for this one cycle?

### Solution

The solution is found in two parts, charging and discharging, using EES. An EES function was written to evaluate the voltage from either Equations 8.10.4 (for positive currents) or Equation 8.10.5 (for negative currents) given the cell current, state of charge  $F$ , and cell capacity. The EES code is shown below. In part 1 the charging is simulated by setting the variable Charging\$ to 'True' and in part 2 the discharging is simulated by setting the variable Charging\$ to 'False'. The power into the battery during charging and that removed from the battery during discharging are found by integrating the product of current and voltage over time.

```
Function V_cell_(I, F, Q_m)
H=1-F
If I < 0 then '!Discharge'
  V_cell_=2.175-ln(abs(I)/2.5+1)/29.3-0.08*H+(0.5*I/Q_m)*(1+H/(1/0.85-H))
else '!Charge'
  V_cell_=2.175+ln(abs(I)/2.5+1)/29.3-0.08*H+(3.0*I/Q_m)*(1+(0.864*H)/(-0.035-H))
EndIf
end V_cell_
```


```

Charging$='True'                                ``Must uncomment one of these two statements``
{Charging$='False'}
R_load=1 [ohm]
ChargeEfficiency=0.95
I_max=11 [amp]                                ``Limit current to 11 amps``
N_s=6
N_p=1
Q_m=50 [amp-hr]
Q_m_cell=Q_m/N_s
V_cell=V_cell_(I_cell, F, Q_m_cell)  ``Function for equations 8.10.1 and 8.10.2``
V_batt=N_s*V_cell
I_batt=min(I_cell*N_p, I_max)
eta=IF(I_batt, 0, 1, 1, ChargeEfficiency)  ``eta = 1 when discharging and
eta = 0.95 when charging``
F=Q/Q_m
Q=Q_o+integral(I_batt*eta, time,Time_initial, Time_final)
P=integral(I_batt*V_batt, time,Time_initial, Time_final)

$IF Charging$='True'
  Q_o=10 [Amp-hr]
  Time_initial=0 [hr]
  Time_final=6.75                                ``By trial and error it takes 6.75 hr to reach 100% charge``
  V_batt=16.6                                    ``Constant charging voltage``
$Else
  Q_o=50 [Amp-hr]
  Time_initial=6.75 [hr]
  Time_final=11.86 [hr]                        ``By trial and error the battery lasts 11.86 hr.``
  V_batt=-I_batt*R_load                        ``Resistance load``
$EndIF
$IntegralTable time: 0.5,Q,F,I_batt, V_batt

```

The state of charge versus time is shown in the graph. During charging the current starts at 9.7 A and decreases to 1.6 A when the battery is fully charged. During discharge the current decreases from 9.4 to 5.8 A; the current and voltage are numerically equal since the load is 1.0  $\Omega$ . The energy to charge the battery is 699 Wh and the energy recovered on discharge is 319 Wh, leading to battery efficiency for this cycle of 46%. A lower charging voltage and/or a larger resistive load will result in higher cycle efficiency. Of course the time to charge and discharge will then be longer.



The battery model has built-in internal resistances which contribute greatly to the low cycle efficiency of the previous example. The charging efficiency is only part of the battery losses.

The battery model presented here is only one of many possible models. The parameters presented here are for a typical lead-acid battery and may vary considerably for batteries from different manufacturers. When designing a system using this battery model the parameters should be obtained from tests on the actual battery being used.

## REFERENCES

- Bacon, F. T., in *Proceedings of the UN Conference on New Sources of Energy*, Vol. 1, p. 174, United Nations, NY (1964). "Energy Storage Based on Electrolyzers and Hydrogen-Oxygen Fuel Cells."
- Balcomb, J. D., J. C. Hedstrom, and R. D. McFarland, *Solar Energy*, **19**, 277 (1977). "Simulation Analysis of Passive Solar Heated Buildings—Preliminary Results."
- Bankston, C. A., in *Advances in Solar Energy*, Vol. 4 (K. W. Boer, ed.), p. 352, Plenum, New York (1988). "The Status and Potential of Central Solar Heating Plants with Seasonal Storage: An International Report."
- Bauerle, G., D. Chung, G. Ervin, J. Guon, and T. Springer, *Proc. ISES Meeting*, **8**, 192 (1976). "Storage of Solar Energy by Inorganic Oxide Hydrides."
- Belton, G. and F. Ajami, Report NSF/RANN/SE/G127979 TR/73/4 to the National Science Foundation by the University of Pennsylvania National Center for Energy Management and Power (1973). "Thermochemistry of Salt Hydrates."
- Bode, H., *Lead Acid Batteries*, Wiley, New York (1977).
- Braun, J., M.S. Thesis, University of Wisconsin-Madison (1980). "Seasonal Storage of Energy in Solar Heating."
- Brunstrom, C. and M. Larsson, in *Proceedings of the ASES Meeting*, American Solar Energy Society, Boulder, CO (1986). "The Lyckebo Rock Cavern Seasonal Storage Plant: Performance and Economy."
- Carlsson, B., H. Stymne, and G. Wettermark, Document D12:1978, Swedish Council for Building Research (1978). "Storage of Low-Temperature Heat in Salt-Hydrate Melts—Calcium Chloride Hexahydrate."
- Eckstein, J. H., M.S. Thesis in Mechanical Engineering, University of Wisconsin-Madison (1990). "Detailed Modeling of Photovoltaic System Components."
- Fender, D. A. and J. R. Dunn, Paper presented at the *ASME Winter Annual Meeting*, Paper 78-WA/Sol-11 (1978). "A Theoretical Analysis of Solar Collector/Storage Panels."
- Fujii, I., K. Tsuchiya, M. Higano, and J. Yamada, *Solar Energy*, **34**, 367 (1985). "Studies of an Energy Storage System by Use of the Reversible Chemical Reaction:  $\text{CaO} + \text{H}_2\text{O} \leftrightarrow \text{Ca}(\text{OH})_2$ ."
- Fujii, I., K. Tsuchiya, Y. Shikakura, and M. S. Murthy, *Trans. ASME J. Solar Energy Eng.*, **111**, 245 (1989). "Consideration on Thermal Decomposition of Calcium Hydroxide Pellets for Energy Storage."
- Gari, H. N. and R. I. Loehrke, *Trans. ASME J. Fluids Eng.*, **104**, 475 (1982). "A Controlled Bouyant Jet for Enhancing Stratification in a Liquid Storage Tank."
- Hodgins, J. W. and T. W. Hoffman, *Can. J. Technol.*, **33**, 293 (1955). "The Storage and Transfer of Low Potential Heat."
- Hughes, P. J., M.S. Thesis in Mechanical Engineering, University of Wisconsin-Madison (1975). "The Design and Predicted Performance of Arlington House."



- Hughes, P. J., S. A. Klein, and D. J. Close, *Trans. ASME J. Heat Transfer*, **98**, 336 (1976). "Packed Bed Thermal Storage Models for Solar Air Heating and Cooling Systems."
- Huxtable, D. D. and D. R. Poole, *Proc. ISES Meeting* Vol. **8**, p. 178, Winnipeg (1976). "Thermal Energy Storage by the Sulfuric Acid-Water System."
- Jeffreson, C. P., *Am. Inst. Chem. Eng. J.*, **18** (2), 409 (1972). "Prediction of Breakthrough Curves in Packed Beds."
- Johnson, T. E., *Solar Energy*, **19**, 669 (1977). "Lightweight Thermal Storage for Solar Heated Buildings."
- Jurinak, J. J. and S. I. Abdel-Khalik, paper presented at ISES Meeting, Atlanta (1979). "On the Performance of Solar Heating Systems Utilizing Phase Change Energy Storage."
- Karaki, S., P. R. Armstrong, and T. N. Bechtel, Report COO-2868-3 from Colorado State University to the U.S. Department of Energy (1977). "Evaluation of a Residential Solar Air Heating and Nocturnal Cooling System."
- Kauffman, K. and I. Gruntfest, Report NCEMP-20 of the University of Pennsylvania National Center for Energy Management and Power to the National Science Foundation (1973). "Congruently Melting Materials for Thermal Energy Storage."
- Kleinbach, E. M., W. A. Beckman, and S. A. Klein, *Solar Energy*, **50**, 155 (1993). "Performance Study of One-Dimensional Models for Stratified Thermal Storage Tanks."
- Kuhn, J. K., G. F. Von Fuchs, A. W. Warren, and A. P. Zob, Report of Boeing Computer Services Company to the U.S. Department of Energy (1980). "Developing and Upgrading of Solar System Thermal Energy Storage Simulation Models."
- Lavan, Z. and T. Thompson, *Solar Energy*, **19**, 519 (1977). "Experimental Study of Thermally Stratified Hot Water Storage Tanks."
- Marcus, R. J. and H. C. Wohlers, in *Proceedings of the UN Conference on New Sources of Energy*, Vol. **1**, p. 187, United Nations, NY (1961). "Chemical Conversion and Storage of Concentrated Solar Energy." See also *Solar Energy*, **4** (2), 1 (1960); **5**, 121 (1961a); **5**, 44 (1961b).
- Morrison, D. J. and S. I. Abdel-Khalik, *Solar Energy*, **20**, 57 (1978). "Effects of Phase-Change Energy Storage on the Performance of Air-Based and Liquid-Based Solar Heating Systems."
- Mumma, S. D. and W. C. Marvin, ASME paper 76-HT-73 (1976). "A Method of Simulating the Performance of a Pebble Bed Thermal Energy Storage and Recovery System."
- Murray, W. D. and F. Landis, *Trans. ASME J. Heat Transfer*, **81C**, 107 (1959). "Numerical and Machine Solutions of Transient Heat Conduction Problems Involving Melting or Freezing."
- Oberndorfer, G., W. A. Beckman, and S. A. Klein, *Proc. ASES Ann. Conf.*, **24**, 153 (1999). "Sensitivity of Annual Solar Fraction of Solar Space and Water Heating Systems to Tank and Collector Heat Exchanger Model Parameters."
- Offenhartz, P. O., *Proc. ISES Meeting*, **8**, 48 (1976). "Chemical Methods of Storing Thermal Energy."
- Ohanessian, P. and W. W. S. Charters, *Solar Energy*, **20**, 275 (1978). "Thermal Simulation of a Passive Solar House Using a Trombe-Michel Wall Structure."
- Schumann, T. E. W., *J. Franklin Inst.*, **208**, 405 (1929). "Heat Transfer: A Liquid Flowing through a Porous Prism."
- Shepard, C. M., *J. Electrochem. Soc.*, **112**, 657 (1965). "Design of Primary and Secondary Cells."
- Simmons, J. A., *Proc. ISES Meeting*, **8**, 219 (1976). "Reversible Oxidation of Metal Oxides for Thermal Energy Storage."
- Smith, R. N., T. E. Ebersole, and F. P. Griffin, *Trans. ASME J. Solar Energy Eng.*, **102**, 112 (1980). "Heat Exchanger Performance in Latent Heat Thermal Energy Storage."
- Telkes, M., *Solar Energy Research*, University of Wisconsin Press, Madison (1955). "Solar Heat Storage."

- TRNSYS, *A Transient Simulation Program, User's Manual*, Version 16, Solar Energy Laboratory, University of Wisconsin-Madison (2012). [The first published version was 7 (1976).]
- Trombe, F., J. F. Robert, M. Cabanot, and B. Sesolis, *Solar Age*, **2**, 13 (1977). "Concrete Walls to Collect and Hold Heat."
- Utzinger, D. M., M.S. Thesis, University of Wisconsin-Madison (1979). "Analysis of Building Components Related to Direct Solar Heating of Buildings."
- Van Koppen, C. W. J., J. P. S. Thomas, and W. B. Veltkamp, paper in *Sun II, Proc. ISES Biennial Meeting*, **2**, 576 (1979). "The Actual Benefits of Thermally Stratified Storage in Small and Medium Sized Solar Systems."

## Solar Process Loads

The supply of solar energy from a collector is time dependent. In general, loads to be met by an energy system are also time dependent. Energy storage, as outlined in the previous chapter, provides a buffer between these two time-dependent functions. In Chapters 6 and 7 we discussed calculation of collector output. In this chapter, we outline briefly the common methods for calculating some common loads and provide references which will provide much more detailed information.

The term *load*, as used here, refers to the time-dependent energy needs which are to be met by an energy system.<sup>1</sup> The system will generally be a combination of a solar system and another system, the auxiliary, or backup, system. We designate the total load as  $L$ , that part that is supplied by solar energy as  $L_S$ , and that by auxiliary as  $L_A$ . These loads will usually be integrated over some time period, such as an hour or a month. (Load rates in this chapter are identified by  $\dot{L}$ ,  $\dot{L}_S$ , or  $\dot{L}_A$ ; in later chapters where the distinction between rates and integrated loads is clear, the dot will not be used.) There may be times when all of the loads are met by solar energy and times when all are met by auxiliary energy.

The objective of solar process performance calculations can be (a) to determine the detailed hour-by-hour supply of solar and auxiliary energy to meet the loads and/or (b) how much of a long-term load (usually for a year) is met by solar energy and thus how much auxiliary energy must be purchased.

The hour-by-hour load patterns together with the solar process characteristics determine the dynamics of a system; the simulation methods outlined in Chapters 10 and 19 are hourly calculations that provide information on how much auxiliary energy must be supplied and when it must be supplied. The monthly loads that an energy system must meet contain no information on process dynamics. However, monthly loads are needed in the design procedures described in Part III, which provide estimates of annual solar energy and auxiliary energy.

In this chapter, we show some samples of time-dependent loads for several applications and outline methods for estimating monthly loads. This presentation is brief, and the reader is referred to sources such as ASHRAE publications and Mitchell (1983) for details.

---


<sup>1</sup>Loads in ASHRAE specifically refer to the rate of energy transfer. Here we use loads for both rates and integrated quantities. The meaning is always clear from the context.

## 9.1 EXAMPLES OF TIME-DEPENDENT LOADS


To determine solar process dynamics, load dynamics must be known. There are no general methods for predicting the time dependence of loads; detailed information on heat requirements (energy and temperature), hot-water requirements, cooling needs, and so on, must be available. Lacking data, it may be possible to assume typical standard load distributions. An illustration of each of these situations is noted.

The possibility of application of a combination of a solar energy system and a waste heat recovery system to supply industrial process heat to a meat-packing operation was considered by Arny (1982). The loads to be met were for hot water at 85°C for sanitary purposes during production operations and at 60 to 71°C during nonproduction hours. Water enters the plant at 12.8°C. The load profile (the variation of energy, temperature, and mass flow rate requirements with time, in this example for 2-h intervals) for a production day is shown in Figure 9.1.1. Other profiles apply to nonproduction days, that is, weekends and holidays. This profile is unique to the particular industrial operation studied; it is not possible to develop a general profile.

A commonly used domestic hot-water load pattern is shown in Figure 9.1.2 (Mutch, 1974). Hot-water use is concentrated in the morning and evening hours; to supply these



**Figure 9.1.1** Process hot-water sensible heat load  $L_w$ , delivery temperature  $T_d$ , and water mass flow rate  $\dot{m}$  (kg/s) as a function of time for 2-h intervals for a production day for a meat processing operation. Adapted from Arny (1982).



**Figure 9.1.2** A normalized profile of hourly hot-water use for a domestic application. Adapted from Mutch (1974).

loads, stored solar energy must be used. Minor changes in time dependence of loads do not have major effect on annual performance of solar domestic hot-water systems. However, variations such as those caused by closure of commercial buildings on weekends can have significant impact on design and performance.

If a solar process system is to meet only a small part of the total loads, that is, if the instantaneous solar energy delivered is always smaller than the instantaneous load, then the load distribution has no effect on system performance. Also, energy storage is not needed and, if provided, will not increase the net solar contribution to the load.

## 9.2 HOT-WATER LOADS

Very detailed models of daily domestic hot-water use have been proposed that include such variables as the number of occupants and their ages, the presence or absence of dishwashers and clothes washers, the size of storage tank, the season of the year, the ambient and delivery temperatures, and whether or not the occupants pay for the hot water (Lutz et al., 1996). It is well known that domestic hot-water use varies considerably day by day, hour by hour, and minute by minute. For use in simulations the average daily load needs to be distributed over days and hours (or even shorter time periods). One approach is to estimate the standard deviation of the daily load and create a day-to-day sequence that has the correct long-term average daily usage. The hourly fluctuations can then be assumed to follow a typical normalized profile such as shown in Figure 9.1.2. Jordan and Vajen [see Weiss (2003)] investigated draw profiles on 1-min, 6-min, and hourly time scales. They conclude that modeling systems on a 1-min time scale is best but for most systems hourly simulations provide adequate results. The maximum difference in predicted annual energy savings using long- and short-term water draws was 3.5%.

The loads to be met by water heating systems can be considered to include three parts. First, the sensible heat requirements of the water must be met. If water flowing at a rate of  $\dot{m}$  is to be heated from a supply temperature  $T_s$  to a delivery temperature  $T_d$ , the required rate of addition of sensible heat will be

$$\dot{L}_w = \dot{m} C_p (T_d - T_s) \quad (9.2.1)$$

Second, losses from the distribution system must be met. These can be estimated by conventional methods. If continuous recirculation is used (as in large buildings where “instant” hot water is required at locations far from the water heater), the losses from the piping may be of the same magnitude as the sensible heat requirements.

Third, losses from storage tanks may be significant. The rate of tank losses  $\dot{L}_t$  is estimated from the tank loss coefficient–area product  $(UA)_t$  and the temperature difference between the water in the tank and the ambient temperature surrounding the tank:

$$\dot{L}_t = (UA)_t (T_t - T'_a) \quad (9.2.2)$$

However, estimation of the loss coefficient based on the thickness and thermal conductivity of insulation will lead to underestimation of tank losses if significant effects of supports,

pipng, and other heat leaks are ignored. Measured values of tank loss coefficients are often two to four times those calculated from insulation thickness and conductivity.

In the case of water heaters located in heated buildings, losses from the hot-water tanks are uncontrolled heat gains for the building.

### 9.3 SPACE HEATING LOADS, DEGREE-DAYS, AND BALANCE TEMPERATURE

A detailed discussion of the calculation of heating loads is beyond the scope of this book, and for such a discussion the reader is referred to the ASHRAE *Handbook of Fundamentals* (2001), the ASHRAE *Cooling and Heating Load Calculation Manual* (1979), Mitchell (1983), or similar publications. Here we briefly outline the degree-day method. Other methods can be used at the discretion of the designer.

The degree-day method of estimating loads is based on the principle that the energy loss from a building is proportional to the difference in temperature between indoors and outdoors. If energy (from a source such as a furnace, space heater, or solar heating system) is added to a building at a rate  $\dot{L}$ , if the rate of heat generation in the building due to occupants, lights, appliances, incoming solar radiation, and so on, is  $\dot{g}$ , and if the rate of energy transfer from the building is proportional to the difference between the house temperature and the ambient temperature, then a steady-state energy balance on the house yields

$$\dot{L} + \dot{g} = (UA)_h (T_h - T_a) \quad (9.3.1)$$

There is an ambient temperature, called the balance point temperature  $T_b$  at which the internal energy generation offsets the losses:

$$\dot{g} = (UA)_h (T_h - T_b) \quad (9.3.2)$$

or

$$T_h = T_b + \frac{\dot{g}}{(UA)_h} \quad (9.3.3)$$

If Equation 9.3.3 is substituted into Equation 9.3.1, the instantaneous load on the building can be expressed in terms of the balance temperature as

$$\dot{L} = (UA)_h (T_b - T_a) \quad (9.3.4)$$

A month's heating load on a building is obtained by integrating Equation 9.3.4 over the month:

$$L = \int_{\text{mo}} (UA)_h (T_b - T_a)^+ dt \quad (9.3.5)$$

where the superscript + indicates that only positive values of  $T_b - T_a$  contribute to the heating load. If the integral is approximated by an hourly summation over the month and  $(UA)_h$  and  $T_b$  are assumed to be constant, then the monthly heating load is given by

$$L = (UA)_h DD \quad (9.3.6)$$

where DD is the number of degree-days. The number of degree-days in a day is approximated by the difference between the balance temperature  $T_b$  and the day's average

temperature  $T_{av}$ , defined by the U.S. Weather Service as  $(T_{max} + T_{min})/2$ , with only positive values of the difference considered.<sup>2</sup> A month's degree-days are the sum of the daily values:

$$DD = \sum_{mo} (T_b - T_{av})^+ \quad (9.3.7)$$

If  $(UA)_h$  is in watts per degree Celsius and  $DD$  is in °C-days, a factor of  $3600 \times 24$  must be used to obtain the monthly load in joules.

Although the balance temperature varies throughout the day, the traditional base (balance) temperature  $T_b = 18.3^\circ\text{C}$  ( $65^\circ\text{F}$ ), which was based on average room temperatures at  $24^\circ\text{C}$  and internal energy generation rates and construction practices typical of residences that were built prior to 1940 in the United States. Most data are available to this base (e.g., those in Appendix D). In recent years, buildings have been better insulated and are kept at lower temperatures and rates of internal energy generation are higher, all of which contribute to a lower base temperature. Thus, degree-day information is needed to other base temperatures. Tables of degree-days to several base temperatures are available (e.g., Balcomb et al., 1984; Butso and Hatch, 1979). A method for calculating degree-days to any base temperature from monthly average ambient temperature was developed by Thom (1954, 1966) and modified by Erbs et al. (1983).

The monthly average degree-days can be approximated by

$$DD = \sigma_m N^{3/2} \left[ \frac{h}{2} + \frac{\ln [\cosh (1.698h)]}{3.396} + 0.2041 \right] \quad (9.3.8)$$

where  $N$  is the number of days in the month and  $h$  is defined as

$$h = \frac{T_b - \bar{T}_a}{\sigma_m \sqrt{N}} \quad (9.3.9)$$

The standard deviation of the monthly average ambient temperature is  $\sigma_m$ , which is generally not available from weather summaries. It can be approximated by the following with essentially no loss in accuracy:

$$\sigma_m = 1.45 - 0.0290\bar{T}_a + 0.0664\sigma_{yr} \quad (9.3.10)$$

where  $\sigma_{yr}$  is the standard deviation of the monthly average ambient temperature from the annual average ambient temperature and  $\bar{T}_a$  is the monthly average temperature in degress Celsius.

When the base temperature is more than  $6^\circ\text{C}$  above the monthly average ambient temperature, the monthly degree-days can be found from the simple formula

$$DD = N(T_b - \bar{T}_a) \quad (9.3.11)$$

The degree-days tabulated in Appendix D are calculated using Equation 9.3.8.

---

<sup>2</sup>The use of  $T_{av}$  in the definition of degree-days instead of using the actual average temperature does not lead to significant errors.

**Example 9.3.1**

Calculate the 12 monthly heating degree-days to a base temperature of 18.3°C for Madison, Wisconsin, and compare them to the values listed in Appendix D.

**Solution**

For all of the winter months, October through April, the simple formula given by Equation 9.3.11 can be used. The calculations will be shown in detail for the month of September, which has an average ambient temperature of 15°C, using Equations 9.3.8 through 9.3.10. The annual average temperature for Madison is 7.9°C. The standard deviation of the monthly temperatures is found from

$$\sigma_{\text{yr}} = \sqrt{\frac{\sum_{i=1}^{12} (\bar{T}_{a,i} - 8.0)^2}{11}} = 10.60$$

Then  $\sigma_m$  is found from Equation 9.3.10 and is equal to 1.72, and  $h = 0.351$  from Equation 9.3.9. The September degree-days are found from Equation 9.3.8:

$$DD = 1.72 \times 30^{1.5} \left[ \frac{0.351}{2} + \frac{\ln [\cosh (1.698 \times 0.351)]}{3.396} + 0.2041 \right] = 121$$

which is within 17 degree-days of the measured value of 103. The measured and calculated degree-days for each month are given in the following table. The differences between the calculated and measured values in this example are due in part to the fact that  $\bar{T}_a$  is not known to better than  $\pm 0.5^\circ\text{C}$ .

Month	$\bar{T}_a$	Measured $DD$	Calculated $DD$
January	−8	821	815
February	−5	656	653
March	1	537	537
April	9	280	283
May	14	136	151
June	19	30	44
July	22	1	16
August	20	25	33
September	15	103	121
October	11	232	234
November	2	479	490
December	−5	699	723
Year	7.9	3999	4100

■

Some buildings (particularly passively heated buildings described in Chapter 14) may have insulation added at night. If night insulation is used, the building loss coefficient



varies with time, and the loads can be approximated by integrating Equation 9.3.5 in two parts, day and night.

Thermostat settings may also vary through the day, with the most common shift being night setback. Changing thermostat settings does not result in an immediate change in room temperature for real buildings that have finite thermal capacitance and heating systems with finite capacity. Typically a reduction in thermostat setting results in a slow reduction of room temperature to the new setpoint, and a rise in thermostat setting results in a faster rise back to the high setpoint brought about by heating systems which normally have excess capacity. An estimate of the upper limit of reduction of heating loads with night setback can be obtained by time-weighted degree-days to appropriate base temperatures. See Mitchell (1983) for a discussion of this problem.

For existing structures where fuel consumption records are available,  $(UA)_h$  may be calculated from

$$(UA)_h = \frac{N_F H_F \eta}{DD} \quad (9.3.12)$$

The numerator is the energy delivered from fuel to the building;  $N_F$  is the number of fuel units used,  $H_F$  is the appropriate heating value of the fuel, and  $\eta$  is the efficiency with which it is burned.

## 9.4 BUILDING LOSS COEFFICIENTS

For new or proposed structures there are standard methods of estimating building  $UA$ . The total heat loss is the sum of the losses through walls, windows, doors, floor, and roof plus infiltration loss. For details of these calculation methods, see Mitchell (1983), ASHRAE (1979), or other standard works on heating loads.

Loss coefficients of windows and walls are of particular importance in passive solar heating. As window areas (i.e., solar aperture) increase, replacing walls which have lower overall loss coefficients, total loads on the building rise. The increases can be modified by use of night insulation. Typical coefficients for several window and wall types are shown in Table 9.4.1.

Important advances have been made in transparent insulation, for example, by manipulating the spectral dependence of transmittance and emittance of glazings to achieve properties that are desirable for particular applications. Where reduction of building heating loads is the major concern, it is desirable to use glazings with low long-wave emittance to reduce outward heat losses through glazings. Products are now in use with  $\varepsilon$  reduced from the usual values of about 0.88 to as low as 0.10; the use of one or more such coatings on double-glazed windows (usually on the inner surfaces) can reduce the loss coefficient  $U$  to a half or less of its value without the coating. Windows are also constructed with low- $\varepsilon$  polymeric films between glazings; these provide additional reduction in convective transport and reduced radiation exchange. All of these coatings and films have reduced transmittance for the solar spectrum; for passively heated buildings in which the solar gain is a direct function of window transmittance, the use of these low-loss glazing systems will depend on the balance between reduced solar gains and reduced losses.

**Table 9.4.1** Overall Loss Coefficients  $U$  for Walls and Windows with and without Movable Insulation

Wall/Window Type	$U$ , $W/m^2 \text{ } ^\circ C$
Wall	
Stud wall, 14 cm fiberglass insulation between studs, plaster board interior, 2.5-cm- (1-in.-) thick foam insulating board.	0.45
Masonry wall, 19-cm-thick concrete blocks with insulation in voids	1.70
Window	
Single glazed, no insulation	6.0
Double glazed, 12-mm gap, no insulation	3.2
Double glazed with low-emittance coating on one interior surface, no insulation	2.1
Single glazed, with tight-fitting shade or drape	2.6
Double glazed, with tight-fitting shade or drape	1.2
Double glazed with 20 mm of foam insulation, tight fitting, with air gap between glazing and foam	0.9
Double glazed, with foam insulation as above but 100 mm thick	0.3

Transparent insulation can be applied to the outside of opaque building walls, making the walls into passive collectors.<sup>3</sup> The application reduces losses and at times results in net gains into the building. For these applications, consideration has been given to multiple parallel covers, honeycombs, layers of transparent beads, or aerogels. Properties and applications are discussed in proceedings of a series of international workshops on Transparent Insulation Technology (1988, 1989).

Where cooling loads are the major concern, control of solar heat gains can be accomplished by controlling spectral dependence of transmittance for the solar spectrum. Coated glass is available which transmits much of the visible part of the spectrum but not the infrared part. These coated glasses also have low emittances to reduce heat transfer between building interior and ambient. The *ASHRAE Handbook of Fundamentals* (2001) is a useful source of information on heat loss coefficients and transmittances of various glazing.

The  $UA$  of a building is the sum of the products of the areas and  $U$  values for all of the areas of the building envelope.

It is also necessary, for satisfactory estimation of heating loads, to include effects of infiltration of outside air into the building. In old residential buildings there are typically one to three air changes per hour due to infiltration; modern buildings have 0.3 to 0.6 changes per hour; very tight buildings may have infiltration rates of 0.1 change per hour. The sensible heat to bring ambient air up to room temperature (plus that to heat any ventilation air) must be added to the losses through the building envelope in estimating the total heating loads.

Measurements of heating loads for buildings of supposedly identical construction show wide variations (often by factors of 2 or 3) in measured energy use. This may be

<sup>3</sup>Section 14.6 discusses collector-storage walls for passive heating.

due to differences in the care with which insulation and vapor barriers are installed, to differences in the ways in which the occupants use the buildings, or to both.

## 9.5 BUILDING ENERGY STORAGE CAPACITY

Building thermal capacitance is the effective heat capacity of a structure per unit change of interior temperature. It is important in a building that undergoes significant temperature changes (additional thermal storage that may be provided in media such as water tanks or pebble beds). Building thermal capacitance is of particular significance in passive heating or in hybrid systems where storage is provided by the building itself.

A procedure for calculating the effective thermal capacitance is to sum the products of mass, heat capacity, and temperature changes of all of the elements of a building<sup>4</sup>:

$$C = \sum_{\text{all } i} (mC_p)_i \Delta T'_i \quad (9.5.1)$$

where  $\Delta T'_i$  is the expected change in temperature of the  $i$ th element per degree of change of interior temperature. This is difficult to calculate exactly as the temperature gradients in walls, floors, furniture, and so on depend on the rates of heat transfer into and out of those elements. However, tables of effective thermal capacity have been worked out for typical building constructions. Table 9.5.1 shows recommended values of Barakat and Sander (1982).

## 9.6 COOLING LOADS

Air conditioning loads arise from energy that flows into a building through its envelope, solar gains through windows, infiltration, and ventilation which brings in outside air that needs to be cooled and/or dried plus heat and moisture that are generated within the building. Building thermal capacitance is often more important in summer cooling than in

**Table 9.5.1** Effective Building Thermal Capacity for Typical Construction per Unit Floor Area<sup>a</sup>

Description	Thermal Capacity (MJ/m <sup>2</sup> °K)
Light: standard frame construction, 13-mm Gyproc walls and ceilings, carpet over wooden floor	0.060
Medium: as above, but 51-mm Gyproc walls and 25-mm Gyproc ceiling	0.153
Heavy: interior wall finish of 102-mm brick, 13-mm, Gyproc ceiling, carpet over wooden floor	0.415
Very heavy: commercial office building with 305-mm concrete floor	0.810

<sup>a</sup>From Barakat and Sander (1982).

<sup>4</sup>This procedure is analogous to that for calculating the effective thermal capacitance of collectors, as shown in Section 6.12.

winter heating, as summer ambient temperatures may fluctuate around room temperature with resulting heat flow into and out of the structure. Building capacitance attenuates the peak loads and may substantially reduce cooling loads over time if ambient temperatures drop below room temperature.

Cooling degree-days have been used to calculate cooling loads in a manner similar to the technique described in Section 9.3 for heating loads. The procedure is generally less reliable. Erbs et al. (1983) also show how to estimate cooling degree-days from knowledge of the average ambient temperature in a manner similar to that described in Section 9.3 for heating degree-days.

If energy storage tanks (for water heating and/or for solar space heating) are located inside the spaces to be cooled, losses from the tanks will add to the cooling loads.

See Mitchell (1983) and ASHRAE (1979, 2001) for details of calculation of cooling loads on an hourly or monthly basis.

## 9.7 SWIMMING POOL HEATING LOADS

Swimming pools have been economically heated by solar energy for many years. The heat loss from outdoor, in-ground pools is by radiation to the sky and both convection and evaporation to the air. Many studies have shown that conduction losses into the ground are minor losses.

In some pool systems the heat losses are made up from a solar collector system, possibly uncovered. In others, the heat losses are reduced by placing a plastic cover on the pool surface whenever it is not being used. The cover lets solar radiation pass into the pool and greatly reduces evaporation losses. Some pool covers are made of ‘bubble’ plastic sheet, similar to the common packing material, to act as an insulator and reduce convection losses as well as evaporation losses. Some pool systems use both collectors and covers. If plastic collectors or covers are used, they must be made of ultraviolet stabilized materials or they may last only a few months.

To properly size an active collector system for a pool or to estimate the temperature rise that will result from a pool cover, it is necessary to estimate the pool heat losses. The best way to estimate the monthly heat loss from a pool is to use measured fuel data from the pool if they already exist or use data from a nearby similar pool. Often these data are not available and it is necessary to estimate the losses by calculations. These calculations are very uncertain since the wind conditions in the vicinity of the pool are seldom known with any degree of certainty.

To be useful, pools operate in a narrow temperature range, typically between 24 and 32°C. Since the pool has a large mass, its temperature does not change quickly. In fact, monthly energy balances are sufficient to estimate either the pool temperature in the absence of auxiliary energy or the auxiliary energy necessary to maintain a desired temperature.

The radiation heat loss from an outdoor pool is to the sky. Equation 3.9.2 provides estimates of the clear-sky temperature for hourly periods. For a whole month, the cosine term in the equation can be neglected and the monthly average dew point temperature can be used to estimate the clear-sky temperature. For dew point temperatures of 10, 20, and 30°C, the ratio is  $\bar{T}_s/\bar{T}_a$  is 0.938, 0.961, and 0.986, respectively. The sky is not always clear. The monthly average sky temperature can be estimated as a weighted average of the

air and clear-sky temperature. Wei et al. (1979) propose that cloud cover be used as the weighting factor. In the absence of cloud cover data,  $\overline{K}_T$  may be a reasonable alternative. Wei et al. measured the outgoing radiation from covered (with clear plastic) and uncovered pools and concluded that the pool surface acts like a blackbody for radiation losses, even with bubble-type covers, at the pool temperature. Thus, Equation 3.9.1 can be used with a pool emittance of 1.0 to estimate the radiation heat loss.

Wei et al. also propose the following dimensional equations for evaporation heat loss from an uncovered pool and for convection losses from covered or uncovered pools in watts per square meter:

$$q_e = P_a[35V + 43(T_p - T_a)^{1/3}](\omega_p - \omega_a) \quad (9.7.1)$$

where  $V$  is the wind speed in meters per second in the vicinity of the pool,  $P_a$  is the ambient air pressure in kilopascals,  $\omega_p$  is the saturation humidity ratio at the temperature of the pool, and  $\omega_a$  is the humidity ratio of the ambient air above the pool. Convection losses are expressed in terms of the evaporation losses as

$$q_c = q_e \times 0.0006 \frac{T_p - T_a}{\omega_p - \omega_a} \quad (9.7.2)$$

The wind speed  $V$  is almost always unknown in the vicinity of the pool. Wei et al. (1979) suggest that one-fifth to one-tenth of the measured wind speed at the local weather station be used to account for the usual shelter around a pool.

All of the solar radiation incident on a pool is not absorbed. For an uncovered pool with an average depth of 2 m, Francey and Golding (1981) estimate that the pool surface transmittance is about 92% and the pool absorptance is on the order of 60%. However, Wei et al. (1979) estimate that the pool absorptance is on the order of 90%. When covers are present, additional reflection losses occur, reducing the transmittance to 70 to 80%. In light of the uncertainties associated with the heat loss mechanisms, further refinement of these optical properties is not warranted.

### Example 9.7.1

A 72-m<sup>2</sup> pool is located in Atlanta, Georgia. Estimate the energy required to maintain the pool at 25°C in April. The pool has a cover installed for 12 h each night.

#### Solution

From Appendix D, the monthly average ambient temperature and horizontal radiation in April are 16°C (289 K) and 19.1 MJ/m<sup>2</sup> ( $\overline{K}_T = 0.53$ ). For the uncovered pool, the absorbed solar radiation is the pool area times the incident solar radiation times the surface transmittance times the pool absorptance times the number of days in April. Here we use the lower estimate of pool absorptance of 0.6:

$$Q_s = 72 \times 19.1 \times 10^6 \times 0.92 \times 0.6 \times 30 = 23 \text{ GJ}$$

If the monthly average relative humidity is 70%, then from a psychrometric chart, the monthly average dew point and wet bulb temperatures are 10 and 12°C. Also, the monthly average humidity ratio is 0.008 and the saturation humidity ratio for the 25°C pool is 0.020.

The clear-sky temperature, from Equation 3.9.2, neglecting the cosine term, is  $0.938T_a$ , or 271 K. Since cloud cover data are not available, the monthly average sky temperature is estimated to be  $(1 - 0.53) \times 271 + 0.53 \times 289 = 281$  K. The calculations will begin assuming the pool is uncovered at all times.

The radiation heat losses are found from Equation 3.9.1:

$$Q_r = 72 \times 5.67 \times 10^{-8} (298^4 - 281^4) \times 2.59 \times 10^6 = 18 \text{ GJ}$$

where  $2.59 \times 10^6$  is the number of seconds in April. Evaporation losses are found from Equation 9.7.1:

$$\begin{aligned} Q_e &= 72 \times 101.3[35 \times 3 + 43(298 - 289)^{1/3}](0.020 - 0.008) \times 2.59 \times 10^6 \\ &= 45 \text{ GJ} \end{aligned}$$

The convection losses are found from Equation 9.7.2:

$$Q_c = 45 \times 0.006 \left( \frac{298 - 289}{0.020 - 0.008} \right) = 21 \text{ GJ}$$

If the pool is uncovered for the whole month, the monthly load is

$$L = 18 + 46 + 21 - 23 = 62 \text{ GJ}$$

If the pool is covered one-half of the time with a film cover, only the evaporation losses will be affected and the monthly load is

$$L = 18 + 0.5 \times 46 + 21 - 23 = 39 \text{ GJ}$$

If the cover is of the bubble type, the evaporation losses will be eliminated and convection losses will be reasonably small. Then the load is

$$L = 18 + 0.5 \times (46 + 21) - 23 = 29 \text{ GJ} \quad \blacksquare$$

## REFERENCES

- Arny, M. D., M.S. Thesis, University of Wisconsin-Madison (1982). "Thermal Analysis for the Design of an Industrial Process Water Heating System Utilizing Waste Heat Recovery and Solar Energy."
- ASHRAE *Cooling and Heating Load Calculation Manual*, GRP 158, American Society of Heating, Refrigerating and Air-Conditioning Engineers, New York. (1979).
- ASHRAE *Handbook of Fundamentals*, American Society of Heating, Refrigerating and Air-Conditioning Engineers, Atlanta, GA (2001).
- Balcomb, J. D., R. W. Jones, R. D. McFarland, and W. O. Wray, *Passive Solar Heating Analysis—A Design Manual*, ASHRAE, Atlanta, GA (1984).
- Barakat, S. A. and D. M. Sander, Building Research Note No. 184, Division of Building Research, National Research Council of Canada (1982).
- Butso, K. D. and W. L. Hatch, Document 4.11, U.S. Department of Commerce (1979). "Selective Guide to Climatic Data Sources."
- Erbs, D. G., S. A. Klein, and W. A. Beckman, *ASHRAE J.*, p. 60 (June 1983). "Estimation of Degree-Days and Ambient Temperature Bin Data from Monthly Average Temperatures."

- Francey, J. L. and P. Golding, *Solar Energy*, **26**, 259 (1981). “The Optical Characteristics of Swimming Pool Covers Used for Direct Solar Heating.”
- Lutz, D. J., X. Liu, J. E. McMahon, C. Dunham, L. J. Shown, and Q. T. McGrue, Lawrence Berkeley National Laboratory Report LBL-37805 UC-1600 (Nov. 1996). “Modeling Patterns of Hot Water Use in Households.”
- Mitchell, J. W., *Energy Engineering*, Wiley, New York (1983).
- Mutch, J. J., RAND Report R 1498 (1974). “Residential Water Heating, Fuel Consumption, Economics and Public Policy.”
- Thom, H. C. S., *Monthly Weather Rev.*, **82**, 5 (1954). “Normal Degree-Days below Any Base.”
- Thom, H. C. S., *Monthly Weather Rev.*, **94**, 7 (1966). “Normal Degree Days above Any Base by the Universal Truncation Coefficient.”
- Transparent Insulation Technology for Solar Energy Conversion, Proceedings of the Third International Workshop* (1989), and *The Second International Workshop on Transparent Insulation in Solar Energy Conversion for Buildings and Other Applications* (1988), available from The Franklin Co., Birmingham, United Kingdom.
- Wei, J., H. Sigworth, Jr., C. Lederer, and A. H. Rosenfeld, Lawrence Berkeley Laboratory Report 9388 (July 1979). “A Computer Program for Evaluating Swimming Pool Heat Conservation.”
- Weiss, W. (ed.), *Solar Heating Systems for Houses*, James & James, London (2003).

# System Thermal Calculations

In Chapters 6 through 9 we have developed mathematical models for two of the key components in solar energy systems: collectors and storage units. In this chapter we show how other components can be modeled and how the component models can be combined into system models. With information on the magnitude and time distribution of the system loads and the weather, it is possible to simultaneously solve the set of equations to estimate the thermal performance of a solar process over any time period. These estimates (simulations) are usually done numerically and provide information on the expected dynamic behavior of the system and long-term integrated performance.

The collector performance is a function of the temperature of the fluid entering the collector. This temperature, neglecting (for the moment) heat losses from the connecting pipes, is the same as the temperature in the exit portion of the storage unit. The outlet temperature from the collector becomes the inlet temperature to the storage unit. In these equations, time is the independent variable and the solution is in the form of temperature as a function of time. Meteorological data (radiation, temperature, and possibly other variables such as wind speed and humidity) are forcing functions that are applied hourly (or at other time steps) to obtain numerical solutions through time.

Once the temperatures are known, energy rates can be determined. It is then possible to integrate the energy quantities over time to develop information such as that in Figure 8.1.1(c) and thus assess the annual thermal performance of a system. This *simulation* approach can be used to estimate, for any process application, the amount of energy delivered from the solar collector to meet a load and the amount of auxiliary energy required. The simulation also can indicate whether the temperature variations for a particular system design are reasonable, for example, whether a collector temperature would rise above the boiling point of the liquid being heated.

In this chapter we provide a brief review of collector and storage models and then show how models of controls, heat exchangers, and pipe and duct losses in collector circuits can be formulated. Methods are given for calculating the effects of partial shading of collectors and the output of collector arrays where sections of the arrays are at different orientations. The need for meteorological data and information on the energy loads a system is to supply is noted. In brief, this chapter treats system models (the combination of individual component models) and their solution.

## 10.1 COMPONENT MODELS

Chapters 6, 7, and 8 presented developments of collector and storage models, performance, measurements, and data. For flat-plate collectors, Equation 6.7.6 is appropriate, and for



focusing collectors, Equation 7.3.12 or its equivalent can be used. The rate of useful gain from a flat-plate collector can be written as

$$Q_u = A_c F_R [S - U_L (T_i - T_a)]^+ \quad (10.1.1)$$

where the  $+$  sign implies the presence of a controller and that only positive values of the term in the brackets should be used. Operation of a forced-circulation collector will not be carried out when  $Q_u < 0$  (or when  $Q_u < Q_{\min}$ , where  $Q_{\min}$  is a minimum level of energy gain to justify pumping the fluid through the system). In real systems, this is accomplished by comparing the temperature of the fluid leaving the collector (i.e., in the top header) with the temperature of the fluid in the exit portion of the storage tank and running the pump only when the difference in temperatures is positive and energy can be collected.

The rate of useful gain is also given by

$$Q_u = \dot{m} C_p (T_o - T_i) \quad (10.1.2)$$

where  $\dot{m}$  is the output of the pump circulating fluid through the collector.

If the storage unit is a fully mixed sensible heat unit, its performance is given by Equation 8.3.2,

$$(mC_p)_s \frac{dT_s}{dt} = Q_u - L_s - (UA)_s (T_s - T'_a) \quad (10.1.3)$$

The equivalent equations for stratified water tank storage systems, pebble bed exchangers, or heat-of-fusion systems are used in lieu of Equation 10.1.3, as appropriate. These equations are the basic equations to be solved in the analysis of systems such as a simple solar water heater with collector, pump, and controller and storage tank. The rate of energy removal to meet all or part of a load is  $L_s$  and is time dependent;  $Q_u$  and  $T'_a$  are also time dependent.

The performance models discussed so far have been based on the fundamental equations describing the behavior of the equipment. Models may also be expressed as empirical or stochastic representations of operating data from particular items of equipment. An example is the model<sup>1</sup> of a LiBr-H<sub>2</sub>O absorption cooler, which relates cooling capacity to temperatures of the fluid streams entering the machine. These empirical relations may be in the form of equations, graphs, or tabular data. In whatever form the models are expressed, they must represent component performance over the range of operating conditions to be encountered in the solar operation.

There is very often a **collector heat exchanger** between the collector and the storage tank when antifreeze is used in collectors. If piping or ducting to and from a collector is not well insulated, the losses from the piping or ducting may have to be taken into account. Each of these can be accounted for by modifications of Equation 10.1.1, as noted in the following sections.

---

<sup>1</sup>See Chapter 15.

## 10.2 COLLECTOR HEAT EXCHANGER FACTOR

Collectors are often used in combination with a heat exchanger between collector and storage allowing the use of antifreeze solutions in the collector loop. A common circuit of this type is shown in Figure 10.2.1.

A useful analytical combination of the equations for the collector and the heat exchanger has been derived by deWinter (1975). In this development the collector equation and the heat exchanger equation are combined into a single expression that has the same form as the collector equation alone. The combination of a collector and a heat exchanger performs exactly like a collector alone but with a reduced value of  $F_R$ . The useful gain of the collector is represented by Equations 10.1.1 and 10.1.2 written in terms of  $T_{ci}$  and  $T_{co}$ . The heat exchanger performance is expressed in terms of effectiveness (Kays and London, 1964) by Equation 3.17.6:

$$Q_{HX} = \varepsilon(\dot{m}C_p)_{\min}(T_{co} - T_i) \quad (10.2.1)$$

where  $(\dot{m}C_p)_{\min}$  is the smaller of the fluid capacitance rates (flow rate  $\dot{m}$  times fluid heat capacity  $C_p$ ) on the collector side  $(\dot{m}C_p)_c$  and tank side  $(\dot{m}C_p)_t$  of the heat exchanger,  $T_{co}$  is the outlet fluid temperature from the collector, and  $T_i$  is the inlet water temperature to the heat exchanger (very nearly the temperature in the bottom of the tank). For a counterflow heat exchanger, a common configuration, the effectiveness  $\varepsilon$  is given by Equation 3.17.7.


Combining Equations 10.1.1, 10.1.2, and 10.2.1,

$$Q_u = A_c F'_R [S - U_L(T_i - T_a)]^+ \quad (10.2.2)$$


where the modified collector heat removal factor  $F'_R$  accounts for the presence of the heat exchanger and is given by

$$\frac{F'_R}{F_R} = \left[ 1 + \left( \frac{A_c F_R U_L}{(\dot{m}C_p)_c} \right) \left( \frac{(\dot{m}C_p)_c}{\varepsilon(\dot{m}C_p)_{\min}} - 1 \right) \right]^{-1} \quad (10.2.3)$$

The factor  $F'_R/F_R$  is an indication of the penalty in collector performance incurred because the heat exchanger causes the collector to operate at higher temperatures than it otherwise



**Figure 10.2.1** Schematic of liquid system with a collector heat exchanger between collector and tank.



**Figure 10.2.2** Collector heat exchanger correction factor as a function of  $\varepsilon(\dot{m}C_p)_{\min}/(\dot{m}C_p)_c$  and  $(\dot{m}C_p)_c/F_R U_L A_c$ . Adapted from Beckman et al. (1977).

would. Another way of looking at the penalty is to consider the ratio  $F_R/F'_R$  as the fractional increase in collector area required for the system with the heat exchanger to give the same energy output as without the heat exchanger. Equation 10.2.2 now represents the performance of a subsystem including the collector and the heat exchanger (and, implicitly, the controller and pumps) and is of the same form as that for the collector only. The ratio  $F'_R/F_R$  can be calculated from Equation 10.2.3. It can also be determined from Figure 10.2.2, which shows  $F'_R/F_R$  as a function of  $\varepsilon(\dot{m}C_p)_{\min}/(\dot{m}C_p)_c$  and  $(\dot{m}C_p)_c/A_c F_R U_L$ .

### Example 10.2.1

A collector to be used in a solar heating system such as that of Figure 10.2.1 heats antifreeze; heat is transferred to water through a collector heat exchanger. The collector  $F_R U_L = 3.75 \text{ W/m}^2 \text{ }^\circ\text{C}$ . Flow rates through both sides of the heat exchanger are  $0.0139 \text{ kg/s}$  per square meter of collector. The fluid on the collector side is a glycol solution having  $C_p = 3350 \text{ J/kg } ^\circ\text{C}$ . The effectiveness of the heat exchanger is  $0.7$ . What is  $F'_R/F_R$ ?

### Solution

The capacitance rate per unit area on the water side of the exchanger is  $0.0139 \times 4190 = 58.2 \text{ W/m}^2 \text{ }^\circ\text{C}$ . On the glycol side it is  $0.0139 \times 3350 = 46.6 \text{ W/m}^2 \text{ }^\circ\text{C}$ . Thus the minimum  $(\dot{m}C_p)$  product is that of the glycol,  $\varepsilon(\dot{m}C_p)_{\min}/(\dot{m}C_p)_c = \varepsilon = 0.7$ , and

$$\frac{(\dot{m}C_p)_c}{A_c F_R U_L} = \frac{0.0139 \times 3350}{3.75} = 12.4$$

From Figure 10.2.2 or Equation 10.2.3,  $F'_R/F_R = 0.97$ . ■

### 10.3 DUCT AND PIPE LOSS FACTORS

The energy lost from ducts and pipes leading to and returning from the collector in a solar energy system can be significant. Beckman (1978) has shown that the combination of pipes or ducts plus the solar collector is equivalent in thermal performance to a solar collector with different values of  $U_L$  and  $(\tau\alpha)$ . (For simplicity in terminology, the term *duct* will be used, but the same analysis holds for pipes. Losses from ducts are more likely to be a problem than those from pipes.)


Consider the fluid temperature distribution shown in Figure 10.3.1. Fluid enters the portion of the duct from which losses occur<sup>2</sup> at temperature  $T_i$ . Due to heat losses to the ambient at temperature  $T_a$ , the fluid is reduced in temperature by an amount  $\Delta T_i$  before it enters the solar collector. The fluid passes through the collector and is heated to the collector outlet temperature. This temperature is then reduced to  $T_o$  as the fluid loses heat to the ambient while passing through the outlet ducts.

From energy balance considerations the useful energy gain of this collector-duct combination is equal to

$$Q_u = (\dot{m}C_p)_c (T_o - T_i) \quad (10.3.1)$$

This energy gain can also be related to the energy gain of the collector minus the duct losses by the following rate equation:

$$Q_u = A_c F_R [G_T (\tau\alpha) - U_L (T_i - \Delta T_i - T_a)] - \text{losses} \quad (10.3.2)$$



**Figure 10.3.1** Temperature distribution through a duct-collector system. From Beckman (1978).

<sup>2</sup>In a house heating system, duct and pipe losses inside the heated space are not net losses but are uncontrolled gains. These gains may not be desirable during warm weather.

The duct losses are equal to the integrated losses over the inlet and outlet ducts and are given by

$$\text{Losses} = U_d \int (T - T_a) dA \quad (10.3.3)$$

where  $U_d$  is the loss coefficient from the duct. It is possible to integrate Equation 10.3.3, but in any well-designed system the losses from ducts must be small and the integral can be approximated to an adequate degree of accuracy in terms of the inlet and outlet temperatures:

$$\text{Losses} = U_d A_i (T_i - T_a) + U_d A_o (T_o - T_a) \quad (10.3.4)$$

where  $A_i$  and  $A_o$  are the areas for heat loss of the inlet and outlet ducts. Upon rearranging Equations 10.3.1 and 10.3.4, the losses can be expressed in terms of the useful energy gain and the inlet fluid temperature as

$$\text{Losses} = U_d (A_i + A_o) (T_i - T_a) + \frac{U_d A_o Q_u}{(\dot{m} C_p)_c} \quad (10.3.5)$$

The decrease in temperature,  $\Delta T_i$ , due to heat losses on the inlet side of the collector can be approximated by

$$\Delta T_i = \frac{U_d A_i (T_i - T_a)}{(\dot{m} C_p)_c} \quad (10.3.6)$$

Substituting Equations 10.3.5 and 10.3.6 into 10.3.2 and rearranging, the useful energy gain of the collector and duct system can be expressed as

$$Q_u = \frac{A_c F_R \left[ G_T (\tau \alpha) - U_L \left( 1 - \frac{U_d A_i}{(\dot{m} C_p)_c} + \frac{U_d (A_i + A_o)}{A_c F_R U_L} \right) (T_i - T_a) \right]}{1 + \frac{U_d A_o}{(\dot{m} C_p)_c}} \quad (10.3.7)$$

Equation 10.3.7 can be made to look like the usual collector equation by defining modified values of  $(\tau \alpha)$  and  $U_L$  so that

$$Q_u = A_c F_R [G_T (\tau \alpha)' - U_L' (T_i - T_a)] \quad (10.3.8)$$

where

$$\frac{(\tau \alpha)'}{(\tau \alpha)} = \frac{1}{1 + \frac{U_d A_o}{(\dot{m} C_p)_c}} \quad (10.3.9)$$

and

$$\frac{U_L'}{U_L} = \frac{1 - \frac{U_d A_i}{(\dot{m} C_p)_c} + \frac{U_d (A_i + A_o)}{A_c F_R U_L}}{1 + \frac{U_d A_o}{(\dot{m} C_p)_c}} \quad (10.3.10)$$

**Example 10.3.1**

Compare the performance equations of an air collector system with ducts insulated and not insulated. The collector has an area of  $50 \text{ m}^2$ ,  $F_R U_L = 3.0 \text{ W/m}^2\text{C}$ , and  $F_R(\tau\alpha) = 0.60$ . The mass flow rate–specific heat product of the air through the collector is  $500 \text{ W/}^\circ\text{C}$ . The area of the inlet duct is  $10 \text{ m}^2$ , as is the area of the outlet duct. Insulation 33 mm thick is available with a conductivity of  $0.033 \text{ W/m } ^\circ\text{C}$ . The heat transfer coefficient outside the duct is  $10 \text{ W/m}^2\text{ }^\circ\text{C}$ , and the coefficient inside the duct is assumed to be large, leading to a loss coefficient  $U_d$  for the insulated duct of  $1.0 \text{ W/m}^2\text{ }^\circ\text{C}$  and for the uninsulated duct of  $10 \text{ W/m}^2\text{ }^\circ\text{C}$ .

**Solution**

For the insulated duct, the modified transmittance-absorptance product is found using Equation 10.3.9:

$$\frac{(\tau\alpha)'}{(\tau\alpha)} = \frac{1}{1 + \frac{1.0 \times 10}{500}} = 0.98$$

and

$$F_R(\tau\alpha)' = 0.60 \times 0.98 = 0.59$$

The modified loss coefficient is obtained with Equation 10.3.10:

$$\frac{U'_L}{U_L} = \frac{1 - \frac{1 \times 10}{500} + \frac{1.0(10 + 10)}{50 \times 3.0}}{1 + \frac{1 \times 10}{500}} = 1.09$$

and

$$F_R U'_L = 3.27 \text{ W/m}^2\text{ }^\circ\text{C}$$

For the system with insulated ducts the collector performance equation becomes

$$Q_u = 50[0.59G_T - 3.27(T_i - T_a)]$$

If the ducts are not insulated,  $U_d = 10 \text{ W/m}^2\text{ }^\circ\text{C}$ ,  $F_R(\tau\alpha)' = 0.50$ , and  $F_R U'_L = 5.3 \text{ W/m}^2\text{ }^\circ\text{C}$ . The performance equation is then

$$Q_u = 50[0.50G_T - 5.3(T_i - T_a)]$$

The addition of insulation has a very substantial effect on the useful gain to be expected from the system. ■

In a liquid system where both pipe losses and a heat exchanger are present and the heat exchanger is near the tank, the collector characteristics should first be modified to account for pipe losses and these modified collector characteristics used in Equation 10.2.3 to account for the heat exchanger.

Close and Yusoff (1978) have developed an analysis of the effects of leakage of air into air heating collectors. Their results can also be expressed in terms of modified collector characteristics.

## 10.4 CONTROLS

Two types of control schemes are commonly used on solar collectors on building-scale applications: on-off and proportional. With an on-off controller, a decision is made to turn the circulating pumps on or off depending on whether or not useful output is available from the collectors. With a proportional controller, the pump speed is varied in an attempt to maintain a specified temperature level at the collector outlet. Both strategies have advantages and disadvantages, largely depending on the ultimate use of the collected energy.

The most common control scheme requires two temperature sensors, one in the bottom of the storage unit and one on the absorber plate at the exit of a collector (or on the pipe near the plate). Assume the collector has low heat capacity. When fluid is flowing, the collector transducer senses the exit fluid temperature. When the fluid is not flowing, the mean plate temperature  $T_p$  is measured. A controller receives this temperature and the temperature at the bottom of the storage unit. This storage temperature will be called  $T_i$ ; when the pump turns on, the temperature at the bottom of storage will equal the inlet fluid temperature if the connecting pipes are lossless. Whenever the plate temperature at no-flow conditions exceeds  $T_i$  by a specific amount  $\Delta T_{\text{on}}$ , the pump is turned on.

When the pump is on and the measured temperature difference falls below a specified amount  $\Delta T_{\text{off}}$ , the controller turns the pump off. Care must be exercised when choosing both  $\Delta T_{\text{on}}$  and  $\Delta T_{\text{off}}$  to avoid having the pump cycle on and off.

When the collector pump is off, the useful output is zero and the absorber plate reaches an equilibrium temperature given by

$$[S - U_L(T_p - T_a)] = 0 \quad (10.4.1)$$

The value of  $S$  when  $T_p = T_i + \Delta T_{\text{on}}$  is

$$S_{\text{on}} = U_L(T_i + \Delta T_{\text{on}} - T_a) \quad (10.4.2)$$

When the pump does turn on, the useful gain is

$$Q_u = A_c F_R [S_{\text{on}} - U_L(T_i - T_a)] \quad (10.4.3)$$

which when Equation 10.4.2 is substituted for  $S_{\text{on}}$  becomes

$$Q_u = A_c F_R U_L \Delta T_{\text{on}} \quad (10.4.4)$$

The outlet temperature under these conditions is found from

$$Q_u = (\dot{m} C_p)(T_o - T_i) \quad (10.4.5)$$

where  $T_o - T_i$  is measured by the controller after flow begins. Consequently, the turn-off criterion must satisfy the following inequality or the system will be unstable. (Two forms of the equation are shown. Use the first for systems without a heat exchanger and the second for systems with a collector heat exchanger.)

$$\Delta T_{\text{off}} \leq \frac{A_c F_R U_L}{\dot{m} C_p} \Delta T_{\text{on}} \quad \text{or} \quad \Delta T_{\text{off}} \leq \frac{A_c F_R U_L}{\varepsilon (\dot{m} C_p)_{\text{min}}} \Delta T_{\text{on}} \quad (10.4.6)$$

### Example 10.4.1

For a water collector with  $A_c = 2 \text{ m}^2$ ,  $F_R U_L = 3 \text{ W/m}^2 \text{ }^\circ\text{C}$ , and  $\dot{m} = 0.030 \text{ kg/s}$ , what is the ratio of turn-on criterion to turn-off criterion?

### Solution

From Equation 10.4.6

$$\frac{\Delta T_{\text{on}}}{\Delta T_{\text{off}}} \geq \frac{0.030 \times 4190}{2 \times 3} = 21$$

From the preceding example, the turn-on criterion must be significantly greater than the turn-off criterion. Another way of looking at this situation is to assume a  $5^\circ\text{C}$  turn-on setting. Then the controller of the example will have to be sensitive to temperature differences of  $0.25^\circ\text{C}$  or oscillations may result if the radiation stays near  $S_{\text{on}}$ . This is a small temperature difference to detect with inexpensive controllers. Raising the turn-on setting to  $20^\circ\text{C}$  or more will not significantly reduce the useful energy collection. In fact, the pump should not be operated until the value of the useful energy collected exceeds the cost of pumping.

Even if the criterion of Equation 10.4.6 is satisfied, cycling may occur, particularly in the morning. The fluid in the pipes or ducts between the storage unit and collector will be colder than the temperature at the bottom of storage. Consequently, when the pump first turns on, cold fluid will enter the collector, resulting in lower temperatures detected by the outlet sensor than expected. The controller may turn the pump off until the fluid in the collector is heated to the proper temperature for the pump to again turn on. Other than wear and tear on the pump and motor, this is an efficient way to heat the fluid in the collector and inlet ducts to the proper temperature.

Proportional controllers have been used to maintain either the collector outlet temperature or the temperature rise through the collector at or near a predetermined value. In such a control system the temperature sensors are used to control the pump speed. Although higher outlet temperatures can be obtained with a proportional controller than with an on-off controller, the useful energy collected by an on-off system with a fully mixed tank and with both turn-off and turn-on criteria equal to zero will be greater than that by a system with a proportional controller, as the highest value of  $Q_u$  is obtained when  $F_R$  is a maximum.<sup>3</sup> If a tank is stratified, reduced flows resulting from the use of proportional control may improve stratification and system performance.

<sup>3</sup>There are other considerations that affect the choice of flow rates. There may be advantages to low collector flow rates or using proportional controls if improved stratification in storage tanks results; the resulting reduction in  $T_i$  may more than compensate for reduced  $F_R$ . See Section 12.5.



There is a growing body of literature on control of solar energy systems. For example, Kovarik and Lesse (1976) have considered optimization of flow rates through collectors. Winn and Hull (1978) have further studied this concept by calculation of an  $F_R$  which leads to a maximum difference between energy collected and energy required for pumping fluid through the collector. Winn (1982) provides a broad review of control technologies in solar energy systems.

## 10.5 COLLECTOR ARRAYS: SERIES CONNECTIONS

Collector modules in arrays may be connected in series, in parallel, or in combinations. The performance of collectors in arrays is dependent on how they are arranged, that is, on the flow rate through risers and on the inlet temperatures to individual modules.


Figure 10.5.1 shows arrays of two modules (or two groups of modules) with parallel and series connections. Assume for the moment that the modules are identical. If the flow rates to the arrays are the same, the velocity through the risers of the series-connected array will be twice that in the parallel array. If this difference in velocity does not make an appreciable difference in  $F'$  through its effect on  $h_{fi}$ , then there will be no appreciable difference in performance between the two arrays as the terms in Equation 6.7.6 will be identical. If there is a significant difference in  $F'$  and thus in  $F_R$  or if the design of the modules is not the same (e.g., with the first having one cover and the second two covers), the performance of the two arrays will not be the same. In the series arrangement, the performance of the second (and subsequent) module will not be the same as the first as its inlet temperature will be the outlet temperature of the first.

For collector modules in series, an analysis can be developed that results in an equation identical in form to that of Equation 6.7.6. It is not necessary that the modules be identical; the constraint is that each can be described by its set of two parameters,  $F_R(\tau\alpha)_n$  and  $F_R U_L$ . The useful output of the combination is

$$\begin{aligned} Q_{u,1} + Q_{u,2} = & A_1 F_{R1} [G_T(\tau\alpha)_1 - U_{L1}(T_i - T_a)] \\ & + A_2 F_{R2} [G_T(\tau\alpha)_2 - U_{L2}(T_{o,1} - T_a)] \end{aligned} \quad (10.5.1)$$

where  $T_i$  is the inlet fluid temperature to the first collector and  $T_{o,1}$  is the inlet temperature to the second collector, which is found from the outlet of the first collector:

$$T_{o,1} = T_i + \frac{Q_{u,1}}{\dot{m}C_p} \quad (10.5.2)$$



**Figure 10.5.1** Collector modules in parallel and series. Flow divides in the parallel set; full flow goes through each module in the series set.

The values of  $F_R(\tau\alpha)$  and  $F_R U_L$  for each collector must be the values corresponding to the actual fluid flow through the collector (i.e., the flow rate through collector 1 in the parallel arrangement is one-half of the flow rate through collector 1 in the series arrangement). By eliminating  $T_{o,1}$  from the previous two equations, the useful output of the combination can be expressed as

$$Q_{u,1+2} = [A_1 F_{R1}(\tau\alpha)_1 (1 - K) + A_2 F_{R2}(\tau\alpha)_2] G_T - [A_1 F_{R1} U_{L1} (1 - K) + A_2 F_{R2} U_{L2}] (T_i - T_a) \quad (10.5.3)$$

where

$$K = \frac{A_2 F_{R2} U_{L2}}{\dot{m} C_p} \quad (10.5.4)$$

The form of Equation 10.5.3 suggests that the combination of the two collectors can be considered as a single collector with the following characteristics:

$$A_c = A_1 + A_2 \quad (10.5.5)$$

$$F_R(\tau\alpha) = \frac{A_1 F_{R1}(\tau\alpha)_1 (1 - K) + A_2 F_{R2}(\tau\alpha)_2}{A_c} \quad (10.5.6)$$

$$F_R U_L = \frac{A_1 F_{R1} U_{L1} (1 - K) + A_2 F_{R2} U_{L2}}{A_c} \quad (10.5.7)$$

If three or more collectors are placed in series, then these equations can be used for the first two collectors to define a new equivalent first collector. The equations are applied again with this equivalent first collector and the third collector becoming the second collector. The process can be repeated for as many collectors as desired.

If the two collectors are identical, then Equations 10.5.6 and 10.5.7 reduce to the following:

$$F_R(\tau\alpha) = F_{R1}(\tau\alpha)_1 \left(1 - \frac{K}{2}\right) \quad (10.5.8)$$

$$F_R U_L = F_{R1} U_{L1} \left(1 - \frac{K}{2}\right) \quad (10.5.9)$$

For  $N$  identical collectors in series, Oonk et al. (1979) have shown that repeated applications of Equations 10.5.6 and 10.5.7 yield

$$F_R(\tau\alpha) = F_{R1}(\tau\alpha)_1 \left( \frac{1 - (1 - K)^N}{NK} \right) \quad (10.5.10)$$

$$F_R U_L = F_{R1} U_{L1} \left( \frac{1 - (1 - K)^N}{NK} \right) \quad (10.5.11)$$

### Example 10.5.1

Calculate  $F_R(\tau\alpha)$  and  $F_R U_L$  for the combination of two air heating collectors connected in series with a flow rate of 0.056 kg/s. The characteristics of a single air heater are

$F_R(\tau\alpha) = 0.67$  and  $F_R U_L = 3.6 \text{ W/m}^2 \text{ } ^\circ\text{C}$  at a flow rate of  $0.056 \text{ kg/s}$ . Each collector is  $1.00 \text{ m}$  wide by  $2.00 \text{ m}$  long and  $C_p = 1008 \text{ J/kg } ^\circ\text{C}$ .

### Solution

From Equation 10.5.4,

$$K = \frac{3.63 \times 2.00}{0.056 \times 1008} = 0.129$$

From Equations 10.5.8 and 10.5.9,


$$F_R(\tau\alpha) = 0.67 \left( 1 - \frac{0.129}{2} \right) = 0.63$$

$$F_R U_L = 3.6 \left( 1 - \frac{0.129}{2} \right) = 3.4 \text{ W/m}^2 \text{ } ^\circ\text{C}$$

## 10.6 PERFORMANCE OF PARTIALLY SHADED COLLECTORS

Two circumstances can lead to nonuniform radiation on collectors. In arrays, shading of the bottom of a collector row from beam radiation by the row in front may occur so that beam and diffuse are incident on the top portion and diffuse only on the bottom portion. Also, collectors with specular planar reflectors may have different levels of radiation on upper and lower portions. It is usually adequate to use an average level of radiation over the whole collector area to calculate its output. However, an analysis similar to that of the previous section can be written for situations where flow is in series through the parts of the collector at two radiation levels; this indicates whether or not there are significant changes in performance and if changing flow direction will result in improved performance.

The collector of Figure 10.6.1 is in two zones: (1) on which the incident radiation is  $G_{T,1}$  and (2) on which the incident radiation is  $G_{T,2}$ . The portion of the total area  $A$  in zone 1 is  $A_1$ , and that in zone 2 is  $A_2$ . The temperature of the fluid at the outlet of the first zone is  $T_{o,1}$ . The values of  $F_R$  and  $U_L$  should be essentially the same for both zones. If the angles of incidence of the radiation on the two zones are different (which will probably



**Figure 10.6.1** Schematic of a collector with zone 1 irradiated at  $G_{T,1}$  and zone 2 irradiated at  $G_{T,2}$ .

be the case if one zone is shaded from beam radiation), the  $(\tau\alpha)$  for the two zones will be different. The useful gains are

$$Q_{u,1} = A_1[F_R(\tau\alpha)_1 G_{T,1} - F_R U_L(T_i - T_a)] \quad (10.6.1)$$

$$Q_{u,2} = A_2[F_R(\tau\alpha)_2 G_{T,2} - F_R U_L(T_{o,1} - T_a)] \quad (10.6.2)$$

and

$$T_{o,1} = T_i + \frac{Q_{u,1}}{\dot{m}C_p} \quad (10.6.3)$$

By eliminating  $T_{o,1}$  from Equations 10.6.2 and 10.6.3 and adding the two gains, a single equation can be written in the same general form as Equation 10.5.3:

$$Q_u = A_1 F_R (\tau\alpha)_1 (1 - K) G_{T,1} + A_2 F_R (\tau\alpha)_2 G_{T,2} - F_R U_L [A_1 (1 - K) + A_2] (T_i - T_a) \quad (10.6.4)$$

where

$$K = \frac{A_2 F_R U_L}{\dot{m}C_p} \quad (10.6.5)$$

In contrast to the series-connected different collectors of Section 10.5 where the areas of the two collectors are fixed, the areas  $A_1$  and  $A_2$  in Equation 10.6.4 will be a function of time where the differences in  $I_{T,1}$  and  $I_{T,2}$  are caused by shading.

### Example 10.6.1

A collector is situated so that it is partially shaded from beam radiation. One zone that has 22% of the area has an incident radiation of 220 W/m<sup>2</sup>. The other zone that has 78% of the area has an incident radiation of 1050 W/m<sup>2</sup>. Water is pumped at a rate of 0.0060 kg/m<sup>2</sup> s through the collector and goes through the two zones in series. The characteristics of the collector at this flow rate are  $F_R = 0.96$  and  $F_R U_L = 6.20$  W/m<sup>2</sup> °C. Temperature  $T_i = 48^\circ\text{C}$  and  $T_a = 9^\circ\text{C}$ . As defined by Equation 5.9.3,  $(\tau\alpha)_{av}$  is 0.86 for the zone with  $G_T = 1050$  W/m<sup>2</sup> and 0.73 for the zone with  $G_T = 220$  W/m<sup>2</sup>.

Calculate the output from this collector with **a** flow from the low-intensity to the high-intensity zone and **b** flow from the high-intensity to the low-intensity zone.

### Solution

**a** For flow from the low- to high-intensity zone

$$K = 0.78 \times \frac{6.20}{0.0060 \times 4190} = 0.192$$

$$\begin{aligned} \frac{Q_u}{A_c} &= 0.96[0.22 \times 0.73(1 - 0.192)220 + 0.78 \times 0.86 \times 1050] \\ &\quad - 6.20[0.22(1 - 0.192) + 0.78](48 - 9) = 472 \text{ W/m}^2 \end{aligned}$$

**b** For flow from the high- to low-intensity zone,

$$K = 0.22 \times 6.20 / (0.060 \times 4190) = 0.054$$

$$\begin{aligned} \frac{Q_u}{A_c} &= 0.96[0.78 \times 0.86(1 - 0.054)1050 + 0.22 \times 0.73 \times 220] \\ &\quad - 6.20[0.78(1 - 0.054) + 0.22](48 - 9) = 442 \text{ W/m}^2 \end{aligned}$$

In this situation there is a 7% advantage to pumping the fluid through the collector in the correct direction.

These results can be checked by calculating the outputs of the two zones independently and summing them. For case b, per square meter of total area,

$$\begin{aligned} \frac{Q_{u,1}}{A_c} &= 0.78(0.96 \times 0.86 \times 1050) - 6.20(48 - 9) = 488 \text{ W/m}^2 \\ T_{o,1} &= 48 + \frac{488}{0.0060 \times 4180} = 67.5^\circ \text{ C} \\ \frac{Q_{u,2}}{A_c} &= 0.22(0.96 \times 0.73 \times 220) - 6.20(67.5 - 9) = -46 \text{ W/m}^2 \\ Q_{u,1} + Q_{u,2} &= 488 - 46 = 442 \text{ W/m}^2 \end{aligned}$$

In this example there is a net loss from the shaded part of the collector. However, the useful gain from the whole collector is positive. ■

For shading of a collector module or set of modules that is part of a larger array piped or ducted in parallel, the gain is simply the sum of the gains from the shaded and unshaded zones.

## 10.7 SERIES ARRAYS WITH SECTIONS HAVING DIFFERENT ORIENTATIONS

Collector arrays are occasionally constructed in sections, with the sections having different orientations (i.e., with different azimuth angles and/or slopes). These arrangements may be imposed by the locations and structure available to mount the collector. If these collector sections are series connected, the analysis of Section 10.6 can be applied to calculate the output.

Consider an array of two sections, 1 and 2, connected in series. Areas of the two sections  $A_1$  and  $A_2$  will be fixed. Flow is in the direction of 1 to 2. The  $F_R$  and  $U_L$  values will be the same for both sections, assuming that  $\dot{m}/A_c$  is the same and neglecting effects of orientation and collector temperature on  $U_L$ . The values of  $(\tau\alpha)$  for the two sections will be different and will depend on orientation. Equation 10.6.4 applies to this array, as shown in the following example.

### Example 10.7.1

A collector array is in two sections of equal area. The slopes of both sections are  $55^\circ$ ; section 1 has  $\gamma = -45^\circ$  and section 2 has  $\gamma = 45^\circ$ . The latitude is  $40^\circ$ . The collector has

one glass cover with  $KL = 0.0125$  and  $\alpha_n = 0.93$ ;  $F_R = 0.933$  and  $U_L = 4.50 \text{ W/m}^2 \text{ }^\circ\text{C}$ . Water is pumped in series through sections 1 and 2 at a rate of  $0.01 \text{ kg/m}^2 \text{ s}$ .

For the hour 2 to 3 on May 15,  $I = 2.83 \text{ MJ/m}^2$ . The ambient temperature is  $10^\circ\text{C}$ . The fluid inlet temperature is  $45^\circ\text{C}$  and ground reflectance is estimated to be 0.25. Estimate the output per square meter of total array area for this hour.

### Solution

For this hour,  $I_o = 3.72 \text{ MJ/m}^2$ ,  $k_T = 0.76$ , and  $I_d/I = 0.177$ :  $\delta = 18.8^\circ$  and  $\omega = 37.5^\circ$ .

For both sections,  $I_d = 0.177 \times 2.83 = 0.50 \text{ MJ/m}^2$  and  $I_b = 2.33 \text{ MJ/m}^2$ . For the diffuse radiation,  $\theta_e = 57^\circ$  (from Figure 5.4.1),

$$\begin{aligned}\tau_d &= 0.85 \quad \text{and} \quad \left(\frac{\alpha}{\alpha_n}\right)_d = 0.94 \\ 1.01\tau\alpha &= 1.01 \times 0.85 \times 0.93 \times 0.94 = 0.751\end{aligned}$$

For the ground reflected radiation,  $\theta_e = 66^\circ$ ,

$$\begin{aligned}\tau_g &= 0.77 \quad \text{and} \quad \left(\frac{\alpha}{\alpha_n}\right)_g = 0.88 \\ 1.01\tau\alpha &= 1.01 \times 0.77 \times 0.93 \times 0.88 = 0.636\end{aligned}$$

For section 1; for beam radiation, from Equation 1.6.2,

$$\begin{aligned}\cos \theta &= 0.277 \quad \text{and} \quad \theta = 74^\circ \\ \tau_b &= 0.65 \quad \text{and} \quad \left(\frac{\alpha}{\alpha_n}\right)_b = 0.79 \\ 1.01\tau\alpha &= 1.01 \times 0.65 \times 0.93 \times 0.79 = 0.482\end{aligned}$$

From Equation 1.6.5,  $\cos \theta_z = 0.782$ ,

$$R_{b,1} = \frac{0.277}{0.782} = 0.355$$

Then

$$\begin{aligned}I_{T,1} &= 2.33 \times 0.355 + \frac{0.50(1 + \cos 55)}{2} + 2.83 \times \frac{0.25(1 - \cos 55)}{2} \\ &= 0.827 + 0.393 + 0.151 = 1.37 \text{ MJ/m}^2\end{aligned}$$

and

$$S_1 = 0.827 \times 0.482 + 0.393 \times 0.751 + 0.151 \times 0.636 = 0.790 \text{ MJ/m}^2$$

So

$$(\tau\alpha)_{av,1} = \frac{0.790}{1.37} = 0.577$$

For section 2; for beam radiation,

$$\cos \theta = 0.942 \quad \text{and} \quad \theta = 19.6^\circ$$

$$\tau_b = 0.91 \quad \text{and} \quad \left(\frac{\alpha}{\alpha_n}\right)_b = 1.00$$

$$1.01\tau\alpha = 1.01 \times 0.91 \times 0.93 = 0.855$$

$$R_{b,2} = \frac{0.942}{0.782} = 1.18$$

Then

$$I_{T,2} = 2.33 \times 1.18 + 0.393 + 0.151 = 3.30 \text{ MJ/m}^2$$

and

$$\begin{aligned} S_2 &= 2.33 \times 1.18 \times 0.855 + 0.393 \times 0.751 + 0.151 \times 0.636 \\ &= 2.75 \text{ MJ/m}^2 \end{aligned}$$

So

$$(\tau\alpha)_{av,2} = \frac{2.75}{3.30} = 0.833$$

We now use Equations 10.6.4 and 10.6.5 to calculate the performance of the two sections in series:

$$K = 0.93 \times \frac{4.5}{0.01 \times 4190} = 0.100$$

$$\begin{aligned} \frac{Q_u}{A_c} &= 0.933\{[0.5 \times 0.577(1 - 0.100)1.37 + 0.5 \times 0.833 \times 3.30]10^6 \\ &\quad - 4.5 \times 3600[0.5(1 - 0.100) + 0.5](45 - 10)\} \\ &= 1.11 \text{ MJ/m}^2 \end{aligned}$$

■

Note that for the hour 9 to 10 for this example, which corresponds to a reversal of flow direction for the hour 2 to 3, the output of the array would be  $1.02 \text{ MJ/m}^2$ , or about 8% less than for the conditions in the example. These calculations show how much difference flow direction makes and thus assists in determining control strategy. (Note that there may be conditions under which the section with the lower irradiation should be bypassed. This can be determined by calculating the output of the first section. If the output is negative, it should be bypassed. If its output is higher than that of the combined sections, the second section should be bypassed.)

If sections of a collector array are connected in parallel, those sections perform as separate collectors and the total output is the sum of the outputs of the sections.


## 10.8 USE OF MODIFIED COLLECTOR EQUATIONS

The equations that have been developed in this chapter up to this point are all modifications of Equation 6.7.6, the basic collector performance model. The result is a series of equations, all of the same form, that are combinations of the collector model plus other components: a controller (by the superscript +), a collector heat exchanger (by  $F_R'$ ), pipe and duct losses [by  $F_R(\tau\alpha)'$  and  $F_R U_L'$ ], and various combinations of series connections (by the factor  $K$ ). For many purposes, it is convenient to use these combined component models and consider the entire collector subsystem (collector, control, piping, and heat exchanger) as a modified collector.<sup>4</sup>

Combinations of these models are often encountered, and it is the purpose of this section to illustrate the logical way to account for the combinations. The example that follows includes many of the modifications noted in previous sections. The logic illustrated can be extended to cover additional modifications.

### Example 10.8.1

An active solar water heating system is shown schematically in the figure. The collector is located at a distance from the tank, and the collector heat exchanger is next to the tank.



There are three modules in the collector array, connected in parallel. The array area  $A_c = 5.90 \text{ m}^2$ . Operating data from the manufacturer indicate that  $F_{av}(\tau\alpha)_n = 0.77$  and  $F_{av} U_L = 3.88 \text{ W/m}^2 \text{ } ^\circ\text{C}$  when the flow rate of water is  $0.020 \text{ kg/m}^2 \text{ s}$ . Data on the incidence angle modifier are shown in the diagram.

The pipe runs between the collector and the heat exchanger are each 12.2 m long. The pipes are 25.5 mm in outer diameter and are insulated with 30.0 mm of foam insulation with  $k = 0.0342 \text{ W/m } ^\circ\text{C}$ . It can be assumed that most of the resistance to heat loss from the pipes is in the insulation and that losses occur to ambient temperature over essentially all of the length of the runs.

An antifreeze solution of 40% propylene glycol in water is pumped through the collector loop at a rate of  $0.110 \text{ kg/s}$ , and water from the storage tank is pumped through the heat exchanger at  $0.122 \text{ kg/s}$ . The manufacturer of the heat exchanger specifies that its  $UA = 260 \text{ W/}^\circ\text{C}$ .

<sup>4</sup>Other modifications have been made. Zarmi (1982) has developed a method for accounting for the transient response of collector subsystems in systems where there are quantities of fluid in the collector and piping that are significant compared to that in a storage tank.



- a** For this system, write an equation in the form of Equation 10.1.1 for  $Q_u$  in terms of  $G_T$ ,  $T_a$ ,  $T_i$ , and  $\theta_b$ .
- b** For an hour when the average value of  $G_T = 1010 \text{ W/m}^2$ ,  $T_a = 13^\circ\text{C}$ ,  $T_i = 34^\circ\text{C}$ , and  $\theta_b = 35^\circ$ , what is  $Q_u$ ?

### Solution

There is a logical order in which to account for the several modifications that are to be made in the collector equation to convert it to the subsystem equation. Start with the collector parameters, convert them to functions of  $F_R$ , correct for capacitance rate, add the pipe losses, and then include the effect of the heat exchanger. In other words, do the calculations in the order in which the components occur, starting with the known collector characteristics and working toward the tank.

The collector data are applicable to the parallel configuration, and no correction is required to account for series connections. The effects of the incidence angle modifier can be entered into the equation at any point; for convenience in writing the equations it will be done last. At the end of each of the five steps that follow, modified values of  $F_R(\tau\alpha)_n$  and  $F_R U_L$  to that point will be shown. These in turn are inputs to the succeeding step.

- a** First, convert the collector parameters to  $F_R(\tau\alpha)_n$  and  $F_R U_L$  using Equations 6.19.2 and 6.19.3. The capacitance rate  $\dot{m}C_p$  through the collector array under test conditions, with  $C_p = 4180 \text{ J/kg K}$ , is  $5.90 \times 0.020 \times 4180 = 493 \text{ W/}^\circ\text{C}$ .

$$F_R(\tau\alpha)_n = \frac{0.77}{1 + \frac{5.90 \times 3.88}{2 \times 493}} = \frac{0.77}{1.0232} = 0.753$$

$$F_R U_L = \frac{3.88}{1.0232} = 3.79 \text{ W/m}^2 \text{ }^\circ\text{C}$$

Second, correct  $F_R(\tau\alpha)_n$  and  $F_R U_L$  to the capacitance rate to be used in the operation. The test capacitance rate is  $493 \text{ W/}^\circ\text{C}$ . The use capacitance rate, with  $C_p = 3750 \text{ J/kg K}$ , is  $0.110 \times 3750 = 413 \text{ W/}^\circ\text{C}$ .

With Equation 6.20.4, calculate  $F' U_L$  from the test conditions:

$$F' U_L = -\frac{493}{5.90} \ln \left( 1 - \frac{3.79 \times 5.90}{493} \right) = 3.88 \text{ W/m}^2 \text{ }^\circ\text{C}$$

(Note that if the temperature rise through the collector is linear,  $F'$  and  $F_{av}$  will be the same. In this case, with high flow rates through the collector, they are essentially equal.) Then from Equation 6.20.2

$$r = \frac{\frac{413}{3.88 \times 5.90} (1 - e^{-5.90 \times 3.88 / 413})}{\frac{493}{3.88 \times 5.90} (1 - e^{-5.90 \times 3.88 / 493})} = 0.995$$

The change in capacitance rate thus produces a very small change in collector parameters, which under use conditions are

$$F_R(\tau\alpha)_n = 0.995 \times 0.753 = 0.749$$

$$F_R U_L = 3.79 \times 0.995 = 3.77 \text{ W/m}^2 \text{ }^\circ\text{C}$$

Third, the pipe losses are accounted for using Equations 10.3.9 and 10.3.10. If the significant resistance to heat loss is in the insulation, the loss coefficient for the pipes to and from the collector, based on the outside area of the insulation, will be

$$U_{\text{out}} = \frac{2k}{D_o \ln(D_o/D_i)} = \frac{2 \times 0.0342}{0.855 \times \ln(0.0855/0.0255)} = 0.661 \text{ W/m}^2 \text{ }^\circ\text{C}$$

Then

$$(UA)_i = (UA)_o = 0.661 \times \pi \times 0.0855 \times 12.2 = 2.17 \text{ W/}^\circ\text{C}$$

$$\frac{(\tau\alpha)'}{(\tau\alpha)} = \frac{1}{1 + 2.17/413} = 0.995$$

$$\frac{U'_L}{U_L} = \frac{1 - \frac{2.17}{413} + \frac{2 \times 2.17}{5.90 \times 3.77}}{1 + 2.17/413} = 1.184$$

The collector parameters with the additional modification for pipe losses are

$$F_R(\tau\alpha)'_n = 0.995 \times 0.749 = 0.745$$

$$F_R U'_L = 1.184 \times 3.77 = 4.47 \text{ W/m}^2 \text{ }^\circ\text{C}$$

Fourth, the parameters are modified to account for the heat exchanger. The effectiveness of the heat exchanger is estimated by the method of Section 3.17. The capacitance rate on the tank side of the heat exchanger is  $0.122 \times 4180 = 510 \text{ W/}^\circ\text{C}$ , so the capacitance rate on the collector side ( $413 \text{ W/}^\circ\text{C}$ ) is the minimum. Thus  $C^* = 413/510 = 0.810$ .

From Equation 3.17.8,

$$NTU = \frac{260}{413} = 0.630$$

Equation 3.17.7 gives the heat exchanger effectiveness:

$$\varepsilon = \frac{1 - e^{-0.630(1-0.810)}}{1 - 0.810e^{-0.630(1-0.810)}} = 0.40$$

Using Equation 10.2.3 (or Figure 10.2.2) to get  $F'_R/F_R$  yields

$$\frac{F'_R}{F_R} = \left[ 1 + \frac{5.90 \times 4.47}{413} \left( \frac{1}{0.40} - 1 \right) \right]^{-1} = 0.913$$

Thus the parameters with modification for the heat exchanger become

$$F'_R(\tau\alpha)'_n = 0.745 \times 0.913 = 0.680$$

$$F'_R U'_L = 4.47 \times 0.913 = 4.08 \text{ W/m}^2 \text{ }^\circ\text{C}$$

Fifth, the incidence angle modifier is needed. The slope  $b_o$  of the  $K_{\tau\alpha}$  curve is  $-0.18$ , so

$$K_{\tau\alpha} = 1 - 0.18 \left( \frac{1}{\cos \theta_b} - 1 \right)$$

Using Equation 10.1.1,

$$Q_u = 5.90 \left\{ 0.680 \left[ 1 - 0.18 \left( \frac{1}{\cos \theta_b} - 1 \right) \right] G_T - 4.08(T_i - T_a) \right\}$$

The desired working equation is thus

$$Q_u = 4.01 \left[ 1 - 0.18 \left( \frac{1}{\cos \theta_b} - 1 \right) \right] G_T - 24.1(T_i - T_a)$$

**b** We can now enter the operating conditions in this equation to get the useful gain from the subsystem:

$$Q_u = 4.01 \left[ 1 - 0.18 \left( \frac{1}{\cos 35} - 1 \right) \right] 1010 - 24.1(34 - 13) = 3190 \text{ W}$$

In this example, the corrections for collector capacitance rate and the differences between the parameters based on  $F_{av}$  and  $F_R$  were small. These corrections can be very much larger if the capacitance rates in the collector are small, as is the case for some water heating systems in which high degrees of stratification are obtained in tanks by use of flow rates an order-of-magnitude smaller than those noted here. This will be discussed in Chapter 12.

## 10.9 SYSTEM MODELS

The previous section dealt with the collector equation and modifications thereof. The next step is the inclusion of models of other system components, including equations for storage, loads, and whatever other components are included in the physical system. System models are assemblies of appropriate component models. The net effect of the assembly is a set of coupled algebraic and differential equations with time as the independent variable. Inputs to these equations include meteorological data as forcing functions that operate on the collector and possibly also on the load, depending on the application.

These equations can be manipulated and combined algebraically or they can be solved simultaneously without formal combinations. Each procedure has some advantages in solar process simulation. If the equations are all linear (and if there are not too many to manipulate), the algebraic equations can be solved and substituted into the differential

equations, which can then be solved by standard methods (e.g., Hamming, 1962). If the algebraic equations are nonlinear or if there is a large number of them coupled so that they are difficult to solve, it may be advantageous to leave them separated and solve the set of combined algebraic and differential equations numerically. Also, leaving the component equations uncombined makes it possible to extract information about the performance of components in the system that is not readily available from solution of combined equations.

As an example of a simple system that yields a single differential equation, consider a solar house heater with an unstratified storage unit supplying energy through a heat exchanger to the house maintained at  $T_h$ . Except for the heat exchanger supplying energy to the house, this is illustrated in Figure 10.2.1. Equation 10.1.1 for the collector can be combined with Equation 10.1.3 for the tank to give

$$(mC_p)_s \frac{dT_s}{dt} = A_c F_R [S - U_L(T_s - T_a)]^+ - (UA)_s(T_s - T_a) - \varepsilon_L(\dot{m}C_p)_{\min}(T_s - T_h) \quad (10.9.1)$$

Once the collector parameters, the storage size and loss coefficient, the magnitude of the load, and the meteorological data are specified, the storage tank temperature can be calculated as a function of time. Also, gain from the collector, losses from storage, and energy to load can be determined for any desired period of time by integration of the appropriate rate quantities.

Various methods are available to numerically integrate equations such as Equation 10.9.1. For example, simple Euler integration can be used, the same technique that was used in Example 8.3.1. Using simple Euler integration, we express the temperature derivative  $dT_s/dt$  as  $(T_s^+ - T_s)/\Delta t$  and obtain an expression for the change in storage tank temperature for the time period in terms of known quantities. Equation 10.9.1 then becomes

$$T_s^+ = T_s + \frac{\Delta t}{(mC_p)_s} \{A_c F_R [S - U_L(T_s - T_a)]^+ - (UA)_s(T_s - T_a) - \varepsilon_L(\dot{m}C_p)_{\min}(T_s - T_h)\} \quad (10.9.2)$$

Integration schemes must be used with care to ensure that they are stable for the desired time step and that reasonably accurate solutions are being attained. When performing hand calculations, both stability and accuracy can be problems. However, most computer facilities have subroutines that will solve systems of differential equations to a specified accuracy and automatically take care of stability problems.

In order to ensure stability in Equation 10.9.2, the time step  $\Delta t$  must be small enough so that the coefficient on  $T_s$  is positive. The critical time step occurs when the coefficient on  $T_s$  is zero. In order to minimize truncation errors on a digital computer, use about one-sixth of the critical time step. However, weather data are usually known in hour increments so hour time steps are often used if stability is maintained.

### Example 10.9.1

The performance of the collector of Example 6.7.1 was based upon a constant water supply temperature of 40°C to the collector. Assume the collector area is 4 m<sup>2</sup>,  $F_R = 0.80$ , and  $U_L = 8.0 \text{ W/m}^2 \text{ }^\circ\text{C}$ . The collector is connected to a water storage tank containing 150 kg

of water initially at 40°C. The storage tank loss coefficient–area product is 1.70 W/°C and the tank is located in a room at 25°C. Assume water is withdrawn to meet a load at a constant rate of 10 kg/h and is replenished from the mains at a temperature of 15°C. Calculate the performance of this system for the period from 7 AM to 5 PM using the collector and meteorological data from Example 6.11.1. Check the energy balance on the tank.

### Solution

Equation 10.9.2 (modified due to lack of a load heat exchanger) is used to calculate hourly temperatures of the tank. For this problem a time step of 1 h is sufficient to guarantee stability. The equations will be left uncombined in order that the individual terms in the energy balance can be seen.

$$T_s^+ = T_s + \frac{1}{150 \times 4190} \{4 \times 0.80[S - 8.0 \times 3600(T_s - T_a)]^+ \\ - 1.70 \times 3600(T_s - 25) - 10 \times 4190(T_s - 15)\}$$

The first term in the brackets is the useful output of the collector and can have only positive values. The second term is the thermal loss from the tank. The third term is the energy delivered to the load. Simplifying the individual terms, this equation becomes

$$T_s^+ = T_s + 1.59\{3.20[S - 0.0288(T_s - T_a)]^+ \\ - 0.00612(T_s - 25) - 0.0419(T_s - 15)\}$$

where  $S$  and all energy terms are in megajoules per square meter. The data in the first four columns of the table below are from Example 6.11.1. The new tank temperature calculated for the end of the hour is  $T_s^+$ . The three terms in the brackets of the equation are  $Q_u$ , load met by solar, and loss, assuming  $T_s$  to be fixed for the hour at its initial value. The change in internal energy of the water should be equal to  $\Sigma Q_u - \Sigma L_s - \Sigma$  losses.

$$150 \times 4190 (53.0 - 40.0) = (23.43 - 1.41 - 13.87) \times 10^6 \\ 8.17 \text{ MJ} \cong 8.15 \text{ MJ}$$

Hour	$I_T$ (MJ/m <sup>2</sup> )	$S$ (MJ/m <sup>2</sup> )	$T_a$ (°C)	$T_s^+$ (°C)	$Q_u$ (MJ)	Loss (MJ)	Load (MJ)
Start				40.0			
7–8	0.02	—	−11	38.2	0	0.09	1.05
8–9	0.43	0.34	−8	36.5	0	0.08	0.97
9–10	0.99	0.79	−2	35.0	0	0.07	0.90
10–11	3.92	3.16	2	44.8	7.07	0.06	0.84
11–12	3.36	2.73	3	50.4	4.88	0.12	1.25
12–1	4.01	3.25	6	57.8	6.31	0.16	1.48
1–2	3.84	3.08	7	62.9	5.17	0.20	1.79
2–3	1.96	1.56	8	59.3	0	0.23	2.01
3–4	1.21	0.95	9	56.0	0	0.21	1.86
4–5	<u>0.05</u>	—	7	53.0	<u>0</u>	<u>0.19</u>	<u>1.72</u>
Total	19.79				23.43	1.41	13.87

This is a satisfactory check. (The calculations shown in the table were carried out to 0.01 MJ to facilitate checking the energy balance. The result is certainly no better than  $\pm 0.1$  MJ.) The day's efficiency is

$$\eta_{\text{day}} = \frac{23.4}{19.8 \times 4} = 0.30 = 30\%$$

■

The preceding example was simple enough that hand calculation was possible to simulate a few hours of real time. Most problems in solar simulation are not so easy, and we are usually interested in more than just a few hours of simulated data. In general, it is necessary to use a computer and simulate over a season or a year to obtain useful solutions.

## 10.10 SOLAR FRACTION AND SOLAR SAVINGS FRACTION

For processes such as active solar building heating systems the total energy supplied to meet the load is independent of the size of the solar heating system. In other words, the energy supplied from the solar system plus the auxiliary energy is a constant. For some processes, the load is a function of the size of the solar energy system. For example, in a passively heated building that has large south-facing windows to admit solar radiation, the losses through the building envelope will vary with the size of the window if the overall loss coefficient for the window is different from that of the walls. Consequently the sum of the auxiliary energy and the solar energy is not a constant. When the total load is a function of solar energy size, it is difficult to define a solar fraction that is unambiguous. For passive processes usage of the term *solar fraction* varies and care must be exercised to understand what a particular author means by the term.

System thermal analyses (and measurements) result in long-term system performance, which is then used in economic analyses. There are two figures of merit commonly used for solar systems: **solar fraction** and **solar savings fraction**. Solar fraction is the ratio of two similar energy quantities (thermal energy except for photovoltaic systems), and this definition ignores the fact that substantial amounts of parasitic electrical energy may be needed to run pumps, fans, and controllers that are not present in a nonsolar system. The solar savings fraction recognizes the need for this additional electrical energy and expresses savings in terms of the ratio of two energy costs.

If the additional parasitic electrical energy in a solar system is small, then the solar fraction is a useful concept. Let the purchased energy with a zero area solar energy system (i.e., a fuel-only system) be  $L$ , the purchased energy (here called auxiliary energy) for the system with solar energy be  $L_A$ , and the solar energy delivered be  $L_S$ . Here it is assumed that  $L = L_A + L_S$ . For month  $i$  the fractional reduction of purchased energy when a solar energy system is used is

$$f_i = \frac{L_i - L_{A,i}}{L_i} = \frac{L_{S,i}}{L_i} \quad (10.10.1)$$

The same concept applies on an annual basis, with energy quantities integrated over the year:

$$\mathcal{F} = \frac{L - L_A}{L} = \frac{L_S}{L} = \frac{\sum_{\text{yr}} f_i L_i}{\sum_{\text{yr}} L_i} \quad (10.10.2)$$

When parasitic energy for pumps, for example, is significant, it is necessary to consider these costs in an economic analysis. The cost to supply the thermal energy for a conventional system in month  $i$  is

$$C_i = C_f L_i \quad (10.10.3)$$

where  $C_f$  is the cost of fuel.<sup>5</sup> The cost to supply auxiliary and parasitic energy in a solar system is

$$C_{A,i} = C_f L_{A,i} + C_e \Delta E_i \quad (10.10.4)$$

where  $C_e \Delta E_i$  is the cost of additional electricity for the solar system above the conventional system. The solar savings fraction is then

$$\begin{aligned} f_{\text{sav},i} &= \frac{C_i - C_{A,i}}{C_i} = \frac{C_f L_i - C_f L_{A,i} - C_e \Delta E_i}{C_f L_i} \\ &= \frac{L_i - L_{A,i} - C_{fe} \Delta E_i}{L_i} = f_i - \frac{C_{ef} \Delta E_i}{L_i} \end{aligned} \quad (10.10.5)$$

where  $C_{ef}$  is the ratio of the cost of electricity to the cost of fuel. The annual solar savings fraction is then

$$\mathcal{F}_{\text{sav}} = \mathcal{F} - \frac{C_{ef} \sum_{\text{yr}} \Delta E_i}{\sum_{\text{yr}} L_i} = \mathcal{F} - \frac{C_{ef} \Delta E}{L} \quad (10.10.6)$$

The economic analysis methods presented in Chapter 11 use the solar fraction as defined by Equation 10.10.2. However, either can be used as shown in Section 11.10.

## 10.11 SUMMARY

The concepts in this chapter are all concerned with techniques for combining component models (i.e., equations) into system models and obtaining solutions for the system models. The solutions of these sets of equation over time, using meteorological and load data as forcing functions, provide valuable information about the dynamics and the integrated performance of solar processes. These *simulations* can be viewed as numerical experiments in which the processes are “operated” in computers quickly and inexpensively. They are the applications of theory and, in combination with physical experiments on components and systems, provide the basis for much of our existing knowledge of solar applications.

Chapters in Part II, on applications, include many studies of effects of design parameters on seasonal or annual performance of systems, and much of this information is derived from simulations. Simulations, their validity, their utility, their use in design of processes, and computer programs for doing them will be noted in Chapter 19.

---

<sup>5</sup>The cost of electricity for the conventional system could have been included in Equation 10.10.3; this would have made Equation 10.10.5 slightly more complex. However, as shown in Section 11.10, the definition of solar savings fraction used here is convenient in economic analyses.

## REFERENCES

- Beckman, W. A., *Solar Energy*, **21**, 531 (1978). "Duct and Pipe Losses in Solar Energy Systems."
- Beckman, W. A., S. A. Klein, and J. A. Duffie, *Solar Heating Design by the f-Chart Method*, Wiley, New York (1977).
- Close, D. J. and M. B. Yusoff, *Solar Energy*, **20**, 459 (1978). "The Effects of Air Leaks on Solar Air Collector Behavior."
- deWinter, F., *Solar Energy*, **17**, 335 (1975). "Heat Exchanger Penalties in Double-Loop Solar Water Heating Systems."
- Hamming, R. W., *Numerical Methods for Scientists and Engineers*, McGraw-Hill, New York (1962).
- Kays, W. M. and A. L. London, *Compact Heat Exchangers*, McGraw-Hill, New York (1964).
- Kovarik, M. and P. F. Lesse, *Solar Energy*, **18**, 431 (1976). "Optimal Control of Flow in Low Temperature Solar Heat Collectors."
- Oonk, R., D. E. Jones, and B. E. Cole-Appel, *Solar Energy*, **23**, 535 (1979). "Calculation of Performance of  $N$  Collectors in Series from Test Data on a Single Collector."
- Winn, C. B., in *Advances in Solar Energy*, Vol. **1** (K. Boer and J. A. Duffie, eds.), American Solar Energy Society and Plenum Press, New York, p. 209 (1982). "Controls in Solar Energy Systems."
- Winn, C. B. and D. E. Hull, *Proc. 1978 Annu. Meeting Am. Sect. ISES*, **2** (2), 493 (1978). "Optimal Controllers of the Second Kind."
- Zarmi, Y., *Solar Energy*, **29**, 3 (1982). "Transition Time Effects in Collector Systems Coupled to a Well Mixed Storage."



## Solar Process Economics

In the first 10 chapters, we have discussed in some detail the thermal performance of components and systems and showed how the long-term thermal performance can be estimated in terms of the design parameters of the components. We also want to be able to assess the value of a solar process in economic terms. Given the performance, we need methods for making economic evaluations.

Solar processes are generally characterized by high first cost and low operating costs. Thus the basic economic problem is one of comparing an initial known investment with estimated future operating costs. Most solar energy processes require an auxiliary (i.e., conventional) energy source so that the system includes both solar and conventional equipment and the annual loads are met by a combination of the sources. In essence, solar energy equipment is bought today to reduce tomorrow's fuel bill.

The cost of any energy delivery process includes all of the items of hardware and labor that are involved in installing the equipment plus the operating expenses. Factors which may need to be taken into account include interest on money borrowed, property and income taxes, resale of equipment, maintenance, insurance, fuel, and other operating expenses. The objective of the economic analysis can be viewed as the determination of the least cost method of meeting the energy need, considering both solar and nonsolar alternatives. For solar energy processes, the problem is to determine the size of the solar energy system that gives the lowest cost combination of solar and auxiliary energy.

In this chapter we note several ways of doing economic evaluations, with emphasis on the life-cycle savings method. This method takes into account the time value of money and allows detailed consideration of the complete range of costs. It is introduced by an outline of cost considerations, note of economic figures of merit (design criteria), and comments on design variables which are important in determining system economics. For additional discussion of economic analyses, see Riggs (1968), De Garmo and Canada (1973), Ruegg (1975), and White et al. (1977).

Section 11.8 describes the  $P_1$ ,  $P_2$  method of doing life-cycle savings analyses. This is a quick and convenient way of carrying out the computations described in detail in earlier sections and is the method used in economic analyses of particular processes in following chapters.

### 11.1 COSTS OF SOLAR PROCESS SYSTEMS

**Investments** in buying and installing solar energy equipment are important factors in solar process economics. These include the delivered price of equipment such as collectors, storage unit, pumps and blowers, controls, pipes and ducts, heat exchangers, and all other

equipment associated with the solar installation. Costs of installing this equipment must also be considered, as these can match or exceed the purchase price. Also to be included are costs of structures to support collectors and other alterations made necessary by the solar energy equipment. Under some circumstances credits may be taken for the solar process if its installation results in reduction of costs; for example, a collector may serve as part of the weatherproof envelope of a building, eliminating the need for some of the conventional siding or roofing.

Installed costs of solar equipment can be shown as the sum of two terms, one proportional to collector area and the other independent of collector area:

$$C_S = C_A A_c + C_E \quad (11.1.1)$$

where  $C_S$  = total cost of installed solar energy equipment (\$)

$C_A$  = total area-dependent costs (\$/m<sup>2</sup>)

$A_c$  = collector area (m<sup>2</sup>)

$C_E$  = total cost of equipment which is independent of collector area (\$)

The area-dependent costs  $C_A$  include such items as the purchase and installation of the collector and a portion of storage costs. The area-independent costs  $C_E$  include such items as controls and bringing construction or erection equipment to the site, which do not depend on collector area.

**Operating costs** are associated with a solar process. These continuing costs include cost of auxiliary energy, energy costs for operation of pumps and blowers (often termed parasitic energy, which should be minimized by careful design), extra real estate taxes imposed on the basis of additional assessed value of a building or facility, interest charges on any funds borrowed to purchase the equipment, and others.

There may be income tax implications in the purchase of solar equipment. In the United States, interest paid on a mortgage<sup>1</sup> for its purchase and extra property tax on an increased assessment due to solar equipment are both deductible from income for tax purposes if the owner itemizes his or her deductions. States may allow similar deductions. The income tax reduction associated with these payments depends on the tax bracket of the owner and serves to reduce the cost of the solar process.<sup>2</sup>

Equipment purchased by businesses has other tax implications. Income-producing property and equipment may be depreciated, resulting in reduced taxable income and thus reduced income tax. But the value of fuel saved by the use of solar equipment is effectively reduced because a business already deducts the cost of fuel from its income for tax purposes. If the equipment is for purposes other than building heating or air conditioning, there may be investment tax credits available in the first year. Further, the equipment may have salvage or resale value which may result in a capital gains tax. Finally, federal and state governments may allow special tax credits to encourage the use of solar energy. (Federal and state tax laws relating to solar energy are often changed, and current law should be used in any economic analysis.)

---

<sup>1</sup>In this chapter we use the term "mortgage," commonly applied to funds borrowed for building projects, for any loan for purchase of solar energy equipment.

<sup>2</sup>This chapter is written with U.S. tax law in mind. For other countries, treatment of tax implications will have to be modified.

In equation form, the annual costs for both solar and nonsolar systems to meet an energy need can be expressed as

$$\begin{aligned} \text{Yearly cost} = & \text{fuel expense} + \text{mortgage payment} \\ & + \text{maintenance and insurance} + \text{parasitic energy cost} \\ & + \text{property taxes} - \text{income tax savings} \end{aligned} \quad (11.1.2)$$

Fuel expense is for energy purchase for auxiliary or for the conventional (nonsolar) system. The mortgage payment includes interest and principal payment on funds borrowed to install the system. Maintenance and insurance are recurring costs to keep a system in operating condition and protected against fire or other losses. Parasitic energy costs are for blowing air or pumping liquids and other electrical or mechanical energy uses in a system. Property taxes are levied on many installations. Income tax savings for a non-income-producing system (such as a home heating system) can be expressed as

$$\text{Income tax savings} = \text{effective tax rate} \times \text{interest payment} + \text{property tax} \quad (11.1.3)$$

If the system is an income-producing installation,

$$\text{Income tax savings} = \text{effective tax rate} \times \left( \begin{array}{l} \text{interest payment} \\ + \text{property tax} \\ + \text{fuel expense} \\ + \text{maintenance and insurance} \\ + \text{parasitic energy costs} \\ - \text{depreciation} \end{array} \right) \quad (11.1.4)$$

State income taxes are deductible from income for federal tax purposes. Where federal taxes are not deductible for state tax purposes, the effective tax rate is given by

$$\begin{aligned} \text{Effective tax rate} = & \text{federal tax rate} + \text{state tax rate} - \text{federal tax rate} \\ & \times \text{state tax rate} \end{aligned} \quad (11.1.5)$$

The concept of **solar savings**, as outlined by Beckman et al. (1977), is a useful one. Solar savings are the difference between the cost of a conventional system and a solar system. (Savings can be negative; they are then losses.) In equation form it is simply

$$\text{Solar savings} = \text{costs of conventional energy} - \text{costs of solar energy} \quad (11.1.6)$$

In this equation it is not necessary to evaluate costs that are common to both the solar and the nonsolar system. For example, the auxiliary furnace and much of the ductwork or plumbing in a solar heating system are often the same as would be installed in a nonsolar system. With the savings concept, it is only necessary to estimate the incremental cost of installing a solar system. If the furnaces or other equipment in the two systems are

different, the difference in their costs can be included as an increment or decrement to the cost of installing a solar system. Solar savings can be written as

$$\begin{aligned}
 \text{Solar savings} = & \text{fuel savings} - \text{incremental mortgage payment} \\
 & - \text{incremental insurance and maintenance} \\
 & - \text{incremental parasitic energy cost} - \text{incremental property tax} \\
 & + \text{income tax savings}
 \end{aligned} \tag{11.1.7}$$

The significance of the terms is the same as for Equation 11.1.2, except that here they refer to the increments in the various costs, that is, the differences between the costs for the solar energy system compared to a nonsolar system. Equations analogous to 11.1.3 and 11.1.4 can be written for the last term in Equation 11.1.7. They are, for a non-income-producing system,

$$\text{Income tax savings} = \text{effective tax rate} \times \left( \begin{array}{l} \text{incremental interest payment} \\ + \text{incremental property tax} \end{array} \right) \tag{11.1.8}$$


and, for an income-producing system,

$$\begin{aligned}
 \text{Income tax savings} = & \text{effective tax rate} \times \\
 & \left( \begin{array}{l} \text{incremental interest payment} \\ + \text{incremental property tax} \\ + \text{incremental maintenance and insurance} \\ + \text{incremental parasitic energy cost} \\ + \text{incremental depreciation} \\ - \text{value of fuel saved} \end{array} \right)
 \end{aligned} \tag{11.1.9}$$

Fuel saved is a negative tax deduction since a business already deducts fuel expenses; the value of fuel saved is effectively taxable income.


## 11.2 DESIGN VARIABLES

The economic problem in solar process design is to find the lowest cost system. In principle, the problem is a multivariable one, with all of the components in the system and the system configuration having some effect on the thermal performance and thus on cost. The design of the load system (the building, the industrial process using energy, or other load) must also be considered in the search for optimum design. Barley (1978) and Balcomb (1986) have investigated the economic trade-off between energy conservation and solar heating. In practice, the problem often resolves to a simpler one of determining the size of a solar energy system for a known load, with storage capacity and other parameters fixed in relationship to collector area. Given a load that is some function of time through a year, a type of collector, and a system configuration, the primary design variable is collector area. System performance is much more sensitive to collector area than to any other variable.



**Figure 11.2.1** An example of annual fraction of heating loads carried by an active solar heating system for a building in Madison, WI. Curve *A* is for a system with a two-cover, selective-surface collector. Curve *B* is for a system with a one-cover, nonselective collector. Curve *C* is the same system as *A* but with twice the storage capacity.

Three examples of the dependence of annual thermal performance on collector area are shown in Figure 11.2.1 for a solar heating operation. Curve *A* is for a system with a two-cover, selective-surface collector, while *B* is for a one-cover, nonselective collector. Curve *C* is for double the storage capacity and the same collector as for curve *A*. Figure 11.2.2 shows the dependence of annual thermal performance on storage capacity for 60 m<sup>2</sup> of type *A* collectors.



**Figure 11.2.2** Annual solar fraction for the system with collector of type *A* of Figure 11.2.1 for a collector area of 60 m<sup>2</sup> as function of storage capacity.

For this active solar heating example, relative sensitivity of annual performance to collector area and relative insensitivity to the differences in these two collectors are apparent. The solar contribution is relatively insensitive to storage capacity within the range shown in Figure 11.2.2 once a critical storage capacity (about 3000 kg in this example) is exceeded. Similar results are found for solar heating for a wide range of locations. It is difficult to generalize this experience with active solar heating systems to other applications. The general procedure for determining which variables are most critical to thermal performance is to do a sensitivity analysis such as that of Close (1967). The economic analysis for solar heating to meet a given load is simplified by the fact that collector area is the primary design parameter; economic analyses for other solar processes must take into account the possibility that other design variables might be of comparable importance.

### 11.3 ECONOMIC FIGURES OF MERIT

Several economic criteria have been proposed and used for evaluating and optimizing solar energy systems, and there is no universal agreement on which should be used. This section outlines some of the possible figures of merit; two of them are discussed in more detail in following sections, and one of these, maximum life-cycle savings, is applied in later chapters on solar energy applications.

**Least cost solar energy** is a reasonable figure of merit for systems in which solar energy is the only energy resource. The system yielding least cost can be defined as that showing minimum owning and operating cost over the life of the system, considering solar energy only. However, the optimum design of a combined solar plus auxiliary energy system based on minimum total cost of delivering energy will generally be different from that based on least cost solar energy, and the use of least cost solar energy as a criterion is not recommended for systems using solar in combination with other energy sources.

**Life-cycle cost (LCC)** is the sum of all the costs associated with an energy delivery system over its lifetime or over a selected period of analysis, in today's dollars, and takes into account the time value of money. The basic idea of life-cycle costs is that anticipated future costs are brought back to present cost (discounted) by calculating how much would have to be invested at a market discount rate<sup>3</sup> to have the funds available when they will be needed. A life-cycle cost analysis includes inflation when estimating future expenses. This method can include only major cost items or as many details as may be significant. **Life-cycle savings (LCS) (net present worth)** is defined as the difference between the life-cycle costs of a conventional fuel-only system and the life-cycle cost of the solar plus auxiliary energy system. Life-cycle savings analysis is outlined in Sections 11.6 and 11.8 and is applied in later chapters to solar processes.

A special case of life-cycle savings is based on cash flow, that is, the sum of the items on the right-hand side of Equation 11.1.2. The major items of cash flow are principal payment, interest, taxes, and insurance, referred to as **PITI**; this is compared to reduction in fuel costs. Cash flow may be an important consideration in residential solar heating

---

<sup>3</sup>Market discount rate is the rate of return on the best alternative investment. See Section 11.4.


applications where the willingness of lending institutions to provide mortgage funds may be dependent on a borrower's ability to meet periodic obligations. The main impacts of solar heating will be increased mortgage payments and decreased fuel costs.

**Annualized life-cycle cost (ALCC)** is the average yearly outflow of money (cash flow). The actual flow varies with year, but the sum over the period of an economic analysis can be converted to a series of equal payments in today's dollars that are equivalent to the varying series. The same ideas apply to an **annualized life-cycle savings (ALCS)**.


**Payback time** is defined in many ways. Below are listed several which may be encountered; these are illustrated in Figure 11.3.1:

- A. The time needed for the yearly cash flow to become positive.
- B. The time needed for the cumulative fuel savings to equal the total initial investment, that is, how long it takes to get an investment back by savings in fuel. The common way to calculate this payback time is without discounting the fuel savings. It can also be calculated using discounted fuel savings.
- C. The time needed for the cumulative savings to reach zero.
- D. The time needed for the cumulative savings to equal the down payment on the solar energy system.
- E. The time needed for the cumulative solar savings to equal the remaining debt principal on the solar energy system.

The most common definition of payback time is B. Each of these payback times may have significance in view of economic objectives of various solar process users. Calculation of payback periods can be done including only major items or including many details. Care must be used in interpreting reported payback periods that the definition of the period and the items included in it are fully understood. Calculation of payback times is discussed in Section 11.8.



**Figure 11.3.1** Changes in mortgage balance, cumulative fuel savings, and cumulative savings as a function of time through the period of a life-cycle cost analysis.



**Figure 11.3.2** An example of life-cycle savings as a function of market discount rate.

**Return on investment (ROI)** is the market discount rate which results in zero life-cycle savings, that is, the discount rate that makes the present worth of solar and nonsolar alternatives equal. This is illustrated in Figure 11.3.2, which shows an example of life-cycle savings as a function of market discount rate.

## 11.4 DISCOUNTING AND INFLATION

The most complete approach to solar process economics is to use life-cycle cost methods that take into account all future expenses. This method provides a means of comparison of future costs with today's costs. This is done by discounting all anticipated costs to the common basis of present worth (or present value), that is, what would have to be invested today at the best alternative investment rate to have the funds available in the future to meet all of the anticipated expenses.

Conceptually, in a life-cycle cost analysis, all anticipated costs are tabulated and discounted to a present worth; the life-cycle cost is the sum of all of the present worths. As a practical matter, the calculations can be simplified. For example, the cash flow (net payment) for each year can be calculated and the life-cycle cost found by discounting each annual cash flow to its present value and finding the sum of these discounted cash flows. When the present values of all future costs have been determined for each of the alternative systems under consideration, including solar and nonsolar options, the system that yields the lowest life-cycle cost is selected as the most cost effective. Life-cycle costing requires that all costs be projected into the future; the results obtained from analyses of this type usually depend very much on predictions of future costs.

The reason that cash flow must be discounted lies in the "time value of money." The relationship of determining the present worth of one dollar needed  $N$  periods (usually years) in the future, with a market discount rate  $d$  (fraction per time period), is

$$PW = \frac{1}{(1 + d)^N} \quad (11.4.1)$$

Thus an expense that is anticipated to be \$1.00 in five years is equivalent to an obligation of \$0.681 today at a market discount rate of 8%. To have \$1000 available in five



years, it would be necessary to make an investment of \$681 today at an annual rate of return of 8%.

Many recurring costs can be assumed to inflate (or deflate) at a fixed percentage each period. Thus an expense of \$1.00, when inflated at a rate  $i$  per time period, will be  $1 + i$  at the end of one time period,  $(1 + i)^2$  at the end of an additional time period, and so on. If a cost  $A$  is considered to be incurred as of the end of the first time period (e.g., a fuel bill is to be paid at the end of the month or year), that recurring cost at the  $N$ th period is


$$C_N = A(1 + i)^{N-1} \quad (11.4.2)$$

Thus a cost which will be \$1.00 at the end of the first period and inflates at 6% per year will at the end of five periods be  $(1 + 0.06)^4$ , or \$1.26.

The progression of a series of payments which are expected to inflate at a rate  $i$  is shown in Figure 11.4.1. The first payment in the series is  $A$ , the second is  $B$ , and the  $N$ th is  $K$ . Here the payments are made at the ends of the periods, but some definitions assume that payments are made at the beginning of the period. The shaded portions of the bars show the present worth of the anticipated payment. At the  $N$ th period the cost is  $A(1 + i)^{N-1}$ , and the present worth of the  $N$ th cost is

$$PW_N = \frac{A(1 + i)^{N-1}}{(1 + d)^N} \quad (11.4.3)$$

This equation is useful for calculating the present worth of any one payment of a series of inflating payments. It is also useful for calculating the present worth of onetime costs that are anticipated during the period of the analysis and for which the cost at the end of the first period is known.



**Figure 11.4.1** Present worth of a geometric series of inflating payments. Each payment is made at the end of a period. The bars show both the payment and the present worth of the payment.

**Example 11.4.1**

- a** A fuel cost is expected to inflate at the rate of 7% per year and for the first year is \$400 (payable at the end of the year). The market discount rate is 10% per year. What is the present worth of the payment to be made at the end of the third year?
- b** It is expected that the blower in an air heater system will need to be replaced at the end of 10 years. The cost in the first year (payable at the end of the year) would be \$300. Under the same assumption of inflation and discount rates, what is the present worth of replacing the blower?

**Solution**

- a** Using Equation 11.4.3, the present worth of the third-year fuel payment is

$$PW_3 = \frac{400(1.07)^2}{(1.10)^3} = \$344$$

- b** The present worth of the blower replacement after 10 years is

$$PW_{10} = \frac{300(1.07)^9}{(1.10)^{10}} = \$213$$

■

The analyses and examples in this chapter are all based on the premise that the costs are known and payable at the end of the first time period. If a cost  $A'$  is known as of the beginning of the first time period, Equation 11.4.2 becomes

$$C_N = A'(1+i)^N \quad (11.4.4)$$

and Equation 11.4.3 becomes

$$PW_N = A' \left( \frac{1+i}{1+d} \right)^N \quad (11.4.5)$$

**11.5 PRESENT-WORTH FACTOR**

In the previous section we dealt with calculating the present worth of a single future payment. If an obligation recurs each year and inflates at a rate  $i$  per period, a present-worth factor,  $PWF$ , of the series of  $N$  such payments can be found by summing Equation 11.4.3 over  $N$  periods:

$$PWF(N, i, d) = \sum_{j=1}^N \frac{(1+i)^{j-1}}{(1+d)^j} = \begin{cases} \frac{1}{d-i} \left[ 1 - \left( \frac{1+i}{1+d} \right)^N \right] & \text{if } i \neq d \\ \frac{N}{i+1} & \text{if } i = d \end{cases} \quad (11.5.1)$$

If the function  $PWF$  of Equation 11.5.1 is multiplied by the first of a series of payments that are made at the end of the periods, the result is the sum of  $N$  such payments discounted to the present with a discount rate  $d$ . This is represented by the sum of the cross-hatched bars in Figure 11.4.1. This function is available in the EES SETP library.

**Example 11.5.1**

What is the present worth of a series of 20 yearly payments, the first of which is \$500, which are expected to inflate at the rate of 8% per year if the market discount rate is 10% per year?

**Solution**

From Equation 11.5.1,

$$PW = 500 \frac{1}{0.10 - 0.08} \left[ 1 - \left( \frac{1.08}{1.10} \right)^{20} \right] = 500 \times 15.35892 = \$7679$$

or, from EES the present-worth factor for  $N = 20$ ,  $i = 0.08$ , and  $d = 0.10$  is 15.359, and the present worth of the series is  $15.359 \times 500 = \$7680$ . ■

The present-worth factor defined in Equation 11.5.1 can be used to find the periodic loan payment on a fixed-rate mortgage which involves a series of  $N_L$  equal payments over the lifetime of the loan. Since all mortgage payments are equal, we have a series of payments with an inflation rate of zero. The discount rate in Equation 11.5.1 becomes the mortgage interest rate. Thus the periodic loan payment<sup>4</sup> is

$$\text{Periodic payment} = \frac{M}{PWF(N_L, 0, m)} \quad (11.5.2)$$

where  $m$  is the mortgage interest rate,  $N_L$  is the period of the mortgage, and  $M$  is the mortgage principal.

**Example 11.5.2**

What is the annual payment and yearly interest charge if an \$11,000 solar installation is to be financed by a 10% down payment with the balance borrowed at an annual interest rate of 9% for 20 years? The payments are to be made at the end of the year. The market discount rate is 8%. What is the present worth of the series of interest payments?

**Solution**

The present-worth factor is used in Equation 11.5.2 to calculate the annual payment. The present worth of the sum of all payments is the mortgage, or  $0.9 \times 11,000 = \$9900$ . The yearly payment is

$$\frac{9900}{PWF(20, 0, 0.09)} = \frac{9900}{9.12855} = 1084.51$$

The interest charge varies with time, since the mortgage payment includes a principal payment and interest. In this example, the interest for the first year is  $0.09 \times 9900 = \$891.00$ .

<sup>4</sup>In this and following sections the examples are based on periods of a year. The identical principles and methods hold for monthly (or other) periods. Interest, inflation, and discount rates must correspond to the time period used.

The payment is \$1084.51, so the principal is reduced by \$193.51 (i.e.,  $1084.51 - 891.00$ ) to \$9706.49. The second year's interest is  $0.09 \times 9706.49 = \$873.58$  and the principal is reduced by \$210.93 to \$9495.56. This progression of payments, remaining principal, interest payment, and present worth of the interest payment is shown in the following table (to the nearest dollar):

Year	Mortgage Payment	Remaining Principal	Interest Payment	Present Worth of Interest Payment
1	1084	9707	891	825
2	1084	9496	874	749
3	1084	9266	855	678
4	1084	9015	834	613
$\vdots$	$\vdots$	$\vdots$	$\vdots$	$\vdots$
20	1084	0	90	19
Total present worth of interest payments				\$6730

■

The total present worth of all of the mortgage interest payments can be calculated as in Example 11.5.2, but it is tedious. Present-worth factors can be used to obtain this total by the equation

$$PW_{\text{int}} = M \left[ \frac{PWF(N_{\min}, 0, d)}{PWF(N_L, 0, m)} + PWF(N_{\min}, m, d) \left( m - \frac{1}{PWF(N_L, 0, m)} \right) \right] \quad (11.5.3)$$

where  $M$  is the initial mortgage principal,  $N_L$  is the term of the mortgage,  $N_e$  is the term of economic analysis,  $N_{\min}$  is the lesser of  $N_L$  or  $N_e$ ,  $m$  is the mortgage interest rate, and other terms are as previously defined. Note that it is not necessary that the term of the economic analysis coincide with the term of the mortgage.

### Example 11.5.3

Calculate the total present worth of all of the mortgage interest payments in Example 11.5.2 over the term of the mortgage.

#### Solution

Here  $N_L = N_e = 20$ ,  $m = 0.09$ , and  $d = 0.08$ . The  $PWF$  values can be calculated from Equation 11.5.1 or they can be obtained from EES. Using Equation 11.5.3,

$$PW_{\text{int}} = 9900 \left[ \frac{9.818}{9.129} + 20.242 \left( 0.09 - \frac{1}{9.129} \right) \right] = \$6731$$

This is in agreement with the value obtained by summing the individual present worths in Example 11.5.2. ■

## 11.6 LIFE-CYCLE SAVINGS METHOD

The previous two sections dealt with discounting of future costs. Now these ideas are applied in a series of examples to illustrate the principles and steps in life-cycle savings analysis. The first two examples are for fuel payments for a conventional process. The next is a calculation of solar savings, the difference in present worth of a solar-plus-fuel system and the fuel-only system. The last is a calculation of optimum system design based on solar savings calculations for several collector areas.<sup>5</sup>

These examples are intended to illustrate the method, and the particular costs used are not intended to have significance. These costs vary widely from one location to another, with time, as state and federal legislation is enacted which impacts the costs of solar equipment, and as international developments occur which affect the prices of energy.

### Example 11.6.1

For a nonsolar process using fuel only, calculate the present worth of the fuel cost over 20 years if the first year's cost is \$1255 (i.e., 125.5 GJ at \$10.00/GJ). The market discount rate is 8% per year and the fuel cost inflation rate is 10% per year.

#### *Solution*

A tabulation of the yearly progression of fuel costs and their present worth follows. Each year's fuel cost is the previous year's cost multiplied by  $1 + i$ . Each item in the present-worth column is calculated from the corresponding item in the fuel cost column using Equation 11.4.1. The same result is obtained by multiplying the first year's fuel cost by  $\text{PWF}(20, 0.10, 0.08)$ .

Year	Fuel Cost	Present Worth of Fuel Cost
1	1,255	1,162
2	1,381	1,183
3	1,519	1,206
$\vdots$	$\vdots$	$\vdots$
20	7,675	1,647
Total present worth of fuel cost =		\$27,822



The next example also shows a calculation of the present worth of a series of fuel costs, but in this case the costs of fuel are expected to inflate at rates dependent on time. It illustrates the general principle that costs need not be expected to change at fixed rates. The variation can be anything from nil to completely irregular; the basic ideas of life-cycle cost hold whether payments are regular or otherwise.

<sup>5</sup>Section 11.8 shows an additional and more convenient way of approaching these same calculations.

**Example 11.6.2**

For a nonsolar process, using fuel only, calculate the present worth of fuel cost over eight years if the first year's cost is \$1200, it inflates at 10% per year for three years, and then it inflates at 6% per year. The market discount rate is 8% per year.

**Solution**

A tabulation of the yearly progression of fuel costs and their present worth follows. As in the previous example, each item in the present-worth column is calculated from the corresponding item in the fuel cost column using Equation 11.4.1. In this example, the sum of the expected payments is 43% more than the present worth of the payments. Note that the present worths increase during the time when  $i > d$  and decrease when  $i < d$ .

Year	Fuel Cost	Present Worth of Fuel Cost
1	1,200	1,111
2	1,320	1,132
3	1,452	1,153
4	1,597	1,174
5	1,693	1,152
6	1,795	1,131
7	1,902	1,110
8	<u>2,016</u>	<u>1,089</u>
Total	12,975	9,052

**Alternate Solution**

This example can also be solved using present-worth factors by considering the series to be in two sets, one at each of the inflation rates. Part of the present worth is that of the first set of four payments, the first of which is \$1200 and which inflate at 10%. The other part is the present worth of the next four, which inflate at 6% per year. From Equation 11.5.1,

$$PWF(4, 0.10, 0.08) = \frac{1}{0.08 - 0.10} \left[ 1 - \left( \frac{1.10}{1.08} \right)^4 \right] = 3.808$$

The present worth of this first set is thus  $1200 \times 3.808 = \$4569$ .

The second set starts at the beginning of the fifth year, when  $i = 6\%$  per year. The initial payment in this set is  $A'$ , the fifth-year payment. To find  $A'$ , the initial payment is inflated three times by 1.10 and once by 1.06. Thus

$$A' = 1200(1.10)^3 (1.06) = \$1693$$

The  $PWF$  for this part of the series as of the beginning of year 5 is

$$PWF(4, 0.06, 0.08) = \frac{1}{0.08 - 0.06} \left[ 1 - \left( \frac{1.06}{1.08} \right)^4 \right] = 3.602$$

The second set in the series is then discounted to the present by

$$PW = \frac{3.602 \times 1693}{(1.08)^4} = \$4482$$

The sum of the present worths of the two sets is  $4569 + 4482 = \$9051$ . ■

With either Equation 11.4.1 or 11.5.1 it is possible to discount any future cost or series of costs to a present worth. In the same way, future savings (negative costs) can be discounted to a present worth. In the following examples we apply these methods to systems using combined solar and auxiliary (conventional) sources.

### Example 11.6.3

A combined solar and fuel system to meet the same energy need as in Example 11.6.1 is to be considered. The proposed collector and associated equipment will supply energy so as to reduce fuel purchase by 56%, will cost \$11,000, and will be 90% financed over 20 years at an interest rate of 9%. The first year's fuel cost for a system without solar would be \$1255. Fuel costs are expected to rise at 10% per year. It is expected that the equipment will have a resale value at the end of 20 years of 40% of the original cost.

In the first year, extra insurance, maintenance, and parasitic energy costs are estimated to be \$110. Extra property tax is estimated to be \$220. These are expected to rise at a general inflation rate of 6% per year. Extra property taxes and interest on mortgage are deductible from income for tax purposes; the effective income tax rate is expected to be 45% through the period of the analysis.

What is the present worth of solar savings for this process over a 20-year period if the market discount rate is 8%?

### Solution

The table that follows shows the incremental yearly costs and savings. Year 1 includes the estimates of the first year's costs as outlined in the problem statement. The annual payment on the \$9900 mortgage is calculated as  $9900/PWF(20, 0, 0.09)$ , or \$1084.46. The entries in the tax savings column are calculated by Equation 11.1.3; for example, in year 1

$$\text{Interest} = 0.09(9900) = \$891.00$$

$$\text{Principal payment} = 1084.46 - 891.00 = \$193.46$$

$$\text{Principal balance} = 9900 - 193.46 = \$9706.54$$

$$\text{Tax savings} = 0.45(891.00 + 220) = \$500.00$$

and in year 2

$$\text{Interest} = 0.09(9706.54) = \$873.59$$

$$\text{Principal payment} = 1084.46 - 873.59 = \$210.87$$

$$\text{Principal balance} = 9706.54 - 210.87 = \$9495.67$$

$$\text{Tax savings} = 0.45(873.59 + 220(1.06)) = \$498.06$$

Solar savings for each year are the sums of the items in columns 2 through 6. Each year's solar savings is brought to a present worth using a market discount rate of 8%. The down payment is \$1100 and is entered in the table in year 0, that is, now; it is a negative present worth in solar savings. The resale value of \$4400 in year 20 is shown as a second entry in year 20 and is positive as it contributes to savings. The sum of the last column, \$4203, is the total present worth of the gains from the solar energy system compared to the fuel-only system, and is termed life-cycle solar savings or simply solar savings.

Year	Fuel Savings	Extra Mortgage Payment	Extra Insurance Maintenance Energy	Extra Property Tax	Income Tax Savings	Solar Savings	Present Worth of Solar Savings
0	—	—	—	—	—	−1100	−1100
1	703	−1084	−110	−220	500	−211	−195
2	773	−1084	−117	−233	498	−163	−140
3	850	−1084	−124	−247	496	−109	−87
4	935	−1084	−131	−262	493	−49	−36
5	1029	−1084	−139	−278	490	18	12
⋮	⋮	⋮	⋮	⋮	⋮	⋮	⋮
20	4298	−1084	−333	−666	340	2555	548
20						4400	944
Total present worth of solar savings = \$4203							

Another approach to this problem is to do a life-cycle cost analysis of both the solar and the nonsolar systems. The difference in the present worth of the two systems (i.e., the difference in the life-cycle costs) is the life-cycle solar savings. More information is needed to do the analyses separately if they are to be complete, as equipment common to both systems should be included. In the calculation of Example 11.6.3 common costs do not influence life-cycle solar savings.

In the previous examples, collector area (i.e., system cost) and annual fraction of loads met by solar were given. In Example 11.6.4, the relationship between solar fraction  $\mathcal{F}$  and the area from thermal performance calculations is given, as are  $C_A$  and  $C_E$ , and the life-cycle solar savings are calculated for various sizes of solar energy systems to find the collector size (combination of solar and auxiliary) which provides the highest savings.

#### Example 11.6.4

A thermal analysis of the process of Example 11.6.3 indicates a relationship between collector area and solar fraction  $\mathcal{F}$  as indicated in the first two columns of the table that follows. Area-dependent costs are \$200/m<sup>2</sup> and fixed cost is \$1000. All economic parameters are as in Example 11.6.3. What is the optimum collector area which shows the maximum life-cycle solar savings relative to the fuel-only system?


#### Solution

The costs of the solar energy system are calculated by Equation 11.1.1, with  $C_A = \$200/\text{m}^2$  and  $C_E = \$1000$ . The third column of the table below indicates the total system cost.



Calculations of the kind shown in Example 11.6.3 give column 4, life-cycle solar savings, as a function of collector area. A calculation is made for a very small collector area, where the cost of the system is essentially  $C_E$ , to establish the “zero area” solar savings. The solar savings of column 4 are plotted in the figure. The maximum savings are realized at a collector area of about  $39 \text{ m}^2$ , and positive savings are realized over an area range of approximately 3 to  $110 \text{ m}^2$ .

Area ( $\text{m}^2$ )	Solar Fraction $\mathcal{F}$	Installed Cost	Solar Savings
0.01	0	1,000	-1,036
25	0.37	6,000	4,088
39	0.49	8,800	4,531
50	0.56	11,000	4,203
75	0.71	21,000	3,204
150	0.92	31,000	-6,468



These examples show only regularly varying costs. All anticipated costs can be included, whether they are recurring, regularly varying, or however they may be incurred. The method, in essence, is to construct a table such as that in Example 11.6.3 and sum the last column. Nonrecurring items such as expected replacement covers in years hence, changes in income tax bracket, or other increments can be included in the present-worth calculation, as were the down payment and resale value in the examples. Example 11.6.3 shows expenses of types associated with non-income-producing applications. Income-producing applications will require that additional terms be taken into account, for example, depreciation.

The assumptions made in these examples are not to be construed as representative or typical of situations that may be encountered. They are intended only to illustrate the methods of calculation. Consideration of the results of these examples, and those in following sections, indicates that the end results, the solar savings, are very sensitive<sup>6</sup> to the assumptions made in the calculations.

<sup>6</sup>Calculation of the sensitivity of solar savings to economic assumptions is discussed in Section 11.9.

## 11.7 EVALUATION OF OTHER ECONOMIC INDICATORS

The principles of the preceding sections can be used to find payback times. Payback time B (Section 11.3) is the time needed for the cumulative fuel savings to equal the total initial investment in the system. Consider first the case where fuel savings are not discounted. The fuel saved in year  $j$  is given by  $\mathcal{F}L C_{F1}(1 + i_F)^{j-1}$ , where  $\mathcal{F}L$  is the energy saved,  $C_{F1}$  is the first period's unit energy cost delivered from fuel,<sup>7</sup> and  $i_F$  is the fuel cost inflation rate. Summing these over the payback time  $N_p$  and equating to the initial investment as given by Equation 11.1.1,

$$\sum_{j=1}^{N_p} \mathcal{F}L C_{F1} (1 + i_F)^{j-1} = C_S \quad (11.7.1)$$

Summing the geometric series

$$\frac{\mathcal{F}L C_{F1} [(1 + i_F)^{N_p} - 1]}{i_F} = C_S \quad (11.7.2)$$

This can be solved for  $N_p$ , the payback period:

$$N_p = \frac{\ln \left[ \frac{C_S i_F}{\mathcal{F}L C_{F1}} + 1 \right]}{\ln (1 + i_F)} \quad (11.7.3)$$

The present-worth factors can also be used to find this payback period. The sum of the fuel savings is the first year's saving,  $\mathcal{F}L C_{F1}$ , times the *PWF* at zero discount rate:

$$\mathcal{F}L C_{F1} \times PWF(N_p, i_F, 0) = C_S \quad (11.7.4)$$

The value of  $N_p$  can be found for which  $PWF = C_S / \mathcal{F}L C_{F1}$ .

### Example 11.7.1

What is the undiscounted payback time B for an \$11,000 investment in solar energy equipment which meets 56% of an annual load of 156 GJ? The first-year fuel cost is \$8.00/GJ and is expected to inflate at 10% per year.

#### Solution

Using Equation 11.7.3,

$$N_p = \frac{\ln \left[ \frac{11,000 \times 0.10}{0.56 \times 156 \times 8} \right]}{\ln (1.10)} = 9.9 \text{ years}$$

■

<sup>7</sup>The energy delivered from a unit of fuel is the product of the fuel heating value times the furnace efficiency. Custom in the U.S. is to use the fuel higher heating value in defining furnace efficiency. Common practice in some countries is to use the lower heating value.

By similar procedures it is possible to equate discounted fuel costs to initial investment. If fuel costs are discounted, an equation like 11.7.4 can be written

$$PWF(N_p, i_F, d) = \frac{C_S}{\mathcal{F}LC_{F1}} \quad (11.7.5)$$

and the appropriate value of  $N_p$  can be found (where  $i_F \neq d$ ) from

$$N_p = \frac{\ln \left[ \frac{C_S (i_F - d)}{\mathcal{F}LC_{F1}} + 1 \right]}{\ln \left( \frac{1 + i_F}{1 + d} \right)} \quad (11.7.6)$$

and (if  $i_F = d$ ) from

$$N_p = \frac{C_S (1 + i_F)}{\mathcal{F}LC_{F1}} \quad (11.7.7)$$

### Example 11.7.2

Repeat Example 11.7.1 but discount future fuel costs at a rate of 8% per year.

#### Solution

Using Equation 11.7.6,

$$N_p = \frac{\ln \left[ \frac{11,000 (0.10 - 0.08)}{0.56 \times 156 \times 8} + 1 \right]}{\ln \left( \frac{1 + 0.10}{1 + 0.08} \right)} = 14.9 \text{ years}$$

■

Other payback times are defined in Section 11.3 in terms of cumulative savings. For these it is necessary to use Equation 11.1.7, including in the equation whatever terms are significant, calculating the solar savings each year, and finding the year in which the cumulative savings meet whatever criteria are established for the particular payback time desired. Table 11.7.1 shows information from Example 11.6.3 and illustrates the several payback periods defined in Section 11.3.

- A. The solar savings become positive (and the cumulative solar savings reach a minimum) by year 5.
- B. The undiscounted cumulative fuel savings exceed the total initial investment in year 10. This is in agreement with Example 11.7.1. (The time for the cumulative discounted fuel savings to reach the initial investment cannot be determined from this table but is obtained as shown in Example 11.7.2.)
- C. The cumulative solar savings reach zero during year 10.
- D. The cumulative solar savings exceed the remaining debt principal (mortgage balance) by the end of year 15.
- E. The cumulative solar savings exceed the down payment of \$1100 by year 12.

**Table 11.7.1** Mortgage Balance, Fuel Savings, Cumulative Fuel Savings, Solar Savings, and Cumulative Solar Savings from Example 11.6.4

Year	Mortgage Balance	Fuel Savings	Cumulative Fuel Savings	Solar Savings	Cumulative Solar Savings
				−1,100	−1,100
1	9,707	703	703	−211	−1,311
2	9,496	773	1,476	−163	−1,474
3	9,266	850	2,326	−109	−1,583
4	9,105	935	3,261	−49	−1,632
5	8,742	1,029	4,290	18	−1,614
6	8,445	1,132	5,422	94	−1,520
7	8,120	1,245	6,667	175	−1,345
8	7,766	1,370	8,037	268	−1,077
9	7,381	1,570	9,607	369	−708
10	6,961	1,657	11,264	481	−227
11	6,503	1,823	13,087	607	380
12	6,004	2,005	15,092	745	1,125
13	5,459	2,206	17,298	900	2,025
14	4,866	2,426	19,724	1,070	3,095
15	4,220	2,669	22,393	1,260	4,355
16	3,513	2,936	25,329	1,469	5,824
17	2,747	3,229	28,558	1,701	7,525
18	1,910	3,552	32,110	1,958	9,483
19	997	3,907	36,017	2,241	11,724
20	—	4,298	40,315	2,550	14,274
	Resale value			4,400	
	Undiscounted savings including resale value			\$18,674	

Annual cash flow (or savings) varies with years (as shown in the next to the last column of the tabulation of results in Example 11.6.3). These costs can be “annualized” or “levelized” by determining the equal payments that are equivalent (in present dollars) to the varying series. The annualized life-cycle cost and annualized life-cycle savings are determined from

$$ALCC = \frac{LCC}{PWF(N_e, 0, d)} \quad (11.7.8)$$

$$ALCS = \frac{LCS}{PWF(N_e, 0, d)} \quad (11.7.9)$$

Thus the annualized life-cycle savings in Example 11.6.3 are

$$ALCS = \frac{4203}{PWF(20, 0, 0.08)} = \$428 \text{ per year}$$

The series of variable savings is equivalent to annual savings of \$428 in today's dollars. (An annualized cost per unit of delivered solar energy can also be calculated. It is necessary to divide annualized life-cycle cost by the total annual load.)

The return on investment of a solar process may be found by determining the market discount rate  $d_o$  which corresponds to zero life-cycle solar savings. This can be done by trial and error, by plotting  $LCS$  versus  $d$  to find  $d_o$  at  $LCS = 0$ . For the 39 m<sup>2</sup>-optimum area of Example 11.6.4, variation of  $d$  results in a plot of  $LCS$  versus  $d$  as shown in Figure 11.3.2. The return on investment under these circumstances is about 21%. (Note that maximizing the return on investment does not lead to the same area as maximizing solar savings.)

## 11.8 THE $P_1, P_2$ METHOD

It is possible to view the calculations of Example 11.6.3 in a different way, by obtaining the present worth of each of the columns and summing these (with appropriate signs) to get the present worth of the solar savings. The life-cycle costs of insurance, maintenance and parasitic power, property taxes, and mortgage payments and the life-cycle fuel savings are determined with the appropriate present-worth factors. The life-cycle benefit of tax savings can be determined by multiplying the present-worth factor for property taxes by the effective income tax rate. This view of the calculation is shown in Example 11.8.1. In this example, we use several new symbols:

$\bar{t}$  Effective federal-state income tax bracket from Equation 11.1.5

$MS_1$  Miscellaneous costs (maintenance, insurance, parasitic power) payable at the end of the first period.

$PT_1$  Property tax payable at the end of the first period

### Example 11.8.1

Redo Example 11.6.3 by obtaining the life-cycle costs of each of the columns in the table in that example and summing them to get the solar savings.

#### Solution

The present worth of the fuel savings is given by

$$\mathcal{F}LC_{F1} \times PWF(N_e, i_F, d) = 703 \times 22.1687 = \$15,585$$

The present worth of the series of mortgage payments is

$$-M \times PWF(N_L, 0, d) = -1084 \times 9.8181 = -\$10,643$$

The present worth of the miscellaneous costs is given by

$$-MS_1 \times PWF(N_e, i, d) = -110 \times 15.5957 = -\$1716$$

The present worth of the extra property tax is

$$-PT_1 \times PWF(N_e, i, d) = -220 \times 15.5957 = -\$3431$$

The present worth of the income tax savings on the interest paid on the mortgage is  $\bar{i}$  times the present worth of the series of interest payments. From Equation 11.5.3,

$$0.45 \times 9900 \left[ \frac{9.818}{9.129} + 20.242 \left( 0.09 - \frac{1}{9.129} \right) \right] = \$3028$$

The present worth of the income tax savings due to the property taxes is  $\bar{i}$  times the present worth of the extra property tax:

$$\bar{i} \times PT_1 \times PWF(N_e, i, d) = 0.45 \times 220 \times 15.5957 = \$1544$$

The down payment is \$1100. The present worth of the estimated resale value is  $4400/(1.08)^{20} = \$944$ . Thus the solar savings are

$$15,585 - 1716 - 10,643 - 3431 + 3028 + 1544 - 1100 + 944 = \$4211$$

Within round-off errors, this is the same result as that of Example 11.6.3. ■

An examination of the terms in the savings calculation of Example 11.8.1 suggests that a general formulation of solar savings can be developed. Two facts are apparent. First, there is one term that is directly proportional to the first year's fuel savings. Second, the remainder of the terms are all related directly to the initial investment in the system (or to the mortgage, which in turn is a fraction of the initial investment). Using these facts, Brandemuehl and Beckman (1979) have shown how the present-worth factors in terms such as those in Example 11.8.1 can be combined to a simple formulation for life-cycle solar savings<sup>8</sup>:

$$LCS = P_1 C_{F1} L_{\mathcal{F}} - P_2 (C_A A_c + C_E) \quad (11.8.1)$$

where  $P_1$  is the ratio of the life-cycle fuel cost savings to the first-year fuel cost savings and  $P_2$  is the ratio of the life-cycle expenditures incurred because of the additional capital investment to the initial investment. Other terms are as defined previously.

Any costs that are proportional to the first-year fuel cost can be included in the analysis by appropriate determination of  $P_1$ , and any costs that are proportional to the investment can be included in  $P_2$ . Thus the full range of costs noted in the examples of Section 11.6 can be included as needed. The ratio  $P_1$  is given by

$$P_1 = (1 - C\bar{i})PWF(N_e, i_F, d) \quad (11.8.2)$$

---

<sup>8</sup>Equation 11.8.1 is written with the implicit assumption that the loads are independent of the size of the solar energy system. To calculate life-cycle savings where there are significant differences between loads with solar and loads without solar, the first term of the equation can be written in terms of the difference in auxiliary energy required, or  $P_1 C_{F1} (L_o - L_A)$ .

where  $C$  is a flag indicating income producing or nonincome producing (1 or 0, respectively),  $i_F$  is the fuel inflation rate, and  $d$  is the discount rate. The ratio  $P_2$  is calculated by

$$\begin{aligned}
 P_2 = & D + (1 - D) \frac{PWF(N_{\min}, 0, d)}{PWF(N_L, 0, m)} \\
 & - \bar{t}(1 - D) \left[ PWF(N_{\min}, m, d) \left( m - \frac{1}{PWF(N_L, 0, m)} \right) \right. \\
 & \quad \left. + \frac{PWF(N_{\min}, 0, d)}{PWF(N_L, 0, m)} \right] \\
 & + M_S(1 - C\bar{t}) \times PWF(N_e, i, d) + tV(1 - \bar{t}) \times PWF(N_e, i, d) \\
 & - \frac{C\bar{t}}{N_D} PWF(N'_{\min}, 0, d) - \frac{R_v}{(1 + d)^{N_e}} (1 - C\bar{t}) \quad (11.8.3)
 \end{aligned}$$

where  $m$  = annual mortgage interest rate

$i$  = general inflation rate

$N_e$  = period of economic analysis

$N_L$  = term of loan

$N_{\min}$  = years over which mortgage payments contribute to analysis (usually minimum of  $N_e$  or  $N_L$ )

$N'_{\min}$  = years over which depreciation contributes to analysis (usually minimum of  $N_e$  or  $N_D$ )

$N_D$  = depreciation lifetime in years

$t$  = property tax rate based on assessed value

$\bar{t}$  = effective income tax rate (from Equation 11.1.5)

$D$  = ratio of down payment to initial investment

$M_S$  = ratio of first-year miscellaneous costs (insurance and maintenance) to initial investment

$V$  = ratio of assessed valuation of solar energy system in first year to initial investment in system

$R_v$  = ratio of resale value at end of period of analysis to initial investment

In this equation the first term on the right represents the down payment. All other terms represent life-cycle costs of payments or series of payments, are in proportion to the initial investment, and are as follows: The second term represents the life-cycle cost of the mortgage principal and interest; the third, income tax deductions of the interest; the fourth, miscellaneous costs such as insurance and maintenance; the fifth, net property tax costs (tax paid less income saved); the sixth, straight-line depreciation tax deduction<sup>9</sup>; and the

<sup>9</sup>Straight-line depreciation is assumed in Equation 11.8.3. For  $N'_{\min} > N_D$ , the sixth term for double declining-balance or sum of digits [from Barley and Winn (1978)] may be written as

$$\begin{aligned}
 DDB &= C\bar{t} + \frac{2\bar{t}}{N_D} \left[ PWF(N_D - 1, -2/N_D, d) - \frac{PWF(N_D - 1, -2/N_D, 0)}{(1 + d)^{N_D}} \right] \\
 SOD &= \frac{2C\bar{t}}{N_D(N_D + 1)} \left[ PWF(N_D, 0, d) + \frac{N_D - 1 - PWF(N_D - 1, 0, d)}{d} \right]
 \end{aligned}$$

seventh, present worth of resale value at the end of the period of the economic analysis. Terms may be added to or deleted from  $P_2$  as appropriate.

The contributions of loan payments to the analysis depend on  $N_L$  and  $N_e$ . If  $N_L \leq N_e$ , all  $N_L$  payments will contribute. If  $N_L \geq N_e$ , only  $N_e$  payments would be made during the period of the analysis. Accounting for loan payments past  $N_e$  depends on the rationale for choosing  $N_e$ . If  $N_e$  is a period over which the discounted cash flow is calculated without regard for costs outside of the period, then  $N_{\min} = N_e$ . If  $N_e$  is the expected operating life of the system and all payments are expected to continue as scheduled, then  $N_{\min} = N_L$ . If  $N_e$  is chosen as the time to anticipated sale of the facility, the remaining loan principal at  $N_e$  would be repaid at that time, and the life-cycle mortgage cost would consist of the present worth of  $N_e$  loan payments plus the principal balance in year  $N_e$ . The principal balance would then be deducted from the resale value.

Similar arguments can be made about the period over which depreciation deductions contribute to an analysis if the facility is part of a business (i.e., is income producing). The contributions will depend on the relationship of  $N_D$  and  $N_e$ .

The equations of  $P_1$  and  $P_2$  include only present-worth factors and ratios of payments to initial investments in the system. They do not include collector area or solar fraction. As  $P_1$  and  $P_2$  are independent of  $A_c$  and  $\mathcal{F}$ , systems in which the primary design variable is  $A_c$  can be optimized by use of Equation 11.8.1. At the optimum, the derivative of the savings with respect to collector area is zero:

$$\frac{\partial LCS}{\partial A_c} = 0 = P_1 C_{F1} L \frac{\partial \mathcal{F}}{\partial A_c} - P_2 C_A \quad (11.8.4)$$

Rearranging, the maximum savings are realized when the relationship between collector area and solar load fraction satisfies

$$\frac{\partial \mathcal{F}}{\partial A_c} = \frac{P_2 C_A}{P_1 C_{F1} L} \quad (11.8.5)$$

The relationship of the optimum area to the annual thermal performance curve is shown in Figure 11.8.1.

### Example 11.8.2


Redo Example 11.6.4 using the  $P_1$ ,  $P_2$  method.

#### Solution

The installation is not an income-producing one so  $C = 0$ . The ratio  $P_1$  is calculated from Equation 11.8.2:

$$P_1 = PWF(20, 0.10, 0.08) = 22.169$$





**Figure 11.8.1** Optimum collector area determination from the slope of the  $\mathcal{F}$  versus  $A_c$  thermal performance curve. From Brandemuehl and Beckman (1979).


The ratio  $P_2$  is calculated from Equation 11.8.3:

$$\begin{aligned}
 P_2 &= 0.1 + 0.9 \frac{PWF(20, 0, 0.08)}{PWF(20, 0, 0.09)} \\
 &\quad - 0.9 \times 0.45 \left[ PWF(20, 0.09, 0.08) \left( 0.09 - \frac{1}{PWF(20, 0, 0.09)} \right) \right. \\
 &\quad \quad \left. + \frac{PWF(20, 0, 0.08)}{PWF(20, 0, 0.09)} \right] \\
 &\quad + 0.01 \times PWF(20, 0.06, 0.08) \\
 &\quad + 0.02 \times 0.55 \times 1.0 \times PWF(20, 0.09, 0.08) - \frac{0.4}{(1.08)^{20}} \\
 &= 0.1 + 0.986 - 0.275 + 0.156 + 0.172 - 0.086 = 1.035
 \end{aligned}$$

From Equation 11.8.5, with  $C_A = \$200/\text{m}^2$  and  $C_{F1}L = \$1255$ ,

$$\frac{\partial \mathcal{F}}{\partial A_c} = \frac{1.035 \times 200}{22.169 \times 1255} = 0.00744$$

A plot of the  $\mathcal{F}$ -versus- $A_c$  data from Example 11.6.4 is shown in the figure. The optimum collector area, where the slope is 0.00744, is about  $40 \text{ m}^2$ .



The  $P_1$ ,  $P_2$  method is not limited to regularly varying costs. The requirements are for  $P_1$  that the fuel expenses be proportioned to the first-year unit energy cost and for  $P_2$  that the owning costs be proportioned to the initial investment. For the irregularly varying fuel costs of Example 11.6.2 the value of  $P_1$  can be found from the ratio of the life-cycle fuel cost to the first-year fuel cost, that is,  $P_1 = 9052/1200 = 7.543$ . This value of  $P_1$  can be used with any other first-year fuel cost that has the same inflation rate schedule as Example 11.6.2. Also  $P_1$  and  $P_2$  can be obtained from a single detailed calculation of life-cycle savings such as that in Example 11.6.3 and can then be applied to all collector areas and solar fractions. If there are highly irregular costs, this may be the easiest way to determine  $P_1$  and  $P_2$ .

The  $P_1$ ,  $P_2$  method is quick, convenient, and extremely useful. It is used in developing economic evaluations of specific applications in later chapters.

## 11.9 UNCERTAINTIES IN ECONOMIC ANALYSES

Many assumptions and uncertainties are involved in the use of the economic analysis methods presented in this chapter. The analyst must make estimates of many economic parameters with varying degrees of uncertainty. In particular, the projection of future energy costs is difficult in view of unsettled international energy affairs. Thus it is desirable to determine the effects of uncertainties on the calculated values of life-cycle savings and optimum system design.

For a given set of conditions, the change in life-cycle savings resulting from a change in a particular parameter,  $\Delta x_j$ , can be approximated by

$$\Delta LCS = \frac{\partial LCS}{\partial x_i} \Delta x_i = \frac{\partial}{\partial x_i} [P_1 C_{F1} L \mathcal{F} - P_2 (C_A + C_E)] \Delta x_i \quad (11.9.1)$$

When there are uncertainties in more than one variable, the maximum possible uncertainty is given by

$$\Delta LCS = \sum_{i=1}^n \left| \frac{\partial LCS}{\partial x_i} \right| \Delta x_i \quad (11.9.2)$$

A “most probable” uncertainty in savings can be written as

$$\Delta LCS_{\text{prob}} = \left[ \sum_{i=1}^n \left( \frac{\partial LCS}{\partial x_i} \Delta x_i \right)^2 \right]^{1/2} \quad (11.9.3)$$

From Equation 11.9.1,

$$\frac{\partial LCS}{\partial x_i} = \frac{\partial (P_1 C_{F1} L_{\mathcal{F}})}{\partial x_i} - \frac{\partial [P_2 (C_A A_c + C_E)]}{\partial x_i} \quad (11.9.4)$$

The partial derivatives of  $P_1$  and  $P_2$  (from Equation 11.8.2 and 11.8.3) for selected variables are as follows:

For the fuel inflation rate

$$\frac{\partial P_1}{\partial i_F} = (1 - C\bar{t}) \frac{\partial PWF(N_i, i_F, d)}{\partial i_F} \quad (11.9.5)$$

For the general inflation rate

$$\frac{\partial P_2}{\partial i} = [(1 - C\bar{t})M_s + (1 - \bar{t})tV] \frac{\partial PWF(N_e, i, d)}{\partial i} \quad (11.9.6)$$

For the effective income tax bracket

$$\frac{\partial P_1}{\partial \bar{t}} = -C \times PWF(N_e, i_F, d) \quad (11.9.7)$$

$$\begin{aligned} \frac{\partial P_2}{\partial \bar{t}} = & -(1 - D) \left[ PWF(N_{\min}, m, d) \left( m - \frac{1}{PWF(N_L, 0, m)} \right) \right. \\ & \left. + \frac{PWF(N_{\min}, 0, d)}{PWF(N_L, 0, m)} \right] \\ & - (tV)PWF(N_e, i, d) - C \left[ M_s PWF(N_e, i, d) + \frac{PWF(N'_{\min}, 0, d)}{N_D} \right] \end{aligned} \quad (11.9.8)$$

For the property tax rate

$$\frac{\partial P_2}{\partial t} = V(1 - \bar{t})PWF(N_e, i, d) \quad (11.9.9)$$

For the resale value

$$\frac{\partial P_2}{\partial R_v} = \frac{1 - C\bar{t}}{(1 + d)^{N_e}} \quad (11.9.10)$$

The partial derivative of the life-cycle savings with respect to the fraction by solar is

$$\frac{\partial LCS}{\partial \mathcal{F}} = P_1 C_{F1} L \quad (11.9.11)$$

A complete set of the partial derivatives is provided by Brandemuehl and Beckman (1979).

It is also necessary to know the partial derivatives of the present-worth functions. From Equation 11.5.1, when  $i \neq d$ ,

$$\frac{\partial PWF(N, i, d)}{\partial N} = -\frac{1}{d-i} \left( \frac{1+i}{1+d} \right)^N \ln \left( \frac{1+i}{1+d} \right) \quad (11.9.12)$$

$$\frac{\partial PWF(N, i, d)}{\partial i} = \frac{1}{d-i} \left[ PWF(N, i, d) - \frac{N}{1+i} \left( \frac{1+i}{1+d} \right)^N \right] \quad (11.9.13)$$

$$\frac{\partial PWF(N, i, d)}{\partial d} = \frac{1}{d-i} \left[ \frac{N}{1+d} \left( \frac{1+i}{1+d} \right)^N - PWF(N, i, d) \right] \quad (11.9.14)$$

For the partial derivatives evaluated at the condition when  $i = d$ ,

$$\frac{\partial PWF(N, i, d)}{\partial N} = \frac{1}{1+i} = \frac{1}{1+d} \quad (11.9.15)$$

$$\frac{\partial PWF(N, i, d)}{\partial i} = \frac{N(N-1)}{2(1+i)^2} \quad \text{and} \quad \frac{\partial PWF(N, i, d)}{\partial d} = \frac{-N(N+1)}{2(1+d)^2} \quad (11.9.16)$$

In the next example, the effect of uncertainty of one variable is illustrated. To estimate the effects of uncertainties of more than one variable, the same procedure is used as for one variable in determining the appropriate terms in Equations 11.9.2 and 11.9.3.

### Example 11.9.1

In Example 11.8.2, the fuel inflation rate was taken as 10% per year. For 50 m<sup>2</sup> collector area, what are the life-cycle savings? What is the uncertainty in life-cycle savings if the fuel inflation rate is uncertain to  $\pm 2\%$ ? From the data of Example 11.6.4, the 50-m<sup>2</sup> collector will provide 0.56 of the annual loads. The first year's fuel cost is \$1255 and the installed cost is \$11,000. Assume  $N_e = 20$  years and  $d = 0.08$ . From Example 11.8.2,  $P_1 = 22.169$  and  $P_2 = 1.035$ .

### Solution

The life-cycle savings are, from Equation 11.8.1,

$$LCS = 22.619 \times 1255 \times 0.56 - 1.035 \times 11,000 = \$4195$$

The effect of fuel inflation rate is only on  $P_1$ . From Equation 11.9.5, with  $C = 0$ ,

$$\frac{\partial P_1}{\partial i_F} = \frac{\partial PWF(N_e, i_F, d)}{\partial i_F}$$

and from Equation 11.9.13,

$$\frac{\partial PWF(N_e, i_F, d)}{\partial i_F} = \frac{1}{0.08 - 0.10} \left[ PWF(20, 0.10, 0.08) - \frac{20}{1.10} \left( \frac{1.10}{1.08} \right)^{20} \right] = 204$$

The uncertainty in  $LCS$  is obtained from Equations 11.9.1, 11.9.2, or 11.9.3 (which all give the same result when uncertainty in only one variable is considered) and 11.9.4:

$$\begin{aligned} \Delta LCS &= \frac{\partial LCS}{\partial i_F} \Delta i_F = C_{F1} L \mathcal{F} \frac{\partial P_1}{\partial i_F} \Delta i_F \\ &= 1255 \times 0.56 \times 204 \times 0.02 = \$2867 \end{aligned}$$

The uncertainty in  $LCS$  due to the uncertainty of 2% in the fuel inflation rate is over half of the projected savings. (An increase in  $i_F$  results in an increase in  $LCS$ .) ■

The effect of any one variable on the life-cycle savings is largely determined by the values of the many other variables. It is not easy to generalize, and a quantitative analysis is usually required.

## 11.10 ECONOMIC ANALYSIS USING SOLAR SAVINGS FRACTION

The solar savings fraction developed in Section 10.10 can also be used in economic analyses. The life-cycle cost of a nonsolar system including the needed electrical energy is

$$LCC_{NS} = P_1 C_{F1} (L + C_{ef} E_{NS}) \quad (11.10.1)$$

where  $C_{ef}$  is the ratio of the cost of electricity to the cost of fuel. The life-cycle cost for a solar system is

$$LCC_S = P_1 C_{F1} (L - L_S + C_{ef} E_S) + P_2 (C_A A + C_E) \quad (11.10.2)$$

The life-cycle savings is the difference between these two life-cycle costs, or

$$\begin{aligned} LCS &= P_1 C_{F1} L \left( \frac{L - L_S - C_{ef} (E_S - E_{NS})}{L} \right) - P_2 (C_A A + C_E) \\ &= P_1 C_{F1} L \left( \mathcal{F} - \frac{C_{ef} \Delta E}{L} \right) - P_2 (C_A A + C_E) \end{aligned} \quad (11.10.3)$$

and with Equation 10.10.6 the life-cycle savings using the solar savings fraction is

$$LCS = P_1 C_{F1} L \mathcal{F}_{SAV} - P_2 (C_A A + C_E) \quad (11.10.4)$$

which is identical in form with Equation 11.8.1. Thus, the techniques developed in Sections 11.8 and 11.9 can be used with either the solar fraction or the solar savings fraction. Since  $\mathcal{F}_{SAV}$  is always less than  $\mathcal{F}$  the life-cycle savings and optimum collector area will always be smaller when using the solar savings fraction rather than the solar fraction.

## 11.11 SUMMARY

In this chapter we have outlined the kinds of investments and operating costs that may be expected with a solar process and indicated that in many circumstances collector area can be considered the primary design variable once a system configuration and collector type are established.

A variety of economic figures of merit have been proposed and used, including payback times, cash flow, and life-cycle savings. The life-cycle costing method is the most inclusive and takes into account any level of detail the user wishes to include, including the time value of money. The use of the life-cycle savings method will be illustrated for specific solar processes in later chapters. The  $P_1$ ,  $P_2$  method of calculating life-cycle savings is particularly useful. The results of these calculations are very dependent on values assumed for  $N_e$ ,  $i_F$ , and  $d$ . If  $i_F > d$  (an abnormal situation that has existed in recent years), the choice of a sufficiently high value of  $N_e$  will make the life-cycle savings of solar (or other capital-intensive fuel-saving technologies) appear positive. Clearly, the selection of values for the critical economic parameters in the analysis will have great influence on the results obtained.

## REFERENCES

- Balcomb, J. D., *Passive Solar J.*, **3**, 221 (1986). "Conservation and Solar Guidelines."
- Barley, C. D., in *Proceedings of Denver Meeting of American Sect., Intl. Solar Energy Soc.*, **2** (1), 163 (1978). "Optimization of Space Heating Loads."
- Barley, C. D. and C. B. Winn, *Solar Energy*, **21**, 279 (1978). "Optimal Sizing of Solar Collectors by the Method of Relative Areas."
- Beckman, W. A., S. A. Klein, and J. A. Duffie, *Solar Heating Design by the f-Chart Method*, Wiley-Interscience, New York (1977).
- Brandemuehl, M. J. and W. A. Beckman, *Solar Energy*, **23**, 1 (1979). "Economic Evaluation and Optimization of Solar Heating Systems."
- Close, D. J., *Solar Energy*, **11**, 112 (1967). "A Design Approach for Solar Processes."
- De Garmo, E. P. and J. R. Canada, *Engineering Economy*, McMillan, New York (1973).
- Riggs, J. L., *Economic Decision Models*, McGraw-Hill, New York (1968).
- Ruegg, R. T., Report No. NBSIR 75-712, U.S. Department of Commerce (July 1975). "Solar Heating and Cooling in Buildings: Methods of Economic Evaluation."
- White, J. A., M. H. Agee, and K. E. Case, *Principles of Engineering Economic Analysis*, Wiley, New York (1977).

# Part II

---

## APPLICATIONS

Part I was concerned with the fundamental concepts and laws that determine the operation of solar process components and systems, the formulation of working equations for collectors and other components, and economics. With this background established, we proceed to discussions of applications of solar energy to meet various energy needs. There is substantial emphasis on applications to buildings for heating, hot water, and cooling by active and passive processes.

Much of Part II is qualitative and descriptive, although most of the chapters include results of quantitative performance calculations and/or measurements and economic evaluations. The objectives are to illustrate what applications have been made, show some of those that may be possible, and cast these applications in a quantitative framework where possible. Practical problems arising with the applications are noted.

Chapter 12 deals with active and passive water heating systems and covers many aspects of the most widespread of all modern solar processes. The extension of water heating practice to larger systems for active space heating is described in Chapter 13. Chapter 14 treats thermal aspects of passive heating processes, that is, the engineering part of the combined engineering and architectural problem of designing buildings to admit and use solar radiation. Chapter 15 concerns cooling processes operated by solar radiation.

The next three chapters are on applications that are usually made on a larger scale. The first is Chapter 16, on industrial process heat, applications that are interesting because so much energy is used in industry at temperatures that are compatible with collector operation but which for practical and economic reasons have not been widely made. Chapter 17, on thermal processes for conversion of solar to mechanical energy, treats experiments and practical applications that have been made in small numbers; it includes a discussion of the Luz power plants in California that have an aggregate electrical generating capacity of several hundred megawatts. Chapter 18, on solar ponds and evaporative processes, includes information on a peaking plant in Israel that is based on a solar pond and also traditional processes of evaporation and drying for water removal and distillation for water recovery. This chapter includes some theory and calculation methods for solar stills.

# Solar Water Heating: Active and Passive

This is the first of a set of chapters on thermal energy applications. In this chapter, we treat the use of solar heating for domestic or institutional hot-water supplies. Descriptions of systems, components, and important design considerations are outlined. Considerations important in designing water heating systems are also basic to solar heating and cooling systems, applications that are covered in succeeding chapters. Many of the principles noted here for service hot water for buildings also apply to industrial process heat, discussed in Chapter 16.

In recent years considerable knowledge has been developed about low-flow hot-water systems; these use collector flow rates a fifth or so of those that have been commonly used in forced-circulation systems. The  $F_R$  of collectors operated this way is lower than that in conventional operation, but higher stratification in storage tanks can be obtained, resulting in lower collector inlet temperatures and improved performance. These developments are of sufficient importance that they are discussed in a separate section.


## 12.1 WATER HEATING SYSTEMS

The basic elements in solar water heaters can be arranged in several system configurations. The most common of these are shown in Figure 12.1.1. Auxiliary energy is shown added in three different ways; these are interchangeable among the four methods of transferring heat from the collector to the tank.

A passive water heater (also called natural circulation or thermosyphon) is shown in Figure 12.1.1(a). The tank is located above the collector, and water circulates by natural convection whenever solar energy in the collector adds energy to the water in the collector leg and so establishes a density difference. Auxiliary energy is shown added to the water in the tank near the top to maintain a hot-water supply. Sometimes the collector is “close coupled” with a horizontal cylindrical storage tank.

Figure 12.1.1(b) shows an example of a forced-circulation system. A pump is required; it is usually controlled by a differential thermostat turning on the pump when the temperature at the top header is higher than the temperature of the water in the bottom of the tank by a sufficient margin to assure control stability (as outlined in Section 10.4). A check valve is needed to prevent reverse circulation and resultant nighttime thermal losses from the





**Figure 12.1.1** Schematic of common configurations of water heaters. (a) A natural-circulation system. (b) One-tank forced-circulation system. (c) System with antifreeze loop and internal heat exchanger. (d) System with antifreeze loop and external heat exchanger. Auxiliary is shown added in the tank, in a line heater, or in a second tank; any of these auxiliary methods can be used with any of the collector-tank arrangements.

collector. Auxiliary energy is shown added to the water in the pipe leaving the tank to the load.

In climates where freezing temperatures occur designs (a) and (b) need to be modified. Design (a) can include a heat exchanger in the tank and design (b) is sometimes provided with a drain-back tank that receives the entire collector and piping water whenever the pump does not operate. Examples of systems using nonfreezing fluids in the collector are shown in Figures 12.1.1(c) and (d). The collector heat exchangers can be either internal or external to the tank. In one modification of design (c) the heat exchanger forms a mantle around the tank (Furbo and Knudsen, 2004; Furbo et al., 2005). Auxiliary energy is shown added to the water in the storage tank in Figure 12.1.1(c) by a heat exchanger in the tank. The auxiliary energy supply can also be provided by a standard electric, oil, or gas water heater with storage capacity of its own; this is the two-tank system shown in Figure 12.1.1(d). Any of these systems may be fitted with tempering valves that mix cold supply water with heated water to put an upper limit on the temperature of the hot water going to the distribution system. Other equipment not shown can include surge tanks and pressure relief valves.

Solar water heaters are manufactured throughout the world. They were common in Florida and California early last century, disappeared when inexpensive natural gas became available, and are again being installed as the costs of gas and other fuels have risen. Solar water heating has the advantage that heating loads are usually uniform through the year, which leads to high-use factors on solar heating equipment. Figure 12.1.2 shows domestic and institutional water heaters. The Griffith and Perth systems utilize natural convection, and the others use forced convection.

The collectors in use in many water heating systems are similar to that shown in Figure 6.23.3, with parallel riser tubes 0.10 to 0.15 m apart. Plate materials may be copper or steel. Other plate designs are also used. For example, some are manufactured of two spot-welded, seam-welded, or roll-bonded plates of stainless or ordinary steel, copper, or aluminum. The fluid passages between the plates are formed by hydraulic expansion after welding. Serpentine tubes are also used and may become more common in the microflow systems to be discussed in Section 12.5. The absorber plates are mounted in a metal box, with 50 to 100 mm of insulation behind the plate and one or two glass covers over the plates. The dimensions of a typical collector module made in the United States are approximately  $1 \times 2$  m; the Australian and Israeli heater modules are typically  $0.6 \times 1.2$  m,  $1.2 \times 1.2$  m, or  $1 \times 2$  m. The thermal performance characteristics of these and other collectors can be determined by equations given in Chapter 6.

It is advantageous to maintain stratification in the storage tanks, and the location and design of tank connections are important, as noted in Chapter 8. The schematics in Figure 12.1.1 show approximate locations of connections in typical use. Close (1962) measured tank temperatures at various levels in an experimental natural-circulation water heating system operated for a day with no hot-water removal from the tank. These data are shown in Figure 12.1.3; this degree of stratification is characteristic of natural-circulation systems. Tanks without baffles or carefully designed diffusers on inlets and outlets will stratify to some degree in forced-circulation systems; at the present time most water heater tanks are not so equipped. Storage tanks should be well insulated, and good practice is to use 0.2 m or more of mineral wool or glass wool insulation on sides, top, and bottom. Piping connections to a tank should also be well insulated.



**Figure 12.1.2** Solar water heaters. (a) Natural-circulation system on hostel, Griffith, Australia. Photo courtesy of CSIRO. (b) Domestic system, with coupled tank and collector, Perth, Australia. (c) Hospital service hot-water system, Madison, WI. Photo courtesy of Affiliated Engineers, Inc. (d) Collectors for a domestic system, Madison, WI.




Figure 12.1.2 (Continued)




Figure 12.1.3 Temperature distribution in a vertical cylindrical water tank used in a thermal circulation water heater. From Close (1962).

## 12.2 FREEZING, BOILING, AND SCALING

Solar collectors and associated piping must be designed to avoid damage from freezing and boiling. Low ambient temperatures during periods of no solar radiation can result in plate temperatures below  $0^{\circ}\text{C}$ . If no energy is withdrawn from a system or if a circulating pump should not operate during times of high radiation, the plate temperature may exceed  $100^{\circ}\text{C}$ .

Freeze protection can be provided by draining the water from the collectors, use of nonfreezing solutions, or warming of the water in the collectors. Five approaches have been developed to protect collectors against damage by freezing.

First, antifreeze solutions can be used in the collector loop with a heat exchanger between the collector and the storage tank. As shown in Figures 12.1.1(c) and (d), the heat exchanger can be external to the tank, wrapped around the tank, or a coil within the tank relying on natural circulation of the water in the tank for heat transfer. The performance of the collector–heat exchanger combination can be treated by the  $F'_R$  method outlined in Section 10.2. A typical overall heat transfer coefficient for a coil in a tank is  $600 \text{ W/m}^2 \text{ }^\circ\text{C}$ .

Ethylene glycol–water and propylene glycol–water solutions are common antifreeze liquids. Their physical properties are included in EES. Ethylene glycol is toxic, as are some commonly used corrosion inhibitors, and many plumbing codes require the use of two metal interfaces between the toxic fluid and the potable water supply. This can be accomplished either by the use of two heat exchangers in series or more commonly by double-walled heat exchangers that can be either internal coils in the tank or external to the tank.

Second, air can be used as the heat transfer fluid in the collector–heat exchanger loop of Figure 12.1.1(d). Air heating collectors have lower  $F_R(\tau\alpha)$  and  $F_R U_L$  than liquid heating collectors. However, no toxic fluids are involved, no second heat exchanger interface is needed, leakage is not critical, and boiling is not a problem.

The third method of freeze protection is to circulate warm water from the tank through the collector to keep it from freezing. Thermal losses from the system are significantly increased, and an additional control mode must be provided. This method can only be considered in climates where freezes are infrequent. In emergencies, when pump power is lost, the collector and piping subject to freezing temperatures must be drained.

The fourth method is based on draining water from the collectors when they are not operating. Draining systems must be vented at their highest point and must be arranged so that collectors and piping exposed to freezing temperatures are completely emptied. These systems are of two types: **drain-back** systems, in which the water drains back into the tank or a sump that is not exposed to freezing temperatures, and **drain-out** systems, which drain out of the system to waste.

The fifth method is to design the collector plate and piping so that it will withstand occasional freezing. Designs have been proposed using butyl rubber risers and headers that can expand if water freezes in them.


High collector temperatures may also be a problem, as no-load (equilibrium) temperatures of good collectors can be well above the boiling point of water under conditions of no fluid circulation, high radiation, and high ambient temperature. These conditions can be expected to occur, for example, when occupants of a residence are away from home in the summer. Several factors may mitigate this problem. First, antifreeze solutions used in collector loops have elevated boiling points (see EES); 50% ethylene glycol and propylene glycol solutions in water have boiling points at atmospheric pressure of  $112$  and  $108^\circ\text{C}$ , respectively. Second, many systems are operated at pressures of several atmospheres, which further raises the boiling point; the boiling points of the two 50% glycol solutions at 2 atm absolute are about  $145$  and  $140^\circ\text{C}$ , respectively. Third, collector loss coefficients rise as plate temperatures rise, as shown in Figure 6.4.4, which tends to hold down no-load

temperatures. Practical systems should include pressure relief valves and vent tanks to relieve excess pressure and contain any antifreeze solution that is vented.

Overheating is a more serious problem in solar house-heating systems than in solar domestic hot-water systems. In the summer a solar house-heating system is really an oversized solar domestic hot-water system. Consequently methods to mitigate overheating problems are discussed in the next chapter on building heating systems. Some of the methods discussed in Section 13.10 are applicable to the solar domestic hot-water systems discussed in this chapter.

### Example 12.2.1

A collector with  $(\tau\alpha) = 0.78$  has a temperature dependence of overall loss coefficient as shown in the figure. The fluid being heated is a 50% solution of propylene glycol in water. The glycol loop is pressurized to a limit of 4.0 atm. On a summer day the radiation on the collector is  $1.15 \text{ kW/m}^2$  and ambient temperature is  $38^\circ\text{C}$ . Will the solution in the collector boil if the circulating pump does not operate?



### Solution

With no flow, absorbed energy equals losses:

$$G_T(\tau\alpha) = U_L(T_{p,m} - T_a) = 1150 \times 0.78 = 900 \text{ W/m}^2$$

so the plate temperature is

$$T_{p,m} = T_a + \frac{900}{U_L}$$

Since the loss coefficient is a function of plate temperature, it is necessary to simultaneously solve the energy balance equation and the equation for  $U_L$  as a function of  $T_p$ . Since the relationship between  $U_L$  and  $T_p$  is in graphical form, it is convenient to perform an iterative solution. Assume for a first estimate that  $U_L = 6.5 \text{ W/m}^2 \text{ }^\circ\text{C}$ . Then

$$T_{p,m} = 38 + \frac{900}{6.5} = 176^\circ\text{C}$$

A second estimate of  $6.8 \text{ W/m}^2 \text{ } ^\circ\text{C}$  yields

$$T_{p,m} = 38 + \frac{900}{6.8} = 170^\circ\text{C}$$


The loss coefficient at this temperature is close to the second estimate, so  $T_p = 170^\circ\text{C}$  is a reasonable estimate of the temperature of the plate and the temperature of the fluid under no-flow conditions. The boiling point of a 50% propylene glycol solution at 4 atm is approximately  $145^\circ\text{C}$  and the solution would boil in the collector under these circumstances. ■

Scaling problems are not limited to solar water heating systems. All water heating systems can deteriorate in performance due to the formation of scale in hard-water conditions. Wang et al. (2005) have experimentally investigated scaling on surfaces such as copper, various types of nylon, polypropylene, polybutylene, and Teflon at conditions expected in solar applications. They present a model of scaling to assist in interpreting the data. They conclude that polymer tubes are prone to scaling at about the same rate as on copper. Nylon 6,6 is an exception as this material appears to enhance the scaling process. Scaling can be particularly detrimental to natural-convection systems as it not only increases the thermal resistance to decrease heat transfer but also increases the hydraulic resistance to reduce the fluid circulation.

## 12.3 AUXILIARY ENERGY

The degree of reliability desired of a solar process to meet a particular load can be provided by a combination of properly sized collector and storage units and an auxiliary energy source. In a few unique areas where there seldom are clouds of significant duration, it may be practical to provide all of the loads with the solar systems. However, in most climates auxiliary energy is needed to provide high reliability and avoid gross overdesign of the solar system.

Auxiliary energy can be provided in any of the three ways shown in Figure 12.3.1:



**Figure 12.3.1** Schematic of alternative location for auxiliary energy supply to a one-tank forced-circulation solar water heater: A, in tank; B, in line to load; C, in a bypass around tank.

**A** Energy can be supplied to the water in the tank, at location A. Auxiliary energy is controlled by a thermostat in the top part of the tank which keeps the temperature in the top portion at or above a minimum setpoint. This is the simplest and probably the least expensive method. However, it has the disadvantage that the auxiliary energy supply may increase the temperature of the water in the bottom of the tank and thus the collector inlet temperature, resulting in reduction of solar gain. In standard electric domestic hot-water tanks there are two elements, one near the bottom and one about one-third of the way down from the top. When using such a tank in a solar system, it is common practice to disable the lower element so that the lower two-thirds of the tank is essentially solar energy storage and the upper one-third of the tank is auxiliary energy storage. The collector inlet and outlet must be suitably arranged.

**B** Auxiliary energy can be supplied to the water leaving the tank, thus “topping off” the solar energy with auxiliary energy. This requires a heater separate from the solar tank. This heater may be a simple line heater or it may be a conventional water heater with storage capacity of its own. Auxiliary energy is controlled to maintain the outlet temperature from the auxiliary heater at a desired level. This method has the advantage of using the maximum possible solar energy from the tank without driving up the collector temperature, but additional heat loss will occur from the auxiliary heater if it has storage capacity. If a second tank is used, it is not sufficient to just have a single pipe connecting the two tanks since energy would be transferred from the solar tank to the auxiliary tank only during periods of hot-water draw.

**C** Auxiliary energy can be added directly to the incoming supply water by bypassing the tank when auxiliary energy is needed. This is a simple method but has the disadvantage that either the solar heated water or the auxiliary heated water must have a temperature above the setpoint so that mixing the two streams produces the desired setpoint temperature. If low-temperature solar heated water is to be utilized, it is necessary that the auxiliary heated water be considerably above the set temperature, a potentially dangerous situation.

The relative merits of these three methods have been examined by Gutierrez et al. (1974). By simulating a month's operation of the three systems having forced circulation, fixed collector size, and a partially stratified (three-node) storage tank under a range of conditions of ambient temperature, time of day, and magnitude of loads, the relative portions of the loads carried by solar and by auxiliary energy were estimated. It was shown for the system and climate data used that when the setpoint temperature was not greatly above ambient temperatures, the method of adding auxiliary energy was not critical (with method B showing minor advantages). However, when the minimum hot-water temperature was raised to setpoints usually used in domestic hot-water systems, method B showed significant advantages over method A, which in turn was better than method C.

The major reasons for the differences in performance on changing the method of adding auxiliary energy concern the temperature at which the collector operates. Adding auxiliary energy to the top of the tank (method A) can result in a higher mean collector temperature, poorer collector performance, and higher requirements for auxiliary energy (depending on the degree of stratification in the tank). Method C, which bypasses the tank when its top section is not hot enough, results in failure to use some collected solar energy.



Method B, with a modulated auxiliary heater (or its equivalent in an on-off auxiliary heater), maximizes the solar collector output and minimizes collector losses by operating at the lowest mean collector temperature of any of the methods. The magnitude of the differences may depend on the degree of stratification in the tank and the insulation on the tank. Losses from the auxiliary heater must be maintained at very low levels or method B may not be best (see Section 12.4).

## 12.4 FORCED-CIRCULATION SYSTEMS

Most domestic solar water heaters in the United States (and other climates where freezing temperatures are frequently encountered) are forced-circulation systems. Typically, two or three collector modules of dimensions about  $1 \times 2$  m are used. Until about 1980, flow rates were commonly around  $0.015 \text{ kg/m}^2 \text{ s}$ . Recently, substantially lower flow rates (usually referred to as low-flow-rate systems) have been used (e.g., in Sweden, rates of  $0.002$  to  $0.006 \text{ kg/m}^2 \text{ s}$  are used) to increase the tank stratification. The collectors are typically one-cover units with black chrome selective surfaces, although some use flat-black absorbers. Heat exchangers are common, including jackets (mantels) on tanks, external shell-and-tube exchangers, or coils immersed in the tank; propylene or ethylene glycol is used in collector loops. Tanks are usually similar to standard hot-water tanks and range in size for residential applications from 200 to 400 liters. Auxiliary heaters may be immersed in the upper part of the tanks or the solar heaters may serve as pre-heaters for standard water heaters. There are many variations on these designs.

In this section we review comparative simulation studies by Buckles and Klein (1980) of the long-term performance of domestic-scale systems of several configurations and designs. Daily loads were kept fixed at 300 liters of water, heated from  $10$  to  $50^\circ\text{C}$ , for an annual heating load of  $18.3 \text{ GJ}$ . The simulations were based on a typical domestic hot-water load pattern, shown in Figure 9.1.2 (Mutch, 1974). Hot-water use is concentrated in morning and evening hours; to supply large fractions of these loads, water heated by solar energy one day must be stored for use the following day. (Minor changes in time dependence of loads do not have a major effect on long-term performance of domestic hot-water systems. However, variations of larger magnitude such as are caused by weekend closures of commercial buildings can have a significant impact on water heater performance and design.)

The collectors were well designed single-cover selective surface collectors with  $F_R(\tau\alpha)_n = 0.84$  and  $F_R U_L = 4.67 \text{ W/m}^2 \text{ }^\circ\text{C}$ . Collector areas were taken as two, three, or four modules each of area  $1.44 \text{ m}^2$ . The tanks in all cases had loss coefficients of  $1.67 \text{ W/m}^2 \text{ }^\circ\text{C}$ . Single-tank systems were modeled as three-node tanks with auxiliary energy supplied to the top node by immersion heaters. Two-tank systems were modeled with the same total volume as the single tanks, with one-third of the volume in the auxiliary tank and the preheat tank and the remaining two-thirds treated as a two-node tank. The collector heat exchangers inside the tank were assumed to have an effectiveness of  $0.5$  (which is probably an overly optimistic assumption in view of measurements that have been made of performance of several systems). The direct systems were modeled without

heat exchangers, with circulation from the bottom of the tank to collector and return to the top of the tank.

An index of performance of these systems is the yearly quantity of solar energy delivered to heat the water. This quantity is often calculated without consideration of thermal losses from the tanks. However, the total energy required by a conventional heater would include such losses. The data that follow are comparisons of solar system performance relative to a conventional system in which the total load is the energy required to heat the water, 18.3 GJ for a year, plus estimated losses from a conventional tank of 3.6 GJ, for a total load  $L$  of 21.6 GJ. The fraction by solar,  $\mathcal{F}$ , is then the ratio of the solar energy delivered to the total conventional load, or  $1 - L_A/L$ , and is a measure of the reduction in annual consumption of energy relative to the conventional system.

Under the assumptions made in this study, that is, with a reasonable degree of stratification in the solar tank and with auxiliary energy supplied to the top third of a single tank or in the second tank of a two-tank system, there is very little difference between one- and two-tank systems. In some cases one-tank systems are slightly better because of less area for heat loss from the tanks. The two-tank direct systems without tempering valves have essentially the same performance as those with tempering valves. During times when the system is oversized (i.e., during very good weather) and the water delivered from storage is hot enough to require tempering with cold water, the higher thermal losses negate any advantages of delivery of less heated water from the tank. At times when the system is undersized, the tempering valve does not function. Direct systems without the heat exchanger performed about 5% better than those with the heat exchanger.

An additional set of simulations was done in which the average daily hot-water load was kept at 300 liters but which had a 15-fold variation from the largest daily draw to the smallest daily draw in each week. The percentage of the week's hot-water load drawn in each of the days of the week (starting with Sunday) was 5.7, 42.9, 2.8, 2.8, 14.4, 2.8, and 28.6%. For the one-tank, external heat exchanger system with three collector modules, the fraction of the load met by solar energy was 0.64 for the regularly recurring load and 0.58 for the irregular load. This simulation study suggests that the effectiveness of the collector heat exchanger is an important aspect of design and that the choice of system configuration otherwise makes less difference in the annual solar output than does the kind of variation in the day-to-day loads which might be expected with a domestic system.

Sizing of domestic forced-circulation systems can be done by “rule of thumb” or by thermal and economic analyses and design procedures.<sup>1</sup> Typical home hot-water usage in the United States is 75 liters per day per person, and typical collector areas per person are about 1.5 m<sup>2</sup> for systems which deliver approximately 0.5 to 0.8 of the annual loads by solar energy. However, these figures vary with quality of the collector and the climate, and there are wide individual variations from average water use.

Systems for institutional, commercial, and office buildings are almost all forced-circulation systems. The magnitude and time dependence of loads in these buildings may be easier to predict than for residences. The loads may go to zero on weekends and holidays in some office and commercial buildings.

---


<sup>1</sup>See Chapters 20 and 21 for details on design procedures.

## 12.5 LOW-FLOW PUMPED SYSTEMS

The collector flow rates noted in Section 12.4, that is, in the range of 0.01 to 0.02 kg/m<sup>2</sup> s, lead to high values of  $F_R$ . However, in direct systems (without a collector heat exchanger) they also lead to relatively high fluid velocities in piping and subsequent mixing (or partial mixing) in tanks. Van Koppen et al. (1979) suggested the advantages of low-flow and stratified tanks, and recent work has confirmed that it can be advantageous to use reduced fluid flow rates in the collector loops, accept a lower  $F_R$ , and gain the advantage of increased stratification with resulting reduced collector inlet temperature. The result can be a net improvement in system performance. Lower flow rates result in greater temperature rise across collectors, and if tanks are perfectly stratified, the temperature differences from top to bottom will increase as the flow rate decreases. As pointed out by Hollands and Lightstone (1989) in a very useful review, the use of lower flow rates can have the additional advantages of reduction in both the first cost and operating cost of the systems through use of smaller pipes and pumps and reduction of operating costs for pump operation. Flow rates used in Swedish flat-plate collectors have typically been in the range of 0.002 to 0.007 kg/m<sup>2</sup> s (Dalenbäck, 1990).

Figure 12.5.1, from simulation studies by Wuestling et al. (1985), illustrates for a specific example the effects of collector flow rate per unit area on system performance (expressed as solar fraction  $\mathcal{F}$ ) for a fully mixed tank and for a highly stratified tank. The potential advantage of the low-flow system are evident; the maximum performance for the stratified tank ( $\mathcal{F} = 0.66$ ) is a third greater than that for the fully mixed tank ( $\mathcal{F} = 0.48$ ). This level of improvement is not realized in practice, as real tanks are in general neither fully mixed nor fully stratified. As Hollands and Lightstone (1989) point out, the degree of improvement depends in part on load patterns, as loads that draw the tank down completely by the beginning of collection in the morning will result in less improvement in performance than if the tank is hot in the morning. However, the gains that have been reported in experiments (e.g., Carvalho et al., 1988) are significant.

There are design and operating problems that must be faced in low-flow systems. Reduction of flow rate in standard collectors may result in poor flow distribution and



**Figure 12.5.1** An example of solar fraction as function of collector flow rate for a very highly stratified tank and for a fully mixed tank. Adapted from Wuestling et al. (1985).

performance penalties due to hot areas. Collector redesign may be needed; serpentine tubes rather than parallel risers can be used to avoid this problem. Care must be taken to see that the flow rate does not go below the peak point on the upper curve of Figure 12.5.1, as performance drops off very rapidly. Tank design should be such that stratification is maintained at the flow rates used in both collector and load loops.

Hollands et al. (1986) described a system designed for low flow. Small-diameter (4.8-mm) serpentine tubes are used on the collectors, which are connected in series. A small gear pump is used to pump the glycol heat exchanger fluid through the collector loop, and a collector heat exchanger is used with natural convection on the tank side. Collector flow rates are about one-sixth of that used in conventional systems. The heat exchanger has an effectiveness of about 0.8, and for much of the day in experimental operation the inlet temperature to the collector was close to the mains water supply temperature. This design has significant cost advantages over conventional systems. The equipment costs are reduced through use of small tubing and pump. Plumbing costs are reduced by simplified connections. Operating costs are reduced through reduced parasitic power requirements for pump operation.


## 12.6 NATURAL-CIRCULATION SYSTEMS

Circulation in passive solar water heaters such as that shown in Figure 12.1.1(a) occurs when the collector warms up enough to establish a density difference between the leg including the collector and the leg including the tank and the feed line from tank to collector. The density difference is a function of temperature difference, and the flow rate is then a function of the useful gain of the collector which produces the temperature difference. Under these circumstances, these systems are self-adjusting, with increasing gain leading to increasing flow rates through the collector. Norton and Probert (1986) have reviewed the theory of operation of these systems.

Two approaches have been taken to the analysis of systems of this type. The first is to model the system in detail, taking into account the dimensions of the system, the temperatures in various parts thereof, the temperature-dependent densities, the pressure differences caused by the density differences, and the resulting flow rates. The solutions of the equations are iterative, as the temperatures and flow rates are interdependent. An early analysis of this type was done by Close (1962). A more recent analysis has been described by Morrison and Braun (1985) and is a standard subroutine in the solar process simulation program TRNSYS (*TRNSYS Users Manual*, 2012).

In a very much simpler approach, Löff and Close (1967) and Cooper (1973) observed that under wide ranges of conditions the increase in temperature of water flowing through many collectors in natural-circulation systems (particularly those of Australian design) is approximately 10°C. Close (1962) compared computed and experimental inlet and outlet temperatures. His results, some of which are shown in Figure 12.6.1, confirm the suggestion that temperature increases of approximately 10°C are representative of these systems if they are well designed and without serious flow restrictions. Gupta and Garg (1968) also show inlet and outlet water temperatures for two collectors that suggest nearly constant temperature rise across the collectors.

If it is assumed that there is a constant temperature increase of water flowing through the collector, it is possible to calculate the flow rate which will produce this temperature



**Figure 12.6.1** Collector inlet and outlet water temperatures for a natural-circulation water heater. From Close (1962).

difference at the estimated collector gain. The basic collector equations are

$$Q_u = A_c F_R [S - U_L (T_i - T_a)] \quad (12.6.1)$$

and

$$Q_u = \dot{m} C_p (T_o - T_i) = \dot{m} C_p \Delta T_f \quad (12.6.2)$$

Solving for the flow rate,

$$\dot{m} = \frac{A_c F_R [S - U_L (T_i - T_o)]}{C_p \Delta T_f} \quad (12.6.3)$$

This equation can be solved for  $\dot{m}$  if it is assumed that  $F'$  is independent of flow rate. Substituting Equation 6.7.4 for  $F_R$  into Equation 12.6.3 and rearranging give

$$\dot{m} = \frac{-U_L F' A_c}{C_p \ln \left\{ 1 - \frac{U_L (T_o - T_i)}{S - U_L (T_i - T_a)} \right\}} \quad (12.6.4)$$

### Example 12.6.1

A natural-circulation water heater operates with a nearly constant increase in water temperature of 10°C. The collector has an area of 4 m<sup>2</sup>, an overall loss coefficient of 4.2 W/m<sup>2</sup> °C, and  $F' = 0.91$ . If the water inlet temperature is 30°C, the ambient temperature is 15°C, and the radiation absorbed by the collector plate is 780 W/m<sup>2</sup>, what is the useful gain from the collector?

**Solution**

All of the information needed to estimate  $\dot{m}$  using Equation 12.6.4 is available:

$$\dot{m} = \frac{-4.2 \times 0.91 \times 4}{4190 \ln \left\{ 1 - \frac{4.2 \times 10}{780 - 4.2(30 - 15)} \right\}} = 0.060 \text{ kg/s}$$

$$Q_u = 0.060 \times 4190 \times 10 = 2550 \text{ W}$$

We have assumed  $F'$  is fixed. If necessary, a first estimate can be made of  $F'$ , a first iteration of  $\dot{m}$  is obtained as shown, and the assumed value of  $F'$  is checked using the calculated  $\dot{m}$  to see if a second iteration is needed. If the fluid temperature rise were  $20^\circ\text{C}$ , the calculation shows  $Q_u = 2450 \text{ W}$ , with the reduction due to lower  $F_R$ . The useful gain is only moderately sensitive to  $\Delta T_f$ , except at low radiation levels or with collectors with high loss coefficients. ■

Collector operation with fluid temperature rises of approximately  $10^\circ\text{C}$  implies for practical systems that water circulates through the collector several times per day. Tabor (1969) suggested an alternative design in which the resistance to flow is higher so that flow rates would be lower and water in the tank would make about one pass through the collector in a day. He calculated that the daily efficiency of a “one-pass” high-  $\Delta T_f$  system will be about the same as a system using several passes per day and lower  $\Delta T_f$ . This is dependent on maintaining good stratification in the tank. Gordon and Zarmi (1981) have analyzed single- and multipass systems and also concluded that under the approximations and assumptions they made (which included the assumption of no daytime load) the two types of systems give approximately the same daily collected energy. In these systems the effects of reduced  $F_R$  are offset by reduced mean fluid inlet temperature (in the same way as in the microflow forced-circulation systems noted in Section 12.5). Many Israeli water heaters are designed to operate this way.

In Australia, where natural-circulation systems are widely used, sizing of systems is based on experience (CSIRO, 1964). They are designed to produce water at  $65^\circ\text{C}$  and at daily average usage of 45 liters per person per day. If an all-solar system is to be used (e.g., in Darwin, which is characterized by almost continuous good solar weather and expensive conventional fuels), a storage capacity of 2.5 times the daily requirement is suggested. For a family of four in Darwin, a collector area of about  $4 \text{ m}^2$  is suggested. If an auxiliary energy source is to be used (e.g., in Melbourne, where radiation is more intermittent and conventional energy is less expensive), the recommended tank size is approximately 1.5 times the daily requirement. The majority of Australian solar water heaters are natural-circulation systems, as freezing is not a problem in most of the country.

Year-long performance of thermosyphon water heaters has been measured by Morrison and Sapsford (1983). Two types of systems were measured: close-coupled systems, such as that shown in Figure 12.1.2(b), and systems with separate tank and collector, such as that shown in Figure 12.1.1(a). Auxiliary energy was supplied electrically, either on a continuous basis or off-peak. Loads were imposed that are typical of Australian hot-water consumption. The close-coupled system showed slightly better performance than the

systems with separate collector and tank when off-peak electric auxiliary was supplied. Systems operated with off-peak auxiliary delivered more solar energy than those with continuous auxiliary, as auxiliary caused less elevation of collector temperature. However, there were times in poor weather when the water output temperature dropped below control points in systems supplied with off-peak auxiliary. In contrast to pumped systems, the solar contribution of thermosyphon systems was better when the major loads were imposed in the morning; the difference is attributed to lower collector operating temperature in the morning and higher circulation rate produced by the introduction of cold water into the tank before the main solar input period.


## 12.7 INTEGRAL COLLECTOR STORAGE SYSTEMS

Water heaters that combine the functions of collector and storage are manufactured in Japan (Tanishita, 1970), the United States, and elsewhere. The designs of these integral collector storage (ICS) systems vary. The basic configuration is that of a tank or set of interconnected tanks, with energy-absorbing surfaces on their exposed surfaces, enclosed in an insulated box with a transparent cover on the top to admit solar radiation. A cross-sectional schematic of a system of this type is shown in Figure 12.7.1. In the morning, water is put in the tubes, which in this configuration are black plastic cylinders about 0.2 m in diameter. Through the day, the water is heated by absorbed solar energy. The top cover and back insulation reduce energy losses from the cylinders. The performance of this type of collector can be estimated by solving the differential equation describing the energy balance on the tank, as shown in the following example.

### Example 12.7.1

A water heater that combines collector and storage is constructed of 150-mm black tubes placed side by side in a box, insulated on its bottom to the extent that bottom losses are small, and covered on the top by a single glass cover. A section of the heater is as shown in Figure 12.7.1. The heater is filled with water at 18°C at 6 AM. The heater is sloped toward the equator with  $\beta = \phi = 40^\circ$ . Meteorological data for a 24-h period are shown in the second and third columns of the table below. Assume that no water is drawn off at any time during the 24-h period.

Estimate the temperature history of the water through the 24-h period.



**Figure 12.7.1** Schematic section of solar water heaters combining collector and storage.

**Solution**

A set of assumptions must be made to estimate the temperature history of this heater. A reasonable set is as follows:

Absorptance = 0.95.

Emissance of black plastic = 0.95.

Solar transmittance of cover = 0.89.

Heat capacities of cover and other structure are negligible compared to that of the water.

Water and tubes are at uniform temperature.

Wind speed is such that  $h_w = 10 \text{ W/m}^2 \text{ }^\circ\text{C}$ .

$U_t = U_L = \text{constant throughout period.}$

First, estimate  $U_L$ . If the plate were flat,  $U_t$  would be approximately  $5.5 \text{ W/m}^2 \text{ }^\circ\text{C}$ , estimated from Figure 6.4.4(b). The area of the plate (i.e., the tubes) is  $\pi/2$  larger than the cover, or

$$A_p = 1.57A_c$$

A first-order estimate of  $U_t$  is

$$U_t = 5.5 \left( 1 + \frac{0.57}{2} \right) = 7.09 \text{ W/m}^2 \text{ }^\circ\text{C}$$

a value used without change in the calculation below.

The basic equation used is Equation 6.12.7. This can be written as

$$T_w^+ = T_a + \frac{S}{U_L} - \left[ \frac{S}{U_L} - (T_w - T_a) \right] \exp \left[ -\frac{A_c U_L t}{(mC_p)_c} \right]$$

For each hour, with  $I_T$  in megajoules per square meter,

$$\begin{aligned} \frac{S}{U_L} &= \frac{1.02 \times 0.89 \times 0.95 I_T \times 10^6}{7.0 \times 3600} = 34.2 I_T \\ \frac{A_c U_L t}{(mC_p)_c} &= \frac{0.15 \times 1 \times 7.0 \times 3600}{(\pi/4)0.15^2 \times 1 \times 1000 \times 4190} = 0.0511 \\ e^{-0.0511} &= 0.95 \end{aligned}$$

A working equation is thus

$$T_w^+ = T_a + 34.2 I_T - (34.2 I_T - T_w + T_a) \times 0.95$$

The temperatures at the end of each hour,  $T^+$ , are shown in the last column in the table. (These heaters are suitable for use where hot water is wanted at the end of the collection period. Thermal losses from the stored hot water are sufficiently high at night or during prolonged cloudy periods that their use for continuous hot water is usually impractical.)



Hour Ending	$I_T$ (MJ/m <sup>2</sup> )	$T_a$ (°C)	$T_w^+$ (°C)	Hour Ending	$I_T$ (MJ/m <sup>2</sup> )	$T_a$ (°C)	$T_w^+$ (°C)
7 AM	0.05	7	17.5	7 PM	0	15	43.4
8	0.32	9	17.7	8	0	14	42.0
9	1.09	14	19.3	9	0	12	40.5
10	1.23	16	21.2	10	0	10	38.9
11	2.36	16	25.0	11	0	9	37.4
12	3.95	17	31.3	12	0	9	36.0
1 PM	3.90	20	37.4	1 AM	0	9	34.7
2	3.52	20	42.5	2	0	8	33.3
3	2.55	21	45.7	3	0	6	32.0
4	1.38	22	46.9	4	0	7	30.7
5	0.46	21	46.4	5	0	7	29.5
6	0.04	16	44.9	6	0	7	28.4

■

Other types of ICS water heaters have been built. Some use a single energy-absorbing storage cylinder with an optical concentrator to increase absorbed radiation; these typically have concentration ratios of about unity. Vaxman and Sokolov (1985) describe experiments with a heater in which a flat tank is divided into two parts, a thin absorber channel under the absorbing surface and a deeper storage zone behind the absorber channel and separated from it by an insulated partition. Water circulates from the storage zone through the channel by convection. Zollner et al. (1985) have worked out an analysis of ICS water heaters and developed a method for estimating long-term performance of these systems.

Water heaters combining collector and storage are passive systems in that they require no mechanical energy for operation. They are similar in some ways to collector-storage walls used in passive space heating (see Chapter 14). Liu et al. (2005) describe experiments using integral solar collector storage systems with immersed tube bundles. They present Nusselt–Rayleigh number correlations for the heat transfer characteristics needed for designing such systems.

## 12.8 RETROFIT WATER HEATERS

It is generally difficult to add solar equipment to buildings not designed for them. Of all solar energy systems, water heaters are the easiest to retrofit. Collector areas of residential water heating systems are manageable, and the addition of a separate solar storage tank can result in a system configuration such as shown in Figure 12.1.1(d), where the existing heater is the second tank. The solar heating system then provides preheated water to the conventional system and integration into the existing system is easy. Or a solar tank equipped with an auxiliary heater can replace the existing heater. The major problems are likely to be collector mounting and space for pipe or duct runs. As these runs are likely to be longer than in buildings designed for solar applications, they must be carefully insulated to avoid excessive losses. The methods of Section 10.3 can be used to estimate the effects of pipe or duct losses.


It is also possible to adapt existing tanks for solar operation, as shown by Czarnecki and Read (1978), by use of special fittings that allow the needed extra connections to be made to the tanks for circulation through the collector. Single openings in a tank can serve as dual openings by use of fittings having concentric center tubes; the center tube and annulus provide two connections that can be separated by lengthening the tube. Czarnecki and Read found that the measured thermal performance of such a system was poorer than that of a similar one-tank forced-circulation system using an outlet to the collector at the bottom of the tank and a return from the collector located halfway up the tank. Thus, reduced installation cost resulted in reduced solar output from the system. It is difficult to generalize on the merits of these various configurations, but as long as collector costs dominate the costs of the system, it is advisable to consider the use of the other components with good performance characteristics which will produce the most useful gain from the collectors.

## 12.9 WATER HEATING IN SPACE HEATING AND COOLING SYSTEMS

The following chapters treat space heating and cooling, and most systems for these applications will include provision for water heating. The water heating subsystems in these systems often include a heat exchanger to extract heat either from the fluid circulated through the collector or from the main storage tank. A “solar preheat” tank to store solar-heated water and a conventional water heater (auxiliary) may be used, as shown in Figure 12.9.1, or a single-tank system including the auxiliary source can be used. The collectors for heating and cooling are usually sized for these functions and are thus oversized for water heating during periods when heating or cooling loads are low. Even in northern U.S. climates, annual residential hot-water loads are typically one-fourth to one-fifth of annual heating loads, and significant contributions to total annual loads can be obtained by well-designed hot-water facilities.

## 12.10 TESTING AND RATING OF SOLAR WATER HEATERS

Standard methods have been devised for testing and rating of water heating systems of the types shown in Figure 12.1.1. The rating of solar water heating systems is done both by



**Figure 12.9.1** A two-tank hot-water subsystem for solar heating/cooling systems.

direct measurements and by simulations (see Chapter 19). ASHRAE-95 is an indoor test procedure in which a water heater is subjected to a defined sequence of operating conditions that are presumed to be typical of those that a solar water heater would undergo. The test conditions are specified by a rating agency such as the Solar Rating and Certification Committee (SRCC, 2002) in the United States. Indoor testing is common in regions where suitable solar conditions are rare. The incident solar radiation is then simulated by the output of high-intensity lamps.

In the United States system tests can be replaced by component tests and the system performance estimated through simulations. The simulated hourly ambient temperatures, irradiation, and incidence angles specified by the SRCC are shown in Table 12.10.1. The tank environmental temperature is maintained at 19.7°C, the mains water temperature is 14.4°C, and the auxiliary set temperature is 57.2°C. Hot water is drawn at a rate of 0.189 liter/s every hour beginning at 09:30 for a total of six equal energy draws. The total daily energy draw is 43.3 MJ. The simulated test is repeated until the delivered energy is approximately equal to that of the previous day.

The result is presented in terms of a solar energy factor (*SEF*) defined as the energy delivered by the system (43.3 MJ for the SRCC conditions) divided by the auxiliary

**Table 12.10.1** SRCC Ambient Temperature, Irradiation, and Incidence Angle

Time (h)	Ambient Temperature (°C)	Solar Radiation (W h/m <sup>2</sup> )	Incident Angle (deg)
0–1	13	0	
1–2	12	0	
2–3	11	0	
3–4	10	0	
4–5	9	0	
5–8	8	0	
8–9	8	315	60
9–10	11	470	45
10–11	13	570	30
11–12	15	660	15
12–13	17	700	0
13–14	19	660	15
14–15	21	570	30
15–16	21	470	45
16–17	21	315	60
17–18	20	0	
18–19	19	0	
19–20	18	0	
20–21	17	0	
21–22	16	0	
22–23	15	0	
23–24	14	0	

energy (including parasitic energy) put into the system. The *SEF* does not differentiate between the cost of auxiliary energy and the cost of parasitic energy (usually electrical). For solar water heaters the auxiliary and parasitic energies are often both electrical. When the auxiliary energy and the parasitic energy are the same type (e.g., both electrical),  $C_{ef}$  in Equation 10.10.6 is equal to 1 and the relationship between *SEF* and the solar savings fraction is  $\mathcal{F}_{SAV} = 1 - 1/SEF$ .

System ratings provide comparative information on the performance of solar water heaters under the conditions of the tests. They do not indicate what the comparative performance would be in various real climates and under other load conditions. Knowing only the system rating is not sufficient to permit calculation of the system performance in any climate and under any load. Data on collector parameters [ $F_R (\tau\alpha)_n$ ,  $F_R U_L$ , and  $b_o$ ], tank loss coefficient  $(UA)_s$ , effects of controls, and so on, would be needed to generalize on the results of these tests.

## 12.11 ECONOMICS OF SOLAR WATER HEATING

Most solar water heating installations are designed for use throughout the year, which results in a high-use factor on the equipment and makes solar water heating more competitive with conventional methods than solar applications that are seasonal. A solar collector used in a water heater will deliver more energy per unit area per year than will a comparable installation used seasonally, such as winter space heating, summer air conditioning, or harvest time crop drying.

The economic principles outlined in Chapter 11 apply directly to solar water heating. The installed costs include the purchase and installation costs of interest and principal payments, parasitic power for fluid circulation, insurance, maintenance, taxes, and any other costs which may be significant. The following example shows the application of life-cycle savings analysis by the  $P_1$ ,  $P_2$  method to a solar water heater installation.

### Example 12.11.1

A solar water heater is proposed to be installed on a residence in Madison. The annual load is estimated to be 22.2 GJ. The collector areas and tank capacities available are such that it is not practical to consider collector area and tank size as continuous variables and a set of discrete system designs must be considered. The following table shows collector areas (for two, three, or four collector modules), tank capacities, installed costs, and fractions of annual hot-water loads carried by solar energy.

Design	Collector Area (m <sup>2</sup> )	Tank Capacity (kg)	System Cost (\$)	Fraction by Solar, $\mathcal{F}$
A	3.66	310	1700	0.41
B	5.49	310	2100	0.55
C	5.49	454	2400	0.56
D	7.32	454	2800	0.67

The water heaters would be purchased by a 20% down payment with the balance to be paid over a 10-year period with interest at 9% per year. The present cost of electrical energy (the auxiliary and alternative energy supply) is \$14.00/GJ, and it is expected to inflate at 8.5% per year. Insurance, maintenance, and parasitic power costs in the first year are expected to be 1% of the system cost. The real estate tax increment in the first year will be 1.5% of the system costs. The insurance, maintenance, parasitic power, and real estate taxes are expected to rise at a general inflation rate of 6% per year.

The owner's effective income tax bracket is 0.45. The market discount rate is to be 8% per year. If the analysis is done over 15 years and the system is assumed to have no appreciable resale value at that time, which system (if any) should be bought? For the best system, how long would it take to recover the system cost in savings on the purchase of electricity?

### Solution

The analysis is done by the  $P_1$ ,  $P_2$  method of Chapter 11, with life-cycle savings in each of the four cases calculated as shown in Example 11.8.2. Values of  $P_1$  and  $P_2$  are common to all four designs and are calculated by Equations 11.8.2 and 11.8.3:

$$\begin{aligned}
 P_1 &= PWF(15, 0.085, 0.08) = 14.348 \\
 P_2 &= 0.20 + 0.80 \frac{PWF(10, 0, 0.08)}{PWF(10, 0, 0.09)} \\
 &\quad - 0.45 \times 0.80 \left\{ PWF(210, 0.09, 0.08) \left[ 0.09 - \frac{1}{PWF(10, 0.09, 0.08)} \right] \right. \\
 &\quad \left. + \frac{PWF(10, 0, 0.08)}{PWF(10, 0, 0.09)} \right\} \\
 &\quad + 0.01 \times PWF(15, 0.06, 0.08) + 0.015(1 - 0.45) PWF(15, 0.06, 0.08) \\
 &= 1.112
 \end{aligned}$$

Then savings are calculated from Equation 11.8.1:

$$LCS = 14.348 \times 14 \times 22.2 \mathcal{F} - 1.112 \times \text{Cost}$$


The savings for the four designs, under these assumptions of costs, are -\$62 for design A, \$118 for B, -\$171 for C, and -\$127 for D.

Design B, the only one showing positive savings, is the one which should be purchased. However, the others are close, and small changes in the cost assumptions could shift all of them either way.

The time to recover the installed costs in undiscounted electricity savings for design B can be determined from Equation 11.7.3:

$$N_p = \frac{\ln \left[ \frac{2100 \times 0.085}{0.55 \times 22.2 \times 14} + 1 \right]}{\ln(1 + 0.085)} = 8.8 \text{ years}$$

■



**Figure 12.11.1** Examples of relations between fuel cost and its inflation rate for break-even solar water heating system operation. The three curves are for three assumptions of resale value at the end of the period of the economic analyses. Areas above curves represent combinations leading to economically feasible solar water heating under the assumptions of Example 12.11.1 in Madison, WI.

The competitive position of solar water heating is very much dependent on the costs of alternative energy and how rapidly it is expected to rise. It may also depend on the potential resale value of the equipment at the end of the period of economic analysis. Figure 12.11.1 was generated for design B, with economic assumptions the same as in Example 12.11.1. Fuel cost inflation rate is plotted against first-year fuel cost for combinations of  $C_{F1}$  and  $i_F$  which result in zero life-cycle savings (“breakeven” combinations). Any combination of  $C_{F1}$  and its inflation rate which lies above and to the right of the line results in positive solar savings and economically feasible solar water heating.

The 0% curve is based on the assumption of zero resale value at the end of the period of the economic analysis. Two additional lines are shown that are based on the assumption that the system is very well built and will have a resale value equal to its first cost (the curve marked 100%) or at its first cost inflated at the general inflation rate (the curve marked 240%). If the present cost of energy from fuel is \$10/GJ and it is expected to increase at 10%/year, this system would show positive life-cycle savings if its resale value will be 100% but not if it will have no resale value. Resale value results in significantly improved competitive positions for solar water heating for short periods of economic analysis. (Note, however, that this is a specific example. A new set of curves would have to be generated for new sets of economic parameters and locations. In particular, tax credits that effectively reduce first cost and other changes in installed cost of the water heaters may substantially alter the economic feasibility.)

## 12.12 SWIMMING POOL HEATING


Heating of swimming pools to prolong swimming seasons represents a significant consumption of energy in some areas and a substantial expense to pool owners and operators. The temperatures required for pools are low, usually not much above average ambient temperatures. For these reasons, solar heating of pools has become an application of increasing interest. Two general approaches have been taken: The first is based on covering the pool in such a way as to use it as the collector, and the second is based on the use of separate collector systems.

Open pools lose heat by conduction to the ground, by convection to the air, and by evaporation,<sup>2</sup> as outlined by Löf and Löf (1977) and analyzed in some detail by Govaer and Zarmi (1981).

The simplest and least expensive method for heating pools may be to cover them when they are not in use with a transparent plastic cover which floats on the surface of the water. The cover may fit within the edges of the pool or it may overlap the edges and be held down on the area around the pool by weights placed on the plastic to keep it in position. Sections of pools with such covers are shown in Figure 12.12.1. As long as the top of the cover is dry, evaporation losses are effectively eliminated. The plastic cover, if largely transparent to solar radiation, admits solar energy which is absorbed in the pool. The cover also serves to keep dirt out of the pool. It is difficult to quantify the performance of such a system, as times of use, winds, humidity, and so on, are highly variable. However, experiments in Denver have indicated that through the summer months an uncovered pool will have an average temperature below ambient, while a pool covered except for periods of occasional use will have average temperatures of 5 to 10°C above ambient temperature.

Either single-layer or double-layer covers are used. Single layers store in less volume when not on the pool and have higher transmittance. Double-layer covers are similar to the familiar “bubble” packing material and float without addition of other buoyant materials but have lower transmittance for solar radiation and do not store in as compact a manner as single-layer covers.

Separate collectors are also used for heating pools. They operate by forced circulation with water inlet temperatures near ambient. Many pool-heating collectors have no covers



**Figure 12.12.1** Schematic section of plastic pool covers: (a) held on pool edges by weights; (b) with floating edge.

<sup>2</sup>Estimation of pool losses is discussed in Section 9.7. Section 18.5 discusses solar evaporators, an analogous situation.

and a minimum of insulation. They may be made of metal or plastic and may be installed as a roof material for a patio or pool cabana. Swimming pool heaters have been described by Andrassy (1964) and others; deWinter (1974) has written a monograph on design and construction of pool heaters of this type, and an analysis of pool-heating collectors without covers has been presented by Farber (1978).

## 12.13 SUMMARY

Water heating is a practical application of solar energy in many parts of the world. Natural-circulation systems are widely used in climates where freezing does not occur. Forced-circulation systems using drain-down or nonfreezing fluids in collector–heat exchanger loops are used in climates where freezing is a problem. Auxiliary energy is used in essentially all systems where high reliability is wanted, and care must be taken to use auxiliary in such a way that it does not drive up collector temperatures.

## REFERENCES

- Andrassy, S., *Proc. UN Conf. New Sources of Energy*, **5**, 20 (1964). “Solar Water Heaters.”
- Buckles, W. E. and S. A. Klein, *Solar Energy*, **25**, 417 (1980). “Analysis of Solar Domestic Hot Water Heaters.”
- Carvalho, M. J., M. Collares-Pereira, F. M. Cunha, and C. Vitorino, *Solar Energy*, **41**, 33 (1988). “An Experimental Comparison of Operating Strategies for Solar Water Systems.”
- Close, D. J., *Solar Energy*, **6** (1), **33** (1962). “The Performance of Solar Water Heaters with Natural Circulation.”
- Cooper, P. I., personal communication (1973).
- CSIRO, Division of Mechanical Engineering Circular No. 2, Commonwealth Scientific and Industrial Research Organization, (CSIRO), Melbourne, Australia (1964). “Solar Water Heaters, Principles of Design, Construction and Installation.”
- Czarnecki, J. T. and W. R. W. Read, *Solar Energy*, **20**, 75 (1978). “Advances in Solar Water Heating for Domestic Use in Australia.”
- Dalenbäck, J-O., personal communication (1990).
- deWinter, F., *How to Design and Build a Solar Energy Swimming Pool Heater*, Copper Development Association, New York (1974).
- Farber, J., *Proc. of the 1978 Annual Meeting of the American Section of the ISES*, Denver (K. W. Böer and G. E. Franta, eds.), **2** (1), 235 (1978). “Analysis of Low Temperature Plastic Collectors.”
- Furbo, S. and S. Knudsen, in *Proceedings of the 2004 EuroSun Conference of ISES Europe*, Freiburg, Germany, p. 272, PSE GmbH, Freiburg, Germany (2004). “Low Flow SDHW Systems Based on Mantle Tanks—Recent Findings.”
- Furbo, S., N. K. Vejen, and L. J. Shah. *Trans. ASME J. Solar Energy Eng.*, **127**, 15 (2005). “Thermal Performance of a Large Low-Flow Solar Heating System with a Highly Thermally Stratified Tank.”
- Gordon, J. M. and Y. Zarmi, *Solar Energy*, **27**, 441 (1981). “Thermosyphon Systems: Single vs. Multi-Pass.”
- Govaer, D. and Y. Zarmi, *Solar Energy*, **27**, 529 (1981). “Analytical Evaluation of Direct Solar Heating of Swimming Pools.”
- Gupta, C. L. and H. P. Garg, *Solar Energy*, **12**, 163 (1968). “System Design in Solar Water Heaters with Natural Circulation.”



- Gutierrez, G., F. Hincapie, J. A. Duffie, and W. A. Beckman, *Solar Energy*, **15**, 287 (1974). "Simulation of Forced Circulation Water Heaters; Effects of Auxiliary Energy Supply, Load Type and Storage Capacity."
- Hollands, K. G. T. and M. F. Lightstone, *Solar Energy*, **43**, 97 (1989). "A Review of Low-Flow, Stratified-Tank Solar Water Heating Systems."
- Hollands, K. G. T., D. A. Richmond, and D. R. Mandelstam, in *Proceedings of the Ninth Biennial Congress of the International Solar Energy Society* (E. Bilgen and K. G. T. Hollands, eds.) (the Biennial Congress of ISES), Vol. 1, Pergamon, New York, p. 544 (1986). "Re-engineering Domestic Hot Water Systems for Low Flow."
- Liu, W., J. H. Davidson, and F. A. Kulaki, *J. Solar Energy Eng.*, **127**, 22 (2005). "Thermal Characterization of Prototypical Integral Collector Storage Systems with Immersed Heat Exchangers."
- Löf, G. O. G. and D. J. Close, in *Low Temperature Engineering Application of Solar Energy* (R. C. Jordan, ed.), ASHRAE, New York (1967). "Solar Water Heaters."
- Löf, G. O. G. and L. G. A. Löf, in *Proceedings of the 1977 Annual Meeting of the American Section of the ISES*, Orlando, Vol. 1, p. 31-1 (1977). "Performance of a Solar Swimming Pool Heater-Transparent Cover Type."
- Morrison, G. L. and J. E. Braun, *Solar Energy*, **34**, 389 (1985). "System Modeling and Operation Characteristics of Thermosyphon Solar Water Heaters."
- Morrison, G. L. and C. M. Sapsford, *Solar Energy*, **30**, 341 (1983). "Long Term Performance of Thermosyphon Solar Water Heaters."
- Mutch, J. J., RAND Report R 1498 (1974). "Residential Water Heating, Fuel Consumption, Economics and Public Policy."
- Norton, B. and S. D. Probert, in *Advances in Solar Energy*, Vol. 3 (K. Boer, ed.), Plenum, New York, p. 125 (1986). "Thermosyphon Solar Energy Water Heaters."
- SRCC, Standard OG-300, Solar Rating and Certification Corporation, Washington, DC (2002). "Operating Guidelines and Minimum Standards for Certifying Solar Water Heating Systems."
- Tabor, H., *Bulletin, Cooperation Mediterranee pour L'Energie Solaire* (COMPLES), No. 17, p. 33 (1969). "A Note on the Thermosyphon Solar Hot Water Heater."
- Tanishita, I., paper presented at Melbourne International Solar Energy Society Conference (1970). "Present Situation of Commercial Solar Water Heaters in Japan."
- TRNSYS Users Manual*, Version 16, University of Wisconsin Solar Energy Laboratory (2012). [First public version was 7.0 (1976).]
- van Koppen, C. W. J., J. P. S. Thomas, and W. B. Veltkamp, in *Sun II, Proceedings of ISES Biennial Meeting* (K. W. Böer and B. H. Glenn, eds.), Vol. 2, Pergamon, New York, p. 576 (1979). "The Actual Benefits of Thermally Stratified Storage in Small and Medium Sized Solar Systems."
- Vaxman, B. and M. Sokolov, *Solar Energy*, **34**, 447 (1985). "Experiments with an Integral Compact Solar Water Heater."
- Wang, Y., J. H. Davidson, and L. Francis, *Trans. ASME J. Solar Energy Eng.*, **127**, 3 (2005). "Scaling in Polymer Tubes and Interpretation for Use in Solar Water Heating Systems."
- Wuestling, M. D., S. A. Klein, and J. A. Duffie, *Trans. ASME, J. Solar Energy Eng.*, **107**, 215 (1985). "Promising Control Alternatives for Solar Water Heating Systems."
- Zollner, A., S. A. Klein, and W. A. Beckman, *Trans. ASME J. Solar Energy Eng.*, **107**, 265 (1985). "A Performance Prediction Methodology for Integral Collection-Storage Solar Domestic Hot Water Systems."

## Building Heating: Active

Heat for comfort in buildings can be provided from solar energy by systems that are similar in many respects to the water heater systems described in Chapter 12. The two most common heat transfer fluids are water (or water and antifreeze mixtures) and air, and systems based on each of these are described in this chapter. The basic components are the collector, storage unit, and load (i.e., the house or building to be heated). In temperate climates, an auxiliary energy source must be provided and the design problem is in part the determination of an optimum combination of solar energy and auxiliary (i.e., conventional) energy. Systems for space heating are very similar to those for water heating, and the same considerations of combination with an auxiliary source, boiling and freezing, controls, and so on, apply to both applications.

In this chapter we deal with active solar heating systems which use collectors to heat a fluid, storage units to store solar energy until needed, and distribution equipment to provide the solar energy to the heated spaces in a controlled manner. In combination with conventional heating equipment solar heating provides the same levels of comfort, temperature stability, and reliability as conventional systems. A building so heated is often referred to as a “solar house.”

The term solar house is also applied to buildings that include as integral parts of the building elements that admit, absorb, store, and release solar energy and thus reduce the needs for auxiliary energy for comfort heating. Architectural design can be used to maximize solar gains in the winter (and minimize them in the summer) to reduce heating (and cooling) loads that must be met by other means. Elements in the building (floors, walls) may be constructed to have high heat capacity to store thermal energy and reduce temperature variations. Movable insulation may be used to control losses (and gains) from windows or other architectural elements in the building. These concepts will be treated in Chapter 14 on passive heating. There is no substitute for good energy-conserving architectural design which (as far as other constraints allow) maximize the solar gains in the building itself. In this chapter we are concerned with meeting the energy needs for heating (and hot water) that are not eliminated by careful design.

Since 1970 there has been a surge of interest and activity in solar heating, and many thousands of active systems have been designed, installed, and operated. Patterns in the configuration of many air and liquid systems have emerged. These “standard” configurations, which are used with many variations, are discussed here in some detail. In addition, other system types are noted. Operating data are shown for two systems that are illustrative of the long-term thermal performance data needed to evaluate the economics of solar heating.

The design of solar heating systems is a three-part problem. The first is to determine the thermal performance, and the second is to carry out an economic analysis. This book is concerned with these two. The third is to assure that the resulting building is aesthetically pleasing and functional; other works treat these aspects of the design process. Thermal analyses can be done by simulation methods that were touched on in Chapter 10 and are discussed in more detail in Chapter 19 or by design methods that are to be covered in Chapters 20 and 21. Economic analyses are done by the  $P_1$ ,  $P_2$  method.

### 13.1 HISTORICAL NOTES

A gift by Godfrey L. Cabot to the Massachusetts Institute of Technology for solar energy studies in 1938 marked the beginning of modern research in solar heating. The MIT program resulted in development of methods of calculating collector performance (see Chapter 6) which, with some modification, are standard methods in use today. It also resulted in the successive development of a series of five solar-heated structures. MIT House IV was a residence equipped with a carefully engineered and instrumented system based on solar water heaters and water storage. The solar heating system was designed to carry approximately two-thirds of the total winter heating loads in the Boston area, and its performance was carefully monitored. In the two years of its experimental operation it supplied 48 and 57% of the combined heating and hot-water loads, the weather being substantially better in the second year than the first (Engebretson, 1964). This series of experiments has provided much of the background information on liquid systems that has been used in development of these systems in the four decades since.

Telkes and Raymond (1949) described a solar house at Dover, Massachusetts, that utilized vertical south-facing air heater collectors and energy storage in the heat of fusion of sodium sulfate decahydrate. This system was designed to carry the total heating load, having theoretical capacity in the storage system to carry the design heating loads for five days.

Bliss (1955) constructed and measured the performance of a fully solar heated house in the Arizona desert using a matrix, through-flow air heater and a rock bed energy storage unit. He noted that the system as built did not represent an economic optimum, and a smaller system using some auxiliary energy would have resulted in lower cost.

Löf designed an air heating system using overlapped glass-plate collectors and a pebble bed for energy storage and, using these concepts, built a residence near Denver in which he and his family have lived since 1959. The performance of this system during the first years of its operation was studied and reported by Löf et al. (1963, 1964) and was again measured in 1976 to 1978. The data are particularly significant in that they are the only data available on a system that has been in operation over a time span of 18 years when essentially no maintenance work was done on it. It was found that the performance in the second measurement period was about 78% of the original; the drop was attributed to breakage of glass inside of the collectors, a problem that more modern collectors do not have. Experience with this system provides evidence that well-designed and well-built air systems can operate reliably over many years with very little maintenance.

Close et al. (1968) described a heating system used for partial heating of a laboratory building in Australia that was operated for many years. This system used a 56-m<sup>2</sup>

vee-groove air heater and a pebble bed storage unit. Airflow through the collectors was modulated to obtain a fixed  $55^{\circ}\text{C}$  air outlet temperature.

Since 1970, many varied experimental systems have been built, and the performance of a few of them has been measured and reported. These experiments have led to commercial production of both liquid and air systems, and these have been sold and installed by the thousands. Weiss (2003) discusses the design and optimization of many different European “solar combisystems” (i.e., solar houses with solar domestic hot water).

## 13.2 SOLAR HEATING SYSTEMS

Figure 13.2.1 is a schematic of a basic solar heating system using air as the heat transfer fluid, with a pebble bed storage unit and auxiliary furnace. The various modes of operation are achieved by appropriate damper positioning. Most air systems are arranged so that it is not practical to combine modes by both adding energy to and removing energy from storage at the same time. The use of auxiliary energy can be combined with energy supplied to the building from collector or storage if that supply is inadequate to meet the loads. In this system configuration it is possible to bypass the collector and storage unit when auxiliary alone is being used to provide heat.

A more detailed schematic of an air system is shown in Figure 13.2.2. Blowers, controls, means of obtaining service hot water, and more details of ducting are shown. The hot-water subsystem is the same as that shown in Figure 12.8.1. Auxiliary energy for space heating is added to “top off” that available from the solar energy system. This is the air system configuration on which the design procedure of Chapter 20 is based. Table 13.2.1 shows typical design parameters for heating systems of this type.

Air systems have a number of advantages compared to those using liquid heat transfer media. Problems of freezing and boiling in the collectors are eliminated and corrosion problems are reduced. The high degree of stratification possible in the pebble bed leads to lower collector inlet fluid temperatures. The working fluid is air, and warm air heating systems are in common use. Control equipment is readily available that can be applied to these systems. Disadvantages include the possibility of relatively high fluid pumping costs (if the system is not carefully designed to minimize pressure drops), relatively large





Figure 13.2.1 Schematic of basic hot-air system.



**Figure 13.2.2** Detailed schematic of a solar heating system using air as the heat transfer fluid.

**Table 13.2.1** Typical Design Parameters for Solar Air Heating Systems

Collector airflow rate	5 – 20 liters/m <sup>2</sup> s
Collector slope	$(\phi + 15^\circ) \pm 15^\circ$
Collector surface azimuth angle	$0^\circ \pm 15^\circ$
Storage capacity	0.15 – 0.35 m <sup>3</sup> pebbles/m <sup>2</sup>
Pebble size (graded to uniform size)	0.01 – 0.03 m
Bed length, flow direction	1.25 – 2.5 m
Pressure drops:	
Pebble bed	55 Pa minimum
Collectors	50 – 200 Pa
Ductwork	10 Pa
Maximum entry velocity of air into pebble bed (at 55-Pa drop in bed)	4 m/s
Water preheat tank capacity	1.5 × conventional heater

volumes of storage, and the difficulty of adding solar air conditioning to the systems. Air systems are relatively difficult to seal, and leakage of solar-heated air from collectors and ductwork can represent a significant energy loss from the system. Air collectors are operated at lower fluid capacitance rates and thus with lower values of  $F_R$  than are liquid heating collectors.

Air heating collectors in space heating systems are usually operated at fixed airflow rates, with outlet temperatures variable through the day. It is possible to operate them at fixed outlet temperature by varying the flow rate. This results in reduced  $F_R$  and thus reduced collector performance when flow rates are low. It leads to a reduction in required storage volume by changing the shape of the temperature profiles in storage beds




Figure 13.2.3 Schematic of basic hot-water system.

from those of Figure 8.5.3 to those of Figure 8.5.2. The uniform bed temperature means that sufficiently warm air can be delivered from storage, which can improve comfort conditions.

Figure 13.2.3 is a schematic of a basic water heating system with water tank storage and auxiliary energy source. This system allows independent control of the solar collector-storage loop on the one hand and storage-auxiliary-load loop on the other, as solar-heated water can be added to storage at the same time that hot water is removed from storage to meet building loads. In the system illustrated, a bypass around the storage tank is provided to avoid heating the storage tank with auxiliary energy.

More details of a liquid-based system are shown in Figure 13.2.4. A **collector heat exchanger** is shown between the collector and storage tank, allowing the use of antifreeze




Figure 13.2.4 Detailed schematic of a liquid-based solar heating system: P, pump; C, controller; T, temperature sensor; B, blower.

**Table 13.2.2** Typical Design Parameter Ranges for Liquid Solar Heating Systems

Collector flow rate	0.010 – 0.020 kg/m <sup>2</sup> s
Collector slope	$(\phi + 15^\circ) \pm 15^\circ$
Collector azimuth	$0^\circ \pm 15^\circ$
Collector heat exchanger	$F'_R/F_R > 0.9$
Storage capacity	50 – 100 liters/m <sup>2</sup>
Load heat exchanger	$1 < \varepsilon_L C_{\min}/(UA)_h < 5$
Water preheat tank capacity	1.5 × conventional heater

solutions in the collector. Relief valves are shown for dumping excess energy should the collector run at excessive temperatures. A **load heat exchanger** is shown to transfer energy from the tank to the heated spaces. Means of extracting energy for service hot water are indicated. Auxiliary energy for heating is added so as to top off that available from the solar energy system. (This system is the basis of the liquid system design method discussed in Chapter 20.) Typical design parameter values for systems of this type are shown in Table 13.2.2.

The load heat exchanger, the exchanger for transferring solar heat from the storage tank to the air in the building, must be adequately designed to avoid excessive temperature drop and corresponding increase in tank and collector temperatures. The parameter describing the exchanger is  $\varepsilon_L C_{\min}/(UA)_h$ , where  $\varepsilon_L$  is the effectiveness of the exchanger,  $C_{\min}$  is the lower of the two fluid capacitance rates (mass flow rate times specific heat of the fluid) in the heat exchanger (usually that of the air), and  $(UA)_h$  is the building overall energy loss coefficient–area product.

An alternative to the use of antifreeze loops to transfer heat from the collector is a drain-back (or drain-down) system. This method of freeze protection was used in MIT House IV.

Advantages of liquid heating systems include high collector  $F_R$ , smaller storage volume, and relatively easy adaptation to supply of energy to absorption air conditioners.

Use of water also involves problems. Freezing of collectors must be avoided, as outlined in Chapter 12 for water heaters. Solar heating systems using liquids will operate at lower water temperatures than conventional hydronic systems and will require more baseboard heater area (or other heat transfer surface) to transfer heat into the building. In spring and fall, solar heaters will operate at excessively high temperatures, and means must be provided to vent energy to avoid pressure build-up and boiling. Care must also be exercised to avoid corrosion problems.

It is useful to consider solar systems as having four basic modes of operation, depending on the conditions that exist in the system at a particular time:

- A. If solar energy is available and heat is not needed in the building, energy gain from the collector is added to storage.
- B. If solar energy is available and heat is needed in the building, energy gain from the collector is used to supply the building need.

- C. If solar energy is not available, heat is needed in the building, and the storage unit has stored energy in it, the stored energy is used to supply the building need.
- D. If solar energy is not available, heat is needed in the building, and the storage unit has been depleted, auxiliary energy is used to supply the building need.

Note that there is a fifth situation that will exist in practical systems. The storage unit is fully heated, there are no loads to be met, and the collector is absorbing radiation. Under these circumstances, there is no way to use or store the collected energy and this energy must be discarded. This can happen through operation of pressure relief valves or other energy-dumping mechanisms, or if the flow of fluid is turned off, the collector temperature will rise until the absorbed energy is dissipated by thermal losses.

Additional operational modes may also be provided, for example, to provide service hot water. It is possible with many systems to combine modes, that is, to operate in more than one mode at a time. Many systems do not allow direct heating from collector to building but transfer heat from collector to storage whenever possible and from storage to load whenever needed.


To illustrate the system configurations, modes of operation, and designs of air and water systems, the following sections describe the design and performance of residential-scale installations. These systems were carefully engineered, and their performance has been measured and the results documented. The buildings and systems are the Colorado State University (CSU) House III drain-back liquid system and the CSU House II air system. Three houses with varying architectural treatment, CSU House II, MIT House IV, and the Löff Denver residence, are shown in Figure 13.2.5.

### 13.3 CSU HOUSE III FLAT-PLATE LIQUID SYSTEM

The CSU solar houses at Ft. Collins, Colorado, are residential-scale buildings that are used as offices and laboratories. The thermal loads on the buildings, for heating and air conditioning, are representative of those of conventional, well-built three-bedroom residences. The buildings serve as “test beds” for development of solar heating and air conditioning systems. Each system that is installed on one of the three houses is operated for at least a heating (and/or cooling) season, and its performance is carefully monitored. In this and the following section the results of two of these operations are described. The systems described here may be more carefully designed, built, and operated than most domestic systems, and their performance may be somewhat better than can be expected of many commercial systems. However, their performance represents achievable goals for commercial systems.

House III is a two-story frame building with a floor area of about 130 m<sup>2</sup> per floor. The estimated  $(UA)_h$  of the building is 420 W/°C, including an infiltration rate of one air change per hour. The 48.7 m<sup>2</sup> of collectors are mounted on a south-facing roof at a slope of 45°. Thermal energy storage is in a 4500-liter horizontal, insulated water tank on the lower level. The water heating subsystem includes a double-walled heat exchanger between the main storage tank and the 300-liter hot-water tank. Auxiliary energy for building heating is supplied in parallel with the solar heat by an air-to-air heat pump (which as far as the solar






**Figure 13.2.5** Three solar heated buildings: (a) Denver House; (b) MIT House IV (Courtesy of H. C. Hottel); (c) CSU House II (Courtesy of Colorado State University).

operation is concerned is the equivalent of a furnace). A schematic of the system is shown in Figure 13.3.1. The building, the system, and its operation are described by Karaki et al. (1984). (The system also included an absorption air conditioner for summer cooling; this will be noted in Chapter 15.)

The collectors are Revere double-glazed, flat-plate collectors with tempered glass covers, copper absorber plates, and black chrome selective surfaces;  $F_R(\tau\alpha)_n = 0.71$  and  $F_R U_L = 4.2 \text{ W/m}^2 \text{ } ^\circ\text{C}$ . When the collector circulation pump is not operating, the collectors drain back into the main storage tank. Piping and manifolds are designed to be large enough so that the water in the collectors will drain completely on shutdown.

The storage tank is fitted with stratification manifolds on the inlet pipes from both collector and load. These are shown schematically in Figure 8.4.2. Water enters the inlet chamber horizontally, and momentum is dissipated radially in the chamber. The water then flows up or down in the perforated pipe to the region where its density matches that of the water in the tank. Temperatures at several levels in the tank and collector inlet and outlet



**Figure 13.3.1** Schematic of the CSU House III heating system. From Karaki et al. (1984).

temperatures are shown in Figure 13.3.2 for two flow rates. At both rates, the temperatures in the top and bottom of the tank are close to the collector inlet and outlet temperatures, indicating that the stratification obtained is close to the maximum possible.


The performance of the building heating system for a season is shown in Figure 13.3.3. During this time the solar heating system met 80% of the space-heating load on the building. (The solar contribution in March was reduced when the tank was drained and refilled for experiments on effects of collector flow rate.) The performance of the system for water heating is shown in Figure 13.3.4 for the same months; the fraction of the water heating loads carried by solar was 0.36. (The March contribution was again reduced by experimentation. Summer operation of the water heating system, when the tank was at higher temperatures for air conditioning, resulted in solar contributions of 90 to 100%.)

A cumulative performance plot for the heating season showing total loads (in MJ) and solar contributions to meeting the loads is shown in Figure 13.3.5.

## 13.4 CSU HOUSE II AIR SYSTEM


An experiment on CSU House II used an air system with conventional air heating collectors and a nearly cubic pebble bed energy store. The system configuration is shown in Figure 13.4.1 and is essentially the same as is shown in Figure 13.2.2. The house is nearly identical in appearance to CSU House III, as shown in Figure 13.2.5. The system as it was installed and operated in 1977 to 1978 is described, and its performance is summarized by Ward et al. (1977) and Karaki et al. (1977, 1978). (Since 1978, the building has been used for other system experiments.)

The building serves as an office and laboratory and has 130 m<sup>2</sup> floor area on the first floor and an equal area on a basement level. The collectors in the experiment were site built and were similar in design to air collectors available on the commercial market. They




**Figure 13.3.2** Temperatures in and out of the collector and at several levels in the storage tank in CSU House III at collector flow rates of (a)  $0.0034 \text{ kg/m}^2 \text{ s}$  and (b)  $0.0086 \text{ kg/m}^2 \text{ s}$ . From Karaki et al. (1984).


occupied an area of  $68.4 \text{ m}^2$  on the south roof and had  $64.1 \text{ m}^2$  net collector area. The storage unit contained  $10.2 \text{ m}^3$  of pebbles 20 to 40 mm in diameter. The auxiliary energy source was a gas-fired duct furnace. Domestic water preheat was obtained by an air-to-water heat exchanger; the preheat tank capacity was 300 liters. The system configuration required only one blower for the heating operation; it had a second blower for providing heated air to the hot-water subsystem in the summer.




**Figure 13.3.3** Monthly performance of the CSU House III flat-plate space heating system. March performance was reduced by experiments. From Karaki et al. (1984).



**Figure 13.3.4** Monthly water heating performance of the CSU House III system. Adapted from Karaki et al. (1984).



**Figure 13.3.5** Measured cumulative performance of the CSU House III system.



**Figure 13.4.1** Schematic of the system in CSU House II. From Karaki et al. (1977).

Controls on the collector loop during the heating season were based on temperature measurements in the top of the collectors and the bottom of the storage unit; when the difference of these two exceeded  $11^{\circ}\text{C}$ , the blower was turned on, and it remained on until the difference dropped to  $0.6^{\circ}\text{C}$ . The solar-heated air went to the building when heat was needed; otherwise it went to storage. A thermostat in the building sensed when the rooms needed heat and positioned the dampers to obtain heat from the collector (if available) or storage. If room temperature dropped  $1.1^{\circ}\text{C}$  below the control point, a second-stage contact was made and the auxiliary gas duct heater was turned on.

The house and its heating system were extensively instrumented, and data for most of the winter of 1976 to 1977 (except for some days when instrumentation was not operable) are shown in Table 13.4.1. For this heating season, the solar heating system carried 72% of the heating and domestic hot-water (DHW) loads. The parasitic power for operation of the solar energy system was 7.4% of the delivered solar energy for space and water heating, resulting in a *coefficient of performance* (COP), the ratio of solar energy delivered to electrical energy to operate the system, of 13.5 for the heating season.

**Table 13.4.1** Thermal Performance Data for Solar House II<sup>a</sup>

	1976		1977			
	Nov 24 days	Dec 10 days	Jan 26 days	Feb 20 days	Mar 27 days	Apr 18 days
Collector (MJ/m <sup>2</sup> day)						
Total solar insolation	13.5	15.8	15.1	15.6	17.7	14.2
Solar insolation while collecting	11.2	13.8	12.9	13.6	15.6	12.2
Heat collected	3.1	4.9	4.6	4.7	5.0	3.7
Efficiency, %						
Based on total solar insolation	23	31	30	30	28	26
Based on insolation while collecting	28	36	36	35	32	30
Total energy required (MJ/day)						
Space	311.6	323.2	432.9	319.9	319.0	192.3
DHW	40.6	52.3	73.0	82.9	75.4	62.8
Total	352.2	375.5	505.9	402.8	394.4	255.1
Solar contribution (MJ/day)						
Space	198.7	257.5	231.4	239.6	245.8	166.1
DHW	21.3	30.8	63.5	75.4	67.4	51.8
Total	220.0	288.5	294.9	315.0	313.2	217.9
Solar fraction						
Space	0.64	0.80	0.53	0.75	0.77	0.86
DHW	0.52	0.59	0.87	0.91	0.89	0.82
Total	0.62	0.77	0.58	0.78	0.79	0.85


<sup>a</sup>From Karaki et al. (1977).

## 13.5 HEATING SYSTEM PARAMETRIC STUDY

In the preceding sections we discussed the design and measured performance of two solar heating systems. Of necessity, each of these systems was of fixed design and was operated and monitored in the particular weather sequence experienced during the operation. Simulations and design procedures,<sup>1</sup> on the other hand, offer the opportunity to determine the effects of changes in system configuration and design parameters and changes in climate on annual performance. In this section, computed performance is used to illustrate the effects of collector area and storage capacity on monthly and annual solar fractions. The meteorological data used are hourly data for a Madison design year, as defined by Klein et al. (1976).

The system in this simulation is similar to that in Figure 13.2.2 and is shown in Figure 13.5.1. It is to provide space heating and hot water for a well-insulated residence of 150 m<sup>2</sup> floor area. Internal heat generation, infiltration, and capacitance of the building are considered. The hot-water demand is 300 liters per day, assumed distributed through the day according to the load profile shown in Figure 9.2, with water entering at 11°C and supplied to the building at 55°C.

<sup>1</sup>As described in Chapters 19, 20, and 21.



**Figure 13.5.1** Schematic of the air system simulated in the Madison simulation example. Details of blowers, pumps, etc., are not shown.

The collectors are air heaters of design similar to that in Figure 6.14.1(b), with  $F_R(\tau\alpha) = 0.62$ . The  $F_R U_L$  is assumed fixed at  $3.38 \text{ W/m}^2\text{C}$ , and airflow rate to collectors is  $0.0125 \text{ kg/m}^2 \text{ s}$ . Collector areas of 10, 30, 55, and  $105 \text{ m}^2$  were used in the simulations. The collector slope is  $58^\circ$  and surface azimuth angle is zero. Ground reflectance is assumed to be 0.2 at all times.

The pebble bed is sized so that its volume is at a fixed ratio to the collector area of  $0.25 \text{ m}^3/\text{m}^2$ . The bulk density of the pebble bed is  $1600 \text{ kg/m}^3$ , and the specific heat of the pebbles is  $840 \text{ J/kg}^\circ\text{C}$ . The loss coefficient of the pebble bed is  $0.5 \text{ W/m}^2\text{C}$ , and losses from the bed are to a  $20^\circ\text{C}$  environment. To show the effects of relative pebble bed size, simulations were done at 25, 50, and 200% of the nominal size for collector areas of 30 and  $55 \text{ m}^2$ .


The auxiliary heater has a maximum capacity of 13.9 kW. The heating system is controlled by a two-stage thermostat which is designed to keep the building near  $20^\circ\text{C}$ . When heat is needed, solar heat is called first. If that will not hold the temperature, the solar heating system is turned off and the auxiliary is turned on. These control modes are indicated in Figure 13.5.2. In summer (June, July, and August), the pebble bed is bypassed so that heat is supplied only to the hot-water preheat tank, and the collector fan operates when the preheat tank is below its control temperature and the collector can deliver energy. The volume of the water preheat tank is  $0.35 \text{ m}^3$ , and its loss coefficient is  $0.5 \text{ W/m}^2\text{C}$ .

Figure 13.5.3 shows the annual solar fraction  $\mathcal{F}$  as a function of the collector area for the normal storage volume–collector area ratio and also shows points for larger and smaller storage capacities for the 30 and  $55 \text{ m}^2$  collector areas. This is a typical  $\mathcal{F}$ -versus- $A_c$  curve for house heating, in that the slope is substantially higher at small collector areas than at large collector areas. The large collectors are oversized a greater part of the year than are the small collectors. Thus an increment in collector area produces more useful energy at small collector areas than at large areas. The effects of change of storage size are

Room temp, °C	Direction of change	Solar heating system	Auxiliary heating system
21.5	↓	Off	Off
	↑	Turns off <sup>1</sup>	Off
20.0	↓	Turns on	Off
	↑	On	Off
19.9	↓	On	Off
	↑	Turns on <sup>2</sup>	Turns off <sup>1</sup>
18.5	↓	Turns off	Turns on
	↑	Off	On

<sup>1</sup> Turns off if on<sup>2</sup> Turns on if off

**Figure 13.5.2** The control logic used in the Madison simulations. In addition to the functions shown, it is a requirement that the solar energy system must be able to supply air at a temperature above 30°C. If it cannot, it is off regardless of the room temperature.





**Figure 13.5.3** Solar fraction  $\mathcal{F}$  as a function of collector area for the Madison simulations. The circled points and curves are for the normal storage size of 0.25 m³ of storage per square meter of collector. The triangles show the effect of increasing storage size to 0.50 m³/m², and the dots show the effects of decreasing it to 0.125 and 0.063 m³/m².

small for the 30-m² collector, as for much of the year the bottom of the bed is at a higher average temperature, resulting in increased air temperature to the collector.

Figure 13.5.4(a) shows the monthly fraction of loads carried by solar for the four collector areas for the normal storage volume–collector area ratio. All of these systems will carry most of the summer hot-water loads. (There are a few times during the design year when auxiliary heat is used to supply hot water during prolonged cloudy periods, and storage capacity limits solar fractions to less than unity.) The largest system meets 95% or more of the loads through nine months, while the smaller systems meet relatively small fractions of the monthly loads in midwinter.






**Figure 13.5.4** Data for four collector areas from the Madison simulations: (a) monthly fraction of loads carried by solar energy; (b) monthly system efficiencies.

Figure 13.5.4(b) shows essentially the same information but is in terms of the monthly efficiencies of the system for the four areas. System efficiency is defined here as the total useful solar energy delivered to the building for the month divided by the total energy incident on the collector in the month. Annual efficiencies  $\eta_a$  are also indicated for the four collector areas. It is clear that the efficiencies of this collector can vary over a very wide range, depending on the relative magnitudes of loads and insolation. (Variations of instantaneous efficiencies are greater than those shown for months.) The larger collectors are oversized for longer periods of the year and operate at higher temperatures and lower efficiencies.

Figure 13.5.5 indicates the cumulative energy quantities, starting from zero at the beginning of the heating season, for the  $55\text{-m}^2$  system with normal storage capacity. It



**Figure 13.5.5** Cumulative loads and solar contributions for the 55-m<sup>2</sup> collector area and 0.25 m<sup>3</sup> of storage per square meter of collector of Madison simulations.

**Table 13.5.1** Annual Energy Quantities for the Madison Simulations

Collector Area (m <sup>2</sup> )	Storage Volume (m <sup>3</sup> )	Solar Energy to Space Heating (GJ)	Solar Energy to Hot Water (GJ)	Total Heating Hot-Water Loads <sup>a</sup> (GJ)	$\mathcal{F}$
10	2.50	11.1	10.7	86.9	0.25
30	7.50	32.7	14.5	89.3	0.53
55	13.75	51.7	15.9	91.2	0.74
105	26.25	68.3	16.9	92.7	0.92

<sup>a</sup>The loads are to some degree a function of system size, as larger systems keep the building at slightly higher mean temperatures.

indicates the cumulative total loads and the heating and hot-water loads met by solar through the year.

The cumulative energy quantities are summarized in Table 13.5.1. These are used in the discussion of economics of solar heating (see Section 13.10).

## 13.6 SOLAR ENERGY–HEAT PUMP SYSTEMS


Heat pumps use mechanical energy to transfer thermal energy from a source at a lower temperature to a sink at a higher temperature. Electrically driven heat pump heating systems

have attracted wide interest as an alternative to electric resistance heating or expensive fuels. They have two advantages: a COP (ratio of heating capacity to electrical input) greater than unity for heating, which saves on purchase of energy, and usefulness for air conditioning in the summer. Heat pumps may use air or water sources for energy, and dual-source machines are under development that can use either.


Yanagimachi (1958, 1964) and Bliss (1964) built and operated heating and cooling systems that use uncovered collectors as daytime collectors and nighttime radiators, “hot”- and “cold”-water storage tanks to supply heating or cooling to the buildings, and heat pumps to assure maintenance of adequate temperature differences between the two tanks. The Yanagimachi system was applied to several houses in the Tokyo area, and the Bliss system was used on a laboratory in Tucson, Arizona.

Heat pumps have been studied by Jordan and Threlkeld (1954) and by an AEIC-EEI Heat Pump Committee (1956). An office building in Albuquerque was heated and cooled by a collector–heat pump system (Bridgers et al., 1957a,b). More recent systems have been built on residential buildings (e.g., Converse, 1976; Kuharich, 1976; Terrell, 1979).

A schematic of an air-to-air heat pump is shown in Figure 13.6.1 operating in the heating mode. The most common types in small sizes are air-to-air units. For a discussion of the design and operation of heat pumps, see, for example, ASHRAE (1976). Typical operation characteristics of a residential-scale heat pump are shown in Figure 13.6.2. As ambient air temperature (the evaporator fluid inlet temperature) increases, the COP increases, as does the capacity. As the air temperature drops, frost can form on the evaporator coils, which adds heat transfer resistance and blocks airflow. Brief operation of the heat pump in the cooling mode removes the frost (a defrost cycle) and causes the irregularity shown in the capacity and COP curves. Figure 13.6.2 also shows a typical building heating requirement curve, which crosses the capacity curve at the balance point (BP). At ambient temperatures below this point a heat pump will have inadequate capacity



**Figure 13.6.1** Schematic of a reversible heat pump system shown operating as a space heater.




**Figure 13.6.2** Operating characteristics of a typical residential-scale air-to-air heat pump as a function of ambient air temperatures for delivery of energy to a building at 20°C.

to heat the building, and the difference must be supplied by a supplemental source (often an electric resistance heater). At ambient temperatures above the balance point, the heat pump has excess capacity.

Several configurations of solar energy–heat pump systems are possible. Schematics of the energy flows of the most important of these are shown in Figure 13.6.3. Part (a) shows a **parallel** configuration, with the heat pump serving as an independent auxiliary source for the solar energy system, and (b) shows a **series** configuration with the heat pump evaporator supplied with energy from the solar energy system. It indicates that energy from the collector can be supplied directly to the building if the tank is hot enough. It also shows that such a system can be a **dual-source** configuration where the heat pump evaporator is supplied with energy either from the solar-heated tank or from another source (usually ambient air).

The performance of collectors is best at low temperatures, and the performance of heat pumps is best at high evaporator temperatures. This combination leads to consideration of series systems in which the evaporator of the heat pump is supplied with energy from the solar system. These systems are arranged and controlled so that solar heat can be added to the building directly from the storage unit when the storage temperature is high enough. Systems of this type typically use liquid collectors and water tank and a water-to-air heat pump.

In a dual-source system, the heat pump evaporator is supplied with energy either from the storage unit (often a liquid system) or from ambient air (or water source if another is



**Figure 13.6.3** (a) Schematic of energy flows in a parallel system. (b) Schematic of energy flow in series and dual-source solar energy-heat pump systems. In either case, an additional and independent auxiliary source (such as electric resistance heating) may have to be provided.

available). Solar energy can be supplied directly to the building. Controls can be arranged to select the source leading to the best heat pump COP, that is, the higher of the two source temperatures (although other control strategies may lead to better long-term system performance). An alternative design would use an air solar heating system and an air-to-air heat pump. The evaporator could be supplied from either ambient air or solar-heated air.

A parallel system could include either an air-based or a liquid-based solar energy system and an air-to-air heat pump. From the solar process point of view, the operation of this system is the same as a conventional solar heating system, but with the heat pump supplying the auxiliary energy.<sup>2</sup>

An integrated overall energy balance for a heat pump-solar energy heating system over a long time period includes  $Q_s$ , the energy supplied by the collector and tank;  $Q_{\text{air}}$ , the energy extracted from the source (air or water) by the heat pump;  $W_E$ , the electric energy used to operate the heat pump; and  $Q_A$ , the auxiliary energy needed to assure meeting the total heating load  $L$ . In equation form

$$Q_s + Q_{\text{air}} + W_E + Q_A = L \quad (13.6.1)$$

A useful index of system performance of these systems is the ratio of “nonpurchased” energy to the total load,  $\mathcal{F}'$ :

$$\mathcal{F}' = \frac{Q_s + Q_{\text{air}}}{L} \quad (13.6.2)$$


This fraction is analogous to the solar fraction  $\mathcal{F}$  defined for conventional solar heating systems.

Simulation studies have been used to compare these systems. Marvin and Mumma (1976) studied air systems of four configurations. Karman et al. (1976) considered two air


<sup>2</sup>Design of parallel heat pump systems is discussed in Section 20.7.

systems and a dual-source system and included simulations in Madison and Albuquerque climates. Hatheway and Converse (1981) simulated several system configurations and compared their thermal performance and economics in the Vermont climate and concluded that the best combination of solar and heat pump is in a parallel configuration. Mitchell et al. (1978) have computed the performance of series, dual-source, and parallel systems and a standard liquid solar heating system of the type of Figure 13.6.3(b) using Madison meteorological data. In this study, the heat pump was modeled using the published performance data of a typical recent model commercial heat pump. The simulations were done using TRNSYS. Figure 13.6.4 summarizes the results for Madison, showing  $\mathcal{F}'$  as a function of collector area for a typical residential-type building. Figure 13.6.5 shows comparative information for a collector area of 30 m<sup>2</sup> for each of the three combined systems and the conventional solar and heat-pump-only systems.

The results of these simulations show that with the same collector the parallel system is substantially better than the series system and slightly better than the dual-source system in all collector sizes, in that it delivers a greater fraction of the loads from non-purchased sources. This arises because the heat pumps in the series and dual-source systems must operate to deliver all solar energy stored below 20°C. The extra electrical energy required to deliver this energy more than compensated for the combined advantages of higher collector efficiency and higher heat pump COP. The temperature of storage in the series



**Figure 13.6.4** The Fraction of energy from nonpurchased sources,  $\mathcal{F}'$ , for series, parallel, dual-source, heat-pump-only, and standard solar energy systems as function of collector area based on simulations of the systems on a residential building in the Madison climate. From Freeman et al. (1979).



**Figure 13.6.5** Sources of energy used for heating under the same circumstances as those of Figure 13.6.4. Collector areas are  $30 \text{ m}^2$  for the solar energy systems. From Freeman et al. (1979).

system (and in the dual-source system) in these simulations is rarely high enough to permit direct solar heating.

The simulations described by Mitchell et al. (1978) were done with the same collector for each of the system configurations. The series collector will run cooler for part of the time than will the collector for the parallel or dual-source system. Thus there is the possibility that less expensive collectors will be adequate for the series system. An economic comparison must be made which takes into account the collector operating temperature ranges for each of the systems.

The combined height of the left bars of Figure 13.6.5 for each of the systems is  $\mathcal{F}'$ . The systems are arranged from left to right in order of decreasing  $\mathcal{F}'$  or increasing purchased energy. The data for the series and dual-source heat pump systems show higher solar energy contribution, as is to be expected with reduced collector temperature, but they also show higher purchased energy. The yearly computed COP for the heat pumps for the parallel, dual-source, series, and heat-pump-only systems were 2.0, 2.5, 2.8, and 2.1, indicating that the series system heat pump with the solar source has the highest mean evaporator temperature and the highest annual COP.

Increasing the COP of a heat pump in a series system configuration does not lead to substantial reduction of collector area. If a load of a specified size is to be met, the energy comes from either the solar-heated tank or the (electrical) input to the heat pump. Assuming that the electrical input is not a large fraction of the total, doubling or halving it will have little impact on the amount of energy to be delivered from the solar-heated tank. [Thus if an annual load is 100 GJ and 10 GJ of electrical energy is required to operate the heat pump, doubling of the annual COP will (approximately) halve the electrical energy requirements and add about 5% to the energy that must come from the solar energy system.]

Mitchell et al. (1978) have explored system design variables including storage size, heat pump characteristics, and reduced minimum tank temperatures (i.e., antifreeze solutions in the storage tank) and found no significant changes in the results of the simulations. Marvin and Mumma (1976) also concluded that parallel operation led to best thermal performance. Many experimental systems in the series configuration have been installed, and based on economic considerations there may be circumstances for which series systems would be better than parallel systems.

Heat pumps are capital intensive, as are solar energy systems. Consideration of the economics of solar energy–heat pump systems indicates that it may be difficult to justify the investment in a heat pump to improve solar energy system performance unless the cost of the heat pump can be justified on the basis of its use for air conditioning or unless the use of the heat pump would reduce collector costs to a small fraction of their present levels.

### 13.7 PHASE CHANGE STORAGE SYSTEMS

Phase change energy storage materials, methods, and problems were reviewed in Chapter 8, and a model developed by Morrison and Abdel-Khalik (1978) for a phase change energy storage unit was presented. This section reviews the results of the use of this model in simulation studies of solar heating systems to evaluate the possible impact of successful development of a phase change storage unit on heating system performance.

A number of buildings have been built using phase change storage. Telkes and Raymond (1949) described a solar house constructed at Dover, Massachusetts, that utilized vertical south-facing air heating collectors and energy storage in Glauber's salt,  $\text{Na}_2\text{SO}_4 \cdot 10\text{H}_2\text{O}$ , contained in 5-gal drums. The system was designed to have five days storage capacity and to carry the total heating load by solar energy. No data are available on its operation, which was terminated after a few years. Solar One, an experimental house at the University of Delaware (Boer, 1973; Telkes, 1975), used phase change storage units for energy storage at two temperature levels in a solar energy–heat pump system. Boer (1973) reported the use of Glauber's salt in drums in a storage wall. MIT House V uses phase change materials in thin layers in the ceiling of the passively heated structure (Johnson, 1977).

Morrison and Abdel-Khalik (1978), in a simulation study of effects of use of phase change storage on solar heating system performance, postulated an idealized phase change operation (free of superheating, supercooling, and property degradation), developed models for phase change storage units for incorporation in simulations of liquid and air heating systems, and made comparative simulation studies of several systems. Their infinite NTU model of the storage unit is outlined in Section 8.8. The phase change material properties used were those of Glauber's salt and P116 wax; the properties of materials are indicated in Table 13.7.1. Meteorological data for Madison, Wisconsin, and Albuquerque, New Mexico, were used.

Typical results of this study are shown in Figure 13.7.1(a) for air systems in Albuquerque. The air systems are the same configuration as that of Figure 13.2.2 using either the pebble bed or the phase change storage unit. The model of the phase change storage allows for flow reversal and temperature stratification in the bed in a manner similar to that of the pebble bed. The figure shows the annual fraction of heating loads carried by solar energy for a residential building for collector area of  $50 \text{ m}^2$  as a function of storage volume. For the idealized phase change units, these data show that the same thermal performance is obtained with smaller volumes of the phase change materials than with pebble beds or water tanks and that the annual performance of systems with any of the three storage media is nearly the same as long as the volume of the storage media is above the “knee” of the curve. Similar results were obtained at other collector areas and with collectors having two different heat loss coefficients.



**Table 13.7.1** Properties of Phase Change Storage Media and Rock<sup>a</sup>

Property	Paraffin Wax	Na <sub>2</sub> SO <sub>4</sub> · 10H <sub>2</sub> O	Rock
$C_{ps}$ , J/kg °C	2890	1920	840
$C_{pl}$ , J/kg °C	<sup>b</sup>	3260	
$k_s$ , W/m °C	0.138	0.514	0.125
$k_l$ , W/m °C	<sup>b</sup>	<sup>c</sup>	
$T^*$ , °C	46.7	32	
$\lambda$ , MJ/kg	0.209	0.251	
$\rho_s$ , kg/m <sup>3</sup>	786	1460	1600
$\rho_l$ , kg/m <sup>3</sup>	—	1330	

<sup>a</sup>From Morrison and Abdel-Khalik (1978).<sup>b</sup>Assumed equal to value for the solid phase.<sup>c</sup>Assumed to be 0.475 W/m °C, the value for liquid Na<sub>2</sub>HPO<sub>4</sub> · 12H<sub>2</sub>O


Figure 13.7.1(b) shows results of similar computations for liquid systems in Madison. The basic system configuration in these simulations was that shown in Figure 13.2.4, with storage in either water in the tank or a phase change unit. These simulation results indicate that the system with the idealized Na<sub>2</sub>SO<sub>4</sub> · 10H<sub>2</sub>O store is better than that with the wax storage medium. The same general conclusions can be reached as for air systems, that is, the annual performance of heating systems using idealized phase change storage is nearly the same as that with sensible heat storage but the storage volumes are significantly smaller.

In all of these systems, the phase change material operates in sensible heat modes as a solid part of the time, as a liquid part of the time, and in a combined phase change and sensible heat mode part of the time. Systems carrying larger fractions of annual loads by solar tend to operate as liquid phase sensible heat stores larger fractions of the time.

These results, based on ideal phase change storage characteristics, represent upper bounds to the performance of heating systems using Glauber's salt or P116 wax. Any change from the ideal can be expected to result in a greater proportion of the operation being in sensible heat modes and a reduction in effective storage capacity. This will lead to a small reduction in annual system output if the storage capacity is very large. If the storage volume is at or near the knee in the curve, deviations from idealized phase change behavior may cause large reductions in annual system output.

Jurinak and Abdel-Khalik (1978) have used the same phase change storage model and idealized behavior and explored the possibilities of improvements in system performance on changing the melting point, latent heat, and melting point range (of mixes of wax-type materials). They found that "fine tuning" of the properties of the materials did not lead to significant increases in long-term system performance. In another paper (1979) they developed the concept of an effective heat capacity of phase change material, as indicated in Section 8.8. This concept permits use of quick design procedures<sup>3</sup> to estimate the performance of systems with phase change storage.

<sup>3</sup>See Chapters 20 to 22.



**Figure 13.7.1** Comparison of annual performance of (a) air systems with phase change or pebble bed storage in Albuquerque and (b) liquid systems with phase change or water tank storage in Madison. From Morrison and Abdel-Khalik (1978).

Successful application of phase change storage in solar heating depends on availability of materials that can cycle thousands of times without significant degradation and which can be packaged or handled without corrosion. The economic feasibility will depend on what the phase change material costs, the expense of packaging it, and the value of the space it saves in the building.

### 13.8 SEASONAL ENERGY STORAGE SYSTEMS

Early studies of the possibility of storing summer solar energy for use in the winter centered on systems for single residential-scale buildings. One of the first was that of Speyer (1959), who concluded that increasing storage capacity to high levels results in reduction of collector area requirements but that the cost of seasonal storage was not justified in terms of increased annual output of the system. Similar conclusions have been reached by others, and most solar heating studies have concerned storage capacities equivalent to approximately one to three days design heating loads of the building. A more optimistic view of long-term storage and a method of estimating heat losses from tanks to ground are provided by Hooper and Attwater (1977).<sup>4</sup>


Another approach to seasonal storage is to consider larger systems with storage capacity orders of magnitude more than those for single residential-scale buildings. In these systems, which are designed to provide heat for communities (i.e., district heating systems), the losses from storage are reduced by the fact that the area for heat loss goes up roughly as the square of the linear dimension of the store, and its capacity goes up roughly as the cube of the linear dimension. Considerable work has been done on these systems, largely in Europe and particularly in Sweden; the prospects for diurnal heating systems (with “overnight” storage) in northern latitudes with short winter days do not appear promising. As pointed out by Bankston (1988) in a review of central solar heating plants, such systems should have low storage losses because of the large storage size, should benefit from reduced costs of large-scale installations, would allow supply of solar energy to buildings with limited solar access, and operation and maintenance of the plants would be the responsibility of paid staff rather than the individual building occupants. Most of the energy collection would occur when ambient temperatures are highest, so the collectors in these systems should perform better than those in diurnal storage systems.

The system configurations for seasonal storage are basically the same as those for short-term (overnight) storage, and most of them have been liquid systems such as that of Figures 13.2.3 and 13.2.4. Some have been combined solar energy–heat pump systems with the heat pumps in series with the tanks. The differences between the two types of systems are in the relative and absolute sizes of the collectors and the storage systems. The capacity of seasonal storage must be large enough to store most or all of the energy over and above the summer loads that is collected. Thus the ratio of storage to collector area is much higher for seasonal storage systems.

The plot of solar fraction versus water storage capacity shown in Figure 11.2.2 covers the usual range of storage capacities considered in building heating. Figure 13.8.1, from Braun (1980), is based on a similar analysis but shows four orders of magnitude variation in water tank storage capacity. The simulations were done using Madison meteorological data. System parameters (other than storage size) were like those of systems with ordinary storage capacity (except that the tank is very heavily insulated). Three collector areas are shown, which with liquid storage of 75 liters/m<sup>2</sup> would deliver 39, 63, and 85% of the annual loads by solar energy. The 50-m<sup>2</sup> collector would supply 21% of the load with no storage. To approach 100% heating by solar, the tank would be of the same order of magnitude in size as the heated spaces. (This study was done with a simple model for heat

---

<sup>4</sup>A simplified design method for systems with long-term storage is shown in Example 21.3.1.




**Figure 13.8.1** Fraction by solar as a function of storage capacity for three collector areas for example based on Madison meteorological data. Adapted from Braun (1980).

losses from storage; more refined models may show different magnitudes of the effects, but the trends will be the same.)

The solar fraction increases sharply as storage is added until approximately 30 liters/m<sup>2</sup> is reached. At this point the storage capacity is adequate to smooth out much of the diurnal solar variation. As more capacity is added to provide more than a day's storage, a gradual increase in solar fraction is noted. As the storage capacity increases by two orders of magnitude, a second knee in the curve appears as the capacity becomes adequate for seasonal storage (i.e., energy collected in the summer can be used in the winter). A similar relationship with two knees in the curve would be observed for community-scale systems.

As the solar fraction approaches unity in a system with seasonal storage (and, for that matter, in any solar energy system), year-to-year variation in weather must be considered. The 50-m<sup>2</sup> system shown at point X in the upper right-hand corner of Figure 13.8.1 was simulated for 21 years, with the results shown in Figure 13.8.2. Useful gain from the




**Figure 13.8.2** Year-to-year variation of performance of the 50-m<sup>2</sup> system with a storage capacity of 5500 liters/m<sup>2</sup>. From Braun (1980).

collector  $Q_u$ , losses from storage  $Q_{st}$ , load  $L$ , and energy supplied by solar  $L_S$  are shown as integrated quantities for each year. The difference between  $L$  and  $L_S$  must be supplied from an auxiliary source. In four of these years very little auxiliary energy was required, and in other years substantial amounts were required. Again, similar considerations hold for community-scale systems. Dalenbäck and Jilar (1987) have concluded that community-scale seasonal storage systems will probably be most economical at solar fractions of about 0.7.

Figure 13.8.3 shows the solar fraction as a function of collector area for a “normal” storage capacity, for very large storage capacity, and for no storage. For large storage, annual output is limited by collector area and is nearly proportional to collector area until the solar fraction approaches unity. The difference between the two curves at constant area is the possible improvement in annual system performance ( $\Delta \mathcal{F}$ ) that can be achieved by addition of large storage capacity. At constant solar fraction, the difference in the two curves ( $\Delta A_c$ ) represents the increment in area that can be saved by going to very large storage capacity. If no storage is provided, there is very little gain on increasing collector area beyond 50 m<sup>2</sup>. (The examples shown in these figures were calculated assuming no building capacitance. At low storage capacity, including building capacitance has the effect of adding some storage.<sup>5</sup>)

Methods for seasonal storage for community-scale applications were outlined in Section 8.7. Reviews of characteristics of 26 seasonal storage projects and experiments that have been built and operated are provided in publications of the International Energy Agency (IEA) (e.g., Dalenbäck, 1989) and by Bankston (1988). Characteristics of five of these are summarized in Table 13.8.1.



**Figure 13.8.3** Fraction by solar versus collector area for system with very large storage, standard storage of 75 liters/m<sup>2</sup>, and no storage. Adapted from Braun (1980).

<sup>5</sup>See Chapter 22.

**Table 13.8.1** Characteristics of Seasonal Storage Solar Heating Systems<sup>a</sup>


	Finland	France	Netherlands	Sweden	Sweden
Location	Kerava, 60° N	Aulnay-Sous-Boi, 49° N	Groningen, 53° N	Ingelstad, 57° N	Lyckebo, 60° N
Year built	1983	1983	1984	1979	1983
Load	44 residences, 1980 GJ	225 residences, 8900 GJ	96 residences, 4300 GJ	52 residences, 3380 GJ	550 residences, 25200 GJ
Delivery temperature, °C					
Maximum	60	50	43	80	70
Minimum	45	25		50	55
Collectors Area, (m <sup>2</sup> )	Flat plate 1100	Unglazed flat plate 1275	Evacuated 2400	Evacuated 1300	Parabolic 4300
Storage	Pit and duct/rock	Aquifer	Duct/clay	Tank	Rock cavern
Volume, m <sup>3</sup>	11,000	85,000	23,000	5000	100,000
Temperature range, °C	10–70	4–14	30–60	40–95	40–90
Capacity, GJ/yr	900	2500	2340	1080	19800
Annual $\eta$		—	0.68	—	0.74
Heat pump	Electric	Electric			
Capacity, kW electric	240	660			
Annual COP	2.7	3.9			
Solar	0.50	0.66	0.66	0.50	<sup>b</sup>
Contribution					
Heat pump	—	0.24			
Other auxiliary	—	0.10	0.34	0.50	

<sup>a</sup>Data are from Bankston (1988).<sup>b</sup>Part of the collectors have been installed; the balance of energy added to the storage is electrical.

## 13.9 SOLAR AND OFF-PEAK ELECTRIC SYSTEMS

Auxiliary energy can be supplied to solar heating systems from supplies stored on site (oil or LPG) or from utilities (gas or electricity). On-site storage poses no unique problems for the distributors of oil or LPG. Supply of auxiliary energy by utilities, in contrast, could cause significant peaking problems for electric utilities if a large number of solar-heated buildings all call for energy during bad weather. A potential solution to this problem is to supply electric auxiliary energy during off-peak periods and store the energy in the building. (The same possible solutions apply to systems that are not solar, i.e., are all electric.) Hughes et al. (1977) have studied off-peak electric options in air solar heating systems; the results of that study are summarized here.

Three systems were considered. The first is a conventional air solar heating system such as that shown in Figures 13.2.2 and 13.4.1; it requires delivery of auxiliary energy whenever solar energy cannot meet the load. The second, shown in Figure 13.9.1(a), uses an electric furnace to supply energy to a separate pebble bed storage unit. The auxiliary storage subsystem acts as any other auxiliary if it is controlled so that at the end of each off-peak period there is sufficient energy in the auxiliary store to meet the maximum anticipated heating loads on the building until the next off-peak period. The solar heating system should not be affected by the nature of the auxiliary energy supply if the combined



**Figure 13.9.1** Schematics of solar off-peak air systems with (a) two storage units and (b) a single store. From Hughes et al. (1977).

operation is such that the collectors operate at the low input temperatures characteristic of air systems.

The third system, shown in Figure 13.9.1(b), combines the storage of solar energy and auxiliary energy in a single unit. During off-peak periods, electrical energy is added to the pebble bed to assure having adequate energy stored in the bed to last until the next off-peak period. Solar energy is also added to the bed as it is available from the collectors. The pebble bed will operate at significantly higher temperatures with this system than with the system with separate storage units, which leads to higher collector temperatures and reduced collector performance. Stratification in the bed helps to diminish the elevation of collector temperature, but the effect is significant for flat-plate collectors. Compared to the two-store system, this system is mechanically simpler but suffers in performance.

The extent of this performance penalty depends on collector characteristics. Hughes et al. (1977) showed that the penalties for evacuated-tube collectors with  $U_L$  of about  $0.8 \text{ W/m}^2 \text{ } ^\circ\text{C}$  were substantially less than for flat-plate collectors with  $U_L = 4.0 \text{ W/m}^2 \text{ } ^\circ\text{C}$ ; the collectors with low  $U_L$  are not nearly as sensitive to temperature as those with  $U_L$  representative of those of flat-plate air heaters.

The off-peak addition of energy to a pebble bed can be controlled by comparing the average bed temperature to a set minimum average temperature which will assure that


adequate heat supply is available until the next off-peak period. The minimum average temperature may be fixed throughout the year or it may be varied to account for variable anticipated loads throughout the year. Collector performance will be influenced by the energy in storage, and there is an advantage in changing the minimum average temperature from month to month. This advantage is a few percent with low-loss collectors but is substantially larger with flat-plate collectors.

## 13.10 SOLAR SYSTEM OVERHEATING

System overheating will occur in solar-heated buildings in the summer or at other times when, over a sufficiently long period of time, the energy use is smaller than the energy delivered by the collectors. The storage tank will reach a maximum temperature (e.g., about  $95^{\circ}\text{C}$  for a water tank) and a control system will turn off the circulating pump. If precautions are not taken, the collectors will then reach their equilibrium (stagnation) temperature typically on the order of 150 to  $300^{\circ}\text{C}$  (see Section 6.58). At these temperatures the pressure in the collector can be very high and most collector fluids either will have been boiled off or far exceeded their maximum working temperature. Proper design of the collector fluid circuits can alleviate overheating problems.

Hausner [Chapter 7.2 in Weiss (2003)] has reviewed design solutions either to avoid boiling while the collectors remain full or to automatically empty the collectors. The most effective method for control is to lay out the collector plumbing in such a way that the fluid can easily return to an expansion tank. For example, if the collectors are arranged as shown on the left side of Figure 13.10.1, the liquid will be trapped in the bottom of the collectors and boiling will continue until all of the fluid is evaporated. Such a situation will result in high system pressures. By rearranging the same collectors as shown on the right side of the figure the fluid can easily drain. When the fluid boils, the bubbles will rise to the top and the increased pressure will force the liquid into the expansion vessel, effectively emptying the collectors without excessive temperatures and pressures.

The expansion vessel must be of sufficient size to hold all of the liquid in its expanded state. Check valves must be appropriately placed to ensure that the hot fluid can enter the expansion tank from both the filling and return leg. The pump must be placed so that the suction side is in contact with liquid at all times.



**Figure 13.10.1** Two collectors arranged with poor emptying behavior (left) and good emptying behavior (right). Adapted from Weiss (2003).



### 13.11 SOLAR HEATING ECONOMICS

The first major economic studies of solar heating by Tybout and Löff (1970) and Löff and Tybout (1973) were based on constant annual savings without anticipation of changing future costs. They devised a thermal model for a liquid-based solar heating system to estimate annual thermal performance (based on one year's meteorological data) and developed a set of cost assumptions to calculate costs of delivered solar energy for houses of two sizes in eight U.S. locations of differing climate types. Several system design parameters were studied in addition to collector area to establish the range of optimum values, including collector slope, number of covers, and heat storage capacity per unit collector area. Their results (which are in general agreement with the conclusions of others) can be summarized as follows:

- A. The optimum tilt is in the range of the latitude plus  $10^\circ$  to the latitude plus  $20^\circ$ , and variation of  $10^\circ$  either way outside of this range, that is, from latitude to latitude plus  $30^\circ$ , has relatively little effect on the cost of delivered energy for heating.
- B. The best number of (ordinary) glass covers with nonselective absorbers was found to be two for all locations except those in the warmest and least severe climates, that is, Miami and Phoenix, where one cover produces less expensive energy from the solar heating system.
- C. The best storage tank capacity per unit collector area was indicated to be in the range of 50 to 75 liters/m<sup>2</sup>. Increasing the size of storage severalfold for fixed collector size had relatively small effect on the cost of delivered solar energy or on the fraction of total heating loads carried by solar.

The costs assumed by Löff and Tybout (approximately \$20/m<sup>2</sup> and \$40/m<sup>2</sup> of collector, installed) are unrealistically low in the light of current costs (\$250/m<sup>2</sup> to \$700/m<sup>2</sup> of factory-built collector installed on new residential buildings). However, their conclusions on collector orientation and storage capacity have been confirmed by others. The availability of durable selective surfaces has led to wider applicability of one-cover collectors than they predicted.

The solar process economic considerations noted in Chapter 11 apply directly to solar heating. The costs of installed solar heating equipment (the first costs) include purchase and installation of all collectors, storage units, pumps, blowers, controls, duct work, piping, heat exchangers, and so on. Operating costs include costs of auxiliary energy, parasitic power, insurance, maintenance, taxes, and so on. In the following discussions, as in Chapter 11, first costs of solar heating systems are taken to be the incremental costs, that is, the difference in cost between the solar heating system and a conventional heating system.

The basic method used in calculating the economics of solar heating is the  $P_1$ ,  $P_2$  life-cycle savings method described in Section 11.9. In this analysis there is a large number of economic parameters that must be determined. This discussion shows how some of these parameters affect the economic viability of active solar heating and is introduced by a brief review of their nature and significance.

A primary economic consideration is the first cost of the solar heating system. The installed costs of many systems are in the range of \$250/m<sup>2</sup> to \$700/m<sup>2</sup> of collector, with fixed costs of the order of \$1000 to \$3000. (An important component in these costs which must be borne by the purchaser is that of marketing, which can vary widely with the size

of the system and the level of sales effort that is involved in getting it to the purchaser.) Retrofit systems tend to be more expensive, particularly on large flat-roof buildings where new structures must be provided for collector support. Some residential-scale systems cost less if integrated into a building or constructed by the owner. If a system is well built, it can have significant salvage or resale value, and if the major components are as durable as the basic building, its value may appreciate.


Tax laws can have important impact on the first cost of solar heating (and other solar processes). In the United States, tax incentives were enacted by Congress and by the legislatures of several states; these subsidies had the effect of reducing the first cost of systems. By 1990 most of these incentives expired. Since 2000 some states in the United States and some countries are again providing incentives for the installation of solar equipment.

The costs of energy delivered from fuel at the time of installation  $C_{F1}$  are a second important economic consideration. They are widely variable with time, location, type of fuel, and efficiency of the fuel-burning system. In 1978 in the United States, some regulated natural gas prices were at the low end of the scale with costs of delivered energy from \$2/GJ to \$3/GJ. Typical costs of energy delivered from oil were \$5/GJ to \$8/GJ. The LPG energy costs were higher than oil. In the years since then, prices have risen and then fallen and risen again, driven primarily by the cost of imported crude oil. Some of the most expensive energy is electricity, which when used in resistance heating in some metropolitan areas costs more than \$20/GJ. Energy costs to consumers at a particular time from different sources have varied over an order of magnitude.

In the decade 1970 to 1980, most energy costs inflated at higher rates than the general inflation rate, but from 1980 through 2000 energy costs followed general inflation. From 2000 through 2005 energy costs have risen faster than general inflation. Future fuel energy costs will be dependent on gas and oil discoveries and on technological developments related to fuel conversion and use. They will also be dependent on international political developments, as many of the world's industrialized nations are energy importers. Life-cycle cost calculations require that projections be made of future energy costs. These projections are uncertain and interject corresponding uncertainties into the life-cycle cost analysis.

A third category of economic factors relates to costs of operation of systems. Insurance, maintenance, and property taxes will probably increase with the general inflation rate. Parasitic power in a well-designed system should be small in relation to other costs. (A good system will have a coefficient of performance, the ratio of solar energy delivered to parasitic energy used to drive pumps, controls, and so on, of 15 to 30.)

A fourth category of economic considerations relates to the costs of money and time periods over which analyses are made. Interest rates and terms of initial mortgages or building improvement loans both affect the life-cycle costs of the capital-intensive solar energy systems. Time periods for economic analysis are sometimes selected as the period of time over which it is expected the building will be occupied or owned, over the expected lifetime of the equipment, or over the term of the loan used to purchase the equipment. In general, longer periods of analysis will tend to improve life-cycle solar savings, although costs or savings far in the future have relatively small impact on life-cycle costs when discounted to present value. Life-cycle costs are sensitive to discount rates, with lower discount rates generally improving life-cycle savings for solar or other energy-conserving



**Figure 13.11.1** Life-cycle solar savings for the Madison example with  $C_A = \$300/\text{m}^2$  and  $C_E = \$1000$  for present fuel costs of \$4, \$8, and \$12/GJ, inflating at 0.10 (solid lines) and 0.15 (dashed lines) per year.

and capital-intensive measures. Market discount rates are often taken as approximately 2% more than the general inflation rate for individuals, approximately 4% more for established businesses, and may be as high as 20% higher than general inflation rates for fast-growing industries. Most industries have developed their own discount rates.

Examples of the solar savings to a homeowner are shown in Figure 13.11.1. The configuration is the air system described in Section 13.5 on a well-insulated building in Madison. The economic parameters assumed are term of analysis 20 years; term of mortgage 20 years; mortgage interest rate 9.5% per year; down payment 20%; market discount rate 9% per year; general inflation rate 7% per year; real estate taxes in first year 2% per year of system first cost; insurance, maintenance, and parasitic power in first year 2% per year of system first cost; and income tax bracket through the period of analysis 45%. The system is assumed to be durable and well built, having a resale value of 100% of its first cost (i.e., it does not decline in value or appreciate as the building is expected to appreciate).

First-year fuel costs are taken as \$4/GJ, \$8/GJ, and \$12/GJ, and these are assumed to inflate at rates of 10 and 15% per year. This covers a range of present costs and possible inflation rates. Figure 13.11.1 is based on  $C_A = \$300/\text{m}^2$  and  $C_E = \$1000$ .

Several trends are clear from this figure. Higher present fuel costs and higher fuel cost inflation rates lead to more favorable savings. As fuel costs or inflation rates rise, the optimum collector area increases. The approximate locus of the maxima is shown. As the optimum collector area increases, the range of areas over which positive savings can be expected will also increase. In all cases the optima are broad and the selection of area is

not critical. For example, from Figure 13.11.1 at  $C_{F1} = \$12/\text{GJ}$  and  $i_F = 10\%$  per year, the optimum area is about  $15 \text{ m}^2$ , any area between 10 and  $25 \text{ m}^2$  results in essentially the same savings, and any area between 2 and  $35 \text{ m}^2$  results in positive savings. A reduction in first cost increases life-cycle savings (not shown on this figure).

Given a full set of economic parameters (other than fuel costs) and the thermal performance of a system, it is possible to determine combinations of present fuel costs and fuel cost inflation rate that will make solar heating just competitive with the alternative, that is, when savings is \$0. At a fuel cost inflation rate of 0.10 per year, a  $C_{F1}$  of about \$6/GJ is a “breakeven” fuel cost. If fuel cost is above this level, solar savings are positive.

The results shown in the figure are for a specific system, location, and (most importantly) a set of economic assumptions. Many economic parameters have not been varied in the estimates that are shown in this figure. As was noted in Chapter 11, the explicit effect of any one variable on the life-cycle savings is influenced by the values of many other variables. Thus “rule-of-thumb” sensitivity trends are not easily recognized, and quantitative sensitivity analyses such as that outlined in Section 11.38 are required. The numbers used in this illustration are subject to argument and are not intended to show the economic feasibility (or lack thereof) of solar heating. However, the trends are shown, and the methods described in Chapter 11 should be applied to individual cases to determine the economics of a particular application.

## 13.12 ARCHITECTURAL CONSIDERATIONS

Active solar heating poses challenges to architectural design of buildings. Many approaches to these challenges have been devised; Shurcliff (1978), Szokolay (1980), and Weiss (2003) have compiled information on a variety of solar-heated buildings. In this section we outline in general terms some of the major architectural considerations to be taken into account in solar building design. While not addressed specifically here, it is implicit throughout this discussion that any building design should be energy conserving, as solar energy and the fuels with which it competes will be expensive.

Economic studies of active solar heating indicated that the optimum fractions of total annual loads range from zero to over three-fourths. For some locations the architect must design into the building collector areas in the range up to approximately one-half of the floor area of the house (depending on the collector, the climate, and the degree of insulation in the building). A basic problem faced by architects and engineers is to integrate the collectors into the building design in such a way that thermal performance is satisfactory and the structure is aesthetically satisfying.

Collectors should be oriented with the slope and azimuth angle within or close to the ranges noted in Tables 13.2.1 and 13.2.2. Vertical collectors may be useful at high latitudes to answer problems of integration of collectors into the building and avoiding snow accumulation. Transpired collectors as discussed in Chapter 6 are almost always installed on a vertical facade. Space must be provided in the structure for energy storage units, piping and ducts, controls, auxiliaries, and all associated equipment. Anderson et al. (1955) have addressed these and related questions on solar house architecture. Similar considerations will apply to institutional buildings.

The collector may be a part of the envelope of the building (as in MIT House IV) or separate (as in the Denver Solar House). The orientation of the collector is substantially

fixed, and if it is part of the envelope of the house, the collector will probably become an important or dominant architectural feature of the structure. The collector may serve as part of the weatherproof enclosure and thus allow a reduction in cost of roofing or siding; such a reduction is a credit which reduces the cost of the collector. Separate collectors, on the other hand, can permit greater flexibility in house design and allow buildings that are more conventional (contemporary or traditional) in appearance.

Figure 13.2.5 shows three solar-heated residential buildings, including MIT House IV, the Denver House, and the House II Laboratory building at Colorado State University. Figure 13.12.1 shows three additional solar-heated buildings, illustrating additional architectural approaches.



**Figure 13.12.1** Three examples of solar heated buildings: (a, b) residences Madison, WI; (c) Wayside, Portage, WI.

Storage is usually not a major architectural problem, other than recognizing the need for appropriate space and access to it within the structure. The volume of storage per unit area of collector depends on the system used. Pebble bed storage units will usually occupy a volume of roughly  $0.15$  to  $0.35 \text{ m}^3/\text{m}^2$  of collector and water tanks about  $0.050$  to  $0.10 \text{ m}^3/\text{m}^2$ . The volume of phase change storage systems would be less than that of water systems. The most common location for storage in buildings is in basements.

Providing solar heat to larger buildings, such as apartment buildings, presents a special set of problems. It may be necessary to consider vertical mounting for collectors, which may cause a significant reduction in their performance. This possibility has been studied by Lorsch and Niyogi (1971). Otherwise, collectors may be mounted like awnings, with improvements in performance but with increased cost of installation. If the building geometry is such that the roof area is adequate, banks of collectors can be mounted on the roof with appropriate piping or ducts leading to the space to be heated.

Most solar heating studies to date have been concerned primarily with new buildings designed to include solar heating systems. Adding solar heating systems to existing buildings presents more formidable tasks. Consideration should be given to the problems of designing buildings that can accommodate the addition of solar heating after construction.

## REFERENCES

- AEIC-EEI Heat Pump Committee, *Edison Electric Inst. Bull.*, **24**, 77 (1956). "Possibilities of a Combination Solar-Heat Pump Unit." (Based on a report by G. O. G. Löf.)
- Anderson, L. B., H. C. Hottel, and A. Whillier, *Solar Energy Research*, University of Wisconsin Press, Madison, p. 47 (1955). "Solar Heating Design Problems."
- ASHRAE *Systems Handbook*, American Society of Heating, Refrigeration, and Air Conditioning Engineers, New York (1976).
- Bankston, C., in *Advances in Solar Energy*, Vol. **4** (K. Boer, ed.), American Solar Energy Society and Plenum Press, New York, p. 352 (1988). "The Status and Potential of Central Solar Heating Plants with Seasonal Storage: An International Report."
- Bliss, R. W., *Air Conditioning, Heating and Ventilating*, **52** (10), 92 (Oct. 1955). "Design and Performance of the Nation's Only Fully Solar-Heated House." See also *Proceedings of the World Symposium on Applied Solar Energy*, SRL, Menlo Park, CA, p. 151 (1956).
- Bliss, R. W., *Proc. UN Conf. New Sources of Energy*, **5**, 148 (1964). "The Performance of an Experimental System Using Solar Energy for Heating, and Night Radiation for Cooling a Building."
- Boer, K., paper presented at the ISES Congress, Paris (1973). "A Combined Solar Thermal Electrical House System."
- Boer, S., in *Proceedings of Solar Heating and Cooling for Buildings Workshop* (R. Allen, ed.), University of Maryland, College Park, Maryland, p. 186 (Mar. 1973). "The Drum Wall."
- Braun, J., M.S. Thesis, University of Wisconsin-Madison (1980). "Seasonal Storage of Energy in Solar Heating."
- Bridgers, F. H., D. D. Paxton, and R. W. Haines, paper 57-SA-26 presented at ASME Meeting (June 1957a). "Solar Heat for a Building."
- Bridgers, F. H., D. D. Paxton, and R. W. Haines, *Heating, Piping, and Air Conditioning*, **29**, 165 (1957b). "Performance of a Solar Heated Office Building."
- Close, D. J., R. V. Dunkle, and K. A. Robeson, *Mechan. Chem. Eng. Trans. Inst. Eng. Australia*, **MC4**, 45 (1968). "Design and Performance of Thermal Storage Air Conditioner System."
- Converse, A. O., *Proc. Joint Conf. Am. Sect. ISES and SES of Canada*, Winnipeg, **3**, 277 (1976). "Solar Heating in Northern New England."



- Dalenbäck, J.-O., *The Status of CSHPPS*, a report of International Energy Agency Solar Heating and Cooling Task VII (1989).
- Dalenbäck, J.-O., and T. Jilar, personal communication (1987)
- Engelbreton, C. D., *Proc. UN Conf. New Sources of Energy*, **5**, 159 (1964). "The Use of Solar Energy for Space Heating-M.I.T.: Solar House IV."
- Freeman, T. L., J. W. Mitchell, and T. E. Audit, *Solar Energy*, **22**, 125 (1979). "Performance of Combined Solar-Heat Pump Systems."
- Hatheway, F. M. and A. O. Converse, *Solar Energy*, **27**, 561 (1981). "Economic Comparison of Solar Assisted Heat Pumps."
- Hooper, F. C. and C. R. Attwater, in *Heat Transfer in Solar Energy Systems*, American Society of Mechanical Engineers, New York (1977). "Design Method for Heat Loss Calculation for In-Ground Heat Storage Tanks."
- Hughes, P. J., W. A. Beckman, and J. A. Duffie, *Solar Energy*, **19**, 317 (1977). "Simulation Study of Several Solar Heating Systems with Off-Peak Auxiliary."
- Johnson, T. E., *Solar Energy*, **18**, 669 (1977). "Lightweight Thermal Storage for Solar Heated Buildings."
- Jordan, R. C. and J. L. Threlkeld, *Heating, Piping and Air Conditioning*, **28**, 122 (1954). "Design and Economics of Solar Energy Heat Pump Systems."
- Jurinak, J. J. and S. I. Abdel-Khalik, *Solar Energy*, **21**, 377 (1978). "Properties Optimization for Phase-Change Energy Storage in Air-Based Solar Heating Systems."
- Jurinak, J. J. and S. I. Abdel-Khalik, *Solar Energy*, **22**, 355 (1979). "Sizing Phase-Change Energy Storage Units for Air-Based Solar Heating Systems."
- Karaki, S., P. R. Armstrong, and T. N. Bechtel, Colorado State University report COO-2868-3 to U.S. Department of Energy (1977). "Evaluation of a Residential Solar Air Heating and Nocturnal Cooling System."
- Karaki, S., T. E. Brisbane, and G. O. G. Löf, Colorado State University Report SAN 11927-15 to U.S. Department of Energy (1984). "Performance of the Solar Heating and Cooling System for CSU House III—Summer Season 1983 and Winter Season 1983–84."
- Karaki, S., W. S. Duff, and G. O. G. Löf, Colorado State University report COO-2868-4 to U.S. Department of Energy (1978). "A Performance Comparison between Air and Liquid Residential Solar Heating Systems."
- Karman, V. D., T. L. Freeman, and J. W. Mitchell, *Proc. Joint Conf. Am. Sect. ISES and SES of Canada*, Winnipeg, **3**, 325 (1976). "Simulation Study of Solar Heat Pump Systems."
- Klein, S. A., W. A. Beckman, and J. A. Duffie, *Solar Energy*, **18**, 113 (1976). "A Design Procedure for Solar Heating Systems."
- Kuharich, R. R., *Proc. Joint Conf. Am. Sect. ISES and SES of Canada*, Winnipeg, **3**, 378 (1976). "Operational Analysis of a Solar Optimized Heat Pump."
- Löf, G. O. G., M. M. El-Wakil, and J. P. Chiou, *Trans. ASHRAE*, **77** (Oct. 1963). "Residential Heating with Solar Heated Air—the Colorado Solar House."
- Löf, G. O. G., M. M. El-Wakil, and J. P. Chiou, *Proc. UN Conf. New Sources of Energy*, **5**, 185 (1964). "Design and Performance of Domestic Heating System Employing Solar Heated Air—The Colorado House."
- Löf, G. O. G. and R. A. Tybout, *Solar Energy*, **14**, 253 (1973). "Cost of House Heating with Solar Energy."
- Lorsch, J. G. and B. Niyogi, Report NSF/RANN/SE/GI 27976/TR72/18 to the National Science Foundation from University of Pennsylvania (Aug. 1971). "Influence of Azimuthal Orientation on Collectible Energy in Vertical Solar Collector Building Walls."
- Marvin, W. C. and S. A. Mumma, *Proc. Joint Conf. Am. Sect. ISES and SES of Canada*, Winnipeg, **3**, 321 (1976). "Optimum Combination of Solar Energy and the Heat Pump for Residential Heating."

- Mitchell, J. W., T. L. Freeman, and W. A. Beckman, *Solar Age*, **3** (7), 20 (1978). "Heat Pumps."
- Morrison, D. J. and S. I. Abdel-Khalik, *Solar Energy*, **20**, 57 (1978). "Effects of Phase Change Energy Storage on the Performance of Air-Based and Liquid-Based Solar Heating Systems."
- Shurcliff, W. A., *Solar Heated Buildings of North America*, Brick House Publishing Co., Harrisville, NH (1978).
- Speyer, E., *Solar Energy*, **3** (4), 24 (1959). "Optimum Storage of Heat with a Solar House."
- Szokolay, S. V., *World Solar Architecture*, Architectural Press, London (1980).
- Telkes, M., in *Proceedings of the Workshop on Solar Energy Storage Subsystems for the Heating and Cooling of Buildings* (L. U. Lilleleht, ed.), Charlottesville, VA, p. 17 (1975). "Thermal Storage for Solar Heating and Cooling"
- Telkes, M. and E. Raymond, *Heating and Ventilating*, 80 (1949). "Storing Solar Heat in Chemicals—A Report on the Dover House."
- Terrell, R. E., *Solar Energy*, **23**, 451 (1979). "Performance of a Heat Pump Assisted Solar Heated Residence in Madison, Wisconsin."
- Tybout, R. A. and G. O. G. Löf, *Natural Resources J.*, **10**, 268 (1970). "Solar Energy Heating."
- Ward, D. S., G. O. G. Löf, C. C. Smith, and L. L. Shaw, *Solar Energy*, **19**, 79 (1977). "Design of a Solar Heating and Cooling System for CSU House II."
- Weiss, W. (ed.), *Solar Heating Systems for Houses—A Design Handbook for Solar Combisystems*, James & James, London (2003).
- Yanagimachi, M., in *Transactions of the Conference on Use of Solar Energy* (E. F. Carpenter, ed.), Vol. **3**, University of Arizona Press, p. 32 (1958). "How to Combine: Solar Energy, Nocturnal Radiational Cooling, Radiant Panel System of Heating and Cooling, and Heat Pump to Make a Complete Year-Round Air Conditioning System."
- Yanagimachi, M., *Proc. UN Conf. New Sources of Energy* **5**, 233 (1964). "Report on Two and a Half Years' Experimental Living in Yanagimachi Solar House II."



## Building Heating: Passive and Hybrid Methods

The active systems described in the previous chapter are based on collectors and storage systems that are not necessarily integrated into a building structure. Passive systems can be distinguished from active systems on either of two bases. The first distinction lies in the degree to which the functions of collection and storage are integrated into the structure of the building; windows and the rooms behind them can serve as collectors, with storage provided as sensible heat of the building structure and contents as they change temperature. Second, many passive systems require no mechanical energy for moving fluids for their operation; fluids and energy move by virtue of the temperature gradients established by adsorption of radiation (and hence the term *passive*). (Mechanical energy may be used to move insulation for loss control or to move fluids to distribute absorbed energy from one part of a building to another.)

By nature, passive heating is intimately concerned with architecture, as the building itself functions as collector and storage unit and as the enclosure in which people live, work, and are protected from an often-harsh exterior environment. In this chapter we discuss in a largely qualitative way the factors that affect the thermal performance of a passive building (i.e., its ability to provide an acceptable level of human comfort). The engineering basis for thermal performance calculations is (as for active systems) the subject of Chapters 1 to 11. This chapter serves as an introduction to Chapter 22 on estimation of annual thermal performance of passive and hybrid systems.

The thrust of this book is the estimation of the long-term thermal performance of solar energy systems to predict how much fuel will be needed to keep a building within a reasonably fixed span of interior temperatures. The esthetic features of a building that make it a pleasant place to live and work can be very much enhanced (or in some cases degraded) by admission of solar energy into the building spaces. Daylighting, the use of the visible part of the solar spectrum rather than artificial lighting, is closely coupled with passive heating. These matters are also of importance and relate to aspects of the overall process of building design that are treated in other books.

Some solar heating systems are combinations of active and passive systems. In this chapter and in Chapter 22 we discuss examples of hybrid systems, including systems with active collectors and passive storage, and combination of direct-gain passive and active systems. Other combinations are possible.

In recent years, there has developed a very substantial body of literature on passive solar processes. The *Passive Solar Journal* was published by the American Solar Energy

Society. Since 1976 the society has run National Passive Solar Conferences which have resulted in conference proceedings. Numerous books on the subject have appeared, as have papers in other journals such as *Solar Energy* and architectural publications. Included in these publications have been works on quantitative aspects of passive heating processes, architecture, building (system) performance, daylighting, shading, heat transfer within buildings by natural and forced convection, cooling, energy storage, commercial aspects, and others.

## 14.1 CONCEPTS OF PASSIVE HEATING

Several concepts for passive and hybrid solar heating have developed that are sufficiently distinct as to provide a useful basis of discussion of the principles and functions of passive systems. These are direct gain, collector-storage wall, and sunspace. (Many other types and combinations of types have been noted, including convective loop, solar chimney, etc.) The common features are means of absorbing solar energy in the building, storing it in parts of the structure, and transferring it to the spaces to be heated.

**Direct gain** of energy through windows can meet part of building heat loads. The window acts as a collector and the building itself provides some storage. Overhangs, wingwalls, or other architectural devices are used to shade the windows during times when heating is not wanted. It is also necessary, in cold climates, to insulate the windows during periods of low solar radiation to prevent excessive losses. Direct gain can provide energy to the south side of a building; means may have to be provided to distribute energy to rooms not having south windows.

The **collector-storage wall**<sup>1</sup> combines the functions of collection and storage into a single unit that is part of a building structure. Part of a south wall may be single or double glazed; inside the glazing is a massive wall of masonry material or water tanks, finished black to absorb solar radiation. Heat is transferred from the storage wall to the room by radiation and convection from the room side of the wall and by forced or natural convection of room air through the space between glazing and wall. Room air may enter this space through openings (vents) in the bottom of the wall and return to the room through openings in the top. The storage unit could also be part of the roof and ceiling. Movable insulation may have to be provided in other than mild climates to control losses at times of low solar radiation.

**Sunspace** attachments to buildings have been used as solar collectors, with storage in walls, floors, or pebble beds. Forced air circulation to the rooms is an option to improve storage and utilization of absorbed energy. In cold climates, energy losses from sunspaces, which are greenhouse-like structures, can exceed the absorbed energy, and care must be used to assure that net gains accrue from such a system. The uses to which a sunspace is put, for human occupancy or for plants, will impose limits on the allowable temperature swings in the sunspace and affect the energy balances on it.

A survey of passive solar buildings has been prepared by the AIA Research Corporation (1978). Many passive buildings are included in broader surveys of solar-heated buildings

---

<sup>1</sup> Also referred to as a Trombe wall or Trombe-Michel wall.

by Szokolay (1975) and by Shurecliff (1978). Many of the concepts now being studied and developed were set forth by Olgyay (1963). Anderson (1977) reviews passive heating concepts. Books on passive heating include those of Mazria (1979), Lebens (1980), and many others.

## 14.2 COMFORT CRITERIA AND HEATING LOADS

Active solar heating systems can be designed to provide the same levels of control of conditions in the heated (or cooled) spaces as conventional systems. With indoor temperatures essentially fixed at or a little above a minimum, load estimations can be done by conventional methods such as those outlined in Chapter 9. Passively heated buildings in many cases are not controlled within the same narrow temperature ranges; the thermal storage capacity of the building structure or contents is usually significant, and it may be necessary to use load calculation methods that take into account variable internal temperatures and capacitance of building components.

For residential buildings, there are limits in the variation of indoor conditions (temperature and humidity) considered comfortable by occupants. The limits are not well defined and are to a degree subjective. They depend on the activities of the individuals in the buildings and on their clothing. Air movement is also important, as are the temperatures of the interior surfaces with which an occupant exchanges radiation. Extensive discussions of comfort under various conditions of temperature, humidity, air movement, radiant exchange, activity levels, and clothing are provided in the ASHRAE *Fundamentals Handbook* (2005) and by Fanger (1972).

The concept of solar fraction, which is useful for systems having loads substantially independent of the size of the solar energy system, is not useful in passive heating. For systems in which energy is absorbed in part of the structure (i.e., in direct gain, collector-storage walls, and sunspace systems) and where the loss coefficient of the solar aperture is different than that of the insulated wall it replaces, the total loads (that are to be met by solar plus auxiliary) will be a function of the design of the solar energy system. The significant number resulting from performance calculations for these systems is the annual amount of auxiliary energy required.

## 14.3 MOVABLE INSULATION AND CONTROLS

Passive elements such as direct-gain and storage wall elements can lose energy at excessive rates if measures are not taken to control the losses. An example of this situation, a water heater equivalent of a storage wall using water tanks, was shown in Example 12.7.1 to have significant night losses. Hollingsworth (1947) and Dietz and Czapek (1950) noted the same problems based on measurements on an early MIT solar house. In passive heating, storage elements are also energy-absorbing elements and thus have large, relatively uninsulated areas, and steps must be taken to control losses in any but mild climates.

Movable insulation is the evident possibility. Movable insulation can take several forms. Drapes, shades, screens, and shutters provide nominal levels of insulation. More extensive insulation can be provided by movable foam plastic or glass wool panels or by such devices as “beadwall” panels described by Harrison (1975), in which lightweight


plastic beads are pneumatically moved into or out of space between glazings. Many movable insulation systems useful in passive heating are now on the market.<sup>2</sup>

Insulation may be moved manually or automatically. If automatic, controls are needed to move it into or out of place, and detectors and control strategies must be arranged to maximize the net gains from the system while keeping indoor conditions within acceptable (and pleasant) limits. Controls must also be provided for mechanical devices that may be used for transferring heat from storage to rooms, such as fans used to circulate air around storage walls. Sebald et al. (1979), for example, have used simulation methods to assess the effects of air circulation control in collector-storage walls.

## 14.4 SHADING: OVERHANGS AND WINGWALLS

Overhangs and wingwalls are used with passive heating to reduce gains during times when heat is not wanted in the building. As these shading devices may partially shade absorbing surfaces during periods when collection is desired, it is necessary to estimate their effect on the absorbed radiation. In this section we show how this can be formulated for any point in time and also how monthly average effects of overhangs can be estimated. This discussion treats overhangs of finite length and is a summary of a detailed treatment by Utzinger (1979) and Utzinger and Klein (1979). For overhangs of infinite length (very long compared to the width of the receiver), the method of Jones (1980), discussed in Section 1.9, can be used.

A horizontal overhang-shading device with its outer extremity parallel to the wall can be represented by one perpendicular to the wall, as shown schematically in Figure 14.4.1. Its geometry is described by a set of dimensions: the projection  $P$ , the gap between the top of the receiver and the overhang  $G$ , and the left and right extensions  $E_L$  and  $E_R$ . The receiver (the window) height is  $H$  and width is  $W$ . Using the receiver height  $H$  as a characteristic dimension, the other dimensions can be expressed in dimensionless form as



**Figure 14.4.1** Diagrams of the shading of a vertical receiver by a horizontal overhang. From Utzinger (1979).

<sup>2</sup>Loss coefficients for windows with and without insulation are shown in Section 9.2.

ratios to the height. Thus the relative width is  $w$ , the relative projection is  $p$ , the relative gap is  $g$ , and the relative extension (with the left and right values the same) is  $e$ .

The ratio  $f_i$  of beam radiation received by the shaded receiver to that received by the unshaded receiver is the same as the fraction of the receiver area  $A_r$  which is exposed to direct beam radiation:

$$f_i = \frac{A_i}{A_r} \quad (14.4.1)$$

The value of  $f_i$  at any time depends on the dimensions of the overhang and receiver and on the angle of incidence of the beam radiation on the wall. An algorithm for computing this fraction has been developed by Sun (1975).

The area average radiation on the partially shaded receiver at any time is the sum of beam, diffuse, and ground-reflected radiation. Assuming that diffuse and ground-reflected radiation are isotropic,<sup>3</sup>

$$I_r = I_b R_b f_i + I_d F_{r-s} + I \rho_g F_{r-g} \quad (14.4.2)$$

The three terms have the same general significance as those in Equation 2.15.1. The first term includes  $f_i$  to account for shading from beam radiation. The view factor of the receiver for radiation from the sky  $F_{r-s}$  is reduced by the overhang from its value without an overhang,  $(1 + \cos 90)/2$ . Values of  $F_{r-s}$  are shown in Table 14.4.1. The third term is the ground-reflected radiation. For vertical receivers, neglecting secondary reflections from the underside of the overhang,  $F_{r-s} = (1 - \cos 90)/2$ , or 0.5.

Although in principle it is possible to calculate  $I_r$  at any time from Equation 14.4.2, the determination of  $f_i$  is tedious. For design purposes, we are normally concerned not with what happens at any particular time but rather with monthly means. A monthly mean fraction of the beam radiation received by the shaded receiver relative to that on the receiver if there were no overhang,  $\bar{f}_i$ , can be calculated by integrating (or summing) beam radiation with and without shading over a month:

$$\bar{f}_i = \frac{\int G_b R_b f_i \, dt}{\int G_b R_b \, dt} \quad (14.4.3)$$

Then with  $\bar{f}_i$ , an equation analogous to Equation 14.4.2 can be written for the time and area average daily radiation on the shaded vertical receiving surface:

$$\bar{H}_r = \bar{H} \left[ \left( 1 - \frac{\bar{H}_d}{\bar{H}} \right) \bar{R}_b \bar{f}_i + \frac{\bar{H}_d}{\bar{H}} F_{r-s} + \frac{\rho_g}{2} \right] \quad (14.4.4)$$

This is analogous to Equation 2.19.1 for monthly average radiation on a tilted, unshaded surface. The  $\bar{H}_d/\bar{H}$  and  $\bar{R}_b$  terms are found by the methods described in Chapter 2 for an isotropic sky. The Klein and Theilacker method can also be applied to this situation by

---

<sup>3</sup>Anisotropic models can also be used with little modification in the analysis.

**Table 14.4.1** Receiver Radiation View Factor of the Sky,  $F_{r-s}$ <sup>a</sup>

$e$	$g$	$w$	$F_{r-s}$								
			$p = 0.10$	$p = 0.20$	$p = 0.30$	$p = 0.40$	$p = 0.50$	$p = 0.75$	$p = 1.00$	$p = 1.50$	$p = 2.00$
0.00	0.00	1.0	0.46	0.42	0.40	0.37	0.35	0.32	0.30	0.28	0.27
		4.0	0.46	0.41	0.38	0.35	0.32	0.27	0.23	0.19	0.16
		25.0	0.45	0.41	0.37	0.34	0.31	0.25	0.21	0.15	0.12
	0.25	1.0	0.49	0.48	0.46	0.45	0.43	0.40	0.38	0.35	0.34
		4.0	0.49	0.48	0.45	0.43	0.40	0.35	0.31	0.26	0.23
		25.0	0.49	0.47	0.45	0.42	0.39	0.34	0.29	0.22	0.18
	0.50	1.0	0.50	0.49	0.49	0.48	0.47	0.44	0.42	0.40	0.38
		4.0	0.50	0.49	0.48	0.46	0.45	0.41	0.37	0.31	0.28
		25.0	0.50	0.49	0.47	0.46	0.44	0.39	0.35	0.27	0.23
	1.00	1.0	0.50	0.50	0.50	0.49	0.49	0.48	0.47	0.45	0.43
		4.0	0.50	0.50	0.49	0.49	0.48	0.46	0.43	0.39	0.35
		25.0	0.50	0.50	0.49	0.48	0.47	0.44	0.41	0.35	0.30
0.30	0.00	1.0	0.46	0.41	0.38	0.35	0.33	0.28	0.25	0.22	0.20
		4.0	0.46	0.41	0.37	0.34	0.31	0.26	0.22	0.17	0.15
		25.0	0.45	0.41	0.37	0.34	0.31	0.25	0.21	0.15	0.12
	0.25	1.0	0.49	0.48	0.46	0.43	0.41	0.37	0.34	0.30	0.28
		4.0	0.49	0.47	0.45	0.42	0.40	0.34	0.30	0.24	0.21
		25.0	0.49	0.47	0.45	0.42	0.39	0.33	0.29	0.22	0.18
	0.50	1.0	0.50	0.49	0.48	0.47	0.45	0.42	0.39	0.35	0.33
		4.0	0.50	0.49	0.47	0.46	0.44	0.39	0.34	0.27	0.26
		25.0	0.50	0.49	0.47	0.46	0.44	0.39	0.34	0.27	0.22
	1.00	1.0	0.50	0.50	0.49	0.49	0.48	0.47	0.45	0.42	0.40
		4.0	0.50	0.50	0.49	0.48	0.48	0.45	0.43	0.38	0.34
		25.0	0.50	0.50	0.49	0.48	0.47	0.44	0.41	0.35	0.30


<sup>a</sup>From Utzinger and Klein (1979).

multiplying the first term in Equation 2.20.5a (or the first two terms in Equation 2.20.4a) by  $\bar{f}_i$ , which results in

$$\bar{H}_r = \bar{H} \left( D\bar{f}_i + \frac{\bar{H}_d}{\bar{H}} F_{r-s} + \frac{\rho_g}{2} \right) \quad (14.4.5)$$

Utzinger and Klein present plots of  $\bar{f}_i$  as a function of  $e$ ,  $g$ ,  $w$ , and  $p$  for various latitudes. One of these plots, for a latitude of  $35^\circ$ ,  $w = 4$ , zero extension  $e$  and four values of the gap  $g$ , is shown in Figure 14.4.2. A set of the plots for latitudes of  $35^\circ$ ,  $45^\circ$ , and  $55^\circ$  (Utzinger, 1979) is in Appendix E. At a latitude of  $35^\circ$ , a projection of 0.3, a gap of 0.2, and no extensions, from Figure 14.4.2,  $\bar{f}_i$  is 0.40 in August and 0.94 in October.

The nature of these curves dictates that a particular interpolation method be used. The general procedure to obtain  $\bar{f}_i$  consists of a set of steps to account for gap, width, and latitude; this procedure is modified in some cases to account for discontinuities in the relationships. The curves are shown as plots of  $\bar{f}_i$  versus  $p$  for months.



**Figure 14.4.2** Monthly mean fraction of a vertical, south-facing receiver area receiving beam radiation as a function of relative overhang dimensions for latitude  $35^\circ$  and  $w = 4$ . For north-facing receivers in the southern hemisphere, interchange months as shown in Figure 1.8.2. From Utzinger (1979).

The first interpolation is a linear interpolation for gap  $g$ . The second step is another linear interpolation for extension  $e$ . Next, interpolation for relative width  $w$  is done by

$$\bar{f}_i = \bar{f}_{i2} + (\bar{f}_{i1} - \bar{f}_{i2}) \left( \frac{\frac{1}{w} - \frac{1}{w_2}}{\frac{1}{w_1} - \frac{1}{w_2}} \right) \quad (14.4.6)$$

Then, linear interpolation is used to account for intermediate values of latitude.

This procedure is modified by two circumstances that are clear on examination of the plots. First, if the projection is large enough,  $\bar{f}_i$  is independent of  $p$  for some months. The value of  $p$  at which  $\bar{f}_i$  becomes independent of  $p$  is a linear function of the relative gap. Care must be used in interpolating for gap when on or near the horizontal portion of the curves. Second, during winter months when the receiver area is not shaded at all,  $\bar{f}_i$  has a limiting value of 1. The intersection of  $\bar{f}_i$  curves for a given month with the  $\bar{f}_i = 1$  axis is also a linear function of the relative gap. Care must be used in interpolating for gap when near these intersections.

All of the computations of  $\bar{f}_i$  described above are for surface azimuth angles of zero. Utzinger and Klein (1979) have shown that for surface azimuth angles within  $\pm 15^\circ$  there is a negligible difference in the estimated radiation on shaded receivers from that on a south-facing surface. When the surface azimuth angles exceed  $\pm 30^\circ$ , the calculation for south-facing surfaces underpredicts summer radiation and overpredicts the winter radiation on the receiver by substantial amounts, and a more detailed computation is needed. If the surface azimuth angles exceed  $\pm 15^\circ$ , wingwalls may be more important in shading than overhangs.

#### Example 14.4.1

Determine  $\bar{f}_i$  for a window receiver with overhang with relative dimensions  $w = 12$ ,  $g = 0.4$ ,  $p = 0.5$ , and  $e = 0$ . The latitude is  $40^\circ$  and the month is March.

#### Solution

Interpolate  $w$  and  $\phi$  in that order. The values of  $\bar{f}_i$  from which the interpolations are done, using the appropriate plots in Appendix E, are as follows:

At  $\phi = 35^\circ$ ,  $e = 0$  and  $g = 0.4$ : If  $w = 4$ ,  $\bar{f}_i = 0.80$ , and if  $w = 25$ ,  $\bar{f}_i = 0.78$ .

At  $\phi = 45^\circ$ ,  $e = 0$  and  $g = 0.4$ : If  $w = 4$ ,  $\bar{f}_i = 0.96$ , and if  $w = 25$ ,  $\bar{f}_i = 0.96$ .

Equation 14.4.5 is used to interpolate for width. The inverse widths are  $1/w = 0.0833$ ,  $1/w_1 = 0.25$ , and  $1/w_2 = 0.04$ . At a latitude of  $35^\circ$

$$\bar{f}_{i,35} = 0.80 + (0.78 - 0.80) \left( \frac{0.0833 - 0.25}{0.04 - 0.25} \right) = 0.79$$

At a latitude of  $45^\circ$ , both  $\bar{f}_{i1}$  and  $\bar{f}_{i2}$  are 0.96, so  $\bar{f}_{i,45} = 0.96$ . We can now linearly interpolate between 0.79 and 0.96 for a latitude of  $40^\circ$ :

$$\bar{f}_i = 0.79 + 0.5(0.96 - 0.79) = 0.87$$




Note that if the gap ratio had been 0.3 (for which curves are not shown), the four initial values would each have been the result of linear interpolations between  $g = 0.2$  and  $g = 0.4$ . ■

Figure 14.4.3 shows the results of month-by-month calculation of radiation on shaded and unshaded south-facing receivers at Albuquerque, New Mexico ( $\phi = 35^\circ$ ), for a particular overhang geometry, calculated by Equation 14.4.5. The overhang is sufficiently large that beam radiation is essentially eliminated during the summer months, yet the total radiation on the shaded receiver in the summer is approximately two-thirds of that on the unshaded receiver. A similar computation for Minneapolis, Minnesota ( $\phi = 45^\circ$ ), shows summer month radiation on the shaded receiver is more than half of that on the unshaded receiver for this geometry.

## 14.5 DIRECT-GAIN SYSTEMS

A direct-gain passive system includes south-facing windows, very often with movable insulation and overhang shading to reduce incident summertime radiation, with the rooms behind the windows and their contents serving as cavity absorbers and having sufficient thermal capacitance to provide energy storage. The windows and room are, in effect, vertical, no-flow collectors with thermal capacitance. Loss coefficients are analogous to those of Chapter 6 but are generally based on room air temperature rather than on plate



**Figure 14.4.3** Monthly estimated radiation on vertical, south-facing receivers at Albuquerque, shaded and unshaded. From Utzinger and Klein (1979).

temperature.<sup>4</sup> Movable insulation which is in place for part of a day means that the loss coefficients will have different values at different times of day.

The net rate of energy transfer across a vertical window (receiver) of area  $A_r$  at any time can be written as

$$\dot{Q}_r = A_r[\alpha F_c(G_b R_b \tau_b f_i + G_d \tau_d F_{r-s} + \rho_s G \tau_g/2) - U_L F_l(T_r - T_a)] \quad (14.5.1)$$

The effective absorptance of the room,  $\alpha$ , can be calculated with Equation 5.11.1. If the (vertical) window is unshaded by overhangs or wingwalls,  $f_i = 1$  and  $F_{r-s} = 0.5$ . If there is shading by architectural features such as overhangs, the methods of Section 14.4 must be used to estimate  $f_i$  and  $F_{r-s}$ . The room temperature  $T_r$  will rise during periods when there is net gain through the windows and will be prevented from dropping below a set temperature by an auxiliary energy source.

The control function  $F_c$  is unity when there is no movable insulation covering the window and zero (or near zero) if movable insulation is in place. The three radiation terms in parentheses are the beam, diffuse, and ground-reflected radiation. The second term in the brackets represents the thermal losses. The loss coefficient  $U_L$  is for the uninsulated window, and  $T_r - T_a$  is the temperature difference between room and ambient. Another control function  $F_l$  is unity when  $F_c = 1$ , and when insulation is in place it is the ratio of  $U_L$  with insulation to  $U_L$  without insulation.

The monthly average net gains (or losses) from a direct-gain system can be estimated by considering the solar gain into the rooms independently of the thermal losses through the window. The calculation of both solar gain and thermal losses must account for movable insulation. Thus the gain and loss terms of Equation 14.5.1 can be written in terms of hourly irradiation ( $I$ ,  $I_b$ , and  $I_d$ ) and summed for the month:

$$\sum \dot{Q}_r = A_r \sum [\alpha F_c(f_i \tau_b I_b R_b + \tau_d J_d F_{r-s} + \rho_g \tau_g I/2) - U_L F_l(T_r - T_a)] \quad (14.5.2)$$

These calculations can be more conveniently done using monthly averages. The  $f_i$  for the individual hours can be replaced by a single value of  $\bar{f}_i$  obtained from Figure 14.4.2 or Appendix E. Each of the solar gain terms includes the transmittance corresponding to the monthly mean angle of incidence determined by methods of Chapter 5. If movable insulation is used,  $\bar{F}_c$  (a radiation-weighted value of the control function  $F_c$ ) must be used. If the insulation is used only when no significant radiation is incident on the receiver,  $\bar{F}_c$  will be unity. If this is not the case, information must be available on which to estimate  $\bar{F}_c$ . The average daily radiation absorbed in the room can then be written:

$$A_r \bar{S} = A_r \alpha \bar{F}_c(\bar{f}_i \bar{\tau}_b \bar{H}_b \bar{R}_b + \bar{\tau}_d \bar{H}_d F_{r-s} + \rho_g \bar{\tau}_g \bar{H}/2) \quad (14.5.3)$$

The average thermal losses for a day are

$$\bar{Q}_l = 24 \times 3600 A_r \bar{U}_L (\bar{T}_r - \bar{T}_a) \quad (14.5.4)$$

---

<sup>4</sup>See Section 22.3.

where  $\overline{U}_L$  is a monthly mean loss coefficient in watts per square meter per degrees Celsius. If night insulation with thermal resistance  $R_N$  is used for a fraction  $f_N$  of the time,

$$\overline{U}_L = (1 - f_N)U_L + f_N \left( \frac{U_L}{1 + R_N U_L} \right) \quad (14.5.5)$$

### Example 14.5.1

A direct-gain system is to be used at a latitude of  $40^\circ$ . The south-facing, double-glazed window, with glass of  $KL = 0.0370$  per sheet and without insulation, has an overall loss coefficient (inside air to outside air) of  $3.2 \text{ W/m}^2 \text{ }^\circ\text{C}$ .

The window is  $15.0 \text{ m}$  wide and  $1.25 \text{ m}$  high. It is shaded by a rectangular overhang  $0.5 \text{ m}$  above the top edge of the window which projects out  $0.625 \text{ m}$  and is the same width as the window. The room surface area is  $440 \text{ m}^2$  and it has a mean solar reflectance of  $0.6$ .

For monthly average March conditions, the interior of the building is at an average temperature of  $20^\circ\text{C}$ , and the average ambient temperature is  $3^\circ\text{C}$ . The monthly average radiation  $\overline{H} = 19.93 \text{ MJ/m}^2$ ,  $\overline{H}_d = 6.26 \text{ MJ/m}^2$ ,  $\overline{H}_b = 13.67 \text{ MJ/m}^2$ , and ground reflectance is  $0.2$ . What will be the net gain (or loss) from the window?

### Solution

The average day of the month for March is the 16th. The monthly average incidence angle on the glazing,  $\overline{\theta}_b$  is estimated from Figure 5.10.1 as  $57^\circ$ . From Figure 5.3.1,  $\tau_b = 0.71$ . From Figure 5.4.1 the mean angle of incidence of both diffuse and ground-reflected radiation for a vertical surface is  $59^\circ$  so the same value of transmittance is used for the diffuse and ground-reflected components. (Note that Figure 5.4.1 does not give an exact equivalent angle for diffuse radiation for a shaded receiver, but uncertainties such as those due to assumption of isotropic diffuse radiation are probably greater than a correction for overhang.) Thus  $\tau_d = \tau_g = 0.70$  and  $\overline{R}_b$  from Figure 2.19.1(d) is  $0.92$ .

For this shading overhang,  $p = 0.625/1.25 = 0.5$ ,  $g = 0.5/1.25 = 0.4$  and  $e = 0$ . The width  $w = 15/1.25 = 12$ . These are the dimensions assumed in Example 14.4.1, and from that example  $\overline{f}_i = 0.87$ . From Table 14.4.1,  $F_{r-s} = 0.42$ .

The room area is  $15.0 \times 1.25 = 18.75 \text{ m}^2$ . The absorptance of the room-window combination is estimated by Equation 5.11.1:

$$\alpha = \frac{1 - 0.6}{(1 - 0.6) + 0.6 \times 0.7 \times 18.75/440} = 0.96$$

The estimated energy absorbed in the rooms, using Equation 14.5.3, is

$$\begin{aligned} A_r \overline{S} &= 18.75 \times 0.96(0.87 \times 0.71 \times 13.67 \times 0.92 + 0.70 \times 6.26 \times 0.42 \\ &\quad + 0.2 \times 0.7 \times 19.93/2) = 198 \text{ MJ} \end{aligned}$$

and from Equation 14.5.4 the window loss over a 24-h period (with  $F_l = 1$ ) is

$$18.75 \times 24 \times 3600 \times 3.2 (20 - 3) = 88 \text{ MJ}$$

The average net gain is  $198 - 88 = 110 \text{ MJ/day}$  for the month. ■

Thus this window gives an estimated net gain of 110 MJ/day. By varying  $F_I$ , taken as unity in this example, the effects of control strategy on performance can be shown. A control method that excludes significant radiation will affect both  $\bar{f}_i$  and  $\bar{\tau}_b$ , and hourly calculations would be needed. If very effective movable insulation were to reduce window losses to near zero whenever there would be a net loss from the wall, the direct-gain system would then produce the maximum possible net input to the rooms.

It is of interest to consider the energy balance on the building as a whole. There will be four major energy flow terms across the boundaries of the direct-gain system, as shown schematically in Figure 14.5.1. The two input streams are the solar energy absorbed in the building and the auxiliary energy added  $L_A$ . The outputs are the excess energy that cannot be used or stored without driving the building to unacceptably high temperatures (the “dumped” energy  $Q_D$ ) and the “load” (here defined as the skin losses and infiltration losses less internal energy generation).


The auxiliary energy required for a month, neglecting differences in stored energy at the beginning and end of the month, will be

$$L_A = Q_D + L - A_r \bar{S} \quad (14.5.6)$$


The absorbed solar energy  $\bar{S}$  is readily calculated. The load  $L$ , including the losses through the direct-gain window, can be estimated by standard building load calculation methods. The difficult term to estimate is  $Q_D$ , the dumped energy. Methods for estimating  $Q_D$  and  $L_A$  are presented in Chapter 22.

The loads on a direct-gain system are a function of the receiver area, as in general the loss coefficient  $U_L$  for a direct-gain window will be greater than that for an insulated wall. This is illustrated in Figure 14.5.2 for a building having a  $(UA)_h$  of 200 W/°C when the area of the direct-gain receiver is zero. The term  $(UA)_h$  is shown as a function of  $A_r$  for a double-glazed receiver with heavy drapes ( $U_{L,r} = 1.3$  W/m<sup>2</sup> °C) and for a receiver with 20 mm of tight-fitting foam insulation ( $U_{L,r} = 0.95$  W/m<sup>2</sup> °C).


Examples of the effects of several design parameters of direct-gain systems on auxiliary energy requirements are shown in Figure 14.5.3. The building without the direct-gain window has a  $(UA)_h$  of 200 W/°C. The addition of direct-gain aperture, replacing corresponding areas of well-insulated wall, results in the increases in  $(UA)_h$  shown in Figure 14.5.2 and affects the annual requirements for auxiliary energy in degrees that depend on system parameters and locations. The calculations were based on the following fixed parameters: minimum noon temperature 17°C,  $\beta = 90^\circ$ ,  $\gamma = 0^\circ$ ,  $(\tau\alpha)_n = 0.75$ , and  $C_b = 25$  MJ/°C. The auxiliary energy required  $L_A$  is shown as a function of receiver



**Figure 14.5.1** Monthly energy balance on a direct-gain building.



**Figure 14.5.2** Dependence of  $(UA)_h$  on the apertures of direct-gain receivers for  $U_{\text{wall}} = 0.3 \text{ W/m}^2 \text{ }^\circ\text{C}$ ,  $U_{\text{window}} = 4 \text{ W/m}^2 \text{ }^\circ\text{C}$ , for heavy drapes with  $U_N = 0.95 \text{ W/m}^2 \text{ }^\circ\text{C}$ . Insulation is assumed to be in place an average of 12 h a day.



**Figure 14.5.3** Examples of effects of receiver area, allowable temperature swing, and night insulation on the annual auxiliary energy requirements for direct-gain passive heating in Madison, WI, Springfield, IL, and Albuquerque, NM.

area for three locations and for combinations of allowable temperature swing in the building and night insulation.

Note that there can be thermal optima in these systems. As the receiver area increases, solar gains increase but loads also increase. A point is reached at which either collector area or storage capacity begins to limit solar gains and incremental losses exceed incremental gains. The thermal optima in general will not coincide with economic optima.

The thermal advantage of direct-gain heating, based on these results, are most impressive in milder climates with high  $\overline{K}_T$ , with systems using night insulation, and with higher allowable temperature swings. Other parameter sets would give different  $Q_A$  requirements, but the trends would be the same.

The occupants of a building may use the system in different ways at different times of the year. For example, auxiliary heat may be turned off during parts of swing months, and higher than usual temperature swings tolerated. Operation of a system in this way can result in further reductions in auxiliary energy requirements.

Methods for estimating the annual performance (i.e., annual auxiliary energy requirements) of direct-gain systems are given in Sections 22.2 and 22.3.

## 14.6 COLLECTOR-STORAGE WALLS AND ROOFS

A collector-storage wall is essentially a high-capacitance solar collector coupled directly to the spaces to be heated. A diagram is shown in Figure 14.6.1. Solar radiation is absorbed on the outer surface of the wall. Energy is transferred from the room side of the wall to the spaces to be heated by convection and radiation. Energy can be transferred to the room by air circulating through the gap between the wall and glazing through openings at the top and bottom of the wall. Circulation can be by natural convection controlled by dampers on the vent openings (not shown) or by forced circulation by fans.

Radiation transmitted by the glazing and absorbed by the wall is calculated for any time period by the same methods as for the direct-gain component noted in Section 14.5, with the additional consideration that absorptance must be evaluated at the appropriate angles of incidence. For vertical surfaces:


$$A_r S = A_r F_c [f_i I_b R_b (\tau\alpha)_b + I_d (\tau\alpha)_d / 2 + I \rho_g (\tau\alpha)_g / 2] \quad (14.6.1)$$

and

$$A_r \bar{S} = A_r \bar{F}_c [\bar{f}_i \bar{H}_b \bar{R}_b (\bar{\tau}\bar{\alpha})_b + \bar{H} (\bar{\tau}\bar{\alpha})_d / 2 + \bar{H} \rho_g (\bar{\tau}\bar{\alpha})_g / 2] \quad (14.6.2)$$

where  $\bar{F}_c$  is an energy-weighted control function that will be less than unity if movable insulation is in place during times when significant radiation is available. An example of calculation of  $\bar{S}$  for a system of this type (but without overhang) was shown in Section 5.10.

If a collector-storage wall uses water to provide thermal capacitance so that there are negligible temperature gradients in the wall and if there is no air circulation through the gap, then the situation is analogous to a flat-plate collector with high capacity. Equation 6.12.7 can then be used to predict the wall temperature as a function of time. Here  $U_L$  includes



**Figure 14.6.1** Section of a collector-storage wall. Dampers may be used to ventilate the gap in summer.

only front losses, as losses out through the glazing are indeed losses but losses out the back are gains to the space to be heated. Hourly calculations are essentially the same as Example 6.12.1, with  $S$  calculated from Equation 14.6.1, except that convection and radiation from the back must be included. (Heat transfer to the rooms by these mechanisms is also needed for use in the energy balances on the rooms.)


A solid storage wall [e.g., a wall of concrete as used by Trombe et al. (1977)] can serve both structural and thermal purposes. A section of such a wall is shown in Figure 14.6.1. There will be temperature gradients through these walls, variable with time, which can be determined from energy balances as outlined in Section 8.6.

Storage walls may be either vented or unvented. Utzinger et al. (1980) have concluded that the annual auxiliary energy required by a building with a vented collector-storage wall is essentially the same as for one with an unvented wall, although the time distribution through the day of the delivered energy to the room will depend in part on venting. Balcomb et al. (1984) indicate that optimum venting can lead to performance improvements of several percent relative to unvented walls. A detailed discussion of flow in gaps is presented by Akbarzadeh et al. (1982).


A collector-storage wall supplying energy to a room and the auxiliary energy supply to the room may be controlled by several alternative strategies. If forced circulation through the gap is used, a thermostat must turn on the fan when the rooms need energy or call for auxiliary energy if the storage wall is unable to provide the needed energy. If natural circulation is used, it may be desirable to control addition of energy to the rooms by means of backdraft dampers on the vents. If summer venting to the outside is used, dampers will have to be positioned; this may be a single seasonal change which can be done manually. It may be necessary to move insulation into the air gap to control losses, and controls and mechanisms for accomplishing this must be provided. The equations for both the collector-storage wall and the rooms must reflect the modes of operation at any time. An example of the results of alternative control strategies is provided by Sebald et al. (1979).

The variations with time of day of energy flow into rooms from direct-gain windows and collector-storage walls are quite different. Figure 14.6.2 shows this contrast for south-facing receivers for a clear day. The energy absorbed in the rooms from the window occurs when the radiation enters the spaces. Energy is added to the rooms from the collector-storage wall by a combination of mechanisms: by heating of air flowing through the gap and by radiation and convection from the room side of the storage wall. The energy added by airflow lags that of the direct-gain system and is in turn lagged by the energy flow through the wall.

The effects of wall area, thickness, and night insulation on the performance of collector-storage wall systems in several locations are illustrated in Figures 14.6.3 and 14.6.4. In this example, the  $(UA)_h$  of the building without a collector-storage wall is  $200 \text{ W/}^\circ\text{C}$ . As with direct-gain systems, the addition of receiver area increases  $(UA)_h$  when losses out through the glazing of the collector-storage wall are greater than that of the insulated wall it replaces. The  $(UA)_h$  is shown as a function of  $A_r$  for collector-storage walls of various thicknesses, with and without night insulation. The walls are assumed to be concrete and the night insulation has  $R = 1 \text{ m}^2 \text{ }^\circ\text{C/W}$  (corresponding to about 25 mm of foam insulation). The loss coefficient is a weak function of wall thickness for the double-glazed storage wall.




**Figure 14.6.2** Energy flows through direct-gain and collector-storage wall systems as a function of time of day. From Utzinger (1979).



**Figure 14.6.3** An example of the variation of a building  $UA$  for a building with a collector-storage wall for no night insulation and for night insulation with  $R = 1 \text{ m}^2 \text{ } ^\circ\text{C}/\text{W}$  for four thicknesses of concrete storage wall. From wall surface to ambient  $U_L = 2.0 \text{ W}/\text{m}^2 \text{ } ^\circ\text{C}$ .





**Figure 14.6.4** Examples of effects of location, collector-storage wall area, wall thickness, and night insulation on auxiliary energy requirements. The wall is double glazed with  $(\tau\alpha) = 0.705$  and is 0.25 m thick unless otherwise noted;  $C = 12.5 \text{ MJ/}^\circ\text{C}$ ,  $\beta = 90^\circ$ , and  $\gamma = 0^\circ$ .

Figure 14.6.4 shows examples<sup>5</sup> of effects of location, receiver area, wall thickness, and night insulation for collector-storage wall systems. In Madison, this system shows an optimum collector area (i.e., minimum  $Q_A$ ) at about  $10 \text{ m}^2$ , but the effect of the wall on auxiliary energy requirements is essentially negligible under the assumptions made here. In Springfield, the uninsulated wall produces minor savings, with a minimum  $Q_A$  at an area less than  $40 \text{ m}^2$ . The insulated wall shows additional small savings.

In the climate of Albuquerque the impacts of the solar wall are more significant. In the range of areas up to  $40 \text{ m}^2$  the auxiliary energy requirement diminishes with increasing  $A_r$ . The wall thickness of 0.1 m shows better performance than either of the thicker walls, and use of night insulation results in more improvement with the thin wall than it does with the thicker walls. The Albuquerque curves do not show a minimum out to  $40 \text{ m}^2$  area; the loss coefficient of the collector-storage wall is higher than that of the insulated wall, but in this range of areas the increase in energy supplied to the building more than compensates for the increased losses from the building.

Again, other assumptions could lead to other results, and comparisons of the systems of Figure 14.6.4 should not be viewed as generalizations. Also, cost considerations have not been included.

This discussion has dealt with collector-storage walls. Similar concepts have been developed for flat roofs with storage capacity by Hay and Yellott (1973) and Hay (1973). The performance of a building using this method is described by Niles (1976). The principles are similar, but energy transport into the rooms is primarily by radiation from the storage ceiling. Collector-storage units are uncovered, and movable insulation is placed over them when collection is not occurring.

<sup>5</sup>These are computed by the unutilizability method presented in Chapter 22.

In closely related developments, transparent insulation of various types has been applied to the outside of opaque walls to reduce losses and at times produce net gains into the buildings. This is discussed in the proceedings of workshops on *Transparent Insulation Technology* (1988, 1989).


Methods for estimation of long-term performance of collector-storage walls are given in Sections 22.2 and 22.4.

## 14.7 SUNSPACES

An attached sunspace (also termed conservatory or greenhouse) is a glazed extension of the south side of a building, designed to provide a combination of energy gain and space which itself may be useful. Storage may be provided in the thermal mass of the floor and/or wall of the sunspace structure itself or it may be provided separately, for example, in the form of a pebble bed using forced or natural circulation. Circulation of warm air from the sunspace to the building can be by natural convection or with the aid of fans and associated controls. Energy will also be transferred into the building through the walls separating the sunspace from the rooms. If a sunspace has a heavy wall between it and the building, it can be thought of as a collector-storage wall with an enlarged space between the glazing and the wall. If its glazing is primarily on the south side and storage is in the rooms to be heated (i.e., the sunspace itself), it can be considered as a direct-gain room.


The design and construction of sunspaces vary widely.<sup>6</sup> They can have open or closed ends, single or multiple slopes, and various arrangements of storage mass in the floor and wall. Representative configurations of sunspace are shown in Figure 14.7.1.

Simulation models of sunspaces are related to those of collector-storage walls. A diagram of a thermal network for a sunspace with negligible end effects is shown in Figure 14.7.2. Schwedler (1981) studied networks of this kind for sunspaces with storage in the back walls and floor. He concluded that multiple nodes were needed in both vertical and horizontal directions in the floor, but multiple nodes were not needed in the horizontal direction in the storage wall. There are many possible variations of these networks to account for venting to the outside, air circulation of the building, end effects, use of water walls instead of masonry walls, use of pebble beds for storage, and sunspace configuration. The sunspace components in simulation programs such as TRNSYS (*TRNSYS Users Manual*, 2012) are based on these networks.




**Figure 14.7.1** Common sunspace configurations. Type (a) can have opaque or glazed ends. Adapted from Balcomb et al. (1983).

<sup>6</sup>See Section 22.2.



**Figure 14.7.2** A thermal network for a two-dimensional sunspace. From Schwedler (1981).

Temperature excursions in sunspaces affect their utility and can be calculated by simulations. If minimum temperatures for protection of plants are maintained, through design or by use of auxiliary energy, sunspaces can serve as greenhouses. Figure 14.7.3, from Littler (1984), shows computed temperature-time history for a two-month span for a sunspace in the winter climate of Kew, England. This sunspace is double glazed and has



**Figure 14.7.3** Sunspace air temperatures for January and February for Kew (London), England. Air is blown from the sunspace to the house when the sunspace temperature is above the room temperature. The three temperatures are at 8 AM, 1 PM, and 7 PM. From Littler (1984).


low thermal capacitance. In colder climates, temperatures will be more variable than those shown; sunspaces with more storage capacity will show less variation.

Sunspaces require the same thermal considerations as collector-storage walls or direct-gain systems, but the glazing area may be significantly larger than the receiver (collector) area. Losses occur continuously, although fans for heat transfer from sunspace to building would be shut off during nonsunny periods. Thus it may be necessary to use movable insulation to control losses or the losses may exceed gains.

## 14.8 ACTIVE COLLECTION–PASSIVE STORAGE HYBRID SYSTEMS

Systems with active collection and passive storage (ACPS) can be of particular interest for closely spaced buildings where shading problems may rule out direct-gain or collector-storage wall systems. These hybrid ACPS systems can also be considered for retrofit, particularly to buildings of masonry construction. The basic concept is that active collectors are fed with fluid from the building and return the heated fluid to the building where it serves to provide heat needed at the time and also to raise the temperature of the structure. Storage is provided by the structure itself, as in a direct-gain system. These systems have the advantage that losses from the collector during nonoperating periods are eliminated by turning off the fluid flow to the collectors. The solar contribution to meeting the heating loads of the building, however, is usually limited by the storage capacity of the structure and thus by the allowable temperature swings of the interior spaces.

Active collection–passive storage systems can be based on either air or liquid systems. The simplest use air collectors which heat room air which is recirculated to the building. This is shown schematically in Figure 14.8.1(a). It is also possible to use liquid heating collectors with a liquid-air heat exchanger as shown in Figure 14.8.1(b); the inlet temperature to the collector is higher than in the air systems, with the increase in temperature a function of the effectiveness of the heat exchanger. With the addition of another heat exchanger (air-water or liquid-water) downstream from the collector, either of these types can be arranged to provide service hot water; these heat exchangers are not shown on the diagrams. The following discussion is based on air systems, but with modification to allow for increased  $T_i$ , the same principles also apply to liquid systems.




**Figure 14.8.1** Active collect–passive store heating system schematics for systems based on (a) air and (b) liquids. The building structure provides storage.

For air systems, the inlet temperature of the collector is as low as it can be, that is, room temperature. For given collector characteristics  $[F_R(\tau\alpha)_n]$  and  $F_R U_L]$  the output of the collector will be very close to the maximum possible (differing only in that the room temperature will rise to some degree as energy is stored in the structure). Thus collector performance is comparable to that of active air systems during winter months and somewhat better during swing months.

Figure 14.8.2 shows an example of comparison of solar contributions to meeting heating loads as a function of collector area for ACPS systems for an allowable temperature swing of  $5^\circ\text{C}$  for residences of conventional and medium-weight construction in Springfield, Illinois. Also shown on the plot is the solar contribution of an active air heating system with pebble bed storage. In this example, at collector areas below solar fractions of about 0.4, the performance of the ACPS and that of the active systems are for practical purposes identical. Above solar contributions (for this particular example) of about 0.4 for the lighter building and 0.5 for the heavier, the increase of solar contribution with increasing collector area levels off. (The temperature variations in the building with the full active systems would be about half that in the ACPS building with the lower temperature swing.)

Active collection-passive storage systems should be designed with collector areas no larger than that corresponding to the knee in curves of  $\mathcal{F}$  versus  $A_c$ . At larger areas, the annual contributions are limited by storage capacity, and little is to be gained by increasing collector area. At collector areas below the knee, collector area will limit the solar contribution in peak heating seasons, and storage capacity will limit the solar contribution in spring and fall.

An economic analysis of an ACPS system shows curves of life-cycle solar savings versus  $A_c$  of the same general shape as those for active systems, but with improved solar savings at low collector areas (due to lower system costs) and sharper drop-off of life-cycle savings as collector area reaches the point at which storage is the limiting factor (i.e., the knee in the  $\mathcal{F}$ -vs.- $A_c$  curve).



**Figure 14.8.2** Solar contributions in Springfield, IL, of ACPS systems with building thermal capacitances of 25 and  $12.5 \text{ MJ}/^\circ\text{C}$  and an active air system;  $(UA)_h = 200 \text{ W}/^\circ\text{C}$ .

## 14.9 OTHER HYBRID SYSTEMS

Many active solar heating systems are on buildings that have significant contributions to their heating loads from passive (usually direct-gain) solar heating. The nature of the active and passive systems dictates that the direct gains will be realized when they are available, and the active system will meet some part of the balance of the loads. Thus the time distribution of the loads being met by the active system will differ from those of systems in which no significant passive contribution is present, as the direct-gain system meets much of the daytime and evening load and the active system meets night-time and early morning loads. The performance of these hybrid systems can be estimated by simulations. It is also possible to use design methods such as the  $f$ -chart method by applying corrections to the active system performance; the auxiliary energy requirement resulting from this calculation is then the load that the passive system sees, and the passive performance is then estimated by one of the available methods. [See Evans and Klein (1984a).]<sup>7</sup>

Another hybrid system that may be encountered is the combination of ACPS systems with direct gain (Evans and Klein, 1984b). Energy collection occurs by two routes, the collectors and the direct-gain windows, but storage is provided only in the form of the thermal capacity of the structures. The inputs coincide in time, so analyzing the two systems independently and adding the solar gains leads to overprediction of the solar contribution and underprediction of auxiliary energy requirements. The energy balances on the building are similar to those of Figure 14.5.1, with the solar input being the sum of the inputs by the two mechanisms noted. If the building becomes overheated by the combination of inputs, venting of energy will become necessary.


## 14.10 PASSIVE APPLICATIONS

A great variety of passively heated buildings have been built, operated, and enjoyed by their occupants. The performance of a few of these has been measured. Many innovative ideas and architectural approaches have evolved. In this section we present a brief picture of the operation of several buildings as illustrations of the range of possibilities.

The section diagrams in Figure 14.10.1 show several possible design concepts for passively heated buildings. Part (a) shows a direct-gain system, the Wallasey school in England. Part (b) is a section drawing of a house in Princeton, New Jersey, with a collector-storage wall two stories high, and also includes a sunspace. Part (c) shows a building with clerestory windows, which provide both direct-gain heating and daylighting for rooms on the north side of the building. Part (d) is a section of a school in Rome, Italy, which includes sunspaces at three levels on the south side of the building [Commission of the European Communities (CEC), 1988b]. The sunspaces are separated from the main part of the building by both Venetian blinds and sliding windows, so light and warm air can be admitted to or kept from the building independently (Funaro, 1986). Daylighting is also provided for the corridors. Part (e) is a schematic section of a building with a central storage wall which is heated by air circulated from the top of the building by a small fan. Part (f) shows a house with air heating collectors below floor level with airflow through a pebble bed store and/or the building by natural circulation.

---


<sup>7</sup>This will be shown in Section 22.6.



**Figure 14.10.1** Sections of passively heated buildings. (a) Section of the Wallasey School direct-gain system. (b) Section of the Kelbaugh collector-storage wall system. (c) A building with clerestory windows to admit radiation to north rooms. (d) Part of a school building in Rome, showing sunspaces, classrooms, and corridors, designed by C. Greco. (e) A building with central storage core and air circulation. (f) A natural-circulation system with separate air heating collectors and pebble bed storage.

One of the best-known passive heating applications is the group of small single-family residential buildings at Odeillo, France. The collector-storage wall in the first of these buildings consists of double glazings spaced 0.12 m from the concrete storage wall, which is 0.60 m thick. The wall is painted black and has vent openings 0.11 by 0.56 m at top and bottom which are 3.5 m apart. The collector occupies most of the south wall of the building. The auxiliary energy supply is electricity. The system was estimated by Trombe et al. (1977) to have supplied between 60 and 70% of the energy for an average house in the Odeillo climate. Based on extensive studies of this system, a building with three apartments was constructed that is better insulated, has smaller collector area per cubic meter of heated space (0.1 rather than 0.16 m<sup>2</sup>/m<sup>3</sup>), and utilizes storage walls of concrete 0.37 m thick. One of the original buildings is shown in Figure 14.10.2(a).

An example of a residence using a combined sunspace-direct-gain concept is the Balcomb house in Santa Fe, New Mexico, shown in Figure 14.10.2(b). This two-story house has 0.35-m-thick adobe walls that provide thermal capacitance and also a pebble bed storage unit to provide additional storage (AIA Research Corporation, 1978). This building operated with very little auxiliary energy input in the Santa Fe climate.

**Figure 14.10.1** (Continued)





**Figure 14.10.2** (a) The Odeillo single-family residence utilizing collector-storage walls. (b) Residence in Santa Fe, NM. (c) Residence in Golden, CO. (d) Monastery in Pecos, NM. (e) Waiting room of the Vielha Hospital, Catalonia, Spain. (f) Apartment buildings in Villefontaine, France.



**Figure 14.10.2** (Continued)

The Sargent house, built in the mid-1980s in Golden, Colorado, is shown in Figure 14.10.2(c). This direct-gain system provides about half of the total heating requirements of the building. Figure 14.10.2(d) shows a monastery building in New Mexico with clerestory windows admitting radiation to north rooms. All windows are double glazed, and solar energy provides most of the heating loads on the building (AIA Research Corporation, 1978).

Many passive buildings have been built and operated in Europe. The CEC publishes a series of case studies illustrating how passive principles can be applied to produce attractive and energy-efficient buildings. The waiting area of the Vielha Hospital in Catalonia, Spain, described in a CEC report (1988c), is shown in Figure 14.10.2(e). It is a direct-gain building with double-glazed windows covering the major part of the south façade. Shading-control awnings are used to avoid summer overheating. The hospital waiting area is on the south side and is two floors high and the first and second floors open off this space. The building is three floors high and of compact shape, and the concrete and ceramics used in floors provide about  $40 \text{ m}^3$  of direct storage. Passive solar gains contributed 33% of the total space-heating load, 44% was supplied by auxiliary energy, and the balance was provided by internal energy generation. There are heating loads on this building throughout the year. All heating loads are met by solar in the summer months and an average of about a quarter of the loads is met by solar in the balance of the year. The monthly ambient temperatures range from about 8 to  $18^\circ\text{C}$ .

A development in Villefontaine, France, includes 42 single-family residences that include a combination of direct-gain and sunspace passive heating (CEC, 1988b). Figure 14.10.2(f) shows three of these buildings. The sunspaces are on walls facing within  $45^\circ$  of south, have floor areas of  $6.5 \text{ m}^2$ , and are recessed into the building. A combination of fixed and movable shading devices control absorbed radiation. Ventilation of the sun-spaces is accomplished by windows and vents. Mechanical circulation of warm air from sunspaces to the rest of the building is used. All controls are operated manually. The space-heating energy required by these buildings is 37% less than conventional designs in the same area. Occupant response to the homes has been positive, and turnover of occupants is low.

Warehouse heating, where temperature control may not be as critical as in buildings for human occupancy, is another application of interest. Thermal storage may be provided by the contents of a warehouse with direct-gain solar heating. Translucent plastic siding has been used on the south wall of such warehouses.

Direct-gain solar heating systems may have some problems associated with them. The contents of the room are, by definition, subjected to solar radiation, which can cause fabric degradation and fading of dyes. If floors are to be built with high capacitance (i.e., of masonry), there may be limits on the placement of rugs and furniture that would reduce the addition of heat to or removal from the storage. An experimental building at MIT is being used in a study of possible answers to these and other problems. Beam radiation incident on the windows is deflected upward by narrow-slat Venetian blinds which have slats shaped to be concave upward and which have reflective materials on their upper surfaces. These blinds reflect the radiation upward to the ceiling rather than admitting it to the floor. The heat storage medium is a phase change material,  $\text{Na}_2\text{SO}_4 \cdot 10\text{H}_2\text{O}$ , in thin layers in ceiling panels. Heat transfer from the ceiling to the rooms is primarily by radiation (Mahone, 1978).

## 14.11 HEAT DISTRIBUTION IN PASSIVE BUILDINGS

There is implicit in the discussion of energy storage in buildings and the characterization of building conditions by a single temperature that energy is distributed throughout the building by natural convection (“passively” in the complete sense of the word) or by forced convection. The basic passive heating systems discussed in this chapter all result (in their simplest forms) in solar energy addition to the south rooms. The transport of heat from the heated rooms to other rooms has been the subject of experimental and theoretical studies, including model studies using water tanks and full-scale experiments in laboratories. A review of this work has been presented by Anderson (1986).

Energy moves from one room to another by a combination of mechanisms. The dominant mechanism, if there are openings between them, is by convection. Thus convective flow through doorways is of importance in energy transport in passive buildings. Natural-convection flows in buildings have been the subject of several studies. For example, Balcomb et al. (1984) report theoretical and experimental measurements of airflow in occupied buildings, and Kirkpatrick et al. (1986) have measured convective flow through doorways that connect a two-story sunspace and the rooms behind the sunspace. A temperature difference from one room to another means that there is a corresponding density difference, which leads to convective flow at the bottom of the doorway from the colder room to the warmer room and flow in the reverse direction at the top.

Any forced convection will be superimposed on the natural-convection exchange between rooms and can dominate the natural-convection processes. In a system such as that shown in Figure 14.10.1(e), air is moved from the warmer upper zones of a building to lower zones by air circulated downward through open cores in a storage wall. The forced convection requires relatively little mechanical energy and makes it possible to maintain comfortable temperature gradients throughout the building.

As pointed out by Anderson (1986), an understanding of the natural-convection processes occurring in a passive building can be essential in assuring that acceptable levels of comfort can be maintained.

## 14.12 COSTS AND ECONOMICS OF PASSIVE HEATING

The first costs, or investments, in passive heating of a building are those incremental costs associated with providing for solar heating compared to a building without solar heating. For direct-gain systems, two major costs must be considered. The first is for additional glazing area, any associated night insulation, and extra mass of the building to provide storage. Windows generally cost more than walls, and the total incremental cost of providing the windows, insulation, drapes, and so on, must be considered. The replacement of a wood frame floor by a concrete and tile floor will entail an increment in cost. The second set of costs includes equipment costs of fans for heat distribution, controls for fans, and/or movable insulation. Some of these costs will be dependent on receiver area and others may be fixed. Equation 11.1.1 can usually be used to represent systems costs.

Collector-storage walls or roofs also involve increments in first cost compared to nonsolar buildings. The costs of the mass wall glazing, movable insulation, controls, vents, and so on, should be included. If a mass wall occupies significant living space floor area or requires additional foundations, the costs of the space occupied and foundation should


be included. The same considerations hold for sunspaces, where glazing and insulation expenses may be important.

For ACPS systems, the incremental costs will be the installed costs of the collector (less credits for wall or roof replaced), blower, pump, controls, ducting or piping, plus any costs of increments to the mass of the building designed to increase its storage capacity.

The economic gain from passive heating is in reduction of purchased (auxiliary) energy. Thus an economic analysis of passive heating must be based on an analysis of the thermal performance of a system to estimate the expected reduction in auxiliary energy needs. With the reduction in cost of purchased energy, the increase in cost of the structure, and the usual set of economic parameters such as interest, discount, and inflation rates, tax data, periods of mortgages, and economic analyses, the economic principles set forth in Chapter 11 can be applied to passive solar processes. However, the loads on the building will usually increase significantly as receiver (window) area increases, in contrast to active systems where the loads are nearly independent of collector area. Thus the important results to be obtained from the thermal analysis are the annual amount of auxiliary energy needed and the reduction in annual energy purchased, and not the solar fraction. As noted in Section 10.10, a modified fractional solar contribution can be defined as

$$\mathcal{F}_c = \frac{L_S}{L_0} \quad (14.12.1)$$

where  $L_S$  is the solar energy supplied, that is, the reduction in purchased energy of the solar building compared to the nonsolar building, and  $L_0$  is the load on the nonsolar building (the same building but with  $A_r = 0$  and a standard wall replacing the receiver) that is to be met by purchased energy. With  $\mathcal{F}_c$  so defined, the analysis of Chapter 11 needs no modification. (Note that the definitions of solar fraction used by many authors differ from this.) The application of the  $P_1$ ,  $P_2$  method leads to results that are similar to those for active systems.



**Figure 14.12.1** An example of LCS of a direct-gain passive system in Albuquerque for four levels of the incremental cost per unit area of direct-gain aperture over that of the insulated wall. Area-independent costs have been assumed negligible.

For example, consider a residence to be constructed in Albuquerque, New Mexico. The building has the thermal performance characteristics (i.e., the auxiliary energy requirements) of the building of Figures 14.5.2 and 14.5.3. The allowable temperature swing is  $4^{\circ}\text{C}$ , and night insulation is to be used on the direct-gain windows, resulting in  $U_L = 1.3 \text{ W/m}^2 \text{ }^{\circ}\text{C}$ . The economic parameters are those of Example 11.8.2 (i.e.,  $C_{F1} = \$10/\text{GJ}$ ,  $P_1 = 22.169$ , and  $P_2 = 1.035$ ). The fractional solar contributions as defined for this purpose are  $\mathcal{F}_c = (L_{A,0} - L_A)/L_{A,0}$ . The annual load on the building with  $A_r = 0$  is 31 GJ, so  $\mathcal{F}_c = (31 - L_A)/31$ . Figure 14.12.1 shows curves of life-cycle savings (LCS) versus receiver area for four cost increments of the direct-gain window and drapes over the insulated wall. The economic optimum area is shown to be less than the thermal optimum area, with the difference increasing as the incremental cost of the direct-gain aperture rises. These curves are generally the same shape as those encountered in active systems, and depending on location and system design, the curves may or may not show positive savings.

## REFERENCES

- AIA Research Corporation, Report to the Department of Housing and Urban Development HUD-PDR-287, Washington, DC (1978). "A Survey of Passive Solar Buildings."
- Akbarzadeh, A., W. W. S. Charters, and D. A. Leslie, *Solar Energy*, **28**, 461 (1982). "Thermocirculation Characteristics of a Trombe Wall Passive Test Cell."
- Anderson, B., *Solar Energy, Fundamentals in Building Design*, McGraw-Hill, New York (1977).
- Anderson, R., *Passive Solar J.*, **3**, 33 (1986). "Natural Convection Research and Solar Building Applications."
- ASHRAE *Fundamentals Handbook*, ASHRAE, Atlanta, GA (2005).
- Balcomb, J. D., G. F. Jones, and K. Yamaguchi, in *Proceedings of the Ninth National Passive Solar Conference* American Solar Energy Society, Columbus, OH (1984). "Natural Convection Air-Flow Measurements and Theory."
- Balcomb, J. D., R. W. Jones, R. D. McFarland, and W. O. Wray, *Passive Solar J.*, **1**, 67 (1983). "Expanding the SLR Method."
- CEC, Research and Development Programmes on Solar Energy Applications to Buildings, Research Digest No. 1 (1988a).
- CEC Project Monitor, Case Study 28 (1988b). "Les Tournesols, Villefontaine, France."
- CEC Project Monitor, Case Study 34 (1988c). "Vielha Hospital, Catalonia, Spain."
- Dietz, A. G. H. and E. L. Czapek, *Heating, Piping and Air Conditioning*, **118** (Mar. 1950). "Solar Heating of Houses by Vertical South Wall Storage Panels."
- Evans, B. L. and S. A. Klein, paper presented at Las Vegas ASME Meeting (1984a). "A Design Method for Active Collection-Passive Storage Space Heating Systems."
- Evans, B. L. and S. A. Klein, paper presented at Anaheim ASES Meeting (1984b). "Combined Active Collection-Passive Storage and Direct Gain Hybrid Space Systems."
- Fanger, P. O., *Thermal Comfort Analysis and Applications in Environmental Engineering*, McGraw-Hill, New York (1972).
- Funaro, G., *Passive Solar J.*, **3**, 291 (1986). "Passive Solar Buildings in Italy."
- Harrison, D., *Solar Energy*, **17**, 317 (1975). "Beadwalls."
- Hay, H. R., *Mech. Eng.*, **95**, 18 (1973). "Energy, Technology, and Solararchitecture."
- Hay, H. R. and J. I. Yellott, *Mech. Eng.*, **92**, 19 (1973). "A Naturally Air-Conditioned Building."
- Hollingsworth, F. N., *Heating and Ventilating*, **76** (May 1947). "Solar Heat Test Structure at MIT."
- Jones, R. E., *Solar Energy*, **24**, 305 (1980). "Effects of Overhang Shading of Windows Having Arbitrary Azimuth."

- Kirkpatrick, A., D. Hill, and K. Stokes, *Passive Solar J.*, **3**, 277 (1986). “Natural Convection in a Passive Solar Building.”
- Lebens, R. M., *Passive Solar Heating Design*, Applied Science, London (1980).
- Littler, J., personal correspondence (1984).
- Mahone, D., *Solar Age*, **3** (9), 20 (1978). “Three Solutions for Persistent Passive Problems.”
- Mazria, E., *The Passive Solar Energy Book*, Rondale, Emmaus, PA (1979).
- Niles, P. W. B., *Solar Energy*, **18**, 413 (1976). “Thermal Evaluation of a House Using a Movable Insulation Heating and Cooling System.”
- Olgyay, V., *Design with Climate*, Princeton University Press, Princeton, NJ (1963).
- Schwedler, M. C. A., M.S. Thesis, Mechanical Engineering, University of Wisconsin-Madison (1981). “The Simulation of Sunspace Passive Solar Energy Systems.”
- Sebald, A. V., J. R. Clinton, and F. Langenbacher, *Solar Energy*, **23**, 479 (1979). “Performance Effects of Trombe Wall Control Strategies.”
- Shurcliff, W. A., *Solar Heated Buildings of North America*, Brick House, Harrisville, NH (1978).
- Sun, Y. T., *ASHRAE Task Group on Energy Requirements*, 48 (1975). “SHADOW 1, Procedure for Determining Heating and Cooling Loads for Computerized Energy Calculations.”
- Szokolay, S. V., *Solar Energy and Building*, Architectural, London (1975).
- Transparent Insulation Technology for Solar Energy Conversion, Proceedings of the Third International Workshop* (1989), and *The Second International Workshop on Transparent Insulation in Solar Energy Conversion for Buildings and Other Applications*, The Franklin Co., Birmingham, UK (1988).
- TRNSYS Users Manual*, Version 16, University of Wisconsin Solar Energy Laboratory (2012). [First public version was 7.0 (1976).]
- Trombe, F., J. F. Robert, M. Cabanot, and B. Sesolis, *Solar Age*, **2**, 13 (1977). “Concrete Walls to Collect and Hold Heat.”
- Uttinger, D. M., M.S. Thesis, Mechanical Engineering, University of Wisconsin-Madison (1979). “Analysis of Building Components Related to Direct Solar Heating of Buildings.”
- Uttinger, D. M. and S. A. Klein, *Solar Energy*, **23**, 369 (1979). “A Method of Estimating Monthly Average Solar Radiation on Shaded Receivers.”
- Uttinger, M. D., S. A. Klein, and J. W. Mitchell, *Solar Energy*, **25**, 511 (1980). “The Effect of Air Flow Rate in Collector-Storage Walls.”



## Solar Cooling

The use of solar energy to drive cooling cycles has been considered for two related purposes, to provide refrigeration for food preservation and to provide comfort cooling. In Section 15.1 we briefly review some of the literature relating to both of the applications, since there is a common underlying technology. From then on, we concentrate on problems relating to solar air conditioning. In particular, for application in temperate climates, we address questions of the use of flat-plate collectors for both winter heating and summer cooling.

Solar cooling of buildings is an attractive idea. Cooling is important in space conditioning of most buildings in warm climates and in large buildings in cooler climates. Cooling loads and availability of solar radiation are approximately in phase. The combination of solar cooling and heating should greatly improve use factors on collectors compared to heating alone. Solar air conditioning can be accomplished by three classes of systems: absorption cycles, desiccant cycles, and solar-mechanical processes. Within these classes there are many variations: for example, using continuous or intermittent cycles, hot- or cold-side energy storage, various control strategies, various temperature ranges of operation, different collectors. Each of these methods is reviewed in this chapter, with emphasis on absorption and desiccant cooling.

The future of many of the methods will depend on developments beyond the cooling process itself. Temperature constraints in the operation of collectors limit what can be expected of solar cooling processes. As collector operating temperatures are pushed upward, storage may then become a critical problem. The relationship of collector and storage characteristics to cooling performance will be evident in the following discussions.

Cooling is expensive, as is heating. Reduction in cooling loads through careful building design and insulation will certainly be warranted and, within limits, will be less expensive than providing additional cooling. Good building design and construction are needed to minimize loads on the air conditioning and heating system. Our concern is with cooling loads that cannot be avoided by building design.

Solar refrigeration can be accomplished with a conventional refrigeration unit but with electrical energy supplied by a photovoltaic system or by a solar thermal/electric system. The problems are not with the cooling equipment but with the solar system to provide electrical energy. Such systems are discussed by Klein and Reindl (2005). An alternative is to supply mechanical energy from a solar system to directly drive the compressor of a vapor compression machine. Such a system is discussed in Section 15.9. Solar refrigeration can also be accomplished with absorption systems that are similar to the cooling systems described in the next few sections.




## 15.1 SOLAR ABSORPTION COOLING

Two approaches have been taken to solar operation of absorption coolers. The first is to use continuous coolers, similar in construction and operation to conventional gas- or steam-fired units, with energy supplied to the generator from the solar collector-storage-auxiliary system whenever conditions in the building dictate the need for cooling. The second is to use intermittent coolers similar in concept to that of commercially manufactured food coolers used many years ago in rural areas (the Crosley “Icyball”) before electrification and mechanical refrigeration were widespread. Intermittent coolers have been considered for refrigeration, but most work in solar air conditioning has been based on continuous cycles.

**Continuous absorption cycles** can be adapted to operation from flat-plate collectors. The principles of these cooling cycles are described in *ASHRAE Handbook—Fundamentals* (2005). A diagram of one possible arrangement is shown in Figure 15.1.1. The present temperature limitations of flat-plate collectors restrict consideration among commercial machines to lithium bromide–water systems. The LiBr–H<sub>2</sub>O machines require cooling water for cooling the absorber and condenser, and in most applications a cooling tower will be required. Operation with flat-plate collectors of ammonia–water coolers such as those now marketed for steam- or gas-fired operation is difficult because of the high generator temperatures required. Coolers based on other refrigerant-absorbent systems may be possible candidates for solar operation.

A commercial lithium bromide–water air conditioner, modified to allow supplying the generator with hot water rather than steam, was operated from a flat-plate water heater by Chung et al. (1963). An analytical study of solar operation of a LiBr–H<sub>2</sub>O cooler and flat-plate collector combination by Duffie and Sheridan (1965) identified critical design parameters and assessed the effects of operating conditions on integrated solar operation. Under the assumptions made in their study, design of the sensible heat exchanger between absorber and generator, cooling water temperature, and generator design are important; the latter is more critical here than in fuel-fired coolers because of the coupled performance of



**Figure 15.1.1** Simplified schematic of a solar absorption air conditioning system.

the collector and cooler. An experimental program was also developed at the University of Queensland, Australia, in a specially designed laboratory house (Sheridan, 1970).


From these and other experiments, it was clear that LiBr-H<sub>2</sub>O absorption air conditioners could be adapted for solar operation. Without modification, the commercial machines operated at reduced capacities, but they could be modified to operate at nominal capacities with energy supply to the generator by hot water. Part-load operation could be accomplished at little loss of the coefficient of performance, with reduced dehumidification. Generator temperatures required for these air conditioners would be in a range suitable for flat-plate collectors (with the collectors operating at about the same temperature levels above ambient as those for winter heating operation).

If cooling requirements rather than heating loads fix collector size requirements, it is advantageous to use coolers with high COP. For example, double-effect evaporators can be used to decrease energy input requirements (Whitlow and Swearingen, 1959; Chinnappa, 1973). The conditions and constraints of solar operation lead to cooler designs different from those for fuel operation.

**Intermittent absorption cooling** may be an alternative to continuous systems. Most work to date on these cycles has been directed at food preservation rather than comfort cooling. These cycles may be of interest in air conditioning because they offer potential solutions to the energy storage problem. In these cycles, distillation of refrigerant from the absorbent occurs during the regeneration stage of operation, and the refrigerant is condensed and stored. During the cooling portion of the cycles, the refrigerant is evaporated and reabsorbed. A schematic of the simplest of these processes is shown in Figure 15.1.2. "Storage" is in the form of separated refrigerant and absorbent. Modifications of this basically simple cycle may result in an essentially continuous cooling capacity and improved performance.

Refrigerant-absorbent systems used in intermittent cycles have been H<sub>2</sub>SO<sub>4</sub>-H<sub>2</sub>O, NH<sub>3</sub>-H<sub>2</sub>O, and NH<sub>3</sub>-NaSCN. In the latter system, the absorbent is a solution of NaSCN in NH<sub>3</sub>, with NH<sub>3</sub> the refrigerant. This system has been studied by Blytas and Daniels (1962) and Sargent and Beckman (1968), and it appears to have good thermodynamic properties for cycles for ice manufacture. Williams et al. (1958) reported an experimental study of an intermittent NH<sub>3</sub>-H<sub>2</sub>O cooler using concentrating collector for regeneration.

Chinnappa (1961, 1962) and Swartman and Swaminathan (1970) experimentally studied the operation of intermittent NH<sub>3</sub>-H<sub>2</sub>O machines in which flat-plate collectors



**Figure 15.1.2** Schematic of an intermittent absorption cooling cycle. On the left is the regeneration cycle. On the right is the refrigeration cycle. The generator-absorber is a single vessel performing both functions, and the condenser-evaporator is also a single vessel performing both functions.


provided the energy supply. The absorber and generator are separate vessels. The generator was an integral part of the collector, with refrigerant-absorbent solution in the tubes of the collector circulated by a combination of thermosyphon and a vapor lift (bubble) pump. Using approximately equal cycle times for the regeneration and refrigeration steps (5 to 6 h each), overall COPs were found to be approximately 0.06 at generator temperatures rising from ambient to approximately  $99^{\circ}\text{C}$  during regeneration. Evaporator temperatures were below  $0^{\circ}\text{C}$ . With cooling water available at approximately  $30^{\circ}\text{C}$ , the effective cooling per unit area of collector surface per day for the experimental machine was in the range of 50 to  $85 \text{ kJ/m}^2$  for clear days.

This is an incomplete history of developments of solar absorption cooling, but it provides an indication of the basis for interest in the combination of solar energy supply and absorption air conditioning. In the following section, we discuss some aspects of the theory of absorption cooling, particularly as it relates to solar operation, and in Sections 15.4 and 15.5 show data on solar cooling system performance.


## 15.2 THEORY OF ABSORPTION COOLING

Operation of absorption air conditioners with energy from flat-plate collector and storage systems is the most common approach to solar cooling. A schematic of a solar absorption cooling system is shown in Figure 15.2.1; this system (or variations using other methods of energy storage, auxiliary energy input, multiple-stage coolers, etc.) has been the basis of most of the experience to date with solar air conditioning.

The coolers used in most experiments are  $\text{LiBr-H}_2\text{O}$  machines with water-cooled absorbers and condensers. A pressure-temperature-concentration equilibrium diagram for  $\text{LiBr}$  and  $\text{H}_2\text{O}$  is shown in Figure 15.2.2. The idealized operation of a cycle is indicated on the diagram. The pressure in the condenser and generator is fixed by the condenser fluid coolant temperature. The pressure in the evaporator and absorber is fixed by the temperature of the cooling fluid to the absorber. The letters on the lines representing the



**Figure 15.2.1** Schematic of a solar-operated absorption air conditioner. The essential components of the cooler are: A, absorber; B, generator; C, condenser; E, evaporator; HX, heat exchanger to recover sensible heat; CT, cooling tower. AX is auxiliary energy source.



**Figure 15.2.2** Pressure-temperature-concentration diagram for LiBr-H<sub>2</sub>O showing an idealized cooling cycle with letters on the segments corresponding to the process components of Figure 15.2.1.

cycle correspond to the processes occurring in the components indicated in Figure 15.2.1. The generation process is one of increasing the concentration from 55 to 60% while the equilibrium temperature of the solution rises from 72 to 82°C at the pressure of the condenser. In the absorber, the solution concentration drops from 60 to 55% as the solution temperature drops from 48 to 38°C, all at the evaporator pressure. In a real cycle, some sensible heat will have to be transferred in the generator and absorber (the amount dependent on the effectiveness of exchanger HX), there will be pressure changes through the generator due to hydrostatic head, and there will be temperature differences across all heat exchangers. Exact pressures, temperatures, and concentrations will vary with the machine and operating conditions; the numbers used here are for illustration of the nature of the process.

The maximum solution temperature in the generator is shown in Figure 15.2.2; the temperature of the heated fluid to the generator must be above the maximum generator temperature, which is determined by the condenser pressure and the concentration of the solution leaving the generator. The generator temperatures must be kept within the limits imposed by the characteristics of flat-plate collectors. The critical design factors and operational parameters include solution concentrations, effectiveness of the heat exchangers, and coolant temperature.

The pressure differences between the high- and low-pressure sides of LiBr-H<sub>2</sub>O systems are small enough that these systems can use a vapor lift pump and gravity return from absorber to generator as an alternative to mechanical pumping to move the solution from the low-pressure to the high-pressure side. Early absorption machines used the vapor lift pump, but more recent designs use mechanical pumps because of improved performance.

An overall steady-state energy balance on the absorption cooler indicates that the energy supplied to the generator and to the evaporator must equal the energy removed from

the machine via the coolant flowing through the absorber and condenser plus whatever net losses may occur to the surroundings:

$$Q_G + G_E = Q_A + Q_C + Q_{\text{Losses}} \quad (15.2.1)$$

The thermal coefficient of performance  $COP$  is defined as the ratio of energy into the evaporator  $Q_E$  to the energy into the generator  $Q_G$  :

$$COP = \frac{Q_E}{Q_G} \quad (15.2.2)$$

The coefficient of performance is a useful index of performance in solar cooling, where collector costs (and thus costs of  $Q_E$ ) are important. Many LiBr-H<sub>2</sub>O machines have nearly constant  $COP$  as the generator temperatures vary over the operating range, as long as the temperatures are above a minimum. The thermal  $COP$  is usually in the range of 0.6 to 0.8, and the major effect of variation in the solar energy temperature to the generator is to vary  $Q_E$ , the cooling rate.


Other types of  $COP$  can be defined (Mitchell, 1986). A  $COP_e$  is the ratio of cooling to electrical energy used to provide air and liquid flows, operate controls, and so on:

$$COP_e = \frac{Q_E}{\text{electric input}} \quad (15.2.3)$$

With water used as a coolant in the absorber and condenser, the generator temperatures are in the range 70 to 95°C. The temperature of the fluid supplied to the generator must be higher than this, which means that there is a small temperature range over which an unpressurized water storage tank can operate. Operation of most flat-plate collectors near 100°C is marginal. In addition, cooling towers are needed. These are three major problem areas in solar application of LiBr-H<sub>2</sub>O coolers.

The schematic diagram of an ammonia-water cooler is similar to that of the cooler of Figure 15.2.1 except that a rectifying section must be added to the top of the generator to reduce the amount of water vapor going to the condenser. Pressure-temperature-concentration data for the ammonia-water system are shown in Figure 15.2.3. The basic solution processes are similar to those of the LiBr-H<sub>2</sub>O system, but the pressures and pressure differences are much higher and mechanical pumps are needed to return solutions from the absorber to the generator. In many applications the condenser and absorber are air cooled with generator temperatures in a range of 125 to 170°C. In applications where water cooling is used, generator temperatures may be in the range of 95 to 120°C. Both air-cooled and water-cooled cycles are shown in Figure 15.2.3. The condensing temperatures for the air-cooled condenser correspond to much higher generator temperatures than those for liquid-cooled systems.

There are two approaches to the calculation of performance of absorption coolers. It is possible to write for each component in the cooler a full set of energy balances, material balances, rate equations, and equilibrium relationships. These are solved simultaneously to determine the operating conditions and energy rates. This approach has been taken, for example, by Allen et al. (1973). The solution of the equations is expensive in computer



**Figure 15.2.3** Pressure-temperature-concentration diagram for  $\text{NH}_3\text{-H}_2\text{O}$  with two idealized cycles corresponding to water-cooled condenser and absorber and air-cooled condenser and absorber.

time, and there is additional difficulty that real absorption coolers may include other components such as concentration adjusters (small containers that retain volumes of refrigerant or absorbent, depending on pressures in the machine, and so change the solution concentrations), which are difficult to include in the analysis.

The second alternative is to devise empirical models based on operating data from specific machines. These are much easier to use, particularly in simulations where repetitive computations are done. An early model of a  $\text{LiBr-H}_2\text{O}$  cooler was devised by Butz (1973) and used in an early simulation of absorption air conditioning (Butz et al., 1974). This model was modified by Ward and Löf (1975) and Oonk et al. (1975) to reflect data on later machines and by Blinn (1979), who has introduced a method of modeling transient operation of the cooler.

As a result of the on-off control strategy most commonly used in residential applications, chillers often do not operate at steady state. The room thermostat calls for cooling when the room temperature rises above a small control range and shuts off the chiller when room temperature drops below the range. If the cooling capacity is significantly greater than the building cooling load, the thermostat will cycle and the chiller will spend part of its operating time in a transient mode.

When a cooler is started up, the lithium bromide–water solution will begin circulating between the generator and absorber. No vapor will be evolved until the generator and all the solution held up in the generator have been heated to a temperature  $T_{\min}$ . This temperature is the boiling point of a lithium bromide solution whose concentration corresponds to the chiller's initial charge at a pressure determined by the condenser temperature.

If the generator, sensible heat exchanger, and absorber are all modeled as constant-effectiveness heat exchangers during start-up, if the generator is modeled as a singlenode

thermal capacitance, and if it is assumed that the absorber and sensible heat exchanger respond much more rapidly than the generator, then the generator temperature during start-up will vary exponentially:

$$T_G = T_{G,ss} + (T_{G,o} - T_{G,ss}) \exp\left(-\frac{t}{t_H}\right) \quad (15.2.4)$$

where  $T_G$  = generator temperature

$T_{G,ss}$  = steady-state generator temperature

$T_{G,o}$  = initial generator temperature

$t_H$  = generator time constant for start-up

Measurements of the time-temperature history of the generator of a 3-ton-capacity chiller (Arkla model WF-36) located at Colorado State University (CSU) Solar House I show that during start-up the generator is described well by Equation 15.2.4, with a time constant  $t_H$  of about 8.0 min.

During cooldown, after the chiller has been shut off, solution will drain to the lowest point of the chiller (usually the absorber) and lose heat to the surrounding air by conduction and natural convection. In that case

$$T_S = T'_a + (T_{G,o} - T'_a) \exp\left(-\frac{t}{t_C}\right) \quad (15.2.5)$$

where  $T_S$  = solution temperature

$T'_a$  = temperature of surroundings

$t_C$  = cooldown time constant

The cooldown time constant  $t_C$  will tend to be much larger than the start-up time constant, since it depends on free rather than forced convection. The cooldown time constant measured for the 3-ton chiller at CSU was about 63 min.

To complete the transient model, it is assumed that the instantaneous cooling delivered is a unique function of generator temperature, condensing water temperature (which fixes condenser and absorber temperatures), and evaporator temperature. The evaporator temperature is assumed constant, and manufacturer's performance data are used to determine cooling capacity and coefficient of performance as empirical functions of generator and condensing water temperatures.



When the generator temperature is above  $T_{\min}$ , cooling and generator heat uptake are given by

$$Q_E = f_1(T_G, T_{CW}) \quad (15.2.6)$$

$$Q_G = f_2(T_G, T_{CW}) \quad (15.2.7)$$

where  $f_1$  and  $f_2$  are curve fits to manufacturer's data in terms of the generator temperature and the cooling water temperature. When the generator temperature is less than  $T_{\min}$ ,  $Q_E = 0$  and  $Q_G = (UA)_G(T_s - T_G)$ .

Figure 15.2.4 shows the measured steady-state operation of a LiBr-H<sub>2</sub>O chiller, indicating fraction of rated capacity and thermal *COP* as functions of inlet temperature of water to the generator and the coolant temperature.



**Figure 15.2.4** Manufacturer's data for 3-ton Arkla LiBr-H<sub>2</sub>O water chiller showing (a) capacity as a function of water inlet temperatures to generator and condenser at chilled water outlet temperature of 7.2 °C, and (b) COP as a function of water inlet temperatures to generator and condenser. From Blinn (1979).



The average *COP* over a long term can be evaluated as

$$\overline{COP} = \frac{\int Q_E dt}{\int Q_G dt} \quad (15.2.8)$$

Simulations using meteorological data for Charleston, South Carolina, over a cooling season indicate that the transient operation of the chiller leads to approximately 8% lower *COP* than would be expected if transients were neglected. The months with the lowest cooling loads are the months with the highest differences, as those are the months when the cooler is oversized and cycles most frequently.

### 15.3 COMBINED SOLAR HEATING AND COOLING


Many applications of solar air conditioning will be done in conjunction with solar heating, with the same collector, storage, and auxiliary energy system serving both functions and supplying hot water. Figure 15.3.1 shows a combined heating and cooling system based on absorption cooling for air conditioning.

An important consideration in combined heating and cooling systems is the relative importance of the summer and winter loads. Either one may dictate the needed capacity of the collector and consequently its size and design. Climate is a major determining factor, and cooling requirements will dominate in climates like those of Phoenix and Miami. Commercial buildings are likely to have design fixed by cooling loads, even in cool climates. Also important are building design features that can affect relative energy requirements for the two loads. These include fenestration, shading by overhangs, wing-walls and foliage, and building orientation. Less obvious is the performance of the heating and cooling system; a poor absorption cooler would require a larger collector area than one with a high *COP* and thus could shift the determination of collector needs from winter heating to summer cooling.

The location of storage, whether inside or outside the building, will have an effect on heating or cooling loads. If heat is to be stored and if the storage unit is inside the structure, heat losses from storage become uncontrolled gains during the heating season and additional loads during the cooling season. If collectors are part of the envelope of the building, back losses from the collector will also become uncontrolled gains during heating and additional loads during cooling.

Collector orientation may be affected by which load dominates; optimum orientation is approximately  $\beta = \phi + 15^\circ$  for winter use,  $\beta = \phi - 15^\circ$  for summer use, and  $\beta = \phi$  for all-year use. Heating loads are likely to be higher in the morning, suggesting that the surface azimuth angle  $\gamma$  should be negative, while cooling loads peaking in the afternoon suggest that  $\gamma$  should be positive. Simulations can be used to answer these questions [see Oonk et al. (1975) for an example]; fortunately collector orientation is usually not critical.

As with solar heating alone, the major design problem is the determination of optimum collector area, with underdesign leading to excessive use of auxiliary energy and overdesign leading to low use factors on the capital-intensive solar energy system. Absorption air




**Figure 15.3.1** Schematic of a combined solar heating, air conditioning, and hot-water system using a LiBr-H<sub>2</sub>O absorption cooler. Solid flow lines are for cooling, dashed lines are for heating, and dotted lines are air conditioner coolant flow. AU is auxiliary energy source, AC is air conditioner, CT is cooling tower, PH is preheat tank, and WH is water heater.

conditioners are more expensive than mechanical air conditioners. In climates where annual cooling loads are low, the use of absorption coolers will lead to higher cooling costs because of low use factors on the coolers.

## 15.4 SIMULATION STUDY OF SOLAR AIR CONDITIONING

Simulations provide useful information on effects of design changes on the long-term performance of solar coolers. In this section we show the results of a simulation study of the system of Figure 15.3.1, a liquid system with a LiBr-H<sub>2</sub>O chiller modeled as described in Section 15.2. The simulations were done using meteorological data for Albuquerque, New Mexico.

The building simulated has a floor area of 150 m<sup>2</sup>, is well insulated with  $(UA)_h = 232 \text{ W/}^\circ\text{C}$ , has infiltration of one-half air change per hour, and has reasonable levels of internal heat generation and building capacitance. Latent cooling loads are estimated as 0.3 of the sensible cooling loads. The desired room temperature range is 19 to 25°C. The hot-water load is 300 kg/day heated from 11 to 55°C, and a tempering valve prevents




**Figure 15.4.1** Annual fraction of energy supplied by solar energy for the Albuquerque simulations.

delivery of water at temperatures above 55°C. Storage capacity of the preheat tank is 0.35 m<sup>3</sup>.

The collectors have  $F_R(\tau\alpha)_n = 0.72$  and  $F_R U_L = 4.94$  W/m<sup>2</sup> °C and are sloped toward the south at  $\beta = 36^\circ$  at the Albuquerque latitude of 35° N. The value of  $F'_R/F_R$  is 0.94. Simulation results are shown for five collector areas, from 5 to 50 m<sup>2</sup>. An antifreeze solution with  $C_p = 3900$  J/kg °C is circulated at  $\dot{m}/A_c = 0.0015$  kg/m<sup>2</sup> s. The storage tank volume is 0.10 m<sup>3</sup>/m<sup>2</sup>, it has a loss coefficient of 10.5 W/m<sup>2</sup> °C, and its temperature is limited to 100°C. The minimum tank temperature for solar heating is 30°C.

The chiller has a nominal capacity of 4.2 kW, a start-up time constant of 0.133 h, and a cooldown time constant of 1.05 h. The minimum useful source temperature is 77°C. Auxiliary energy in this set of simulations is provided in either of two ways. The primary method is by addition of heat to the generator of the chiller when needed. If the temperature in the building continues to be above the control temperature, parallel cooling by a separate (mechanical) cooler is computed to provide an approximation of energy required to meet any cooling loads not met by the absorption chiller.


Figure 15.4.1 shows the variation of the fraction of the annual energy needs (for heating, hot water, and cooling) met by this system as a function of collector area. The curve has the same general shape as those for space heating. In the Albuquerque climate, the solar fraction reaches 0.98 at a collector area of 50 m<sup>2</sup> in the particular year used in these simulations. The monthly fractions are shown in Figure 15.4.2(a), where the inability of smaller collectors to meet large winter heating loads or summer cooling loads is evident. As with solar heating, the larger systems show poorer integrated efficiencies as they are oversized during spring and fall. The larger systems run at higher temperatures and have more thermal losses from the collectors. Figure 15.4.2(b) shows a plot of monthly efficiency (the ratio of the collected energy to the total radiation incident on the collector for the month) for the five collector areas. It is clear that high collector efficiencies are associated with low solar fractions in these systems with seasonally varying loads.



**Figure 15.4.2** (a) Monthly fractions of loads met by solar energy for five collector areas for the Albuquerque simulation. (b) Monthly collector efficiencies for five collector areas for the Albuquerque simulations.

Figure 15.4.3 shows, for a collector area of 15 m<sup>2</sup>, the cumulative heating, cooling, and hot-water loads and the contributions by solar to meeting those loads. The year starts in September, between the heating and cooling seasons.

The annual results of these simulations are summarized in Table 15.4.1. The space-heating and space-cooling loads increase slightly with collector area, as the control scheme maintains the building at higher mean temperatures in the winter and lower mean temperatures in the summer as the size of the solar energy system increases. (Different



**Figure 15.4.3** Cumulative loads and solar contributions for the 15-m<sup>2</sup> collector area for the Albuquerque simulations.

**Table 15.4.1** Summary of Annual Performance for Albuquerque Simulations of Solar Heating, Hot Water, and Cooling

Collector area, m <sup>2</sup>	5	10	15	30	50
Space-heating load, GJ	38.6	40.2	41.0	42.1	43.3
Air conditioning load, GJ	13.9	13.6	13.2	14.3	16.9
DHW load, GJ	20.2	20.2	20.2	20.2	20.2
Total load, GJ	72.8	74.0	74.5	76.6	80.4
Solar to space heating, GJ	8.7	17.9	24.5	36.1	42.5
Solar to air conditioning, GJ	0.0	5.0	6.7	13.8	16.8
Solar to DHW, GJ	12.9	15.2	16.6	18.6	19.6
Total solar to load, GJ	21.6	35.6	47.8	68.4	78.9
Fraction of load met by solar	0.30	0.28	0.64	0.89	0.98
Collector efficiency, %	52	44	39	30	22
Energy delivered, GJ/m <sup>2</sup>	4.32	3.56	3.19	2.28	1.58

controls would have made some difference in these loads, but the general trends and conclusions would not change.) Annual efficiencies are shown; they decrease as collector area increases. Annual energy delivered per square meter of collector is shown; it is an approximate index of energy delivered per unit cost of the system (insofar as system cost is proportional to collector area).


## 15.5 OPERATING EXPERIENCE WITH SOLAR COOLING

Detailed performance measurements of several solar cooling systems have been published. These systems are best described as experiments; the data provide an indication of the technical feasibility of solar absorption air conditioning.


The solar collector and heating system used on CSU House III in 1983 to 1984 (Karaki et al., 1984) was described in Section 13.3. The building is shown in Figure 13.2.5. The system was also equipped with an Arkla 3-ton LiBr-H<sub>2</sub>O absorption chiller. A schematic of the complete system is shown in Figure 15.5.1. The 48.7 m<sup>2</sup> of collectors were double glazed with selective surfaces, and storage was in a water tank of 4530 kg capacity that was fitted with inlet and outlet manifolds designed to enhance stratification. Chilled water from the absorption machine was pumped through a heat exchanger in the air supply ducts for the building.

The chiller was a stand-alone unit located outside of the conditioned space. Heat rejection was accomplished by direct evaporative cooling by water trickling down over the outside walls of the condenser and absorber, so the functions of chiller and cooling tower were integrated into a single unit. The chiller had included in it a number of features designed to make it perform well under the transient operating conditions experienced in the solar operation and to avoid crystallization of LiBr in the generator during low-temperature operation. The effects of on-off cycling were minimized by controls that called for cooling to be continued during shutdown transients. [See Karaki et al. (1984) for details of the chiller, system, and controls.]

A diagram of the energy flows in the cooling operation is shown in Figure 15.5.2. A complete energy analysis of the system would involve determination of all of the flows; the experiments at CSU included measurement or calculation of all but a few noncritical flows.



**Figure 15.5.1** Schematic of the solar cooling system on CSU House III. From Karaki et al. (1984).



**Figure 15.5.2** Energy flows in cooling operation at CSU House III. Adapted from Karaki et al. (1984).

This system carried about one-quarter of the summer cooling loads. The building houses offices, and internally generated cooling loads from office machines and computers started early in the day hours before the collectors turned on. Solar cooling performance by months is shown in Table 15.5.1. Table 15.5.2 provides information on three months of solar operation and shows the incident solar radiation, energy collected, energy supplied to the generator, energy removed at the evaporator, amount of cooling provided in the building, and a solar cooling performance factor (SCPF) (the ratio of heat removed at the cooling coil to the radiation incident on the collector). The maximum SCPF would be the product of the daily collection efficiency and the chiller coefficient of performance. The

**Table 15.5.1** 1983 Solar Cooling Performance of CSU House III<sup>a</sup>

Month	Total Cooling Load	Heat Pump Cooling	Solar Cooling	Percent by Solar
July	476	380	96	20
August	511	369	142	28
September	413	325	88	21

<sup>a</sup>Energy quantities are in MJ/day (average). Data are from Karaki et al. (1984).

**Table 15.5.2** Incident Radiation and System Performance<sup>a</sup>

Month	Solar Radiation	Energy Collected	Energy to Generator	$Q_E$	Cooling	SCPF
July	904	272	183	126	96	0.11
August	964	300	232	159	141	0.15
September	1068	238	199	159	88	0.08

<sup>a</sup>Energy quantities are in MJ/day (average). Data from Karaki et al. (1984).

SCPFs measured at CSU were a one-half to three-quarters of the maximum. Losses from storage (and other parts of the system) were substantial contributors to the difference; the tank cooled off at night and considerable collection of energy was required to bring it back up to the threshold operating temperature. Redesign of the system to reduce losses and changes in operating strategy could improve system performance.

## 15.6 APPLICATIONS OF SOLAR ABSORPTION AIR CONDITIONING

Under the auspices of various research, development, and demonstration programs, a number of solar-operated cooling systems have been installed and operated by companies and government agencies. Many are 3- or 25-ton LiBr-H<sub>2</sub>O units, and applications have been made to residential- and commercial-scale buildings. Flat-plate collectors have been used on most of the systems; several have been equipped with evacuated-tube collectors that will operate at higher temperatures. According to Mitchell (1986), the performance of these systems has ranged from very bad to very good. Major problems included high parasitic power requirements for operation of fans, pumps, and cooling towers; inappropriate controls and control strategies; and use of oversized chillers that results in frequent cycling and performance degradation.

Single-effect LiBr-H<sub>2</sub>O chillers operate with thermal coefficients of performance that are limited to about 0.7, and actual operating coefficients may be very much less due to cycling and other problems. Double-effect chillers, in which two generators in series are used, can have coefficients of performance in the range 1.0 to 1.5; these improvements are obtained at the expense of considerable complication of the machines and will probably require the use of collectors operating at temperatures beyond the range of flat-plate collectors.

In contrast to solar heating, there are two major additional factors to be considered in evaluating solar air conditioning. First, there are substantial additional items of cost for the air conditioner and its associated piping, controls, auxiliary energy supply, and so on. Second, in many climates there will be a substantial annual increment in the useful energy supplied from the collector, as it will not be oversized in the cooling season as it is for heating alone. The same methods of economic analysis that have been applied to other applications can be applied to cooling, and system sizing can be optimized. However, the factors that determine overall system performance (cycling, storage losses, etc., as noted in the CSU system development experiments) must be considered in the thermal performance calculations.




## 15.7 SOLAR DESICCANT COOLING


The second class of solar air conditioners is based on open-cycle dehumidification-humidification processes. These systems take in air from outside or from the building, dehumidify it with a solid or liquid desiccant, cool it by exchange of sensible heat, and then evaporatively cool it to the desired state. The desiccant is regenerated with solar energy. The components used include heat exchangers, heat and mass exchangers for dehumidification, and evaporative coolers. Many cycles have been studied; several of these are briefly noted in this section, and two are discussed in more detail in the following section.

Löf (1955) suggested solar operation of a system as shown in Figure 15.7.1. In this system, the drying agent is liquid triethylene glycol. The glycol is sprayed into an absorber where it picks up moisture from the building air. It is then pumped through a sensible heat exchanger to a stripping column where it is sprayed into a stream of solar-heated air. The high-temperature air removes water from the glycol, which then returns to the heat exchanger and absorber. Heat exchangers are provided to recover sensible heat, maximize the temperature in the stripper, and minimize the temperature in the absorber. Eliminators remove glycol spray from the air streams. This type of cycle, operated by steam, is marketed commercially and used in hospitals and other large installations. Solar operation has been studied by Lodwig et al. (1977), and a variation using the collector as the stripper is described by Collier (1979).


Dunkle (1965) showed a cycle designed for air conditioning in humid tropical or subtropical areas that is based on use of desiccant beds such as silica gel for drying air. The desiccants are regenerated by solar-heated air, and a pebble bed energy storage unit is included to allow operation during times of inadequate solar radiation. Rotary heat exchangers are used. Figure 15.7.2(a) shows a schematic of Dunkle's cycle, and



**Figure 15.7.1** Schematic of a triethylene glycol open-cycle air conditioning system. From Löf (1955).




(a)



(b)

**Figure 15.7.2** (a) Schematic of open-cycle solar air conditioning system using a rotary desiccant bed and heat exchangers. (b) The cycle on a psychrometric chart. From Dunkle (1965).



**Figure 15.7.3** LiCl-H<sub>2</sub>O open-cycle cooling system. From Baum et al. (1973).


Figure 15.7.2(b) shows the cycle on a psychrometric chart with the state numbers corresponding to conditions on the cycle schematic.

Baum et al. (1973) worked with a related system for solar cooling. Their cycle is shown schematically in Figure 15.7.3. The absorbing liquid is a solution of lithium chloride in water. Starting at the absorber (1), dilute LiCl solution is transferred by a pump (2) to a heat exchanger-distributor-header (3) and then to an open flat-plate collector (4) where water evaporates. Concentrated solution returns, via a heat exchanger (3) for recovery of sensible heat, to the absorber. Water is cooled in the evaporator (5), with water vapor from the evaporator going to the absorber. The chilled water from the evaporator is moved by a pump (6) to the air-to-water heat exchanger (7), which cools the building air (in this case, without direct contact with the absorbent solution). Means are provided to deaerate the solutions, recover sensible heat, and add makeup water. The absorber is cooled with a separate cooling coil.

## 15.8 VENTILATION AND RECIRCULATION DESICCANT CYCLES

In the 1980s there was considerable research on two related desiccant cycles that may have applications for operation with solar energy. The ventilation cycle is that used by Munters in the Munters Environmental Control (MEC) system; the other is the recirculation cycle.

The ventilation cycle (the MEC cycle) is shown in Figure 15.8.1(a) and is traced on the psychrometric chart of Figure 15.8.1(b), where the state points are numbered to correspond to the points on the process schematic. Ambient air is dried and heated by a dehumidifier from 1 to 2, regeneratively cooled by exhaust air from 2 to 3, evaporatively cooled from 3 to 4 (allowing control of both temperature and humidity), and introduced into the building. Exhaust air at state 5 moves in the countercurrent direction and is evaporatively cooled to 6, heated to 7 by the energy removed from the supply air in the regenerator, heated by solar or other source to 8, and then passed through the dehumidifier (desiccant) where it regenerates the desiccant.




**Figure 15.8.1** (a) Schematic of a solar-MEC system based on the ventilation cycle. (b) The solar-MEC cycle on a psychrometric chart. From Jurinak (1982).

The recirculation cycle is shown in Figure 15.8.2(a), and the corresponding psychrometric chart is in Figure 15.8.2(b). The same components are used, but building air is recirculated and ambient air is used only for regeneration. Both of the cycles use rotary dehumidifiers with solid desiccants and rotary heat exchangers.

The conditions shown in the figures are based on reasonable assumptions of the effectiveness of the various components. In operation, the ambient conditions change over time and the response to changing conditions must be estimated. For solar operation, energy would be supplied (e.g., by a water-to-air heat exchanger from water heated by flat-plate collectors) to heat the air from state 7 to state 8 in the ventilation cycle or state 3 to state 4 in the recirculation cycle. Nelson (1976), Nelson et al. (1978), Jurinak (1982), and Jurinak et al. (1984) have reported simulations of these systems. These studies have led to several generalizations about their solar operation.

Desiccant bed design is critical to solar operation if regeneration is to be accomplished at the temperatures of 60 to 80°C that can be produced by flat-plate collectors. High heat and mass transfer coefficients in the bed and low diffusion resistance in the desiccant particles are needed. The objective is to minimize the temperature difference driving forces needed to accomplish regeneration.



**Figure 15.8.2** (a) Schematic of the recirculation cycle desiccant air conditioner. (b) The recirculation cycle on a psychrometric chart. From Jurinak (1982).

There are new degrees of freedom in the control of desiccant systems. Optimum meeting of variable latent and sensible cooling loads can be accomplished through control of airflow rates, dehumidifier wheel rotation rates, regeneration temperatures, and other process variables. The systems operate most efficiently at the highest supply temperature and humidity (states 4 of the ventilation cycle and 5 of the recirculation cycle) that allow the total load to be met.

These cycles, and others related to them, are potentially of interest for solar operation. The theory of their operation and how they can be integrated with solar energy supplies is the subject of research. Economic evaluations cannot yet be made.

## 15.9 SOLAR-MECHANICAL COOLING

The third type of solar cooling system that has received some attention couples a solar-powered Rankine cycle engine with a more or less conventional air conditioning system. The design of conventional air conditioning systems is well established; the problems


associated with solar operation are basically those associated with generating mechanical energy from solar energy and adaptation of air conditioning equipment for part-load operation.

Studies of Rankine cycle solar air conditioning systems have concentrated on theoretical analysis (e.g., Teagan and Sargent, 1973; Beekman, 1975; Olson, 1977). An experimental system in a mobile laboratory (Barber, 1974; Prigmore and Barber, 1974) was in operation for several years, but no long-term operating data are available. The National Security and Resources Study Center at Los Alamos National Laboratory was partially cooled by a 77-ton solar vapor-compression system. Biancardi and Meader (1976), Eckard and Bond (1976), and others describe development studies of engine-compressor systems.


The problems associated with solar Rankine air conditioning systems are substantial. Generation of mechanical power from solar radiation has not been shown to be economical on the scale of air conditioning operations, and it is difficult to envision a household-scale system that will convert solar to mechanical energy at less expense than conventional systems.

A simple Rankine cycle cooling system is shown in Figure 15.9.1(a). Energy from the storage tank is transferred through a heat exchanger to a heat engine. The heat engine exchanges energy with the surroundings and produces work. As shown in Figure 15.9.1(b), the efficiency of the solar collector decreases as the operating temperature increases while the efficiency of the heat engine will increase as the operating temperature increases. Figure 15.9.1(c) shows overall system efficiency for converting solar energy to mechanical work and indicates an optimum operating temperature exists for steady-state operation.

A schematic diagram of a Rankine heat engine is shown in Figure 15.9.2(a). The corresponding temperature-entropy diagram is shown in Figure 15.9.2(b). This cycle is somewhat different from the conventional power plant cycle using water as a working



**Figure 15.9.1** (a) Schematic of a solar-operated Rankine cycle cooler. (b) Collector and power cycle efficiencies as a function of operating temperature. (c) Overall system efficiency.



**Figure 15.9.2** (a) Rankine power cycle with regeneration. (b) Temperature-entropy diagram of Rankine power cycle.

fluid. In a conventional power plant cycle superheating and extraction are used to increase the cycle efficiency and to prevent moisture from eroding the turbine blades. In a solar energy system superheating is not desirable due to the increased temperature requirements of the collector, and extraction is not economical in small systems. To avoid moisture in the turbine, a fluid such as R 114 must be selected which has a positive slope to the saturated vapor line on a temperature-entropy diagram. With R 114, the outlet temperature of the turbine is significantly higher than the temperature of condensation, so a regenerator can be used to preheat the fluid leaving the condenser before it enters the boiler (Olson, 1977).

The steady-state thermodynamic analysis of such a cycle is not difficult. However, the prediction of component performance at off-design conditions and the matching of components into a complete system so that the overall performance is optimized are not easy. For example, as the storage tank temperature changes through the day, the temperature to the boiler will change. This will result in variable energy being added to the working fluid. To ensure that fluid does not enter the turbine from the two-phase region, either auxiliary energy must be added at the boiler or the circulation rate of the fluid must be reduced. Both of these options result in design problems.

The expander that drives the air conditioner can be either a turbine (which will require a gearbox speed reduction unit) or a piston engine. It is not now possible to determine which system is best for solar operation. Some designs use a single working fluid for both the expander and the air conditioner compressor.

When a Rankine heat engine is coupled with a constant-speed air conditioner, the output of the engine will seldom match the required input to the air conditioner. Consequently, a control system is needed to ensure matching of the engine and air conditioner. When the engine output is greater than needed, matching can be accomplished by throttling the energy supply to the engine, which means that the engine will work at an off-design

condition and available energy will be wasted. Or excess energy from the engine can be used to produce electrical energy for other purposes. When the engine output is less than that required by the air conditioner, auxiliary energy must be supplied. This auxiliary can be supplied in the form of heat to the Rankine cycle or in the form of mechanical work to drive the air conditioner. The system can be designed to operate at variable speed. However, the operation of the air conditioner will be off-design with subsequent reduction of output.

As with all solar processes, steady-state conditions cannot be used to find optimum designs. It is necessary to evaluate design options based on estimates of integrated yearly performance. The effects of design variables are not intuitively obvious. The design and control of Rankine engine–vapor compression cooling has been studied by Olson (1977), who found that for a given location and collector size there are optimum sizes of both the engine and the storage tank which maximize the annual solar contribution to meeting the cooling load.

Two other routes to solar-operated coolers are to be noted. There are now in existence solar power plants<sup>1</sup> that feed electrical energy into utility grids to help meet peak power demands; much of these peak demands are for air conditioning. In a more direct application, electrical energy from photovoltaic generators is used to operate mechanical refrigerators for storage of medicines and other valuable items.<sup>2</sup>

## 15.10 SOLAR-RELATED AIR CONDITIONING

Some components of systems installed for the purpose of heating a building can be used to cool the building, but without the direct use of solar energy. In this section we note three examples: (1) night cold storage system, (2) sky radiation systems, and (3) heat pump systems. These are referred to as “solar-related” methods for cooling, and the economics of the processes are interrelated with the economics of solar heating.

**Night chilling of pebble beds** to store “cold” for use the following day can provide some cooling capacity. In climates where the night temperature and humidity are low, pebble bed storage units of solar air heating systems can be cooled by passing outside air through an evaporative cooler, through the pebble bed, and to exhaust. This system was used on part of a laboratory building in Melbourne, Australia (Close et al., 1968). During the air conditioning season the rock pile storage unit was cooled with evaporatively cooled air at night when, in that climate, the ambient wet-bulb temperatures were at most 15 to 20°C.

Essentially the same system was used on CSU House II (Karaki et al., 1977). During the night, airflow was through the evaporative cooler, down through the pebble bed, and to exhaust. When cooling the building, flow was from the rooms, up through the pebble bed, and returned to the rooms. The pebble bed stratified, as it does in the heating mode, and sample profiles are shown in Figure 15.10.1. Karaki et al. found that in the climate of Fort Collins there was very little charging of the bed on the warmest summer nights, and the bed was underdesigned for cooling purposes during the height of the cooling season. Early

---

<sup>1</sup>See Sections 17.3 and 18.3.

<sup>2</sup>See Chapter 23.





season. From Karaki et al. (1977).

at 7.5°C from the evaporative cooler.

**Radiation to the night sky** has been used to dissipate energy in several experimental systems. The nearly horizontal radiators are also used as collectors for solar heating. Bliss (1964), Yanagimachi (1958, 1964), Hay (1973), and Hay and Yellott (1970) describe systems that use nocturnal radiation to chill water for subsequent cooling. Bliss found that on a monthly average the uncovered collectors on his laboratory at Tucson could dissipate at most approximately  $4.1 \text{ MJ/m}^2$  per night. For the  $93\text{-m}^2$  collector-radiator on the Tucson laboratory, the monthly average cooling was equivalent to about  $3.5 \text{ kW}$  of continuous cooling.

Two problem areas are encountered in the design and operation of systems of this type. First, the characteristics that make a good collector are not those that make a good radiator. Neither covers nor selective surfaces can be used (unless movable covers are provided, as by Hay), as either one effectively limits nocturnal radiation to very low levels. Thus collectors are limited to the kinds that can be used at temperatures close to ambient, for example, collectors that could be used as sources for series heat pump systems. The second limitation is a climatic one. These systems could only be used where night sky temperatures are low, that is, where atmospheric moisture and dust content are low. Also, it is necessary that the nighttime wind speeds are low.

**Heat pumps** used as part of solar heating systems can also be used for cooling. If the cost of the heat pump can be justified by its use for air conditioning, the result will be to make the economics of the solar energy–heat pump systems described in Section 13.6 more favorable.

## 15.11 PASSIVE COOLING

Passive cooling depends on transfer of heat by natural means from a building to environmental sinks, including clear skies, the atmosphere, the ground, or water. Mechanisms of transport include radiation to clear skies, naturally occurring wind, airflow induced by temperature differences, conduction to ground, and conduction or convection to bodies of water. The options available are dependent on climate type, that is, whether arid or humid. Many of these topics are discussed in the *Passive Cooling Handbook* (1980), in all of the recent proceedings of the passive solar conferences of the American Solar Energy Society, the International Solar Energy Society, and elsewhere.

As with any cooling processes, the first approach is to minimize the cooling loads. In residential applications, major heat gains will often be solar gains through windows; these can be minimized through shading and by use of glass with high transmittance for the visible spectrum to provide daylighting and low transmittance in the infrared part of the solar spectrum. Shading can be provided by architectural features such as overhangs and wingwalls or in many cases by proper placement of deciduous trees. Double roofs, with space between for air circulation, can keep the temperature of the ceilings of living spaces at reduced levels. Building temperatures may also be stabilized by provision of thermal capacitance if there are large diurnal ambient temperature variations.

Ventilation of building interiors is effective in cooling if ambient temperatures are moderate. Techniques for maximizing natural ventilation range from placement of windows and doors to take maximum advantage of prevailing winds to use of appropriate vents in attic and roof spaces to induce thermal circulation of air upward through a building. Gaps between wall and glazing in collector-storage walls can be vented to the outside during cooling seasons.

Earth tempering is a term applied to use of the ground as a heat sink. Ground temperatures below the surface normally do not vary much and are low enough that conduction to the ground can be a means of removal of energy from a building interior. Thermal coupling to ground can also provide some thermal capacitance.

Other methods of cooling and cooling load reduction can be considered, including hybrid methods that are in part operated with mechanical energy and in part by passive means. Control of humidity can be an important question for passively heated buildings. Desiccant coolers and systems with mechanical dehumidification can be considered hybrid systems and are discussed in this context in the *Passive Cooling Handbook* (1980).

## REFERENCES

- Allen, R. W., R. H. Morse, et al., Reports on project NSF/RANN/SE/GI 39117, Mechanical Engineering Department, University of Maryland, (1973–1976). “Optimization Study of Solar Absorption Air Conditioning Systems.”
- ASHRAE *Handbook—Fundamentals*, American Society of Heating, Refrigeration, and Air Conditioning Engineers, Atlanta, GA (2005).

- Barber, R. E., report from Barber-Nichols to Honeywell (1974). "Final Report on Rankine Cycle Powered Air Conditioning System."
- Baum, V. A., A. Kakabaef, A. Khandurdyev, O. Klychiaeva, and A. Rakhmanov, paper presented at the International Solar Energy Congress, Paris (1973). "Utilization de L'énergie Solair dans Les Conditions Particulieres des Regions a Climate Torrride et Aride Pour la Climatisation En Ete."
- Beekman, D. M., M.S. Thesis, Mechanical Engineering, University of Wisconsin-Madison (1975). "The Modeling of a Rankine Cycle Engine for Use in a Residential Solar Energy Cooling System."
- Biancardi, R. and M. Meader, in *Proceedings of the Second Workshop on the Use of Solar Energy for the Cooling of Buildings* (F. deWinter and J. W. deWinter, eds.), p. 137 (1976). "Demonstration of a 3 ton Rankine Cycle Powered Air Conditioner." Available from NTIS.
- Blinn, J. C., M.S. Thesis, Chemical Engineering, University of Wisconsin-Madison (1979). "Simulation of Solar Absorption Air Conditioning."
- Bliss, R. W., *Proc. UN Conf. New Sources of Energy*, **5**, 148 (1964). "The Performance of an Experimental System Using Solar Energy for Heating, and Night Radiation for Cooling a Building."
- Blytas, G. C. and F. Daniels, *J. Am. Chem. Soc.*, **84**, 1075 (1962). "Concentrated Solutions of NaSCN in Liquid Ammonia: Solubility, Density, Vapor Pressure, Viscosity, Thermal Conductance, Heat of Solution, and Heat Capacity."
- Butz, L. W., M.S. Thesis, Mechanical Engineering, University of Wisconsin-Madison (1973). "Use of Solar Energy for Residential Heating and Cooling."
- Butz, L. W., W. A. Beckman, and J. A. Duffie, *Solar Energy*, **16**, 129 (1974). "Simulation of a Solar Heating and Cooling System."
- Chinnappa, J. C. V., *Solar Energy*, **5**, 1 (1961). "Experimental Study of the Intermittent Vapour Absorption Refrigeration Cycle Employing the Refrigerant-Absorbent System of Ammonia Water and Ammonia Lithium Nitrate."
- Chinnappa, J. C. V., *Solar Energy*, **6**, 143, (1962). "Performance of an Intermittent Refrigerator Operated by a Flat-Plate Collector."
- Chinnappa, J. C. V., paper presented at the International Solar Energy Society Congress, Paris (1973). "Computed Year-Round Performance of Solar-Operated Multi-State Vapour Absorption Air Conditioners at Georgetown, Guyana, and Colombo, Ceylon."
- Chung, R., J. A. Duffie, and G. O. G. Löf, *Mech. Eng.*, **85**, 31 (1963). "A Study of a Solar Air Conditioner."
- Close, D. J., R. V. Dunkle, and K. A. Robeson, *Mech. Chem. Eng. Trans. Inst. Eng. Australia*, **MC4**, 45 (1968). "Design and Performance of a Thermal Storage Air Conditioning System."
- Collier, R. K., *Solar Energy*, **23**, 357 (1979). "The Analysis and Simulation of an Open Cycle Absorption Refrigeration System."
- Duffie, J. A. and N. R. Sheridan, *Mech. Chem. Eng. Trans. Inst. Eng. Australia*, **MC1**, 79 (1965). "Lithium Bromide-Water Refrigerators for Solar-Operation."
- Dunkle, R. V., *Mech. Chem. Eng. Trans. Inst. Eng. Australia*, **MC1**, 73 (1965). "A Method of Solar Air Conditioning."
- Eckard, S. E. and J. A. Bond, in *Proceedings of the Workshop on the Use of Solar Energy for the Cooling of Buildings* (F. deWinter and J. W. deWinter, eds.), p. 110 (1976). "Performance Characteristics of a 3-Ton Rankine Powered Vapor-Compression air Conditioner." Available from NTIS.
- Hay, H. R., *Mech. Eng.*, **95** (11), 18 (1973). "Energy Technology and Solararchitecture."
- Hay, H. R. and J. I. Yellott, *Mech. Eng.*, **92** (1), 19 (1970). "Naturally Air Conditioned Building."
- Jurinak, J. J., Ph.D. Thesis, Mechanical Engineering, University of Wisconsin-Madison (1982). "Open Cycle Solid Desiccant Cooling—Component Models and System Simulations."

- Jurinak, J. J., J. W. Mitchell, and W. A. Beckman, *Trans. ASME J. Solar Energy Eng.*, **106**, 252 (1984). "Open-Cycle Desiccant Air Conditioning as an Alternative to Vapor Compression Cooling in Residential Applications."
- Karaki, S., P. R. Armstrong, and T. M. Bechtel, Colorado State University Report COO-2868-3 to U.S. Department of Energy (1977). "Evaluation of a Residential Solar Air Heating and Nocturnal Cooling System."
- Karaki, S., T. E. Brisbane, and G. O. G. Löf, Colorado State University Report SAN 11927-15 to U.S. Department of Energy (1984). "Performance of the Solar Heating and Cooling System for CSU House III—Summer Season 1983 and Winter Season 1983–84."
- Klein, S. A. and D. T. Reindl, *ASHRAE J.*, **47** (9) p. 526 (2005). "How Can Heat Generate Refrigeration? A Review of Solar Refrigeration Alternatives."
- Lodwig, E., D. A. Wilkie, and J. Bressman, *Proc. Am. Solar Energy Soc. Meeting*, Orlando, **1**, 7–1 (1977). "A Solar Powered Desiccant Air Conditioning System."
- Löf, G.O.G., in *Solar Energy Research* (F. Daniels and J. A. Duffie, eds.), University of Wisconsin Press, Madison, p. 33 (1955). "House Heating and Cooling with Solar Energy."
- Mitchell, J. W., in *Proceedings of the 1986 Annual Meeting of the American Solar Energy Society*, Boulder, CO, p. 63 (1986). "State of the Art of Active Solar Cooling."
- Nelson, J. S., M.S. Thesis, Mechanical Engineering, University of Wisconsin-Madison (1976). "An Investigation of Solar Powered Open-Cycle Air Conditioners."
- Nelson, J. S., W. A. Beckman, J. W. Mitchell, and D. J. Close, *Solar Energy*, **21**, 273 (1978). "Simulations of the Performance of Open-Cycle Desiccant Systems Using Solar Energy."
- Olson, T. J., M.S. Thesis, Mechanical Engineering, University of Wisconsin-Madison (1977). "Solar Source Rankine Cycle Engine for Use in Residential Cooling."
- Oonk, R. L., W. A. Beckman, and J. A. Duffie, *Solar Energy*, **17**, 21 (1975). "Modeling of the CSU Heating/Cooling System."
- Passive Cooling Handbook*, prepared for U.S. Department of Energy (1980).
- Prigmore, D. R. and R. E. Barber, paper presented at the Ninth IECEC Conference (1974). "A Prototype Solar Powered, Rankine Cycle System Providing Residential Air Conditioning and Electricity."
- Sargent, S. L. and W. A. Beckman, *Solar Energy*, **12**, 137 (1968). "Theoretical Performance of an Ammonia-Sodium Thiocyanate Intermittent Absorption Refrigeration Cycle."
- Sheridan, N. R., paper presented at the International Solar Energy Society Conference, Melbourne (1970). "Performance of the Brisbane Solar House."
- Swartman, R. K. and C. Swaminathan, paper presented at the International Solar Energy Society Conference, Melbourne (1970). "Further Studies on Solar-Powered Intermittent Absorption Refrigeration."
- Teagan, W. P. and S. L. Sargent, Paper EH-94-1 presented at the Solar Energy Society Paris Conference (1973). "A Solar Powered Combined Heating-Cooling System with the Air Conditioning Unit Driven by an Organic Rankine Cycle Engine."
- Ward, D. S. and G. O. G. Löf, *Solar Energy*, **17**, 13 (1975). "Design and Construction of a Residential Solar Heating and Cooling System."
- Whitlow, E. P. and J. S. Swearingen, paper presented at the Southern Texas American Institute of Chemical Engineers Meeting (1959). "An Improved Absorption-Refrigeration Cycle."
- Williams, D. A., R. Chung, G. O. G. Löf, D. A. Fester, and J. A. Duffie, *Refrig. Eng.*, **66**, 33 (Nov. 1958). "Cooling Systems Based on Solar Regeneration."
- Yanagimachi, M., *Trans. Conf. Use of Solar Energy*, **3**, 32 (1958). "How to Combine: Solar Energy, Nocturnal Radiational Cooling, Radiant Panel System of Heating and Cooling, and Heat Pump to Make a Complete Year-Round Air Conditioning System."
- Yanagimachi, M., *Proc. UN Conf. New Sources of Energy*, **5**, 233 (1964). "Report on Two and a Half Years' Experimental Living in Yanagimachi Solar House II."

## Solar Industrial Process Heat

Very large amounts of energy are used for low-temperature process heat in industry, for such diverse applications as drying of lumber or food, cleaning in food processing, extraction operations in metallurgical or chemical processing, cooking, curing of masonry products, paint drying, and many others. Temperatures for these applications can range from near ambient to those corresponding to low-pressure steam, and energy can be provided from flat-plate collectors or concentrating collectors of low concentration ratios.

The principles of operation of components and systems outlined in earlier chapters apply directly to industrial process heat applications. The unique features of these applications lie in the scale on which they are used, system configurations and controls needed to meet industrial requirements, and the integration of the solar energy supply system with the auxiliary energy source and the industrial process. Process simulations similar to those outlined in Chapter 10 and chapters on heating and cooling are useful tools in the study of industrial applications. The design methods outlined in Chapters 20 (if energy is to be delivered at about 20°C) and 21 (for systems delivering energy at temperatures other than 20°C) are applicable to many solar industrial process-heating operations. Chapter 17 treats solar applications for power generation and Chapter 18 is on solar ponds and evaporative processes; these are subjects closely related to industrial process applications.

Other than traditional crop drying and solar evaporation, which have been practiced over centuries, most solar applications for industrial process heat have been on a relatively small scale and are experimental in nature. A few large systems are in use. In this chapter we outline some general design and economic considerations and then briefly describe several examples of industrial applications to illustrate the potential utility of solar energy to industry and the kinds of special problems that industrial applications can present. Experiments of the 1970s are described in the *Proceedings of the Solar Industrial Process Heat Symposium* (1977) and *Proceedings of the Solar Industrial Process Heat Conference* (1978).

### 16.1 INTEGRATION WITH INDUSTRIAL PROCESSES

Two primary questions to be considered in a possible industrial process application concern the use to which the energy is to be put and the temperature at which it is to be delivered. If a process requires hot air for direct drying, an air heating system is probably the solar energy system best matched to the need. If steam is needed to operate an autoclave or indirect dryer, the solar energy system must be designed to produce steam and concentrating collectors will probably be required. If hot water is needed for cleaning in food processing,

the solar energy system will be a liquid heater. An important factor in determination of the best system for a particular use is the temperature of the fluid to the collector. The generalizations of building heating applications (e.g., that return air to collectors in air systems is usually at or near room temperatures) do not necessarily carry over to industrial processes, as the system configurations and energy uses may be quite different.

The energy may be needed at particular temperature or over a range of temperatures. If low-pressure steam is condensed in an indirect dryer, the condensate will probably be recirculated, and the solar process system will be called on to deliver essentially all of the energy at a constant temperature level. A once-through cleaning process may call for freshwater to be heated from supply temperature to some useful minimum level, so energy can be added to the water over a range of temperatures. A system in which a working fluid is recirculated back to the tank will probably operate over an intermediate range of temperatures.

The temperature at which energy is used in many industrial processes has not been limited by the characteristics of conventional energy supplies. The partial replacement of conventional sources by solar energy in retrofit applications is usually limited to operations in the same temperature ranges as that of the sources replaced. In new applications, since solar collectors operate more efficiently at lower temperatures, the industrial process itself should be examined to see if the temperature of energy delivery can be optimized.

Storage would usually be used in industrial processes, except where the maximum rate at which the solar energy system can deliver energy is not appreciably larger than the rate at which the process uses energy. In these cases the annual fraction of the energy needs delivered by solar energy will be small if the process operates in other than daylight hours. If storage is used, the energy balances and rate equations of Chapter 8 can be used to describe the storage subsystem.

The investments in industrial processes are generally large, and the transient and intermittent characteristics of solar energy supply are so unique that the study of options in solar industrial applications can be done by simulation methods at costs that are very small compared to the investments.

## 16.2 MECHANICAL DESIGN CONSIDERATIONS

Many industrial processes use large amounts of energy in small spaces. If solar is to be considered for these applications, the location of collectors can be a problem. It may be necessary to locate collector arrays on adjacent buildings or grounds, resulting in long runs of pipe or duct. Collector area may be limited by building roof area and orientation. Existing buildings are generally not designed or oriented to accommodate arrays of collectors, and in many cases structures to support collector arrays must be added to the existing structures. New buildings can be readily designed, often at little or no incremental cost, to allow for collector mounting and access.

Interfacing with conventional energy supplies must be done in a way that is compatible with the process. If air to dryers is to be preheated, it must be possible to get the solar-preheated air into the dryer air supply. In food processing, sanitation requirements of the plant must be met. It is not possible to generalize on these matters; the engineering of the solar energy process and the industrial process must be mutually compatible. In most of the examples in the following sections, solar heating was retrofitted, it supplied a relatively

small part of the plant loads, and in varying degrees the range of problems noted here have been encountered.

### 16.3 ECONOMICS OF INDUSTRIAL PROCESS HEAT

Economic analyses of industrial processes are the same as outlined in Chapter 11, but in contrast to non-income-producing applications, deduction of fuel costs as a business expense, investment tax credits, and depreciation must be taken into account.<sup>1</sup> And industry usually requires a higher return on investment (i.e., shorter payback time) than do individuals.

The investments in solar industrial process systems are as outlined in Section 11.1. For a retrofit system, mounting a collector array may be a major item of investment; in some experimental installations the cost of providing mountings exceeded the cost of the collectors. In new construction, provision for collector mounting may mean only nominal changes in the design of the structure. The operating costs include the same kinds of items as for other solar applications, such as parasitic power, maintenance, insurance, and real estate taxes.

The generalization made for solar heating that collector area can be considered as the primary design variable does not necessarily extend to industrial process applications. There is no general relationship between time dependence of loads and energy supply, and both collector area and storage capacity (and possibly others) may be important design parameters. In general, the design of a solar industrial process will have to be based on a study of the appropriate ranges of variables of all the important parameters, done in view of the characteristics of the energy-using process.

As high reliability is needed for industrial applications, solar will normally be combined with a conventional energy supply. The useful energy produced by the solar energy system serves to reduce the fuel consumption of the conventional (auxiliary) energy supply. Industry buys fuels in quantities that are large compared to homeowners, and the price of that fuel is generally less than is paid by the small buyer. In addition, funds spent for purchase of fuel are business expenses and therefore deductible from corporate income taxes. With a basic corporate income tax rate of 50%, the effective cost of energy would be halved. As with nonindustrial applications, it is difficult to build solar heating systems that can deliver energy at a sufficiently low cost to compete with inexpensive fuels. Differences in taxation of fuels, investment tax credits, and depreciation of equipment can make very substantial difference in the economic viability of these processes and are matters of legislation.

Miscellaneous expenses for parasitic power, insurance, and maintenance are also business expenses and therefore tax deductible. Investment tax credits effectively reduce first costs and thus encourage investments in equipment. Equipment costs can be depreciated, which has the effect of decreasing corporate taxes. Depreciation can be by straight line, declining balance, sum of digits, or other methods. Most industries will have established methods for depreciation and discount rates.

Seasonal industrial processes, which can only utilize the output of solar heating systems over part of the year, will show less favorable economics than will processes that

---

<sup>1</sup>This section is written with U.S. tax laws in mind; other treatments will be necessary where tax laws are substantially different from those of the United States.



operate all year. Food processing applications in temperate climates provide examples. This disadvantage can, in part, be minimized by collector orientation to maximize output over the period of use. It may also be possible to develop other off-season uses for energy, such as building heating. One of the examples in a following section shows such a combination of uses.

## 16.4 OPEN-CIRCUIT AIR HEATING APPLICATIONS

Heated outside air is used in many industrial applications where recirculation of air is not practical because of contaminants. Examples are drying, paint spraying, and supplying fresh air to hospitals. Heating of ambient air is an ideal operation for a collector, as it operates very close to ambient temperature. In this case, Equation 6.7.6 becomes simply

$$Q_u = A_c F_R S \quad (16.4.1)$$

where  $F_R$  may be essentially fixed if flow rate is fixed or it may vary if, for example, system controls are arranged to provide a fixed outlet temperature by adjusting the flow rate as solar radiation and inlet (ambient) temperature vary.

Equation 16.4.1 is evaluated for the hours of operation of the solar system. All of the methods of Chapters 2, 4, and 5 in determining  $S$  and Chapter 6 in calculating  $F_R U_L$ ,  $F_R(\tau\alpha)_n$ , and incidence angle effects apply directly to these calculations. The critical radiation level of a collector heating ambient air is zero and utilizability is unity. For a full month's operation of such a system, the average daily useful gain can be approximated by

$$\overline{Q}_u = A_c F_R (\overline{\tau\alpha})_n \frac{(\overline{\tau\alpha})}{(\overline{\tau\alpha})_n} \overline{H}_T \quad (16.4.2)$$

where  $(\overline{\tau\alpha})/(\overline{\tau\alpha})_n$  can be estimated by the methods of Section 5.10.<sup>2</sup> This calculation of monthly gains will work for systems that operate whenever the incident radiation is high enough to justify operation of the fan.

Two systems in which heating of ambient air is carried out are described here. The first is an experimental application to food drying, entailing several unique problems illustrative of special considerations that must be taken into account by a system designer. The second is a space-heating system in which large quantities of outside air must be supplied to a bus maintenance facility in order to meet indoor air quality requirements.

An experimental application of air heating to drying of soybeans at the Gold Kist plant at Decatur, Alabama, was one of a series of demonstrations of solar industrial process heating sponsored in part by the U.S. Department of Energy. The system, described by Guinn (1978), consisted of 1200 m<sup>2</sup> (672 modules) of air heating collectors supplying warmed air to the dryer. The air was mixed with additional ambient air, heated by oil to the desired temperature, and used in the drying operation. Since the maximum output from the collectors was less than the energy needs of the dryer, all collected energy could be used (during the drying season) and no storage was provided. Figure 16.4.1 is a schematic of the process, and Figure 16.4.2 shows the collector array.

<sup>2</sup>Recall that the bar over the transmittance-absorptance product implies both a time-weighted and radiation-weighted average.






Figure 16.4.1 Layout of collector array and soybean drying installation. Adapted from Guinn (1978).




**Figure 16.4.2** The 1200-m<sup>2</sup> air heating collector array at the Gold Kist soybean plant at Decatur, AL. Courtesy of Solaron Co.

In this system, the filter and blower were on the upstream side of the collectors, to put the collectors under positive pressure and avoid ingestion of dusty air into the system where it might become an explosive mixture. The size of the collector array was essentially fixed by the dimensions of a parking lot over which the array was mounted. The collector slope was 15°, chosen as a compromise between performance and greater structural costs associated with larger slopes. The atmosphere in the plant area was dusty, and keeping the collectors reasonably clean was a significant operational problem.

Systems of this type, which are designed for small contributions by solar in relation to the total loads, can be operated without energy storage. No energy will be dumped as long as the maximum output of the collector is less than the energy needs of the application at the time the collector maximum occurs. It may be that the time of collector operation would be determined by the process itself (e.g., times when paint spraying is going on or when materials are in the dryer ready to be dried), and under these circumstances storage may be needed.

The second once-through air system is on a bus maintenance facility in Denver, Colorado, in which diesel-powered buses are stored, serviced, and maintained. Large quantities of fresh air are required in the facility to assure adequate air quality and remove exhaust fumes. The facility serves dual purposes, as a storage facility and as a maintenance base. The minimum allowable temperature in the storage area is 7 to 10°C, and the minimum in the maintenance area is 13 to 19°C. There is also an office area that is maintained at 21°C or above. The facility requires 12 to 15 air changes per hour, and the bulk of the heating load is heating the ventilation air. The building floor area is 32,500 m<sup>2</sup>. A view of the roof of the building and the collector system is shown in Figure 16.4.3.

There are five independent solar heating systems, each heating ambient air for supply to the building. One of them also supplies service hot water through an air-to-water heat exchanger in the duct from the collector to the building; this heated water is used for washing buses. Total collector area is 4300 m<sup>2</sup> of flat-plate air heaters of the type shown in Figure 6.14.1(b). They have one cover and a flat-black absorbing surface and are sloped 55° to the south. The performance of two of these systems has been measured by Marlatt




**Figure 16.4.3** View of the roof-mounted collectors on the Denver bus maintenance facility. Photo courtesy of Colorado State University.

and Smith (1988). A schematic of the systems, including provision of heat with steam, is shown in Figure 16.4.4.

There are significant differences between these systems and the “standard” air systems noted in Chapter 13. They are once-through systems, and there is no air recirculation either from the building or from the storage units. Air to the stores is exhausted to the outside regardless of its temperature, and outside air is heated in the storage units when the controls call for this mode of heating.

There are three basic modes of operation of these systems. The first is direct delivery of air from the collectors to the supply air units and thence to the building. Excess



**Figure 16.4.4** Schematic of the solar and auxiliary (steam) heating systems on the Denver RTD facility. From Wirsum (1988).

energy from the collectors is diverted to storage. In the second mode, outside air is drawn through the storage units to the supply air units and the building. In either of these two modes, auxiliary heat is supplied by steam coils in the supply air units. The third mode is the summer ventilation of the collector arrays. Wirsum (1988) has made a detailed simulation study of the operation of this system, its controls, modeling of the collectors, the utility of storage in this system in the Denver climate, and the factors that limit system performance.

This application represents an ideal one for air heaters. Performance of the collectors is as good as it can be expected to be. Solar contribution is limited primarily by the area of the collector that can be readily accommodated on the roof of the building; the annual solar contribution is estimated to be 20% of the total heating load.


## 16.5 RECIRCULATING AIR SYSTEM APPLICATIONS

Indirect drying, with solar-heated air supplied to a drying chamber, has been applied to a variety of materials, including foods, crops, and lumber. In most such operations, adequate control of temperature and humidity can lead to improved product quality by controlling the rate of drying; this is usually accomplished by recycling to the collectors part of the air that has passed through the dryer.


Solar drying of lumber, to reduce its moisture content from that of the green wood from the trees to levels acceptable for use in building and manufacturing, has been the subject of several experiments (e.g., Read et al., 1974; Duffie and Close, 1978). Based on experiments at the U.S. Forest Products Laboratory (Tschernitz and Simpson, 1979; Simpson and Tschernitz, 1985), a production dryer has been constructed at a furniture manufacturing plant in Sri Lanka and is in routine use processing rubberwood for use in making furniture and laminated beams. The performance of the kiln and its energy supplies has been described by Simpson and Tschernitz (1989).

A schematic of the Sri Lanka dryer is shown in Figure 16.5.1. The major components of the system, designed for use at low latitudes, are a flat-plate collector built essentially horizontally on the ground, the kiln, an auxiliary waste wood burner, and controls, dampers, blowers, and so on. The kiln is designed to have a capacity of  $14 \text{ m}^3$  of 25-mm-thick boards with 19-mm sticks (spacers to allow air circulation). Four collectors are used; they have a total area of  $132 \text{ m}^2$  and are sloped at about  $0.5^\circ$  to allow rainwater runoff. A cross section of the collectors is shown in Figure 16.5.2. A single glass cover is used, with air circulating between the cover and a bed of charcoal that absorbs radiation and provides both extended heat transfer surface and insulation to minimize energy losses to the ground. The collectors operate at negative pressure so that leaks are into the system. They are fed with a mixture of recycled air from the dryer and ambient air.

The kiln is of concrete block construction with inside dimensions  $3.0 \times 10.4 \times 3.3 \text{ m}$ . The roof is arranged to serve as a preheater for air entering the collectors. Automatic controls on the dryer are arranged to control the temperature and relative humidity of the drying air in acceptable ranges. Airflow through the collector is modulated on and off depending on whether the collector temperature is above a predetermined setpoint, which depends on the stage of dryness of the lumber. Four fans are available to move air through the dryer, with four used in early stages of drying and two in later stages when drying is slower and air requirements are less.




**Figure 16.5.1** Schematic of a section of the Sri Lanka solar lumber dryer. (A) Drying chamber. (B) Collectors. (C) Blower to induce airflow through the collectors. (D) Hot-air discharge to internal fans. (E) Internal fans. (G) Disk humidifier. (H) Damper motor for collector airflow. (J) Fresh air intake. (K) Exhaust fan. Adapted from Simpson and Tschernitz (1985).



**Figure 16.5.2** Cross section of part of the collectors of the Sri Lanka lumber dryer. The single glazing layer is sealed to the concrete frames with silicone sealant. Adapted from Simpson and Tschernitz (1985).

The dryer has been in use since 1984. Its performance has been measured over two periods, one during the monsoon (wet) season and one during a period of clearer skies. In a two-week drying operation on a load of lumber in the wet season, the solar contribution to the total energy requirements of the process was 18%. During this period the solar radiation on the horizontal surface averaged  $7.57 \text{ MJ/m}^2$ , the dryer efficiency was 33%, and the moisture content of the wood was reduced from 73 to 18% (dry basis). During



**Figure 16.5.3** Cross section of an experimental solar lumber dryer at Thunder Bay, Ontario (latitude  $48^{\circ}$  N). From Yang (1980).

the nine-day drying operation on a load of lumber during better weather, the average daily radiation on the collectors averaged  $14.7 \text{ MJ/m}^2$ , the collectors supplied about 34% of the energy required, and the dryer efficiency was estimated to be 51%. The maximum estimated solar contributions in this dryer, in periods of minimum clouds, are estimated at 50%, and collector efficiencies are estimated at 35 to 40%. Air temperature rises through the collector are a maximum of about  $30^{\circ}\text{C}$  in the midday hours of clear days. Maximum temperatures in the dryer were about  $35^{\circ}\text{C}$  early in the drying cycles to  $50^{\circ}\text{C}$  late in the cycles. Drying cycles are 7 to 14 days in length.

A solar kiln design for use at high latitudes and its operation in Ontario for drying jack pine studs is described by Yang (1980). Figure 16.5.3 shows a cross section of this dryer. Drying cycles in the summer are about 12 days and in the winter about 100 days, compared to air drying cycles of about 240 days. The quality of the dried lumber was better than that for air drying.


A detailed review of indirect solar wood drying has been prepared by Steinmann (1989), who has made detailed measurements and simulations of drying lumber in an experimental kiln that is similar in general design to that of Figure 16.5.3.

## 16.6 ONCE-THROUGH INDUSTRIAL WATER HEATING

Large quantities of water are used for cleaning in the food processing industries, and recycling of used water is not practical because of contaminants picked up by the water in the cleaning processes. These processes involve heating of water from mains supply temperature to the desired temperature level for the process. As with other systems, if the solar collector output is always smaller than the loads on a process, the solar heating operation can be carried out without storage, but solar contributions relative to total loads will be small. Storage should usually be used with system schematics similar in concept to the domestic water system configurations shown in Figure 12.1.1. Systems are also

designed in which supply water passes through the collector once and then to storage or the industrial process. If there is no storage or if the amount of water in storage is constant, flow through the collector is fixed by draw-off at the point of use. If variable-capacity storage is provided, flow through the collector can be controlled independently of the loads on the system.

An example of this application is the experimental water heater that was constructed for the Campbell soup plant at Sacramento, California, shown in Figure 16.6.1. Water supply from a well was pumped in series through a flat-plate collector and a concentrating collector and then to an insulated storage tank. The quantity of water in the tank was variable with time. The temperature of this water was boosted as needed by an auxiliary steam heater to bring it to 85 to 90°C as required in the can washer. This solar-heated water was mixed with heated water from the conventional system, used for can washing, treated, and discarded. The system, described by Vindum and Bonds (1978), was designed to provide 75% of the energy to one can washing line (of 20) in the plant, so its output was small compared to the total energy requirement for hot water for the plant. This system, while it produced hot water in the same temperature range as that of flat-plate collectors used in absorption cooling, uses concentrating collectors for part of the heating process.



**Figure 16.6.1** Schematic of the experimental water heating system in the Campbell Soup Co. plant, Sacramento, CA. Adapted from Vindum and Bonds (1978).


## 16.7 RECIRCULATING INDUSTRIAL WATER HEATING

An experimental solar heating system to preheat air and boiler feedwater in an onion-drying plant in Gilroy, California (Graham et al., 1978), was based on the use of evacuated tubular collectors delivering hot water at temperatures of 70 to 100°C. The gas-fired burner received preheated air from the solar system and delivered 93°C air to the dryer. The capacity of the collectors to deliver energy was small compared to the energy requirements of the plant, and no storage was used. A schematic of the solar heating process is shown in Figure 16.7.1.

In normal operation of the system, water was circulated through the collectors and the air-water preheat exchanger to heat drying air before it went to the gas burners. It was also possible to heat water in the condensate tank, which is part of the plant boiler system, so during months when there was no drying to be done, the output from the collector could still be used.


The collector elements were evacuated collector tubes similar to the type shown in Figure 7.5.1(a) and were fitted with vee-shaped specular reflectors behind the tubes. The steady-state thermal characteristics of the collectors are shown in Figure 16.7.2, with the normal range of operating conditions indicated. Tubes were assembled into modules, with each 1.36-m<sup>2</sup> module including eight tubes and reflectors with appropriate manifold and mounting units. Four hundred and two modules were used for a total collecting area of 548 m<sup>2</sup>. The collector array was mounted on the roof of a warehouse near the building housing the dryers.

A large-area, industrial-scale water heating installation was in operation in Green Bay, Wisconsin (from 1984 to 1998), supplying hot water to a meat-packing plant (Lane, 1990). The system uses recirculation of fluid in the collectors and partial recirculation of water in the storage tank. The basic system layout is shown in Figure 16.7.3; it includes arrays of




**Figure 16.7.1** Schematic of the water heating system for the Gilroy Foods onion-drying facility. Adapted from Graham et al. (1978).





**Figure 16.7.2** Characteristics of the evacuated tubular collectors used on the Gilroy Foods onion dryer. Adapted from Graham et al. (1978).



**Figure 16.7.3** Schematic of the layout of the Green Bay water heating facility that supplies heated water to a meat-packing plant.

flat-plate collectors heating propylene glycol and two heat exchangers with an intermediate water loop to transfer collected energy to water from mains or recirculated from storage. Water from the tank is pumped to the plant where it is heated in one of four load heat exchangers or mixed with mains water to obtain the desired temperatures. The collector arrays consist of 5256 modules, each with absorber area  $2.77 \text{ m}^2$ . The storage tank has a capacity of  $1250 \text{ m}^3$ ; it contains variable quantities of water, allowing the collector heat exchangers to be fed with mains water during periods when the tank is not full, thus partially decoupling the collector operation from the water demands of the plant. The requirements of the plant are for water heated to four temperatures ( $32$ ,  $35$ ,  $50$ , and  $82^\circ\text{C}$ ); a maximum of about  $1300 \text{ m}^3$  of heated water is required each working day.

The solar heating system was built in 1984, suffered significant damage in its first winter of operation, and has since been redesigned and rebuilt. Figure 16.7.4 shows the collector arrays. Its performance has been monitored; over the first 9 months of 1989, in 188 days of operation, it delivered a total of 21 TJ to the packing plant. During this period the collector panels were available 99% of the time. The average temperature increase of the water delivered was  $33^\circ\text{C}$ . The plant delivers hot water to the packinghouse under the



**Figure 16.7.4** Collectors at the Green Bay water heating plant. Photo courtesy of R. Lane.

terms of a 10-year contract. The system was shut down in 1998 due to the very low cost of natural gas. Electrical costs for pumping had reached a point where they were almost as much as the revenue generated by sale of energy displacing natural gas. At the time of dismantling it was technically fine and producing more energy each year as the operators learned to better manage the system.


## 16.8 SHALLOW-POND WATER HEATERS

Large horizontal collectors consisting of plastic envelopes to contain water, rigid covers supported on concrete curbs, and underlying foam glass and sand insulation have been studied for possible application to provide large quantities of hot water for mineral-leaching operation, for providing service hot water to a military base, and for heating water used for various purposes in a poultry processing plant (Dickenson, 1976; Guinn and Hall, 1977). A cross section of a collector module of this type is shown in Figure 16.8.1. Dimensions of single collector units are of the order of 3 or 4 m wide and 50 m long, with water depths of the order of 0.1 m. Details of construction of such a collector are provided by Casamajor and Parsons (1979).


The deeper the pond is, the less the temperature will rise and the higher the integrated efficiency. Pond depth is a function of the desired water temperature and cost of energy; it is also influenced by the practical considerations of preparation of large areas of very level ground for support of the collectors. Operation of the shallow-pond collectors is usually in a batch mode. In a batch operation the collectors are filled in the morning, the temperature rises through the day as energy is absorbed, and when losses exceed absorbed energy, the heated water is drained to an insulated storage tank for subsequent use.

A schematic for a system proposed for preheating water for a poultry processing plant is shown in Figure 16.8.2. This plant requires a total of 150,000 liters of water per day, 40% of which is for boiler feedwater and 60% for can washing and plant cleanup operations. In this design, essentially all of the water from the insulated tank is used each day, and the collectors are fed with freshwater at supply temperature each morning.

Collectors of this type have been studied experimentally at Livermore, California, and at Grants, New Mexico, by Dickenson (1976) and Casamajor et al. (1977). Some practical



**Figure 16.8.1** Schematic cross sections of a shallow-pond water heater. Adapted from Guinn and Hall (1977).



**Figure 16.8.2** Schematic intermittent shallow-pond solar water heating system for a poultry processing plant. Adapted from Guinn and Hall (1977).

problems have been encountered. The collectors must be very carefully sloped to drain, so as to diminish the amount of water left in them at night. Snow loads on the wide, flat spans of the covers have resulted in structural problems. The durability of the system is not yet established.

Collectors of this type are restricted to horizontal orientation, so there is a seasonal variation of the incident energy on them that is a function of latitude. The monthly average radiation data from Appendix D are directly applicable to these collectors. Hour-by-hour estimates of the performance of these collectors can be made by the methods of Section 6.12, as illustrated by Example 12.7.1. Long-term performance estimates can be made by the  $\bar{\phi}$  method (see Chapter 21).

## 16.9 SUMMARY

Use of solar energy for industrial process heat represents a range of potential applications that could replace large quantities of fossil fuels. These applications face formidable competition. Industry purchases fuel in large quantities at relatively low cost. These costs are effectively further reduced by their deduction as an operating expense from corporate income with a resulting reduction of corporate income taxes. On the other hand, investment tax credits and depreciation of equipment tend to make the economics of solar application more favorable. There are not many industrial applications now being made (although the Luz power plants and the Israeli solar ponds described in the next chapters could be considered to be industrial processes).

## REFERENCES

- Casamajor, A. B. and R. E. Parsons, Lawrence Livermore Laboratory Report UCRL 52385 Rev. 1 to U.S. Department of Energy (1979). "Design Guide for Shallow Solar Ponds."
- Casamajor, A. B., T. A. Trautt, and J. M. Flowers, in *Proceedings of the Solar Industrial Process Heat Symposium* (D. K. Anand and R. W. Allen, eds.), College Park MD, Conf-770966 p.141 (1977). "Shallow Solar Pond Design Improvements."
- Dickenson, W. W., Report SAN/1038-76/1 to NATO Committee on Challenges of Modern Society for U.S. Energy Research and Development Administration (1976). "Performance of the Sohio Solar Water Heating System Using Large Area Plastic Collectors."
- Duffie, N. A. and D. J. Close, *Solar Energy*, **20**, 405 (1978). "The Optimization of a Solar Timber Dryer Using an Absorbent Energy Store."
- Graham, B. J., M. Sarlas, and P. D. Sirer, in *Proceedings of the Solar Industrial Process Heat Conference* (D. K. Anand and R. W. Allen, eds.), College Park MD, Conf-770966 p. 79 (1978). "Application of Solar Energy to the Dehydration of Onions."
- Guinn, G. R., in *Proceedings of the Solar Industrial Process Heat Conference* (D. K. Anand and R. W. Allen, eds.), College Park MD, Conf-770966 p. 63 (1978). "Process Drying of Soybeans Using Heat from Solar Energy."
- Guinn, G. R. and B. R. Hall, in *Proceedings of the Solar Industrial Process Heat Symposium* (D. K. Anand and R. W. Allen, eds.), College Park MD, Conf-770966 p. 161 (1977). "Solar Production of Industrial Process Hot Water Using Shallow Solar Ponds."
- Lane, R., *Solar Today*, **4** (5), 18 (1990). "Successful Large Scale Solar Hot Water."
- Marlatt, W. P. and C. C. Smith, paper presented at the IEA Status Seminar on Solar Air Systems (Mar. 1988). "Seasonal Performance Monitoring of a Large Solar Air-Heating System."

- Proceedings of the Solar Industrial Process Heat Conference*, Report No. Conf. 781015 to U.S. Department of Energy, National Technical Information Service (1978).
- Proceedings of the Solar Industrial Process Heat Symposium*, College Park, MD, Report No. Conf. 770966 to U.S. Energy Research and Development Administration, Government Printing Office, Washington, DC (1977).
- Read, W. R., A. Choda, and P. I. Cooper, *Solar Energy*, **15**, 309 (1974). "A Solar Timber Kiln."
- Simpson, W. T. and J. L. Tschernitz, Forest Products Laboratory Report FPL-44, U.S. Department of Agriculture, Forest Service (1985). Madison, WI, "FPL Design for Lumber Dry Kiln Using Solar/Wood Energy in Tropical Latitudes."
- Simpson, W. T. and J. L. Tschernitz, *Forest Products J.*, **39**, 23 (Jan. 1989). "Performance of a Solar/Wood Energy Kiln in Tropical Latitudes."
- Steinmann, D. E., Ph.D. Thesis, University of Stellenbosch, South Africa (1989). "Solar Kiln Drying of Wood."
- Tschernitz, J. L. and W. T. Simpson, *Solar Energy*, **22**, 563 (1979). "Solar Heated Forced Air Lumber Dryer."
- Vindum, J. O. and L. P. Bonds, in *Proceedings of the Solar Industrial Process Heat Conference* (D. K. Anand and R. W. Allen, eds.), College Park, MD, Conf-770966, p. 15 (1978). "Solar Energy for Industrial Process Hot Water."
- Wirsum, M. C., M.S. Thesis, Mechanical Engineering, University of Wisconsin-Madison (1988). "Simulation Study of a Large Solar Air Heating System."
- Yang, K. C., *Forest Products J.*, **30**, 37 (Mar., 1980). "Solar Kiln Performance at a High Latitude, 48°N."

# Solar Thermal Power Systems

Conversion of solar to mechanical and electrical energy has been the objective of experiments for over a century. In 1872, Mouchot exhibited a steam-powered printing press at the Paris Exposition, in 1902 the Pasadena Ostrich Farm system was exhibited, and in 1913 a solar-operated irrigation plant started its brief period of operation at Meadi, Egypt. These and other developments utilized concentrating collectors to supply steam to heat engines. An interesting historical review of these experiments is provided by Jordan and Ibele (1956). In May of 2002 the *ASME Journal of Solar Energy Engineering* published a special issue on solar thermal power.


Much of the early attention to solar thermal-mechanical systems was for small-scale applications, with outputs ranging up to 100 kW, and most of them were designed for water pumping. In the past four decades, the possibilities of operating vapor compression air conditioners have been studied analytically and experimentally. Since 1985 there have been several large-scale power systems (up to 80 MW) constructed and operated. Several of these will be noted in this chapter.

The processes for conversion of solar to mechanical and electrical energy by thermal means are fundamentally similar to other thermal processes, and the principles treated earlier on radiation, materials, collectors, storage, and systems form the basis of estimating the performance of solar thermal power systems. In addition, a new set of practical considerations are important, as these processes operate at higher temperatures than those treated in earlier chapters.

This chapter is concerned with generation of mechanical and electrical energy from solar energy by processes based on flat-plate or concentrating collectors and heat engines. The use of solar ponds for power production is noted in Chapter 18. There are three other kinds of solar power systems. The first includes photovoltaic processes for the direct conversion of solar to electrical energy by solid-state devices and is discussed in Chapter 23. The second, which is outside the scope of this book, includes solar-biological processes that produce fuels for operation of conventional engines or power plants. Finally, wind power is discussed in Chapter 24.

## 17.1 THERMAL CONVERSION SYSTEMS

The basic process for conversion of solar to mechanical energy is shown schematically in Figure 17.1.1. Energy is collected by either flat-plate or concentrating collectors, stored (if appropriate), and used to operate a heat engine. Problems of these systems lie in the fact that the efficiency of a collector diminishes as its operating temperature rises, while the



**Figure 17.1.1** Schematic of a solar thermal conversion system.

efficiency of the engine rises as its operating temperature rises. The maximum operating temperatures for flat-plate collectors are low relative to desirable input temperatures for heat engines, and system efficiencies are low if flat-plate collectors are used.

Hottel (1955) pointed out that the availability of cover materials with high transmittance for solar radiation may make it possible to consider the use of flat-plate collectors to supply energy to heat engines. Recent developments in collector loss control by honeycombs, CPCs, concentrating collectors, or use of evacuated-tubular collectors may open up additional systems for thermal conversion of solar to mechanical energy.


Methods of estimation of system performance are based on analysis of the components in the system. The analysis of the collectors has been covered in Chapters 6 and 7. If arrays are large, two factors must be taken into account. First, if collector modules are arranged in series, the methods of Section 7.6 can be used to calculate the effective  $F_R U_L$  and  $F_R(\tau\alpha)$ . Second, large arrays inevitably mean long runs of piping, and the methods of Section 10.5 can be used or adapted to account for these losses. If pipe runs are very long, their heat capacity and that of the fluid in them can represent an appreciable factor in the energy balances during transient operation.

Models are also needed for engines. These can be derived from basic thermodynamic relationships or they can be graphical or analytical representations of operating data. Olson (1977) derives and uses one such model.

## 17.2 GILA BEND PUMPING SYSTEM

The Gila Bend solar irrigation pumping system described by Alexander et al. (1979) is shown schematically in Figure 17.2.1. It was based on an array of cylindrical parabolic collectors that was designed to produce hot water at 150°C (pressurized at about 7 atm). The hot water went to a heat exchanger which serves as a Freon boiler where its temperature dropped about 10°C in vaporizing the Refrigerant 113 working fluid. The hot water then went through the preheater where it preheated the fluid returning to the boiler. The water returned to the collector at about 134°C. There was no thermal energy storage in this system. Water was pumped into the irrigation canals whenever possible, and storage was in the form of water at the desired higher elevation.

The working fluid vapor went from the boiler through an entrainment separator and to a 50-hp turbine. The turbine drove a 630-liter/s (10,000-gpm) pump through a gear-box. After leaving the turbine, the vapor went through a regenerator to partially preheat the



**Figure 17.2.1** Schematic of the Gila Bend solar pumping system. Design flow and conditions are shown. Adapted from Alexander et al. (1979).

boiler feed liquid and then to the condenser where it was condensed at approximately 32°C by part of the irrigation water. Condensate was returned by a feed pump to the boiler via the regenerator and preheater.

The collector array included nine rows of concentrating collectors, each 24.4 m long, with an aperture of 2.45 m and focal length of 0.91 m, for a total collecting area of 537 m<sup>2</sup>. The rows were rotated about horizontal north–south axes. The receivers were copper tubes



41 mm in diameter, with nonselective black coatings, insulated on the side away from the concentrator. First-year experiments were done with a glass half-cylinder cover, and in second-year experiments the cover was removed. Each of the nine rows of collectors was individually oriented to track the sun.

Alexander et al. (1979) describe a range of practical design and operating problems that were encountered in this experimental system. These include maintenance of specular reflectance of the reflector, tracking accuracy on various kinds of days, maintenance of mechanical and electronic components, integration of the solar energy system with an electric drive system to increase the use factor on the pump, and others.

This system, even though it underwent frequent and prolonged developmental changes, operated for 323 h in the first year at an average capacity of 240 liters/s and a maximum of 570 liters/s. In its second year, it operated for 188 h and delivered  $1.24 \times 10^5 \text{ m}^3$  of irrigation water.

### 17.3 LUZ SYSTEMS

Nine commercial Solar Electric Generating Systems (SEGS), designed and constructed by Luz International Limited, are operating in the Mojave Desert of southern California. These plants are based on large parabolic trough concentrators providing steam to Rankine power plants. They generate peaking power which is sold to the Southern California Edison utility. Located at the Dagget site are the first two of these plants owned and operated by Sunray Energy. SEGS I is a 14-MW electric (MWe) plant and SEGS II is a 30-MWe plant. The next five are all 30-MWe plants built at the Kramer Junction site and the last two are 80-MWe plants located at the Harper Lake site. SEGS III to IX are partially owned and operated by FPL Energy. Basic data on the nine operational plants are shown in Table 17.3.1. An aerial view of SEGS III, IV, and V (Kramer Junction site) is shown in Figure 17.3.1.

**Table 17.3.1** Characteristics of SEGS I to IX<sup>a</sup>

Plant	First Year	Turbine Size (MWe)	Solar Temperature (°C)	Field Area (m <sup>2</sup> )	Turbine Efficiency		Annual Output (MWh)
					Solar	Gas	
I	1985	13.8	307	82,960	31.5 <sup>b</sup>	—	30,100
II	1986	30	316	190,338	29.4	37.3	80,500
III	1987	30	349	230,300	30.6	37.3	91,311
IV	1987	30	349	230,300	30.6	37.3	91,311
V	1988	30	349	250,560	30.6	37.3	99,182
VI	1989	30	390	188,000	37.5	39.5	90,850
VII	1989	30	390	194,280	37.5	39.5	92,646
VIII	1990	80	390	464,340	37.6	37.6	252,842
IX	1991	80	390	483,960	37.6	37.6	256,125

<sup>a</sup>Data courtesy FPL Energy.


<sup>b</sup>Includes natural gas superheating.



**Figure 17.3.1** Aerial view of SEGS III, IV, and V, three of the Luz plants located on the Mojave Desert of southern California. Photo courtesy of Luz International, Inc.

The design and economics of these plants are substantially influenced by U.S. federal law. The plants qualify under the Public Utilities Regulatory Policies Act (PURPA) as small power producers and are allowed under this law to supplement solar output of the plant by fuels (natural gas) to the extent of 25% of the annual output. The plants can supply peaking power, using all solar energy, all natural gas, or a combination of the two, regardless of time or weather, within the constraint of the annual limit on gas use. The most critical time for power generation and delivery (and the time in which the selling price of the power per kilowatt-hour is highest) is between noon and 6 PM in the months of June through September. Operating strategy is designed to maximize solar energy use and depends on gas to provide power during cloudy periods early in the year and late in the summer when solar output drops off before the end of the peak-power period. The turbine-generator efficiency is best at full load, and use of gas supplement to allow full-load operation maximizes plant output. The plants do not have energy storage facilities. A schematic of a typical plant is shown in Figure 17.3.2; the solar and natural gas loops are in parallel to allow operation with either or both of the energy sources. Data and experience with these plants have been reported by Jaffe et al. (1987), Kearney and Gilon (1988), Kearney et al. (1988), Jensen et al. (1989), and Harats and Kearney (1989).

The major components in the systems are the collectors, the fluid transfer pumps, the power generation system, the natural gas auxiliary subsystem, and the controls. Three collector designs have been used in these plants, LS-1 in SEGS I, LS-2 in II to VII, and LS-3 in part of VII and in subsequent plants. Data for LS-2 and LS-3 are shown in Table 17.3.2. Photographs of the collector field are shown in Figures 17.3.3(a) and (b). The reflectors are made up of back-silvered, low-iron float-glass panels which are shaped over parabolic forms. Metallic and lacquer protective coatings are applied to the back of the silvered surface, and no measurable degradation of the reflective surface has been observed. The glass is mounted on truss structures, with the position of large arrays of modules adjusted by hydraulic drive motors. The receivers are 70-mm-diameter steel tubes with cermet selective surfaces surrounded by a vacuum glass jacket. The surfaces have an absorptance of 0.96 and an emittance of 0.19 at 350°C.



**Figure 17.3.2** Schematic process diagram for SEGS systems. Adapted from Kearney and Gilon (1988).

**Table 17.3.2** Characteristics of LS-2 and LS-3 Collector Modules<sup>a</sup>

Parameter	LS-2	LS-3
Area, m <sup>2</sup>	235	545
Mirror segments	120	224
Aperture, m	5.0	5.76
Length, m	47.1	95.2
Focal length, m	1.84	2.12
Concentration ratio	71	82
Distance between rows, m	12.5–15	17.3
Optical efficiency	0.74–0.76	0.80

<sup>a</sup>Adapted from Harats and Kearney (1989).

The reflectance of the mirrors is 0.94 when clean. Maintenance of high reflectance is critical to plant operation. With a total of  $2.31 \times 10^6$  m<sup>2</sup> of mirror area, mechanized equipment has been developed for cleaning the reflectors, which is done primarily in the summer. These results have led to average reflectance maintained at 92% year round.

Tracking of the collectors is controlled by sun sensors that utilize an optical system to focus radiation on two light-sensitive diodes, with imbalance causing corrections in the positioning of the collectors. There is a sensor and controller on each collector assembly; the resolution of the sensor is about  $0.5^\circ$ . The collectors rotate about horizontal north-south axes, an arrangement which results in slightly less energy incident on them over a year but which favors summertime operation when peak power is needed and its sale brings the greatest revenue.

A synthetic heat transfer fluid is heated in the collectors and is piped to the solar steam generator and superheater where it generates the steam to be supplied to the turbine. Reliable high-temperature circulating pumps are critical to the success of the plants, and



**Figure 17.3.3** (a) SEGS collector fields.



**Figure 17.3.3** (b) Individual collector.

significant engineering effort has gone into assuring that pumps will stand the high fluid temperatures and temperature cycling. The normal temperature of the fluid returned to the collector field is 304°C and that leaving the field is 390°C. Recent experience indicates that availability of the collector fields is about 99%.

The power generation system consists of a conventional Rankine cycle reheat steam turbine with feedwater heaters, deaerators, and so on. The condenser cooling water is cooled in forced-draft cooling towers.

The Luz plants are designed with the help of a simulation program that uses hourly radiation data. Plant performance guarantees based on that program are provided to the investors in the projects. SEGS III to VII show performance slightly exceeding the warranted performance in the initial years of operation. On-peak hour capacity factors, the ratio of available output to rated (warranted) output over all of the on-peak hours of the year, exceeded 100% by a small margin. Annual overall capacity factors have been about 30%. The actual levelized cost of delivered energy from SEGS VII in 2001 was 0.164 US\$/kWh.

In 1991 Luz International Limited filed for bankruptcy partly because it was unable to obtain financing for SEGS X but also because of declining energy costs and incentives (Price et al., 2002). The operating companies were not affected and in 2013 the plants continue to operate.

New SEGS plants are under construction throughout the world (see Wikipedia, “List of Solar Thermal Power Stations”). The next generation of SEGS plants will benefit from substantial technological progress in vacuum technology, selective surfaces, manufacturing processes, and improved materials. Inexpensive short-term thermal storage will reduce the cost of delivered energy. In fact, the first SEGS plant had 3 h of thermal storage using mineral oil heat transfer fluid, but this fluid severely limits the maximum operating temperature. Mineral oil is also highly flammable; a leak in SEGS I resulted in a fire so the thermal storage was disconnected from the system. Advanced storage techniques are described by Price et al. (2002) and include passing the heat transfer fluid through pipes imbedded in concrete, use of molten salt in a two-tank (alternating one cold and one hot) arrangement, use of an inexpensive filler material (e.g., quartzite) in a tank with the heat transfer fluid in contact with the filler to produce a thermocline (analogous to pebble bed/air storage systems), and the use of organic salts as both the heat transfer fluid and the storage medium.

## 17.4 CENTRAL-RECEIVER SYSTEMS

In Chapter 8, some of the optical properties of large “power tower” or central-receiver concentrators were noted. The potential application of these collectors is in large-scale conversion processes with output in the megawatt range. Large-scale systems must collect energy from large areas. In these systems beam radiation from a large array of (relatively) small heliostats is focused on a central receiver, thus collecting by optical rather than thermal means. Numerous photographs are available at Wikipedia, “Solar Thermal Power Stations.”

An early paper on a central-receiver concept by Baum (1956) outlined a design in which heliostats were to be mounted on semicircular railway tracks, with the assemblies of mirrors moved through the day to keep beam radiation focused on the central receiver. More

recent design concepts call for heliostats on mounts at fixed locations and movable about two axes of rotation to accomplish concentration. Major research-and-development efforts are aimed at solving the range of optical, thermal, and mechanical problems associated with the development of electric power generation systems based on these concepts. These early efforts were reported in the *Proceedings of the 1978 DOE Workshop on Systems Studies for Central Solar Thermal Electric* (1978). A review of general design considerations is provided by Winter et al. (1991). A more recent review of solar central-receiver systems is provided by Romero et al. (2002).

The major components in the system are the heliostat field, the heliostat controls, the receiver, the storage system, and the heat engine which drives the generator. Heliostat design concepts were briefly outlined in Section 7.9. The objective of heliostat design is to deliver radiation to the receiver at the desired flux density at minimum cost. For an extensive discussion of optical problems, see the *Proceedings of the ERDA Solar Workshop* (1977) on optical analysis.

A range of receiver shapes has been considered, including cavity receivers and cylindrical receivers. The optimum shape is a function of intercepted and absorbed radiation, thermal losses, receiver cost, and design of the heliostat field. Vant-Hull in a paper in the *Proceedings of the ERDA Solar Workshop* (1977) suggests that for a large heliostat field a cylindrical receiver has advantages when used with Rankine cycle engines, particularly for radiation from heliostats at the far edges of the field. If higher temperatures are required for operation of Brayton cycle turbines, it may be necessary to use cavity receivers with larger tower height–heliostat field area ratios.

It has been observed in many solar power studies that the solar collector represents the largest cost in the system. Under these circumstances, an efficient engine is justified to obtain maximum useful conversion of the collected energy. Several possible thermodynamic cycles have been considered. First, Brayton or Stirling gas cycle engines operated at inlet temperatures of 800 to 1000°C provide high engine efficiencies but are limited by low gas heat transfer coefficients, by the need for recuperators, and by the practical constraints on collector design (i.e., the need for cavity receivers) imposed by the requirements of 1000°C temperatures. Second, turbines driven from steam generated in the receiver would operate at 500 to 550°C and have several advantages over the Brayton cycle. Heat transfer coefficients in the steam generator are high, allowing the use of high energy densities and smaller receivers with energy absorption on the outer surface. Cavity receivers are not needed and cylindrical receivers permit larger heliostat fields to be used. Use of reheat cycles improves steam turbine performance but entails mechanical design problems. It is also possible to use steam turbines with steam generated from an intermediate heat transfer fluid circulated through the collector and boiler. The fluids could be molten salts or liquid metals, and cylindrical receivers could be operated at around 600°C with such systems. These indirect systems are the only ones that readily lend themselves to the use of storage. Low-temperature steam or organic fluid turbines may also be used, with collector temperatures around 300°C in receivers with lower solar radiation flux densities.

In the next section, a large 10-MWe central-receiver system, Solar One (later modified and called Solar Two), is described. Other experimental plants have been built and operated, including a 5-MWe plant in Russia, a 2.5-MWe plant in France, and 1-MWe plants in Japan, Italy, Spain, and the United States.

## 17.5 SOLAR ONE AND SOLAR TWO POWER PLANTS

The construction of Solar One, a large central-receiver plant with a peak electric generating capacity of over 10 MWe, was completed in 1982. Located at Barstow, California, the plant underwent two years of operation in an experimental test and evaluation phase and three years in a power production phase. Power generated by the plant was supplied to the grid of Southern California Edison. Photographs of the collector, the receiver, and heliostats are shown in Figure 17.5.1. A summary of experience with the plant during the three years of power production operation is provided by Radosevich and Skinrood (1989).



The heliostat system consists of 1818 individually oriented reflectors, each consisting of 12 concave panels with a total area of  $39.13 \text{ m}^2$ , for a total array area of  $71,100 \text{ m}^2$ . The reflecting material is back-silvered glass.

The receiver is a single-pass superheat boiler, generally cylindrical in shape, 13.7 m high, 7 m in diameter, with the top 90 m above ground. It is an assembly of 24 panels, each 0.9 m wide and 13.7 m long. Six of the panels on the south side (which receives the least radiation) are used as feedwater preheaters and the balance are used as boilers. Each panel is made up of parallel 0.069-m-diameter alloy tubes welded together along their total length. The panels are coated with a nonselective flat-black paint which was heat cured in place with solar radiation. Average absorptance for solar radiation, after a second coating was applied, was about 0.96. The receiver was designed to produce 50,900 kg/h of steam at  $516^\circ\text{C}$  with the absorbing surface operating at a maximum temperature of  $620^\circ\text{C}$ .



**Figure 17.5.1** Solar One, at Barstow, CA. (a) Overall view of the heliostat field and receiver tower when system was not operating. (b) A heliostat. (c) The receiver, photographed from above, when in operation. Photographs courtesy of Sandia National Laboratories.





**Figure 17.5.1** (Continued)



The thermal storage system is in a fluid loop that is separated from the steam cycle loop by heat exchangers. Steam generated in excess of that required for power generation can be diverted to the charging heat exchanger, in which oil is heated for transfer to a bed of oil, sand, and gravel. Since the plant is basically a peaking plant, most steam is used in the turbine as it is generated.

The power generation system includes the turbine generator and its auxiliaries and the cooling system for heat rejection.

The control systems include the computers that monitor and control the plant and the beam characterization system that corrects the alignment of the heliostats and evaluates heliostat performance.

The plant support system includes all of the auxiliaries necessary for the operation of the plant, such as water conditioners, compressed gas supplies, liquid waste disposal, and electrical systems.

During its three years of power production operation, measurements were made on the performance of the various components in the systems. Radosevich and Skinrood (1989) have summarized the main conclusions of the operation; highlights from their summary serve to illustrate the potential and the problems of operation of large central-receiver systems.

The heliostat field uses mirrors with an average reflectance of 90.3%. Dirt on the mirrors reduced this reflectance, with the reduction a function of frequency of washing. Based on experience with Solar One, it appears that the reflectance of the mirrors can be maintained at about 93% of its nominal value if heliostats are washed effectively at biweekly intervals. Some corrosion of the silver backing was experienced; this can be held to a few percent per year by proper design of the modules to minimize the contact of the silvering with moisture. A third consideration with the large heliostat field is reliability. During the third year of the power production operation, an average of 98.8% of the 1818 heliostats were operational.

The receiver was a source of more problems. The panels experienced warping, presumably due to temperature gradients caused by uneven distribution of incident radiation. In addition, leaks developed in tubes and repairs were required. Warpage did not itself affect operation of the receiver other than to expose support structure to radiation entering through openings that developed between the panels, but it probably contributed to leaks and would reduce the useful life of the receiver. The black paint on the receiver had an initial high absorptance of 0.96 to 0.97; this diminished at the rate of about 0.02 per year over a three-year span.

During the power production operation, the plant availability averaged 82% of the time in which beam radiation was available to operate it. Thus the turbogenerator was connected to the grid or the store was being charged 0.82 of the time for which beam radiation was available. (The balance of the time, the downtime, was attributable to scheduled or unscheduled maintenance, stowing of the heliostats because of excessive winds, etc.) In the Barstow climate, the annual average availability, based on total daylight hours, averaged 55%. The plant more than met its design goal of 10 MWe; its maximum power output was a net (after auxiliary energy for plant operation was deducted) of 11.7 MWe.

The annual system efficiencies, the ratio of net electrical energy produced (based on 24-h plant energy requirements) to annual incident beam radiation, were 4.1, 5.8, and 5.7% during the three years of power production operation. The maximum monthly efficiency

was 8.7%. (Maximum instantaneous efficiencies would be higher, probably close to the design maximum of 15%.) Capacity factors, the ratio of the net electrical output to the rated net output over 24 h, averaged 8, 12, and 11% over the three years of power production operation, with a maximum monthly factor of 24% in a summer month.

Solar One was a large-scale experiment that provided operating data and experience on a range of component and system problems while at the same time providing peaking power to a utility. One important conclusion from Solar One operation was that the storage system was inadequate to operate the turbine at peak efficiency. Solar One ceased operation in 1988 and was rebuilt and restarted in 1996 as Solar Two (Romero et al., 2002). The primary modification was the replacement of the oil-rock thermocline storage unit with a two-tank molten salt storage system. Other modifications included a new receiver, a new steam generator, a new control system, and the addition of 108 heliostats each with an area of 95 m<sup>2</sup> (the original heliostats were 39 m<sup>2</sup>). The success of the new storage design is illustrated by a one-time operation around the clock for 154 continuous hours.

## REFERENCES

- Alexander, G., D. F. Busch, R. D. Fischer, and W. A. Smith, Battelle Columbus Laboratories Report SAND 79-7009 (1979). "Final Report on the Modification and 1978 Operation of the Gila Bend Solar-Powered Irrigation Pumping System."
- Baum, V. A., in *Proceedings of the World Symposium on Applied Solar Energy*, Stanford Research Institute, Menlo Park, CA, p. 289 (1956). "Prospects for the Application of Solar Energy, and Some Research Results in the USSR."
- Harats, Y. and D. Kearney, paper presented at the ASME Meeting, San Diego (1989). "Advances in Parabolic Trough Technology in the SEGS Plants."
- Hottel, H. C., in *Solar Energy Research* (F. Daniels and J. A. Duffie, eds.), University of Wisconsin Press, Madison, p. 85 (1955). "Power Generation with Solar Energy."
- Jaffe, D., S. Friedlander, and D. W. Kearney, in *Proceedings of the ISES World Congress* (W. H. Bloss and F. Pfisterer, eds.), Hamburg, Germany, Pergamon, Oxford (1987). "The Luz Solar Electric Generating Systems in California."
- Jensen, C., H. Price, and D. Kearney, paper presented at the ASME Meeting, San Diego (1989). "The SEGS Power Plants: 1988 Performance."
- Jordan, R. C. and W. C. Ibele, in *Proceedings of the World Symposium on Applied Solar Energy*, Stanford Research Institute, Menlo Park, CA, p. 81 (1956). "Mechanical Energy from Solar Energy."
- Kearney, D. W. and Y. Gilon, paper presented at VDI Solarthermische Kraftwerke, Koln, Germany Meeting (1988). "Design and Operation of the Luz Parabolic Trough Solar Electric Plants."
- Kearney, D. W., H. Price, Y. Gilon, and D. Jaffe, paper presented at the ASME Meeting, Denver (1988). "Performance of the SEGS Plants."
- Olson, T. J. M.S. Thesis, Mechanical Engineering, University of Wisconsin-Madison (1977). "Solar Source Rankine Cycle Engines for Use in Residential Cooling."
- Price, H., L. Eckhard, D. Kearney, E. Zarza, G. Cohen, R. Gee, and R. Mahoney, *Trans. ASME, J. Solar Energy Eng.*, **124**, 109 (2002). "Advances in Parabolic Trough Solar Power Technology."
- Proceedings of the ERDA Solar Workshop on Methods for Optical Analyses of Central Receiver Systems*, University of Houston-Sandia Laboratories (1977). Available from U.S. Department of Commerce.
- Proceedings of the 1978 DOE Workshop on Systems Studies for Central Solar Thermal Electric*, University of Houston-Sandia Laboratories (1978). Available from U.S. Department of Commerce.

- Radosevich, L. G. and A. C. Skinrood, *Trans. ASME J. Solar Energy Eng.*, **111**, 144 (1989). “The Power Production Operation of Solar One, the 10 MWe Solar Thermal Central Receiver Pilot Plant.”
- Romero, M., R. Buck, and J. E. Pacheco, *Trans. ASME J. Solar Energy Eng.*, **124**, 98 (2002). “An Update on Solar Central Receiver Systems, Projects and Technologies.”
- Winter, C. J., R. L. Sizmann, and L. L. Vant-Hull, *Solar Power Plants: Fundamentals, Technology, Systems, Economics*, Springer-Verlag (1991).

# Solar Ponds: Evaporative Processes


In this chapter we start with a discussion of solar ponds. These are large, shallow bodies of salt water that are arranged so that the temperature gradients are reversed from the normal, that is, so the hottest layers are at the bottom of the ponds. This allows their use for collection and storage of solar energy, which may under ideal conditions be delivered at temperatures of 40 to 50°C above ambient. The first section is a description of ponds and their operation. The next is an introduction to analysis of the thermal performance of ponds (and thus might have been placed in Part I), and in the third section three applications are discussed.

At least two other methods have been noted for maintaining inverted temperature gradients by suppressing convection in ponds through the use of horizontal, vertical, or honeycomb membranes (Hull, 1980) and polymer gel layers (Wilkins and Lee, 1987). These are not treated here.

We then note three evaporative processes: distillation of salt water to produce freshwater, evaporation of salt brines to produce salt, and drying to remove moisture from solids. Evaporation for salt production and drying of crops are many centuries old and are the basis of commercial and agricultural enterprises in many parts of the world. A substantial body of know-how and design information has been developed on evaporation and drying, and in the discussion here only the principles involved are noted. Distillation developments have occurred over the past century and are treated in more detail. In all cases our concern is with direct distillation, evaporation, and drying in which solar energy is absorbed in the apparatus where evaporation occurs rather than in a separate collector; indirect processes, in which solar energy is delivered from collectors to evaporation, drying, or distillation processes, are covered, by implication, in the chapter on industrial processes.

## 18.1 SALT-GRADIENT SOLAR PONDS

Temperature inversions have been observed in natural lakes, with higher temperatures in the bottom layers than near the surface. These lakes have high concentrations of dissolved salts in the bottom layers and much more dilute solutions at the surface. This phenomenon suggested the possibility of constructing and using ponds as large-scale horizontal solar collectors. Tabor (1964), Weinberger (1964), and Tabor and Matz (1965) reported a series



**Figure 18.1.1** Salinity and temperature profiles for salt-gradient pond. From Nielsen (1978).

of theoretical and experimental studies of these salt-gradient ponds.<sup>1</sup> Salt-gradient ponds have been proposed for power production, salt production, and providing thermal energy for buildings. Tabor and Weinberger (1981) review the theory and operation of ponds. See Nielsen (1988) for a recent and useful review of the theory and applications. For a comprehensive treatment of all aspects of the topic, see Hull et al. (1989).

Typical gradients of salinity and temperature in an operating solar pond are shown in Figure 18.1.1. Three layers are present. At the top is a homogeneous layer of solution of low concentration, an upper convecting zone (UCZ). The next layer is a thick non-convecting or gradient zone (GZ), which provides insulation as heat is transferred up out of the heated layer below it only by conduction. The bottom layer is another homogeneous layer, the lower convecting zone (LCZ), with a high concentration of salt. The basic criterion for solar pond operation is that the density of the concentrated solution in the bottom zone must be higher at its maximum temperature than the density of the more dilute layers above it. Much of the solar radiation is transmitted through the upper layers, and the bottom layers become heated.

Several phenomena occurring in the operation of ponds are briefly described below. These include absorption of radiation, diffusion processes that tend to drive ponds toward homogeneity, stability, pond construction, salt and water requirements, and heat extraction.

The reflectance of a smooth water surface for solar radiation is of the order of 5% at near normal incidence. As radiation is transmitted through water, the longer wavelengths are absorbed near the surface. Measurements by Nielsen (1988) indicate that little radiation at  $\lambda > 0.7 \mu\text{m}$  is transmitted through a meter of clean water, but over 95% of the radiation in the wavelength range 0.3 to  $0.6 \mu\text{m}$  is transmitted through this much water. At the time of these measurements, the zenith angle of the sun was approximately  $12^\circ$ , so radiation was nearly normal to the water surface. In this pond there was significant radiation transmitted to the bottom layers.

The concentration gradients that exist in ponds lead to diffusion of salt from the concentrated layer at the bottom to the dilute layer at the top. In order for pond stability to be maintained, salt must be added to the lower layer and removed from the upper layer. As this must be done by injecting and removing solutions, there is an additional upward flow due to water addition and removal. Nielsen notes that the rates of salt transport into the upper zone are of the order of  $3 \text{ kg/m}^2$  per month. Thus the quantities of salt which

<sup>1</sup>These are often called simply "solar ponds." As there are other types of ponds called by the same name, the term salt-gradient pond avoids confusion.

must be added and removed are significant. The corresponding quantities of dilute solution must be discarded and concentrated solution obtained or the dilute solution processed to allow recycling. Water evaporation from the open surfaces of ponds must also be replaced. [See Batty et al. (1987).]

Solar ponds are of the order of 1 to 3 m deep. They are constructed on level ground by a combination of excavation and embankments, and membrane liners are used to make the basins leakproof. Layers of clay may be used over the liners to protect them and improve their durability. Leaks from ponds can prevent their functioning as useful energy collection systems. Filling ponds must be done in such a way that the necessary salinity gradients are established by addition of freshwater or brines at appropriate levels.

Surface waves caused by winds tend to cause mixing and increases in thickness of the upper convective layer, ultimately leading to degradation of pond performance. Floating nets or arrays of floating pipes are used as wave barriers. The larger the ponds, the more critical are the use of the barriers.

There are several advantages to large ponds. The larger the pond, the smaller will be the ratio of perimeter to area. As edge losses can be significant, performance of larger ponds is better than that of smaller ponds. Also, wall effects such as development of convection in the gradient layer due to temperature gradients and conduction in the wall are minimized. Costs per unit area of ponds will decrease as pond size increases. (Ponds that have been built have ranged in size from about 300-m<sup>2</sup> experiments to a 210,000-m<sup>2</sup> production pond.)

Removal of heat from the bottom layer of a pond can be accomplished either by means of a large-area heat exchanger submerged in the pond or by simultaneous slow removal of hot brine from the lower level at one part of the pond and return of (cooled) brine at the lower level at another location. Hull et al. (1986) describe experiments on a 1000-m<sup>2</sup> pond in which both methods were studied; properly done, either one can be an effective method for extracting energy without destabilizing the pond.

Cleanliness of the ponds may be a problem if they are not large in extent as contaminants can reduce transmittance. Some “dirt” will float at the surface, some will sink to the bottom, and some will float at intermediate levels where its density matches that of the solution, and removal of these contaminants may have to be done by filtration or skimming. The effects of dirt may be of diminishing importance as pond size increases, as the effects will be more pronounced at edges. In very large ponds, significant effects of dirt may be caused only by major events such as dust storms.

## 18.2 POND THEORY

Numerous studies of various aspects of the theory of solar ponds have been published; Nielsen (1988) and Hull et al. (1986, 1989) provide useful introductions to these publications. In this section some aspects of the basic theory of ponds are outlined.

Equations for the steady-state operation of ponds can be written that are the same in form as the Hottel-Whillier equation (Equation 6.7.6) (Kooi, 1979), where heat removal from the pond is by brine extraction and injection at the LCZ. The factor  $F'$  is unity. The temperature gradient in the flow (horizontal) direction from injection point to extraction point is accounted for by an  $F_R$ , which has the same functional form as that for a flat-plate collector; its value for practical ponds is close to unity. The loss coefficient  $U_L$  includes

contributions for upward losses through the nonconvective (gradient) zone and for ground and edge losses. Hull et al. (1986) have used the Kooi analysis and work on ground heat losses to derive an equation for a steady-state pond with  $F_R$  near unity as

$$Q_u = A \left[ I\tau\alpha - \left( \frac{k}{\Delta x} + g \right) (T_{LCZ} - T_{UCZ}) \right] \quad (18.2.1)$$


where  $k$  is the thermal conductivity of the solution in the gradient zone (nearly that of water),  $\Delta x$  is the thickness of the gradient zone, and  $g$  is a ground loss coefficient. The coefficient  $g$  is estimated by an equation of the form

$$g = (a/x_g + bP/A)k_g \quad (18.2.2)$$

where  $P$  is the perimeter of a pond of area  $A$ ,  $k_g$  is the effective thermal conductivity of the ground under the pond, and  $x_g$  is the distance from the bottom of the pond down to the water table. The constants  $a$  and  $b$  are for a particular pond. This assumes that both upward and ground losses are to a single temperature  $T_{UCZ}$ , which will be close to the mean ambient temperature. See Hull et al. (1984) for a detailed discussion of ground losses.

Radiation is absorbed in a pond at various depths and wavelengths, as the optical extinction coefficient is a strong function of wavelength in the solar energy spectrum. Transmission in ponds has been represented in two ways, as the sum of four exponentials representing four parts of the spectrum by Rabl and Nielsen (1975) or as a logarithmic function by Bryant and Colbeck (1977), both based on early experiments by oceanographers. Afeef and Mullett (1989) review these experiments and describe new experiments indicating that the transmittance of unfiltered salt solutions was substantially less than that of water alone but that filtering or prolonged settling (such as would occur in solar ponds) increases transmittances of 20% solutions of sodium and magnesium chlorides to close to that of water.

Kooi (1979) has calculated  $\eta/F_R$  as a function of  $\Delta T/I$  for ponds of varying depths and compared them to flat-plate collectors, as shown in Figure 18.2.1. Curves *B* and *C*



**Figure 18.2.1** Calculated  $\eta/F_R$ -versus- $\Delta T/I$  curves for (A) one-cover selective flat-plate collector, (B) solar pond with the top of LCZ 1 meter from surface, and (C) a pond with the top of the LCZ 2 m below the surface. Adapted from Kooi (1979).

are for ponds with the top of the lower nonconvecting zone 1 and 2 m below the surface. The difference in intercepts represents additional radiation absorption by the additional meter of solutions in the UCZ and GZ. The lower slope of  $C$  reflects the additional meter of insulation (i.e., solution) over the LCZ. Curve  $A$  is for a one-cover, selective flat-plate collector. At high operating points (i.e., high values of  $\Delta T/I$ ), the performance of ponds appears to be better than the performance of the flat-plate collector. The utility of this comparison is limited, however. It does not account for the increases in incident radiation on the flat-plate collector gained by orienting it at more favorable angles or the fact that ponds lose heat continuously and collectors lose heat only when they are operating. Costs and applicability to specific energy supply problems must also be considered.

### 18.3 APPLICATIONS OF PONDS

Several dozen ponds have been constructed and operated. Most of them are designed for experimental purposes, but as of 1989 several are production ponds delivering energy routinely to meet energy loads. The ponds briefly described in the following paragraphs are each designed for a different type of application.

At El Paso, Texas, an existing 3350-m<sup>2</sup> water storage pond near a food canning plant was converted to a solar pond for providing process heat to the plant and for experiments on power generation and desalination. The operation started in 1986 with production of heat for the plant and experimental operation of a Rankine cycle turbine using an organic working fluid. The long-term intention is to use the pond for process water heating only.

A 2000-m<sup>2</sup> pond was constructed at Miamisburg, Ohio, in 1978 for supplying heat to a municipal swimming pool. Difficulties were initially encountered with leaks in the liner and corrosion of a submerged copper pipe heat extraction exchanger. These were overcome, and the pond is now operated with an external heat exchanger. It supplies all of the heat needed for the pool during the swimming season and also provides heat to a bathhouse during other parts of the year. The water supply used to fill the pool in the spring is at 11°C; after the pool is filled, the pond provides the energy to heat it to the desired 27°C operating temperature and maintain that temperature until the pool is closed in the fall (Wittenberg and Etter, 1982).

The largest solar ponds have been built in Israel. After years of research and experience with experimental ponds (by Tabor and his colleagues) a series of large ponds have been constructed in the Dead Sea area which have been designed for power production. The first of these was a 6250-m<sup>2</sup> pond at En Boqek that operated a 150-kW power plant. This has been superseded by two much larger ponds, one of 40,000 m<sup>2</sup> and the other of 210,000 m<sup>2</sup>, which together supply energy for a 5-MW Rankine cycle peaking plant. These ponds operate at substantially higher temperatures than does the Miamisburg pond; bottom layer temperatures of 70 to 80°C are used. Heat is extracted by withdrawing concentrated brine from the lower convective layer, pumping it through the heat exchanger (boiler) where it supplies heat to the organic working fluid, and returning it to the lower layer through low-velocity injectors.

Photographs of the pond at El Paso and the Israeli Dead Sea installation are shown in Figure 18.3.1.






**Figure 18.3.1** (a) The 3350-m<sup>2</sup> El Paso pond. Photo courtesy of University of Texas at El Paso, (b) The 210,000- and 40,000-m<sup>2</sup> ponds at the Dead Sea, Israel. Photo courtesy of Ormat.

## 18.4 SOLAR DISTILLATION

The first known application of solar distillation was in 1872 when a still at Las Salinas on the northern deserts of Chile started its three decades of operation to provide drinking water for animals used in nitrate mining. The still utilized a shallow black basin to hold the salt water and absorb solar radiation; water vaporized from the brine, condensed on the underside of a sloped transparent cover, ran into troughs, and was collected in tanks at the end of the still. Most stills built and studied since then have been based on the same concepts, though many variations in geometry, materials, methods of construction, and operation have been employed. This section is concerned with these basin-type stills. Other configurations have been used based on evaporation from wicks or from brines cascading over weirs to allow other than horizontal energy-absorbing surfaces. A very comprehensive summary of literature on all aspects of solar distillation is provided by Talbert et al. (1970). A more recent review is available by Delyannis and Stefanakos (2003).


The basin-type still is shown in section in Figure 18.4.1. A still may have many bays side by side, each of the type shown. The covers are usually glass; they may also be air-supported plastic films. The basin may be on the order of 10 to 20 mm deep (referred to as shallow basins) or they may be 100 mm or more deep (referred to as deep basins). The widths are of the order of 1 to 2 m, with lengths widely variable up to 50 to 100 m.




**Figure 18.4.1** Schematic cross section of a bay of a basin-type solar still.

In operation, solar radiation is transmitted through the cover and absorbed by the salt water and the basin. The solution is heated, water evaporates, and vapor rises to the cover by convection where it is condensed on the underside of the cover. Condensate flows by gravity into the collection troughs at the lower edges of the cover; the covers must be at sufficient slope that surface tension of the water will cause it to flow into the troughs without dropping back into the basin. The trough is constructed with enough pitch along its length so that condensate will flow to the lower end of the still, where it drains into a product water collection system. Operation of a still may be continuous or batch. If seawater (approximately 3.5% salt) is used as feed, the concentration is usually allowed to double before the brine is removed, so about half of the water in the feed is distilled off.

Figure 18.4.2 shows the major energy flows in a still while it is operating. The objective of still design is to maximize  $Q_{\text{evap}}$ , the transport of absorbed solar radiation to the cover-condenser by water vapor, as this is directly proportional to still productivity. All other energy transfer from basin to surroundings should be suppressed as far as is possible. Most energy flows can be evaluated from basic principles, but terms such as leakage and edge losses are difficult to quantify and may be lumped together in a catchall term determined experimentally for a particular still.



**Figure 18.4.2** The major energy transport mechanisms in a basin-type still. From Talbert et al. (1970).



**Figure 18.4.3** Basic thermal network for a basin-type still.

The basic concepts of solar still operation have been set forth by Dunkle (1961) and others. The thermal network for a basin-type still is similar in principle to Figure 6.4.1 for a flat-plate collector, but with three differences. Energy transfer from basin to cover occurs by evaporation-condensation in addition to convection and radiation. The losses from the back of the still are to the ground. The depth of the water in the still is usually such that its capacitance must be taken into account. There is no useful energy gain in the sense of that of a flat-plate collector; still output is measured by the evaporation-condensation transfer from basin to cover. A thermal network is shown in Figure 18.4.3, where the resistances correspond to the energy flows in Figure 18.4.2. Terms for leakage, edge losses, entering feedwater, and leaving brine or product are not shown.

An energy balance on the water in the basin (and the basin itself), per unit area of basin, can be written as

$$G\tau_c\alpha = q_e + q_{r,b-g} + q_{c,b-g} + q_k + (mC_p)_b \frac{dT_b}{dt} \quad (18.4.1)$$

where the subscripts,  $e$ ,  $r$ ,  $c$ , and  $k$  represent evaporation-condensation, radiation, convection, and conduction, respectively. The subscripts  $b$  and  $g$  refer to basin and glazing (cover), and  $\tau_c$  is the transmittance of the cover and the water film or droplets on its underside.

The capacitance of the glazing will normally be small compared to that of the water and basin. In most modern still designs the pitch of the covers is small and the cover area is approximately the same as the basin area. An energy balance on the cover, neglecting its capacitance and solar energy absorbed by it, can be written as

$$q_e + q_{r,b-g} + q_{c,b-g} = q_{c,g-a} + q_{r,g-a} \quad (18.4.2)$$

These two equations are analogous to Equations 6.12.1 and 6.12.2 for flat-plate collectors. Here  $q_e$  is not a linear function of the temperature difference between the plate and the glazing, and the two equations need to be solved simultaneously to find  $T_b$ ,  $T_c$ , and  $q_e$  as functions of time.

Dunkle (1961) provides convenient ways of estimating the terms for internal heat transfer in the still for use in these equations. The radiation exchange between basin and cover,  $q_{r,b-g}$ , is calculated by Equation 3.8.3. The cover is usually glass, and during operation a thin layer of condensate forms on most of its undersurface. Dunkle recommends that the term be written in the form

$$q_{r,b-g} = 0.9\sigma(T_b^4 - T_g^4) \quad (18.4.3)$$

For estimating the convection energy transfer from basin to cover,  $q_{c,b-g}$ , he suggests that the normal Rayleigh number must be modified to account for buoyancy effects due to the fact that heat and mass transfer occur simultaneously. The buoyancy term in the Grashof number is modified by the density gradient caused by the composition gradient (in addition to the temperature gradient). In a horizontal enclosed air gap, a relationship between Nusselt and Rayleigh numbers is

$$\text{Nu} = 0.075(\text{Ra})^{1/3} \quad (18.4.4)$$

where the temperature difference in the Rayleigh number,  $\Delta T'$ , is an equivalent temperature difference accounting for density differences due to water vapor concentration differences. For air and water,

$$\Delta T' = (T_b - T_g) + \left( \frac{p_{wb} - p_{wg}}{2016 - p_{wb}} \right) T_b \quad (18.4.5)$$

where  $p_{wb}$  and  $p_{wg}$  are the vapor pressures of water in millimeters of mercury of the solution in the basin at  $T_b$  and of water at the cover temperature  $T_g$ . Temperatures are in degrees kelvin.

From Equations 18.4.4 and 18.4.5 the convection coefficient in a still is

$$h'_c = 0.884 \left[ (T_b - T_g) + \left( \frac{p_{wb} - p_{wg}}{2016 - p_{wb}} \right) T_b \right]^{1/3} \quad (18.4.6)$$

and the heat transfer between the basin and cover is

$$q_{c,b-g} = h'_c(T_b - T_g) \quad (18.4.7)$$

By analogy between heat and mass transfer, the mass transfer rate can be written as

$$m_D = 9.15 \times 10^{-7} h'_c(p_{wb} - p_{wg}) \quad (18.4.8)$$

and the heat transfer by evaporation-condensation is

$$q_e = 9.15 \times 10^{-7} h'_c(p_{wb} - p_{wg})h_{fg} \quad (18.4.9)$$

where  $m_D$  is the mass transfer rate in kilograms per meters squared per second and  $h_{fg}$  is the latent heat of water in joules per kilogram.

The heat transfer terms from cover to ambient are formulated in the same way as for flat-plate collectors. If the still has insulation under the basin, heat loss to the ground can be written as

$$q_k = U_G(T_b - T_a) \quad (18.4.10)$$

where  $U_G$  is an overall loss coefficient to ground assuming the ground to be at a temperature equal to ambient. This term should be small in a large, well-designed still.

If the basin is very shallow and well insulated, the heat capacity term in Equation 18.4.1 can be neglected and steady-state solutions found. However, for practical reasons, most stills will have sufficient depth that the capacitance of the basin should be considered. If the still is not well insulated, an effective ground capacitance will also have to be considered by writing another differential equation relating energy stored in a layer of ground to heat flows into and out of that layer.

This set of equations, with data on radiation, temperature, and wind speed and with design parameters of the still, can be solved for  $T_b$  as a function of time, and the productivity is then calculated from Equation 18.4.8. This analysis does not include capacitance rates of feedwater or leaving brine or product or edge effects and leakage, which are difficult to formulate; these are often lumped together in a term determined experimentally as that required to make energy balances close. There is evidence for the existence of temperature gradients in still basins that make the surface temperature different from the bulk temperature of the salt water.

The instantaneous efficiency of a still at any time is defined as the ratio of the heat transfer in the still by evaporation-condensation to the radiation on the still:

$$\eta_i = \frac{q_e}{G} \quad (18.4.11)$$

This is usually integrated over some extended period (e.g., day or month) to indicate long-term performance. If there is any loss of product water back into the still (by dripping from the cover or by evaporation or leakage from collecting troughs), less product would be available than is indicated by this equation. Efficiency from experimental measurements is

$$\eta_i = \frac{\dot{m}_p h_{fg}}{AG} \quad (18.4.12)$$

where  $\dot{m}_p$  is the rate at which distillate is produced from the still (which may be less than  $\dot{m}_D$ ) and  $h_{fg}$  is the latent heat of vaporization.

The objective of still design is to maximize  $q_e$  (i.e.,  $\dot{m}_D$ ), which is proportional to the vapor pressure difference between basin and cover. Thus it is desirable to have the basin temperature as high as possible, which will increase the ratio of heat transfer by evaporation-condensation to that by convection and radiation. This has led to designs with shallow basins with small heat capacity which heat up more rapidly than deep basins and operate at higher mean temperatures.


Many practical considerations govern still design and operation. Shallow basins require precise leveling of large areas, which is costly. Crystals of salt build up on dry

spots in basins, leading to reduced overall absorptance and reduced effective basin area. Leakage can cause problems in three ways: Distillate can leak back into the basin, salt water can leak out of the basin, and humid air from inside the still can leak out through openings in the cover. Occasional flushing of still basins has been found necessary to remove accumulations of salt and organisms such as algae which grow in the brines. Algal growths can be controlled by additions of algacides.


A wide variety of experiment basin-type stills have been built and studied. Two design trends have evolved. Large-area deep basin stills as shown in Figure 18.4.4 can be built by standard construction techniques, are durable, and are relatively inexpensive. Part of the distillate production from these deep-layer stills is obtained at night, when the basin remains warm and the cover temperature goes down as the ambient temperature drops.

Modular shallow basin stills, as shown in Figure 18.4.5, have lower thermal capacitance, produce somewhat more water, and yield most of their product water in the daytime. They may be more expensive to construct than deep-layer stills.

Details of these and many other designs are included in Talbert et al. (1970). A less extensive report on the potential of distillation applications in developing economies was published by the United Nations (1970). Cooper, in a series of papers (e.g., 1973), has made a detailed simulation study of solar still performance. Proctor (1973) has experimentally investigated the possibility of augmenting solar still output with waste heat.



**Figure 18.4.4** Schematic section of an experimental deep-layer still at Daytona Beach, FL. Brine depth in still is 0.1 to 0.15 m. From Talbert et al. (1970).



**Figure 18.4.5** Schematic section of experimental shallow basin still at Muresk, Western Australia. Brine depth is 0.01 to 0.03 m. Adapted from Morse and Read (1968).

## 18.5 EVAPORATION

Solar evaporation to produce salts from seawater or other brines is a large-scale industrial operation, and on a worldwide basis approximately one-third of the annual salt production is from solar processes. In the United States, solar salt production facilities are concentrated in the Great Salt Lake and San Francisco Bay areas. This is a well-established technology.

A description of the history and operation of salt manufacture by solar evaporation of seawater is provided by See (1960). The process is a fractional crystallization. Shallow pans or ponds are filled with the brine to be evaporated and exposed to radiation. As long as evaporation exceeds rainfall, concentration will increase with time, and crystallization will occur when saturation is reached. Pond operation depends on the source of feedwater. Seawater contains approximately 3.5% salts, of which approximately two-thirds is NaCl (the usual desired product). Seawater evaporation can be considered to consist of three steps. The first is brine concentration to bring the solution to saturation (approximately 23% salts) and is the largest in area. This solution is transferred to second-stage pans, where the first salts to crystallize are calcium, magnesium, and iron carbonates and sulfates. Then the solution goes to the crystallizing ponds where NaCl crystallizes out. More water is allowed to evaporate until the solution nears the saturation point for the magnesium and potassium chlorides and bromides and other salts (the “bittern” salts), at which point the solution is removed from the pond. The salt precipitated in the crystallizer pond is NaCl in a reasonably pure form and is harvested mechanically.

Solar evaporation is used with feeds other than seawater. Sodium sulfate solutions are concentrated in 440,000-m<sup>2</sup> ponds on the Atacama Desert of Chile for the manufacture of anhydrous sodium sulfate (Suhr, 1970). The Caracol, a solar evaporating process near Mexico, D. F., concentrates brines from the Lake Texcoco area to feed a fuel-fired evaporator plant producing sodium carbonate decahydrate.

Solar evaporation has been of substantial interest for salt production and also for estimation of evaporative losses from water storage reservoirs. A number of studies of the process have been published, including reports of measurements from salt pans (e.g., Bloch et al., 1951) and lakes and reservoirs (e.g., Geological Survey, 1954). (Salt solutions in evaporators will have lower vapor pressures than lake water; otherwise the processes are similar.)

An energy balance over a fully mixed pond is very much like Equation 18.4.1 for the basin of a solar still, but heat is transferred to the atmosphere by evaporation, convection, and radiation rather than to a cover:

$$G\alpha = q_e + q_{r,p-a} + q_{c,p-a} + q_k + (mC_p) \frac{dT_b}{dt} \quad (18.5.1)$$

where  $q_e$ ,  $q_k$ , and capacitance terms have the same significance as for a still and the subscript  $p$  refers to the pond. (For deep ponds that are thermally stratified, the heat capacity term requires more detailed treatment.)

For evaporation from open water surfaces, the ratio of energy transport from the water by convection to that by evaporation has been shown by Bowen (1926) to be nearly constant regardless of wind speed. The ratio is given by

$$\frac{q_{c,p-a}}{q_e} = \frac{0.46(T_p - T_a)}{p_{wp} - p_a} \frac{p}{760} \quad (18.5.2)$$

where  $T_p$  and  $T_a$  are the temperatures of the brine surface and ambient,  $p_{wp}$  and  $p_a$  are the vapor pressure of the surface solution and the ambient vapor pressure of water, and  $p$  is the barometric pressure (with all pressures in millimeters of mercury).

These equations have been applied to evaporation from lakes by Cummings (1946) and others and to evaporation from salt pans by Bloch et al. (1951) [see also Spiegler (1955)]. Bloch et al., in an experimental study of evaporation from brines, measured diurnal temperature variations of solution, temperature gradients in solution during evaporation and at night, and effects of dyes which increase absorptance of the brines for solar radiation.

Net annual evaporation from salt pans in the San Francisco area is usually in the range of 0.9 to 1.1 m with an annual rainfall in the range of 0.25 to 0.5 m, and in dry years the net annual evaporation was 1.2 m (See, 1960). Thus in this area 0.5 to 1 m<sup>3</sup> of water is evaporated per year per square meter of pond.

## 18.6 DIRECT SOLAR DRYING

Direct crop drying is another well-established use of solar energy in which the standard practice is to spread the materials to be dried in thin layers to expose them to radiation and wind. (Indirect drying, by supply of solar-heated air to more or less conventional dryers, was noted in Chapter 16.) The practices of solar drying are based on long experience. Questions regarding further applications concern possible improvements in the process or changes that might be made to improve product quality or dry additional kinds of materials.

The equations describing a radiant drying process can be written in forms similar to those for evaporation from pans. However, several additional phenomena may have to be considered. If the material to be dried is opaque to solar radiation, drying occurs at the surface and moisture is transported to the surface by capillary action or diffusion. As with other drying processes, there may be constant-rate periods when energy balances determine rates of drying (when the surface of the material is always saturated with moisture) and falling-rate periods when moisture transport through the drying material to its surface controls the rate of evaporation. The determination of the vapor pressure of water at the surface of the drying material may be difficult.

In addition to field crops, drying of grapes in tiers of trays has been reported by Wilson (1965), and an analysis of this type of dryer is presented by Selcuk et al. (1974). Experiments on direct drying of an oil shale to reduce its moisture content prior to retorting have been described by Talwalkar et al. (1965). Taylor and Weir (1985) describe an analytical and experimental study of a timber-drying kiln with forced air circulation in which some of the radiation is absorbed in the drying lumber and some in the adjoining structure.

## 18.7 SUMMARY

In this chapter we have briefly described some of the major considerations regarding solar ponds, distillation, evaporation, and direct drying. Much of the information needed in estimating the performance of these processes can be found by methods outlined in earlier chapters. Most are horizontal collectors, some of which have integral storage, and evaporation of water is either an objective or a problem in each of the processes.



## REFERENCES

- Afeef, M. and L. B. Mullett, *Solar & Wind Technol.*, **6**, 1 (1989). "Solar Transmission in Salt Solutions with Reference to Solar Ponds."
- Batty, J. C., J. P. Riley, and Z. Panahi, *Solar Energy*, **39**, 483 (1987). "A Water Requirement Model for Salt-Gradient Solar Ponds."
- Bloch, M. R., L. Farkas, and K. S. Spiegler, *Ind. Eng. Chem.*, **43**, 1544 (1951). "Solar Evaporation of Salt Brines."
- Bowen, I. S., *Phys. Rev.*, **27B**, 779 (1926). "The Ratio of Heat Loss by Conduction and by Evaporation from Any Water Surface."
- Bryant, H. C. and I. Colbeck, *Solar Energy*, **19**, 321 (1977). "A Solar Pond for London?"
- Cooper, P. I., *Solar Energy*, **14**, 451 (1973). "Digital Simulation of Experimental Solar Still Data."
- Cummings, N. W., *Trans. Am. Geophys. Union*, **27**, 81 (1946). "The Reliability and Usefulness of the Energy Equations for Evaporation."
- Delyannis, E. and E. Stefanakos (eds.), *Solar Energy J.*, **75** (5) (2003). Special Issue, Solar Desalination.
- Dunkle, R. V., *International Developments in Heat Transfer*, Conference at Denver, Part 5, p. 895 (1961). "Solar Water Distillation: The Roof Type Still and a Multiple Effect Diffusion Still."
- Geological Survey Professional Paper 269, U.S. Government Printing Office, Washington, DC (1954). "Water Loss Investigations: Lake Hefner Studies, Technical Report."
- Hull, J. R., *Solar Energy*, **25**, 317 (1980). "Membrane Stratified Solar Ponds."
- Hull, J. R., K. V. Liu, W. T. Sha, J. Kamal, and C. E. Nielsen, *Solar Energy*, **33**, 25 (1984). "Dependence of Ground Heat Loss upon Solar Pond Size and Perimeter Insulation: Calculated and Experimental Results."
- Hull, J. R., C. E. Nielsen, and P. Golding, *Salinity Gradient Solar Ponds*, CRC Press, Boca Raton, FL (1989).
- Hull, J. R., A. B. Scranton, J. M. Mehta, S. H. Cho, and K. E. Kasza, Report ANL 86-17, Argonne National Laboratory, Argonne, IL (1986). "Heat Extraction from the ANL Research Salt-Gradient Solar Pond."
- Kooi, C. F., *Solar Energy*, **23**, 37 (1979). "The Steady State Salt-Gradient Solar Pond."
- Morse, R. N. and W. R. Read, *Solar Energy*, **12**, 5 (1968). "A Rational Basis for the Engineering Development of a Solar Still."
- Nielsen, C. E., *Proc. 1978 Annu. Meeting Am. Sect. ISES*, **2** (1), 932 (1978). "Equilibrium Thickness of the Stable Gradient Zone in Solar Ponds."
- Nielsen, C. E., in *Advances in Solar Energy*, Vol. 4 (K. Boer, ed.), American Solar Energy Society and Plenum Press, New York, **4**, p. 445 (1988). "Salinity-Gradient Solar Ponds"
- Proctor, D., *Solar Energy*, **14**, 433 (1973). "The Use of Waste Heat in a Solar Still."
- Rabl, A. and C. E. Nielsen, *Solar Energy*, **17**, 1 (1975). "Solar Ponds for Space Heating."
- See, D. S., in *Sodium Chloride: The Production and Properties of Salt and Brine* (D. W. Kaufman, ed.), American Chemical Society, Washington, DC, Monograph 145, Chapter 6 (1960). "Solar Salt."
- Selcuk, M. K., O. Ersay, and M. Akyurt, *Solar Energy*, **16**, 81 (1974). "Development, Theoretical Analysis and Performance Evaluation of Shelf Type Solar Dryers."
- Spiegler, K. S., in *Solar Energy Research* (F. Daniels and J. A. Duffie, eds.), University of Wisconsin Press, Madison, WI, p. 119 (1955). "Solar Evaporation of Salt Brines in Open Pans."
- Suhr, H. B., Paper No. 4/27 presented at the International Solar Energy Society Conference, Melbourne (1970). "Energy-Balance Calculations on the Production of Anhydrous Sodium Sulfate with Solar Energy and Waste Heat."
- Tabor, H., *Proc. UN Conf. New Sources of Energy*, **4**, 59 (1964). "Large Area Solar Collectors (Solar Ponds) for Power Production."

- Tabor, H. and R. Matz, *Solar Energy*, **9**, 177 (1965). "Solar Pond Project."
- Tabor, H. and Z. Weinberger, in *Solar Energy Handbook* (J. Kreider and F. Kreith, eds.), McGraw-Hill, New York (1981). "Nonconvecting Solar Ponds."
- Talbert, S. B., J. A. Eibling, and G. O. G. Löf, *Manual on Solar Distillation of Saline Water*, Research and Development Progress Report No. 546, Office of Saline Water, U.S. Department of Interior, Washington, DC, (1970).
- Talwalkar, A. T., J. A. Duffie, and G. O. G. Löf, *Proc. UN Conf. New Sources of Energy*, **5**, 284 (1965). "Solar Drying of Oil Shale."
- Taylor, K. J. and A. D. Weir, *Solar Energy*, **34**, 249 (1985). "Simulation of a Solar Timber Dryer."
- United Nations Department of Economic and Social Affairs, *Solar Distillation*, Publication Sales No. E. 70. II. B. 1, New York (1970).
- Weinberger, H., *Solar Energy*, **8**, 45 (1964). "The Physics of the Solar Pond."
- Wilkins, E. S. and T. K. Lee, *Solar Energy*, **39**, 33 (1987). "Development of the Gel Pond Technology."
- Wilson, B. W., *Proc. UN Conf. New Sources of Energy*, **5**, 296 (1965). "The Role of Solar Energy in the Drying of Vine Fruit."
- Wittenberg, L. J. and D. E. Etter, paper presented at ASME Meeting, Phoenix (1982). "Heat Extraction from a Large Solar Pond."

# Part III

---

## DESIGN METHODS

In Part I we treated fundamentals of solar processes and in Part II we described applications of these fundamental ideas to several practical processes. In Part III, we consider methods of estimation of long-term thermal performance of solar energy processes, an essential step in their design.

Chapter 19 is on simulations. These are detailed transient thermal performance calculations. Parallels are drawn between these numerical experiments and the physical experiments that are necessary in order to have confidence in the calculations. A brief description of a transient process simulation program TRNSYS is provided and examples of its use are included. Simulations are shown to be clearly warranted in the design of large, one-of-a-kind, or experimental systems.

Chapters 20 to 22 are discussions of methods for substituting monthly calculations for the detailed calculations of simulations. These “design methods” are based on correlations of the results of many numerical experiments (simulations) or on utilizability concepts. A range of active and passive system types are treated in these chapters.

Chapter 23 is unique in that it treats a process that is not thermal in nature, that is, photovoltaic (PV) processes, but it builds on the same background information and systems approach that we use for thermal processes. A brief, qualitative description of solar cells is provided, followed by discussion of generator and system models, and then a design procedure that is applicable for determining the long-term output of many PV systems.

Chapter 24 is on wind energy, an indirect form of solar energy. The first sections cover general wind ideas that lead to an understanding of wind statistics. The next section presents the fundamentals governing wind power and the transformation of wind power into mechanical power as the wind passes through a wind machine. The aerodynamics of turbine blades and the flow of wind over irregular ground or around obstacles are not covered as they are beyond the scope of this chapter. A design procedure for predicting the long-term performance of isolated wind machines is presented.

# Simulations in Solar Process Design

In Chapter 10 the basic concepts of simulation were developed, that is, the simultaneous solutions of the sets of equations (models) that describe the performance of solar processes. Example 10.9.1 is a simulation, albeit a simple one amenable to hand calculation. In Chapters 12 through 18, the parametric studies of applications that were presented were developed using simulations. This chapter carries the use of simulations a step further and treats the application of simulations to the design of specific processes.

Simulations, like any other calculations, are only as good as the models that are the basis of the programs and the skill with which they are used. There have been over five decades of experience with simulations, and considerable effort has been placed on validations. There have been detailed intercomparisons of simulation programs that were developed independently by authors in various countries. There have been experimental studies of component performance that are (with theory) the basis of confidence in component models. There have been detailed comparisons of simulations with measurements on the operation of systems. The conclusion to be drawn from these validations is that if simulations are properly used, they can provide a wealth of information about solar processes and thermal design.

This chapter includes a brief description of TRNSYS (see Klein et al., 2012), a transient process simulation program developed for study of solar processes, and its applications. Examples are shown of the kinds of information that simulations and experiments can provide and illustrate the use of a simulation program to determine dynamic system behavior and integrated performance. Comparisons of physical measurements and simulations are discussed, and problems and limitations of simulations are noted. The program CombiSys described in the Introduction is an example of TRNSYS running with the TRANSED front end.

## 19.1 SIMULATION PROGRAMS

The use of simulation methods in the study of solar processes is a relatively recent development. Sheridan et al. (1967) used an analog computer in simulation studies of operation of solar water heaters. Gupta and Garg (1968) developed a model for thermal performance of a natural circulation solar water heater with no load, represented solar radiation and ambient temperature by Fourier series, and were able to predict a day's performance in a manner that agreed substantially with experiments. Close (1967) used

numerical modeling and a factorial design method to determine which water heater system design factors are most important. Gupta (1971) used a response factor method that is amendable to hand calculation for short-term process operation. Buchberg and Roulet (1968) developed a thermal model of a house heating system, simulated its operation with a year's hourly meteorological data, and applied a pattern search optimization procedure in finding optimum designs. Other process simulations have been done by Löf and Tybout (1973), Butz et al. (1974), and Oonk et al. (1975). Since these early publications, solar process simulation programs have come into widespread use.

Some of the programs that have been applied to solar processes have been written specifically for study of solar energy systems. Others were intended for nonsolar applications but have had models of solar components added to them to make them useful for solar problems. The common thread in them is the ability to solve the combinations of algebraic and differential equations that represent the physical behavior of the equipment. Simulation programs fall into two general categories. The first includes those that are "special-purpose" programs that represent the performance of specific types of systems. In these programs, the equations for the components are combined algebraically to simplify the computations and are generally easy to use but are not flexible. Programs in the second category, the general-purpose programs, are more flexible and can be applied to a wide range of systems but are more difficult to use. In these programs, the equations representing components (collectors, storage units, pumps, etc.) are kept separate and are solved simultaneously rather than being combined algebraically.

Over the past two decades hundreds of programs have been written to study energy efficiency, renewable energy, and sustainability in buildings. The U.S. Department of Energy lists 293 building software tools in its 2005 Energy Efficiency and Renewable Energy web page. These programs evolve with time, and their exact nature can only be recorded as of a particular time. TRNSYS, the program to be described below that in 2012 was available in version 17.1, has undergone 12 major revisions and many more minor changes and is a far more powerful program than it was when it first became available in 1977.

## 19.2 UTILITY OF SIMULATIONS

Simulations are numerical experiments and can give the same kinds of thermal performance information as can physical experiments. They are, however, relatively quick and inexpensive and can produce information on effect of design variable changes on system performance by a series of numerical experiments all using exactly the same loads and weather. These design variables could include selectivity of the absorbing surface, number of covers on the collector, collector area, and so on. With cost data and appropriate economic analysis, simulation results can be used to find least cost systems.

Simulations are uniquely suited to parametric studies and thus offer to the process designer the capability to explore the effects of design variables on long-term system performance. They offer the opportunity to evaluate effects of system configuration and alternative system concepts. They have the advantage that the weather used to drive them is reproducible, allowing parametric and configuration studies to be made without uncertainties of variable weather. By the same token, a system can be "operated" by simulations in a wide range of climates to determine the effects of weather on design.

Simulations are complementary to physical experiments. Component-scale experiments are necessary to understand component behavior and lend confidence to the corresponding mathematical models. System-scale experiments are necessary to bring to light the many practical problems inherent in any complicated system that simulations cannot fully model. Careful comparisons of experiments and simulations lead to improved understanding of each. Once simulations have been verified with experiments, new systems can be designed with confidence using simulation methods.

In principle, all of the physical parameters of collectors, storage, and other components are the variables that need to be taken into account in the design of solar processes. The number of parameters that must be considered may be quite small, as there is a backlog of experience which indicates that the sensitivity of long-term performance or process economics to many parameters is small. For the solar heating of a building, for example, the primary system design variable is collector area, with storage capacity and other design variables being of secondary importance provided they are within reasonable bounds of good design practice (as noted in Chapter 13). Simulations can provide information on effects of collector area (or other variables) which is essentially impossible to get by other means.


### 19.3 INFORMATION FROM SIMULATIONS

The parallels between numerical experiments (simulations) and physical experiments are strong. In principle, it is possible to compute what it is possible to measure. In practice, it may be easier to compute than to measure some variables (e.g., temperatures in parts of a system that are inaccessible for placement of temperature sensors). Simulations can be arranged to subject systems to extremes of weather, loads, or other external forces. They also can be used to interject faults in a system (e.g., a failure in a circulating pump) to see what the effects of the fault would be.

There are two basic kinds of data that can be obtained from simulations. First, integrated performance over extended periods can be determined. This is normally wanted for a year that represents the long-term average climate in which a proposed process would operate. A year is the time base of most economic studies, but information may be needed for other periods from days to spans of many years. These data are readily obtained by integrating the desired quantities (collector output, tank losses, pump or blower on time, heat exchange across an exchanger, amount of auxiliary energy required, etc.) over the appropriate time period.

Second, information on process dynamics is available. The selection of materials of construction may be affected by the temperature excursions through which the component goes in either normal or abnormal operation. Pressure on liquid systems is determined by temperatures in the various parts of the liquid loops. For example, temperatures in the tops of storage tanks in systems with collector heat exchangers may be moderate, but temperatures in the collector outlets may be well above the boiling point, and pressure relief valves may be needed on collector outlets as well as on tanks.

A year's operation of a solar heating system for a residence in the Madison, Wisconsin, climate has been simulated. The building has 150 m<sup>2</sup> floor area, is well insulated, and is to have a solar heating and hot-water system to supply part of the heating load. Collector area



**Figure 19.3.1** (a) Thermal performance of a solar space and water heating system showing the fraction of annual heating and hot-water loads carried by solar energy as function of collector area, (b) Thermal performance of a solar water heating system showing the fraction of annual hot-water loads carried by solar energy as function of collector area.


is the primary design variable. Values of other design parameters were selected to represent good design practice, including collector characteristics and ratio of storage capacity to collector area. Integration of delivered solar energy and auxiliary energy required at several collector areas give information on the solar fraction  $\mathcal{F}$ , the fraction of annual heating and hot-water loads carried by solar energy, that is, on the amount of energy usefully delivered to the building from the solar energy system. This is shown in Figure 19.3.1(a). A similar curve for water heating only is shown in Figure 19.3.1(b), but it is more nearly linear over a wide range of collector areas than the solar heating fraction (primarily because the loads and solar radiation are more evenly matched throughout the whole year in this application).

A two-week example of temperature variation with time is shown in Figure 19.3.2 for two collector areas for a space and water heating system. These data, if examined for the whole year (or for those periods in the year when temperatures are likely to go to extremes), provides an indication of the magnitude of safety problems which must be addressed by providing means to “dump” energy.

Other kinds of information can also be obtained. It is possible to estimate the times at which auxiliary energy is needed and the relationship of those times to meteorological conditions. It is possible to estimate storage unit losses. In general, any variable that appears in the set of system equations can be investigated.

## 19.4 TRNSYS: THERMAL PROCESS SIMULATION PROGRAM

TRNSYS (Klein et al., 1975, 1976, 2012) is a widely used, modular thermal process simulation program. Originally developed for solar energy applications, it now is used for simulation of a wider variety of thermal processes. Subroutines are available that represent



**Figure 19.3.2** Tank temperature versus time for two-week period in March for a heating and hot-water system for Madison, WI, assuming a fully mixed tank, for two collector areas and fixed storage-collector area ratio.

the components in typical solar energy systems. A list of the components and combinations of components in the TRNSYS library (as of 2005) is shown in Table 19.4.1. Users can readily write their own component subroutines if they are not satisfied with those provided. By a simple language, the components are “connected” together in a manner analogous to piping, ducting, and wiring in a physical system. The programmer also supplies values for all of the parameters describing the components to be used. The program does the necessary simultaneous solutions of the algebraic and differential equations which represent the components and organizes the input and output. Varying levels of complexity can be used in the calculation. For example, a flat-plate collector can be represented by constant values of  $F_R U_L$  and  $F_R (\tau\alpha)$  or it can be represented by values of  $U_L$  and  $(\tau\alpha)$ , which are calculated at each time step for the conditions that change through time as the simulation proceeds. The user of the program must determine how detailed the simulation is to be; the more detail, the higher the cost in terms of programming effort and computer time. Most of the simulation studies reported in preceding chapters on specific solar application were done with TRNSYS.

Current versions of TRNSYS have, in the executive program, convergence promoters and other means of speeding computations. There are three integration algorithms in TRNSYS; the user can choose the one best suited to the problem at hand. The one that is extensively used is the Modified-Euler method. It is essentially a first-order predictor-corrector algorithm using Euler’s method for the predicting step and the trapezoid rule for the correcting step. The advantage of a predictor-corrector integration algorithm for solving simultaneous algebraic and differential equations is that the iterative calculations occurring during a single time step are performed at a constant value of time. (This is not the case for the Runge–Kutta algorithms.) As a result, the solutions to the algebraic equations of the system converge, by successive substitution, as the iteration required



**Table 19.4.1** Components in Standard Library of TRNSYS

<b>Controller components</b>	<b>Hydronics</b>
Differential controller with hysteresis	Pumps (various)
Three-stage room thermostat	Tee-piece, flow mixer, flow diverter, tempering valve
Iterative feedback controller	Pressure relief valve
Proportional-integral-differential (PID) controller (in heating)	Pipe
Microprocessor controller	Duct
Five-stage room thermostat	Fans (various)
<b>Electrical components</b>	<b>Building loads and structures</b>
Shepherd and Hyman battery models	Energy/(degree-hour) house
Regulators and inverters	Roof and attic
Photovoltaic (PV) thermal collector	Detailed zone (transfer function)
Wind energy conversion system (wind turbines)	Overhang and wingwall shading
Photovoltaic array	Window
Diesel Engine Generator Set (DEGS) dispatch controller	Thermal storage wall
Diesel Engine Generator Set (DEGS)	Attached sunspace
Power conditioning	Detailed multizone building
Lead-acid battery (with gassing effects)	Lumped-capacitance building
Alternating-current bus bar	
<b>Heat exchangers</b>	<b>Output devices</b>
Constant-effectiveness heat exchanger	Printer
Counterflow heat exchanger	Histogram plotter
Cross-flow	Simulation summarizer
Parallel flow	Economics
Shell and tube	Online plotter
Waste heat recovery	
<b>Heating, ventilation, and air conditioning (HVAC) equipment</b>	<b>Physical phenomena</b>
Auxiliary heaters	Solar radiation processor
Dual-source heat pumps	Collector array shading
Cooling coils (simplified and detailed models)	Psychrometrics
Conditioning equipment	Hourly weather data generator
Part-load performance	Refrigerant properties
Cooling towers	Shading by external objects
Parallel chillers	Effective sky temperature calculation
Auxiliary cooling unit	Undisturbed ground temperature profile
Single-effect hot-water-fired absorption chiller	Convective heat transfer coefficient calculation
Furnace	
<b>Hydrogen systems</b>	<b>Solar collector components</b>
Electrolyzer controller	Flat-plate solar collector
Master level controller for stand alone power systems	Thermosyphon collector with integral storage
Advanced alkaline electrolyzer	Evacuated-tube solar collector
Compressed gas storage	Performance map solar collector
Multistage compressor	Theoretical flat-plate solar collector
Fuel cells (PEM and alkaline)	Compound parabolic trough (CPC) solar collector
	<b>Thermal storage components</b>
	Stratified fluid storage tank
	Rock bed thermal storage
	Algebraic tank (plug flow)

**Table 19.4.1** (Continued)

<b>Utility components</b>	Variable-volume tank
Data file reader	Detailed fluid storage tank with optional heaters and variable internal timestep
Time-dependent forcing function	Input value recall
Quantity integrator	Holiday calculator
Load profile sequencer	Utility rate scheduler
Periodic integrator	Calling CONTAM
Unit conversion routine	Calling MATLAB
Calling Excel worksheets	Calling COMIS
Calling Engineering Equation Solver (EES) routines	
Parameter replacement	<b>Weather data reading and processing</b>
Formatted file data reader (TRNSYS TMY, TMY2, EnergyPlus)	Standard format files
	User format files

solving the differential equation progresses. The calculation scheme can be described in the following manner.

At time  $t$ , the values of the dependent variables  $T^p$  are predicted using their values,  $T_o$ , and the values of their derivatives,  $(dT/dt)_o$ , from the previous time step:

$$T^p = T_o + \Delta t \left( \frac{dT}{dt} \right)_o \quad (19.4.1)$$

where  $T^p$  is the predicted value of all of the dependent variables at time  $t$  (note that this prediction step is exactly the method used to integrate Example 19.3.1);  $T_o$  is the value of the dependent variables at time  $t - \Delta t$ ;  $\Delta t$  is the time step interval at which solutions to the equations of the system model will be obtained; and  $(dT/dt)_o$  is the value of the derivative of the dependent variables at time  $t - \Delta t$ .

The predicted values of the dependent variables,  $T^p$ , are then used to determine corrected values,  $T^c$ , by evaluating their derivatives,  $(dT/dt)$ , as a function  $t$ ,  $T^p$ , and the solutions to the algebraic equations of the model:

$$\frac{dT}{dt} = f(t, T^p, \text{algebraic solutions}) \quad (19.4.2)$$

The corrected values of the dependent variables,  $T^c$ , are obtained by applying the trapezoidal rule:

$$T^c = T_o + \frac{\Delta t}{2} \left[ \left( \frac{dT}{dt} \right)_o + \frac{dT}{dt} \right] \quad (19.4.3)$$

if

$$\frac{2(T^c - T^p)}{T^c + T^p} > \varepsilon \quad (19.4.4)$$

where  $\varepsilon$  is an error tolerance,  $T^p$  is set equal to  $T^c$ , and application of Equations 19.4.2 and 19.4.3 is repeated. When the error tolerance is satisfied, the solution for that time step is complete and the whole process is repeated for the next time step.

As an illustration of the use of the general program TRNSYS for simulating a solar energy system and the nature of the results that can be obtained by simulations, consider the following example.

### Example 19.4.1

A hot-water load of 3000 kg water/day at a minimum temperature of 60°C is evenly distributed between the hours of 0700 and 2100. This load is to be met in substantial part by a solar collector assembly of total effective area 65.0 m<sup>2</sup>. The two-cover collector has the following characteristics:

$$\text{Tilt} = \beta = 40^\circ \quad \text{to south}$$

$$U_L = 4.0 \text{ W/m}^2 \text{ } ^\circ\text{C}$$

$$(\tau\alpha) = 0.77$$

$$F' = 0.95$$

$$\text{Flow rate through collector} = \dot{m}_c = 0.903 \text{ kg/s}$$

The tank has the following characteristics:

$$V = 3.9 \text{ m}^3$$

$$\text{Height-diameter ratio} = 3$$


$$\text{Loss coefficient } U_L = 0.40 \text{ W/m}^2 \text{ } ^\circ\text{C}$$


$$\text{Ambient temperature at tank} = 21^\circ\text{C}$$

$$\text{Supply water to tank} = 15^\circ\text{C}$$

The auxiliary heater is controlled such that if the temperature of the water from the tank is less than 60°C, it will heat the water from the storage tank temperature to 60°C. If  $T_s > 60^\circ\text{C}$ , the water delivered to meet the load will be at a temperature above 60°C.

The system shown in the first diagram is to be operated at Boulder, Colorado, latitude 40° N, for a week in January. Hourly values of solar radiation and ambient temperature are as shown in the plots and are the same data as given in Table 2.5.2. Assuming that the initial tank temperature is 60°C, compute the percentage of the load that is carried by solar energy.





### Solution


Solution to this problem was obtained using TRNSYS. A summary of the results is given in the table below. Two solutions are shown, one for an unstratified storage tank and one for a three-node approximation to a stratified storage tank. The load requirement is a fixed amount of water at a temperature of at least 60°C; the two energy deliveries are slightly different, as the stratified tank delivers water at slightly higher temperature. The minimum total load is 3.96 GJ, and both systems slightly exceed this since the delivery temperature sometimes exceeds 60°C. The percentages of the total energy supplied to the water by solar energy for the two cases are  $(2.74/4.04)100 = 68\%$  and  $(3.03/4.10)100 = 74\%$ . The amount of auxiliary energy that is required in the two cases is 1.30 GJ for the unstratified

#### • Case 1 Unstratified Storage Tank:

End of Day	Cumulative Energy			Change of Energy of Tank	Cumulative Energy		Total Load
	Incident Solar	Useful Gain	Thank Loss		Supplied from Tank	Supplied from Auxiliary	
1	0.71	0.21	0.02	-0.27	0.46	0.10	0.56
2	1.34	0.43	0.03	-0.38	0.78	0.35	1.13
3	2.84	1.17	0.04	-0.11	1.24	0.47	1.71
4	2.95	1.17	0.05	-0.45	1.57	0.71	2.28
5	3.34	1.28	0.05	-0.53	1.76	1.00	2.76
6	4.87	2.09	0.07	-0.13	2.15	1.26	3.41
7	6.43	2.81	0.08	-0.01	2.74	1.30	4.04

• **Case 2 Three-Section Storage Tank:**

End of Day	Cumulative Energy			Change of Energy of Tank	Cumulative Energy		
	Incident Solar	Useful Gain	Thank Loss		Supplied from Tank	Supplied for Auxiliary	Total Load
1	0.71	0.24	0.02	−0.30	0.52	0.05	0.57
2	1.34	0.50	0.03	−0.42	0.89	0.25	1.14
3	2.84	1.28	0.04	−0.15	1.39	0.34	1.73
4	2.95	1.28	0.05	−0.58	1.81	0.50	2.31
5	3.34	1.42	0.05	−0.60	1.97	0.90	2.87
6	4.87	2.27	0.06	−0.18	2.39	1.06	3.45
7	6.43	3.05	0.08	−0.06	3.03	1.07	4.10



tank and 1.07 GJ for the three-node tank. If a conventional water heater were designed to deliver exactly the minimum energy required (3.96 GJ), the savings in purchased energy would have been 2.66 and 2.89 GJ, respectively.

Plots of cumulative energy quantities versus time for the week are shown for the case of the stratified tank. The points for the totals at the end of each day are connected by straight lines but smoother plots could have been obtained by using smaller time intervals. The tables are summaries of integrated energy quantities. All energy quantities are in gigajoules. ■

## 19.5 SIMULATIONS AND EXPERIMENTS

The extent to which simulations represent the operation of real physical systems depends on the level of detail included in the numerical experiment. Component models can vary in complexity, as can systems. In principle, simulations can be as detailed as the user wishes. In practice, there may be factors in system operation which are difficult to simulate, such as leaks in air systems, and operation of real systems may be less ideal than the simulation indicates.


Many component experiments have been carried out, for example, the kind noted in Chapter 6 on flat-plate collectors. Some comparisons of simulations and experiments of building heating have been made of both short-term process dynamics and long-term integrated performance. For example, Mitchell et al. (1980) have used tank temperatures and integrated energy quantities as indicators of process operation and compared measured and computed tank temperatures and energy quantities over several 10-day periods from CSU House I. An example of a tank temperature comparison is shown in Figure 19.5.1.

Comparisons of the simulated and measured useful energy gain from the collector and solar auxiliary contribution are shown in Table 19.5.1. In this study, the simulation was very carefully done to closely represent the physical situation; by doing so, it was possible to obtain agreements that are comparable to the accuracy of the measurements on the physical system.

## 19.6 METEOROLOGICAL DATA

Weather conditions and loads can be considered as forcing functions operating on the sets of equations that describe system performance. As noted in Chapter 9, loads may be functions of weather for building heating and cooling or they may be determined by factors not related to weather. Meteorological data, including solar radiation, ambient temperature, and wind speed, influence collector performance, and information such as that in Table 2.5.2 is needed to calculate system performance over time.

All simulations are done with past meteorological data, and it is necessary to select a data set to use in simulations. For studies of process dynamics, data for a few days or weeks may be adequate if they represent the range of conditions of interest. For design purposes it is best to use a full year's data or a full season's data if the process is a seasonal one. Data



**Figure 19.5.1** Comparisons of measured and predicted storage tank temperatures for CSU House I. Adapted from Pawleski (1976).

**Table 19.5.1** Comparison of Simulated and Measured Energy Quantities from CSU House I from Three Different Time Periods<sup>a</sup>

	Period	Measured (MJ)	Simulated (MJ)	Difference (%)
Collected solar energy	I	2388	2577	7.0
	II	2419	2292	5.2
	III	2086	2012	3.5
Air heater heat flow	I	2076	2041	1.4
	II	3243	3238	0.0
	III	1810	1736	3.6
Delivered solar energy	I			
	II	1952	2025	3.1
	III	1517	1573	2.7
Auxiliary energy	I	0	0	0.0
	II	1291	1213	3.3
	III	238	162	3.7
Preheater heat flow	I	398	303	3.8
	II	132	116	0.7
	III	204	132	3.5

<sup>a</sup>From Mitchell et al. (1980).

are available for many years for some stations, and it is necessary to select a satisfactory set. Klein (1976) developed the concept of a **design year**. He used heating season data for nine months for each of eight years. For each of the months (e.g., the Januarys) the month was selected that had the radiation closest to the eight-year average. Monthly average temperatures were used as a secondary criterion where needed. The set of months so selected constituted the design year. Discontinuities between months normally cause no difficulty. The selection of the design year was evaluated by simulations. Table 19.6.1 shows the results of this procedure and indicates the annual fraction of heating loads carried by solar energy for two collector areas for a particular building for the design year and for the full eight years. The design year provides a good representation of the eight-year period, at least for purposes of simulating solar heating systems.

A related but more detailed study by Hall et al. (1978) of 23 years of data for each of 26 stations in the U.S. solar radiation network has led to the generation of **typical meteorological year** (TMY) data for these and additional locations. The TMY data for Madison have been used in heating system simulations and the results compared to those based on the full 23 years of data. In one comparison the TMY data indicated a solar contribution of 0.60, and the value for the full 23-year simulation was 0.58. The TMY data for the United States has been replaced by TMY2 data derived from measurements at 239 U.S. cities for the years 1961 to 1990. TMY3 data (for the years 1991 to 2005) is available for 1020 U.S. locations. Solar radiation data were measured in only a few of these locations and statistical techniques were used to estimate hourly values in locations without solar measurements. The TMY, TMY2, and TMY3 data cannot be used interchangeably due to differences in time (solar versus local), formats, data types, and units. Version 5 of the METEONORM program by Remund and Kunz (2003) has a database of over 7000

**Table 19.6.1** 19.6.1 Design (Heating Season) Year for Madison Based on Eight Years of Data (1948–1949 to 1955–1956)<sup>a</sup>

Month	Year	Solar Fractions	
		Area 1	Area 2
September	1951–1952	0.97	1.00
October	1955–1956	0.79	0.98
November	1949–1950	0.35	0.63
December	1949–1950	0.26	0.49
January	1953–1954	0.23	0.43
February	1954–1955	0.36	0.66
March	1953–1954	0.53	0.85
April	1955–1956	0.72	0.96
May	1952–1953	0.77	0.98
Annual contribution		0.47	0.69
Annual contribution for 8 years		0.47	0.67

<sup>a</sup>From Klein (1976).

worldwide stations that can generate data on monthly, daily, or hourly time scales on surfaces of any orientation.

Caution must be exercised in the use of typical years if the process to be designed is to provide a high fraction of the loads by solar energy. Years that are far from the average years tend to include unusual sequences or extremes of weather, and the results of simulations based on the typical year data may be significantly different from the long-term average for systems with high solar fraction. Also, year-to-year variation in weather will lead to significant year-to-year variation in a solar process output, and a performance prediction based on a typical year will not apply for a specific year unless that year happens to be nearly the same as the typical year. Schmitt et al. (2000) have developed algorithms for generating extreme-weather data sequences.

Another approach to the use of existing meteorological data is to synthesize from it data for shorter periods which, when used in simulations, will provide information on longer periods of operation. For example, Anand et al. (1978) have worked out a two-step procedure for condensing data. First, they statistically arrange the data (insolation and temperature) to place it in bins (ranges of data pairs). For these data pairs, they curve fit expressions for diurnal variation of insolation and temperature to get a small number of synthesized days which are representative of a large number of actual days.

Another approach to development of meteorological data is to synthesize sequences of hours and days, starting from the means, with the synthesized sequences having the same means, the same distributions, the same autocorrelations, and (ultimately) the same cross correlations between one meteorological variable and another as the real data. This procedure has the advantage that it would allow generation of data for locations for which only monthly means are available. Based on the original work of Degelman (1976), Knight et al. (1991) used a combination of autoregression models for solar radiation and ambient temperature to generate data that have statistics comparing favorably with TMY data. An Hourly Weather Data Generator based upon these algorithms is available in TRNSYS.



Information on time dependence of loads must also be available if simulations are to be done. The general approach to determination of loads is the same as other parts of a system, that is, develop the set of equations or numerical data that relate energy rates and temperatures to time. These load characteristics are then solved as part of the overall set of equations that describe the solar process.

The usual situation is to have the loads on a nonsolar system the same as those on a solar energy system designed for the same task. However, there are many systems where the total amount of energy to be supplied is influenced by the solar energy system. For example, solar water heating systems with tanks larger than conventional tanks will have larger losses and consequently increased loads. Passively heated buildings will have loads that depend on the size of the solar aperture, as the heat losses per unit area through the aperture will in general be more than through well-insulated walls.

## 19.7 LIMITATIONS OF SIMULATIONS

Simulations are powerful tools for process design, for study of new processes, and for understanding how existing systems function and might be improved. However, there are limits to what can be done with them.

First, there is implicit in this discussion of simulations the assumption that they are properly done. It is easy to make program errors, assume erroneous constants, neglect factors which may be important, and err in a variety of other ways. As in other engineering calculations, a high level of skill and judgment is required in order to produce useful results.

As noted above, it is possible, in principle, to model a system to whatever degree is required to extract the desired information. In practice, it may be difficult to represent in detail some of the phenomena occurring in a system. Physical world realities include leaks, plugged or restricted pipes, scale on heat exchangers, failure of controllers, poor installation of equipment, and so on. The simulations discussed here are of the thermal processes but mechanical and other considerations can affect the thermal performance of systems.

There is no substitute for carefully conceived and carefully executed experiments. Such experiments will reveal whether or not the theory is adequate and where difficulties lie in design and operation of the systems. At its best, a combination of numerical experiment (simulation) and physical experiment will lead to better systems, better understanding of how processes work, better knowledge of what difficulties can be expected and what can be done about them, and what next logical steps should be taken in the evolution of new systems.

Simulations and development laboratory experiments are complementary. Comparisons of the results of measurements in the field of performance of purchased and installed systems with simulations have in some instances shown greater differences than those with experiments. The reasons are two. First, field measurements are often very difficult to make, and differences may be ascribed to poor measurements. Second, commercially installed systems are not always built and operated with the same care and knowledge as laboratory systems, and they may not work as well as laboratory systems.

In brief, simulations are powerful tools for research and development, for understanding how systems function, and for design. They must, however, be done with care and skill.

## REFERENCES

- Anand, D. K., I. N. Dief, and R. W. Allen, Paper 78-WA/Sol-16, ASME, San Francisco (1978). "Stochastic Predictions of Solar Cooling System Performance."
- Buchberg, H. and J. R. Roulet, *Solar Energy*, **12**, 31 (1968). "Simulation and Optimization of Solar Collection and Storage for House Heating."
- Butz, L. W., W. A. Beckman, and J. A. Duffie, *Solar Energy*, **16**, 129 (1974). "Simulation of a Solar Heating and Cooling System."
- Close, D. J., *Solar Energy*, **11**, 112 (1967). "A Design Approach for Solar Processes."
- Degelman, L. O., *ASHRAE Trans. Symp. Weather Data*, Seattle, WA, p. 435 (1976). "A Weather Simulation Model for Building Energy Analysis."
- Gupta, C. L., *Solar Energy*, **13**, 301 (1971). "On Generalizing the Dynamic Performance of Solar Energy Systems."
- Gupta, C. L. and H. P. Garg, *Solar Energy*, **12**, 163 (1968). "System Design in Water Heaters with Natural Circulation."
- Hall, I. J., R. R. Prairie, H. E. Anderson, and E. C. Boes, *Proc. 1978 Annu. Meeting Am. Sect. ISES*, Denver, **2** (2), 669 (1978). "Generation of a Typical Meteorological Year."
- Klein, S. A., Ph.D., *Thesis*, University of Wisconsin-Madison (1976). "Design Procedure for Solar Heating Systems."
- Klein, S. A. and W. A. Beckman, *ASHRAE Trans.*, **82**, 623 (1976). "TRNSYS—A Transient Simulation Program."
- Klein, S. A., P. I. Cooper, T. L. Freeman, D. M. Beckman, W. A. Beckman, and J. A. Duffie, *Solar Energy*, **17**, 29 (1975). "Method of Simulation of Solar Processes and Its Application."
- Klein, S. A., et al., *TRNSYS Users Manual*, Version 17, University of Wisconsin Solar Energy Laboratory, Madison, Wisconsin, (2012). [The first public version was 7 (1976).]
- Knight, K. M., S. A. Klein, and J. A. Duffie, *Solar Energy*, **46**, 109 (1991). "Methodology for the Synthesis of Hourly Weather Data."
- Löf, G. O. G. and R. A. Tybout, *Solar Energy*, **14**, 253 (1973). "Cost of House Heating with Solar Energy."
- Mitchell, J. W., W. A. Beckman, and M. J. Pawelski, *Trans. ASME J. Solar Energy Eng.*, **102**, 192 (1980). "Comparisons of Measured and Simulated Performance for CSU Solar House I."
- Oonk, R. L., W. A. Beckman, and J. A. Duffie, *Solar Energy*, **17**, 21 (1975). "Modeling of the CSU Heating /Cooling System."
- Pawelski, M. J., *M.S. Thesis, Mechanical Engineering*, University of Wisconsin-Madison (1976). "Development of Transfer Function Load Models and Their Use in Modeling the CSU House I."
- Remund, J. and S. Kunz, METEONORM program Version 5.0, METEOTEST, Bern, Switzerland, (2003)
- Schmitt, D., S. A. Klein, and D. T. Reindl, *ASHRAE Trans.*, **106** (1), 158 (2000). "Automated Generation of Hourly Design Sequences."
- Sheridan, N. R., K. J. Bullock, and J. A. Duffie, *Solar Energy*, **11**, 69 (1967). "Study of Solar Processes by Analog Computer."

## Design of Active Systems: $f$ -Chart

The liquid and air system configurations described in Section 13.2 are common configurations, and there is considerable information and experience on which to base designs. For residential-scale applications, where the cost of the project does not warrant the expense of a simulation, performance predictions can be done with “short-cut” methods. Design procedures are available for many of these systems that are easy to use and provide adequate estimates of long-term thermal performance. In this chapter we briefly note some of these methods. The  $f$ -chart method, applicable to heating of buildings where the minimum temperature for energy delivery is approximately 20°C, is outlined in detail. Methods for designing systems delivering energy at other minimum temperatures, as encountered in solar absorption air conditioning or industrial process heat applications, are presented in Chapter 21.

### 20.1 REVIEW OF DESIGN METHODS

Design methods for solar thermal processes can be put in three general categories, according to the assumptions on which they are based and the ways in which the calculations are done. They produce estimates of annual useful outputs of solar processes, but they do not provide information on process dynamics.

The first category applies to systems in which the collector operating temperature is known or can be estimated and for which critical radiation levels can be established. The first of these, the utilizability methods, are based on analysis of hourly weather data to obtain the fraction of the total month’s radiation that is above a critical level.<sup>1</sup> Another example in this category is the heat table method of Morse as described by Proctor (1975). This is a straightforward tabulation of integrated collector performance as a function of collector characteristics, location, and orientation, assuming fixed fluid inlet temperatures.

The second category of design methods includes those that are correlations of the results of a large number of detailed simulations. The  $f$ -chart method of Klein et al. (1976, 1977) and Beckman et al. (1977) is an example. The results of many numerical experiments (simulations) are correlated in terms of easily calculated dimensionless variables. The results of the  $f$ -chart method have served as the basis for further correlations, for example, by Ward (1976), who has used only January results to characterize a year’s

---

<sup>1</sup>This method and a further development are outlined in Chapter 21.

system operation; by Barley and Winn (1978), who used a two-point curve fit to obtain location-dependent annual results; and by Lameiro and Bendt (1978), who also obtained location-dependent annual results with three-point curve fits. The SEU (Solar Energy Unit of University College Cardiff) methods of Kenna (1984a,b) are correlation methods which are applicable to designing open-loop and closed-loop heating systems. Another example in the second category is the method of Los Alamos Scientific Laboratory (Balcomb and Hedstrom, 1976), which is a correlation of the outputs of simulations for specific systems and two collector types.

The third category of design methods is based on short-cut simulations. In these methods, simulations are done using representative days of meteorological data and the results are related to longer term performance. The SOLCOST method (Connelly et al., 1976) simulates a clear day and a cloudy day and then weights the results according to average cloudiness to obtain a monthly estimate of system performance.


In recent years annual simulations are replacing design methods as a result of the ever-increasing computational speed of computers. However, design methods are still much faster and so are useful for early design studies, general-survey-type studies, and system design where simulations are too expensive.

## 20.2 THE $f$ -CHART METHOD

This and the following sections outline the  $f$ -chart method for estimating the annual thermal performance of active heating systems for buildings (using either liquid or air as the working fluid) where the minimum temperature of energy delivery is near 20°C. The system configurations that can be evaluated by the  $f$ -chart method are expected to be common in residential applications.

The  $f$ -chart method provides a means for estimating the fraction of a total heating load that will be supplied by solar energy for a given solar heating system. The primary design variable is collector area; secondary variables are collector type, storage capacity, fluid flow rates, and load and collector heat exchanger sizes. The method is a correlation of the results of many hundreds of thermal performance simulations of solar heating systems. The conditions of the simulations were varied over appropriate ranges of parameters of practical system designs. The resulting correlations give  $f$ , the fraction of the monthly heating load (for space heating and hot water) supplied by solar energy as a function of two dimensionless parameters. One is related to the ratio of collector losses to heating loads, and the other is related to the ratio of absorbed solar radiation to heating loads.

The  $f$ -charts have been developed for three standard system configurations, liquid and air systems for space (and hot-water) heating and systems for service hot water only. A schematic diagram of the standard heating system using liquid heat transfer fluids is shown in Figure 20.2.1. This system normally uses an antifreeze solution in the collector loop and water as the storage medium. Collectors may be drained when energy is not being collected, in which case water is used directly in the collectors and a collector heat exchanger is not needed. A water-to-air load heat exchanger is used to transfer heat from the storage tank to a domestic hot-water (DHW) subsystem. Although Figure 20.2.1 shows a two-tank DHW system, a one-tank system could be used as described in Section 12.4. An auxiliary heater



**Figure 20.2.1** Schematic of standard system configuration using liquid heat transfer and storage media.


is provided to supply energy for the space-heating load when it cannot be met from the tank. The ranges for major design variables used in developing the correlations are given in Table 20.2.1.

The standard configuration of a solar air heating system with a pebble bed storage unit is shown in Figure 20.2.2. Other equivalent arrangements of fans and dampers can be used to provide the same modes of operation. Energy required for DHW is provided by an air-to-water heat exchanger in the hot-air duct leaving the collector. During summer operation, it is best not to store solar energy in the pebble bed, and a manually operated storage bypass is usually provided in this system to allow summer water heating. The ranges of design parameters used in developing the correlations for this system are also shown in Table 20.2.1.

**Table 20.2.1** Ranges of Design Parameters  
Used in Developing *f*-Charts for Liquid and Air  
Systems<sup>a</sup>


$0.6 \leq (\tau\alpha)_n \leq 0.9$
$5 \leq F'_R A_c \leq 120 \text{ m}^2$
$2.1 \leq U_L \leq 8.3 \text{ W/m}^2 \text{ }^\circ\text{C}$
$30 \leq \beta \leq 90^\circ$
$83 \leq (UA)_h \leq 667 \text{ W/}^\circ\text{C}$

<sup>a</sup>From Klein et al. (1976, 1977).



**Figure 20.2.2** Standard air system configuration.

The standard configuration for a solar domestic water heating system is shown in Figure 20.2.3. The collector may heat either air or liquid. The solar energy is transferred via a heat exchanger to a DHW preheat tank, which supplies solar-heated water to a conventional water heater or an in-line low-capacitance “zip” heater where the water is further heated to the desired temperature if necessary. A tempering valve may be provided to maintain the tap water below a maximum temperature. These changes in the system configuration do not have major effects on the performance of the system (see Section 12.4).



**Figure 20.2.3** Standard system configuration for water heating only. The collector may heat air or water.

Detailed simulations of these systems have been used to develop correlations between dimensionless variables and *f*, the monthly fraction of loads carried by solar energy. The two dimensionless groups are

$$X = \frac{A_c F'_R U_L (T_{\text{ref}} - \bar{T}_a) \Delta t}{L} \quad (20.2.1)$$

$$Y = \frac{A_c F'_R (\bar{\tau}\alpha) \bar{H}_T N}{L} \quad (20.2.2)$$

where  $A_c$  = collector area (m<sup>2</sup>)  
 $F'_R$  = collector heat exchanger efficiency factor<sup>2</sup>  
 $U_L$  = collector overall loss coefficient (W/m<sup>2</sup> °C)  
 $\Delta t$  = total number of seconds in month  
 $\bar{T}_a$  = monthly average ambient temperature (°C)  
 $T_{\text{ref}}$  = empirically derived reference temperature (100°C)  
 $L$  = monthly total heating load for space heating and hot water (J)  
 $\bar{H}_T$  = monthly average daily radiation incident on collector surface per unit area (J/m<sup>2</sup>)  
 $N$  = days in month  
 $(\bar{\tau}\alpha)$  = monthly average transmittance-absorptance product

Equations 20.2.1 and 20.2.2 can be rewritten as

$$X = F_R U_L \times \frac{F'_R}{F_R} \times (T_{\text{ref}} - \bar{T}_a) \times \Delta t \times \frac{A_c}{L} \quad (20.2.3)$$

$$Y = F_R (\tau\alpha)_n \times \frac{F'_R}{F_R} \times \frac{(\bar{\tau}\alpha)}{(\tau\alpha)_n} \times \bar{H}_T N \times \frac{A_c}{L} \quad (20.2.4)$$

where  $F_R U_L$  and  $F_R (\tau\alpha)_n$  are obtained from collector test results by the methods noted in Chapter 6. The ratio  $F'_R / F_R$  corrects for various temperature drops between the collector and the storage tank and is calculated by methods summarized in Chapter 10. The ratio  $(\bar{\tau}\alpha) / (\tau\alpha)_n$  is estimated by the methods noted in Section 5.10. The average air temperature  $\bar{T}_a$  is obtained from meteorological records for the month and location desired, and  $\bar{H}_T$  is found from the monthly average daily radiation on the surface of the collector as outlined in Chapter 2. The calculation of monthly loads  $L$  is discussed in Chapter 9. (There is no requirement in the *f*-chart development that any particular method be used to estimate the loads.) The collector area is  $A_c$ . Thus all of the terms in these two equations are readily determined from available information. Also, from Equation 5.10.3  $\bar{S}$  can be substituted for  $(\bar{\tau}\alpha) \bar{H}_T$  and then  $(\tau\alpha)_n$  cancels out.

<sup>2</sup>Although we indicate only a modification to  $F_R$  to account for the collector-storage heat exchanger, both  $F_R (\tau\alpha)$  and  $F_R U_L$  can be modified to account for the collector heat exchanger, duct losses, and flow arrangements. (See Chapter 10.)

**Example 20.2.1**

A solar heating system is to be designed for Madison, Wisconsin (latitude  $43^\circ$  N), using one-cover collectors with  $F_R(\tau\alpha)_n = 0.74$  and  $F_R U_L = 4.00 \text{ W/m}^2 \text{ }^\circ\text{C}$  as determined from standard collector tests. The flow rate in use will be the same as that in the tests. The collector is to face south with a slope of  $60^\circ$  from the horizontal. The average daily radiation on a  $60^\circ$  surface for January in Madison is  $13.7 \text{ MJ/m}^2$  (from Example 2.19.1) and the average ambient temperature is  $-8^\circ\text{C}$  (from Appendix D). The heating load is  $36.0 \text{ GJ}$  for space and hot water. The collector heat exchanger correction factor  $F'_R/F_R = 0.97$ . For all months  $(\overline{\tau\alpha})/(\tau\alpha)_n$ , the ratio of the monthly average to normal-incidence transmittance-absorptance product, is taken to be  $0.96$  for one-cover collectors, as noted in Section 5.10. (This ratio can be calculated month by month, if desired.) Calculate  $X$  and  $Y$  for these conditions for collector areas of  $25$  and  $50 \text{ m}^2$ .

**Solution**

From Equations 20.2.3 and 20.2.4 with  $A_c = 25 \text{ m}^2$ ,

$$X = \frac{4.0 \times 0.97[100 - (-8)] \times 31 \times 86,400 \times 25}{36 \times 10^9} = 0.779$$

$$Y = \frac{0.74 \times 0.97 \times 0.96 \times 13.7 \times 10^6 \times 31 \times 25}{36 \times 10^9} = 0.203$$

For  $50 \text{ m}^2$ , the values of  $X$  and  $Y$  are proportionally higher:

$$X = \frac{0.779 \times 50}{25} = 1.56$$

$$Y = \frac{0.203 \times 50}{25} = 0.41$$

■

As will be shown in later sections, the variables  $X$  and  $Y$  are used to determine  $f_i$ , the monthly fraction of the load supplied by solar energy. The energy contribution for the month is the product of  $f_i$  and the monthly heating and hot-water load  $L_i$ . The fraction of the annual heating load supplied by solar energy  $F$  is the sum of the monthly solar energy contributions divided by the annual load:


$$F = \frac{\sum f_i L_i}{\sum L_i} \quad (20.2.5)$$

**20.3 THE  $f$ -CHART FOR LIQUID SYSTEMS**

For systems of the configuration shown in Figure 20.2.1, the fraction  $f$  of the monthly total load supplied by the solar space and water heating system is given as a function of  $X$  and  $Y$  in Figure 20.3.1. The relationship of  $X$ ,  $Y$ , and  $f$  in equation form is

$$f = 1.029Y - 0.065X - 0.245Y^2 + 0.0018X^2 + 0.0215Y^3 \quad (20.3.1)$$





**Figure 20.3.1** The  $f$ -Chart for systems using liquid heat transfer and storage media. From Beck-man et al. (1977).

Because of the nature of the curve fit of Equation 20.3.1, *it should not be used outside of the range shown by the curves of Figure 20.3.1*. If a calculated point falls outside of this range, the graph can be used for extrapolation with satisfactory results.

### Example 20.3.1

The solar heating system described in Example 20.2.1 is to be a liquid system. What fraction of the annual heating load will be supplied by the solar energy for a collector area of  $50 \text{ m}^2$ ? The monthly combined loads on the system are indicated in the following table. (See Example 2.19.1 for  $\overline{H}_T$  values.)

### Solution

From Example 20.2.1, the values of  $X$  and  $Y$  for  $50 \text{ m}^2$  are 1.56 and 0.41, respectively, in January. From Figure 20.3.1 (or Equation 20.3.1),  $f = 0.28$ . The total heating load for January is 36.0 GJ. Thus, the energy delivery from the solar heating system in January is

$$fL = 0.28 \times 36.0 = 10.1 \text{ GJ}$$

The fraction of the annual heating load supplied by solar energy is determined by repeating the calculation of  $X$ ,  $Y$ , and  $f$  for each month and summing the results as indicated by Equation 20.2.5. The table shows the results of these calculations. From Equation 20.2.5 the annual fraction of the load supplied by solar energy is

$$\mathcal{F} = \frac{95.4}{203.2} = 0.47$$

## Monthly and Annual Performance of Liquid Heating System in Madison


Month	$\overline{H}_T$ , MJ/m <sup>2</sup>	$\overline{T}_a$	$L$ , GJ	$X$	$Y$	$f$	$fL$ , GJ
January	13.7	−8	36.0	1.56	0.41	0.28	10.1
February	18.8	−5	30.4	1.62	0.55	0.39	11.9
March	15.8	1	26.7	1.93	0.63	0.44	11.7
April	14.7	9	15.7	2.91	0.97	0.61	9.6
May	16.6	14	9.2	4.86	1.92	0.95	8.8
June	16.5	19	4.1	9.93	4.17	1.00 <sup>a</sup>	4.1
July	16.8	22	2.9	13.98	6.17	1.00 <sup>a</sup>	2.9
August	17.5	20	3.4	12.23	5.49	1.00 <sup>a</sup>	3.4
September	15.6	15	6.3	6.78	2.56	1.00	6.3
October	15.2	11	13.2	3.50	1.23	0.73	9.6
November	11.4	2	22.8	2.16	0.51	0.34	7.7
December	12.7	−5	<u>32.5</u>	1.68	0.42	0.28	<u>9.3</u>
Total			203.2				95.4

<sup>a</sup>These points have coordinates outside of the range of the  $f$ -chart correlation.

■

To determine the economic optimum collector area, the annual load fraction corresponding to several different collector areas must be determined. The annual load fraction is then plotted as a function of collector area, as shown in Figure 20.3.2. The information in this figure can then be used for economic calculations as shown in Chapter 11.

For liquid systems,  $f$ -chart calculations can be modified to estimate changes in long-term performance due to changes in storage tank capacity and load heat exchanger characteristics. This is done by modifying the values of  $X$  or  $Y$  as described below.



**Figure 20.3.2** Annual load fraction versus collector area.

## Storage Capacity

Annual system performance is relatively insensitive to storage capacity as long as capacity is more than approximately 50 liters of water per square meter of collector. When the costs of storage are considered, there are broad optima in the range of 50 to 200 liters of water per square meter of collector.


The *f*-chart was developed for a standard storage capacity of 75 liters of stored water per square meter of collector area. The performance of systems with storage capacities in the range of 37.5 to 300 liters/m<sup>2</sup> can be determined by multiplying the dimensionless group *X* by a storage size correction factor  $X_c/X$  from Figure 20.3.3 or Equation 20.3.2:

$$\frac{X_c}{X} = \left( \frac{\text{actual storage capacity}}{\text{standard storage capacity}} \right)^{-0.25}$$

$$\text{for } 0.5 \leq \left( \frac{\text{actual storage capacity}}{\text{standard storage capacity}} \right) \leq 4.0 \quad (20.3.2)$$

### Example 20.3.2

For the conditions of Example 20.3.1, what would be the annual solar contribution if the storage capacity of the tank were doubled, to 150 liters/m<sup>2</sup>?



**Figure 20.3.3** Storage size correction factor for liquid systems. Standard storage size is 75 liters/m<sup>2</sup>

**Solution**

To account for changes in storage capacity, the value of  $X$  calculated in the previous examples must be modified using Figure 20.3.3 or Equation 20.3.2. The ratio of actual storage size to standard storage size is 2.0, so

$$\frac{X_c}{X} = 2.0^{-0.25} = 0.84$$

For January the corrected value of  $X$  is then

$$X_c = 0.84 \times 1.56 = 1.31$$

The value of  $Y$  remains 0.41. From the  $f$ -chart,  $f = 0.30$ . The solar contribution for January is

$$fL = 0.30 \times 36.0 = 10.8 \text{ GJ}$$

Repeating these calculations for the remaining 11 months gives an annual solar load fraction of 0.49 (versus 0.47 for the standard storage size). ■


**Load Heat Exchanger Size**

As the heat exchanger used to heat the building air is reduced in size, the storage tank temperature must increase to supply the same amount of heat, resulting in higher collector temperatures and reduced collector output. A measure of the size of the heat exchanger needed for a specific building is provided by the dimensionless parameter  $\varepsilon_L C_{\min}/(UA)_h$ , where  $\varepsilon_L$  is the effectiveness of the water-air load heat exchanger,  $C_{\min}$  is the minimum fluid capacitance rate (mass flow rate times the specific heat of the fluid) in the load heat exchanger and is generally that of the air, and  $(UA)_h$  is the overall energy loss coefficient–area product for the building used in the degree-day space-heating load model.

From thermal considerations, the optimum value of  $\varepsilon_L C_{\min}/(UA)_h$  is infinity. However, system performance is asymptotically dependent upon the value of this parameter, and for  $\varepsilon_L C_{\min}/(UA)_h > 10$ , performance will be essentially the same as that for the infinitely large value. The reduction in performance due to an undersized load heat exchanger will be significant for values of  $\varepsilon_L C_{\min}/(UA)_h$  less than about 1. Practical values of  $\varepsilon_L C_{\min}/(UA)_h$  are generally between 1 and 3 when the cost of the heat exchanger is considered. See Beckman et al. (1977) for further discussion.

The  $f$ -chart for liquid systems was developed with  $\varepsilon_L C_{\min}/(UA)_h = 2$ . The performance of systems having other values of  $\varepsilon_L C_{\min}/(UA)_h$  can be estimated from the  $f$ -chart by modifying  $Y$  by a load heat exchanger correction factor  $Y_c/Y$ , as indicated in Equation 20.3.3 or Figure 20.3.4:

$$\frac{Y_c}{Y} = 0.39 + 0.65 \exp\left(-\frac{0.139(UA)_h}{\varepsilon_L C_{\min}}\right) \quad \text{for } 0.5 \leq \frac{\varepsilon_L C_{\min}}{(UA)_h} \leq 50 \quad (20.3.3)$$



**Figure 20.3.4** Load heat exchanger size correction factor.

### Example 20.3.3

For the conditions of Example 20.3.1, what will be the solar contribution if the load heat exchanger is used under the following circumstances: The airflow rate is 520 liters/s, the water flow rate is 0.694 liters/s, and the heat exchanger effectiveness at these flow rates is 0.69. The building overall energy loss coefficient–area product  $(UA)_h = 463 \text{ W/}^\circ\text{C}$ .

#### Solution

First, the value of  $C_{\min}$  is determined. This usually is the capacitance rate of the air, which in this example is

$$C_{\min} = 520 \times 1.20 \times 1010/1000 = 630 \text{ W/}^\circ\text{C}$$

The capacitance rate of the water is 2910 W/°C so that of the air is lower. Then

$$\frac{\epsilon_L C_{\min}}{(UA)_h} = \frac{0.69 \times 630}{463} = 0.94$$

This heat exchanger is smaller than the standard value of 2 used in developing Figure 20.3.1. The correction factor from Figure 20.3.4 or Equation 20.3.3 is

$$\frac{Y_c}{Y} = 0.95 \quad \text{and} \quad Y_c = 0.95 \times 0.41 = 0.39$$

From Figure or equation 20.3.1,  $f = 0.27$  for January, and the solar energy contribution for the month is

$$fL = 0.27 \times 36.0 \text{ GJ} = 9.7 \text{ GJ}$$

The annual solar load fraction is 0.45 (versus 0.47 for the standard heat exchanger). ■

If both the storage and load heat exchanger sizes differ from the standards used to develop the *f*-chart, the correction factors discussed in Examples 20.3.2 and 20.3.3 would both be applied to find the appropriate values of  $X_c$  and  $Y_c$  for determination of *f*. Thus

if the storage correction of Example 20.3.2 and the load heat exchanger correction of Example 20.3.3 are both needed,  $f$  would be determined at  $X_c = 1.31$  and  $Y_c = 0.39$ , where  $f = 0.28$ .

## 20.4 THE $f$ -CHART FOR AIR SYSTEMS


The monthly fraction of total heating load supplied by the solar air heating system shown in Figure 20.2.2 has been correlated with the same dimensionless parameters  $X$  and  $Y$  as were defined in Equations 20.2.1 and 20.2.2. The correlation is given in Figure 20.4.1 and Equation 20.4.1. It is used in the same manner as the  $f$ -chart for liquid-based systems:

$$f = 1.040Y - 0.065X - 0.159Y^2 + 0.00187X^2 - 0.0095Y^3 \quad (20.4.1)$$

*Note:* This equation is not to be used outside of the range of values of  $X$  and  $Y$  shown in Figure 20.4.1.

### Example 20.4.1

A solar heating system is to be designed for a building in Madison, Wisconsin, with two-cover collectors facing south at a slope of  $60^\circ$ . The air heating collectors have the following characteristics:  $F_R U_L = 2.84 \text{ W/m}^2 \text{ } ^\circ\text{C}$  and  $F_R(\tau\alpha)_n = 0.49$ . For this application of the two-cover collector  $(\overline{\tau\alpha})/(\tau\alpha)_n = 0.93$ . The total space and water heating load for January is 36.0 GJ (as in Examples 20.3.1 to 20.3.3). What fraction of the load would be supplied by solar energy with a system having a collector area of  $50 \text{ m}^2$ ?



**Figure 20.4.1** The  $f$ -Chart for air systems of the configuration shown in Figure 20.2.2. From Beckman et al. (1977).

**Solution**

For air systems there will be no correction factor for the collector heat exchanger, and duct losses are assumed to be small, so  $F'_R/F_R = 1$ . From Equations 20.2.3 and 20.2.4,

$$X = 2.84[100 - (-8)] \times 31 \times 86,400 \times \frac{50}{36.0 \times 10^9} = 1.14$$

$$Y = 0.49 \times 1 \times 0.93 \times 13.7 \times 10^6 \times 31 \times \frac{50}{36.0 \times 10^9} = 0.27$$

Then  $f$  for January, from Figure 20.4.1 or Equation 20.4.1, is 0.20. The solar energy supplied by this system in January is

$$fL = 0.20 \times 36 \times 10^9 = 7.1 \text{ GJ}$$

As with the liquid systems, the annual system performance is obtained by summing the energy quantities for all months. The result of the calculation is that 37% of the annual load is supplied by solar energy. ■

Air systems require two correction factors, one to account for effects of storage size if it is other than  $0.25 \text{ m}^3/\text{m}^2$  and the other to account for airflow rate that affects stratification in the pebble bed. In addition, care must be exercised to be sure that the values of  $F_R(\tau\alpha)_n$  and  $F_R U_L$  from collector tests are obtained for the same airflow rates as will be used in an installation. The corrections shown in Chapter 10 can be used to account for duct losses, airflow rate, and so on. The correction factors for storage capacity and airflow rate are outlined below. There is no load heat exchanger in air systems.

**Airflow Rate**


An increase in airflow rate tends to improve system performance by increasing  $F_R$  and tends to decrease performance by reducing the thermal stratification in the pebble bed. The  $f$ -chart for air systems is based on a standard collector airflow rate of 10 liters/s of air per square meter of collector area. The performance of systems having other collector airflow rates can be estimated by using the appropriate values of  $F_R$  and  $Y$  and then modifying the value of  $X$  by a collector airflow rate correction factor  $X_c/X$  (as indicated in Figure 20.4.2 or Equation 20.4.2) to account for the degree of stratification in the pebble bed:

$$\frac{X_c}{X} = \left( \frac{\text{actual airflow rate}}{\text{standard airflow rate}} \right)^{0.28}$$

$$\text{for } 0.5 \leq \left( \frac{\text{actual airflow rate}}{\text{standard airflow rate}} \right) \leq 2.0 \quad (20.4.2)$$

**Example 20.4.2**

The system of Example 20.4.1 is to be designed using a collector airflow rate of 15 liters/s per square meter of collector. Estimate the change in annual performance of the system resulting from the increased airflow.



**Figure 20.4.2** Correction factor for airflow rate to account for stratification in the pebble bed. The standard flow rate is 10 liters/m<sup>2</sup> s.

### Solution

Increasing the airflow rate affects  $F_R$  and stratification in the pebble bed. The effects of airflow rate on  $F_R$  and thus on  $F_R U_L$  and  $F_R(\tau\alpha)_n$  must either be determined by collector tests at the correct airflow rate or be estimated by the methods of Section 6.20. In this case,  $F_R(\tau\alpha)_n = 0.52$  and  $F_R U_L = 3.01$  W/m<sup>2</sup> °C at 15 liters/m<sup>2</sup> s. The corrected  $X$  to account for pebble bed stratification is found from Equation 20.4.2 or Figure 20.4.2:

$$\frac{X_c}{X} = \left( \frac{15}{10} \right)^{0.28} = 1.12$$

Thus the  $X$  to be used is the value from Example 20.4.1 corrected for the increased airflow rate both through the collector and through the pebble bed:

$$X_c = \frac{1.14 \times 3.01 \times 1.12}{2.84} = 1.35$$

Correcting  $Y$  for the new value of  $F_R$  [i.e.,  $F_R(\tau\alpha)_n$ ] yields

$$Y_c = \frac{0.27 \times 0.52}{0.49} = 0.29$$

From the air  $f$ -chart,  $f = 0.20$  and  $fL = 7.2$  GJ for January. The calculation for the year indicates that 39% of the annual load is supplied by solar energy. (This is essentially the same as at the standard airflow rate, although there will be increased fan power required at the higher airflow rate.) ■



## Pebble Bed Storage Capacity

The performance of air systems is less sensitive to storage capacity than that of liquid systems. Air systems can operate in the collector-load mode, in which the storage unit is bypassed. Also, pebble beds are highly stratified, and additional capacity is effectively added to the cold end of the bed, which is seldom heated and cooled to the same extent as the hot end.


The *f*-chart for air systems is for a standard storage capacity of 0.25 m<sup>3</sup> of pebbles per square meter of collector area, which corresponds to 350 kJ/m<sup>2</sup> °C for typical void fractions and rock properties. The performance of systems with other storage capacities can be determined by modifying *X* by a storage size correction factor  $X_c/X$ , as indicated in Figure 20.4.3 or Equation 20.4.3:

$$\frac{X_c}{X} = \left( \frac{\text{actual storage capacity}}{\text{standard storage capacity}} \right)^{-0.30}$$

$$\text{for } 0.5 \leq \left( \frac{\text{actual storage capacity}}{\text{standard storage capacity}} \right) \leq 4.0 \quad (20.4.3)$$

### Example 20.4.3

If the system of Example 20.4.1 has storage capacity which is 60% of the standard capacity, what fraction of the annual heating load would the system be expected to supply?



**Figure 20.4.3** Storage size correction factor for air systems. The standard storage capacity is 0.25 m<sup>3</sup>/m<sup>2</sup>.

**Solution**

The storage size correction factor, from Figure 20.4.3 (or Equation 20.4.3), is 1.17. Then for January

$$\frac{X_c}{X} = 1.17 \quad \text{and} \quad X_c = 1.17 \times 1.14 = 1.33$$

Here  $Y$  remains 0.27. From Figure 20.4.1 or Equation 20.4.1,  $f = 0.19$  and  $fL = 0.19 \times 36.0 \text{ GJ} = 6.7 \text{ GJ}$ . The fraction of the annual load supplied by solar energy  $\mathcal{F}$  is 0.36 (compared to 0.39 for the standard storage size). ■

If both airflow rate and storage size are not standard, there will be two corrections on  $X$  to be made (in addition to any corrections due to changes in  $F_R$ ) and the final  $X$  will be the product of the uncorrected value and the two correction factors.

If a phase change energy storage unit is used in place of the rock bed, Equation 8.8.9, an empirical equation for the equivalent rock bed storage capacity, can be used to predict system performance. The properties and mass of the phase change material are used to estimate the size of an equivalent rock bed, which is then used in the air  $f$ -chart correlations. Some phase change material properties are given in Table 8.8.1.

## 20.5 SERVICE WATER HEATING SYSTEMS

Figure 20.3.1, the  $f$ -chart for liquid heating systems, can be used to estimate the performance of solar water heating systems having the configuration shown in Figure 20.2.3 by defining an additional correction factor on  $X$ . The mains water temperature  $T_m$  and the minimum acceptable hot-water temperature  $T_w$  both affect the performance of solar water heating systems. Both  $T_m$  and  $T_w$  affect the average system operating temperature level and thus also the collector energy losses. The dimensionless group  $X$ , which is related to collector energy losses, can be corrected to include these effects. If monthly values of  $X$  are multiplied by a water heating correction factor  $X_c/X$  in Equation 20.5.1, the  $f$ -chart for liquid-based solar space and water heating systems (Equation 20.3.1 or Figure 20.3.1) can be used to estimate monthly values of  $f$  for water heating systems (all temperatures are in degrees Celsius):

$$\frac{X_c}{X} = \frac{11.6 + 1.18T_w + 3.86T_m - 2.32\bar{T}_a}{100 - \bar{T}_a} \quad (20.5.1)$$

This method of estimating water heater performance is based on storage capacity of 75 liters/m<sup>2</sup> and on the typical day's distribution of hot-water use occurring each day as shown in Figure 9.1.2. Other distributions of use in a day have small effect on system performance; however, day-to-day variations in loads can have a substantial effect on performance. [See Buckles and Klein (1980).]

The water heating correction factor is based on the assumption of a well-insulated solar preheat tank, and losses from an auxiliary tank were not included in the  $f$ -chart correlations. For systems supplying hot water only, loads on the system should also include losses from the auxiliary tank. (These are normally included in the energy supplied to a conventional water heater.) Tank losses can be estimated from the insulation and tank area, but this frequently leads to their underestimation as losses through connections, mounting

brackets, and so on, can be significant. It is recommended that tank loss calculations be based on the assumption that the entire tank is at the water set temperature  $T_w$ .

The use of a tempering valve on the supply line to mix cold supply water with solar-heated water above the water set temperature has little effect on the overall output of the solar system, as noted in Section 12.4, and the method indicated here can be used for systems either with or without the tempering valve.

### Example 20.5.1

A solar water heating system is to be designed for a residence in Madison, Wisconsin (latitude  $43^\circ$  N). The collectors considered for this purpose have two covers with  $F'_R(\tau\alpha)_n = 0.64$  and  $F'_R U_L = 3.64 \text{ W/m}^2 \text{ }^\circ\text{C}$ . The collectors are to face south at a slope of  $45^\circ$ . The water heating load is 400 liters/day heated from 11 to  $60^\circ\text{C}$ . The storage capacity of the preheat tank is to be 75 liters of water per square meter of collector area. The auxiliary tank has a capacity of 225 liters and a loss coefficient of  $0.62 \text{ W/m}^2 \text{ }^\circ\text{C}$ . The tank is a cylinder 0.50 m diameter and 1.16 m high. Estimate the fraction of the January heating load supplied by solar energy for this system with a collector area of  $10 \text{ m}^2$ . The radiation on the collector  $\bar{H}_T = 12.7 \text{ MJ/m}^2$  and  $(\bar{\tau}\alpha)_n/(\tau\alpha) = 0.94$ .

### Solution

The monthly load is the energy required to heat the water from  $T_m$  to  $T_w$  plus the auxiliary tank losses. For January, the energy to heat the water is

$$400 \times 31 \times 4190(60 - 11) = 2.55 \text{ GJ}$$

The loss rate from the auxiliary tank is  $UA(T_w - T'_a)$ . The tank area is  $2.21 \text{ m}^2$ , so the loss rate for  $T'_a$  of  $20^\circ\text{C}$  is

$$2.21 \times 0.62(60 - 20) = 55 \text{ W}$$

The energy required to supply this loss for the month is

$$55 \times 31 \times 24 \times 3600 = 0.15 \text{ GJ}$$

The total load to be used in calculation of  $X$  and  $Y$  is then

$$2.55 + 0.15 = 2.70 \text{ GJ}$$

Then  $X_c$  and  $Y$  are calculated:

$$\begin{aligned} X_c = X \frac{X_c}{X} &= \frac{10 \times 3.64 \times [100 - (-8)] \times 31 \times 24 \times 3600}{2.70 \times 10^9} \\ &\times \frac{11.6 + 1.18 \times 60 + 3.86 \times 11 - 2.32(-8)}{100 - (-8)} = 5.19 \\ Y &= 0.64 \times 0.94 \times 12.7 \times 10^6 \times 31 \times \frac{10}{2.70 \times 10^9} = 0.88 \end{aligned}$$

From Figure 20.3.1 or Equation 20.3.1,  $f = 0.44$ . When this process is repeated for all 12 months, the annual solar contribution is estimated to be 64%. ■

## 20.6 THE $f$ -CHART RESULTS

In the original development of  $f$ -charts (Klein, 1976), it was necessary to make a number of assumptions about systems and their performance. Several of these are worth noting as they are useful in interpreting results obtained from this method.

First, all liquid storage tanks were assumed to be fully mixed, both for main storage tanks for liquid systems and preheat tanks for all water heating. This assumption, as shown in Chapter 10, tends to lead to conservative estimates of long-term performance by overestimating collector inlet temperature. Second, for reasons of economy in simulations, all days were considered symmetrical about solar noon. This also leads to conservative estimates of system outputs. For water heating only, it has been noted that energy in water above the set temperature is not considered useful. Thus, the computations tend to be conservative in their predictions. On the other hand, very well insulated storage tanks were assumed for liquid systems, and it was assumed that there are no leaks in systems; most air systems leak to some extent, which will tend to degrade performance below predicted levels.

There are implicit assumptions in the  $f$ -chart method. Systems are well built, flow distribution to collectors is uniform, flow rates are as assumed, system configurations are close to those for which the correlations were developed, and control strategies used are nearly those assumed in the  $f$ -chart development. If systems do not meet these conditions, they cannot be expected to perform as estimated by the  $f$ -chart method.

Three steps have been used to check the results of the  $f$ -chart predictions. The first is comparisons with detailed simulations in many locations (simulations themselves having been compared with measurements). Second, laboratory measurements on experimental systems have been compared to  $f$ -chart results. Third, measurements made on operating systems in the field have also been used for comparisons. The comparisons must be based on use of measured meteorological data in the  $f$ -chart calculations and on measured loads; variability in weather is large enough that the weather experienced by a system in any one year may be substantially different from the average data ordinarily used in the calculations.

The results obtained with the  $f$ -chart have been compared to results of detailed simulations for a variety of locations. Agreement is generally to within 3% for most U.S. locations and within 11% for Seattle, the worst case. Agreement of monthly solar fractions is not nearly as good as annual fractions, and the  $f$ -chart method should be used to estimate annual performance only.


Fanney (1979) did a year-long experimental study of solar DHW systems at the U.S. National Bureau of Standards. The annual fraction of the total load (water draw-off plus auxiliary tank losses) supplied by solar from measurements and from  $f$ -chart predictions is given in Table 20.6.1. Although there are some differences between measured and predicted performance, the results agree reasonably well.

Two experimental building heating systems supply data for comparisons. MIT House IV (Section 13.5) was 52% heated by solar energy over two years, while  $f$ -chart estimates (based on measured meteorological conditions) indicate a solar fraction of 57%. (The system configuration is close to, but not the same as, the  $f$ -chart system.) CSU House II, an air system (Section 13.4), was supplied with 72% of its heat by solar energy and the  $f$ -chart predicts 76% for the period.

The U.S. National Solar Data Network (NSDN) program and other related programs provide additional data on operation of systems in routine use on buildings. The quality of the data and the operation of the systems do not match that of laboratory experiments, but

**Table 20.6.1** Measured and Predicted Values of Annual Solar Fraction<sup>a</sup>

Number of Tanks	Type	Heat Exchanger	Measured	Predicted
1	Liquid	External	0.36	0.37
2	Liquid	External	0.37	0.40
1	Liquid	Internal	0.45	0.43
2	Liquid	Internal	0.33	0.30
1	Air	External	0.20	0.21

<sup>a</sup>From Fannee (1979).**Figure 20.6.1** Comparison of predicted and measured annual or seasonal performance of solar heating systems. From Duffie and Mitchell (1983).

the circumstances under which the operations are carried out are “real world.” Duffie and Mitchell (1983) have summarized some of these data for systems that are reasonably close in design to the standard configurations. The results were shown in terms of comparisons of measured solar fraction  $F_M$  with predicted solar fraction  $F_p$ . A set of these comparisons is shown in Figure 20.6.1. The agreement is generally within  $\pm 15\%$ . Three air systems show better performance than predicted; this may reflect the difficulty of making good measurements on air systems.

Data for some systems, when plotted on the coordinates of Figure 20.6.1, lie in the upper left portion of the plot. This is an indication that there is a problem in the design or construction of the systems and that corrective action should be taken to improve performance.

## 20.7 PARALLEL SOLAR ENERGY-HEAT PUMP SYSTEMS


For the parallel solar energy–heat pump system shown in Figure 20.7.1, Anderson (1979) and Anderson et al. (1980) have developed a design method based on a combination of the “bin” method and the  $f$ -chart method. In the parallel mode of operation the solar

system is the primary energy source, and its operation is unaffected by the presence of a heat pump, that is, the heat pump system acts as the solar system auxiliary energy source. Consequently, the  $f$ -chart method can be used to determine the solar contribution to the heating load. The remaining portion of the load is met by a combination of the energy delivered by the heat pump and auxiliary energy. Although the performance of the heat pump is affected by the presence of the solar system, the Anderson et al. study observed that this interaction is small and can be neglected. This means that the only effect of the solar system on the heat pump is a reduction of the load that the heat pump will meet. The results of bin method calculations for a heat-pump-only system can then be modified to predict heat pump performance in the presence of a solar system.


A typical set of heat pump and load characteristics is shown in Figure 20.7.2 as a function of ambient temperature. When the ambient temperature is above the balance point, the heat pump can supply more energy  $Q_{\text{del}}$  than is needed by the load  $L$ . When the ambient temperature is below the balance point, auxiliary energy must be used in addition to the heat pump.

The bin method for estimating the monthly energy usage of a stand-alone heat pump system is described in ASHRAE (1976). The method uses long-term weather data to determine the number of hours in which the ambient temperatures were within  $2.8^\circ\text{C}$  ( $5^\circ\text{F}$ ) temperature ranges called bins. The number of hours in each temperature bin for a particular month can be used to estimate the monthly purchased energy. For example, suppose a month has 15 h in a temperature bin centered around  $10^\circ\text{C}$ . To meet the load during this 15 h, the system needs to run only 15 h times the ratio of  $L$  to  $Q_{\text{del}}$ , or  $15(2.2/8.1) = 4.1$  h, and in this 4.1 h the energy required by the heat pump is  $4.1 \times 3.4 = 13.9$  kWh (50 MJ). This calculation must be repeated for each temperature bin above the balance point.

At temperatures below the balance point the heat pump alone cannot meet the load, and auxiliary energy must be used to make up the deficit. If 12 h are in the bin centered around  $-10^\circ\text{C}$ , the heat pump will run continuously for the 12 h at a rate of 2.1 kW for a total electrical requirement of  $2.1 \times 12 = 25.2$  kWh (91 MJ). In addition, auxiliary energy must make up the difference between the load of 7.7 kW times 12 h and the delivered energy of 4.6 kW times 12 h, or 37.2 kWh (134 MJ). By repeated application of these



**Figure 20.7.1** Parallel solar energy-heat pump system. From Anderson (1979).




**Figure 20.7.2** Typical heat pump and load characteristics as a function of ambient temperature. From Anderson (1979).

calculations, the monthly purchased energy can be estimated from which annual values can be calculated.

For a house with a parallel solar–heat pump system in Columbia, Missouri, the combined system performance is shown in Figure 20.7.3 as a function of collector area. For zero collector area the system is a stand-alone heat pump and the fraction of the load supplied by nonpurchased energy from the air is  $FATM_0$ . At any finite collector area, some energy is supplied by solar and some is from the ambient air. The design procedure assumes that on a monthly basis

$$FATM = FATM_0 (1 - f) \quad (20.7.1)$$



**Figure 20.7.3** Parallel solar energy–heat pump system performance for January in Columbia, MO. From Anderson et al. (1980).

where  $f$  is the monthly fraction by solar. This equation is a result of assuming that the only effect of the solar system on the heat pump performance is a reduction in the load.


With monthly results from the  $f$ -chart, a bin method calculation, and Equation 20.7.1, the monthly fraction of the load supplied by nonpurchased energy can be estimated. The remainder of the load is supplied by a combination of compressor work supplied to the heat pump and auxiliary energy. If the auxiliary energy is electricity, there is no need to separate the purchased energy into fractions by compressor work and by auxiliary. However, if the auxiliary is not electricity, it is necessary to know each of the two fractions to do an economic assessment. Equation 20.7.2 is recommended by Anderson et al. (1980) to find the work fraction,

$$FW = FW_0 (1 - f) \quad (20.7.2)$$

where  $FW_0$  is the work fraction for the stand-alone heat pump. The auxiliary fraction is then

$$FAUX = (1 - FATM_0 - FW_0)(1 - f) \quad (20.7.3)$$

The results of using the design procedure given by Equations 20.7.1 through 20.7.3 have been compared to detailed computer simulations, and typical results are shown in Figure 20.7.4. In this figure the fractions of total load supplied by purchased energy



**Figure 20.7.4** Comparison of purchased energy fractions calculated by design procedure and by detailed simulations. From Anderson et al. (1980).



calculated by the two methods compare very well. A similar conclusion can be made concerning the work fraction, the fraction from the atmosphere, and the fraction by solar.

## 20.8 SUMMARY

The  $f$ -chart method provides a means of quickly estimating the long-term performance of solar heating systems of standard configurations. The data needed are monthly average radiation and temperature, the collector parameters available from standard collector tests, and estimates of loads.

It should be recognized that there are uncertainties in the estimates obtained from the  $f$ -chart procedure. The major uncertainties arise from several sources. First, the meteorological data can be in error by as much as 5 to 10%, particularly when the horizontal data are converted to radiation on the plane of the collector. Second, average data are used in the calculations, and any particular year may vary widely from that average. Third, it is extremely difficult to predict what building heating loads will be as they are dependent on the habits of the occupants. Fourth, systems must be carefully engineered and constructed, with minimal heat losses, leakage, and other mechanical and thermal problems. Finally (and probably least important), there are some differences between the  $f$ -chart correlation and individual data points.

It is difficult to quantitatively assess the impacts of these uncertainties on the results obtained from the method. However, two generalizations can be made. First, the relative effects of design changes can be established. For example, the effects on annual performance of a change in plate absorptance and emittance can be shown. The second decimal place is significant in this context. Second, the method will predict the performance of a given system, but because of the uncertainties, only the first decimal should be considered as significant.

The calculations of the  $f$ -chart method can easily be done by hand, but they can be tedious. The method has been programmed in combination with life-cycle economic analysis. [See, e.g., *FCHART Users Manual* (2005).]

## REFERENCES

- Anderson, J. V., M. S. Thesis, Mechanical Engineering, University of Wisconsin-Madison (1979). "Procedures for Predicting the Performance of Air-to-Air Heat Pumps in Stand-Alone and Parallel Solar-Heat Pump Systems."
- Anderson, J. V., J. W. Mitchell, and W. A. Beckman, *Solar Energy*, **25**, 155 (1980). "A Design Method for Parallel Solar-Heat Pump Systems."
- ASHRAE *Systems Handbook*, American Society of Heating, Refrigeration, and Air-Conditioning Engineers, New York (1976).
- Balcomb, J. D. and J. C. Hedstrom, *Proc. Int. Solar Energy Soc. Conf.*, Winnipeg, **4**, 281 (1976). "A Simplified Method for Sizing a Solar Collector Array for Space Heating."
- Barley, C. D. and C. B. Winn, *Solar Energy*, **21**, 279 (1978). "Optimal Sizing of Solar Collectors by the Method of Relative Areas."
- Beckman, W. A., S. A. Klein, and J. A. Duffie, *Solar Heating Design by the  $f$ -Chart Method*, Wiley-Interscience, New York (1977).
- Buckles, W. E. and S. A. Klein, *Solar Energy*, **25**, 417 (1980). "Analysis of Solar Domestic Hot Water Heaters."

- Connelly, M., R. Giellis, G. Jenson, and R. McMordie, *Proc. Int. Solar Energy Soc. Conf.*, Winnipeg, **10**, 220 (1976). "Solar Heating and Cooling Computer Analysis—A Simplified Sizing Method for Non-Thermal Specialists."
- Duffie, J. A. and J. W. Mitchell, *Trans. ASME J. Solar Energy Eng.*, **105**, 3 (1983). "*f*-Chart: Predictions and Measurements."
- Fanney, A. H., personal communication on the National Bureau of Standards Solar Domestic Hot Water Test Facility (1979).
- FCHART Users Manual*, [www.fchart.com](http://www.fchart.com) (2005).
- Kenna, J., *Solar Energy*, **32**, 687 (1984a). "A Parametric Study of Open Loop Solar Heating Systems—I."
- Kenna, J., *Solar Energy*, **32**, 707 (1984b). "A Parametric Study of Open Loop Solar Heating Systems—II."
- Klein, S. A., Ph.D. Thesis, Chemical Engineering, University of Wisconsin-Madison (1976). "A Design Procedure for Solar Heating Systems."
- Klein, S. A., W. A. Beckman, and J. A. Duffie, *Solar Energy*, **18**, 113 (1976). "A Design Procedure for Solar Heating Systems."
- Klein, S. A., W. A. Beckman, and J. A. Duffie, *Solar Energy*, **19**, 509 (1977). "A Design Procedure for Solar Air Heating Systems."
- Lameiro, G. and P. Bendt, *Proc. 1978 Meeting Am. Sect. Int. Solar Energy Soc.*, Denver, **2** (1), 113 (1978). "The GFL Method for Designing Solar Energy Space Heating and Domestic Hot Water Systems."
- Proctor, D., paper presented at International Solar Energy Society Meeting, Los Angeles (1975). "Methods of Predicting the Heat Production of Solar Collectors for System Design."
- Ward, J. C., *Proc. Int. Solar Energy Soc. Conf.*, Winnipeg, **4**, 336 (1976). "Minimum-Cost Sizing of Solar Heating Systems."

## Design of Active Systems by Utilizability Methods

In Chapter 20 the  $f$ -chart method was presented as a design tool for solar systems that deliver energy to a load at minimum temperatures near 20°C. There are, however, many applications that use energy at temperatures higher or lower than 20°C. A warehouse heating system may be required to keep the building above freezing so that all energy delivered above 0°C is useful. A solar-operated absorption cycle air conditioning system may be able to use all energy above 75°C. Industrial process heat temperature requirements can be at almost any level. This chapter describes design methods for active systems for which the  $f$ -chart method does not apply.

The design of active solar systems can be done with detailed computer simulations, as noted in Chapter 19. The expense of simulations can be significant, but the procedure should be considered in the final analysis for all large systems. Preliminary designs and designs for small systems require inexpensive methods for predicting long-term performance, and the methods presented here (and the  $f$ -chart method) are in this category.

The first utilizability method is monthly average hourly utilizability for flat-plate collectors (the  $\phi$  method). In Chapter 2, the concepts of utilizability were introduced, and methods were shown for calculating hourly and daily utilizability without reference to how critical radiation levels are determined. In this chapter, we briefly review the initial development of Whillier (1953) and Hottel and Whillier (1958), the generalized  $\phi$  method of Liu and Jordan (1963), and the  $\bar{\phi}$  method of Klein (1978) and Collares-Pereira and Rabl (1979a, 1979b). We then show how Klein and Beckman (1979) combined daily utilizability with the  $f$ -chart concept to account for finite storage capacity (the  $\bar{\phi}$ ,  $f$ -chart method). In each case we show how critical radiation levels are established and illustrate the use of the methods.

Design methods are available for many solar thermal systems, but not all. The utilizability methods all require knowledge of the collector inlet fluid temperature, which often is not known. The  $\bar{\phi}$   $f$ -chart method allows collector inlet temperature to vary with the storage tank temperature but requires that the load be a closed loop with the fluid returned to the tank at or above a minimum temperature. Also, any device between the solar system and the load must have a conversion efficiency which is independent of the temperature level at which energy is delivered (as long as it is above the minimum temperature). This requirement rules out solar-to-mechanical systems.

## 21.1 HOURLY UTILIZABILITY

Utilizability can be defined as the fraction of the incident solar radiation that can be converted to useful heat. It is the fraction utilized by a collector having  $F_R(\tau\alpha) = 1$  and operating at a fixed inlet to ambient temperature difference. Although this collector has no optical losses and has a heat removal factor of unity, the utilizability is always less than 1 since the collector does have thermal losses.<sup>1</sup>

As shown in Section 6.8, an analytical expression for utilizability in terms of the hourly radiation incident on the plane of the collector can be derived from Equation 6.7.6:

$$Q_u = A_c F_R [I_T(\tau\alpha) - U_L(T_i - T_a)]^+ \quad (21.1.1)$$

The radiation level must exceed a critical value before useful output is produced. This critical level is found by setting  $Q_u$  in Equation 21.1.1 equal to zero:

$$I_{Tc} = \frac{F_R U_L (T_i - T_a)}{F_R(\tau\alpha)} \quad (21.1.2)$$

The useful output of the collector can be expressed in terms of the critical radiation level as

$$Q_u = A_c F_R(\tau\alpha)(I_T - I_{Tc})^+ \quad (21.1.3)$$

If the critical radiation level is constant for a particular hour (say 10 to 11) for a month ( $N$  days), then the monthly average hourly collector output for this hour is given by

$$\overline{Q}_u = \frac{A_c F_R(\tau\alpha)}{N} \sum_N (I_T - I_{Tc})^+ \quad (21.1.4)$$

The monthly average radiation in this particular hour is  $\overline{I}_T$ , so the average useful output can be expressed as

$$\overline{Q}_u = A_c F_R(\tau\alpha) \overline{I}_T \phi \quad (21.1.5)$$

where the utilizability  $\phi$  is defined as

$$\phi = \frac{1}{N} \sum_N \frac{(I_T - I_{Tc})^+}{\overline{I}_T} \quad (21.1.6)$$

The procedure for calculating  $\phi$  was shown in Example 2.22.1 for a vertical surface at Blue Hill, Massachusetts. The result of the procedure, when the critical radiation level was varied, was the utilizability curve of Figure 2.22.3. Whillier (1953) and later Liu and Jordan (1963) have shown that in a particular location for a one-month period  $\phi$  is essentially the same for all hours. Thus, although the curve of Figure 2.22.3 was derived for the hour-pair 11 to 12 and 12 to 1, it is valid for all hour-pairs in Blue Hill.

---

<sup>1</sup>If a collector heat exchanger is present,  $F'_R$  can be used in place of  $F_R$ .

The  $\phi$  curve of Figure 2.22.3 is specific to a particular location and orientation. In order for the method to be more generally useful, Liu and Jordan developed the generalized  $\phi$  curves presented in Section 2.23. These are independent of location and orientation. Figure 2.23.1 or Equation 2.23.5 are used to determine  $\phi$  at the dimensionless critical radiation level  $X_c$ , which was defined as  $I_{Tc}/\bar{I}_T$ . We can now write  $X_c$  in terms of collector parameters:

$$X_c = \frac{I_{Tc}}{\bar{I}_T} = \frac{F_R U_L (T_i - T_a)}{F_R (\tau\alpha)_n \frac{(\tau\alpha)}{(\tau\alpha)_n} \bar{I}_T} \quad (21.1.7)$$

where  $(\tau\alpha)/(\tau\alpha)_n$  is determined for the mean day of the month and the appropriate hour angle. This ratio can be estimated from  $b_o$ . With  $\phi$  determined, the utilizable energy is  $\phi \bar{I}_T$ .

The main utility of hourly utilizability is in estimating the output of processes which have a critical radiation level that changes significantly through the day. This change may be due to a regular and pronounced diurnal temperature variation or to shifts in collector inlet temperature caused by characteristics of the load. The following example is an industrial process in which the water returned to the collector varies in a regular manner through the day, allowing critical radiation levels (and thus useful energy) to be calculated for each hour.

### Example 21.1.1

An industrial process is supplied water from an array of collectors. The temperature of the return water from the process to the collectors varies from hour to hour but for a given hour is nearly constant throughout the month. The system is located in Albuquerque, New Mexico, at latitude  $35^\circ$ , and the collectors are sloped  $35^\circ$  to the south. For the month of March, the temperatures at which water returns to the collectors are shown in the second column of the table below. The average ambient temperatures for the hours are shown in the next column. Data for  $\bar{I}_T$  are shown in the fourth column; they are calculated from  $\bar{H}$  from Appendix D by Equation 2.23.3. The angles of incidence of beam radiation on the collector (which are nearly the same as the hour angles for the south-facing collectors with  $\beta = \phi$  and  $\delta$  close to zero) are shown in the fifth column.

The collector characteristics are  $F_R(\tau\alpha)_n = 0.726$ ,  $F_R U_L = 3.89 \text{ W/m}^2 \text{ }^\circ\text{C}$ , and  $b_o = -0.11$ . The ground reflectance can be taken as 0.2.

Estimate the March output of the collector operating under these circumstances.

### Solution

The data in columns 6 through 9 in the table show the results of the hour-by-hour calculations for March. The calculations for the hour 8 to 9 are as follows: At  $\theta_b = 52.5^\circ$ , from Equation 6.17.10,

$$K_{\tau\alpha} = \frac{(\tau\alpha)}{(\tau\alpha)_n} = 1 - 0.11 \left( \frac{1}{\cos 52.5} - 1 \right) = 0.929$$

The dimensionless critical radiation level  $X_c$  is calculated from Equation 21.1.7:

$$X_c = \frac{3.89(23 - 3)3600 \times 10^{-6}}{0.726 \times 0.929 \times 1.74} = 0.239$$

For the month of March,  $\overline{K}_T = 0.68$ . It is thus necessary to interpolate between  $\overline{K}_T$  of 0.6 and 0.7 in Figure 2.23.1(d). For March with  $\beta = \phi$ ,  $\overline{R}_b = 1.28$  from Equation 2.19.4. From Figure 2.23.1(d),  $\phi$  is very close to 0.77 at both values of  $\overline{K}_T$ . Alternatively, Equations 2.23.5 can be used, which leads to  $\phi = 0.769$ . The useful gain for the collector for this hour for the 31 days of the month is thus

$$F_R(\tau\alpha)_n \frac{(\tau\alpha)}{(\tau\alpha)_n} N\overline{I}_T\phi = 0.726 \times 0.929 \times 31 \times 1.74 \times 0.769 = 27.9 \text{ MJ/m}^2$$

This process is repeated for each hour of the day. The conditions of operation for the hours 11 to 12 and 12 to 1 happen to be the same, so the calculations are done once for that hour-pair. The sum of the outputs for all hours is the expected gain from the collector for the month. Thus the month's useful gain is 378 MJ per square meter of collector.

Hour	$T_r$ , °C	$T_a$ , °C	$\overline{I}_T$ , MJ/m <sup>2</sup>	$\theta_b$ , deg	$K_{\tau\alpha}$	$X_c$	$\phi$	$NQ_u/A$ , MJ/m <sup>2</sup>
8–9	23	3	1.74	52.5	0.929	0.239	0.769	27.9
9–10	23	3	2.49	37.6	0.971	0.160	0.843	45.9
10–11	23	3	3.08	22.6	0.991	0.126	0.875	60.1
11–12	28	4	3.41	7.9	1.000	0.136	0.865	66.3
12–1	28	4	3.41	7.9	1.000	0.136	0.865	66.3
1–2	47	9	3.08	22.6	0.991	0.240	0.764	52.5
2–3	47	9	2.49	37.6	0.971	0.303	0.706	38.4
3–4	47	9	1.74	52.5	0.929	0.454	0.575	<u>20.9</u>
Total								378

The  $\phi$  curves are very powerful design tools, but they can be misused. They cannot be directly applied to many liquid-based building heating systems since the critical level varies considerably during the month due to the finite storage capacity. Two limiting cases of solar heating fit into the  $\phi$  curve restrictions: air heating systems in midwinter and systems with seasonal storage. For the case of air systems, the inlet air temperature to the collector during much of the winter will be the return air from the house. This is because little excess energy is available for storage and what is stored is effectively stratified by the rock bed. Only in the spring and fall will the collector inlet temperature rise much above the room temperature. In the case of annual (long-term) storage, the storage tank temperature varies slowly during a month so that a monthly average tank temperature and the critical level can be found by trial and error. This is illustrated in the next section. As shown in

Example 21.1.1, some industrial process heat applications can also be analyzed with  $\phi$  curves if a critical level for each hour for the month can be determined.

The line on the  $\phi$ -charts labeled “limiting curve of identical days” is the  $\phi$  curve that would be obtained if all days in a month were identical. Only if  $K_T$  is high or if the critical level is very low do all  $\phi$  curves approach this limit, and only then can average days be used to predict long-term performance.

## 21.2 DAILY UTILIZABILITY

As noted in Section 2.24, the use of  $\phi$  curves involves calculations for each hour or hour-pair. This means that for the most common problems four to eight calculations will be needed per month. This situation led Klein (1978) and Collares-Pereira and Rabl (1979a,b) to simplify the calculations for those systems for which a single critical radiation level can be defined for all hours for a month.

Daily utilizability was defined in Section 2.24 as the sum for a month, over all hours and all days, of the radiation on a tilted surface that is above a critical level divided by the monthly radiation. In equation form

$$\bar{\phi} = \sum_{\text{days}} \sum_{\text{hours}} \frac{(I_T - I_{Tc})^+}{\bar{H}_T N} \quad (21.2.1)$$

The critical level  $I_{Tc}$  is similar to that defined by Equation 21.1.2 except that monthly average transmittance-absorptance must be used in place of  $(\tau\alpha)$ , and  $T_i$  and  $\bar{T}_a$  are representative inlet and daytime temperatures for the month:

$$I_{Tc} = \frac{F_R U_L (T_i - \bar{T}_a)}{F_R (\tau\alpha)_n \frac{(\tau\alpha)}{(\tau\alpha)_n}} \quad (21.2.2)$$

The value of  $(\bar{\tau\alpha})/(\tau\alpha)_n$  can be calculated with Equation 5.10.4. The monthly average daily useful energy gain is then given by

$$\sum Q_u = A_c F_R (\bar{\tau\alpha}) \bar{H}_T \bar{\phi} \quad (21.2.3)$$

It will be recalled from Section 2.24 that Klein (1978) developed a method for calculating  $\bar{\phi}$  as a function of  $\bar{K}_T$ , the geometric factor  $\bar{R}/R_n$ , and the dimensionless critical radiation level  $\bar{X}_c$ ;  $\bar{R}$  is calculated by the methods of Sections 2.19 and 2.20 and  $R_n$  by Equation 2.24.2.

The monthly average critical radiation ratio is the ratio  $\bar{X}_c$  of the critical radiation  $I_{Tc}$  to the noon radiation level for a day of the month in which the total radiation for the day is the same as the monthly average. Writing this ratio for the noon hour, we have

$$\bar{X}_c = \frac{I_{Tc}}{r_{t,n} R_n \bar{H}} = \frac{F_R U_L (T_i - \bar{T}_a) / F_R (\bar{\tau\alpha})}{r_{t,n} R_n \bar{K}_T \bar{H}_o} \quad (21.2.4)$$

Equations 2.24.4 or Figure 2.24.2 will then give  $\bar{\phi}$ .<sup>2</sup> The procedure, except for the calculation of  $\bar{X}_c$ , was illustrated in Example 2.24.1.

In the next example a problem involving a large-capacity seasonal storage unit will be used to illustrate an application of the  $\bar{\phi}$  method.

### Example 21.2.1

Estimate the annual performance of a liquid solar heating system located at 43° N latitude having a very large storage volume (seasonal storage). The collector area is 50 m<sup>2</sup>, and its slope is 60° to the south. The storage tank contains 250,000 liters of water. The losses from the tank are to the ground at an average temperature of 7°C. The storage tank area–loss coefficient product  $(UA)_s = 30 \text{ W/°C}$ . The building  $(UA)_h = 200 \text{ W/°C}$  and the characteristics of the collector heat exchanger–piping combination are  $F'_R(\bar{\tau}\bar{\alpha})_n = 0.78$  and  $F'_R U_L = 4.55 \text{ W/m}^2 \text{ °C}$ . The monthly average weather data are given in the table that follows.

### Solution

Since the storage tank is very large, its temperature will not change significantly throughout each month so an average collector inlet temperature can be assumed, and the  $\bar{\phi}$  method can be used. An energy balance on the tank for a one-month period is

$$(mC_p \Delta T)_s = \text{collector output} - \text{tank losses} - \text{energy to load}$$

In this solution, it will be assumed that all of the energy necessary to meet the heating needs of the building for all months can be supplied across a load heat exchanger, that is, that all of the loads are met by solar energy.

The initial step is to guess a tank temperature at the beginning of March. March is conveniently used as the beginning of the year since it usually has the lowest tank temperature and is therefore easiest to estimate. Once the tank temperature is known at the beginning of the month, the tank temperature at the end of the month is guessed. The average tank temperature for the month is used to calculate the collector output and tank losses.<sup>3</sup> The tank energy balance equation is used to determine the tank temperature at the end of the month. This calculated temperature is compared with the assumed value, and if they agree, the calculation continues with the next month. If they disagree, another monthly average temperature is estimated and a new final tank temperature is calculated. The procedure is repeated for all 12 months, and the final tank temperature is compared

<sup>2</sup>For convenience, Equations 2.24.4 are repeated here:

$$\begin{aligned}\bar{\phi} &= \exp[[a + b(R_n/\bar{R})][\bar{X}_c + c\bar{X}_c^2]] \\ a &= 2.943 - 9.271\bar{K}_T + 4.031\bar{K}_T^2 \\ b &= -4.345 + 8.853\bar{K}_T - 3.602\bar{K}_T^2 \\ c &= -0.170 - 0.3061\bar{K}_T + 2.936\bar{K}_T^2\end{aligned}$$

<sup>3</sup>An Euler-type integration could also have been used.



to the initial guess made for March. If they agree, the calculations are complete; if they disagree, the calculations must be repeated. The details of the March calculations follow, and the results for all 12 months are given in the table. The month's heating load is found with Equation 9.2.6:

$$(UA)_h(DD) = 200 \times 3600 \times 24 \times 599 = 10.4 \text{ GJ}$$

The tank losses depend on the monthly average tank temperature  $\bar{T}_s$ , which is unknown. An initial tank temperature of 24.6°C and an average temperature of 24.9°C will be assumed (and later checked):

$$(UA)_s(\bar{T}_s - T_{\text{ground}}) = 30 \times 3600 \times 24 \times 31(24.9 - 7) = 1.4 \text{ GJ}$$

The monthly average daily useful energy gain will be estimated first using the assumed 24.9°C tank temperature. For the month  $\bar{H} = 12.89 \text{ MJ/m}^2$ . Following the method of Section 2.19 the monthly average radiation on the collector is  $15.8 \text{ MJ/m}^2$ . The monthly average ratio  $(\bar{\tau}\alpha)/(\tau\alpha)_n$  will be assumed to be a constant at 0.96. The critical radiation level  $I_{Tc}$  is given as

$$I_{Tc} = \frac{4.55(24.9 - 1)}{0.78 \times 0.96} = 145 \text{ W/m}^2$$

Here the daytime average temperature was estimated to be 2°C higher than the 24-h average.

Details of the radiation and utilizability calculations are given in Example 2.24.1. The dimensionless critical radiation level is calculated by Equation 21.2.4:

$$\bar{X}_c = \frac{145 \times 3600}{0.146 \times 1.12 \times 12.89 \times 10^6} = 0.25$$

Using Equations 2.24.4 with  $\bar{K}_T = 0.50$ ,  $\bar{\phi} = 0.68$ . The monthly energy gain is then calculated by multiplying Equation 21.2.3 by 31, the number of days in the month:

$$N \sum \bar{Q}_u = 31 \times 50 \times 0.78 \times 0.96 \times 15.8 \times 10^6 \times 0.68 = 12.4 \text{ GJ}$$

The change in tank temperature during the month of March is then

$$\Delta T = \frac{(12.4 - 1.4 - 10.4) \times 10^9}{4190 \times 0.25 \times 10^6} = 0.6^\circ\text{C}$$

Thus the tank temperature at the end of the month is 0.6°C higher than at the beginning. The average temperature is equal to the assumed 24.9°C, and the final temperature is 25.2°C. This final March temperature is taken as that for the beginning of April and is the basis for estimation of the April average temperature. This process is repeated for all months. At the end of February (i.e., after a year's calculation) the tank temperature is back to 24.6°C, which is the same as the assumed starting temperature. The results of the year's calculations are shown in the table. If there had been differences in the year's initial and final temperatures, the calculations for the year would be repeated until they agreed.

Nothing has been specified in this problem about the characteristics of the heat exchanger between the tank and the building; it is assumed that it is large enough so that the needed energy can be transferred to the building even late in the winter when the tank temperature drops to levels that are not much higher than room temperature. There is also an implicit assumption that the collector area and storage capacity are large enough so that the tank is always hot enough to meet the load. A more complete analysis would include the characteristics of the load heat exchanger, and energy delivered to the load would be calculated as the heat transferred rather than the heating loads on the building.


Month	$\rho_g$	$\bar{T}_a + 2,$ °C	DD, °C-day	$\bar{H},$ MJ/m <sup>2</sup>	$\bar{K}_T$	$\bar{R}$	$R_n$	$\bar{X}_c$	$\bar{\phi}$	$N \sum \frac{Q_u}{\text{GJ}}$	$\frac{Q_{\text{loss}}}{\text{GJ}}$	$\frac{Q_{\text{load}}}{\text{GJ}}$	$T,$ °C
March	0.4	1	602	12.89	0.500	1.23	1.12	0.25	0.68	12.4	1.4	10.4	24.6
April	0.2	9	340	15.88	0.475	0.91	0.93	0.21	0.72	11.7	1.6	5.9	25.2
May	0.2	15	194	19.79	0.507	0.78	0.86	0.19	0.72	12.9	2.1	3.4	29.2
June	0.2	21	79	22.11	0.535	0.72	0.83	0.20	0.71	12.6	2.6	1.4	36.4
July	0.2	23	50	21.96	0.547	0.74	0.85	0.25	0.64	12.1	3.3	0.8	44.6
August	0.2	22	60	19.39	0.545	0.86	0.92	0.32	0.56	10.8	3.9	1.0	52.1
September	0.2	17	140	14.75	0.518	1.07	1.03	0.43	0.47	8.3	4.0	2.4	57.8
October	0.2	12	282	10.34	0.500	1.44	1.21	0.53	0.42	7.3	4.2	4.9	59.6
November	0.2	4	508	5.72	0.395	1.69	1.18	0.92	0.32	3.5	3.6	8.8	57.9
December	0.4	−4	743	4.42	0.374	1.92	1.28	0.99	0.34	3.3	2.9	12.8	49.4
January	0.7	−6	828	5.85	0.442	2.03	1.46	0.55	0.48	6.6	2.1	14.3	37.5
February	0.7	−5	695	9.13	0.490	1.69	1.38	0.34	0.60	9.8	1.4	12.0	28.2

There are many other applications of  $\bar{\phi}$ . These include processes such as swimming pool heating, passive and hybrid heating systems, and photovoltaic systems. Some of these will be discussed in the following chapters. In the next section a combination of  $\bar{\phi}$  with a correlation method is described and applied to additional problems.

## 21.3 THE $\bar{\phi}$ , $f$ -CHART METHOD

The utilizability design concept is useful whenever the collector operates at a known critical radiation level throughout a month. In a more typical situation the collector is connected to a tank so that the monthly sequence of weather and the load time distribution result in a fluctuating storage tank temperature and consequently a variable critical radiation level. The  $f$ -chart method was developed to overcome the restriction of constant critical level, but it is limited to systems which deliver energy to a load near 20°C. The method presented here is not restricted to loads at 20°C.

In this section, the  $\bar{\phi}$  concept is combined with the  $f$ -chart idea to produce a design method for closed-loop solar systems shown in Figure 21.3.1. In these systems energy supplied to the load must be above a specified minimum useful temperature, and it must be used at a constant coefficient of performance or thermal efficiency so that the load on the solar system can be calculated. (If the load is, for example, a heat engine that performs



**Figure 21.3.1** Schematic of a closed-loop solar energy system.

better as the temperature increases, then the thermal load on the solar system cannot be calculated from knowledge of the heat engine output.)

The storage tank is assumed to be pressurized so that energy dumping does not occur. The return temperature from the load is always at or above  $T_{min}$ . A separate auxiliary system is in parallel with the solar system and makes up any energy deficiency of the solar system.

The maximum monthly average daily energy that can be delivered by such a system is given by

$$\sum Q_u = A_c F_R (\overline{\tau\alpha}) \overline{H}_T \overline{\phi}_{max} \quad (21.3.1)$$

which is similar to Equation 21.2.3 except that  $\overline{\phi}$  is replaced by  $\overline{\phi}_{max}$ . The maximum daily utilizability is calculated from the minimum monthly average critical radiation ratio:

$$\overline{X}_{c,min} = \frac{F_R U_L (T_{min} - \overline{T}_a) / F_R (\overline{\tau\alpha})}{r_{t,n} R_n \overline{K}_T \overline{H}_o} \quad (21.3.2)$$

The method of calculating  $\overline{\phi}_{max}$  is exactly as illustrated in Example 21.2.1.

For a particular storage size–collector area ratio, Klein and Beckman (1979) correlated the results of many detailed simulations of the system of Figure 21.3.1 with two dimensionless variables. These variables are similar to the  $f$ -chart variables but are not exactly the same. The  $f$ -chart ordinate  $Y$  is replaced by  $\overline{\phi}_{max} Y$ :

$$\overline{\phi}_{max} Y = \overline{\phi}_{max} \frac{A_c F_R (\overline{\tau\alpha}) \overline{H}_T N}{L} \quad (21.3.3)$$



and the  $f$ -chart abscissa  $X$  is replaced by a modified variable  $X'$ :

$$X' = \frac{A_c F_R U_L (100) \Delta t}{L} \quad (21.3.4)$$

The change in  $X$  is that  $100 - \overline{T}_a$  has been replaced by an empirical constant 100 (or 180 if English units are used).

Figures 21.3.2(a) to (d) are  $\overline{\phi}$ ,  $f$ -charts for four different storage volume–collector area ratios. The information in these figures can be represented analytically by

$$f = \overline{\phi}_{max} Y - 0.015 [\exp(3.85 f) - 1] [1 - \exp(-0.15 X')] R_s^{0.76} \quad (21.3.5)$$



**Figure 21.3.2** The  $\bar{\phi}$ ,  $f$ -charts for various storage capacity-collector area ratios. From Klein and Beckman (1979).





Figure 21.3.2 (Continued)

where  $R_s$  is the ratio of the standard storage heat capacity per unit of collector area of  $350 \text{ kJ/m}^2 \text{ }^\circ\text{C}$  to the actual storage capacity. Although  $f$  is given implicitly by Equation 21.3.5, it is easy to solve for  $f$  by Newton's method or by trial and error.

The  $\bar{\phi}$ ,  $f$ -charts are used in the same manner as the  $f$ -charts. Values of  $\bar{\phi}_{\max} Y$  and  $X'$  are calculated from long-term radiation data and load patterns for the location in question. The value of  $f$  is then determined from the figures or from Equation 21.3.5. The product  $fL$  is the average monthly contribution of solar energy to meeting the load. The calculations are repeated for each month, from which the annual fraction  $\mathcal{F}$  can be determined.

### Example 21.3.1

An industrial solar energy system in Omaha, Nebraska (latitude  $41^\circ$ ), requires energy above  $60^\circ\text{C}$  at a rate of 12 kW for a 12-h period each day. The average ambient temperature and the monthly average daily radiation on a horizontal surface are given in the table below. The collector heat exchanger characteristics are  $F'_R(\tau\alpha)_n = 0.72$ ,  $F'_R U_L = 2.63 \text{ W/m}^2 \text{ }^\circ\text{C}$ ,  $F_R = 0.8$ ,  $(\bar{\tau}\alpha)/(\tau\alpha)_n = 0.94$ ,  $\beta = 40^\circ$ ,  $\gamma = 0$ , and  $A_c = 50 \text{ m}^2$ . The storage tank holds 4180 liters of water.

### Solution

The detailed calculations for January will be illustrated. Results of intermediate calculations for all months are given in the table. The radiation incident on the tilted surface is calculated by the methods of Section 2.19. The ground reflectance will be assumed to be 0.2.  $\bar{H}_o = 14.6 \text{ MJ/m}^2$  for January,  $\bar{K}_T = 0.59$ , and  $\bar{H}_d/\bar{H} = 0.31$ . From Equation 2.19.2,  $\bar{R} = 1.90$ , and  $r_{t,n}$  and  $r_{d,n}$  are 0.176 and 0.164, respectively.

The beam radiation conversion factor at noon,  $R_{b,n}$ , is 1.97 from Equation 1.8.3a. For an average day with  $K_T = 0.59$ , the ratio of diffuse to total radiation  $H_d/H = 0.38$  from Figure 2.11.2. From Equation 2.24.2, the noon ratio of radiation on a tilted surface to that on a horizontal surface for the average day of the month therefore

$$\begin{aligned} R_n &= \left(1 - \frac{0.164 \times 0.38}{0.176}\right) 1.97 + \frac{0.164 \times 0.38}{0.176} \left(\frac{1 + \cos 40}{2}\right) + 0.2 \left(\frac{1 - \cos 40}{2}\right) \\ &= 1.61 \end{aligned}$$

Then the ratio  $R_n/\bar{R} = 0.85$ .

The monthly average transmittance-absorptance product divided by the normal-incidence value is 0.94 from the method given in Section 5.10. The critical level at the minimum useful temperature is found from Equation 21.3.2:

$$\bar{X}_c = \frac{2.63[60 - (-5)]/(0.72 \times 0.94)}{0.176 \times 1.61 \times 8.6 \times 10^6/3600} = 0.37$$

The value of  $\bar{\phi}_{\max}$  is found from Figure 2.24.2 or Equation 2.24.4, with  $a = -1.123$ ,  $b = -0.376$ , and  $c = 0.672$ :

$$\bar{\phi}_{\max} = \exp[(-1.123 - 0.376 \times 0.85)(0.37 + 0.672 \times 0.37^2)] = 0.51$$

The value of  $Y$  is found from Equation 21.3.3,

$$Y = \frac{50 \times 0.72 \times 0.94 \times 1.90 \times 8.6 \times 10^6 \times 31}{12000 \times 12 \times 3600 \times 31} = 1.07$$

and  $\bar{\phi}_{\max} Y$  is then  $0.51 \times 1.07 = 0.54$ .

From Equation 21.3.4

$$X' = \frac{50 \times 2.63 \times 100 \times 31 \times 24}{12000 \times 12 \times 31} = 2.19$$

and it remains constant for the whole year. The storage capacity per unit of collector area is

$$\frac{mC_p}{A_c} = \frac{4180 \times 4190}{50} = 350 \text{ kJ/m}^2 \text{ } ^\circ\text{C}$$

so Figure 21.3.2(b) can be used to find  $f$ . Alternatively, Equation 21.3.5 can be used but a trial-and-error solution is necessary. With  $X'$  and  $\bar{\phi}_{\max} Y$  equal to 2.19 and 0.54, respectively,  $f = 0.52$ . The load for the month of January supplied by solar is then  $0.52 \times 16.1 = 8.3$  GJ. The other months are shown in the table. The annual fraction by solar is then the sum of column 22, the energy from solar, divided by the sum of column 21, the yearly load:

$$\mathcal{F} = 127.2/189.2 = 0.67$$

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22
Average Day	$\bar{H}_o$ , MJ/m <sup>2</sup>	$\bar{T}_a$ , °C	$\bar{H}$ , MJ/m <sup>2</sup>	$\bar{R}_b$	$\bar{K}_T$	$\frac{\bar{H}_d}{\bar{H}}$	$\bar{R}$	$r_{t,n}$	$r_{d,n}$	$R_{b,n}$	$R_n$	$\frac{R_n}{\bar{R}}$	$\frac{(\tau\alpha)_n}{(\tau\alpha)}$	$\bar{X}_c$ (min)	$\bar{\phi}$ (max)	$Y$	$\bar{\phi}Y$ (max)	$X'$	$f$	$L$ , GJ	$fL$ , GJ
Jan. 17	14.6	−5	8.6	2.32	0.59	0.31	1.90	0.176	0.164	1.91	16.1	0.85	0.94	0.37	0.51	1.07	0.54	2.19	0.52	16.1	8.3
Feb. 16	20.0	−3	11.6	1.83	0.58	0.32	1.55	0.160	0.148	1.65	1.39	0.90	0.94	0.34	0.55	1.17	0.64	2.19	0.60	14.5	8.7
Mar. 16	27.0	3	14.9	1.40	0.55	0.38	1.23	0.145	0.134	1.37	1.16	0.95	0.93	0.32	0.57	1.18	0.68	2.19	0.63	16.1	10.2
Apr. 15	34.4	10	19.4	1.08	0.56	0.37	1.03	0.131	0.121	1.06	1.03	1.03	0.93	0.26	0.63	1.29	0.81	2.19	0.74	15.6	11.6
May 15	39.6	17	21.5	0.89	0.54	0.39	0.91	0.122	0.112	1.03	0.98	1.08	0.91	0.24	0.66	1.23	0.81	2.19	0.74	16.1	11.9
June 11	41.8	22	23.6	0.81	0.56	0.37	0.86	0.188	0.109	0.97	0.96	1.11	0.90	0.21	0.70	1.27	0.88	2.19	0.80	15.6	12.4
July 17	40.6	25	23.8	0.84	0.59	0.35	0.88	0.120	0.110	1.00	0.97	1.10	0.91	0.18	0.73	1.33	0.97	2.19	0.86	16.1	13.8
Aug. 16	36.3	23	21.8	0.99	0.60	0.34	0.98	0.127	0.117	1.10	1.04	1.06	0.92	0.18	0.73	1.36	0.99	2.19	0.88	16.1	14.1
Sept. 15	29.6	19	15.6	1.26	0.56	0.37	1.14	0.139	0.128	1.28	1.12	0.98	0.93	0.22	0.69	1.22	0.84	2.19	0.76	15.6	11.9
Oct. 15	22.0	12	12.3	1.67	0.56	0.37	1.40	0.54	0.143	1.55	1.26	0.90	0.94	0.28	0.62	1.12	0.70	2.19	0.65	16.1	10.5
Nov. 14	15.8	4	8.3	2.17	0.52	0.37	1.72	0.171	0.159	1.88	1.42	0.82	0.93	0.39	0.53	0.92	0.49	2.19	0.46	15.6	7.2
Dec. 10	13.1	−2	7.0	2.50	0.53	0.36	1.94	0.181	0.169	2.09	1.55	0.80	0.94	0.44	0.48	0.89	0.42	2.19	0.41	<u>16.1</u>	<u>6.6</u>
Total																				189.6	127.2

The  $\bar{\phi}$ ,  $f$ -chart calculations overestimate  $f$  due to the assumptions that there are no losses from the tank and that the load heat exchanger is infinite in size. Corrections can be applied to eliminate both of these assumptions.

The rate at which energy is lost from the storage tank to the surroundings at  $T'_a$  is given by

$$\dot{Q}_{st} = (UA)_s (T_s - T'_a) \quad (21.3.6)$$

If  $T'_a$  and  $(UA)_s$  are both constant for a month, then integration of Equation 21.3.6 over a month yields the month's tank losses:

$$Q_{st} = (UA)_s (\bar{T}_s - T'_a) \Delta t \quad (21.3.7)$$

where  $\bar{T}_s$  is the monthly average tank temperature.

The total load on the solar system is the useful load plus the energy required to meet the tank losses. If the tank losses are modest so that the tank seldom drops below the minimum temperature, the solar system cannot tell the difference between the energy withdrawn to supply the load and the tank losses. In equation form, the fraction of the total load supplied by solar (including the tank losses) is

$$f_{TL} = \frac{L_s + Q_{st}}{L_0 + Q_{st}} \quad (21.3.8)$$

where  $L_s$  is the solar energy supplied to the load. Once  $Q_{st}$  is known,  $f_{TL}$  can be calculated from the  $\bar{\phi}$ ,  $f$ -charts in exactly the same manner as illustrated in Example 21.3.1. The usual interpretation for the fraction of the load supplied by solar energy is the ratio  $L_s/L_0$ , the solar energy supplied to the load divided by the useful load. If we use the symbol  $f$  for this fraction, Equation 21.3.8 can be written as

$$f = f_{TL} \left( 1 + \frac{Q_{st}}{L_0} \right) - \frac{Q_{st}}{L_0} \quad (21.3.9)$$

The tank losses cannot be calculated exactly, but two limiting values can be determined which should bracket the actual losses. A low estimate for tank losses is to assume the tank remains at  $T_{\min}$  all month. An upper bound for tank losses is to assume the average tank temperature is the same as the monthly average collector inlet temperature  $\bar{T}_i$ . The actual average tank temperature will be lower than this value since the collector does not operate 24 h a day. An estimate for  $\bar{T}_i$  can be found using the  $\bar{\phi}$ -charts. The average daily utilizability is

$$\bar{\phi} = \frac{f_{TL}}{Y} \quad (21.3.10)$$

With this value of  $\bar{\phi}$ , the monthly average operating critical level can be found from the  $(\bar{\phi}$ -charts) and  $\bar{T}_i$  can then be found. Klein and Beckman (1979) recommend that the arithmetic average of  $T_{\min}$  and  $\bar{T}_i$  be used to evaluate tank losses from Equation 21.3.7. A more conservative estimate is to use  $\bar{T}_i$  for estimating tank losses.

The process is iterative. An estimate is first made of the monthly average tank temperature from which  $Q_{st}$  is found from Equation 21.3.7. This estimate of tank losses is used as part of the total load and the  $\bar{\phi}$ ,  $f$ -charts method is used to estimate  $f_{TL}$ . Then  $\bar{\phi}$



is calculated from Equation 21.3.10 and  $\bar{X}_c$  is found from the  $\bar{\phi}$ -charts or Equation 2.13.5. This dimensionless critical level is used to find  $I_{Tc}$  and  $\bar{T}_i$  from Equation 21.2.4. The tank temperature is compared with the initial guess and the process is repeated if necessary. With the final value of  $Q_{st}$ , Equation 21.3.9 is used to find  $f$ , the fraction of the load supplied by solar.

### Example 21.3.2

Consider the solar system of Example 21.3.1 but include the effect of tank losses. The tank has  $(UA)_s = 5.9 \text{ W/}^\circ\text{C}$  and tank losses are to surroundings at  $20^\circ\text{C}$ . Do the calculations for January.

#### Solution

Only the month of January will be considered in this example. For January the average tank temperature will be assumed to be  $62^\circ\text{C}$  so that the tank losses, from Equation 21.3.7, are

$$Q_{st} = 5.9(62 - 20) \times 3600 \times 24 \times 31 = 0.7 \text{ GJ}$$

The total load is then  $16.1 + 0.7 = 16.8 \text{ GJ}$ . The values of  $\bar{\phi}_{\max} Y$  and  $X'$  are then  $16.1/16.8$  times the values from Example 21.3.1. Thus

$$\bar{\phi}_{\max} Y = \frac{0.54 \times 16.1}{16.8} = 0.52 \quad X' = \frac{2.19 \times 16.1}{16.8} = 2.10$$

From the  $\bar{\phi}$ ,  $f$ -charts (or Equation 21.3.5) we obtain

$$f_{TL} = 0.50$$

From Equation 21.3.10,

$$\bar{\phi} = \frac{0.50}{1.07} = 0.47$$

and  $X_c = 0.39$  from Figure 2.24.2 or Equation 2.24.4 (by trial and error). Since the original value of  $X_c$  was 0.37, the temperature difference of  $65^\circ\text{C}$  must be increased by the ratio  $0.39/0.37$ . The estimate of  $\bar{T}_i$  is then

$$\bar{T}_i = 65 \frac{0.39}{0.37} = 63.5^\circ\text{C}$$

and the average tank temperature is estimated to be  $(63.5 + 60)/2 = 61.7^\circ\text{C}$ , which is close to the initial guess so no iterations are necessary. The fraction by solar is then found from Equation 21.3.9:

$$f = 0.50 \left( 1 + \frac{0.7}{16.1} \right) - \frac{0.7}{16.1} = 0.48$$

The tank losses have reduced the fraction of the load by solar in January from 52 to 48% and result in  $0.48 \times 16.1 = 7.7 \text{ GJ}$  being supplied by solar rather than 8.3 GJ. On an annual basis the solar fraction is reduced from 67 to 64%. ■

The load heat exchanger adds thermal resistance between the storage tank and the load. This resistance elevates the storage tank temperature, which results in reduced useful energy collection and increased tank losses. In the development of the  $\bar{\phi}$ ,  $f$ -charts the load heat exchanger was assumed to be infinite in size, and consequently the value of  $f$  will be optimistic and a correction is necessary.

The average rate of solar energy supplied to the load is found by dividing  $L_S$  by the number of seconds during the month in which the load was required,  $\Delta t_L$ . The average increase in tank temperature necessary to supply the required energy rate is

$$\Delta T = \frac{L_S / \Delta t_L}{\varepsilon_L C_{\min}} = \frac{fL / \Delta t_L}{\varepsilon_L C_{\min}} \quad (21.3.11)$$

where  $\varepsilon_L$  is the load heat exchanger effectiveness and  $C_{\min}$  is the smaller of the two fluid capacity rates in the heat exchanger. This temperature difference is added to  $T_{\min}$  to find the monthly average critical radiation ratio from Equation 21.3.2. Since  $f$  is unknown at the beginning, it is necessary to first estimate  $\Delta T$  and then follow the procedure illustrated in Example 21.3.2 to find  $f$ . This value of  $f$  is used in Equation 21.3.11 to check the estimate of  $\Delta T$ . The calculations are illustrated in the following example.

### Example 21.3.3

Include the effect of a load heat exchanger on the performance of the system described in Examples 21.3.1 and 21.3.2. The heat exchanger effectiveness is 0.45 and the minimum capacitance rate is 3000 W/°C.

#### Solution

From Example 21.3.1 for January  $\bar{R} = 1.90$ ,  $R_n = 1.61$ , and  $R_n / \bar{R} = 0.85$ ;  $r_{t,n} = 0.176$ ,  $\bar{K}_T = 0.59$ ,  $\bar{H} = 8.6 \text{ MJ/m}^2$ ,  $\bar{T}_a = -5^\circ\text{C}$ , and  $(\bar{\tau}\bar{\alpha})/(\tau\alpha)_n = 0.94$ . As a first estimate of  $\Delta T$  use  $4^\circ\text{C}$ , so from Equation 21.3.2 the minimum critical radiation level is

$$\bar{X}_{c,\min} = \frac{\frac{2.63[60 + 4 - (-5)]}{0.72 \times 0.94}}{0.176 \times 1.61 \times 8.6 \times 10^6 / 3600} = 0.40$$

From Figure 2.24.2 or Equations 2.24.4,  $\bar{\phi}_{\max} = 0.49$ .

Since we wish to consider tank losses, a guess of the tank temperature is necessary to determine the total load. With a tank temperature of  $66^\circ\text{C}$ ,  $Q_{\text{st}} = 0.7 \text{ GJ}$ . The total load is  $16.1 + 0.7 = 16.8 \text{ GJ}$ . Then

$$Y = \frac{50 \times 0.72 \times 0.94 \times 1.90 \times 8.6 \times 10^6 \times 31}{16.8 \times 10^9} = 1.02$$

Thus  $\bar{\phi}_{\max} Y = 0.49 \times 1.02 = 0.50$ . The value of  $X'$  is

$$X' = \frac{50 \times 2.63 \times 100 \times 3600 \times 24 \times 31}{16.8 \times 10^9} = 2.11$$

From Equation 21.3.5 or Figure 21.3.2(b),  $f_{TL} = 0.48$ .

We must now check the tank loss approximation by evaluating  $\bar{X}_c$  at  $\bar{\phi} = 0.48/1.02 = 0.47$ . From Figure 2.24.2 or Equation 2.24.4,  $\bar{X}_c = 0.41$ . From Equation 21.3.2

$$\bar{T}_i - T_a = \frac{0.41 \times 0.176 \times 1.61 \times 8.6 \times 10^6 \times 0.72 \times 0.94}{2.63 \times 3600} = 73$$

so that  $\bar{T}_i = 73 - 5 = 68$ . The average temperature for tank losses is then

$$\bar{T} = (64 + 68)/2$$

Since this is the same as the guess, no iteration is necessary for tank losses. From Equation 21.3.9, the fraction by solar is

$$f = 0.48 \left( 1 + \frac{0.7}{16.1} \right) - \frac{0.7}{16.1} = 0.46$$

This value of  $f$  is used in Equation 21.3.11 to find  $\Delta T$ :

$$\Delta T = \frac{0.46 \times 16.1 \times 10^9 / (12 \times 3600 \times 31)}{0.45 \times 3000} = 4^\circ\text{C}$$

Since this is the same as the initial guess, the calculations for January are complete. The load met by solar is then  $0.46 \times 16.1 = 7.3$  GJ. ■

It is interesting to compare the January results of the last three examples. With no tank losses or load heat exchanger, the contribution by solar is 8.3 GJ. With tank losses considered, this was reduced to 7.7 GJ, and with the addition of the load heat exchanger, the energy supplied by solar is 7.3 GJ. These are not insignificant reductions.

Comparisons have been made of  $\bar{\phi}$ ,  $f$ -chart predictions with detailed performance predictions from the TRNSYS simulation. In Table 21.3.1, the results for space-heating systems which deliver energy to the load with a minimum temperature of  $20^\circ\text{C}$  are compared in six climates. Also, the  $f$ -chart results are presented. The estimates from all three methods are in good agreement.

**Table 21.3.1** Comparison of TRNSYS,  $f$ -Chart, and  $\bar{\phi}$ ,  $f$ -Chart Results for  $T_{\min} = 20^\circ\text{C}^a$

Location	Space Heating Annual Solar Load Fractions		
	TRNSYS	$f$ -Chart	$\bar{\phi}$ , $f$ -Chart
Albuquerque, NM (1959)	0.79	0.78	0.81
Blue Hill, MA (1958)	0.49	0.50	0.52
Boulder, CO (1956)	0.67	0.68	0.72
Madison, WI (1948)	0.45	0.47	0.47
Medford, OR (1969)	0.55	0.53	0.56
Seattle, WA (1960)	0.57	0.56	0.59

<sup>a</sup>From Klein and Beckman (1979).

**Table 21.3.2** Solar Load Fractions for Process Heating Application ( $T_{\min} = 60^{\circ}\text{C}$ )

Month	Albuquerque, NM		New York, NY	
	TRNSYS	$\bar{\phi}$ , $f$ -Chart	TRNSYS	$\bar{\phi}$ , $f$ -Chart
January	0.89	0.86	0.77	0.76
February	0.96	1.00	0.65	0.67
March	0.80	0.82	0.58	0.63
April	0.90	1.00	0.49	0.52
May	0.75	0.78	0.30	0.32
June	0.66	0.64	0.20	0.16
July	0.69	0.66	0.26	0.21
August	0.74	0.71	0.39	0.37
September	0.95	0.93	0.73	0.68
October	0.92	0.89	0.58	0.56
November	0.91	0.90	0.45	0.40
December	0.94	0.93	0.66	0.66
Year	0.84	0.84	0.50	0.49

<sup>a</sup>From Klein and Beckman (1979).

In Table 21.3.2, the monthly results of an industrial process heating example are compared for two climates. The process used energy above a minimum temperature of  $60^{\circ}\text{C}$  at a constant rate between 6 AM and 6 PM seven days a week. The agreement between TRNSYS and  $\bar{\phi}$ ,  $f$ -chart results is excellent in both locations. Differences between the TRNSYS results and  $\bar{\phi}$ ,  $f$ -chart results on a monthly basis are affected by energy carryover from month to month, and the radiation data used in the TRNSYS simulations may be too small a sample to adequately represent the long-term statistical distribution.

The  $\bar{\phi}$ ,  $f$ -chart method has potential for misuse, and as a result its limitations need to be emphasized. The method is intended for applications in which the load can be characterized by a single temperature,  $T_{\min}$ . The load must be relatively uniform on a day-to-day basis as it will produce inaccurate results for processes in which the load distribution is highly irregular. The method is not applicable for systems in which energy supplied to the load is used at an efficiency or COP that depends upon temperature, such as the solar Rankine engine.

## 21.4 SUMMARY

In this chapter three design methods have been presented:  $\phi$ ,  $\bar{\phi}$ , and  $\bar{\phi}$ ,  $f$ -chart. The  $\phi$  method can usually be replaced by the  $\bar{\phi}$  method with approximately a fourfold reduction in calculation. The hourly and daily utilizability methods require that the collector critical radiation level remain constant for a month, which means that the difference between the collector inlet temperature and ambient temperature is nearly fixed. In practice this applies best to systems with very large storage tanks or to systems with no storage in which the collector inlet fluid is from a constant temperature source. Neither of these two situations is very common. The  $\bar{\phi}$ ,  $f$ -charts were developed for closed-loop systems with finite storage where the load is characterized by a single minimum useful temperature. This is a common system, but it does not cover all practical applications. Systems that are not covered by these methods must be designed using detailed simulations.

## REFERENCES

- Collares-Pereira, M. and A. Rabl, *Solar Energy*, **23**, 223 (1979a). "Derivation of Method for Predicting Long Term Average Energy Delivery of Solar Collectors."
- Collares-Pereira, M. and A. Rabl, *Solar Energy*, **23**, 235 (1979b). "Simple Procedure for Predicting Long Term Average Performance of Nonconcentrating and of Concentrating Collectors."
- Hottel, H. C. and A. Whillier, in *Transactions of the Conference on the Use of Solar Energy* (E. F. Carpenter, ed.), Vol. **2**, Part I, University of Arizona Press, Tucson, Arizona, p. 74 (1958). "Evaluation of Flat-Plate Collector Performance."
- Klein, S. A., *Solar Energy*, **21**, 393 (1978). "Calculation of Flat-Plate Collector Utilizability."
- Klein, S. A. and W. A. Beckman, *Solar Energy*, **22**, 269 (1979). "A Generalized Design Method for Closed-Loop Solar Energy Systems."
- Liu, B. Y. H. and R. C. Jordan, *Solar Energy*, **7**, 53 (1963). "A Rational Procedure for Predicting the Long-Term Average Performance of Flat-Plate Solar-Energy Collectors."
- Whillier, A., Sc.D. Thesis, Mechanical Engineering, Massachusetts Institute of Technology (1953). "Solar Energy Collection and Its Utilization for House Heating."

# Design of Passive and Hybrid Heating Systems

The principles underlying passive (and active) solar processes are outlined in Chapters 1 to 11, and passive heating and cooling processes and phenomena associated with them are described in Chapters 14 and 15. In this chapter we deal with questions of estimating the annual performance of several types of passive building-heating systems. The solar-load ratio correlation method developed at Los Alamos Scientific Laboratory is first introduced. The application of utilizability methods to direct-gain and collector-storage wall systems is shown. Then design methods for two hybrid systems are outlined, for active collection–passive storage systems and for systems having significant fractions of annual loads carried by both active and passive processes. This combination of methods will allow the annual performance of a wide variety of passive and hybrid systems to be estimated.

## 22.1 APPROACHES TO PASSIVE DESIGN

Thermal design of passive buildings is closely interrelated to architectural design, as the collection of solar energy and its storage are accomplished in elements of the structure itself. There is a spectrum of methods for estimating long-term thermal performance of these buildings that range from practical experience (“do it this way in this climate and it will work”), to use of charts and tables that are based on combinations of experience and calculations, to correlation and utilizability methods that are the counterparts of the methods for active systems, and to the use of special computer programs developed for passive buildings. An example of such a program is Energy-10. The Energy-10 website describes the program as follows: “ENERGY-10 integrates daylighting, passive solar heating, and low-energy cooling strategies with energy-efficient shell design and mechanical equipment. It enables designers to make good decisions about energy efficiency early in the design process. ENERGY-10 was developed with a building industry task force that included architects, engineers, builders, and utility representatives. The program is geared toward buildings of 10,000 square feet or less—in fact, that’s where the “10” in ENERGY-10 comes from.”

Estimation of solar energy absorbed in a building is not difficult and can be done by the methods outlined in Sections 5.10 and 5.11. Load calculations are more uncertain but can be done by the methods outlined in Chapter 9 or other suitable means that the designer may wish to use. An important problem in estimating passive system performance is the

estimation of how much of the absorbed energy cannot be used because it is available at a time when it exceeds the loads and the capacity of the building to store it (i.e., how much energy is “dumped”). The thermal problem that is addressed in this chapter is coupled with the aesthetic problem, the challenge of making the building attractive and functional.

Mazria (1979) presents specific recommendations on sizing of solar apertures and providing storage capacity. For example, for a direct-gain system in cold climates, the ratio of area of south-facing glass to floor area should be 0.19 to 0.38; if masonry storage is to be used, the interior walls and floors should be a minimum of 0.1 m (4 in.) thick; movable insulation should provide a tight cover for the glazing. A design based on these specific recommendations can then be “fine tuned” by calculation of heat losses, solar gains, average indoor temperature, indoor temperature fluctuations, auxiliary energy requirements, and economics.

The Method 5000 developed in France and described by Lebens and Myer (1984) is a three-part method: first, calculation of heat loss from the building; second, calculation of the total solar energy absorbed by the passive solar components; third, calculation of the utilized solar and internal gains and thus of the auxiliary energy requirements. The critical step is the third. Utilization factors are obtained from correlations as a function of absorbed solar and internal gains, the average ambient temperature, a heat loss coefficient of the building, and the thermal mass of the building.

These design methods, and the solar-load ratio and unutilizability methods to be described in more detail in the following sections, have a common basic feature: They all use correlations of results of simulations to determine long-term performance. The correlating variables, the definitions of terms, the ways in which the correlations are used, and the generality of the correlations are, however, very different from one method to another. Care must be exercised in the use of these methods to ensure that the terminology and correlations are understood and properly used.

## 22.2 SOLAR-LOAD RATIO METHOD

The solar-load ratio (SLR) method is widely used for designing direct-gain, collector-storage wall, and sunspace systems; it was developed by Balcomb et al. (1980, 1983a,b). It is a method of calculating annual requirements for auxiliary energy based on extensive simulation studies of performance of many passive heating systems done with the simulation program PASOLE (McFarland, 1978). The simulations were in turn compared to experiments on test cells. A total of 94 standard system configurations were simulated and correlations were developed for their performance. In addition, sensitivity curves were developed to assess the impact on performance of a number of design and climatic variables. Background information on this method is in volume 1 of the *Passive Solar Design Handbook* (1980), and details of the method and sensitivity analyses are in volumes 2 and 3 (Balcomb et al., 1980, 1983a,b). The method is presented in *Passive Solar Heating Analysis* (Balcomb et al., 1984) and summarized in Balcomb et al. (1983b). In this section we show the essentials of the SLR method for selected systems of each of the three types and examples of the sensitivity curves. The significant end result of SLR calculations is the annual requirement for auxiliary energy; individual months may be substantially in error, but annual results of the method are generally within  $\pm 3\%$  of results of detailed simulations.

The SLR method is based on a set of defined terms that must be properly used in order for the correlations to work. All energy terms and calculations are on a monthly basis. Some of the terms in the SLR method have dimensions, and care must be exercised to see that appropriate units are used. In particular, in SI units, energy quantities in this method are in watt-hours (Wh) rather than in joules. In the discussion to follow, loss coefficient–area products are in watts per degree Celsius, and loads and auxiliary energy quantities are in watt-hours. Important definitions and symbols follow.

The **solar wall** is the glazed building wall that provides the solar gains that are to be estimated. The **solar aperture** is that portion of the wall that is glazed to admit solar radiation. The **net glazing area**  $A_r$  is the area of the solar aperture after mullions, framing, and so on, have been subtracted. The **projected area**  $A_{rp}$  is the projection of the net glazing area on a vertical plane normal to the azimuth of the glazing. (Note that for direct-gain and collector-storage walls,  $A_r$  and  $A_{rp}$  are the same; for sunspaces,  $A_r$  will be substantially larger than  $A_{rp}$ .)

The SLR correlations are based on loads that do not include losses<sup>1</sup> through the solar aperture. The **net reference load**  $L_{ns}$  is the monthly heat loss from the nonsolar portions of the building, that is, from the entire building envelope except the solar aperture. The **net load coefficient** is the net reference load per degree of temperature difference between indoors and outdoors, that is, a  $UA$  of the nonsolar parts of the building.<sup>2</sup> The net reference load in watt-hours for the month if  $(UA)_{ns}$  is in watts per degree Celsius and  $DD$  is °C-days for the month is

$$L_{ns} = 24(UA)_{ns} (DD) \quad (22.2.1)$$

where  $DD$  is the number of degree-days in the month using the appropriate base temperature. (See Chapter 9 for a method for calculating degree-days to any desired base temperature.)

The **gross reference load**  $L$  is the heat loss from the building, including both solar and nonsolar portions of the building. The **total load coefficient** is the gross reference load per degree of difference between indoor and outdoor temperature, that is, a  $UA$  for the whole building. In a form analogous to Equation 22.2.1, the load in watt-hours is

$$L = 24(UA)(DD) \quad (22.2.2)$$

The building load coefficients  $(UA)_{ns}$  and  $UA$  can be calculated by standard methods (e.g., ASHRAE, 2005).

The **solar savings fraction**  $f_{ns}$  is the fraction of the net reference load that is met by solar energy.<sup>3</sup> Thus

$$f_{ns} = 1 - L_A/L_{ns} \quad (22.2.3)$$

The **load collector ratio**  $LCR$  is the ratio of the net load coefficient to the projected area of the solar aperture:

$$LCR = \frac{24(UA)_{ns}}{A_{rp}} \quad (22.2.4)$$

<sup>1</sup>Losses through the solar aperture are, however, included in the calculation of auxiliary energy required, as will be shown.

<sup>2</sup>It can be thought of as the  $UA$  of the building if the solar wall were adiabatic.

<sup>3</sup>The fraction  $f_{ns}$  is not comparable to the solar fraction as defined and used in active systems or to that in the unutilizability passive design methods described in Sections 22.3 and 22.4. Since  $f_{ns}$  is the fraction of a nonexistent load, it should not be viewed as having physical significance.



The **load collector ratio for the solar aperture**  $LCR_s$  is the ratio of the loss coefficient of the solar aperture (based on the projected area) to the projected area. The 94 standard systems are so defined that  $LCR_s$  is determined for each of them, and appropriate values are tabulated.

The monthly average daily solar radiation absorbed in the building per unit of projected area  $\overline{S'}$  is calculated by the methods of Sections 5.10 and 14.4 if there are shading overhangs. In equation form,

$$\overline{S'} = \frac{\overline{S}A_r}{A_{rp}} \quad (22.2.5)$$

The general correlation for solar savings fraction that is applicable to all three types of systems (direct-gain, collector-storage wall, and sunspace) is

$$f_{ns} = 1 - (1 - F)K \quad (22.2.6a)$$

$$K = 1 + \frac{G}{LCR} \quad (22.2.6b)$$

$$F = \begin{cases} B - Ce^{-DX} & \text{if } X > R \\ AX & \text{if } X < R \end{cases} \quad (22.2.6c)$$

In either case,  $F \leq 1$ . Here  $X$  is a generalized SLR given by

$$X = \frac{\frac{N\overline{S'}}{DD} - LCR_s \times H}{LCR \times K} \quad (22.2.6d)$$

In these equations  $A$ ,  $B$ ,  $C$ ,  $D$ ,  $G$ ,  $H$ ,  $LCR_s$ , and  $R$  are constants that have been determined for each of the 94 passive system types and  $N$  is the number of days in the month.

The auxiliary energy required for each month is obtained by rearranging Equation 22.2.3:

$$L_A = L_{ns}(1 - f_{ns}) \quad (22.2.7)$$

The calculation is done for each month of the year or heating season to provide an estimate of the annual auxiliary energy required.

Original development of the SLR method was done in English units, and some of the defined quantities are not dimensionless. In Balcomb et al. (1983b), constants and examples are given in both English and SI units. A summary of units that should be used in calculations using either set of units is in Table 22.2.1. The table also shows the symbols used by Balcomb et al. and those used in this book.

Tables 22.2.2 and 22.2.3 indicate design parameters for a set of 22 passive system designs selected from the 94 designs for which correlations have been developed. This limited set covers a variety of combinations of direct-gain, collector-storage wall, and sunspace systems; various glazings; storage characteristics; and systems with and without night insulation. Table 22.2.4 gives the necessary constants for Equations 22.2.4 for

**Table 22.2.1** Units Used in the SLR Design Method<sup>a</sup>

Quantity	Symbols		Units	
	This Book	Balcomb et al.	SI	English
Net glazing area	$A_r$	—	m <sup>2</sup>	ft <sup>2</sup>
Projected area	$A_{rp}$	$A_p$	m <sup>2</sup>	ft <sup>2</sup>
Net reference load	—	—	Wh	Btu
Net load coefficient	$24(UA)_{ns}$	$NLC$	Wh/°C-day	Btu/°F-day
Gross reference load	$L$	—	Wh	Btu
Total load coefficient	$24(UA)$	$TLC$	Wh/°C-day	Btu/°F-day
Load collector ratio	$LCR$	$LCR$	Wh/m <sup>2</sup> °C-day	Btu/ft <sup>2</sup> °F-day
Solar savings fraction	$f_{ns}$	$SSF$	—	—
Degree-days	$DD$	$DD$	°C-day	°F-day
Absorbed solar radiation	$\bar{S}$	$S'$	Wh/m <sup>2</sup>	Btu/ft <sup>2</sup>
Dimensional correlation constant	$G$	$G$	(Wh/m <sup>2</sup> °C-day) <sup>-1</sup>	(Btu/ft <sup>2</sup> °F-day) <sup>-1</sup>

<sup>a</sup> Adapted from Balcomb et al. (1983a).**Table 22.2.2** Design Parameters for Direct-Gain and Collector-Storage Wall Passive Systems<sup>a</sup>

Type	Thermal Storage Capacity, kJ/m <sup>2</sup> °C	Storage <sup>b</sup> Mass Thickness, m	Number of Glazings	Storage Mass Glazing Area Ratio	Night <sup>c</sup> Insulation
<i>Direct-Gain Systems</i>					
A1	613	0.051	2	6	No
A2	613	0.051	3	6	No
A3	613	0.051	2	6	Yes
C1	1227	0.102	2	6	No
C2	1227	0.102	3	6	No
C3	1227	0.102	2	6	Yes
<i>Vented Collector-Storage Wall Systems</i>					
A1	306	0.0152	2	1	No
A2	459	0.0229	2	1	No
A3	613	0.0305	2	1	No
A4	919	0.0457	2	1	No
D2	613	0.0305	3	1	No
D3	613	0.0305	1	1	Yes
E2 <sup>d</sup>	613	0.0305	3	1	No
E3 <sup>d</sup>	613	0.0305	1	1	Yes

<sup>a</sup> Adapted from Balcomb et al. (1983b).<sup>b</sup> Mass (or wall) thickness assuming a volumetric heat capacity of 620 kJ/m<sup>3</sup> °C.<sup>c</sup> Night insulation; when used it is R9 ( $U_N = 0.63$  W/m<sup>2</sup> °C).<sup>d</sup> The E systems have a selective surface with  $\alpha = 0.95$ ,  $\varepsilon = 0.10$  on the glazing side of the wall. For nonselective surfaces,  $\alpha = 0.95$  and  $\varepsilon = 0.90$ .

**Table 22.2.3** Design Parameters for Sunspace Passive Systems<sup>a</sup>

Type	Geometry <sup>b</sup>	Glazing <sup>c</sup> Slope	Common <sup>d</sup> Wall	End Walls	Night Insulation
A1	Attached	50	Masonry	Opaque	No
A2	Attached	50	Masonry	Opaque	Yes
B3	Attached	90/30	Masonry	Glazed	No
B4	Attached	90/30	Masonry	Glazed	Yes
B5	Attached	90/30	Insulated	Opaque	No
B6	Attached	90/30	Insulated	Opaque	Yes
E3	Semi-enclosed	90/30	Insulated	Common	No
E4	Semi-enclosed	90/30	Insulated	Common	Yes

<sup>a</sup> Adapted from Balcomb et al. (1983b).<sup>b</sup> See Figure 15.7.1.<sup>c</sup> Double-glazing, south-facing, slopes as indicated and shown in Figure 15.7.1.<sup>d</sup> Common wall separates sunspace from balance of building. If masonry, 0.30 m thick,  $k = 1.73 \text{ W/m}^\circ\text{C}$ . If insulated, conductance is  $0.28 \text{ W/m}^2^\circ\text{C}$ .

this set. Note that all of the entries in this table are dimensionless except  $LCR_s$ , which has units of  $\text{Wh/m}^2^\circ\text{C-day}$ , and  $G$ , which has units of  $(\text{Wh/m}^2^\circ\text{C-day})^{-1}$ .

In the development of the correlations a number of assumptions were made in addition to those indicated in the tables. The room temperatures were assumed to be in the range of  $18.3$  to  $23.9^\circ\text{C}$  and sunspace temperatures in the range of  $7.2$  to  $35.0^\circ\text{C}$ . The collector-storage wall top and bottom vents were each assumed to have areas of 3% of the projected area, with the vertical distance between vents 2.4 m. Night insulation, when used, was assumed to be in place from 5:30 PM to 7:30 AM throughout the year. Shading was taken as negligible and ground reflectance was taken as 0.3. Sketches of the three types of sunspaces included in the table are shown in Figure 22.2.1. Glazing is assumed to be glass 3.2 mm thick with 12.7-mm spacing between panes.

The SLR correlations (in addition to those shown here) included unvented collector-storage walls, water walls, and designs of sunspaces similar to those shown but with different design parameters.

### Example 22.2.1

A residential building in Tulsa (latitude  $36^\circ$ ) has a south-facing vented concrete collector-storage wall of  $15 \text{ m}^2$  area. The wall is 0.305 m thick, and the thermal storage capacity is  $610 \text{ kJ/m}^2^\circ\text{C}$ . Triple glazing is used, a flat-black paint is applied to the outer surface of the masonry, and no night insulation is provided. The building exclusive of the solar wall has  $UA = 200 \text{ W/}^\circ\text{C}$ , including effects of infiltration and internal generation. The average January daily absorbed solar radiation and degree-days to the appropriate base are  $567 \text{ MJ/m}^2$  per day and  $491^\circ\text{C-days}$ ; these are calculated from the data in Appendix D using the methods of Chapters 2 and 5. Here  $(\tau\alpha)_n$  was taken as 0.70.

Estimate the January requirement for auxiliary energy to heat this building.

**Table 22.2.4** Solar-Load Ratio Correlation Parameters<sup>a</sup>

Type	A	B	C	D	R	G	$LCR_s$	H
<i>Direct-Gain Systems</i>								
A1	0.5650	1.0090	1.0440	0.7175	0.3931	53.1	0	0
A2	0.5906	1.0060	1.0650	0.8099	0.4681	29.9	0	0
A3	0.5442	0.9715	1.1300	0.9273	0.7086	15.0	0	0
C1	0.6344	0.9887	1.5270	1.4380	0.8632	54.5	0	0
C2	0.6763	0.9994	1.4000	1.3940	0.7604	29.9	0	0
C3	0.6182	0.9859	1.5660	1.4370	0.8990	13.6	0	0
<i>Vented Collector-Systems Storage Wall</i>								
A1	0	1	0.9194	0.4601	-9	0	73.7	1.11
A2	0	1	0.9680	0.6318	-9	0	73.7	0.92
A3	0	1	0.9964	0.7123	-9	0	73.7	0.85
A4	0	1	1.0190	0.7332	-9	0	73.7	0.79
D2	0	1	1.0150	0.8994	-9	0	52.2	0.80
D3	0	1	1.0346	0.7810	-9	0	50.5	1.08
E2	0	1	1.0476	1.0050	-9	0	49.3	0.66
E3	0	1	1.0919	1.0739	-9	0	31.2	0.61
<i>Sunspace Systems</i>								
A1	0	1	0.9587	0.4770	-9	0	105.5	0.83
A2	0	1	0.9982	0.6614	-9	0	59.0	0.77
B3	0	1	0.9689	0.4685	-9	0	109.5	0.82
B4	0	1	1.0029	0.6641	-9	0	55.0	0.76
B5	0	1	0.9408	0.3866	-9	0	92.5	0.97
B6	0	1	1.0068	0.6778	-9	0	48.2	0.84
E3	0	1	0.9565	0.4827	-9	0	111.2	0.81
E4	0	1	1.0214	0.7694	-9	0	61.3	0.79

<sup>a</sup>From Balcomb et al. (1983b).**Solution**

This system is essentially the same as the vented collector-storage wall system D2 in Table 22.2.4. From the table the constants for this system are  $A = 0$ ,  $B = 1$ ,  $C = 1.015$ ,  $D = 0.8994$ ,  $R = -9$ ,  $G = 0$ ,  $LCR_s = 52.2 \text{ Wh/m}^2 \text{ }^\circ\text{C-day}$ , and  $H = 0.80$ . Then


$$\text{Net load coefficient} = 200 \times 24 = 4800 \text{ Wh/}^\circ\text{C-day}$$

$$LCR = \frac{24(UA)_{ns}}{A_{rp}} = \frac{4800}{15} = 320 \text{ Wh/m}^2 \text{ }^\circ\text{C-day}$$

$$K = 1 + \frac{G}{LCR} = 1$$

From Equation 22.2.6d,

$$X = \left( \frac{31 \times 5.67 \times 10^6}{3600 \times 491} - 52.2 \times 0.8 \right) (320)^{-1} = 0.180$$



**Figure 22.2.1** Geometry of sunspaces included in Tables 22.3 and 22.4. Adapted from Balcomb et al. (1983a).

From Equation 22.2.6c,

$$F = 1 - 1.015 \exp(-0.8994 \times 0.180) = 0.137$$

From Equation 22.2.6a,

$$f_{ns} = 1 - (1 - F) = 0.137$$


From Equation 22.2.7 the auxiliary energy is then

$$L_A = 4800 \times 3600 \times 491(1 - 0.137) = 7.3 \text{ GJ}$$

■

Figure 22.2.2 is an example of the interrelationships of the  $LCR$ ,  $\overline{N\bar{S}}/DD$ , and  $f_{ns}$ . It is for direct-gain system A1; the shapes of other curves are generally similar. As the load collector ratio diminishes at a fixed value of  $\overline{N\bar{S}}/DD$ , the solar savings fraction rises and  $L_A$  (the ultimate criterion of a system's worth) will decrease. At a fixed  $LCR$ , as the ratio  $\overline{N\bar{S}}/DD$  increases, the solar savings fraction will increase but the increase is sharper at low values of  $LCR$  than at high.

The SLR method includes correlations for 94 designs. However, systems other than those of the 94 designs will need to be evaluated. Thus the sensitivity of the solar savings fraction to several design parameters has been computed using simulations. Two types of sensitivities are shown. The first is a set of general relationships of sensitivity of all systems in all climates to design parameters; this is illustrated here by the response of  $f_{ns}$



**Figure 22.2.2** Sample plot of  $f_{ns}$  as function of  $LCR$  and  $NS/DD$ . Adapted from Balcomb et al. (1980).

to the amount of night insulation used. The second type includes sensitivities of specific types of systems in specific locations to design parameter changes; many of these have been determined, and a single illustration is included here.

Night insulation can have very substantial effects on passive heating performance. The reference insulation conductance used in development of the SLR correlations for systems with night insulation is  $0.63 \text{ W/m}^2 \text{ }^\circ\text{C}$  ( $R9$ ), a value that may be difficult to achieve, so it is necessary to assess the effects of lesser levels. Figure 22.2.3 shows a correction factor to be applied to the difference in  $f_{ns}$  for the reference insulation ( $R9$ ) and no insulation for direct-gain and collector-storage wall systems. The factor is given by the equation


$$Y = \frac{1 + R_o/1.59}{R_o/R} \quad (22.2.8)$$

where  $R_o$  is  $0.32 \text{ m}^2 \text{ }^\circ\text{C/W}$  for direct-gain systems,  $0.56 \text{ m}^2 \text{ }^\circ\text{C/W}$  for water wall, and  $0.81 \text{ m}^2 \text{ }^\circ\text{C/W}$  for masonry collector-storage wall systems. The  $f_{ns}$  for a system with an intermediate level of night insulation is

$$f_{ns} = f_{ns, \text{no ins.}} + Y(f_{ns, \text{ref. ins.}} - f_{ns, \text{no ins.}}) \quad (22.2.9)$$

### Example 22.2.2

Calculation of the solar savings fraction of a direct-gain system in a particular location and month shows  $f_{ns} = 0.46$  with no insulation and  $f_{ns} = 0.78$  with the reference night insulation. What would be the  $f_{ns}$  if the system were to be insulated at night with  $R3$  insulation having a resistance  $R = 0.53 \text{ m}^2 \text{ }^\circ\text{C/W}$ ?



**Figure 22.2.3** Effectiveness of night insulation for levels other than the reference levels. Adapted from Balcomb et al. (1980).

### Solution

From Figure 22.2.3 or Equation 22.2.8,


$$Y = \frac{1 + 0.32/1.59}{1 + 0.32/0.53} = 0.75$$

Then for the insulation with  $R = 0.53 \text{ m}^2 \text{ } ^\circ\text{C/W}$ ,

$$f_{ns} = 0.46 + 0.75(0.78 - 0.46) = 0.70$$

An example of a specific sensitivity curve, the dependence on storage mass, thickness, and ratio of mass area to glazing area of direct-gain systems with particular values of  $LCR$  in Madison, Wisconsin, is shown in Figure 22.2.4. The reference system performance is shown by heavy dots. The solid curves are for systems with load collector ratio of  $148 \text{ Wh/m}^2 \text{ } ^\circ\text{C-day}$ , and the dashed curves are for  $LCR$  of  $415 \text{ Wh/m}^2 \text{ } ^\circ\text{C-day}$ . In both cases night insulation with an  $R$  value of  $1.59 \text{ m}^2 \text{ } ^\circ\text{C/W}$  is used.

The sensitivity of  $f_{ns}$  to storage mass and absorptance, number of glazings, and temperature limits has been computed for direct-gain systems. Effects of storage mass and properties, glazing properties, wind speed, wall-to-room heat transfer coefficient, and several other parameters have been worked out for collector-storage wall systems. See the *Passive Solar Design Handbook* (Balcomb et al., 1983a,b) or *Passive Solar Heating Analysis* (Balcomb et al., 1984) for details.



**Figure 22.2.4** Example of the SLR method sensitivity curve: effects of thickness of storage mass and ratio of mass area to glazing area for double-glazed, direct-gain systems with the reference night insulation at two values of  $LCR$ , in Madison. Adapted from Balcomb et al. (1983a).


## 22.3 UNUTILIZABILITY DESIGN METHOD: DIRECT GAIN

The unutilizability method (the “double-U method”) for design of direct-gain and collector-storage wall systems, developed by Monsen et al. (1981, 1982), is based on the concept that a passively heated building can be viewed as a collector with finite heat capacity. Analyses are developed for estimating the auxiliary energy requirements of two limiting cases. The first is for an infinite-capacitance structure that can store all energy in excess of loads. The second is for a zero-capacitance structure that can store no energy. Correlations are used to determine where between these limits the auxiliary energy requirements of a real structure must lie.

As is the case with  $f$ -chart and SLR design methods, the double-U method calculations are done on a monthly basis. The significant end result of the calculations is the annual auxiliary energy required. The method requires calculation of loads; these calculations can be done by any method the designer wishes. The simplest load calculation method is the degree-day method; allowance can be made in the base temperature to account for night thermostat setback, night insulation on the direct-gain windows, and internal generation (other than solar gains through the direct-gain receiver). In contrast to the SLR method the load as defined for this method is for the whole building, including the direct-gain aperture.

Figure 22.3.1 shows the monthly energy streams entering and leaving a direct-gain structure. Solar energy absorbed in the room is  $\overline{H}_T N(\overline{\tau\alpha}) A_r = N\overline{S}A_r$ . The energy lost through the building shell by conduction, by infiltration, and so on, is shown as the load. At times there will be insufficient solar energy to meet loads and auxiliary energy  $Q_{\text{Aux}}$  must be supplied. There will also be times when there is excess solar energy absorbed that is not used to meet losses and cannot be stored, and this  $Q_D$  must be vented, or “dumped.” The diagram does not show energy stored; at any time during a month sensible heat may be stored in or removed from the structure if it has thermal capacitance.





**Figure 22.3.1** Monthly energy streams for a direct-gain building. Energy storage is not indicated.

Consider first a hypothetical building with **infinite storage capacity**. During a month, all absorbed energy in excess of the load is stored in the structure. The temperature of the conditioned space remains constant, as infinite capacitance for storage implies zero temperature change. This stored energy can be used at any time to offset auxiliary energy needs. However, month-to-month carryover is not considered.

A monthly energy balance gives the auxiliary energy requirement for the infinite capacity building,  $Q_{Aux,\infty}$ :

$$Q_{Aux,\infty} = (L - N\bar{S}A_r)^+ \quad (22.3.1)$$

where  $L$  is the load for the entire building, that is, the auxiliary energy that would be required if the transmittance of the glazing were zero. The superscript plus sign indicates that only positive values of the difference of monthly energy quantities in the parentheses are considered. Energy is dumped for this infinite-capacity building only when the monthly auxiliary energy is zero so that  $Q_{D,\infty} = (N\bar{S}A_r - L)^+$ .

Next consider a hypothetical **zero-storage-capacity** building. Since there is no storage capacity, energy deficits must be made up as they occur by use of auxiliary energy and excess solar energy is dumped as it is absorbed. The temperature in the building is again fixed, but by addition or removal of energy rather than energy from storage. An instantaneous energy balance on the zero-capacity structure gives the rate at which energy must be removed,  $\dot{Q}_{D,0}$ :


$$\dot{Q}_{D,0} = [I_T (\tau\alpha) A_r - (UA)_h (T_b - T_a)]^+ \quad (22.3.2)$$

As with collectors in active systems, a critical radiation level can be defined as that level at which the gains just offset the losses so that  $\dot{Q}_{D,0}$  is zero:

$$I_{Tc} = \frac{(UA)_h (T_b - T_a)}{(\tau\alpha) A_r} \quad (22.3.3)$$

In this case absorbed radiation above the critical level must be dumped and is “unutilizable.” The dumped energy for the month  $Q_{D,0}$  can then be written as

$$Q_{D,0} = A_r (\tau\alpha) \int_{\text{month}} (I_T - I_{Tc})^+ dt \quad (22.3.4)$$



**Figure 22.3.2** Dumped, useful, and auxiliary energy for a zero-capacitance direct-gain system. From Monsen et al. (1981).

Figure 22.3.2 shows operation over a sequence of days of a zero-capacitance system. It is assumed that over a month  $I_{T,c}$  can be considered to be constant at its monthly average value given by Equation 22.3.5:

$$I_{T,c} = \frac{(UA)_h (T_b - \bar{T}_a)}{(\bar{\tau}\bar{\alpha}) A_r} \quad (22.3.5)$$

Energy above  $I_{T,c}$  must be dumped, and energy below  $I_{T,c}$  is useful. Thus the shaded area represents dumped energy, the white areas under the curves represent useful solar energy, and the cross-hatched areas represent auxiliary energy for the zero-capacitance building.

Equation 22.3.4 can be expressed in terms of the monthly average utilizability  $\bar{\phi}$ , defined in Equation 2.24.1:

$$\bar{\phi} = \frac{1}{\bar{H}_T N} \sum_{\text{days}} \sum_{\text{hours}} (I_T - I_{T,c})^+ \quad (22.3.6)$$

So the dumped energy for this zero-capacity building is given by

$$Q_{D,0} = N \bar{S} A_r \bar{\phi} \quad (22.3.7)$$

The amount of auxiliary energy required by the zero-capacitance building can now be determined from a monthly energy balance. It is the load plus dumped energy less the absorbed solar energy:

$$Q_{\text{Aux},0} = L - (1 - \bar{\phi}) N \bar{S} A_r \quad (22.3.8)$$

Equations 22.3.1 and 22.3.8 are bounds on the amount of auxiliary energy required. A correlation based on simulations indicates where within these limits the auxiliary energy for a real system will lie. The correlations have been developed in terms of the fraction of the load supplied by solar energy, which is defined in the same way as for active systems (i.e., as  $f = 1 - Q_{\text{Aux}}/L$ ). A SLR is defined as

$$X = \frac{\bar{H}_T N (\bar{\tau}\bar{\alpha}) A_r}{L} = \frac{N \bar{S} A_r}{L} \quad (22.3.9)$$

For the infinite-capacitance system, from Equation 22.3.1,  $X$  is the solar fraction  $f_\infty$  so that

$$f_\infty = \left(1 - \frac{Q_{\text{Aux},\infty}}{L}\right) = X \quad (22.3.10)$$

For the zero-capacitance case

$$f_0 = (1 - \bar{\phi})X \quad (22.3.11)$$

In the simulation study of systems with finite capacitance, the building interior was assumed to consist of a single zone at uniform temperature with an effective building thermal capacitance (mass times heat capacity)  $C_b$ . The temperature was allowed to float between minimum and maximum thermostat set temperatures. Auxiliary energy was provided to keep the temperature at the minimum setpoint temperature, and ventilation was used to dump energy and keep the temperature below the specified maximum.

The monthly solar fraction  $f$  was found to correlate with the solar-load ratio  $X$  and a storage-dump ratio:

$$Y = \frac{C_b \Delta T_b}{\overline{H_T}(\overline{\tau\alpha}) A_r \bar{\phi}} = \frac{C_b \Delta T_b}{\overline{S} A_r \bar{\phi}} = \frac{N C_b \Delta T_b}{Q_{D,0}} \quad (22.3.12)$$

where  $C_b$  is the effective thermal capacitance,  $\Delta T_b$  is the difference in upper and lower temperatures (i.e., the range over which building temperature is allowed to float), and the units are such that  $Y$  is dimensionless. Values of  $C_b$  are available from Table 9.5.1. ( $C_b$  is approximately  $120 \text{ kJ/m}^2 \text{ }^\circ\text{C}$  based on floor area for typical residential frame construction.) The parameter  $Y$  is the monthly ratio of the maximum storage capacity of the building to the solar energy that would be dumped if the building has zero thermal capacitance. The zero- and infinite-capacitance buildings thus have values of  $Y$  of zero and infinity, respectively.

A correlation for a monthly solar fraction  $f$ , in terms of  $X$ ,  $Y$ , and  $\bar{\phi}$ , is

$$f = \min \{PX + (1 - P)(3.082 - 3.142\bar{\phi})[1 - \exp(-0.329X)], 1\} \quad (22.3.13a)$$

where

$$P = [1 - \exp(-0.294Y)]^{0.652} \quad (22.3.13b)$$


The auxiliary energy required is then calculated from  $f$  by

$$Q_{\text{Aux}} = L(1 - f) \quad (22.3.14)$$

Note that since the load varies with aperture, values of  $f$  calculated this way for different solar apertures are not comparable with one another. It is appropriate to compare auxiliary energy requirements  $L_A$  for different apertures.

An example of an  $f$ -versus- $X$  plot for various values of  $Y$  for  $\bar{\phi} = 0.6$  is shown in Figure 22.3.3.

The annual auxiliary energy requirements predicted with Equations 22.3.12 and 22.3.13 have been compared to results of detailed simulations for a wide variety of system



**Figure 22.3.3** The  $(1 - Q_{Aux}/L)$  versus  $X$  and  $Y$  for direct-gain system for  $\bar{\phi} = 0.6$ . (Note: Use Equations 22.3.13 for other values of  $\bar{\phi}$ .) From Monsen et al. (1981).

parameters and climates. The standard deviation of the differences of annual solar fractions was 3%. (The standard deviation of monthly differences was 6%.)

### Example 22.3.1

A well-insulated residence in Springfield, Illinois, is to be heated by direct gain. There are four rooms having direct-gain south-facing windows; the characteristics of each of the energy absorption structures are as outlined in Example 5.10.1. The area of each of the direct-gain windows is  $4.5 \text{ m}^2$  and the absorptance of the cavities is 0.87. In the table that follows  $\bar{S}$  and  $(\bar{\tau}\alpha)$  are reproduced from Example 5.10.1.

The effective heat capacity of the building (which is of moderately heavy construction) is estimated to be  $41.4 \text{ MJ}/^\circ\text{C}$ . The allowable temperature swing is  $6^\circ\text{C}$  and the low setpoint temperature is  $18.3^\circ\text{C}$ . The  $UA$  of the building exclusive of the direct-gain windows is  $138 \text{ W}/^\circ\text{C}$ , and the  $U$  of the windows (which do not have night insulation) is  $4.17 \text{ W}/\text{m}^2 \cdot ^\circ\text{C}$ .

Estimate the annual auxiliary energy requirements for heating this building.

### Solution

The calculations for January are outlined in detail. The results for the year are summarized in the table below. The degree-day data are from Appendix D. (The low setpoint is  $18.3^\circ\text{C}$ , the same as the base temperature for the degree-day data in the table.)

First calculate the load. The  $UA$  of the entire building, including the four direct-gain windows of area  $4 \times 4.5 = 18 \text{ m}^2$ , is

$$(UA)_h = 138 + 18 \times 4.17 = 213 \text{ W}/^\circ\text{C}$$

The January load is then

$$L = 213 \times 657 \times 24 \times 3600 = 12.09 \text{ GJ}$$

Second, calculate the solar-load ratio  $X$  from Equation 22.3.9:

$$X = 7.60 \times 10^6 \times 31 \times \frac{18}{12.09 \times 10^9} = 0.351$$

Third, calculate  $I_{Tc}$  with Equation 22.3.5;  $\bar{T}_a = -3^\circ\text{C}$ , so

$$I_{Tc} = \frac{213[18.3 - (-3)]}{0.70 \times 18} = 360 \text{ W/m}^2$$

Fourth,  $\bar{\phi}$  is to be calculated. The procedure is essentially the same as that of Example 2.24.1. The quantities needed and their values for the mean day of January are as follows:

$$\begin{aligned} \omega_s &= 71.3^\circ, & r_{t,n} &= 0.174, & r_{d,n} &= 0.162 \\ \frac{H_d}{H} &= 0.7 & \text{at } K_T &= 0.436, & R_{b,n} &= \frac{\cos|\phi - \delta - \beta|}{\cos|\phi - \delta|} = 1.80 \\ R_n &= 1.108, & \bar{R} &= \frac{\bar{H}_T}{H} = \frac{10.84}{6.63} = 1.63 \\ \frac{\bar{R}}{R_n} &= \frac{1.63}{1.108} = 1.47 \end{aligned}$$

We can now calculate  $\bar{X}_c$ :

$$\bar{X}_c = \frac{I_{Tc}}{R_{t,n} R_n \bar{H}} = \frac{360 \times 3600}{0.174 \times 1.180 \times 6.63 \times 10^6} = 1.014$$

With these, we get  $\bar{\phi}$  from Equation 2.24.4, with  $\bar{K}_T = 0.436$ ,  $a = -0.332$ ,  $b = -1.171$ , and  $c = 0.254$ :

$$\bar{\phi} = \exp\{-(0.332 - 1.171 \times 0.678)[1.014 + 0.254(1.014)^2]\} = 0.239$$

Fifth,  $Y$  can now be calculated from its defining equation:

$$Y = \frac{41.4 \times 10^6 \times 6.0}{7.6 \times 10^6 \times 18 \times 0.239} = 7.60$$

Sixth, a solar fraction for January is calculated from Equation 22.3.13:

$$\begin{aligned} P &= [1 - \exp(-0.294) \times 7.60]^{0.652} = 0.929 \\ f &= 0.929 \times 0.351 + (1 - 0.929)(3.082 - 3.142 \times 0.239) \\ &\quad \times [1 - \exp(-0.329 \times 0.351)] = 0.344 \end{aligned}$$

The auxiliary energy is then calculated with Equation 22.3.14:

$$Q_{\text{Aux}} = 12.09 \times 10^9 (1 - 0.344) = 8.0 \text{ GJ}$$

Finally, the significant result of the calculations is the sum of the monthly auxiliary energy requirements. From the table, the annual auxiliary energy required is 29.5 GJ.

Month	$\bar{S}$ , MJ/m <sup>2</sup>	$(\bar{\tau}\bar{\alpha})$	$L$ , GJ	$X_c$	$I_{Tc}$ , W/m <sup>2</sup>	$\bar{\phi}$	$Y$	$f$	$Q_{\text{Aux}}$ , GJ
January	7.60	0.70	12.09	1.01	360	0.24	7.60	0.34	7.93
February	8.47	0.67	9.90	0.79	340	0.28	5.93	0.42	5.79
March	7.32	0.63	8.15	0.64	269	0.34	5.62	0.48	4.27
April	6.36	0.58	3.90	0.30	129	0.59	3.66	0.74	1.00
May	5.84	0.55	1.56	0.07	28	0.90	2.64	1.00	0.00
June	5.63	0.54	0.33	0.00	0	1.00	2.45	1.00	0.00
July	5.66	0.53	0.18	0.00	0	1.00	2.44	1.00	0.00
August	6.42	0.55	0.26	0.00	0	1.00	2.15	1.00	0.00
September	7.98	0.60	0.87	0.00	0	1.00	1.73	1.00	0.00
October	9.35	0.66	3.07	0.15	77	0.80	1.86	1.00	0.00
November	8.44	0.70	7.12	0.51	208	0.48	3.39	0.55	3.20
December	6.61	0.70	<u>10.89</u>	1.08	327	0.27	7.81	0.33	<u>7.28</u>
Totals			58.3						29.5


## 22.4 UNUTILIZABILITY DESIGN METHOD: COLLECTOR-STORAGE WALLS

The unutilizability concept developed for direct-gain systems has been applied, with modifications, to collector-storage wall systems (Monsen et al., 1982). The presence of the wall introduces significant differences in the manner in which the energy balances on the building are written, in the definition of the critical radiation level and SLR, and in the form of the correlations for solar contribution. As with the direct-gain system, the double-U method establishes the limiting cases of zero- and infinite-capacitance buildings; where a real building performance lies between the limits and is determined by correlations based on simulations. The calculations are again done monthly, with the significant final result being the annual amount of auxiliary energy needed for the passively heated structure.

The monthly energy flows in a collector-storage wall building are shown schematically in Figure 22.4.1. The heating loads are shown in two parts. Load  $L_{\text{ad}}$  is that which would be experienced if the collector-storage wall were replaced by an adiabatic wall. It is the same as the net reference load in the SLR method and can be calculated by conventional means such as the degree-day method (Equation 22.4.1a). The load  $L_w$  is the monthly energy loss from the building through the collector-storage wall that would be experienced if the transmittance of the glazing for solar radiation were zero and can be estimated by Equation 22.4.1b:

$$L_{\text{ad}} = (UA)_{\text{ad}}(DD) \quad (22.4.1a)$$

$$L_w = U_w A_r(DD) \quad (22.4.1b)$$



**Figure 22.4.1** Monthly energy flows for a collector-storage wall building. Storage of energy in the wall or structure is not indicated. From Monsen et al. (1982).

The wall conductance is

$$U_w = \frac{1}{\frac{1}{\bar{U}_L} + \frac{1}{U_i} + \frac{\delta}{k}} \quad (22.4.2)$$

where  $U_i$  is the inside heat transfer coefficient between the inner wall surface and the air in the room. ASHRAE (2005) recommends a value of  $8.3 \text{ W/m}^2 \text{ }^\circ\text{C}$  for  $U_i$ . The wall thickness is  $\delta$  and its thermal conductivity is  $k$ ;  $\bar{U}_L$  is the average heat loss coefficient from the outer wall surface through the glazing to ambient. Here,  $\bar{U}_L$  is conceptually the same as loss coefficients from plates of flat-plate collectors and has typical values for one to three glazings of 3.7, 2.5, and  $1.9 \text{ W/m}^2 \text{ }^\circ\text{C}$ , respectively. If night insulation is used,  $\bar{U}_L$  can be estimated as a time average of day and night conductances:

$$\bar{U}_L = (1 - i)U_L + i \left( \frac{U_L}{1 + R_N U_L} \right) \quad (22.4.3)$$

where  $U_L$  is the loss coefficient without night insulation,  $R_N$  is the thermal resistance of the night insulation, and  $i$  is the fraction of the 24-h day in which the insulation is in place.

The energy dump stream,  $Q_D$  in Figure 22.4.1, can be considered as the sum of two energy flows. The loads  $L_{ad}$  and  $L_w$  are calculated assuming the indoor temperature to be at the low thermostat set temperature. In general, the room temperature can be expected to rise above this temperature, and the actual losses from the building will be greater than  $L_{ad} + L_w$ ; this increase represents one contribution to  $Q_D$ . The other contribution is energy which must be removed from the building to keep the indoor temperature from exceeding the high thermostat set temperature.

Let  $Q_n$  be the net monthly heat transfer through the collector-storage wall into the heated space. It is at any time a complex function of wall parameters and meteorological conditions. The wall can be modeled as a distributed network of resistors, capacitors, and current sources, as shown in Figure 8.6.2. However, by assuming (a) that there are no vents in the wall to allow circulation between the room and the gap between the wall and the glazing<sup>4</sup> and (b) that the thermal storage capacity of a wall (the maximum change in

<sup>4</sup>Utzinger et al. (1980) show that there is little difference in the annual performance of vented and unvented collector-storage walls.

internal energy of a wall) over a month is negligible compared to the total energy flow through the wall over the month,<sup>5</sup> it can be shown that the monthly average temperature profile through the wall is linear. Thus, for monthly average computations, the network of Figure 8.6.2 is replaced by the simple resistance network shown in Figure 22.4.2. An estimation of  $Q_n$  for a month can be based on this network.

A monthly average daily energy balance on the outer (energy-absorbing) surface of the wall shows how the absorbed energy is distributed to losses to ambient through the glazing and by conduction through the wall with subsequent transfer into the heated space. If  $T_a$  and  $\bar{U}_L$  are assumed constant at their monthly average values,

$$\bar{S} = U_k (\bar{T}_w - T_r) \Delta t + \bar{U}_L (\bar{T}_w - \bar{T}_a) \Delta t \quad (22.4.4)$$

where  $U_k$  is the conductance from the outer wall surface to the room given by

$$U_k = \frac{U_i k}{k + U_i \delta} \quad (22.4.5)$$

Here  $\bar{T}_w$  is the monthly average outer wall temperature and  $T_r$  is the room temperature which is assumed to be at the low thermostat set temperature; additional losses through the wall occurring as a result of the average room temperature being above  $T_r$  will be accounted for in  $Q_D$ . The number of time units in a day is  $\Delta t$ .

The average outer wall temperature can be found from Equation 22.4.4:


$$\bar{T}_w = \frac{\bar{S} + (U_k T_r + \bar{U}_L \bar{T}_a) \Delta t}{(U_k + \bar{U}_L) \Delta t} \quad (22.4.6)$$

This can be used to calculate the net monthly heat transfer to the building:

$$Q_n = U_k A_r (\bar{T}_w - T_r) \Delta t N \quad (22.4.7)$$

We turn now to the question of establishing the limits of performance of buildings with collector-storage walls. For a hypothetical building with infinite thermal capacitance, all of the net gain  $Q_n$  can be used. Allowing no month-to-month carryover of stored energy, a monthly energy balance on this infinite-capacitance building is

$$Q_{\text{Aux},\infty} = (L_{\text{ad}} - Q_n)^+ \quad (22.4.8)$$



**Figure 22.4.2** Monthly average resistance network for collector-storage walls. From Mosen et al. (1982).

<sup>5</sup>Typically, the storage capacity of a collector-storage wall is less than the heating loads on the building for a single day.



A hypothetical building having zero thermal capacitance in the collector-storage wall and in the rest of the structure will have the maximum auxiliary energy requirements. A collector-storage wall with zero mass can be considered to be a radiation shield which alters the amplitude but not the time of the solar gains to the building. A monthly energy balance on this zero-capacitance building gives

$$Q_{\text{Aux},0} = (L_{\text{ad}} - Q_n + Q_D)^+ \quad (22.4.9)$$

where  $Q_D$ , the energy dumped, is the month's energy entering the building through the collector-storage wall that does not contribute to reduction of the auxiliary energy requirement. Here  $Q_D$  can be determined by integrating  $\dot{Q}_D$ , the rate at which excess energy must be removed to prevent the indoor temperature from rising above the low thermostat set temperature. At any time,  $\dot{Q}_D$  is the difference between the rate of heat transfer through the collector-storage wall into the building and the rate of energy loss from the rest of the building:

$$\dot{Q}_D = [U_k A_r (T_w - T_r) - (UA)_{\text{ad}} (T_b - T_a)]^+ \quad (22.4.10)$$

An energy balance on the absorbing surface of the hypothetical zero thermal capacity collector-storage wall at any time gives

$$I_T (\tau\alpha) A_r = U_L A_r (T_w - T_a) + U_k A_r (T_w - T_r) \quad (22.4.11)$$

This can be solved for  $T_w$ :

$$T_w = \frac{I_T (\tau\alpha) + U_L T_a + U_k T_r}{U_L + U_k} \quad (22.4.12)$$

which when substituted into Equation 22.4.10 yields

$$\dot{Q}_D = \left[ U_k A_r \left( \frac{I_T (\tau\alpha) - U_L (T_r - T_a)}{U_L + U_k} \right) - (UA)_{\text{ad}} (T_b - T_a) \right]^+ \quad (22.4.13)$$

Assuming  $(\tau\alpha)$  and  $T_a$  to be constant at their monthly mean values of  $(\overline{\tau\alpha})$  and  $\overline{T}_a$ , Equation 22.4.13 can be integrated over the month to give  $Q_D$  for this zero-capacitance building:

$$Q_D = \frac{U_k A_r (\overline{\tau\alpha})}{U_L + U_k} \sum (I_T - I_{Tc})^+ \quad (22.4.14)$$

where the critical radiation level  $I_{Tc}$  which makes  $\dot{Q}_D$  zero is given by

$$I_{Tc} = \frac{1}{(\overline{\tau\alpha}) A_r} \left[ (UA)_{\text{ad}} \left( \frac{U_L}{U_k} + 1 \right) \frac{T_b - \overline{T}_a}{T_r - \overline{T}_a} + U_L A_r \right] (T_r - \overline{T}_a) \quad (22.4.15)$$

The summation in Equation 22.4.14 is the same as that in the definition of the daily utilizability  $\bar{\phi}$  Equation 2.24.1. Thus

$$Q_D = \frac{U_k A_r \bar{S} N \bar{\phi}}{U_L + U_k} \quad (22.4.16)$$

Equations 22.4.8 and 22.4.9 provide estimates of the limits of the performance of collector-storage wall systems. The solar fractions corresponding to the limits are defined as

$$f_\infty = 1 - \frac{Q_{\text{Aux},\infty}}{L_{\text{ad}} + L_w} = \frac{L_w + Q_n}{L_{\text{ad}} + L_w} \quad (22.4.17)$$

and

$$f_0 = 1 - \frac{Q_{\text{Aux},0}}{L_{\text{ad}} + L_w} = f_\infty - \frac{U_k}{U_L - U_k} \bar{\phi} X \quad (22.4.18)$$

where the solar-load ratio  $X$  is defined as

$$X = \frac{\bar{S} N A_r}{L_{\text{ad}} + L_w} \quad (22.4.19)$$

To establish where between these limits a real system will operate, correlation methods are used. A parameter is needed that describes the storage capacity of the system that includes the storage capacity of the building,  $S_b$ , and that of the wall,  $S_w$ . The building thermal storage capacity for a month (i.e., with  $N$  cycles) is

$$S_b = C_b (\Delta T_b) N \quad (22.4.20)$$

where  $C_b$  is the effective building storage capacitance and  $\Delta T_b$  is the allowable temperature swing, that is, the difference between the high and low thermostat setpoints. Values of  $C_b$  can be estimated from information in Table 9.5.1. The storage capacity of the wall for the month (i.e., with  $N$  cycles) is

$$S_w = C_p \delta A_r \rho (\Delta T_w) N \quad (22.4.21)$$

where  $C_p$ ,  $\rho$ ,  $\delta$ , and  $A_r$  are the heat capacity, density, thickness, and area of the wall, respectively, and  $\Delta T_w$  is one-half of the difference of the monthly average temperatures of the outside and inside surfaces of the wall (the monthly average gradient through the wall being linear). The heat transfer through the wall into the heated space,  $Q_n$ , can be expressed in terms of  $\Delta T_w$  as

$$Q_n = \frac{2kA_r}{\delta} (\Delta T_w) \Delta t N \quad (22.4.22)$$

Thus

$$S_w = \frac{\rho C_p \delta^2 Q_n}{2k \Delta t} \quad (22.4.23)$$

A correlation for  $f$  [here defined as  $1 - Q_{\text{Aux}}/(L_{\text{ad}} + L_w)$ ] has been developed from simulations. Here,  $f$  is a function of  $f_\infty$  and a dimensionless storage-dump ratio defined as the ratio of a weighted storage capacity of the building and wall to the energy that would be dumped by a building having zero capacitance:

$$Y = \frac{S_b + 0.047 S_w}{Q_D} \quad (22.4.24)$$


The correlation for  $f$  is shown in Figure 22.4.3. The equation for the solar fraction is<sup>6</sup>

$$f = \min \{ P f_\infty + 0.88(1 - P)[1 - \exp(-1.26 f_\infty)], 1 \} \quad (22.4.25a)$$

$$P = [1 - \exp(-0.144 Y)]^{0.53} \quad (22.4.25b)$$

[Monsen et al. (1982) did not use the zero-capacitance limit in the correlation. However, Equations 22.4.25 and 22.4.18 predict approximately the solar fraction at zero thermal storage.]

To estimate the annual performance of a collector-storage wall system, a set of steps for each month are to be followed. First, the month's absorbed radiation is calculated by the methods of Section 5.10. Second, the loads  $L_{\text{ad}}$  and  $L_w$  are estimated, taking into account



**Figure 22.4.3** Correlation for  $f$  as function of  $f_\infty$  and storage-dump ratio  $Y$ . From Monsen et al. (1982).

<sup>6</sup>In Equation 22.4.18,  $f_\infty$  can exceed unity, and it should not be limited to the range 0 to 1 when used in Equation 22.4.25a.

internal generation if necessary. Third, the month's net heat gain across the collector-storage wall  $Q_n$  is estimated using Equations 22.4.5 to 22.4.7. Fourth, the energy dump that would occur in a zero-capacitance system  $Q_D$  is calculated from Equation 22.4.16. This requires that daily utilizability be known based on the critical radiation level given by Equation 22.4.15. Fifth, a series of additional parameters are needed to calculate  $f$  from Equation 22.4.25. These are  $f_\infty$  (from Equation 22.4.17),  $S_b$  and  $S_w$  (the building and wall effective thermal capacitances from Equations 22.4.20 and 22.4.23), and  $Y$  (the storage-dump ratio, Equation 22.4.24). The last step is to calculate the auxiliary energy required for the month:

$$Q_{\text{Aux}} = (L_{\text{ad}} + L_w)(1 - f) \quad (22.4.26)$$

The monthly auxiliary energy requirements are then summed to get the annual auxiliary energy needs.

### Example 22.4.1

A collector-storage wall system is to be designed for Springfield, Illinois. The daily average energy absorbed by this wall in megajoules per square meter,  $(\overline{\tau\alpha})$ , the ambient temperature, and the number of degree days to base 18.3°C are given in the table for Example 22.3.1. The south-facing vertical collector-storage wall is double glazed. Night insulation is not to be used.

The building has the following characteristics. The minimum allowable inside temperature  $T_r = 18.3^\circ\text{C}$ , the allowable temperature swing  $\Delta T = 6^\circ\text{C}$ , and internal energy generation is small. The  $(UA)_h = 138 \text{ W}/^\circ\text{C}$ , and the effective heat capacity of the building  $C_b = 23.5 \text{ MJ}/^\circ\text{C}$ . The overall heat transfer coefficient from the storage wall to the interior is  $8.3 \text{ W}/\text{m}^2 \text{ }^\circ\text{C}$ .

The wall has the following characteristics. It is masonry with a density of  $2105 \text{ kg}/\text{m}^3$ , and its heat capacity is  $0.95 \text{ kJ}/\text{kg } ^\circ\text{C}$ . The wall is  $0.46 \text{ m}$  thick and has an area of  $18 \text{ m}^2$  (the same as the solar aperture). The loss coefficient for the double-glazed wall to the outside is estimated by the methods of Section 6.4 to be  $2.50 \text{ W}/\text{m}^2 \text{ }^\circ\text{C}$ . Thus  $\delta_w = 0.46 \text{ m}$ ,  $\rho_w = 2105 \text{ kg}/\text{m}^3$ ,  $C_{p,w} = 0.95 \text{ kJ}/\text{kg } ^\circ\text{C}$ ,  $A_r = 18 \text{ m}^2$ ,  $U_L = 2.50 \text{ W}/\text{m}^2 \text{ }^\circ\text{C}$ ,  $U_i = 8.3 \text{ W}/\text{m}^2 \text{ }^\circ\text{C}$ , and  $k_w = 1.73 \text{ W}/\text{m } ^\circ\text{C}$ .

What is the estimated need for auxiliary energy for this building for the year?

### Solution

The solution for January is shown in detail. The results of the calculations for all months are tabulated. The steps are outlined below.

*Step 1:* The values of  $\overline{S}$  and  $(\overline{\tau\alpha})$  are reproduced from Examples 5.10.1 and 22.3.1.

*Step 2:* Calculate the loads  $L_{\text{ad}}$  and  $L_w$  with Equations 22.4.1 and 22.4.2 using degree-day data from Appendix D:

$$L_{\text{ad}} = 138 \times 657 \times 24 \times 3600 = 7.83 \text{ GJ}$$

$$U_w = \left( \frac{1}{2.5} + \frac{1}{8.3} + \frac{0.46}{1.73} \right)^{-1} = 1.27 \text{ W}/\text{m}^2 \text{ }^\circ\text{C}$$

$$L_w = 1.27 \times 18 \times 657 \times 24 \times 3600 = 1.30 \text{ GJ}$$

*Step 3:* Estimate  $Q_n$  from Equations 22.4.5 to 22.4.7. The conductance from the outer wall to the room is

$$U_k = \frac{8.3 \times 1.73}{1.73 + 8.3 \times 0.46} = 2.59 \text{ W/m}^2 \text{ } ^\circ\text{C}$$

The average wall temperature is

$$\bar{T}_w = \frac{7.6 \times 10^6 + [2.59 \times 18.3 + 2.5(-3)] \times 86,400}{(2.59 + 2.5) \times 86,400} = 25.1^\circ\text{C}$$

Then the net heat transferred into the rooms through the storage wall is

$$Q_n = 2.59 \times 18(25.1 - 18.3) \times 86,400 \times 31 = 0.849 \text{ GJ}$$

*Step 4:* Estimate  $Q_D$  that would occur if the capacitance of the system were zero using Equation 22.4.16. This requires the calculation of  $I_{Tc}$  and  $\bar{\phi}$ :

$$I_{Tc} = \frac{1}{0.7 \times 18} \left[ 138 \left( \frac{2.5}{2.59} + 1 \right) \frac{18.3 - (-3)}{18.3 - (-3)} + 2.5 \times 18 \right] \\ \times [18.3 - (-3)] = 535 \text{ W/m}^2$$

(Note that  $T_r$  and  $T_b$  are the same in this example. As shown in Chapter 9, where internal generation  $\dot{g}$  is significant,  $T_b$  will be lower than  $T_r$ .)

Next calculate  $\bar{\phi}$ . The procedure is like that outlined in Example 22.3.1. The following intermediate results are obtained:  $\omega_s = 71.3^\circ$ ,  $r_{t,n} = 0.174$ ,  $r_{d,n} = 0.162$ ,  $H_d/H$  (at  $K_T = 0.436$ ) = 0.70,  $R_{b,n} = 1.80$ ,  $R_n = 1.108$ ,  $\bar{R} = 1.63$ , and  $\bar{R}/R_n = 1.47$ . Thus

$$\bar{X}_c = \frac{535 \times 3600}{0.174 \times 1.108 \times 6.63 \times 10^6} = 1.50$$

Now calculate  $\bar{\phi}$  from Equation 2.24.4. As in Example 22.3.1,  $a = -0.332$ ,  $b = -1.171$ ,  $c = 0.254$ :

$$\bar{\phi} = \exp[(-0.332 - 1.171 \times 0.678)(1.50 + 0.254 \times 1.50^2)] = 0.097$$

We can now calculate  $Q_D$  from Equation 22.4.16:

$$Q_D = \frac{2.59 \times 18 \times 7.60 \times 10^6 \times 31 \times 0.097}{2.5 + 2.59} = 0.208 \text{ GJ}$$



## 22.5 HYBRID SYSTEMS: ACTIVE COLLECTION WITH PASSIVE STORAGE

Active air or liquid collectors may be used in heating of buildings in which storage is provided in the structure of the building. This hybrid system has the advantages of control of thermal losses from the receiver (the collector) by shutdown when the radiation is below the critical level and elimination of the cost and complexity of a separate storage system. It has the disadvantages of the significant temperature swings needed in the building to provide storage and, for given building structure and allowable temperature swing, upper limits on the amount of solar energy that can be delivered to the building. Active collection–passive storage systems may be applied as retrofits to buildings that cannot accommodate large active systems, particularly in areas of high building density where shading limits the utility of direct-gain or collector-storage wall passive systems but roof areas are available for collection.

The systems are relatively simple. Air heating collectors or liquid heating collectors with liquid–air heat exchangers may be used to supply energy that is distributed by airflow to the heated spaces. Controls are required to turn on collector fluid flow when collection is possible and to turn off the collector or otherwise dump energy when the building interior temperature reaches its maximum allowable value.

A method for estimation of annual performance of these systems based on utilizability concepts has been devised by Evans and Klein (1984a). It is similar to that of Monsen et al. (1981) for direct-gain passive systems (Section 22.3), with estimation of active collector performance by  $\bar{\phi}$  methods. Two critical radiation levels are defined, one for the collector and one for the building. Limits of performance are again established by consideration of infinite- and zero-capacitance buildings, with the performance of real buildings determined by correlations based on simulations.

As shown in Section 21.2, the output of an active collector for a month can be expressed as

$$\sum Q_u = A_c \bar{H}_T F_R (\bar{\tau}\alpha) N \bar{\phi}_c = A_c F_R \bar{S} N \bar{\phi}_c \quad (22.5.1)$$

where the monthly average utilizability associated with collecting energy is designated as  $\bar{\phi}_c$ . The heat removal factor in Equation 22.5.1 and subsequent equations should include the modifications discussed in Chapter 10 (i.e.,  $F'_R$  should be used for  $F_R$ ). The critical radiation level to be used in determining  $\bar{\phi}_c$  is

$$I_{Tc,c} = \frac{F_R U_L (\bar{T}_i - \bar{T}_a)}{F_R (\bar{\tau}\alpha)} \quad (22.5.2)$$

where all symbols are the same as for Equation 21.2.2 and  $\bar{T}_i$  is the monthly average inlet temperature, in this case the building temperature during collection. For the limiting cases of zero and infinite building capacitance,  $T_i$  will be constant. For real cases,  $T_i$  will vary above the minimum building temperature, but this variation normally does not significantly affect  $\sum Q_u$ .

For a building with infinite storage capacity the monthly energy balance is

$$Q_{\text{Aux},\infty} = \left( L - \sum Q_u \right)^+ \quad (22.5.3)$$

For a building with zero capacitance, energy will have to be dumped if at any time the solar gain exceeds the load. The analysis is exactly parallel to that in Section 22.3 for direct-gain systems. The intensity of radiation incident on the collector that is just enough to meet the building heating load without dumping is called the dumping critical radiation level  $I_{Tc,d}$ . On a monthly average basis it is given by

$$I_{Tc,d} = \frac{(UA)_h (\bar{T}_b - \bar{T}_a) + A_c F_R U_L (\bar{T}_i - \bar{T}_a)}{A_c F_R (\bar{\tau}\bar{\alpha})} \quad (22.5.4)$$

where  $(UA)_h$  is again the overall loss coefficient-area product of the building,  $\bar{T}_b$  is the average building base temperature, and  $\bar{T}_i$  is the average building interior temperature.

Thus for the zero-capacitance building, on a monthly average basis, a radiation level of  $I_{Tc,c}$  is necessary to permit collection. A radiation level of  $I_{Tc,d}$  is necessary for the collector to just meet the building loads without dumping. This is shown in Figure 22.5.1 for a sequence of three days. Energy above  $I_{Tc,d}$  must be dumped and can be estimated as


$$Q_D = A_c F_R \bar{S} N \bar{\phi}_d \quad (22.5.5)$$

where  $\bar{\phi}_d$  is the monthly average utilizability (more accurately, unutilizability) based on  $I_{Tc,d}$ . The energy supplied by the collector that is useful in meeting the heating load of this zero-capacitance building is then the difference between the total energy collected and the energy dumped:

$$Q_{u,b} = \sum Q_u - Q_D = A_c F_R \bar{S} N (\bar{\phi}_c - \bar{\phi}_d) \quad (22.5.6)$$

The auxiliary energy required for the month for this zero-capacitance building is then

$$Q_{\text{Aux},0} = \left( L - \sum Q_u + Q_D \right)^+ \quad (22.5.7)$$



**Figure 22.5.1** Sequence of days showing the collecting critical radiation level  $I_{Tc,c}$  and the dumping critical radiation level  $I_{Tc,d}$  for the zero-capacitance house.



Equations 22.5.3 and 22.5.7 establish the limits of auxiliary energy requirements. The auxiliary energy requirements for a building with finite capacitance can be estimated by correlations of  $f$ , the fraction of the month's energy supplied from solar energy, with a solar-load ratio  $X$  and a storage-dump ratio  $Y$ , where  $X$  and  $Y$  must be properly defined for the active collection-passive storage system. The SLR is

$$X = \frac{A_c F_R \bar{S} N}{L} \quad (22.5.8)$$

The storage-dump ratio is

$$Y = \frac{C_b \Delta T_b}{A_c F_R \bar{S} \bar{\phi}_d} = \frac{N C_b \Delta T_b}{Q_D} \quad (22.5.9)$$

The building capacitance is the product of the passive energy storage capacity  $C_b$  and the allowable building temperature swing  $\Delta T_b$ , as in Equation 22.3.12.

The correlation for monthly solar fraction is in terms of  $\bar{\phi}_c$ , the monthly collecting utilizability, and  $\bar{\phi}_d$ , the monthly dumping utilizability<sup>7</sup>:

$$f = P X \bar{\phi}_c + (1 - P)(3.082 - 3.142 \bar{\phi}_u)[1 - \exp(-0.329X)] \quad (22.5.10a)$$

$$P = [1 - \exp(-0.294Y)]^{0.652} \quad (22.5.10b)$$

$$\bar{\phi}_u = 1 - \bar{\phi}_c + \bar{\phi}_d \quad (22.5.10c)$$

The quantity  $\bar{\phi}_u$  is the zero-capacitance system unutilizability resulting from energy loss from collectors  $(1 - \bar{\phi}_c)$  and energy loss by dumping  $\bar{\phi}_d$ .


For the month, the auxiliary energy requirement is then

$$Q_{\text{Aux}} = L(1 - f) \quad (22.5.11)$$

As with other design methods, this method is applied each month and the auxiliary energy requirements summed to obtain annual energy needs, the significant result. Comparisons of annual energy requirements obtained by this method with those obtained from detailed simulations show good agreement for a wide range of system design parameters and locations.

Systems with active storage (evaluated with the  $f$ -chart-chart method) can be compared with the same systems except for passive storage (evaluated with the utilizability techniques of this section). Figure 22.5.2 shows an example of solar fraction as a function of collector area for each type. For the systems with active storage, the storage capacity increases in proportion to collector area. For the system with passive storage, the capacity is fixed by the design of the building. For this example, the solar contribution is the same for each system up to an area of about 25 m<sup>2</sup> and an annual solar fraction of 0.3. Evans et al. (1985)

<sup>7</sup>Equation 22.5.10 reduces to Equation 22.3.1 for direct-gain systems. For direct-gain systems,  $I_{T,c} = 0$  and  $\bar{\phi}_c = 1$ . Then  $\bar{\phi}_u$  is the same as  $\bar{\phi}_d$ ,  $F_R = 1$ , and  $X$  and  $Y$  will be the same as in Equations 22.3.9 and 22.3.12.



**Figure 22.5.2** Annual solar fraction as function of collector area for systems in Madison, WI. Adapted from Evans and Klein (1984a).

show that the collector area at which the differences in performance became significant can be characterized by a ratio of active storage capacity to passive storage capacity. If it is assumed that the active storage capacity is  $A_c(mC_p)_s \times 75$ , that is, that the store can change temperature over a  $75^\circ\text{C}$  range, and if the passive capacity is the numerator in Equation 22.5.9, that is,  $C_b \Delta T_b$ , then the ratio of the two storage capacities is

$$\frac{Q_{s,a}}{Q_{s,p}} = \frac{75 A_c (mC_p)_s}{C_b \Delta T_b} \quad (22.5.12)$$

If this ratio is less than 2.5, the active storage annual performance advantage will be less than 5%. If the ratio is greater than 2.5, the advantage may or may not exceed 5%, and analyses of both types of systems should be made to evaluate relative performance.


Passive storage implies an upper limit to storage capacity and thus to solar contributions to annual loads. Addition of collector area beyond about  $100 \text{ m}^2$  to the passive storage system of Figure 22.5.2 adds little to the solar contribution. A maximum annual solar contribution  $\mathcal{F}_{\max}$  is shown; it can be estimated from the passive storage capacity  $Q_{s,p}$  and the yearly heating load  $Q_{\text{Aux}}$ :

$$\mathcal{F}_{\max} = 0.655 \left( \frac{Q_{s,p}}{Q_{\text{Aux}}} \right)^{0.36} \quad (22.5.13)$$

The resulting estimated maximum annual solar fraction is within  $\pm 6\%$  for a 90% confidence interval compared to the design method. Figure 22.5.3 shows  $\mathcal{F}_{\max}$  as a function of the annual load per square meter of floor area for light, medium, and heavy construction as defined in Table 9.5.1 for an allowable temperature swing of  $7^\circ\text{C}$ . This figure is based on a wide range of heating loads for uninsulated to heavily insulated buildings. It serves to quickly estimate the best that can be done with large collector areas, that is, the limits imposed on annual performance by storage considerations alone.

### Example 22.5.1

A building in Springfield, Illinois, is to be heated by an active collection–passive storage system. The collector is to be located on the roof facing south at a slope of  $55^\circ$ . The



**Figure 22.5.3** The  $F_{\max}$  as function of annual load per square meter of floor area and building construction for an allowable temperature swing of  $7^{\circ}\text{C}$ . From Evans and Klein (1984a).

incident radiation and  $(\overline{\tau\alpha})$  (calculated by the methods of Chapters 2 and 5 using a ground reflectance of 0.3) are shown in the table below.

The collector is an air heater with  $F_R (\tau\alpha)_n = 0.62$  and  $F_R U_L = 3.10 \text{ W/m}^2 \text{ }^{\circ}\text{C}$ . Absorptance at normal incidence is 0.93 and the collector has one cover with  $KL = 0.0125$ , resulting in  $(\tau\alpha)_n = 0.846$ . Air goes from the building interior into the collector and the heated air is returned directly via the warm air duct system to the building. Collector area is  $20 \text{ m}^2$ .

By the notation of Table 9.5.1 the structure is of medium construction and is estimated to have a thermal capacitance of  $22.9 \text{ MJ/}^{\circ}\text{C}$ . It has a floor area of  $150 \text{ m}^2$ , the overall loss coefficient-area product  $(UA)_h = 175 \text{ W/}^{\circ}\text{C}$ , and the loads are adequately represented by use of degree-days to base  $18.3^{\circ}\text{C}$  when the interior temperature is  $21^{\circ}\text{C}$ . The allowable temperature range in the building is  $21$  to  $26^{\circ}\text{C}$ .

### Solution

The calculations are done by months. For a month, the first calculation is the load. Then the critical radiation levels  $I_{T_{c,c}}$  and  $I_{T_{c,d}}$  are determined from Equations 22.5.2 and 22.5.4, and the utilizabilities  $\overline{\phi}_c$  and  $\overline{\phi}_d$  are calculated by the methods of Section 2.24. The solar-load ratio  $X$  and the storage-dump ratio  $Y$  are then determined by Equations 22.5.8 and 22.5.9. Then  $f$  is calculated by Equation 22.5.10 and  $Q_{\text{Aux}}$  by Equation 22.5.11. The procedure is illustrated in detail for January, and the results for the year are summarized in the table.

For January,

$$F_R (\overline{\tau\alpha}) = 0.62 \times \frac{0.812}{0.846} = 0.595$$

$$Q_{\text{Aux}} = 175 \times 657 \times 86,400 = 9.93 \text{ GJ}$$

From Equation 22.5.2, the collecting critical radiation level is

$$I_{T_{c,c}} = \frac{3.10[21 - (-3)]}{0.595} = 125 \text{ W/m}^2$$

From Equation 22.5.4, the dumping critical radiation level is

$$I_{Tc,d} = \frac{175[18.3 - (-3)] + 20 \times 3.10[21 - (-3)]}{20 \times 0.595} = 438 \text{ W/m}^2$$

For this month and location, from the methods of Chapter 2,  $n = 17$ ,  $\delta = -20.9^\circ$ ,  $\omega_s = 71.3^\circ$ ,  $\overline{H}_o = 15.21 \text{ MJ/m}^2$ ,  $r_{t,n} = 0.174$ ,  $r_{d,n} = 0.162$ ,  $\overline{K}_T = 0.436$ , and  $H_d/H$  (at  $K_T = 0.436$ ) is 0.70. Then  $R_{b,n} = 2.05$ ,  $R_n = 1.30$ ,  $\overline{R} = 1.764$ ,  $R_n/\overline{R} = 0.734$ ,  $a = -0.332$ ,  $b = -1.171$ , and  $c = 0.254$ . To calculate  $\overline{\phi}_c$  we first calculate  $\overline{X}_{c,c}$  from Equation 2.24.3:

$$\overline{X}_{c,c} = \frac{125 \times 3600}{0.174 \times 1.30 \times 6.63 \times 10^6} = 0.300$$

and then, from Equation 2.24.4,  $\overline{\phi}_c = 0.680$ .

To calculate  $\overline{\phi}_d$ , we need  $\overline{X}_{c,d}$ :

$$\overline{X}_{c,d} = \frac{438 \times 3600}{0.174 \times 1.30 \times 6.63 \times 10^6} = 1.051$$

and  $\overline{\phi}_d = 0.204$ .

The absorbed radiation per unit area of collector  $\overline{S}$  is 9.50 MJ. Next calculate the solar-load ratio  $X$  by Equation 22.5.8:

$$X = \frac{20 \times 0.733 \times 9.50 \times 10^6 \times 31}{9.93 \times 10^9} = 0.435$$

Calculate  $Y$ , the storage-dump ratio, by Equation 22.5.9:

$$Y = \frac{22.9 \times 10^6 \times 5}{20 \times 0.733 \times 9.50 \times 10^6 \times 0.204} = 4.030$$

We can now use Equations 22.5.10 to get  $P$ ,  $\overline{\phi}_u$ , and  $f$ :

$$P = [1 - \exp(-0.294 \times 4.030)]^{0.652} = 0.788$$

$$\overline{\phi}_u = 1 - 0.680 + 0.204 = 0.524$$

$$f = 0.788 \times 0.435 \times 0.680 + (1 - 0.788)(3.082 - 3.142 \times 0.524) \\ \times [1 - \exp(-0.329 \times 0.435)] = 0.273$$

Then

$$Q_{\text{Aux}} = 9.93(1 - 0.273) = 7.22 \text{ GJ}$$

A check of the solar fraction  $f$  for May and October shows 100% solar, and no auxiliary will be required for those and the intervening months. The annual auxiliary energy required is the sum of the monthly values and is estimated to be 27 GJ.

Month	$\bar{S}$ , MJ/m <sup>2</sup>	$(\bar{\tau}\alpha)$	$L$ , GJ	$I_{Tc,c}$ , W/m <sup>2</sup>	$I_{Tc,d}$ , W/m <sup>2</sup>	$\bar{\phi}_c$	$\bar{\phi}_d$	$f$	$Q_{Aux}$ , GJ
January	9.50	0.81	9.93	125	438	0.68	0.20	0.27	7.2
February	11.65	0.80	8.13	116	404	0.73	0.28	0.36	5.2
March	11.74	0.78	6.70	92	311	0.78	0.39	0.46	3.6
April	12.38	0.76	3.21	50	149	0.88	0.66	0.75	0.8
May	12.97	0.75	1.29	23	43	0.95	0.90	1.00	0.0
June	13.46	0.75	0.27	0	0	1.00	1.00	1.00	0.0
July	13.66	0.75	0.15	0	0	1.00	1.00	1.00	0.0
August	13.85	0.76	0.21	0	0	1.00	1.00	1.00	0.0
September	14.16	0.79	0.71	5	0	0.99	1.00	1.00	0.0
October	13.59	0.80	2.53	37	101	0.92	0.78	0.90	0.2
November	11.11	0.84	5.89	75	250	0.81	0.36	0.47	3.1
December	8.16	0.81	<u>8.95</u>	115	399	0.68	0.22	0.26	<u>6.6</u>
Total			47.93						26.7

■

## 22.6 OTHER HYBRID SYSTEMS

Buildings may have both passive and full active heating systems. The nature of these systems is such that the passive system will meet whatever part of the loads it can, and the active system, plus auxiliary, will meet the balance of the loads. The passive part of this hybrid system will function in essentially the same way as it would without the active part, and its performance can be estimated by the methods of Sections 22.2 to 22.4. The loads that the active system plus the auxiliary source must meet are as a first approximation the  $Q_{Aux}$  for the passive system.

Corrections to this load on the active plus auxiliary system can be made for two effects. First, the time distribution of the loads on the active system is different. Passive gains tend to be in the daytime and evening, so the loads seen by the active system tend to be in the night and morning, resulting in increased storage temperature and diminished performance. Second, the strategy of control of these hybrid systems will affect mean building temperature and thus loads. The set temperature for operation of the active solar system will be higher than that for the auxiliary to assure that solar is used before auxiliary is supplied. Thus the higher the solar fraction, the higher the mean building temperature and the greater the loads (Chapter 13), and thus the actual load on the active system will be higher than that estimated as  $Q_{Aux}$  by the passive method.

Evans et al. (1985) have used simulations to evaluate the extent of these two effects on the performance of the active part of this kind of hybrid system. The results of temperature elevation induced by controls are shown in terms of an increase in active system load

relative to a zero-active-collector-area load; it is a function of the active and passive contributions. The effects of time distribution of loads are shown in terms of overprediction of active system performance by the  $f$ -chart method and are a function of active and passive contributions and of active system storage capacity. Neither of these effects is large; typically they are each a few percent.

Evans and Klein (1984b) have also used simulation methods to analyze the combination of active collection—passive storage systems and direct-gain passive systems, both of which use only the capacitance of the building as storage. Both of these systems deliver energy to the building, and thus to storage, at the same time. Consequently, energy dump from the two systems also occurs at the same time, and the flow to the collector must be shut off and the direct-gain aperture blocked by curtains or shades. It is not practical to calculate the contributions of the two systems independently, as the performance of each is degraded from what it would be if the other were not there. The alternative is to assume that the active and passive collectors deliver energy to the building in essentially the same way and can be considered as a single system. Under this assumption, the unutilizability methods can be applied to this hybrid if the critical radiation levels for dumping energy from the building are properly defined.

## REFERENCES

- ASHRAE *Handbook—Fundamentals*, American Society of Heating, Refrigeration, and Air-Conditioning Engineers, Atlanta, GA (2005).
- Balcomb, J. D., D. Barley, R. D. McFarland, J. Perry, W. D. Wray, and S. Noll, *Passive Solar Design Handbook*, Vol. 2, Report No. DOE/CS-0127/2, U.S. Department of Energy, Washington, DC (1980).
- Balcomb, J. D., R. W. Jones, C. E. Kosiewicz, G. S. Lazarus, R. D. McFarland, and W. D. Wray, *Passive Solar Design Handbook*, Vol. 3, American Solar Energy Society, Boulder, CO (1983a).
- Balcomb, J. D., R. W. Jones, R. D. McFarland, and W. O. Wray, *Passive Solar J.*, **1**, 67 (1983b). “Expanding the SLR Method.”
- Balcomb, J. D., R. W. Jones, R. D. McFarland, W. O. Wray, D. Barley, C. Kosiewicz, G. Lazarus, J. Perry, and G. Schoenau, *Passive Solar Heating Analysis—A Design Manual*, ASHRAE, Atlanta, GA (1984).
- Evans, B. L. and S. A. Klein, paper presented at Las Vegas ASME Meeting (1984a). “A Design Method of Active Collection-Passive Storage Space Heating Systems.”
- Evans, B. L. and S. A. Klein, paper presented at Anaheim American Solar Energy Society Meeting (1984b). “Combined Active Collection-Passive Storage and Direct-Gain Hybrid Space Systems.”
- Evans, B. L., S. A. Klein, and J. A. Duffie, *Solar Energy*, **35**, 189 (1985). “A Design Method for Active-Passive Hybrid Space Heating Systems.”
- Lebens, R. M. and A. Myer, paper presented at United Kingdom/International Solar Energy Society Workshop on Microcomputers in Building Energy Design, Birmingham, UK (1984). “An Outline of the Methode 5000.”
- McFarland, R. D., Los Alamos National Laboratory Report LA-7433-MS (1978). “PASOLE: A General Simulation Program for Passive Solar Energy.”
- Mazria, E., *The Passive Solar Energy Book*, Rodale Press, Emmaus, PA (1979).

- Monsen, W. A., S. A. Klein, and W. A. Beckman, *Solar Energy*, **27**, 143 (1981). “Prediction of Direct Gain Solar Heating System Performance.”
- Monsen, W. A., S. A. Klein, and W. A. Beckman, *Solar Energy*, **29**, 421 (1982). “The Unutiliz-ability Design Method for Collector-Storage Walls.”
- Passive Solar Design Handbook, Vol. 1, Report No. DOE/CS-0127/1, U.S. Department of Energy, Washington, DC (1980).
- Utzinger, D. M., S. A. Klein, and J. W. Mitchell, *Solar Energy*, **25**, 511 (1980). “The Effect of Air Flow Rate in Collector-Storage Walls.”

## Design of Photovoltaic Systems

This chapter is an anomaly in that the processes it treats are not primarily thermal in nature. However, the equations that are encountered in design of many photovoltaic (PV) systems are very similar to those describing passive heating processes, and design methods based on utilizability concepts have been developed that are analogous to those in Chapter 22 for passive heating. Radiation calculations developed for thermal processes are directly applicable to PV converters. This chapter includes a brief description of PV converters (solar cells), models that describe their electrical and thermal characteristics, a short treatment of models of batteries and other components in the systems, and notes on applications. These serve as introductions to the design method and to comments on simulation of PV systems.

Photovoltaic converters are semiconductor devices that convert part of the incident solar radiation directly into electrical energy. A brief history of photovoltaics is presented by Wolf (1981). An early public demonstration of solar cells occurred in 1955 in Americus, Georgia, where a small panel of experimental silicon cells provided energy to charge a battery and power telephone equipment. Since then, tremendous progress has been made in the development of cell technology and applications. Early hand-made cells were 5% efficient, were 1 or 2 cm<sup>2</sup> in area, and had outputs of a few milliwatts. In recent years laboratory cells have been reported with efficiencies of over 30%, modules (groups of cells) are being manufactured with areas of many square meters, and the cells produced in the world in 2011 had an aggregate peak generating capacity of over 70 GW with the cumulative installed capacity of over 185 GW. Solar cells are being used in a range of applications, from powering watches and calculators to charging batteries for boats and communications systems to medium-scale systems for power generation. Photovoltaics have been the means of supplying power to most of the satellites that have been launched since the beginnings of space programs.

There is a very substantial body of literature on PVs. Maycock and Stirewalt (1981) present a layman's treatment of the subject; examples of technical books are Green (1982) on semiconductors and cells, Nelson (2003) on cell physics, Rauschenbach (1980) on cell array design, Kenna and Gillett (1985) on a particular application (water pumping), Messenger and Ventre (2004) on system design, and Fanney et al. (2002) on building integrated photovoltaics. In addition, there are proceedings of many conferences and meetings (such as the Photovoltaic Specialists Conferences that are held at approximately two-year intervals), reviews that have appeared in *Advances in Solar Energy* and elsewhere, and papers in scientific journals.



## 23.1 PHOTOVOLTAIC CONVERTERS

Incident solar radiation can be considered as discrete “energy units” called photons. From Sections 3.1 and 3.2, the product of the frequency  $\nu$  and wavelength  $\lambda$  is the speed of light:

$$C = \lambda \nu \quad (23.1.1)$$

The energy of a photon is a function of the frequency of the radiation (and thus also of the wavelength) and is given in terms of Planck’s constant  $h$  by


$$E = h\nu \quad (23.1.2)$$

Thus the most energetic photons are those of high frequency and short wavelength.

The most common PV cells are made of single-crystal silicon. An atom of silicon in the crystal lattice absorbs a photon of the incident solar radiation, and if the energy of the photon is high enough, an electron from the outer shell of the atom is freed. This process thus results in the formation of a hole–electron pair, a hole where there is a lack of an electron and an electron out in the crystal structure. These normally disappear spontaneously as electrons recombine with holes. The recombination process can be reduced by building into the cells a potential barrier, a thin layer or junction across which a static charge exists. This barrier is created by doping the silicon on one side of the barrier with very small amounts (of the order of one part in  $10^6$ ) of boron to form *p*-silicon, which has a deficiency of electrons in its outer shell, and that on the other side with phosphorus to form *n*-silicon, which has an excess of electrons in its outer shell. The barrier inhibits the free migration of electrons, leading to a buildup of electrons in the *n*-silicon layer and a deficiency of electrons in the *p*-silicon. If these layers are connected by an external circuit, electrons (i.e., a current) will flow through that circuit. Thus free electrons created by absorption of photons are in excess in the *n*-silicon and flow through the external circuit to the *p*-silicon. Electrical contacts are made by metal bases on the bottom of the cell and by metal grids or meshes on the top layer (which must be largely uncovered to allow penetration of photons). A schematic section of a cell of this type and a schematic of a cell in a circuit are shown in Figure 23.1.1.

There are many variations on cell material, design, and methods of manufacture. Amorphous or polycrystalline silicon (Si), cadmium sulfide (CdS), gallium arsenide (GaAs), and other semiconductors are used for cells.

The output of cells is limited by several factors. There is a minimum energy level (and thus a maximum wavelength) of photons that can cause the creation of a hole–electron pair. For silicon, the maximum wavelength is  $1.15 \mu\text{m}$ . Radiation at higher wavelengths does not produce hole–electron pairs but heats the cell. Each photon causes the creation of a single hole–electron pair, and the energy of photons in excess of that required to create hole–electron pairs is also converted to heat. From these considerations alone, the maximum theoretical efficiency of silicon cells is 23%. In addition, there are reflection losses at the top surface of the cells (which can be reduced by antireflective coatings). Part of the top layer of a cell must be covered by the contact grid, which reduces active cell




**Figure 23.1.1** (a) Cross section of a silicon solar cell. (b) Schematic of a cell showing top contacts.

area. There are also electrical effects such as sheet resistance (resistance to the flow of electrons across the top layer to the grid) that limit cell output.

Solar cell technology is evolving rapidly, in developing new and more efficient cells and in reducing costs of manufacture. Modules are available with many cells connected in series and parallel to provide convenient currents and voltages. Cell modules can be purchased on the market that are over 15% efficient and have design lifetimes of over 10 years. Experimental single crystalline silicon cells have been produced with efficiencies of 25% and cells with multiple junctions (i.e., two or more layers of materials with varying spectral response) have been constructed that have efficiencies of more than 30%.

## 23.2 PV GENERATOR CHARACTERISTICS AND MODELS

An assessment of the operation of solar cells and the design of power systems based on solar cells must be based on the electrical characteristics, that is, the voltage-current relationships of the cells under various levels of radiation and at various cell temperatures. Many cell models have been developed, ranging from simple idealized models to detailed models that reflect the details of the physical processes occurring in the cells. For system design purposes, the model must provide the means to calculate current, voltage, and power relationships of cell arrays over the range of operating conditions to be encountered. For this purpose detailed models do not appear to be needed, and simple models work well. Rauschenbach (1980), Townsend (1989), Eckstein (1990), and Schroder (1998) review several models and their utility for system design purposes. The model presented here for



**Figure 23.2.1** Typical  $I$ - $V$  and  $P$ - $V$  curves for a PV module.


the current-voltage characteristic of PV converters and its dependence on solar radiation and cell temperature relies only on information available from the manufacturer. Other models, for example, the Sandia model (King et al., 2004), are available that require additional information generally not provided by the manufacturer.

Current-voltage ( $I$ - $V$ ) characteristics of a typical PV module are shown in Figure 23.2.1. The current axis (where  $V = 0$ ) is the short-circuit current  $I_{sc}$ , and the intersection with the voltage axis (where  $I = 0$ ) is the open-circuit voltage  $V_{oc}$ . For this module the current decreases slowly to about 15 V and then decreases rapidly to the open-circuit conditions at about 21.4 V. For comparison, a single 1-cm<sup>2</sup> silicon cell at a solar radiation level of 1000 W/m<sup>2</sup> has an open-circuit voltage of about 0.6 V and a short-circuit current of about 20 to 30 mA.

The power as a function of voltage is also shown in Figure 23.2.1. The maximum power that can be obtained corresponds to the rectangle of maximum area under the  $I$ - $V$  curve. At the maximum power point the power is  $P_{mp}$ , the current is  $I_{mp}$ , and the voltage is  $V_{mp}$ . Ideally, cells would always operate at the maximum power point, but practically cells operate at a point on the  $I$ - $V$  curve that matches the  $I$ - $V$  characteristic of the load. This will be discussed further in Section 23.4.

Current-voltage curves are shown in Figure 23.2.2 for a module operating at a fixed temperature and at several radiation levels. The locus of maximum power points is also shown. For this module, the short-circuit current increases in proportion to the solar radiation while the open-circuit voltage increases logarithmically with solar radiation. As long as the curved portion of the  $I$ - $V$  characteristic does not intersect the current axis (where  $V = 0$ ), the short-circuit current is nearly proportional to the incident radiation.<sup>1</sup>

<sup>1</sup>Thus if the incident radiation is assumed to have a fixed spectral distribution, the short-circuit current can be used as a measure of incident radiation. It is also possible to impose a bias voltage across the cell, in effect move the voltage axis to the left, and extend the range of radiation fluxes that can be measured. [See Schöffer et al. (1964).]



**Figure 23.2.2** The  $I$ - $V$  curves for a PV generator at several radiation levels. The locus of maximum power points is shown.

Cells are mounted in modules, and multiple modules are used in arrays. Individual modules may have cells connected in series and parallel combinations to obtain the desired current and voltage. Arrays of modules may likewise be arranged in series and parallel. For modules or cells connected in series, the voltages are additive, and when connected in parallel, the currents are additive. If the cells or modules are identical, then connecting, say, five in series will increase all voltages by a factor of 5 and connecting five in parallel will increase the current by a factor of 5. If the cells or modules are not identical, a detailed analysis is required. Figure 23.2.3 shows  $I$ - $V$  characteristics of one, two, and four identical modules connected in various ways.


Figure 23.2.4 is an equivalent circuit that can be used for an individual cell, a module consisting of several cells, or an array consisting of several modules. At a fixed temperature and solar radiation, the  $I$ - $V$  characteristic of this model is given by

$$I = I_L - I_D - I_{sh} = I_L - I_o \left[ \exp \left( \frac{V + IR_s}{a} \right) - 1 \right] - \frac{V + IR_s}{R_{sh}} \quad (23.2.1)$$


and the power is given by

$$P = IV \quad (23.2.2)$$

This circuit requires that five parameters be known: the light current  $I_L$ , the diode reverse saturation current  $I_o$ , the series resistance  $R_s$ , the shunt resistance  $R_{sh}$ , and a parameter  $a$ . All five parameters may be functions of cell temperature and absorbed solar radiation as discussed later in this section. The parameter  $a$ , here called the modified ideality factor, is related to physical constants and a parameter  $n$  by  $a \equiv nkTN_s/q$ , where the only unknown is the ideality factor  $n$  (equal to 1 for an ideal diode and typically



**Figure 23.2.3** The  $I$ - $V$  curves for PV generators connected in various series and parallel arrangements.



**Figure 23.2.4** Equivalent circuit for a PV generator.

between 1 and 2 for real diodes),  $k$  is Boltzmann's constant ( $1.381 \times 10^{-23}$  J/K),  $T$  is the cell temperature,  $N_s$  is the number of cells in series, and  $q$  is the electronic charge [ $1.602 \times 10^{-19}$  coulomb (1 C = 1 A s)]. Schroder (1998) reviews a number of alternatives for finding the parameters.

The five parameters in the model are obtained using measurements of the current and voltage characteristics of a module at reference conditions supplied by the manufacturer and other known PV characteristics. Measurements of PV electrical characteristics traditionally are made at a standard reference condition: incident radiation of  $1000 \text{ W/m}^2$ , a cell temperature of  $25^\circ\text{C}$ , and a spectral distribution corresponding to an air mass of 1.5. Measurements of  $I$ - $V$  pairs at reference conditions are usually available from the manufacturer at open-circuit conditions, short-circuit conditions, and maximum-power conditions. In addition, manufacturers usually supply both the temperature coefficient of short-circuit current,  $\mu_{I,sc}$ , and the temperature coefficient of open-circuit voltage,  $\mu_{V,oc}$ . The remainder of this section discusses a method for finding the five parameters at reference conditions and how the parameters vary with operating conditions.

Since five parameters are to be determined, five different conditions need to be known. The method adopted here is to use the three known  $I$ - $V$  points, the condition at the maximum power point where the derivative of power with respect to voltage is zero, and the temperature coefficient of open-circuit voltage.

At short-circuit conditions the voltage is zero and the current is  $I_{sc,ref}$  :

$$I_{sc,ref} = I_{L,ref} - I_{o,ref} \left[ \exp \left( \frac{I_{sc,ref} R_{s,ref}}{a_{ref}} \right) - 1 \right] - \frac{I_{sc,ref} R_{s,ref}}{R_{sh,ref}} \quad (23.2.3)$$

At open-circuit conditions the current is zero and the voltage is  $V_{oc}$  so that

$$I_{L,ref} = I_{o,ref} \left[ \exp \left( \frac{V_{oc,ref}}{a_{ref}} \right) - 1 \right] + \frac{V_{oc,ref}}{R_{sh,ref}} \quad (23.2.4)$$

The measured  $I$ - $V$  pair at maximum-power conditions can be substituted into Equation 23.2.1, resulting in

$$I_{mp,ref} = I_{L,ref} - I_{o,ref} \left[ \exp \left( \frac{V_{mp,ref} + I_{mp,ref} R_{s,ref}}{a_{ref}} \right) - 1 \right] - \frac{V_{mp,ref} + I_{mp,ref} R_{s,ref}}{R_{sh,ref}} \quad (23.2.5)$$

The fourth condition, where the derivative of power with respect to voltage is equal to zero, results in

$$\frac{I_{mp,ref}}{V_{mp,ref}} = \frac{\frac{I_{o,ref}}{a_{ref}} \exp \left( \frac{V_{mp,ref} + I_{mp,ref} R_{s,ref}}{a_{ref}} \right) + \frac{1}{R_{sh,ref}}}{1 + \frac{I_{o,ref} R_{s,ref}}{a_{ref}} \exp \left( \frac{V_{mp,ref} + I_{mp,ref} R_{s,ref}}{a_{ref}} \right) + \frac{R_{s,ref}}{R_{sh,ref}}} \quad (23.2.6)$$


The final condition ensures that the known temperature coefficient of open-circuit voltage is correctly predicted by the model, resulting in

$$\frac{\partial V_{oc}}{\partial T} = \mu_{V,oc} \approx \frac{V_{oc}(T_c) - V_{oc}(T_{c,ref})}{T_c - T_{c,ref}} \quad (23.2.7)$$

The value chosen for the cell temperature  $T_c$  does not matter much as choosing  $T_c$  from 1 to 10 degrees above or below  $T_{ref}$  does not significantly change the result. The open-circuit voltage at temperature  $T_c$  is found from Equation 23.2.1 with  $I = 0$ . But, since  $V_{oc}$  cannot be explicitly solved for in this equation, numerical methods must be used. In addition, it is necessary to obtain general relationships as to how the parameters  $a$ ,  $I_L$ , and  $I_o$  vary with operating conditions.

Figure 23.2.5 shows the effect of temperature on a module  $I$ - $V$  characteristic; at a fixed radiation level, increasing temperature leads to decreased open-circuit voltage and slightly increased short-circuit current. From semiconductor theory (i.e., the definition of  $a$ ), assuming the ideality factor  $n$  does not depend on temperature, we have

$$\frac{a}{a_{ref}} = \frac{T_c}{T_{c,ref}} \quad (23.2.8)$$



**Figure 23.2.5** The  $I$ - $V$  characteristics of a PV module at temperatures of 0 and 75°C.

The light current ( $I_L$ ) is nearly a linear function of incident solar radiation. Some pyranometers in fact use the short-circuit current of a solar cell as a measure of the incident solar radiation. The light current is observed to depend on the effective absorbed solar radiation ( $S$  as given in Section 5.12), the cell temperature ( $T_c$ ), and the short-circuit current temperature coefficient ( $\mu_{I,sc}$ ). The light current  $I_L$  for any operating conditions is related to the light current at reference conditions by

$$I_L = \frac{S}{S_{\text{ref}}} [I_{L,\text{ref}} + \mu_{I,sc} (T_c - T_{c,\text{ref}})] \quad (23.2.9)$$

where  $S/S_{\text{ref}}$  is the effective absorbed solar ratio estimated according to methods in Section 5.12. When using Equation 23.2.9 to find the reference parameters,  $S = S_{\text{ref}}$ .

Messenger and Ventre (2004) present an equation from diode theory for the diode reverse saturation current,  $I_o$ . The ratio of their equation at the new operating temperature to that at the reference temperature yields

$$\frac{I_o}{I_{o,\text{ref}}} = \left( \frac{T_c}{T_{c,\text{ref}}} \right)^3 \exp \left( \frac{E_g}{kT} \Big|_{T_{c,\text{ref}}} - \frac{E_g}{kT} \Big|_{T_c} \right) \quad (23.2.10a)$$

$$\frac{E_g}{E_{g,\text{ref}}} = 1 - C(T - T_{c,\text{ref}}) \quad (23.2.10b)$$

where  $E_g$  is the material bandgap energy [ $E_{g,\text{ref}} = 1.12 \text{ eV}$  ( $1.794 \times 10^{-19} \text{ J}$ ) and  $C = 0.0002677$  for silicon and  $E_{g,\text{ref}} = 1.35 \text{ eV}$  ( $2.163 \times 10^{-19} \text{ J}$ ) and  $C = 0.0003174$  for

gallium arsenide] and  $k$  is Boltzmann's constant ( $1.381 \times 10^{-23}$  J/K). All of the quantities with the subscript ref are from measurements at reference conditions.

The shunt resistance  $R_{sh}$  is found to be essentially independent of temperature but varies with absorbed radiation. As shown by Rauschenbach (1980), the slope of the  $I$ - $V$  curve at open-circuit conditions is approximately equal to the negative inverse of the shunt resistance. That is,  $dI/dV$  at  $V = 0$  is approximately equal to  $-1/R_{sh}$ . At typical nonconcentrating radiation levels many modern cells have a very small negative slope at open-circuit conditions indicating a large shunt resistance. For cells with a significant slope at nonconcentrating radiation levels the slope is found to decrease (and thus the shunt resistance increase) as the radiation level decreases (DeSoto et. al, 2006). The following relationship is used to relate the shunt resistance at reference conditions to that at operating conditions:

$$\frac{R_{sh}}{R_{sh,ref}} = \frac{S_{ref}}{S} \quad (23.2.11)$$

The series resistance is assumed to be independent of both temperature and solar radiation so that

$$R_s = R_{s,ref} \quad (23.2.12)$$

The model is now complete. Equations 23.2.3 through 23.2.7 must be solved simultaneously in order to determine the five parameters at reference conditions. Due to the highly nonlinear nature of these equations they are not easily solved unless good initial guesses and variable limits are used. For modern cells the shunt resistance should be high so a guess for  $R_{sh,ref}$  of  $100 \Omega$  is reasonable. A good initial guess for  $a_{ref}$  is  $1.5kT_{ref}N_s/q$ . At short-circuit conditions the second and third terms in Equation 23.2.3 are small, leading to  $I_{sc,ref}$  as a good initial guess for  $I_{L,ref}$ . Neglecting the last term in Equation 23.2.5 and the  $-1$ , a good guess for  $I_{o,ref}$  is  $I_{sc,ref} \exp(-V_{oc,ref}/a_{ref,guess})$ . Finally, a good guess for  $R_{s,ref}$  is found by substituting the above guess values into Equation 23.2.1 at maximum power but with  $R_{sh}$  assumed to be very large (the last term is then negligible) so the equation can be solved for  $R_{s,ref,guess}$ . Once values are found for the parameters at the reference condition Equations 23.2.8 through 23.2.12 are used to find the parameters at any operating condition.

Sometimes it is desirable to find the maximum power point for the model. Differentiating Equation 23.2.2 with respect to  $V$  and setting the result equal to zero results in

$$\frac{I_{mp}}{V_{mp}} = \left[ \frac{\frac{I_o}{a} \exp\left(\frac{V_{mp} + I_{mp}R_s}{a}\right) + \frac{1}{R_{sh}}}{1 + \frac{R_s}{R_{sh}} + \frac{I_o R_s}{a} \exp\left(\frac{V_{mp} + I_{mp}R_s}{a}\right)} \right] \quad (23.2.13)$$

The general  $I$ - $V$  equation at the maximum power point must also be satisfied:

$$I_{mp} = I_L - I_o \left[ \exp\left(\frac{V_{mp} + I_{mp}R_s}{a}\right) - 1 \right] - \left[ \frac{V_{mp} + I_{mp}R_s}{R_{sh}} \right] \quad (23.2.14)$$

The simultaneous solution of these two equations yields the maximum power point current and voltage.



**Example 23.2.1**

A typical PV module with 36 cells in series and an area of  $0.633 \text{ m}^2$  has the following measured characteristics at reference conditions:  $I_{sc} = 4.5 \text{ A}$ ,  $V_{oc} = 21.4 \text{ V}$ ,  $I_{mp} = 3.95 \text{ A}$  and  $V_{mp} = 16.5 \text{ V}$ . The temperature coefficient of the short-circuit current  $\mu_{I,sc}$  and the open-circuit voltage  $\mu_{V,oc}$  are  $0.00026 \text{ A/K}$  and  $-0.085 \text{ V/K}$ , respectively. Determine the values of  $I_o$ ,  $I_L$ ,  $R_s$ ,  $R_{sh}$ , and  $a$  at reference conditions. Estimate the maximum power efficiency at a cell temperature of  $67.2^\circ\text{C}$  and an incident radiation of  $648.3 \text{ W/m}^2$  on June 1 at latitude  $39.2^\circ$  (from Example 5.12.1).

**Solution**

Finding guess values for the reference parameters following the recommendations in the paragraph after Equation 23.2.12 results in

$$\begin{aligned}
 R_{sh,guess} &= 100 \, \Omega \\
 a_{ref,guess} &= \frac{1.5 \times 1.381 \times 10^{-23} \times 298.2 \times 36}{1.602 \times 10^{-19}} = 1.387 \\
 I_{L,ref,guess} &= 4.5 \text{ A} \\
 I_{o,ref,guess} &= 4.5e^{-21.4/1.387} = 8.96 \times 10^{-7} \\
 R_{s,ref,guess} &= \frac{1.387 \ln [(4.5 - 3.65)/8.96 \times 10^{-7}] - 16.5}{3.95} = 0.503
 \end{aligned}$$

With these guess values Equations 23.2.3 through 23.2.7 must be simultaneously solved for the five parameters at reference conditions. In Equation 23.2.7 the open-circuit voltage at  $T_c - T_{ref} = 10 \text{ K}$  is found from Equation 23.2.1 with  $I = 0$  and with values of  $a$  and  $I_o$  from Equations 23.2.8 and 23.2.10, respectively.<sup>2</sup> The results are

$$\begin{aligned}
 R_{sh,ref} &= 52.4 \, \Omega \\
 a_{ref} &= 0.9352 \text{ V} \\
 I_{L,ref} &= 4.549 \text{ A} \\
 I_{o,ref} &= 4.782 \times 10^{-10} \text{ A} \\
 R_{s,ref} &= 0.567 \, \Omega \\
 a &= 0.9666 \text{ V at } 308.2 \text{ K} \\
 I_o &= 2.432 \times 10^{-9} \text{ A at } 308.2 \text{ K}
 \end{aligned}$$

The maximum power point current and voltage can be obtained by solving Equations 23.2.13 and 23.2.14. The equations must be solved numerically. It is just as easy to

<sup>2</sup>There are really seven equations and seven unknowns, the five parameters at reference conditions and  $a$  and  $I_o$  at a cell temperature of 10 K above the reference temperature.

numerically solve for the maximum power by varying  $V$  until the maximum power is found (in some software this is done automatically by maximizing the power with respect to the voltage). The result of using either method is  $I_{mp,ref} = 3.95$  A,  $V_{mp,ref} = 16.5$  V, and  $P_{mp,ref} = 65.2$  W. With an incident solar radiation of  $1000$  W/m<sup>2</sup> the cell efficiency is  $65.2/(0.633 \times 1000) = 0.103$  or 10.3%.

Equations 23.2.8 through 23.2.11 are used at a cell temperature of  $67.2^\circ\text{C}$  and an effective absorbed radiation ratio  $S/S_{ref} = 0.622$  (from Example 5.12.1) to determine  $a$ ,  $I_L$ , and  $I_o$  at operating conditions. From Equation 23.2.8

$$a = 0.9352 \frac{273.15 + 67.2}{273.15 + 25} = 1.068 \text{ V}$$

From Equation 23.2.9

$$I_L = 0.684[4.549 + 0.00026(67.2 - 25)] = 3.119 \text{ A}$$

From Equation 23.2.10

$$\begin{aligned} E_g &= 1.12[1 - 0.0002677(67.2 - 25)] = 1.11 \\ I_o &= 4.782 \times 10^{-10} \left( \frac{340.35}{298.15} \right)^3 \exp \left[ \frac{1.602 \times 10^{-22}}{1.381 \times 10^{-26}} \left( \frac{1.120}{298.15} - \frac{1.107}{340.15} \right) \right] \\ &= 2.436 \times 10^{-7} \text{ A} \end{aligned}$$

The two resistances in this model are assumed to be independent of temperature so  $R_{s,ref} = R_s$ . However,  $R_{sh}$  is a function of absorbed radiation. From Equation 23.2.11

$$R_{sh} = \frac{52.4}{0.684} = 76.7 \text{ } \Omega$$

The maximum power point current and voltage at the operating conditions (incident radiation  $648.3$  W/m<sup>2</sup> and a cell temperature of  $67.2^\circ\text{C}$ ) are obtained by solving Equations 23.2.13 and 23.2.14. The result is  $I_{mp} = 2.69$  A,  $V_{mp} = 13.2$  V, and  $P_{mp} = 35.5$  W. The cell efficiency is then  $35.5/(0.633 \times 648.3) = 0.086$ , or 8.6%. ■

The temperature dependence of the maximum power point efficiency of a module is an important parameter in estimating system performance as presented in Section 23.4. The maximum power point efficiency of a module is given by


$$\eta_{mp} = \frac{I_{mp} V_{mp}}{A_c G_T} \quad (23.2.15)$$

The temperature dependence of this efficiency can be expressed in terms of a maximum power point efficiency temperature coefficient  $\mu_{\eta,mp}$  as<sup>3</sup>

$$\eta_{mp} = \eta_{mp,ref} + \mu_{\eta,mp} (T_c - T_{c,ref}) \quad (23.2.16)$$

---

<sup>3</sup>Generally  $\mu_{\eta,mp}$  is a negative number.



**Figure 23.2.6** Maximum power as function of module temperature for three radiation levels.

A value of  $\mu_{\eta,mp}$  can be obtained by solving the cell model for the maximum power efficiency over a range of temperatures. Figure 23.2.6 shows the results of these calculations for the module used in the examples of this section. The maximum power point efficiency is seen to be a linear function of temperature, and for this and many modules it is also a function of solar radiation.

Fortunately, it is not necessary to repeat the calculations that generated Figure 23.2.6 to estimate  $\mu_{\eta,mp}$ . From Equation 23.2.12,

$$\mu_{\eta,mp} = \frac{d\eta_{mp}}{dT} = \left( I_{mp} \frac{dV_{mp}}{dT} + V_{mp} \frac{dI_{mp}}{dT} \right) \frac{1}{A_c G_T} \quad (23.2.17)$$

For many modules,  $\mu_{I,sc}$  is small, which indirectly results in a value of  $dI_{mp}/dT$  of approximately zero and  $dV_{mp}/dT$  to be approximately equal to  $dV_{oc}/dT$ . With these approximations, the temperature coefficient of maximum power efficiency is approximated by

$$\mu_{\eta,mp} \approx \frac{I_{mp}}{A_c G_T} \frac{dV_{oc}}{dT} = \eta_{mp,ref} \frac{\mu_{Voc}}{V_{mp}} \quad (23.2.18)$$

### Example 23.2.2

For the module and reference conditions of Example 23.2.1, estimate  $\mu_{\eta,mp}$  from Equation 23.2.18 and compare it with the results obtained from Figure 23.2.6. Estimate the module maximum power at  $67.2^\circ\text{C}$  and an incident radiation of  $648.3 \text{ W/m}^2$ ?

**Solution**

At the reference conditions the maximum power voltage is 16.5 V with an efficiency of 10.3% (Example 23.2.1). Thus, from Equation 23.2.18,

$$\mu_{\eta,mp} = -\frac{0.103 \times 0.085}{16.5} = -0.00053 \text{ K}^{-1}$$

From Figure 23.2.6 the correct value is

$$\mu_{\eta,mp} = \frac{\eta_{T2} - \eta_{T1}}{T_2 - T_1} = \frac{P_{T2} - P_{T1}}{A_c G_T (T_2 - T_1)} = \frac{54.5 - 73.1}{0.633 \times 1000 \times 50} = -0.00059 \text{ K}^{-1}$$

which is about 10% higher than the estimate.

The maximum power point efficiency at operating condition 67.2°C is found from Equation 23.2.16 using the efficiency of 0.103 from Example 23.2.1:

$$\eta_{mp} = 0.103 - 0.00053(67.2 - 25) = 0.081$$

which predicts the maximum power to be

$$P_{mp} = 0.081 \times 0.633 \times 648.3 = 33 \text{ W}$$

The maximum power at operating conditions from Example 23.2.1 is 34 W. ■

## 23.3 CELL TEMPERATURE

The temperature of operation of a PV module is determined by an energy balance. The solar energy that is absorbed by a module is converted partly into thermal energy and partly into electrical energy which is removed from the cell through the external circuit. The thermal energy must be dissipated by a combination of heat transfer mechanisms; the upward losses occur by the same mechanisms as losses from the covers of flat-plate collectors, as detailed in Section 6.4. Back losses will usually be more important than in thermal collectors, since heat transfer from the module should be maximized so the cells will operate at the lowest possible temperature.

In some array designs, cells are operated at elevated radiation levels by use of linear or circular concentrators. Cell temperature control may be enhanced by water cooling; in these cases, the loss coefficient must be modified to account for the additional mechanism for heat transfer, and the sink temperature to which this heat transfer occurs may not be the ambient temperature.

Cell arrays have been designed and built to produce combinations of electrical and thermal energy. The University of Delaware Solar One, a residential-scale experimental building, was equipped with PV cells that were air cooled; the cooling air was used for space heating in the building. A system based on a similar concept is installed on a house in Providence, Rhode Island (Loferski et al., 1988). For best operation of the cells, they

should be at the minimum possible temperature which limits the possible applications of combined systems to situations where thermal energy is needed at low temperatures.

An energy balance on a unit area of module which is cooled by losses to the surroundings can be written as<sup>4</sup>

$$(\tau\alpha)G_T = \eta_c G_T + U_L (T_c - T_a) \quad (23.3.1)$$

where  $(\tau\alpha)$  is the effective transmittance-absorptance product that when multiplied by the incident radiation yields the energy that is absorbed and  $\eta_c$  is the efficiency of the module in converting incident radiation into electrical energy. This efficiency will vary from zero to the maximum module efficiency depending on how close to the maximum power point the module is operating. The loss coefficient  $U_L$  will include losses by convection and radiation from top and bottom and by conduction through any mounting framework that may be present, all to the ambient temperature  $T_a$ .

The nominal operating cell temperature (NOCT) is defined as the cell or module temperature that is reached when the cells are mounted in their normal way at a solar radiation level of  $800 \text{ W/m}^2$ , a wind speed of  $1 \text{ m/s}$ , an ambient temperature of  $20^\circ\text{C}$ , and no-load operation (i.e., with  $\eta_c = 0$ ). The mounting has a strong impact on the NOCT so care must be exercised in using the NOCT if the cells are not mounted in the same manner as they are tested. Measurements of the cell temperature, ambient temperature, and solar radiation can be used in Equation 23.3.1 at NOCT conditions:

$$(\tau\alpha)G_{T,NOCT} = U_{L,NOCT} (T_{NOCT} - T_{a,NOCT}) \quad (23.3.2)$$

The cell temperature at any ambient temperature is then found from

$$\frac{T_c - T_a}{T_{NOCT} - T_{a,NOCT}} = \frac{G_T}{G_{NOCT}} \frac{U_{L,NOCT}}{U_L} \left[ 1 - \frac{\eta_c}{(\tau\alpha)} \right] \quad (23.3.3)$$

The  $(\tau\alpha)$  in the last term of Equation 23.3.3 is not generally known, but an estimate of 0.9 can be used without serious error since the term  $\eta_c/(\tau\alpha)$  is small compared to unity. It is clear that Equation 23.3.3 does not account for the variation in cell temperature with wind speed unless the ratio of the two loss coefficients is known. One approximation is to replace the ratio by the ratio of Equation 3.15.2 at NOCT and actual operating conditions:

$$\frac{T_c - T_a}{T_{NOCT} - T_{a,NOCT}} = \frac{G_T}{G_{NOCT}} \frac{9.5}{(5.7 + 3.8V)} \left[ 1 - \frac{\eta_c}{(\tau\alpha)} \right] \quad (23.3.4)$$

where  $V$  is the local wind speed in meters per second. In design practice the local wind speed is seldom known with any certainty. If the actual mounting is not the same as used in the NOCT test, then estimates given by Equation 23.3.3 or 23.3.4 will not be correct.

Other approaches to determining the operating cell temperature have been proposed by Sandia (King et al., 2004) and NIST (Davis et al., 2001). In both cases additional

---

<sup>4</sup>These energy balances can also be written for an hour in terms of  $I_T$ .

information beyond that supplied by the manufacturer is needed. However, the necessary information for many PV modules using the Sandia method is provided on its website.

### Example 23.3.1

For the module of Examples 23.2.1 and 23.2.2, determine the module temperature in a desert location where the ambient temperature is  $48.8^{\circ}\text{C}$ , the wind speed is  $1\text{ m/s}$ , and the incident solar radiation is  $648.3\text{ W/m}^2$ . The module is operating at its maximum power point. At NOCT conditions, the module temperature is  $45.0^{\circ}\text{C}$ .

### Solution

This is a trial-and-error solution. First guess the module efficiency and find the cell temperature from Equation 23.3.3. With this cell temperature and with values of  $I_{o,\text{ref}}$ ,  $L_L$ ,  $L_{L,\text{ref}}$ , and  $a_{\text{ref}}$  from Example 23.2.1, use Equations 23.2.8 through 23.2.12 to find values for  $I_L$ ,  $L_o$ ,  $R_{\text{sh}}$ , and  $R_s$  at this temperature. Use Equations 23.2.13 and 23.2.14 to find the maximum power current and voltage. Find the maximum power from Equation 23.2.2. Evaluate the module efficiency and compare with the initial guess. Since the module efficiency is not a strong function of temperature, the process will converge rapidly. Only the final iteration will be shown.

From NOCT conditions, Equation 23.3.4 is used to find the cell temperature:


$$T_c = 48.8 + (45 - 20) \frac{648.3}{800} \left( 1 - \frac{0.083}{0.9} \right) = 67.2^{\circ}\text{C}$$

From this point on the process is exactly as described in Example 23.2.1, leading to the maximum power point efficiency of 8.6% ■


## 23.4 LOAD CHARACTERISTICS AND DIRECT-COUPLED SYSTEMS

A PV cell will operate at the voltage and current at which its characteristics match that of the load to which it is connected. Examples of load characteristics are a resistive load, a battery, a series motor, and the power grid. The examples in this section are of direct-connected systems. In the following section, note is made of power conditioning equipment (maximum power point trackers) that can be used where there is serious mismatch between generator and load characteristics.

Figure 23.4.1 shows the characteristics of three resistive loads and three  $I$ - $V$  curves for a solar cell module of  $65\text{ W}$  rated capacity. The  $I$ - $V$  curves are typical of those for three times of day for modules with fixed orientation. The three resistive loads shown each intersect the module  $I$ - $V$  curves at the maximum power points. At any time, the combination of the module and the load will operate at the intersection of the characteristic curves of the two components. The optimum load resistance, that is, the slope of the resistive load curve, will vary throughout a day. A fixed resistive load is thus not an optimum load for a PV generator. Khouzam et al. (1991) studied the problem of determining the optimum fixed resistance for clear days. An electronic load that effectively changes the load resistance with solar radiation to follow the maximum power point is called a *maximum power point tracker*, or MPPT (see Section 23.5).




**Figure 23.4.1** Photovoltaic generator characteristics at three incident radiation levels and resistive load lines corresponding to the maximum power points for each radiation level.



**Figure 23.4.2** Charging and discharging characteristics of a lead-acid storage battery.

The charging and discharging characteristics of a single cell of a typical 250-Ah lead-acid storage battery are shown in Figure 23.4.2 (see Section 8.10). The internal resistance of a battery depends on the rate of charging, and the battery characteristic thus has a finite slope. Also, the voltage required to charge a battery (and the voltage produced by a battery on discharge) is a function of the state of charge  $F$  so that as the state of charge nears 100%



**Figure 23.4.3** Current-voltage characteristics for a PV array at three radiation levels and a storage battery.


the voltage rises rapidly with charging current. As shown in Figure 23.4.3 battery-charging characteristics can more nearly match the locus of maximum power points than that of a resistive load. In this figure the cell temperature is 25°C. As the cell temperature increases, the curve of the PV maximum power points will shift to the left, providing an even better match (see Figure 23.2.5).

Photovoltaic generators may be used to drive machines such as electric pumps, refrigerators, and other devices. Direct-current motors are of several types, each having different characteristics. The speed at which motors run is a function of voltage and torque, which in turn depend on the characteristics of the load on the motor. Thus an analysis of the operation of PV generators supplying energy to motors must be a simultaneous solution of the characteristics of all of the components. Townsend (1989) and Eckstein (1990) have compared series, shunt, and permanent-magnet DC motors, including as loads ventilating fans, centrifugal pumps, and positive-displacement pumps. Figure 23.4.4 shows the characteristic of two different DC motors (connected to a water-pumping system) and PV generator characteristics at three radiation levels. The system with the separately excited motor begins delivering water at a lower incident radiation than the system with the series motor. Both systems operate far from the maximum power point at both low and high radiation levels. Thus this load is not well matched to PV cell characteristics, direct connection is not an efficient arrangement, and power-conditioning equipment would probably be justified.<sup>5</sup>


Electrical loads that are combinations of components may be used. A battery may be wired so as to charge when there is current from the PV generator that exceeds load current and discharge when the generator does not produce enough. A common circuit

<sup>5</sup>See Section 23.5.






**Figure 23.4.4** Characteristics of an array of cell modules at five radiation levels coupled to a water pumping system using two different DC motors. Adapted from Townsend (1989).



**Figure 23.4.5** Photovoltaic array with battery and load in parallel.

to accomplish this is shown in Figure 23.4.5. In such a parallel circuit the voltage across the PV panel, the battery, and the load is the same. At operating conditions the PV array current is the sum of the load current and the battery current as shown in Figure 23.4.6. The operating voltage in this situation is found by moving the operating voltage line shown in the figure until  $I_{\text{array}} = I_{\text{battery}} + I_{\text{load}}$ .



**Figure 23.4.6** Characteristics of PV array, motor, and battery showing the operating voltage when connected in parallel.

The effective use of PV generators in many applications will depend on system arrangements more complex than those of the direct-coupled arrangements inferred here. Devices for controlling voltage (with some sacrifice of power) can be used for tracking maximum power points. Some of these control devices and strategies are noted in the following section.

## 23.5 CONTROLS AND MAXIMUM POWER POINT TRACKERS

Solar cells are expensive, and in most installations controls are used to maximize the output of arrays and protect electrical components from damage. Kirpich et al. (1980) and Messenger and Ventre (2004) provide a general discussion of some of these problems. Two examples of control mechanisms are described here to illustrate the kinds of considerations that may be important.

Systems that consist of PV generators, storage batteries, and loads need controls to protect the battery from overcharge or deep discharge. Overcharge will damage the storage batteries used in these systems, and high-voltage cutoff or power-shunting devices are used to interrupt the current to batteries after full charge has been achieved. The voltage across a battery is a function of the state of charge of the battery. Excessive discharge will also damage the batteries, and low-voltage cutoff devices are used to detect low voltages and disconnect the batteries. This results in an interruption of power to the loads and necessitates the use of either very large batteries or an additional source of electric energy if very high degrees of reliability are required. Stand-alone systems requiring very high degrees of reliability have been studied by Klein and Beckman (1987) and Gordon (1987).

Cell output can be maximized by operating near or at the maximum power point. It is clear from the descriptions of load characteristics in the previous section that except in special cases this cannot be achieved without decoupling of the cells and the load (and batteries). Maximum power trackers are devices that keep the impedance of the circuit of the cells at levels corresponding to best operation and also convert the resulting power from the PV array so that its voltage is that required by the load. There is some power loss associated with the tracking process but efficiencies greater than 90% are possible.

If AC power is needed, DC/AC inverters will be required. This may be the case if AC machinery is to be operated or if the PV system is to be tied into a utility grid. Inverters are available that will generate frequencies to match utility frequencies. Grid-connected systems may have batteries and be controlled so as to maximize the contribution of the PV system to meeting the load and thus minimize the energy purchased. Or, they may “float” on the grid without batteries, with the system adding to or drawing from the grid depending on the loads and available radiation. For practical purposes, this type of system functions as one with infinite storage capacity if the capacity of the grid is large compared to the capacity of the PV system. Grid-connected systems are sometimes connected in such a manner that the power meter runs backward whenever excess power is produced by the PV system and, of course, forward when power is needed from the grid. In effect the electric utility is paying the PV system owner full retail price for the generated power. Laws vary and local regulations should be consulted when designing PV systems.

## 23.6 APPLICATIONS

There are many millions of installed PV systems. A handbook on stand-alone PV systems produced by Sandia (1988) notes that applications as of 1987 included 3100 refrigerators and freezers; 17,500 remote monitoring and data communications stations; 1100 communications systems; 17,000 systems for residences, boats, recreational vehicles, and so on; and 21,000 water-pumping installations. In recent years these applications have expanded to uncountable numbers. In addition there are innumerable very small scale applications for calculators, watches, toys, and so on. In this section, brief descriptions are provided of four applications to illustrate the range of energy problems that can be approached with PV generators

A 1320-W generator provides energy to drive an AC submersible pump to provide a community water supply at Bendals, Antigua (West Indies). The cell array consists of twenty-eight 12-V modules with four parallel subarrays each with seven modules in series. The array is mounted at a fixed slope of  $17^\circ$  on a tracking mount. Batteries are not used, and pumped water is stored. A 1500-W three-phase inverter is used. The multistage pump is driven by a 105-V induction motor, with the pump-motor assembly in a 15-cm borehole. The head on the pump is 50 m, and an average of 19,000 liters of water per day is needed to supply the community with water.

In the high, dry environment of central Oregon, a VHF radio repeater station is powered by a 350-W system which includes battery storage. The array is ground mounted at a slope of  $59^\circ$  and consists of eleven 12-V modules in three subarrays, two of 180 W and one of 135 W nominal capacity. Each subarray has its own controller to avoid overcharge or excessive discharge of the batteries. The batteries used have a capacity of 1800 Ah, and the loads on the system are 58 Ah/day. Thus the system has a nominal storage capacity of energy to meet the loads for 30 days. Restrictions on charging and deep discharging put the actual capacity at 14 days; a very high degree of reliability is needed in this application.

A 50-kWp (peak) system provides electrical energy to a dairy farm on Fota Island, Cork, Ireland (McCarthy and Wrixon, 1986). The loads on the system vary seasonally, from peak loads of 115 kWh/day in summer to minimum loads of 5 kWh/day in winter. In the Irish climate, the generator output exceeds 200 kWh/day in summer but provides only 30 kWh/day in winter. The array includes 2775 modules each of nominal 19-W capacity, mounted facing south at a  $45^\circ$  slope. The maximum recorded output of the array was 47 kW. The maximum recorded module temperature was  $50^\circ\text{C}$  when the ambient temperature was  $22^\circ\text{C}$ . Storage is provided in lead-acid batteries having aggregate capacity of 600 Ah. Inverters are used in the supply to the farm, and a large line-commutated inverter conditions excess electric energy that is supplied to the utility grid. The system was installed in 1983; it operates automatically with a weekly visual check and a general maintenance check each three months.

At Gardner, Massachusetts (near Boston), thirty 2.2-kW generators were installed in 1985 and 1986 on neighboring residences in an experimental study of the impact of large, distributed PV systems on utility grid loading, design, and protection (Gulachenski et al., 1988). Each of the 30 systems included a 2-kW inverter, and the outputs of the inverters were directly connected to the existing distribution panels in the houses. The systems were all in a small area and represent a possible future “saturation” of PV generators in a

utility service area. Problems of concern include the effects of slow transients caused by normal variation of PV generator output; effects of fast transients due to short circuits, lightning, reduced utility voltage, switching surges, and so on; and the performance of the inverters and their interactions with household appliances. In aggregate, the 30 systems have a 50.4-kW capacity at a solar irradiance of 1000 W/m<sup>2</sup>. The output of the systems peaks at times of utility peak loads during normal working hours in the summer. The output exceeds the loads on the residences during the peak hours, and residential systems such as these can feed power to the grid at peak hours and reduce the utility's peak generating capacity needs.

## 23.7 DESIGN PROCEDURES

There are many parallels between the design of thermal systems and the design of PV systems. The equipment is sufficiently expensive that investment costs dominate life-cycle costs, and overdesign of the systems is to be avoided. Thus there is need for means to predict the annual useful electrical output from PV systems. There is a substantial body of experience now available on which to base the sizing of these systems. The methods available for predicting long-term output range from detailed simulations to design methods based on utilizability concepts to hand calculation methods shown in the Sandia (1988) handbook. Eckstein (1990) has developed PV component models for the simulation program TRNSYS (Chapter 19). Computer programs are available that can assist in the sizing of PV systems and selecting the associated wiring, controls, inverters, and so on. In this section, a design method developed by Siegel et al. (1981) and Evans (1981) and extended by Clark et al. (1984) is presented. (It is similar in concept to the unutilizability design method of Monsen et al. for direct-gain passive heating systems presented in Chapter 22.) It can be applied to systems meeting loads with any monthly average hourly load profile but is limited to systems using maximum power point control.

The method includes two major steps. First, systems without storage are considered, and then the effects of finite (or infinite) storage are taken into account. The simplest system to analyze is one in which the load always exceeds the generating capacity. If at times the capacity of the generator is larger than the load, there is an additional problem of determining how much electrical energy must be dumped, stored, or sold to a utility. If a system includes storage batteries of finite capacity, it is also necessary to estimate the amount of excess energy that will be produced at times when the batteries are fully charged. Evans et al. (1980a,b) have addressed all of these problems in preparing graphs for predicting the fraction of loads carried by solar energy for a wide range of daily load patterns. The method presented here is an analytical method that provides the same information.

For the  $i$ th hour of the day, the power output of a PV array with maximum power point tracking is

$$P_i = A_c G_{T,i} \eta_{mp} \eta_e \quad (23.7.1)$$

where  $A_c$  is the array area,  $G_{T,i}$  is the incident solar radiation on the array,  $\eta_{mp}$  is the maximum power point efficiency of the array as found from Equation 23.2.16, and  $\eta_e$  is the

efficiency of any power-conditioning equipment. Substituting the cell temperature from Equation 23.3.3 into 23.2.13 yields

$$\eta_{mp} = \eta_{mp,ref} \left[ 1 + \frac{\mu_{mp}}{\mu_{mp,ref}} (T_a - T_{ref}) + \frac{\mu_{mp} G_T}{\mu_{mp,ref}} \frac{\tau \alpha}{U_L} \left( 1 - \frac{\eta_{mp}}{\tau \alpha} \right) \right] \quad (23.7.2)$$

The term  $\eta_{mp}/\tau \alpha$  is always small compared to unity and thus can be approximated by  $\eta_{mp,ref}$  without introducing significant error. The power is then

$$P_i = A_c G_{T,i} \eta_{mp,ref} \eta_e \left[ 1 + \frac{\mu_{mp}}{\mu_{mp,ref}} (T_a - T_{ref}) + \frac{\mu_{mp} G_{T,i}}{\mu_{mp,ref}} \frac{\tau \alpha}{U_L} (1 - \eta_{mp,ref}) \right] \quad (23.7.3)$$

The monthly average array electrical energy output  $\bar{E}_i$  for the hour  $i$  is found by integrating Equation 23.7.3 over the hourly period  $i$  and then summing over the month (e.g., from 10:00 to 11:00 for the month of June). The monthly average array efficiency  $\bar{\eta}_i$  for the hour  $i$  is the ratio  $\bar{E}_i/A_c \bar{I}_T$ . Carrying out the summation yields<sup>6</sup>

$$\bar{\eta}_i = \eta_{mp,ref} \eta_e \left[ 1 + \frac{\mu_{mp}}{\eta_{mp,ref}} (\bar{T}_a - T_{ref}) + \frac{\mu_{mp} \bar{G}_T}{\eta_{mp,ref}} \frac{\tau \alpha}{U_L} (1 - \eta_{mp,ref}) Z_i \right] \quad (23.7.4)$$

where

$$Z_i = \frac{1}{N \bar{I}_T^2} \sum_{n=1}^N I_{T,n}^2 \quad (23.7.5)$$

and is a function of geometry and  $\bar{k}_T$ . Although  $Z_i$  can be found using the long-term distribution of hourly radiation, the process is time consuming. An empirical fit for  $Z_i$  is

$$Z_i = \left( \frac{\bar{I}_o}{\bar{I}_T} \right)^2 (a_1 b_1 + a_2 b_2 + a_3 b_3) \quad (23.7.6a)$$

where

$$a_1 = R_b^2 + \rho(1 - \cos \beta) R_b + \frac{\rho^2 (1 - \cos \beta)^2}{4} \quad (23.7.6b)$$

$$a_2 = R_b (1 + \cos \beta - 2R_b) + \rho(1 + \cos \beta - 2R_b) \frac{1 - \cos \beta}{2} \quad (23.7.6c)$$

$$a_3 = \left( \frac{1 - \cos \beta}{2} - R_b \right)^2 \quad (23.7.6d)$$

$$b_1 = -0.1551 + 0.9226 \bar{k}_T \quad (23.7.6e)$$

$$b_2 = 0.1456 + 0.0544 \ln \bar{k}_T \quad (23.7.6f)$$

$$b_3 = \bar{k}_T (0.2769 - 0.318 \bar{k}_T) \quad (23.7.6g)$$

<sup>6</sup>The instantaneous power output of the cell and the monthly average hourly ambient temperature are assumed to remain constant for the hour.

A dimensionless critical radiation is defined as the ratio of a critical radiation level to the monthly average radiation where the critical level is that at which the output of the array is equal to the monthly average hourly load for that hour,  $\bar{L}_i/A_c\bar{\eta}_i$ :

$$X_c = \frac{I_{Tc,i}}{\bar{I}_{T,i}} = \frac{\bar{L}_i}{A_c\bar{\eta}_i\bar{I}_{T,i}} \quad (23.7.7)$$

The fraction of the incident radiation that exceeds this critical radiation level is  $\phi_i$  and can be estimated by the Liu and Jordan generalized utilizability functions (Section 2.23) or (more easily) by the Clark et al. (1984) utilizability functions (Equations 2.23.5 to 2.23.8).

The monthly average hourly generation that exceeds the load can be written as

$$\bar{E}_{ex,i} = \bar{E}_i\phi_i \quad (23.7.8)$$

and the energy to the load is

$$\bar{E}_{L,i} = \bar{E}_i(1 - \phi_i) \quad (23.7.9)$$

Monthly average daily excess energy and energy to the load are obtained by summing over all hours of the day:

$$\bar{E}_L = \sum_{i=1}^{24} \bar{E}_{L,i} \quad (23.7.10)$$

and

$$\bar{E}_{ex} = \sum_{i=1}^{24} \bar{E}_{ex,i} \quad (23.7.11)$$

Thus the monthly average fraction of the load carried by the PV system with no storage is

$$f_o = \frac{\bar{E}_L}{\sum_{i=1}^{24} \bar{L}_i} = \frac{\bar{E}_L}{\bar{L}} \quad (23.7.12)$$

Clark et al. (1984) and Evans (1981) have both studied the effects of load variation on a time scale smaller than an hour and found that the variation causes little difficulty and that use of an  $I_{T,c}$  that is constant for an hour is a satisfactory procedure.

From Equation 23.7.11,  $\bar{E}_{ex}$  is the monthly average daily amount of energy that cannot be utilized by the load when it is generated and so must be stored, dumped, or fed to a utility grid. If storage is provided, the fraction of the load met by solar will increase by an amount  $\Delta f_s = f - f_o$ , where  $f$  is the solar fraction with storage and  $f_o$  is that with no storage. From physical considerations it is possible to put bounds on  $\Delta f_s$ . To do so, it is convenient to define a term that is the value of  $\Delta f_s$  that would be found if all of the excess energy of a system without storage could be stored. This dumped energy without storage is

$$d_o = \frac{\eta_b \bar{E}_{ex}}{\bar{L}} \quad (23.7.13)$$

where  $\eta_b$  is the battery storage efficiency.

If  $d_o$  is much smaller than  $B_c/\bar{L}$ , the ratio of battery capacity to the average daily load, the battery will never become completely charged and no energy will be dumped. Thus at the lower limit, as  $d_o$  approaches 0,  $\Delta f_s$  approaches 0.

If  $d_o$  is very large, that is, if the excess energy that is available for storage is large compared to the average load,  $\Delta f_s$  approaches its upper limit. This limit is  $1 - f_o$ , since the fraction of the load supplied by solar energy cannot exceed unity. In addition to this limit, there is another upper limit on  $\Delta f_s$ . If  $d_o$  is large, all loads in daytime will be met by the array and the battery will only be discharged at night. In this situation  $\Delta f_s$  may be limited by the ratio of the battery capacity to the load,  $B_c/\bar{L}$ . Thus the upper limit on  $\Delta f_s$  can be expressed as

$$\Delta f_{\max} = \min \left[ (1 - f_o), \frac{B_c}{\bar{L}} \right] \quad (23.7.14)$$

Clark et al. (1984) developed an empirical equation for  $\Delta f_s$  which satisfies these constraints for both high and low values of  $d_o$ :

$$\Delta f_s = \frac{d_o + \Delta f_{\max} - [(d_o + \Delta f_{\max})^2 - 4P d_o \Delta f_{\max}]^{1/2}}{2P} \quad (23.7.15)$$

where

$$P = 1.315 - 0.1059 \frac{f_o \bar{L}}{B_c} - \frac{0.1847}{\bar{K}_T} \quad (23.7.16)$$

The correlation was developed by computing values of  $\Delta f_s$  for a range of diurnal load types, three climates, and battery capacities from 0 to  $2\bar{L}$ . The simulation program TRNSYS, including PV generator, regulator-inverter, and battery models based on those of Evans et al. (1978), was used.

Clark et al. (1984) compared the results of performance calculations using the procedures outlined above with the TRNSYS simulations and found that the standard deviation of the annual differences was 2.4%. (The standard deviation of 672 monthly load fractions was 3.9%.)

### Example 23.7.1

Determine the March electrical output and solar fraction for a PV power system array that uses four modules having the following characteristics: NOCT temperature  $46^\circ\text{C}$ , reference temperature  $25^\circ\text{C}$ , maximum power efficiency 10.4%, single module area  $0.427\text{ m}^2$ , temperature coefficient of maximum power point efficiency  $-0.00050$ , efficiency of maximum power point electronics 0.9, array slope  $35^\circ$ , array azimuth  $0^\circ$ , usable battery capacity 1200 Wh, and battery efficiency 0.8. The system is located at a latitude of  $40^\circ$ , the month is March, the monthly average daily horizontal radiation is  $13.2\text{ MJ/m}^2$ , the ground reflectance is 0.2, and the load is constant at 100 W between 9 AM and 3 PM and zero at other times. The 12 monthly average hourly temperatures, beginning at 6 AM, are 4, 5, 5, 6, 8, 10, 11, 12, 12, 11, 10, and  $9^\circ\text{C}$ .

**Solution**

The details for only the hour 10 to 11 will be shown. Intermediate values for the 12 hours of interest are shown in the table below. It is first necessary to calculate solar radiation incident on the array for the hour. For day 75, the average day in March,  $\delta = -2.4^\circ$ ,  $H_o = 27.4$  MJ, and  $\omega_s = 88^\circ$ . Thus,  $\overline{K}_T = 13.2/27.4 = 0.481$ . From Equations 2.13.2 and 2.13.4 for the hour 10 to 11,  $\omega = -22.5$ ,  $r_t = 0.129$ , and  $r_d = 0.123$ . From Equation 1.8.2,  $R_b = 1.347$ , and from Equation 2.12.1,  $\overline{H}_d/\overline{H} = 0.448$ , so that from Equation 2.23.4,

$$\begin{aligned}\overline{I}_T &= 13.2 \times 10^6 [(0.129 - 0.448 \times 0.123) 1.347 \\ &\quad + 0.448 \times 0.123 \times (1 + \cos 35)/2 + 0.2 \times 0.129 (1 - \cos 35)/2] \\ &= 2.0 \text{ MJ}\end{aligned}$$

The extraterrestrial radiation for the hour,  $\overline{I}_o$ , from Equation 1.10.4 is 3.37 MJ. From Equation 23.7.6,  $Z_i = 1.525$ . From Equation 23.3.2 at NOCT conditions,  $U_L/\tau\alpha = 800/(46 - 20) = 30.8 \text{ W/m}^2 \text{ K}$ . The module efficiency for the hour can now be calculated from Equation 23.7.4:

$$\begin{aligned}\overline{\eta}_i &= 0.104 \times 0.9 \left[ 1 - \frac{0.0005}{0.104} (8 - 25) \right. \\ &\quad \left. - \frac{0.0005 \times 2 \times 10^6 \times (1 - 0.104) 1.525}{0.104 \times 30.7 \times 3600} \right] = 0.090\end{aligned}$$

The monthly average hourly electrical output is  $\overline{E}_i = 0.090 \times 4 \times 0.427 \times 2 \times 10^6/3600 = 86 \text{ W}$ .

From 2.23.8,  $R_h = \overline{I}_T/(\overline{H}_T r_T) = 2.00/(13.2 \times 0.129) = 1.17$ . The dimensionless critical radiation is the ratio of the critical radiation level from Equation 23.7.7 to the incident radiation:

$$\begin{aligned}X_{c,i} &= \frac{L_i}{\overline{I}_T A_c \eta_i} \\ &= \frac{100 \times 3600}{2 \times 10^6 \times 4 \times 0.427 \times 0.090} = 1.166\end{aligned}$$

From Equation 2.23.5, the utilizability  $\phi = 0.159$  and from Equation 23.7.8 the hourly excess  $\overline{E}_{ex,i} = 86 \times 0.159 = 14 \text{ W}$ . The monthly energy to the load is  $\overline{E}_i - \overline{E}_{ex,i} = 86 - 14 = 72 \text{ W}$ .

The table shows the results for all of the hours of interest. The monthly average electric generation is 664 W and the excess is 242 W. With no storage, useful energy is available only during the middle 6 h of the days. The total energy to the load for the month



is 422 Wh,<sup>7</sup> so the monthly average fraction of the load carried by the PV system without batteries,  $f_o$ , is  $422/600 = 0.703$ .

Hour	$T_a$ , °C	$\bar{I}_T$ , MJ	$Z_i$	$\bar{\eta}_i$	$\bar{E}_i$ , Wh	$\bar{L}_i$ , Wh	$X_{c,i}$	$\phi$	$\bar{E}_{ex,i}$ , Wh	$\bar{E}_{L,i}$ , Wh
6–7	4	0.15	2.228	0.102	7	0	0.000	1.000	7	0
7–8	5	0.60	1.906	0.099	28	0	0.000	1.000	28	0
8–9	5	1.11	1.728	0.096	50	0	0.000	1.000	50	0
9–10	6	1.61	1.604	0.093	71	100	1.412	0.087	6	65
10–11	8	2.00	1.525	0.090	86	100	1.166	0.159	14	72
11–12	10	2.22	1.486	0.088	93	100	1.072	0.193	18	75
12–1	11	2.22	1.486	0.088	93	100	1.077	0.191	18	75
1–2	12	2.00	1.525	0.088	84	100	1.189	0.149	13	71
2–3	12	1.61	1.604	0.090	69	100	1.454	0.075	5	64
3–4	11	1.11	1.728	0.093	49	0	0.000	1.000	49	0
4–5	10	0.60	1.906	0.096	27	0	0.000	1.000	27	0
5–6	9	0.15	2.228	0.100	7	0	0.000	1.000	7	0
Totals					664	600			242	422

To find the contribution by the battery system,  $\Delta f_s$  must be determined. From Equation 23.7.13,  $d_o = 0.8 \times 242/600 = 0.323$ , and from Equation  $\Delta f_{\max} = \min [1 - 0.703, 0.323] = 0.297$ . From Equation 23.7.16,  $P = 1.315 - 0.1059 \times 0.703 \times 600/1200 - 0.1847/0.481 = 0.894$ , and from Equation 23.7.15,  $\Delta f_s = 0.232$ . The monthly fraction of the load supplied by the PV system is then  $0.703 + 0.232 = 0.935$ , and the monthly average daily electrical output is  $0.935 \times 600 = 561$  Wh. ■

A study by Menicucci (1986) compared predictions of long-term PV generator output using the Clark et al. (1984) method (in the form of the program PV-FCHART) with measurements on operating systems and found very good agreement. Differences were between 1 and 4% on an annual basis when the radiation measured on the plane of the array was used in the performance calculation.

## 23.8 HIGH-FLUX PV GENERATORS

Cell array costs are for most systems an important part of the total cost of the system. The contribution of array costs to the total cost ranged from 12 to 60% in the 15 examples cited in the (Sandia 1988) handbook, with the fraction tending to be larger in larger systems. The predominance of cell costs has led to consideration of operation of cells at high solar radiation flux levels on the basis that concentrators cost less than cells. A consideration in the design of high-flux systems is the maintenance of uniform radiation intensity on all cells in an array. The current in a series array will be limited by the current in the

<sup>7</sup>These calculations are shown in terms of rates, in watts. Since these rates are taken as constant over hours, the energy quantities in watt-hours are numerically the same as the rates.

cell subjected to the lowest flux; this can degrade performance if one or more cells are underilluminated.

An early high-flux generator was built and tested by Beckman and Schöffner (1966); it utilized water cooling from extended heat transfer area on the backs of cells that operated at about 200 times ordinary solar flux. The output of the cells was about 100 times larger than that of the same cells in nonconcentrated radiation. Uniform radiation on the array was achieved by using an assembly of flat mirrors, each reflecting a uniform image onto the focal plane larger than the PV array. The cells were *p-n* silicon cells with 20 gridlines/cm; these were optimized for the 150 to 350 kW/m<sup>2</sup> radiation fluxes used in the experiments.

One- and two-axis tracking concentrators are used with PV generators. Refracting and reflecting systems have been applied. Fresnel refractors have been used with concentration ratios (ratio of aperture area to cell area) of 40 to 400, linear reflecting concentrators with ratios of 25 to 40, and CPC-type optics at ratios of about 9. Cells for use with concentrators have closely spaced front contacts to minimize series resistance in the cells, and as they operate at higher fluxes and thus higher temperatures, the materials in the cells and coatings must be able to withstand higher temperatures than cells in normal operation. Cell cooling can be passive or active; passive cooling involves natural convection over extended heat transfer areas on the backs of the cells, and active cooling depends on forced circulation of coolant. A system with active cooling must be fitted with safety devices to defocus the concentrator in case of coolant flow failure, as permanent cell damage will result from severe overheating.

## 23.9 SUMMARY

This discussion of PV cells and their applications is an extremely brief treatment of a subject about which many books have been written and one in which new technology appears at a rapid rate. Applications are increasing almost daily. Thus this chapter is only an introduction to a very large and dynamic topic. However, the same considerations of incident radiation on fixed and tracking surfaces apply here as in strictly thermal processes. There is an added consideration that the spectral response of PV cells is such that spectral distribution of solar radiation is more significant than in thermal devices. The same energy balance concepts that apply to collectors apply to PV modules, with the modification that some energy is removed as electrical energy. And the application of utilizability concepts to the estimation of monthly performance of PV generators is parallel to that for passive thermal processes. Thus the earlier chapters provide the groundwork for understanding both thermal and PV processes.

## REFERENCES

- Beckman, W. A. and P. Schöffner, in *Proceedings of the Twentieth Annual Power Sources Conference*, p. 190 (1966). "An Experimental High Flux Solar Power System."
- Clark, D. R., S. A. Klein, and W. A. Beckman, *Solar Energy*, **33**, 551 (1984). "A Method for Estimating the Performance of Photovoltaic Systems."
- Davis, M. W., A. H. Fanney, and B. P. Dougherty, *Trans. ASME J. Solar Energy Eng.*, **123**, 200 (2001). "Prediction of Building Integrated Photovoltaic Cell Temperatures."

- DeSoto, W., S. A. Klein, and W. A. Beckman, *Solar Energy*, **80**, 78 (2006). "Improvement and Validation of a Model for Photovoltaic Array Performance."
- Eckstein, J. H., M.S. Thesis, Mechanical Engineering, University of Wisconsin-Madison (1990). "Detailed Modelling of Photovoltaic Systems Components."
- Evans, D. L., *Solar Energy*, **27**, 555 (1981). "Simplified Method for Predicting Photovoltaic Array Output."
- Evans, D. L., W. A. Farinelli, and L. P. Koehler, Sandia National Laboratories Report SAND 80-7013 (1980a). "Simulation and Simplified Design Studies of Photovoltaic Systems."
- Evans, D. L., W. A. Farinelli, and L. P. Koehler, Sandia National Laboratories Report SAND 80-7185 (1980b). "Simplified Design Guide for Estimating Photovoltaic Flat Array and System Performance."
- Evans, D. L., W. A. Farinelli, and R. T. Otterbein, Sandia National Laboratories Report SAND 78-7031 (1978). "Combined Photovoltaic/Thermal System Studies."
- Fanney, A. H., B. P. Dougherty, and M. W. Davis, in *Proceedings of the Twenty-Ninth IEEE Photovoltaic Specialists Conference (PVSC)*, May 20-24, 2002, New Orleans, LA. "Evaluating Building Integrated Photovoltaic Performance Models."
- Gordon, J., *Solar Cells*, **20**, 295 (1987). "Optimal Sizing of Stand-Alone Photovoltaic Power Systems."
- Green, M. A., *Solar Cells*, Prentice-Hall, Englewood Cliffs, NJ (1982).
- Gulachenski, E. M., et al., in *Proceedings of the 1988 Annual Meeting* (M. J. Coleman, ed.), American Solar Energy Society, p. 63 (1988). "The Gardner, MA, 21st Century Residential Photovoltaic Project."
- Kenna, J. P. and W. B. Gillett, *Solar Water Pumping—A Handbook*, I. T. Publications, London (1985).
- Khouzam, K., L. Khouzam, and P. Groumpos, *Solar Energy*, **46**, 101 (1991). "Optimum Matching of Ohmic Loads to the Photovoltaic Array."
- King, D. L., W. E. Boyson, and J. E. Kratochvil, Sandia National Laboratories Report SAND2004-3535 (Aug. 2004). "Photovoltaic Array Performance Model."
- Kirpich, A., G. O'Brien, and N. Shepard, in *Solar Energy Technology Handbook* (W. C. Dickinson and P. N. Cheremisinoff, eds.), Marcel Dekker, New York, p. 313 (1980). "Electric Power Generation: Photovoltaics."
- Klein, S. A. and W. A. Beckman, *Solar Energy*, **39**, 499 (1987). "Loss-of-Load Probabilities for Stand-Alone Photovoltaic Systems."
- Loferski, J. J., J. M. Ahmad, and A. Pandey, in *Proceedings of the 1988 Annual Meeting of the American Solar Energy Society*, (M. J. Coleman, ed.), p. 427 (1988). "Performance of Photovoltaic Cells Incorporated into Unique Hybrid Photovoltaic/Thermal Panels of a 2.8 kW Residential Solar Energy Conversion System."
- McCarthy, S. and G. T. Wrixon, in *Energy for Rural and Island Communities*, Vol. **4** (J. Twidell, I. Hounam, and C. Lewis, eds.), Pergamon, Oxford, p. 9 (1986). "The Fotovoltaic Project—a 50 kWp Photovoltaic Array on Fota Island."
- Maycock, P. D. and E. N. Stirewalt, *Photovoltaics*, Brick House Publishing, Andover, MA (1981).
- Menicucci, D. F., *Solar Cells*, **18**, 383 (1986). "Photovoltaic Array Performance Simulation Models."
- Messenger, R. A. and J. Ventre, *Photovoltaic Systems Engineering*, 2nd ed., CRC Press, Boca Raton, FL (2004).
- Nelson, J., *The Physics of Solar Cells*, Imperial College Press, London (2003).
- Rauschenbach, H. S., *Solar Cell Array Design Handbook: The Principles and Technology of Photovoltaic Energy Conversion*, Van Nostrand Reinhold, New York (1980).
- Sandia National Laboratories Report SAND 87-7023 (1988), Stand-Alone Photovoltaic Systems—A Handbook of Recommended Design Practices. Available from National Technical Information Service, U.S. Department of Commerce, Washington, DC.

- Schöffner, P., P. Kuhn, and C. M. Sapsford, *Proc. UN Conf. New Sources of Energy*, **4**, 444 (1964).  
“Instrumentation for Solar Radiation Measurements.”
- Schroder, D. K., *Semiconductor Material and Device Characterization*, 2nd ed., Wiley-Interscience, New York (1998).
- Siegel, M. D., S. A. Klein, and W. A. Beckman, *Solar Energy*, **26**, 413 (1981). “A Simplified Method for Estimating the Monthly-Average Performance of Photovoltaic Systems.”
- Townsend, T. U., M.S. Thesis, Mechanical Engineering, University of Wisconsin-Madison (1989).  
“A Method for Estimating the Long-Term Performance of Direct-Coupled Photovoltaic Systems.”
- Wolf, M., in *Solar Energy Handbook* (J. F. Kreider and F. Kreith, eds.), McGraw-Hill, New York (1981). “Photovoltaic Solar Energy Conversion Systems.”

# Wind Energy


Wind energy is an indirect form of solar energy; the solar heating of the atmosphere along with the earth's rotation creates planetary and local wind patterns. In this chapter the wind resource is described and a method for reducing wind data to a useful mathematical form is presented. A simplified theory of wind turbines is then presented. This simplified theory leads to a basic understanding of the characteristics of actual wind turbines. Combining the analytical description of the wind resource with the characteristic of an actual wind turbine leads to a prediction of electrical energy production. Much about wind energy is not discussed in this chapter, such as the complex meteorology that produces favorable wind sites, the aerodynamics of turbine blades, the needed controls for producing acceptable electrical waveforms, the mechanical aspects of gears trains and tower structures, the visual and avian siting issues, and noise problems.

## 24.1 INTRODUCTION

Windmills (wind machines used to mill grain) have been used for more than two thousand years. One of the earliest descriptions is of Persian windmills found in Arab writings of the ninth century describing windmills in use in the seventh century (El-Wakil, 1984). However, it is believed that the Persians had vertical-axis grindstones as early as about 200 BC (Eldridge, 1980).

A large variety of wind turbines have been suggested and used at various times and for various purposes. Figures 24.1.1(a) and (b) show horizontal-axis and vertical-axis machines. Today the most common new installations are three-bladed horizontal-axis turbines as shown in Figure 24.1.2, although two-bladed turbines are also common. Most of these turbines are of the up-wind variety where the blades are in front of the nacelle. The downwind variety has the advantage that it automatically faces into the wind but the disadvantage is that the tower blocks some of the incoming wind as well as creating increased cyclic stressing of the blades as they pass behind the tower. The size of turbines has increased dramatically over the years. Figure 24.1.3 shows relative sizes of modern turbines of various power outputs.

Worldwide wind energy production has grown significantly over the past few years. Figure 24.1.4 shows a 25% annual growth in the worldwide installed capacity between 1996 and 2004, a growth rate that is expected to continue into the immediate future. While the number of wind turbines has increased significantly, the cost of producing electricity from the wind has dropped from around 0.30 \$US/kWh in 1985 to under 0.05 \$US/kWh



**Figure 24.1.1** (a) Horizontal axis wind turbines. (b) Vertical axis wind turbines. From Eldridge (1980).

in 2005. The costs are expected to continue to decline as the technology matures and as turbine size increases.

Denmark is the leading country in the world relying on wind energy. In 2012 Denmark produced about 34% of its electrical needs from the wind although some of this wind-generated electricity was exported. This large fraction is a result of political decisions to rely heavily on a renewable resource and to promote local industry.

According to the American Wind Energy Association wind farms across the United States have a total capacity of 47 GW in 2011, enough electricity to serve more than


Primarily drag type

Savonius


Multibladed  
Savonius

Plates


Shield




Cupped

Primarily lift type $\phi$ -Darrieus $\Delta$ -Darrieus


Giromill




Turbine

CombinationsSavonius/ $\phi$ -Darrieus


Split Savonius




Magnus




Airfoil

Others


Deflector



Sunlight



Venturi



Confined vortex

(b)


**Figure 24.1.1** (Continued)

13 million households. The United States expects to install 13 GW of wind energy during 2012, a record-breaking year. The U.S. Department of Energy estimates that approximately 600 GW of wind energy is economical when natural gas prices exceed \$4/GJ. This amount of electricity is enough to provide about 20% of U.S. electrical needs.


It is clear that wind energy is already a major source of electricity and will continue to grow.



**Figure 24.1.2** Altamont Pass, CA. Photo courtesy of U.S. Department of Energy.



**Figure 24.1.3** Relative sizes of modern wind turbines. Adapted from Manwell et al. (2002).




**Figure 24.1.4** Twenty-five percent annual growth in the worldwide installed capacity between 1996 and 2004.



## 24.2 WIND RESOURCE

The planetary wind patterns shown in Figure 24.2.1 are caused by a combination of unequal solar heating of the earth and the earth's rotation. The earth receives greater solar heating at the equator than at the poles, resulting in warm air rising at the equator and flowing through the upper atmosphere toward the poles. This upper atmospheric wind falls back to the earth's surface at the horse latitudes (about  $25^\circ$ ). Simultaneously cold air leaves the poles and flows near the earth's surface toward the equator rising at the polar front at about  $50^\circ$ . The westerlies, between about  $25^\circ$  and  $50^\circ$ , flow near the ground between the horse latitudes and the polar front. The northeast and southeast trade winds flow near the earth's surface from the horse latitudes to the equator where the air is heated and rises to the upper atmosphere. Since this upward flow does not create any steady surface winds the region is called the doldrums. Because the earth rotates in an eccentric orbit about a tipped axis relative to the sun-earth plane, seasonal variations occur in these general flow patterns. Coriolis, inertial, and frictional forces also play a large role in determining the planetary wind pattern.

Local winds are a result of two different phenomena, the first being the differential heating of the air above land and the air above water. The sun warms the land surface, which warms the air above it, thereby reducing the average density. Solar energy incident on water is partially absorbed in depth and partially used to evaporate water. The result is that the air above the water is not heated as much as the air above land and thus the




**Figure 24.2.1** Planetary wind patterns.

air over the water is denser. The resulting pressure gradient causes cool denser air to flow toward the warm lighter air. On clear nights the land cools faster than the water and the airflow reverses. The second mechanism is the heating and cooling on the sides of hills and mountains. During the day the air on the sides of mountains is heated and rises, drawing in the cool air above the valley. The airflow direction reverses at night when the cool air drains down the hillside and settles in the valley floor.


Although interesting and useful for general studies the prediction of wind speed using general planetary and local wind concepts is not useful for predicting wind power from an actual wind turbine at a particular site. What are needed are long-term measurements of the local wind. Figure 24.2.2 shows typical large turbulent fluctuations of local wind speed over about a 2-min time period. Figure 24.2.3 shows the annual average wind speed in Madison, Wisconsin (not a very good wind power candidate), for different years along with the standard deviation. The year-to-year variation is significant. Figure 24.2.4 shows the diurnal (time-of-day) variation of wind speed in July for Madison averaged over each hour for 22 years.<sup>1</sup> Again the variation is significant. As will be shown, finding average wind speeds is not sufficient to estimate long-term turbine power output. Two locations with the same average wind speed can have very different wind power potential due to differences in the distribution of wind about the mean.

With all of these variations how can the power of a wind turbine be estimated at a particular location? Fortunately, Aspliden et al. (1988) note that one year of recorded data is generally sufficient to predict long-term seasonal mean wind speeds to within 10% with a confidence level of 90%. A few years of data is therefore sufficient to characterize a particular site with high degree of confidence. In some locations 30 years or more of data is available. However, this easily available measured wind data are often taken at airports, which are not desirable locations for wind turbines, and taken at a height of 10 m, which is too low for estimating wind turbine performance. Great




**Figure 24.2.2** Sample turbulent fluctuations. From Manwell et al. (2002).

<sup>1</sup>For 8 years during the 30-year period 1961 to 1990 the U.S. Weather Service reported meteorological variables on 3-h intervals. These data were not included in preparing Figure 24.2.4.



**Figure 24.2.3** Thirty-year annual average wind speed and standard deviation for Madison, WI.



**Figure 24.2.4** Twenty-two-year average July diurnal wind speed ( $\pm 1$  standard deviation) for Madison, WI.

care must be exercised in using airport/weather station data for nearby locations. The books by Manwell et al. (2002) and Freris (1990) discuss this problem at length. In the United States the National Renewable Energy Laboratory (NREL) along with Pacific Northwest Laboratory published the *Wind Energy Resource Atlas of the United States* (available on the NREL website). This atlas contains wind resource maps of all 50 states plus U.S. territories. Information on more than 50 other wind atlases is available at [www.windatlas.dk](http://www.windatlas.dk).

The power of the wind is a convenient metric for assessing the potential of a wind energy site. At an instant of time the mass flow rate of air  $\dot{m}$  passing through an area  $A$

with kinetic energy  $U^2/2$  is the wind power (the wind power density is the wind power divided by the area):

$$P_w = \frac{\dot{m}U^2}{2} = \frac{\rho AU^3}{2} \quad (24.2.1)$$


So, for an area of  $1 \text{ m}^2$ , a wind speed of  $10 \text{ m/s}$  and an air density of  $1.225 \text{ kg/m}^3$  (sea level at  $15^\circ\text{C}$ ), the power is  $\frac{1}{2}(1.225 \text{ kg/m}^3 \times 1 \text{ m}^2 \times 10^3 \text{ m}^3/\text{s}^3) = 612 \text{ W}$ . However, it is not correct to cube the average wind speed to determine the average wind power. The correct wind power calculation must take into account the wind speed distribution as given by

$$\overline{P}_w = \frac{A}{2N} \sum_{i=1}^N \rho_i U_i^3 \quad (24.2.2)$$

With a time series that includes wind speed and air density the average wind power can be calculated (most likely the data would contain air temperature and pressure from which the density can be calculated by the ideal gas law).

Time series wind data are useful if the value of the energy produced is dependent on time (e.g., electricity is more valuable during the so-called peak period, which for the Madison utility is from 10 AM to 9 PM Monday through Friday excluding holidays). As will be shown in Section 24.4 time series wind data and wind turbine performance characteristics can be combined to estimate the wind energy production in any time period.

A useful representation of the wind resource is the wind (or velocity) duration curve, as illustrated for Madison in Figure 24.2.5. This curve is generated by taking all wind speed observations and sorting them from highest value to lowest value. The abscissa can be hours or, as shown here, the fraction of the total time. This particular graph used 30 years of data (1960 to 1991) at the Madison airport. From the graph, 75% of the time the wind speed exceeds  $2.4 \text{ m/s}$  and 25% of the time the wind speed exceeds  $5.7 \text{ m/s}$ . For Madison the 30-year average wind speed and standard deviation are  $4.27 \text{ m/s}$  and  $2.41 \text{ m/s}$ , respectively.



**Figure 24.2.5** Wind duration curve for Madison, WI.

The velocity duration curve loses the associated density data that are needed in Equation 24.2.2 to compute the wind power. Usually a reasonable guess can be made of the average density. For Madison the mean daily maximum temperature (July) is  $28^{\circ}\text{C}$  and the mean daily minimum temperature (January) is  $-13^{\circ}\text{C}$ . The annual average temperature is  $8^{\circ}\text{C}$ . The average barometric pressure is 98.5 kPa. A reasonable average density for dry air of  $1.22\text{ kg/m}^3$  can be found using the annual averages of temperature and pressure. The range, using the mean daily minimum and maximum temperatures, is about 8% high and 7% low. The actual power-weighted average density  $\bar{\rho}$  for Madison calculated from

$$\frac{\bar{P}_w}{A} = \frac{\bar{\rho}}{2N} \sum_{i=1}^N U_i^3 \quad (24.2.3)$$

is  $1.216\text{ kg/m}^3$ . If the reported humidity is used in the density to find the average power in Equation 24.2.2, then the Madison average density reduces to  $1.205\text{ kg/m}^3$ .

The data collected at most weather stations are at a height of 10 m. The hub center of large modern wind turbines can easily exceed 150 m. Consequently it is necessary to extrapolate wind data measured at a height of 10 m to other heights. The most commonly used technique is to use a power law profile of the form

$$\frac{U(z_1)}{U(z_2)} = \left( \frac{z_1}{z_2} \right)^{\alpha} \quad (24.2.4)$$

where  $z$  is the height and  $U(z)$  is the velocity at  $z$ . The exponent  $\alpha$  depends on almost everything (terrain, wind speed, temperature, surface roughness, time of day, and season), but without detailed information in a stable flow it is generally accepted to be  $\frac{1}{7}$  (0.14). The range of  $\alpha$  can be large: from 0.05 for smooth-surface conditions in the tropics to 0.4 for rough-surface conditions in temperate latitudes. If wind velocity measurements at two different heights at the location of interest are known, then it is a simple matter to evaluate  $\alpha$ . Manwell et al. (2002) present empirical relationships that correlate  $\alpha$  to other variables. They also provide references to detailed studies and to other models for extrapolating wind speed with height.


### Example 24.2.1

Seven observations of wind speed (in meters per second) at both 10 and 50 m are shown in the table (normally there would be much more data). Determine the best value of the exponent  $\alpha$  in Equation 24.2.4 that fits the data.

10 m	50 m
5.0	6.3
9.8	12.3
5.5	6.9
6.2	8.0
7.1	8.8
8.2	10.6
7.5	9.5

### Solution

The data pairs are plotted in the figure. A least-squares curve fit of the form  $U_{50} = SU_{10}$ , where  $S$  is the slope, is also shown. Note that this equation goes through the point 0, 0, as it must. The value of  $S$  is 1.263. Comparing  $U_{50} = SU_{10}$  with Equation 24.2.4 shows that  $S = (z_2/z_1)^\alpha$  so that  $\alpha = \ln S / \ln 5 = 0.145$ , which is very close to  $\frac{1}{7}$  (0.143).



It is often convenient to replace wind data, which can be a very large data set, with statistical expressions that represent the data with only a few parameters. The two most common distribution functions are the Rayleigh and Weibull distributions. The Weibull distribution is used here since the Rayleigh distribution is a special case of the Weibull distribution.

The standard deviation of the wind velocity is given by

$$\sigma = \sqrt{\frac{1}{N-1} \sum_{i=1}^N (U_i - \bar{U})^2} \quad (24.2.5)$$

where the average velocity is given by

$$\bar{U} = \frac{1}{N} \sum_{i=1}^N U_i \quad (24.2.6)$$

The probability density function for the Weibull distribution is given by

$$p(U) = \frac{k}{c} \left(\frac{U}{c}\right)^{k-1} \exp\left[-\left(\frac{U}{c}\right)^k\right] \quad (24.2.7)$$

and the cumulative distribution function [the integral of  $p(U)$  from zero to  $U$ ] is given by

$$F(U) = 1 - \exp \left[ - \left( \frac{U}{c} \right)^k \right] \quad (24.2.8)$$

The parameter  $k$  is called the Weibull shape factor and the parameter  $c$  is called the Weibull scale factor. It is necessary to find two relationships to determine these two parameters. The integration of  $U \times p(U)$  over all wind speeds yields the average wind speed (i.e., the expected value of  $U$ ) and can be shown to be


$$\bar{U} = c \Gamma \left( 1 + \frac{1}{k} \right) \quad (24.2.9)$$

where  $\Gamma$  is the gamma function. It can also be shown that the square of the standard deviation of the wind speed (Equation 24.2.5) is equal to

$$\sigma^2 = \bar{U}^2 \left[ \frac{\Gamma(1 + 2/k)}{\Gamma^2(1 + 1/k)} - 1 \right] \quad (24.2.10)$$

Once the average and standard deviation of the wind velocity are known, the parameters  $c$  and  $k$  can be found from the simultaneous solution of Equations 24.2.9 and 24.2.10. Figure 24.2.6 shows the probability density function for an average wind velocity of 10 m/s and various values of  $\sigma$ .

When  $k = 2$  the Weibull distribution reduces to the Rayleigh distribution. That is, when  $k = 2$ , the gamma function  $\Gamma^2(1 + 1/k) = \pi/4$  so that, with some algebra,



**Figure 24.2.6** Probability density function for an average wind speed of 10 m/s and for various values of the standard deviation.

Equation 24.2.7 reduces to

$$p(U) = \frac{\pi}{2} \left( \frac{U}{\bar{U}} \right) \exp \left[ -\frac{\pi}{4} \left( \frac{U}{\bar{U}} \right)^2 \right] \quad (24.2.11)$$

With  $k = 2$  and  $\bar{U} = 10$  m/s the standard deviation from the Weibull distribution is 5.227. Thus, the Rayleigh distribution in Figure 24.2.6 is between  $\sigma$  of 5 and 6.

One property of the gamma function is that the expected value of the  $n$ th moment of  $U$  is given by  $\overline{U^n} = c^n \Gamma(1 + n/k)$  so that the average kinetic energy is given by

$$\rho A \frac{\overline{U^2}}{2} = \rho A \frac{c^2}{2} \Gamma \left( 1 + \frac{2}{k} \right) \quad (24.2.12)$$

and the average power is given by

$$\rho A \frac{\overline{U^3}}{2} = \rho A \frac{c^3}{2} \Gamma \left( 1 + \frac{3}{k} \right) \quad (24.2.13)$$

### Example 24.2.2

A wind energy pattern factor  $K_e$  is defined as the ratio of the average power of the wind divided by the power of the wind calculated (incorrectly) using the average velocity cubed. For the Weibull distribution determine the energy pattern factor for an average wind speed of 10 m/s having a range of standard deviations shown in Figure 24.2.6.

### Solution

The average power of the wind is given by Equation 24.2.13. The average velocity is given by Equation 24.2.9. The energy pattern factor in terms of the Weibull parameters is then

$$K_e = \frac{0.5 \rho A c^3 \Gamma(1 + 3/k)}{0.5 \rho A c^3 \Gamma^3(1 + 1/k)} = \frac{\Gamma(1 + 3/k)}{\Gamma^3(1 + 1/k)}$$

For  $\bar{U} = 10$  m/s and  $\sigma = 2$  m/s the simultaneous solution of Equations 24.2.9 and 24.2.10 yield  $k = 5.797$  (also,  $c = 10.80$ , but it is not needed) and  $k_e = 1.117$ . Since  $k_e \neq 1.0$ , the claim made earlier in this section that two locations with the same average wind speed can have very different average wind powers is validated. The following table provides values of  $k_e$  for various values of  $\sigma$ :

$\sigma$ (m/s)	$c$ (m/s)	$k$	$K_e$
2	10.80	5.797	1.117
3	11.08	3.714	1.269
4	11.25	2.696	1.498
5	11.29	2.101	1.821
6	11.22	1.717	2.264
8	10.75	1.258	3.645



### 24.3 ONE-DIMENSIONAL WIND TURBINE MODEL

In 1926 Betz [see Manwell et al. (2002)] published a paper that is the basis of the analysis presented here. Although the model is considerably simplified, it provides a basis for understanding the characteristics of wind turbines. The major assumptions are as follows:

Incompressible and frictionless steady flow

An ideal rotor (i.e., an infinite number of blades with uniform flow and forces over the rotor)

A nonrotating wake

Static pressure in the stream tube far upstream and downstream of the rotor that is equal to the undisturbed static pressure

As shown in Figure 24.3.1, two different control volumes will be used for this analysis: the stream tube and the rectangular box shown with dotted lines. It is not necessary to use two control volumes, but some of the forces on the rectangular box are easier to visualize than on the stream tube. Mass balances along the stream tube with constant density (the density cancels out) yields

$$A_i U_o = A_R U_R = A_w U_w \quad (24.3.1)$$

where subscripts  $o$ ,  $R$ , and  $w$  represent the undisturbed region, the rotor region, and the wake region, respectively. The area  $A_i$  is the upstream area of the stream tube. A mass balance for the rectangular control volume yields

$$A U_o = Q + (A - A_w) U_o + A_w U_w \quad (24.3.2)$$

which can be solved for the volume flow out of the control volume,  $Q$ :


$$Q = A_w (U_o - U_w) \quad (24.3.3)$$

Conservation of horizontal momentum on the control volume,

$$\sum F + \dot{M}_{\text{in}} - \dot{M}_{\text{out}} = 0 \quad (24.3.4)$$

leads to

$$-T + \rho A U_o^2 - \rho A_w U_w^2 - \rho (A - A_w) U_o^2 - \rho Q U_o = 0 \quad (24.3.5)$$



**Figure 24.3.1** Two wind turbine control volumes.

where the thrust  $T$  is the force required to hold the wind turbine in place. Solving for the thrust using Equation 24.3.3 to eliminate  $Q$  yields

$$T = \rho A_w U_w (U_o - U_w) \quad (24.3.6)$$

Bernoulli's equation can be applied along the stream tube from the inlet to the upstream of the rotor and from the downstream side of the rotor to the exit:

$$p_o + \frac{\rho U_o^2}{2} = p_R^+ + \frac{\rho U_R^2}{2} \quad (24.3.7a)$$

$$p_R^- + \frac{\rho U_R^2}{2} = p_o + \frac{\rho U_w^2}{2} \quad (24.3.7b)$$

Solving for the change in pressure across the rotor yields

$$p_R^+ - p_R^- = \Delta p_R = \frac{\rho(U_o^2 - U_w^2)}{2} \quad (24.3.8)$$

The force on the rotor (the thrust) is the pressure difference across the rotor times the rotor area:

$$\Delta p_R A_R = T = \frac{\rho A_R (U_o^2 - U_w^2)}{2} \quad (24.3.9)$$

The thrust can be eliminated between Equations 24.3.5 and 24.3.9 to determine the velocity at the rotor,  $U_R$ .

$$U_R = \frac{U_o + U_w}{2} \quad (24.3.10)$$

It is convenient to introduce the **axial induction factor**  $a$  as the fractional reduction of the wind velocity at the rotor,

$$a = \frac{U_o - U_R}{U_o} \quad (24.3.11)$$

so that eliminating  $U_R$  from the previous two equations yields

$$U_w = U_o(1 - 2a) \quad (24.3.12)$$

The power of the turbine is the thrust times the velocity at the rotor:

$$P = T U_R \quad (24.3.13)$$

Substituting into this equation the thrust from Equation 24.3.9 and the velocity at the rotor from Equation 24.3.10 yields

$$P = \frac{\rho A_R}{2} (U_o^2 - U_w^2) \frac{U_o + U_w}{2} \quad (24.3.14)$$

Eliminating  $U_w$  between Equations 24.3.12 and 24.3.14 expresses the power in terms of the free stream velocity and the axial induction factor:

$$P = 4a(1 - a)^2 \frac{\rho A_R U_o^3}{2} \quad (24.3.15)$$

It is convenient to define the turbine power coefficient as the ratio of the turbine power to the power of the wind so that for this ideal Betz turbine  $C_p$  is given as

$$C_p \equiv \frac{P}{\rho A_R U_o^3 / 2} = 4a(1 - a)^2 \quad (24.3.16)$$

The maximum value of the ideal power coefficient is found by differentiating the power coefficient with respect to  $a$  and setting the derivative to zero.

$$\frac{dC_p}{da} = \frac{d(4a - 8a^2 + 4a^3)}{da} = 4 - 16a + 12a^2 = 0 \quad (24.3.17)$$

Equation 24.3.17 has two solutions:  $a = 1$  and  $a = \frac{1}{3}$ . With  $a = 1$ ,  $C_p$  is at its minimum value of zero. So, the maximum value of  $C_p$  occurs with  $a = \frac{1}{3}$ :

$$C_{p,\max} = 4 \times \frac{1}{3} \times \left(1 - \frac{1}{3}\right)^2 = \frac{16}{27} = 0.593 \quad (24.3.18)$$

This maximum value of the power coefficient is called the Betz limit; no turbine can extract more than 59.3% of the power of the wind.

The thrust coefficient of a wind turbine is defined as

$$C_T \equiv \frac{\text{drag}}{\text{force of wind}} = \frac{T}{\rho A_R U_o^2 / 2} \quad (24.3.19)$$

The power is the thrust times the wind velocity at the rotor so that from Equation 24.3.15 the thrust can be expressed as

$$T = \frac{\rho A_R U_o^3}{2U_R} 4a(1 - a)^2 \quad (24.3.20)$$

Substituting Equation 24.3.20 into 24.3.19 yields


$$C_T = \frac{U_o}{U_R} 4a(1 - a)^2 = 4a(1 - a) \quad (24.3.21)$$

Since both  $C_T$  and  $C_p$  are related only to  $a$ , it is possible to eliminate  $a$  to find a relationship between the two coefficients:


$$C_p = C_T \left( \frac{1}{2} \pm \sqrt{1 - C_T} \right) \quad (24.3.22)$$

So if one coefficient for this ideal wind turbine is known, the other is also known. Figures 24.3.2(a) and (b) show the relationship between the three variables. From Equation 24.3.12 it is clear that  $a$  cannot exceed 0.5 (otherwise the wake velocity would be negative).

Real wind turbines have a rotating wake. In 1976 Wilson et al. [as reported by Manwell et al. (2002)] refined the Betz model to include wake rotation. The results are shown in Figure 24.3.3 in terms of the ratio of the turbine tip velocity to the undisturbed air velocity.



(a)




(b)

**Figure 24.3.2** (a) Relationship of both  $C_T$  and  $C_p$  with axial induction factor, (b) Relationship between  $C_T$  and  $C_p$ .

As this ratio increases, the power coefficient approaches the Betz limit. Also shown in this figure are power coefficients for a variety of different wind turbines.

### Example 24.3.1

Consider a location where the wind speed is 10 m/s, the pressure is 1 atm, and the ambient temperature is 15°C. A large wind turbine has a diameter of 120 m: (a) What is the wind power density? (b) What is the maximum turbine power? (c) At maximum efficiency what



**Figure 24.3.3** Power coefficient for various turbine designs. Adapted from El-Wakil (1984).

is the force required to hold the turbine in place? (d) What is a reasonable estimate for the maximum output of a real turbine?

### Solution

The air density is  $1.225 \text{ kg/m}^3$ . The wind power density is the wind power per unit of wind area:

$$\frac{P}{A} = \frac{\rho U^3}{2} = \frac{1.225 \times 10^3}{2} = 613 \text{ W/m}^2$$

The maximum turbine power is at the Betz limit:

$$\begin{aligned} P_{\text{Betz}} &= \frac{C_{p,\text{Betz}} \rho A U^3}{2} = \frac{0.593 \times 1.225 \times \pi \times (120^2/4) \times 10^3}{2} \\ &= 4.11 \text{ MW} \end{aligned}$$

The thrust is found from Equations 24.3.19 and 24.3.21 with  $a = \frac{1}{3}$ :

$$\begin{aligned} T &= \frac{C_T \rho A U^2}{2} = \frac{4a(1-a)\rho A U^2}{2} \\ &= \frac{4}{3} \times \frac{2}{3} \times 1.225 \times \frac{\pi \times 120^2}{4} \times \frac{10^2}{2} = 616 \text{ kN} \end{aligned}$$

A reasonable power coefficient from Figure 24.3.3 for the high-speed two-blade turbine is 0.46:

$$P_{\text{real}} = P_{\text{Betz}} \frac{C_{p,\text{real}}}{C_{p,\text{Betz}}} = 4.11 \frac{0.46}{0.593} = 3.19 \text{ MW}$$

■

## 24.4 ESTIMATING WIND TURBINE AVERAGE POWER AND ENERGY PRODUCTION


The previous two sections provide sufficient information to predict the performance of an isolated wind turbine if the wind speed data are available and if the turbine power curve or power coefficient is known. Here “isolated” means that the turbine is not part of a wind farm and is not located near hills or buildings where the wakes of nearby obstructions must be considered. At a given wind speed the power output of a wind turbine of area  $A$  is equal to the wind power times the turbine power coefficient times the combined efficiency of the drive train and generator,  $\eta$ :

$$P = \eta P_T = \frac{\eta \rho A C_p U^3}{2} \quad (24.4.1)$$

The average power output is obtained by summing the power over all of the available data:

$$\bar{P} = \frac{\eta}{N} \sum_{i=1}^N P_{T,i} = \frac{A\eta}{2N} \sum_{i=1}^n \rho_i C_{p,i} U_i^3 \quad (24.4.2)$$

where the efficiency  $\eta$  is assumed to be a constant. The computation involved in evaluating Equation 24.4.2 is significant since one year of measured data are usually not sufficient to estimate future turbine output. The method of bins can be used to reduce the computation. The wind duration curve shown Figure 24.2.5 can be divided into  $N$  time duration bins of equal size, as shown in Figure 24.4.1. It is not necessary to use equal-sized bins; the number of bins and size of each bin need to be chosen such that the bin data adequately



**Figure 24.4.1** Madison wind duration curve divided into 10 equal fraction bins.

represent the shape of the velocity distribution curve.<sup>2</sup> The average power using the bin data is

$$\bar{P} = \eta \bar{\rho} \sum_{i=1}^N f_i P_{T,i} = \frac{A \eta \bar{\rho}}{2} \sum_{i=1}^N f_i C_{p,i} U_i^3 \quad (24.4.3)$$

where  $f_i$  is the fraction in bin  $i$  and  $N$  is the number of bins. Since density data are lost when forming the bins, the average density must be estimated (two-dimensional bins of density and velocity can be generated from the data). The limiting case of an ideal Betz turbine can be used to illustrate the process.

### Example 24.4.1

An ideal Betz turbine with a rotor diameter of 34 m is installed on a 40-m-high tower in Madison, Wisconsin. The mechanical and generator efficiency is constant at 90%. The turbine is located far from any obstacles or hills. What is the estimated average power and energy?

#### Solution

From Figure 24.4.1 ten equal-sized fractional bins with centers at fractions of 0.05, 0.15, ..., 0.95 have representative reference wind speeds of 0.95, 1.79, 2.44, 3.03, 3.63, 4.25, 4.93, 5.74, 6.81, and 8.73 m/s. The average air density for Madison is 1.22 kg/m<sup>3</sup> (see discussion just above Equation 24.2.3). For a Betz turbine the power coefficient is a constant at 0.593. Since the wind data were taken at a reference height of 10 m, it is necessary to extrapolate the velocity data to a height of 40 m using Equation 24.2.4 with a  $\frac{1}{7}$  exponent. Equation 24.4.3 becomes

$$\begin{aligned} \bar{P}_w &= \frac{A \eta \bar{\rho} f C_p}{2} \sum_{i=1}^{10} \left[ U_{i,\text{ref}} \left( \frac{Z_{\text{lower}}}{Z_{\text{ref}}} \right)^{1/7} \right]^3 \\ &= \frac{\pi \times 34^2 \times 0.9 \times 1.22 \times 0.1 \times 0.593}{4 \times 2} \left( \frac{40}{10} \right)^{3/7} \sum_{i=1}^{10} U_{i,\text{ref}}^3 = 53.5 \sum_{i=1}^{10} U_{i,\text{ref}}^3 \\ &= 78.3 \text{ kW} \end{aligned}$$

The annual energy production is the average power times the number of hours in the year, or  $78.3 \times 8760 = 686$  MWh. If 100 bins are used instead of only 10, the average power is 87.4 kW and the annual energy is 766 MWh, both about 10% higher. Using more than 100 bins does not change the results. ■

An alternative approach to using the time series or bin data is to use the Weibull statistical representation of the wind. The average power of the wind turbine can be calculated from

<sup>2</sup>The bin data can be obtained directly from the original time series data by counting the number of times the wind speed is between speed  $i$  and speed  $i + 1$ . The counts in each bin divided by the total number of counts is the fraction in the bin.

the integral form of Equation 24.4.2:

$$\bar{P} = \int_0^{\infty} \eta P_T p(U) dU = \frac{A\bar{\rho}}{2} \int_0^{\infty} \eta C_p U^3 p(U) dU \quad (24.4.4)$$

where the average density has been used since it is unlikely that the variation of density with wind speed would be known. The efficiency  $\eta$  may be a function of wind speed. The probability density function for the Weibull distribution is given by Equation 24.2.7. The power coefficient is also a function of wind speed except for the limiting case of an ideal Betz turbine. For this special case of a Betz turbine the integral can be evaluated analytically (see Equation 24.2.13), so that

$$\bar{P}_{\text{Betz}} = \frac{A\bar{\rho}\eta C_{p,\text{Betz}}}{2} \int_0^{\infty} U^3 p(U) dU = \frac{A\bar{\rho}\eta C_{p,\text{Betz}} \bar{U}^3}{2} = \frac{A\bar{\rho}\eta C_{p,\text{Betz}} c^3 \Gamma(1 + 3/k)}{2} \quad (24.4.5)$$

### Example 24.4.2

Repeat Example 24.4.1 but use the Weibull distribution for the wind velocity. At a height of 10 m in Madison the average wind speed is 4.27 m/s and the standard deviation is 2.41 m/s.

#### Solution

The Weibull parameters at 40 m need to be found from the average and standard deviation at 10 m. Both the average wind velocity and the standard deviation of the wind velocity can be modified with the  $\frac{1}{7}$  power law:  $(40/10)^{1/7} = 1.219$ . At a height of 40 m the average wind speed is  $1.219 \times 4.27 = 5.21$  m/s and the standard deviation is  $1.219 \times 2.41 = 2.94$  m/s. With this wind speed and standard deviation the Weibull parameters  $c$  and  $k$  are found to be 5.864 and 1.837 from the simultaneous solution to Equations 24.2.9 and 24.2.10 (the program EES was used to solve these equations). Substituting values into Equation 24.4.5 yields

$$\bar{P}_{\text{Betz}} = \frac{\pi \times 34^2 \times 1.22 \times 0.9 \times 0.593 \times 5.864^3 \times \Gamma(1 + 3/1.837)}{4 \times 2} = 87.4 \text{ kW}$$


which is the same as the result of Example 24.4.1 when 100 bins are used. ■

Real turbines have to contend with low and high wind speeds. If the wind speed is too low, the turbine cannot operate, and if it is too high, the mechanical loads may be extreme and cause damage to the turbine or tower. A typical turbine power curve is shown in Figure 24.4.2. For this 255-kW machine the cut-in wind speed is 8 m/s and the cut-out wind speed 22 m/s. The following example illustrates how a turbine power curve along with the statistical description of the wind can be used to estimate the annual average power and the annual energy production.

### Example 24.4.3

The turbine shown in Figure 24.4.2 has a rotor area of 300 m<sup>2</sup> with the hub located at a height of 30 m. At this height the average wind speed is 8.1 m/s with a standard deviation





**Figure 24.4.2** Typical wind turbine power curve showing cut-in and cut-out wind speeds and control for high wind speeds.

of 3.5 m/s. The power as a function of wind speed is represented by the data in the table. Together the mechanical and electrical efficiency is 0.89. Estimate the average annual power output.

$U$ , m/s	Power, kW	$U$ , m/s	Power, kW
8	5.4	14	199.3
9	27.6	15	221.8
10	60.3	16	237.6
11	97.9	17	247.9
12	135.7	18	255.0
13	170.3	22	255.0

### **Solution**

Although not necessary it is convenient to fit a polynomial to the turbine power data. Using EES, a fourth-order curve fit through the data points from 8 to 18 m/s is given by

$$P_T = 1274.57 - 460.48U + 56.849U^2 - 2.7724U^3 + 0.047808U^4$$

where  $P_T$  is in kilowatts. The wind power in kilowatts at a velocity  $U$  is given by

$$P_w = \frac{\rho AU^3}{2000}$$


where the average density is assumed to be  $1.225 \text{ kg/m}^3$ . The turbine power coefficient (from Equation 24.3.16, the definition of  $C_p$ ) for wind speeds between 8 and 18 m/s is then

$$\begin{aligned} C_p &= \frac{2000 P_T}{\rho A U^3} \\ &= \frac{2000}{1.225 \times 300} \left( \frac{1274.57}{U^3} - \frac{460.48}{U^2} + \frac{56.849}{U} - 2.7724 + 0.047808U \right) \\ &= \frac{6936.4}{U^3} - \frac{2506}{U^2} + \frac{309.38}{U} - 15.09 + 0.2602U \end{aligned}$$

and for the range from 18 m/s to the cutoff speed of 22 m/s it is

$$C_p = \frac{P_{T,\max}}{\rho A U^3 / 2} = \frac{2 \times 255000}{1.225 \times 300 \times U^3} = \frac{1388}{U^3}$$

The power coefficient versus velocity is plotted in the figure:



The annual average power output is found from Equation 24.4.4 modified for the conditions of this problem:

$$\bar{P} = \frac{A \bar{\rho} \eta}{2} \int_8^{22} C_p U^3 p(U) dU$$

where the probability density function  $p(U)$  is given by Equation 24.2.7. This integral is easily evaluated using EES. Because the power coefficient is not a continuous function, it is convenient to write an EES function to determine the power coefficient over the whole range from 8 to 22 m/s. Also, the determination of the Weibull parameters  $c$  and  $k$  is done in an EES subroutine that can be reused in other problems. The following EES code is used to evaluate the above integral:

```

Subprogram Find_CK_(U_bar, sigma : c, k)
  U_bar=c*gamma_(1+1/k)
  sigma^2=U_bar^2*(gamma_(1+2/k)/gamma_(1+1/k)^2-1)
End Find_CK

Function C_p_(U)
  If ((U<8) or (U>22)) then
    C_p_= 0
  Else
    If U<18 then
      C_p_=6936.4 [(m/s)^3]/U^3-2506 [(m/s)^2]/U^2+309.38 [(m/s)]/U-15.09+0.2602 [(m/s)^-1]*U
    Else
      C_p_=1388 [(m/s)^3]/U^3
    Endif
  EndIf
End Function C_p

''Knowns''
rho=1.225[kg/m^3]; A=300[m^2]; eta=0.89; sigma=3.5[m/s]; U_bar=8.1 [m/s]

''Find Weibull c and k''
Call Find_CK_(U_bar, Sigma: c, k)

p=(k/c)*(U/c)^(k-1)*exp(-(U/c)^k) ''Weibull probability density function''

''Integrate from 8 to 22 m/s''
P_bar=(A*rho*eta)/2*integral(C_p_(U)*U^3*p, U, 8[m/s],22[m/s])*Convert(W, kW)

```

The resulting average power is 40.9 kW. ■

The previous example used data for the whole year to estimate average power. If the average wind speed and standard deviation are known for a time period, such as the local utility's peak hours (e.g., 10 AM to 9 PM), then the calculations can be done in exactly the same way to predict the average power in the peak hours. With these data it is also possible to estimate the fraction of the time during the peak period that the wind speed is below the cut-in velocity. Information on when a wind machine will operate is important in estimating the value of wind-generated electricity. Most utilities pay substantially more for electricity during on-peak periods than during off-peak periods.

## 24.5 SUMMARY

This short chapter barely touches on many of the important aspects of producing electrical/mechanical energy from the wind. This chapter concentrated on how to estimate annual energy production from an isolated turbine located in an area with no hills or other obstacles to disturb the wind. The reader is encouraged to study the books by Freris (1990) and Manwell et al. (2002) for a much more detailed discussion of all aspects of wind power.

## REFERENCES

- Aspliden, C. I., D. L. Elliot, and L. L. Wendell, in *Physical Climatology for Solar and Wind Energy* (R. Gussi and C. G. Justus, eds.), World Scientific, Teaneck NJ (1988). "Resource Assessment Methods, Siting and Performance Evaluation."
- Eldridge, F. R., *Wind Machines*, 2nd ed., Van Nostrand Reinhold, New York (1980).
- El-Wakil, M. M., *Powerplant Technology*, McGraw-Hill, New York (1984).
- Freris, L. L., *Wind Energy Conversion Systems*, Prentice-Hall International, London (1990).
- Manwell, J. F., J. G. McGowan, and A. L. Rogers, *Wind Energy Explained; Theory, Design and Application*, Wiley, West Sussex, England (2002).

## Problems

The problems below are arranged by chapters. Most of them have quantitative answers. A few of them are descriptive. They are selected to be representative of interesting and significant problem types; many of them can be rearranged or broadened in scope to provide a wider range of problem-solving experience. In many of the chapters the last problem is comprehensive and requires the use of a computer program such as Engineering Equation Solver (EES). In all problems time is assumed to be solar time unless otherwise stated.

Chapter problems that are identified with a leading letter S require running or constructing some part or all parts of a solar simulation program. These problems can be solved using a high-level programming language such as BASIC, FORTRAN, Pascal, etc. Spreadsheets such as Excel can sometimes be used. However, EES is recommended and is available to academic institutions at a reasonable cost from F-Chart Software, LLC (see [fchart.com](http://fchart.com)) or for free from McGraw-Hill if certain textbooks are adopted for use in other courses—see <http://www.mhhe.com/engcs/mech/ees/na.html>. The EES solar functions library (SETP.LIB) is used whenever convenient. This EES library can be downloaded for free from [fchart.com](http://fchart.com) under EES “Additional Items.” The S problems associated with the Introduction use the free simulation program CombiSys and are used to illustrate solar system behavior prior to the detailed study of subsequent chapters.

### FINDING AND INSTALLING COMBISYS:

1. Use a browser and search for <Wiley “Solar Engineering of Thermal Processes”>. The Wiley website for the 4th edition of this book has information on how to download the program CombiSys.
2. Download the file CombiSys.zip from the Wiley website. Place the file in a folder of your choosing. Here it is assumed the folder is C:\CombiSys.
3. Right click on the ZIP file and choose to extract to this folder.
4. The directory C:\CombiSys should contain two files (CombiSys.exe and CombiSys.trd) and six folders (Data, Doc, Exe, Img, Out, and Weather).
5. To run CombiSys, double click on C:\CombiSys\CombiSys.exe and then click “OK.”
6. A dialog box will come up asking which file should be opened. Choose CombiSys.trd (make sure to look in the folder C:\CombiSys) and a window describing the default system will open. This is a read-only file so if changes are

made it is necessary to save the file with a new name. The file CombiSys.trd cannot be saved in this directory.

7. The various system options should be self-explanatory. Help is available by clicking on the question marks. The program is run by either pressing the F8 key or by choosing “Calculate” from the TRNSYS menu.

## THE SYSTEM

The *collectors* are either single-cover flat-plate liquid heaters, similar to those shown in Figures 6.1.1 and 6.3.1, or evacuated-tubular collectors similar to those shown in Figures 6.13.1(d–f). The collectors are mounted flush on the building [in a manner similar to that in Figure 13.2.5(b) and (c)]. The total roof area suitable for collectors is 75 m<sup>2</sup>. The collectors can face any direction. If collectors are selected from a list, then three performance levels are available for each of the two collector types: low, average, and high. Collector details can also be specified so that it is possible to model any collector with known performance characteristics.

The *collector-tank heat exchanger* isolates the antifreeze solution in the collector loop from the water storage-tank loop. The heat exchanger can be located outside the tank or inside the tank. Not shown are pumps and controllers. One pump and controller is needed for an internal heat exchanger and two pumps and two controllers are required for an external heat exchanger. If antifreeze is not needed, then tank water can be circulated to the collectors and a heat exchanger is not needed. In this case the heat exchanger effectiveness should be set to 1.0.

The *main storage tank* is an insulated tank that is sized in proportion to the collector area. Typical values range from 30 to 100 liters/m<sup>2</sup>. Whenever solar energy heats the upper portion of the tank above the specified maximum tank temperature, then energy is “dumped” by turning off the collector pump.

The *domestic hot-water* (DHW) subsystem consists of a heat exchanger in the main storage tank (not shown) and an auxiliary heater. Mains water enters the in-tank heat exchanger and is heated to the maximum tank temperature (i.e., a perfect heat exchanger). If solar energy heats the domestic hot water above a safe limit (as it probably will in the summer), then a bypass system (not shown) takes main water and mixes it with the too-hot water to deliver water at the desired set delivery temperature. The domestic hot-water auxiliary heater supplies energy as needed to maintain the delivery temperature. This auxiliary system can be a conventional hot-water tank or it can be a separate “in-line” heater. In either case it has sufficient capacity to supply all of the domestic hot water energy needs. The hot-water load is specified in terms of liters per person per day times the number of persons.

The *space heating system* can meet the entire space heating load through a combination of solar energy and auxiliary energy. Water is removed from the tank, circulated through a perfect water-to-air load heat exchanger, and returned to the tank. If sufficient solar energy is unavailable, then the house heating auxiliary heater is used to maintain the house at the desired temperature. The house auxiliary heater is large enough to meet the entire house load. The building load is specified in terms of an overall loss coefficient that includes infiltration.

## THE TRANSED INPUT AND DEFAULT VALUES

The TRNSYS program is run from a front-end called TRNSED (pronounced Trans-ed) which accepts inputs in the form of check boxes, radio buttons, pull-down menus, and input boxes. The individual inputs along with the default parameter values (shown in square brackets) are:

### Simulation Period

Month for Simulation Start (Pulldown: January to December) [January]

Day of Month for Simulation Start (Numbers 1–31) [1]

Length of Simulation (Pulldown: one day to one year) [One-Year Simulation]

Simulation Timestep (Pulldown: 1, 5, 10, 15, 30 or 60) [Sixty-Minute Timestep]

### Radiation Calculations

Radiation Data: Pulldown with two choices

- Use Total Horizontal and Beam Normal Radiation
- Use Total Horizontal Radiation Only

Tilted Surface Radiation Mode: Pulldown with four choices

- Isotropic Sky Model (Equation 2.15.1)
- Hay and Davies Model (Equation 2.16.4)
- HDKR Model (Equation 2.16.7)
- Perez Model (Equation 2.16.14)

### Location

City Name (Pulldown with 239 choices of TMY2 weather data) [CO: Pueblo]

Collector Slope (Numbers 0–90) [60°]

Collector Azimuth (Number; facing equator equator = 0°, East = −90°, West = +90°) [0°]

### Solar Collectors Parameter Options

- Select Solar Collector from a List
  - Collector Type (Pulldown: 6 collectors to choose from) [Choose 2nd]
  - Collector Total Area (Numbers 0–75) [30 m<sup>2</sup>]
  - Collector–Storage tank Heat Exchanger Effectiveness (Numbers 0–1) [0.80]
  - Collector Efficiency Equation (Pulldown: Equation 6.17.3 or 6.17.5) [6.17.3]
- Enter Detailed Solar Collector Parameters
  - Collector Total Area (Numbers 0–75) [30 m<sup>2</sup>]
  - Intercept (maximum) Efficiency (Numbers 0–1) [0.80]
  - First-Order Loss Coefficient (Number) [3.5 W/m<sup>2</sup> K]
  - Second-Order Loss Coefficient (Number) [0.013 W/m<sup>2</sup>/K<sup>2</sup>]

Incidence Angle Modifier (IAM) Coefficient  $b_o$  (Number) [0.20]  
 Collector Flow Rate During Tests (Number > 0) [40 kg/h/m<sup>2</sup>]  
 Collector–Storage Heat Exchanger Effectiveness (Numbers 0–1) [0.8]  
 Collector Flow Rate (Number > 0) [40 kg/h/m<sup>2</sup>]  
 Collector Efficiency Equation Mode (Pulldown: 6.17.3 or 6.17.5) [6.17.3]

### Number of Storage Tank Nodes

- 1 Node Storage Tank
- 3 Node Storage Tank
- 5 Node Storage Tank

### Tank Parameters

Tank Volume per Collector Area (Number 10–100) [75 liters/m<sup>2</sup>]  
 Tank Loss Coefficient (Number 0.10–5.0) [1.0 W/m<sup>2</sup> K]  
 Maximum Tank Temperature (Numbers 40–110) [100°C]

### Load Parameters

Two Check boxes to select or unselect:

- ☒ Turn Solar Domestic Hot-Water Load ON
- ☒ Turn Solar Space Heating Load ON

### Domestic Hot-Water Load

Average Hot-Water Draw per Occupant (Number 0–100) [60 liters/day]  
 Number of Occupants (Number 0–50) [5]  
 Main Temperature (Number 0–40) [10°C]

### Space Heating Load

Overall House Heat Loss Coefficient (Number 0–500) [350 W/K]  
 Spacing Heating Setpoint (Number 15–25) [20°C]

### Online Plotter Options

Two Check boxes to select or unselect:

- ☒ Plot Instantaneous Values
- ☒ Plot Integrated Energy

## RUNNING THE SIMULATION

For your first simulation it is suggested that you use the default conditions. You can use this first simulation to become accustomed to the program and understand what it does. The computing time will be very small. You can run the simulation by either pressing the F8

key or by choosing “Calculate” from the TRNSYS menu. If you have made any changes (even if you made a change and then changed it back) you must save the file with a new name. Since the file CombiSys.trd is a read-only file, it cannot be overwritten, but whenever TRNSYS detects that a change has been made, it tries to save the current conditions before running. Trying to save CombiSys.trd will result in an error. It is suggested that you save this first run with the file name MyFirstRun.trd. To identify later runs it is suggested that a name be assigned to each run that describes the situation. For example, if the collector area for the default case is changed to  $50 \text{ m}^2$ , the file name might be DefaultWithArea = 50.trd.

## EXAMINING THE ONLINE PLOTS

The default settings will generate two plots, one of hourly values and one of integrated values. The right mouse button will start and stop the simulation. After the simulation is complete select NO to the question “Exit Online Plotter.” Two tabs will be shown at the bottom to choose either plot. If the simulation had been more than one page in length, then additional tabs at the bottom can be used to move back and forth in time. The plots can be manipulated in a variety of ways. With the integrated plot on the screen, click on the various plot identifiers at the top of the plot—the individual plots should disappear and reappear. With the hourly plot on the screen click near the 100 on the left-hand temperature scale to bring up a Scale Axis window. Choose a maximum of  $120^\circ\text{C}$  with 6 divisions. On the right-hand axis click on the  $1.00\text{E}+5$  and choose a maximum value of  $1.5\text{E}+5$ . A few hours of the collector temperature (TColl) exceed  $120^\circ\text{C}$  during the late summer. With the hourly plot on the screen click and drag the mouse over a thin slice at the beginning of the plot for a blow-up of that region. The scales on the ordinate and abscissa can both be changed. Right click on the largest time on the abscissa and choose 48 with 12 divisions to view the first 2 days. If time does not start at zero, right click on the left-hand smallest time and choose zero. When finished, go to menu item Calculations and choose “Exit Online Plotter.”

## EXAMINING THE ANNUAL OUTPUT

Once the simulation has completed and you have returned to TRNSED, you will find near the bottom of the window “View simulation results.” Left click in this region to display a plot of the solar fraction and the collector efficiency as a function of month. During two summer months the solar system supplies 100% of the load. Numerical values are supplied for five energy terms, integrated over the time of the simulation: the Total System Load (ELoad), which is the sum of the DHW Load and the Space Heating Load, the thermal Tank Losses and the required Auxiliary Energy (EAux) that must be purchased. As will become obvious, the most useful result is the “Simple Yearly Solar Fraction (1-Eaux/ELoad).” The collector efficiency is the ratio of the useful solar energy delivered to the loads divided by the incident solar energy.

## EXAMINING THE DETAILED NUMERICAL OUTPUT

Hourly integrated and monthly integrated energy quantities are available for each simulation. If the simulation ends within a month, the last monthly integrated values are for the completed portion of the last month.



Six output files are listed under the TRNSYS menu Windows/Other files. They can be opened in a simple word processor such as Notepad or in a spreadsheet program such as EXCEL. If the most recent run was for Pueblo, Colorado, and was saved as MyFirstRun.trd, then the six files are named:

Weather\USA-Co-Pueblo.dat

CombiSys.csv

CombiSys\_hourly.csv

MyFirstRun.csv

MyFirstRun\_hourly.csv

Out\Combisys\_sum.tsv.

The weather file contains 8760 values of total horizontal radiation, beam normal radiation, and ambient temperature. This is exactly the same data as found in the file USA-CO=Boulder.dat in the folder C:\Combisys\Weather\. The two files with the name MyFirstRun are identical to the two corresponding files CombiSys.csv and CombiSys\_hourly.csv. Each new run will generate new versions of all six files. If in the TRANSED window you select to open any of these files, they will be opened in Notepad. It is usually more convenient to open .csv files (comma-separated variables) in a spreadsheet program such as EXCEL. All four .csv files are in your CombiSys directory and can be opened in your spreadsheet program. If you have associated .csv files with your spreadsheet program, then all you need to do is select the file you wish to examine.

The file CombiSys.csv (and MyFirstRun.csv) contains monthly integrated results and the file CombiSys\_hourly.csv (and MyFirstRun\_hourly.csv) contains hourly integrated results. If the time step is less than one hour, the quantities in the hourly file will have been integrated over the hour. In these four files the following 11 quantities are provided:

Time: the time at the end of each integrated output step

Delta\_UTank: the change in tank internal energy from the end of the previous Time [kJ]

ESol: the integrated energy transferred across the collector loop heat exchanger [kJ]

EAuxDHW: integrated auxiliary energy needed to meet the hot-water load requirements [kJ]

EAuxHouse: integrated auxiliary energy added to the space to meet heating load requirements [kJ]

ELossTank: the integrated energy loss from the tank (assumed to be in an unheated area of the house) [kJ]

EMains: the integrated energy entering the tank with the water from the mains [kJ]

EDHW: the integrated energy leaving the DHW system [kJ]

EHouse: integrated energy losses from the house [kJ]

EIncSol: the integrated solar radiation incident on the collectors [kJ]

EHorSol: the integrated solar radiation incident on a horizontal surface [kJ]

You will need to add up the monthly or hourly values to obtain yearly values. Annual information of this type, as will be seen later, is essential information in determining the economics of the application.

The last two columns are the solar fraction (SolFrac) and the collector efficiency (EffCol). The solar fraction is equal to  $(1 - (EA_{\text{AuxDhw}} + EA_{\text{AuxHouse}}) / (E_{\text{House}} + ED_{\text{HW}} - EM_{\text{Mains}}))$ . The collector efficiency is equal to  $(ESol / E_{\text{incSol}})$ . Note that the annual solar fraction is not equal to the monthly average solar fraction.

## INTRODUCTION

### S0.1 Running Combisys

You are to write a brief report that is intended to inform the home owner about the performance of the system and the effects of changes in the major design variables on system performance. The usual performance figure is the solar fraction,  $\mathcal{F}$ , defined as the ratio of the solar contribution to the load divided by the load. Note that due to losses from the tank the solar contribution to the load is not  $ESol$ . The major design variables are the collector area, which cannot exceed  $75 \text{ m}^2$  (suggestion, use 0, 25, 50, and  $75 \text{ m}^2$ ), the storage unit size relative to the collector area, which can be 50, 75, or  $100 \text{ liters/m}^2$ , and the collector slope, which can vary between  $30^\circ$  and  $75^\circ$  (suggestion, use  $30^\circ$ ,  $45^\circ$ ,  $60^\circ$ , and  $75^\circ$ ). CombiSys will not accept a zero collector area, but the results of a nonsolar system are easy to calculate. To reduce the number of runs, you can investigate slope and collector area only for the  $75 \text{ liters/m}^2$  storage tank and for an azimuth angle of zero (the azimuth angle is the angle measured east or west of due south in the northern hemisphere and due north in the southern hemisphere). Display your results on a single graph with four plots (one for each slope) of  $\mathcal{F}$  versus the collector area,  $A_c$ .

Estimate how much the homeowner can afford to pay for the solar equipment if the auxiliary energy is (a) natural gas and (b) electricity. Use a simple 10-year analysis (i.e., ignore inflation, the time value of money, and all operating costs other than the fuel costs). Use the cost of gas and electricity from your local utility. The fuel savings are then  $10 \times C_F \times (\text{auxiliary energy with out solar} - \text{auxiliary energy with solar})$  where  $C_F$  is the cost of fuel per unit of auxiliary energy.

### S0.2 Impact of Collector Type

For the default parameters in CombiSys, investigate the financial impact of selecting different solar collectors. Using the simple 10-year analysis of problem S0.1, estimate how much the homeowner can afford to pay for the system using each of the six different solar collector choices if auxiliary energy costs  $\$40/\text{GJ}$ . Based only on this economic analysis, make a suggestion to the homeowner as to which collector he should choose. Note that there will be an economic optimum collector area that is different for each collector type. Finding the economic collector area is covered in Chapter 11.

### S0.3 Impact of Heat Exchanger Effectiveness

Heat exchanger costs increase with increasing effectiveness. Plot the solar fraction  $\mathcal{F}$  (defined in Problem S0.1) as a function of heat exchanger effectiveness ( $\varepsilon$ ) ranging from 0.1 to 1. Using the simple 10-year economic analysis of problem S0.1, estimate how much the homeowner can afford to pay for the solar system with a perfect heat exchangers

( $\varepsilon = 1$ ). Assume that as the heat exchanger effectiveness is reduced the rest of the solar system does not change. Plot the difference between the system cost with  $\varepsilon = 1$  and the system cost with reduced effectiveness as a function of  $\varepsilon$ . Provide an explanation of the graph for the homeowner.

### S0.4 Impact of Integration Time Step

The CombiSys program solves a set of algebraic and differential equations. For thermal systems the development of the equations is covered in the first 11 chapters of the text. The differential equations in CombiSys are solved using a modified Euler method described in Section 19.4 and used in Problem S0.5. The choice of the integration time step will have a significant impact on simulation time and may also impact on the accuracy of the results. Weather data is seldom available on time intervals of less than one hour, so one hour is often used in solar system simulations. The CombiSys program provides a choice of time steps ranging from one minute to one hour. Since hourly weather data is being used, assumptions must be made to estimate the solar radiation between two successive hourly values. CombiSys assumes that the solar radiation is constant for the hour preceding each recorded value. With the CombiSys default system running in Madison, Wisconsin, what time step do you recommend?

### S0.5 Numerical Solution to an Ordinary Differential Equation (ODE)

The form of the differential equation(s) for the tank temperature ( $T$ ) as a function of time ( $t$ ) solved in CombiSys is

$$\frac{dT}{dt} = A - BT$$

where  $A$  and  $B$  are known functions of time and temperature (like historical weather data, sun position, and collector characteristics). For this problem assume  $A$  and  $B$  are both constant at  $A = 3$  and  $B = 2$  and the initial condition is  $T(t = 0) = 0$ . Calculate and plot the analytical solution and the numerical solutions using Euler, backward Euler, and modified Euler (the average of Euler and backward Euler) integration over an appropriate range of  $t$ . If you are using EES, then use the Parametric Table for your solution. You will want to use the EES functions TableValue and TableRun#. On one graph plot the three solutions using a step size of 1.0 and on another graph plot the three solutions using a step size of 0.1.

### S0.6 Tolerances in Solving Ordinary Differential Equations

TRYSYS (and therefore CombiSys) uses an iterative method to solve the system of algebraic and differential equations. Run CombiSys using the default parameter set. Perform an energy balance on the main solar tank for the entire year (Energy in – Energy out – Energy Stored = Error). The error is due to numerical tolerances in solving the simultaneous equations. Express the error as a percentage of the required energy for the house and the domestic hot water, that is,  $\%error = 100 * \text{EnergyError} / \text{EnergyRequired}$ . Note that the percent error should be very small. The tolerances used in TRNSYS could have been a part of the TRANSED input screen, but the casual user would not have

any idea as to a reasonable choice. Make a copy of CombiSys.trd and name the copy TolCheck.trd. Open TolCheck.trd in a simple text editor like Notepad and search for the word “Tolerance” where you will find two tolerance values (one is for integration tolerance and the other for algebraic equation tolerance—without a good reason to do otherwise, the two numbers can be the same). These numbers can be changed, the file saved, and then run. Simultaneously change the two values over the range from 1 to  $1\text{e-}6$  (i.e., 1, 0.1, 0.001, . . . , 0.000001), run CombiSys, and reevaluate the error. What conclusions can you draw from your results?

## CHAPTER 1

- 1.1 From the diameter and effective surface temperature of the sun, estimate the rate at which it emits energy. What fraction of this emitted energy is intercepted by the earth? Estimate the solar constant, given the mean earth-sun distance.
- 1.2 What would be the “solar constant” for Venus? Mean Venus-sun distance is 0.72 times the mean earth-sun distance. Assume the sun to be a blackbody emitter at 5777 K.
- 1.3 What fraction of the extraterrestrial radiation is at wavelengths below  $0.5\ \mu\text{m}$ ?  $2\ \mu\text{m}$ ? What fraction is included in the wavelength range  $0.5$  to  $2.0\ \mu\text{m}$ ?
- 1.4 Divide the extraterrestrial solar spectrum into 10 equal increments of energy. Specify a characteristic wavelength for each increment.
- 1.5 Calculate the angle of incidence of the beam solar radiation at 1400 (2 PM) solar time on February 10 at latitude  $43.3^\circ$  on surfaces of the following orientations:
  - a Horizontal
  - b Sloped to south at  $60^\circ$
  - c Slope of  $60^\circ$ , facing  $40^\circ$  west of south
  - d Vertical, facing south
  - e Vertical, facing west
- 1.6
  - a When it is 2 PM Mountain Standard Time (MST) on February 3 in North Platte, NE ( $L = 101^\circ\text{ W}$ ,  $\phi = 41.1^\circ\text{ N}$ ), what is the solar time?
  - b When it is 2 PM MST in Boise, ID ( $L = 116^\circ\text{ W}$ ,  $\phi = 43.6^\circ\text{ N}$ ), on February 3, what is the solar time?
  - c What Eastern Daylight Time corresponds to solar noon on July 31 for Portland, ME ( $L = 70.5^\circ\text{ W}$ ,  $\phi = 43.7^\circ\text{ N}$ )?
  - d What Central Daylight Time corresponds to 10:00 AM on July 31 for Iron Mountain, MI ( $L = 90^\circ\text{ W}$ ,  $\phi = 45.8^\circ\text{ N}$ )?
- 1.7 Determine the sunset hour angle and day length for Madison and for Miami for the following dates: **a** January 1, **b** March 22, **c** July 1, **d** mean day of February.
- 1.8 A concentrating collector is located at  $\phi = 27^\circ$  and is rotated about a single axis so as to always minimize the angle of incidence of beam radiation on it. On April 5, at solar times of 9 AM and noon, calculate the angle of incidence:
  - a If the axis is horizontal and east-west
  - b If the axis is horizontal and north-south
  - c If the axis is parallel to the earth’s axis

- 1.9** Estimate  $R_b$  for a collector at Madison ( $\phi = 43^\circ$ ):
- Sloped  $60^\circ$  from horizontal, with  $\gamma = 0^\circ$ , at 2:30 solar time on March 5
  - Sloped  $45^\circ$ , with surface azimuth angle of  $15^\circ$ , at 10:30 solar time on March 5
- 1.10** For Minneapolis ( $\phi = 45^\circ$ ) on February 8:
- What is  $H_o$ ?
  - For the month, what is  $\overline{H_o}$ ?
  - What is  $I_o$  for the hour ending at 11:00 AM on the 8th?
- 1.11** A window on a building in Kansas City faces  $15^\circ$  west of south. An “ell” of the building is 10 ft away from the east edge of the window and projects out 20.2 ft from the plane of the window. If the vertical dimension of the edge of the ell is large compared to that of the window, plot the times of day at which the east edge of the window will start to receive beam radiation as a function of the time of year.
- 1.12** An overhang over a south-facing window has dimensions as follows (see Figure 14.4.1):  $G = 0.25$  m,  $H = 1.75$  m,  $W = 3.25$  m,  $P = 0.75$  m,  $E_L = E_R = 0.50$  m.
- For a location at  $\phi = 35^\circ$  for a point at the middle of the window, plot a shading diagram.
  - Will this point receive beam radiation at 1 PM solar time on February 16? At 3 PM on July 17? At 5 PM on August 16?
- 1.13** For February 16 (the average day for February from Table 1.6.1) in Pueblo, CO:
- What is the day length and the sunrise hour angle?
  - What is the declination? Is it significantly different at sunrise and sunset?
  - How does theta, the angle of incidence of beam radiation, vary through the day for a surface sloped to the south as the slope varies? Show plots of theta versus slope.
  - For a collector slope of  $60^\circ$ , show a plot of  $R_b$  versus time of day.
  - What is the extraterrestrial radiation on a horizontal surface for this day?
  - How does  $I_o$  vary through this day?
  - For the hour 10 to 11 AM (solar time), how much of the extraterrestrial horizontal solar radiation is in a wavelength range of 0.640 to 1.100  $\mu\text{m}$ ? Express the result as a fraction of the total and as energy in watts per square meter.
  - At 10 AM solar time, what is the local clock time?

## CHAPTER 1

- S1.1** Extraterrestrial radiation on a tilted surface.
- Write a program to calculate the extraterrestrial radiation in  $\text{kWh/m}^2$  on a surface of any orientation, location, day, and hour. What is the extraterrestrial radiation incident on a surface located at latitude  $45^\circ$ , longitude  $90^\circ$ , slope  $40^\circ$ , and azimuth  $15^\circ$  at 11:00 hours?

- S1.2** Variation of extraterrestrial radiation over a year.  
Develop a program to plot the monthly average daily total extraterrestrial radiation ( $\text{kWh/m}^2$ ) on a surface of any orientation and any latitude between  $\pm 60^\circ$ . Use the 12 average days listed in Table 1.6.1. For latitude  $43^\circ$  (Madison, WI) plot the monthly average daily radiation on a surface with a slope of  $60^\circ$  and an azimuth angle of  $30^\circ$ .
- S1.3** Annual extraterrestrial radiation on a tilted surface.  
Develop a computer program to calculate the 8760 hourly values of the extraterrestrial radiation on a fixed surface of any orientation and location. For latitude  $43^\circ$  (Madison, WI) what slope and azimuth angles maximize the annual incident extraterrestrial radiation?
- S1.4** Annual extraterrestrial radiation on a one-axis tracking surfaces.  
For any location, write a computer program to calculate the annual extraterrestrial radiation on surface of any slope that rotates on a vertical axis.
- S1.5** Solar position diagram  
Use EES (or another convenient program) to generate solar position diagrams like Figure 1.9.1 for any latitude.

## CHAPTER 2

- 2.1**    **a** For the clear day illustrated in Figure 2.5.1, determine the hourly and daily solar radiation on a horizontal surface.  
      **b** For the cloudy day illustrated in Figure 2.5.1, determine the hourly and daily solar radiation on a horizontal surface.
- 2.2** Do Problem 1.4 for a typical terrestrial distribution.
- 2.3** Estimate the monthly average radiation on a horizontal surface in January and June in Madison, starting with the average hours of sunshine data from Table 2.7.1. Compare the result with data from Appendix D.
- 2.4**    **a** Solar radiation on a horizontal surface integrated over the hour 11 to 12 PM on January 9 at Boulder, CO ( $\phi = 40^\circ$ ) is  $402 \text{ kJ/m}^2$ . What is the clearness index  $k_T$  for that hour? Estimate the fraction of the hour's radiation that is diffuse.  
      **b** Solar radiation on a horizontal surface integrated over the day of January 9 at Boulder ( $\phi = 40^\circ$ ) is  $4.48 \text{ MJ/m}^2$ . What is the clearness index  $K_T$  for that day? What is the estimated fraction of the day's energy that is diffuse?
- 2.5** The monthly average daily solar radiation on a horizontal surface in Lander, WY ( $\phi = 42.8^\circ$ ) is  $18.9 \text{ MJ/m}^2$  in March. How much of this is beam and how much is diffuse?
- 2.6** For Madison,  $43^\circ \text{ N}$ , on January 20, the total radiation on a horizontal surface is  $8.0 \text{ MJ/m}^2$ .  
      **a** Estimate the total horizontal radiation for 10 to 11.  
      **b** Estimate the beam and diffuse radiation for 10 to 11.  
      For a surface sloped  $60^\circ$  to the south:  
      **c** What is  $R_b$  for that hour?

- d If all radiation is treated as beam, what is total radiation on the tilted surface  $I_T$  for that hour?
  - e If the diffuse and ground-reflected radiation together are considered to be independent of orientation, what is  $I_T$  for that hour?
  - f If the diffuse radiation is uniform over sky and ground reflectance is considered, what is  $I_T$  for that hour? Let  $\rho_g$  be 0.2 (bare ground) and 0.7 (snow).
  - g If the Hay and Davies model is assumed, with circumsolar diffuse added to the beam radiation, what is  $I_T$  for that hour? Let  $\rho_g$  be 0.2 (bare ground) and 0.7 (snow).
  - h If the HDKR model is assumed, accounting for circumsolar diffuse and horizon brightening, what is  $I_T$  for that hour? Let  $\rho_g$  be 0.2 (bare ground) and 0.7 (snow).
  - i If the Perez model is assumed, what is  $I_T$  for that hour? Let  $\rho_g$  be 0.2 (bare ground) and 0.7 (snow).
- 2.7 The day's radiation on a horizontal surface in Madison ( $\phi = 43^\circ$ ) on December 22 is  $8.80 \text{ MJ/m}^2$ . There is a fresh snow cover. For the hour 11 to 12, estimate the diffuse radiation, the ground-reflected radiation, and the total radiation on a south-facing vertical surface.
- 2.8 Estimate the average daily radiation in March on a surface sloped  $35^\circ$  to the south for Albuquerque:
- a Using the Liu and Jordan model
  - b Using the Klein-Theilacker method
- 2.9 For Albuquerque, plot the monthly average daily radiation as a function of month for collectors with the following orientations: Assume ground reflectance is 0.2 for all months.
- a Horizontal surface
  - South-facing:
  - b Collector tilt of  $20^\circ$
  - c Collector tilt equal to latitude ( $35^\circ$ )
  - d Collector tilt of  $50^\circ$
  - e Vertical collector
- 2.10 A window faces south at a location with latitude  $36^\circ$ . Estimate the January average radiation on the window if  $\overline{K}_T$  for the month is 0.47.
- 2.11 For Madison in October, for a south-facing surface sloped at  $58^\circ$ , estimate  $\overline{R}$  and  $\overline{H}_T$ . What assumptions have you made?
- 2.12 Estimate the monthly average daily radiation incident on a south-facing vertical surface in July in Madison. Take the ground reflectance as 0.2.
- a Using Equation 2.19.2
  - b Using Equation 2.20.4
- 2.13 Estimate the standard clear-sky (i.e., 23-km-visibility) beam and diffuse radiation on a horizontal surface for December 23 for Minneapolis ( $\phi = 45^\circ$ , elevation 432 m) for each of the hours from sunrise to noon.

- 2.14** Estimate the hourly beam radiation on the aperture of a collector which rotates continuously about a horizontal north-south axis so as to track the sun. The database is measurements of normal-incidence radiation measured with a pyrheliometer and integrated over the hour and is indicated in the table. The latitude is  $38^\circ$  and the date is January 7.

Hour	8–9	9–10	10–11	11–12	12–1	1–2	2–3	3–4
$I_{bn}$	0.35	0.70	2.66	3.05	3.30	3.19	1.80	1.42

- 2.15** For Minneapolis ( $\phi = 45^\circ$ ) in February:
- The radiation integrated over the hour from 10:00 to 11:00 on February 8 is  $1.57 \text{ MJ/m}^2$ . What is  $k_T$ ? Estimate  $I_b$  and  $I_d$  for the hour.
  - For February 8, the day's integrated radiation is  $10.80 \text{ MJ/m}^2$ . What are  $k_T$ ,  $H_b$ , and  $H_d$ ?
  - For the month of February, the average daily radiation is  $8.67 \text{ MJ/m}^2$ . What are  $\bar{K}_T$ ,  $\bar{H}_b$ , and  $\bar{H}_d$ ?
- 2.16** On February 8 in Minneapolis, the total radiation for the hour 10:00 to 11:00 is  $1.57 \text{ MJ/m}^2$ . Estimate the beam, diffuse, and ground-reflected radiation and the total radiation on a south-facing surface having a slope of  $60^\circ$ :
- By the Liu and Jordan model
  - By the HDKR model
  - By the Perez model
- 2.17** For the circumstances of Problem 2.16, estimate the beam radiation on a surface that is rotated continuously about a horizontal north-south axis so as to minimize the angle of incidence of the beam radiation.
- 2.18** For Madison, with  $\gamma = 0^\circ$ ,  $\beta = 60^\circ$ , and with  $\rho_g$  for the 12 months of 0.7, 0.7, 0.4, 0.2, 0.2, 0.2, 0.2, 0.2, 0.2, 0.4, and 0.7, estimate monthly  $\bar{H}_T$  values and their three parts.
- 2.19** A building in Springfield, IL, has a south-facing vertical surface that is designed to absorb solar radiation. Calculate the monthly radiation on the surface and the three components of the radiation
- Using the Liu and Jordan method
  - Using the Klein and Theilacker method
- Use the following values for ground reflectance for the 12 months, starting with January: 0.7, 0.7, 0.4, 0.2, 0.2, 0.2, 0.2, 0.2, 0.2, 0.2, 0.4, 0.7.
- 2.20** A south facing window is 2.1 m high and 4.2 m long. A horizontal diffuse reflector is placed in front of the window. It is hinged at the bottom edge of the window so that when raised to a vertical position against the window it just covers the window. During daylight hours, the reflector is lowered to its horizontal position. Radiation data for an hour are  $I = 1.61 \text{ MJ/m}^2$ ,  $I_d = 0.33 \text{ MJ/m}^2$ ,  $I_b = 1.28 \text{ MJ/m}^2$ , and  $R_b = 2.31$ .
- If the (diffuse) reflectance of the reflector is 0.85, what will be the total radiation per unit area on the window?
  - If the diffuse reflectance drops to 0.7, what will be the total radiation per unit area on the window?



- 2.21** A cylindrical concentrator like that shown in Figure 7.9.1 is installed at latitude  $40^\circ$ . The date is February 20. Radiation for two hour-long periods is shown in the table.

Hour	$I_{bn}$ , MJ/m <sup>2</sup>
11–12	2.31
3–4	1.67

- a** If the collector is rotated about a horizontal east-west axis to minimize the angle of incidence of beam radiation on the aperture, what is the estimated beam radiation on the aperture for each hour?
- b** If the collector is rotated on a horizontal north-south axis, what is the estimated beam radiation on the aperture for each hour?
- 2.22** A south-facing window is on a building at Blue Hill, MA. For the month of January, the critical radiation level is  $0.72 \text{ MJ/m}^2$  (based on an indoor temperature of  $20^\circ\text{C}$  and an outdoor temperature of  $-1^\circ\text{C}$ ). The average January solar radiation on a vertical surface at Blue Hill is 1.52, 1.15, and  $0.68 \text{ MJ/m}^2$  for the hour pairs centered at 0.5, 1.5, and 2.5 h from solar noon. Use Figure 2.22.3 to calculate the utilizable energy.
- 2.23** A collector with  $\beta = 60^\circ$  and  $\gamma = 0^\circ$  is located at Madison. The critical radiation level is  $536 \text{ W/m}^2$ . For the month of February, for the hour-pair 10 to 11 and 1 to 2, what is the utilizability? What is the utilizable energy?  
If the loss coefficient of the collector is reduced to 60% of the stated value (i.e., the critical radiation level is reduced to  $322 \text{ W/m}^2$ ), what are the utilizability and the utilizable energy? (See Appendix D for data. Assume  $\rho_g = 0.60$ .)
- 2.24** A collector is used in a swimming pool heating system at latitude  $34^\circ \text{ S}$  and is sloped  $20^\circ$  to the north. For the month of December the average daily radiation on a horizontal surface is  $28.7 \text{ MJ/m}^2$ . The critical radiation level for the collector for this month in this application is  $124 \text{ W/m}^2$ . Calculate the daily utilizability and the month's utilizable energy.
- 2.25** Using the shading plane concept calculate the beam and estimate the total radiation incident on a window 2 m high and 3 m long located 0.5 m below an infinitely long horizontal overhang with a projection of 0.7 m. The latitude is  $38^\circ$ , the window faces south, and the hour is 1 to 2 p.m. The normal beam radiation is  $800 \text{ W/m}^2$ . Do the calculation for **a** January 17 and **b** April 15.
- 2.26** For a south-facing surface in Pueblo, CO (longitude =  $104^\circ 48'$ ), on February 16, the hour-by-hour radiation on a horizontal surface,  $I$ , the normal beam radiation,  $I_{bn}$ , and the ambient temperature,  $T_{\text{amb}}$ , are given in the table. The time is solar time at the local standard meridian ( $105^\circ$ ). The ground reflectance is 0.4.

Time (h)	$I$ (Wh/m <sup>2</sup> )	$I_{bn}$ (Wh/m <sup>2</sup> )	$T_{amb}$ (°C)
7–8	72	254	2.8
8–9	218	377	5.4
9–10	406	741	8.0
10–11	503	705	10.6
11–12	478	490	12.1
12–13	637	853	13.5
13–14	440	485	15.0
14–15	463	739	14.8
15–16	330	756	14.6
16–17	166	738	14.4

For the hour 10 to 11, for a slope of 60° to the south:

- a What is  $k_T$ ?
- b What is  $I_T$  in kilojoules per square meter? What are the beam, diffuse, and ground-reflected components of  $I_T$  in megajoules per square meter?
- c Estimate  $I_{bn}$  from  $I$  and compare the values with those given in the table. Use your estimated value of  $I_{bn}$  and estimate  $I_T$ . Compare to the value obtained in part b.
- d For the day, plot  $I_o$  and  $k_T$  versus time.
- e For slopes of 30°, 45°, 60°, and 75°, plot  $I_T$  versus time. Use the Liu and Jordan method with  $I_d$  estimated as in part c.
- f If the selection of slope is based on maximizing incident radiation (as we will see, this is not necessarily the correct basis), what slope would you select for this day? What would you think might be the answer to this question if a summer's day had been used in the calculations?
- g What are  $H$ ,  $K_T$ , and  $H_o$ ?
- h Calculate  $\overline{H_T}$  and its components for a slope of 60°.
- i What is  $\overline{H_T}$  and what are its components for the month of February at a slope of 60°? The monthly average radiation for February is 13.30 MJ/m<sup>2</sup>. Use the Liu and Jordan method.

## CHAPTER 2

- S2.1 Air mass 1.5 beam normal plus circumsolar spectral data.  
From the Internet find and download air mass 1.5 solar spectral data (search for ASTM G-173 for a free download). For the three energy bands 0.20 to 0.25, 0.50 to 0.55, and 0.70 to 0.75 of table 2.6.1 verify that these bands in the downloaded data each contain 5% of the total.
- S2.2 Read and write a TMY3 weather data file.  
The weather data available in the simulation program CombiSys is a reduced set of TMY2 data and consists of 239 U.S. locations each with three columns and 8760 lines (representing local standard time). The first column is the total

solar radiation on a horizontal surface for the preceding hour ( $\text{Wh/m}^2$ ), the second is the beam normal solar radiation for the preceding hour ( $\text{Wh/m}^2$ ), and the third is the average ambient temperature ( $^{\circ}\text{C}$ ) for the preceding hour. Download Madison, WI, TMY3 data from the Internet (Search the NREL website for both the data and the user's manual). Use EES to read the hourly TMY3 data and produce a data file that is compatible with the CombiSys program. Name the file USA-WI-MadisonTMY3.dat and copy this file into your CombiSys/Weather folder. In the folder CombiSys/Data folder you will find the file Cities.dat. Each row contains nine elements separated by commas (this format is called a CSV file for Comma Separated Variables). The nine elements are the row number, a text string of State:CityName, latitude, longitude, difference between standard longitude and actual longitude, elevation above sea level [m], the average annual temperature (not used in CombiSys), the US WBAN identification number, and the relative Folder\File Name of the weather data. Modify this file by first copying the line for Madison, WI, and then pasting the copy just below the original line. For the new line change the city name from USA-WI-Madison to USA-WI-MadisonTMY3. Renumber the remaining lines so that there are a total of 240 cities. Change the first line from 239 to 240. Run the CombiSys default system using both TMY2 and TMY3 data and comment on the observed differences.

### S2.3 Hourly radiation on a tilted surface.

Run the CombiSys default parameter set for the first day of January (using the default time step of one hour). For the hour 11 to 12 verify the CombiSys estimate of the radiation incident on the plane of the collector. Start with the beam normal and total horizontal radiation found in the TMY2 data. Note that the reported measured radiation for local standard time hour 12 is the integrated value from 11 to 12. For this analysis assume the radiation is constant from 11 to 12. Perform all calculations at the local solar time corresponding to the local standard time of 11:30.

### S2.4 Calculation of solar radiation on a tilted surface.

Use EES and the HDKR solar radiation processing method (Equation 2.16.7) to calculate the hourly incident solar radiation on a surface of any orientation using the Madison, WI, TMY3 data file produced in Problem S2.2. For the first day in January compare your hourly results with the results from using CombiSys with TMY3 data. Sum the hourly radiation to determine the 12 monthly totals. Compare your results with the values obtained using CombiSys (using a one-hour time step). Note that the time basis of the data is standard time, but all calculations will need to be done in solar time. So, for example, you will need to convert two adjacent hours, say 10 and 11, to solar time, do the calculations at the midpoint of the solar time hour, and then report the results for 11. Complications arise during hours that contain either sunrise or sunset. For an hour that contains sunrise the reported data is the integrated value from sunrise to the first hour with data. An appropriate solar time must be chosen to do the calculations. If the midpoint of the solar time hour is used to do the calculations, the time may be before sunrise and the governing equations will yield nonsense. Two choices are apparent: use the midpoint between sunrise

and the end of the hour or use the time of the first reported data. Since there is little usable solar energy available in the early hour, making an error will have little impact on the final result. Similar arguments can be made for hours that contain sunset. Making measurements near sunrise and sunset is fraught with difficulty. For example, cloud reflections can increase the measurements such that the recorded value exceeds the extraterrestrial value. CombiSys reports the number of times this happens in the file CombiSys.LST.

- S2.5** Estimate beam and diffuse radiation.  
Repeat Problem S2.4 but modify your program to use *only* the reported global horizontal radiation. That is, from the hourly global horizontal radiation estimate the hourly direct normal and hourly horizontal diffuse radiation using Equation 2.10.1. Compare the annual solar fraction results with the results of Problem S2.4.
- S2.6** Impact of weather data.  
Discuss the use of Madison, WI, TMY2 data versus TMY3 data (see Problem S2.2) for predicting system performance using the default parameter set of CombiSys. Are your conclusions for Madison useful for other locations? Compare the Madison, WI, weather data provided in Appendix D with the TMY2 and TMY3 data.
- S2.7** Impact of system orientation.  
For the default parameter set in CombiSys determine the collector slope that maximizes solar fraction,  $\mathcal{F}$ . For this optimum slope investigate the impact on solar fraction when the collector azimuth angle varies between  $\pm 90^\circ$ .
- S2.8** Impact of system location.  
Repeat Problem S2.7 for Albuquerque, NM, and Portland, OR. With the Madison, WI, results these three cities cover the range of climates from sunny (Albuquerque), partly cloudy (Madison), and overcast (Portland). What general conclusions can you draw from these results?
- S2.9** Impact of radiation processor model.  
Using the four different radiation processor algorithms offered in CombiSys and the default parameter set, what general conclusions can you draw (at least for the default city) from these results?
- S2.10** Calculate utilizability:  
For a south-facing surface in Madison, WI, tilted up at  $45^\circ$ , calculate the 12 monthly average daily utilizability values ( $\bar{\phi}$ ) for a critical radiation level  $I_{Tc}$  equal to  $145 \text{ W/m}^2$ . Compare the results with Equation 2.24.4. Show the results on a plot of the two values of  $\bar{\phi}$  as a function of month.

## CHAPTER 3

- 3.1** Verify the values of the blackbody spectral emissive power shown in Figure 3.4.1 for  
**a**  $T = 1000 \text{ K}$  and  $\lambda = 10 \mu\text{m}$ ; **b**  $T = 400 \text{ K}$  and  $\lambda = 5 \mu\text{m}$ ; and **c**  $T = 6000 \text{ K}$  and  $\lambda = \mu\text{m}$ .

- 3.2** What is the percentage of the blackbody radiation from a source at 300 K in the wavelength region from 8 to 14  $\mu\text{m}$ ? (This is the so-called window in the earth's atmosphere.)
- 3.3** Write a computer subroutine to calculate the fraction of the energy from a blackbody source at  $T$  in the wavelength interval  $a$  to  $b$ .
- 3.4** Calculate the energy transfer per unit area by radiation between two large parallel flat plates. The temperature and emittance of one plate are 500 K and 0.45 and for the other plate are 300 K and 0.2. What is the radiation heat transfer coefficient?
- 3.5** Calculate an overall heat loss coefficient for a plate at 50°C, facing up, when exposed to an ambient temperature of 10°C. The plate emittance is 0.88, the dew point is 3°C, and the wind heat transfer coefficient is 25 W/m<sup>2</sup> °C. Assume time is midnight.
- 3.6** Consider two large flat plates spaced  $l$  mm apart. One plate is at 100°C and the other is at 50°C. Determine the convective heat transfer between the plates for the following conditions:
- a** Horizontal, heat flow up,  $l = 20$  mm
  - b** Horizontal, heat flow up,  $l = 50$  mm
  - c** Inclined at 45°, heat flow up,  $l = 20$  mm
- 3.7** Compute the equilibrium temperature of a thin, polished copper plate 1 m  $\times$  1 m  $\times$  1 mm under the following conditions:
- a** In earth orbit, with solar radiation normal to a side of the plate. Neglect the influence of the earth. See Table 4.7.1.
  - b** Just above the earth's surface, with solar radiation normal to the plate and the sun directly overhead. See Table 4.7.1.

Assume the following: the sky is clear and transmits 0.80 of the solar radiation, the equivalent blackbody sky temperature is 10°C less than the ambient temperature, the ambient air temperature is 25°C, the wind heat transfer coefficient is 23 W/m<sup>2</sup> °C, and the earth's surface is effectively a blackbody at 15°C.

- 3.8** Consider two thin circular disks thermally isolated from each other and suspended horizontally side by side in the same plane inside a glass sphere on low-conductance mounts. The sphere is filled with an inert gas, such as dry nitrogen, to prevent deterioration of the surfaces. The dimensions of the disks are identical. One disk is painted with black paint ( $\alpha_b = 0.95$ ,  $\varepsilon_b = 0.95$ ) and the other with white paint ( $\alpha_w = 0.35$ ,  $\varepsilon_w = 0.95$ ). The glass has a transmittance for solar radiation  $\tau_c$  of 0.90 and an emittance for long-wave radiation of 0.88. The convection coefficient  $h$  between each of the disks and the glass cover is 16 W/m<sup>2</sup> °C. (Note that the disks have two sides and that the edges can be neglected.) When exposed to an unknown solar radiation on a horizontal surface  $G$ , the temperature of the white disks,  $T_w$ , is 5°C and the temperature of the black disc,  $T_b$ , is 15°C.  $T_a = 0^\circ\text{C}$ .
- a** Write the energy balances for the black and white disks assuming the glass cover is at a uniform temperature  $T_c$ .

- b** Derive an expression for the combined convection and radiation heat transfer coefficient.
  - c** Using the result of part b, derive an expression giving the incident solar radiation as a function of the difference in temperature between the black and white disks.
  - d** What is the incident solar radiation  $G$  for the conditions stated?
- 3.9** Determine the convection heat transfer between two large flat plates (covers in a collector) separated by a distance of 20 mm and inclined at an angle of  $60^\circ$ . The temperature of the lower plate is  $110^\circ\text{C}$  and that of the upper plate is at  $60^\circ\text{C}$ .
- 3.10** What is the convective heat transfer for the conditions of Problem 3.9 when a slat-type honeycomb is inserted in the space between the plates? The slat spacing is 10 mm.
- 3.11** Determine the heat transfer coefficient for air flowing by forced convection in a 1-m-wide, 2-m-long, 15-mm-deep channel. The flow rate is 0.012 kg/s. What is the heat transfer coefficient if the plate spacing is halved? What is the heat transfer coefficient if the mass flow rate is doubled?  $T_{\text{air}} = 25^\circ\text{C}$ .
- 3.12** Estimate the pressure drop in a pebble bed with  $3 \times 4$  m flow area and with 2 m flow length. The flow rate through the bed is 1.1 kg/s. The pebbles are 0.02-m-diameter river-washed gravel with a void fraction of 0.45. Use an average air temperature of  $40^\circ\text{C}$ .
- 3.13** Estimate the rock diameter required for a pressure drop of 55 Pa for the conditions of Problem 3.12. Assume the pebble void fraction remains at 0.45 for all pebble sizes.
- 3.14** A flat-plate collector with one cover is inclined at a slope of  $50^\circ$  from the horizontal. The plate temperature is  $100^\circ\text{C}$  and its emittance is 0.10. The cover temperature is  $31.5^\circ\text{C}$ , and the (glass) cover has an emittance of 0.88. The plate-cover spacing is 25 mm.
  - a** Calculate the radiative transfer from plate to cover.
  - b** Calculate a radiation heat transfer coefficient from plate to cover.
  - c** Calculate the convective transfer from plate to cover.
  - d** Given an effective surrounding temperature of  $10^\circ\text{C}$ , estimate the net radiative exchange between the cover and the surroundings.
- 3.15** The ambient temperature around the collector in Problem 3.14 is  $10^\circ\text{C}$ , and the wind speed is 5.0 m/s. Estimate the wind coefficient  $h_w$ :
  - a** If the collector is free standing and has dimensions  $2.5 \times 10$  m.
  - b** If the collector is flush mounted on a building with a volume of  $564 \text{ m}^3$ .
- 3.16** A counterflow heat exchanger has water entering one side at a rate of 3.75 kg/s and a temperature of  $49^\circ\text{C}$ . Glycol enters the other side at a variable flow rate and a temperature of  $65^\circ\text{C}$ . The  $C_p$  of the glycol is  $3780 \text{ J/kg }^\circ\text{C}$ . The  $UA$  of the exchanger is  $2.10 \times 10^5 \text{ W/}^\circ\text{C}$ . What are the outlet temperatures of the two streams as functions of the glycol flow rate?
- 3.17** In the design of a solar collector it is necessary to estimate the heat transfer from the hot absorber plate to the ambient. Consider a single glass-covered

collector with an absorber plate having an emittance of 0.2, a temperature of  $85^{\circ}\text{C}$ , and a plate-to-cover spacing of 30 mm. Assume the collector is mounted on a roof with a slope of  $60^{\circ}$  with a wind heat transfer coefficient of  $7\text{ W/m}^2\text{ K}$ . The ambient air and sky temperatures are both  $15^{\circ}\text{C}$ .

- a Estimate the heat loss from this collector per unit area.
- b How does the overall loss coefficient  $U[U(T_{\text{plate}} - T_{\text{amb}}) = q]$  vary with plate temperature?
- c What energy transfers are we neglecting in this analysis of a collector?

## CHAPTER 3

### S3.1 Evaluate the Stefan-Boltzmann constant.

Numerically integrate Equation 3.5.1 (with Equation 3.4.1 substituted for  $E_{\lambda b}$ ) to determine the numerical value of  $\sigma$ . Hint: change the integration variable from  $\lambda$  to  $\lambda T$ .

### S3.2 Verify Table 3.6.1a.

Develop a computer program to numerically integrate Equation 3.6.3 and use the program to verify a few entries in Table 3.6.1a.

### S3.3 Sky temperature throughout a day.

Develop a computer program to calculate and plot the equivalent sky temperature as a function of time (0 to 24 h) for the first 24 h of the CombiSys default city (i.e., Pueblo, Colorado). Assume the humidity ratio (mass of water vapor per mass of dry air) remains constant throughout the day at the value found for the first hour if the relative humidity in that first hour is 60%.

### S3.4 Radiation exchange from collector to ground and sky.

Equation 3.8.3 can be used to estimate the radiation exchange between a collector at a slope  $\beta$  that faces both the ground and the sky. The view factor from a collector to the ground is given by  $(1 - \cos(\beta))/2$ . Assume the collector cover surface is at  $60^{\circ}\text{C}$  with an emittance of 0.88 and the ground is at  $25^{\circ}\text{C}$  with an emittance of 0.96. What is the hour-by-hour thermal radiation loss throughout the day described in Problem S3.3?

### S3.5 Heat transfer between two concentric cylinders.

For two concentric horizontal cylinders of  $D_o = 50\text{ mm}$  and  $D_i = 30\text{ mm}$  plot the ratio  $k_{\text{eff}}/k$  as a function of air pressure (think about an appropriate pressure scale between 2 atm and a perfect vacuum) at mean air temperatures of 100, 200, and  $300^{\circ}\text{C}$ . Use the curve-fitting option in EES to generate a polynomial expression relating  $k_{\text{eff}}/k$  to air pressure and mean air temperature. Curve fits to analytical results can often be used to reduce simulation computation time.

### S3.6 Convection heat loss from a single-cover flat-plate collector.

Solar collectors are typically tested at a single slope. Changing the collector slope can have a significant impact on the incident solar radiation and thus on system performance. However, in simulating a solar system's performance the effect of slope on the heat loss from the collector is typically neglected. Typical single-cover flat-plate collectors have an absorber plate-to-cover distance of 25 mm. Investigate the effect of collector slope on the heat loss (both convection

and radiation) from a collector with the absorber plate maintained at 70°C and with an ambient temperature of 25°C. The convection heat transfer coefficient on the outside of the glass cover is 10 W/m<sup>2</sup> °C. The glass and absorber plate infrared emittances are 0.88 and 0.20, respectively. The effective temperature of the sky is given by Equation 3.9.2 with a dew point temperature of 10°C and hours from midnight ( $t$ ) equal to 12.

**S3.7** Relationship between a packed-bed particle parameter and the flow Reynolds number.

A rock bed consisting of screened rocks is often used for energy storage in air-based solar systems. Screened rocks have been passed through screens of various sized openings to obtain rocks of a more-or-less uniform size. Equations 3.16.4 and 3.16.5 both predict pressure drop in packed beds. Equating the pressure drop from these two equations provides a relationship between Reynolds number ( $G_o D/\mu$ ) and a rock parameter  $(1 - \varepsilon)\alpha/\varepsilon^{3/2}$ . Graphically show this relationship.

**S3.8** Heat exchanger effectiveness.

Plot the effectiveness of a counterflow heat exchanger as a function of NTU for an appropriate set of  $C^*$  values.

## CHAPTER 4

**4.1** Consider a surface that has been prepared for use in outer space and has the following spectral characteristics:

$$\rho_\lambda = \begin{cases} 0.10 & \text{for } 0 < \lambda < \lambda_c \text{ } \mu\text{m} \\ 0.90 & \text{for } \lambda_c < \lambda < \infty \text{ } \mu\text{m} \end{cases}$$

For  $\lambda_c$  of 1, 2, and 3  $\mu\text{m}$ , calculate the equilibrium temperature of the plate. Assume the sun can be approximated by a blackbody at 6000 K and that the solar flux on the plate is 1367 W/m<sup>2</sup>. Also assume that the backside of the plate is perfectly insulated.

**4.2** A selective surface for solar collector absorber plates has the characteristics

$$\alpha_\lambda = \varepsilon_\lambda = \begin{cases} 0.95 & \text{for } 0 < \lambda < 1.8 \text{ } \mu\text{m} \\ 0.05 & \text{for } 1.8 < \lambda < \infty \text{ } \mu\text{m} \end{cases}$$

Assume the sun to be a blackbody emitter at 5777 K. Calculate the absorptance of the surface. If the surface is at 150°C, calculate its emittance.

**4.3** For the black chrome surface (after the humidity test) of Figure 4.8.3:

- a** Determine the absorptance for extraterrestrial solar radiation for the surface.
- b** What is the absorptance of the surface for the terrestrial solar radiation distribution of Table 2.6.1?
- c** What is the emittance of the surface at a temperature of 350°C?

**4.4** Estimate the emittance of a surface having characteristics of curve *C* of Figure 4.8.2 if its temperature is **a** 175°C and **b** 30°C.



- 4.5** A surface is designed for use in space. It has wavelength-dependent properties as shown in the table. The surface (on a spacecraft) is at 350 K. Calculate the ratio  $\alpha/\varepsilon$ .

Wavelength Range, $\mu\text{m}$	$\alpha_\lambda$	$\varepsilon_\lambda$
0–0.6	0.80	0.20
0.6–2.6	0.25	0.75
2.6–100	0.10	0.90

- 4.6** The absorptance of the surface of curve  $C$  of Figure 4.8.2 can be assumed to be that for radiation at normal incidence. Assuming that Figure 4.11.1 adequately represents the characteristics of the surface, what is  $\alpha$  at  $30^\circ$ ?  $45^\circ$ ?  $60^\circ$ ?
- 4.7** A collector that is to be used on the Madison, WI, heating system has radiation properties of the absorber plate as given in Figure 4.8.2, curve  $C$ . The collector is expected to deliver most of its output when the absorber surface temperature is about 325 K.

The data range from 0.41 to 25  $\mu\text{m}$ , which is not sufficient for the calculations of this problem. Extend the data down to 0.01  $\mu\text{m}$  by adding a point at 0.01 with the same reflectance value as at 0.41. Extend to 100  $\mu\text{m}$  in the same manner.

- What is the absorptance for solar radiation assuming the sun is a blackbody at 5777 K? Write an EES function called `Planck(lambda, T)` that will evaluate the blackbody energy at a specified wavelength and temperature (Equation 3.4.1). Use the EES integral function and your Planck function to integrate Equation 4.5.1 where  $\varepsilon$  and  $\varepsilon_\lambda$  are replaced by  $\rho$  and  $\rho_\lambda$ . Comment on the differences when you integrate from 0.01 to 100  $\mu\text{m}$  versus integrating from 0.41 to 25  $\mu\text{m}$ .
- Repeat part a but assume the solar radiation is distributed as in Table 2.6.1 (i.e., air mass 2). Use the Insert Modify Array command from the Edit menu to insert the wavelength bands from Table 2.6.1. Find an average  $\rho$  in each band and use Equation 4.6.5 to evaluate the solar absorptance.
- What is the emittance for long-wave radiation at 325 K? Comment on the error associated with extrapolating the data.
- This surface is proposed for use in other collectors that will operate at different temperatures. Plot the emittance versus surface temperature for a range of temperatures from 300 to 800 K. Use the EES curve-fit option under the menu Plots and find a second-order polynomial (in degrees kelvin) that fits your results.

## CHAPTER 4

### S4.1 Spectral radiation data processing.

Develop a computer program to integrate spectral data (Equation 4.5.1) to determine emissivity. Test your program using the spectral data found in the two tables of Example 4.6.1 to determine the absorptance for radiation from a source at 5777 K (effective blackbody temperature of the sun) and the emittance at a temperature of  $450^\circ\text{C}$ .

- S4.2** Material radiation properties as a function of temperature.  
Use a digitizing program (e.g., the free program Engauge Digitizer) to digitize the data of surface *C* of Figure 4.8.2. Plot the solar absorptance and the infrared (IR) emittance of surface *C* for the surface temperature ranging from 0 to 300°C. Develop polynomial approximations for your results.
- S4.3** Spacecraft thermal control.  
Spacecraft passive thermal control experts use radiation properties to control spacecraft temperatures. Consider a flat-plate normal to the sun with the back side perfectly insulated. A surface coating is available that has the properties displayed in Figure 4.8.1 but with the cutoff wavelength being a design variable. What is the equilibrium temperature of the plate (far from earth but at nominal sun-earth distance) as a function of the cutoff wavelength? For simplicity, assume the sun is a blackbody at 5777 K.
- S4.4** More spacecraft thermal control.  
Accurate passive thermal control of spacecraft depends upon having coatings with known and stable thermal radiation properties. Sometimes surfaces are prepared in a pattern of two or three different coatings. As an example from Table 4.7.1 consider gold with solar absorptance of 0.22 and infrared emittance of 0.04 and carbon black paint in acrylic binder with solar absorptance of 0.94 and infrared emittance of 0.83. A surface that is patterned with 60% gold and 40% black paint will have average  $\alpha = 0.6 \times 0.22 + 0.4 \times 0.94 = 0.508$  and average  $\varepsilon = 0.6 \times 0.04 + 0.4 \times 0.83 = 0.356$ . What combination of what surfaces from Table 4.7.1 will produce a temperature of 300 K?

## CHAPTER 5

- 5.1** Calculate the reflectance of one glass surface for angles of incidence of **a** 10°, **b** 30°, **c** 50°, and **d** 70°. The index of refraction is 1.526.
- 5.2** Calculate the transmission of three nonabsorbing glass covers at angles of 10° and 70° and compare your results to Figure 5.1.3.
- 5.3** For glass with  $K = 20 \text{ m}^{-1}$  and 2.0 mm thick, calculate the transmission of two covers: **a** at normal incidence and **b** at 50°.
- 5.4** Calculate the  $(\tau\alpha)$  product for a two-glass-cover collector ( $KL = 0.0370$  per plate) with a flat black collector absorber for radiation incident on the collector at an angle of **a** 25° and **b** 60°.  $\varepsilon_p = 0.96$ .
- 5.5** Estimate the transmittance of a single glass cover with  $KL = 0.0370$  for diffuse radiation from the sky and for radiation reflected from the ground. The slope of the cover is **a** 45° and **b** 90°.
- 5.6** What is the transmittance for solar radiation of a collector cover with index of refraction 1.60 at an angle of incidence of 58°? The cover is 2 mm thick and the extinction coefficient is  $10 \text{ m}^{-1}$ . If the index of refraction is 1.40, what will be the transmittance?
- 5.7** A glass to be used for a cover on a solar collector has  $K = 25 \text{ m}^{-1}$  and is 2.5 mm thick. Solar radiation is incident on the glass at an angle of incidence of 55°.

- a What is the reflectance of a single surface?
  - b What is the transmittance of a single cover?
  - c What is the transmittance of two covers?
  - d For part b, compare the results obtained with the exact method and the approximate method.
- 5.8** Estimate the radiation absorbed by a collector under the following conditions:  $I = 3.0 \text{ MJ/m}^2$ ,  $I_{bT} = 4.1 \text{ MJ/m}^2$ ,  $I_d = 0.4 \text{ MJ/m}^2$ ,  $\theta_{bT} = 25^\circ$ ,  $\beta = 45^\circ$ ;  $\tau$  is given in Figure 5.3.1 for  $KL = 0.037$  and one cover;  $\alpha = 0.93$  and is independent of angle; and ground reflectance is 0.2.
- 5.9** A collector has a single cover of low-iron glass. It is at a latitude of  $48^\circ$  and a slope of  $63^\circ$ . For a particular hour, the angle of incidence of beam radiation on the collector (taken as that at the half-hour point) is  $10.7^\circ$  and the zenith angle is  $71.3^\circ$ .  $I = 1.03 \text{ MJ/m}^2$  and  $I_o = 1.62 \text{ MJ/m}^2$ . Ground reflectance is 0.4. The cover is glass with  $KL = 0.013$ . The absorptance of the plate for total radiation at normal incidence is 0.955, and it has an angular dependence as shown in Figure 4.11.1.
- a What is  $(\tau\alpha)_b$ ?
  - b What is  $(\tau\alpha)_d$ ?
  - c What is  $(\tau\alpha)_g$ ?
  - d Calculate  $S$  for the hour.
- 5.10** A vertical, south-facing collector in Madison has an angular dependence of absorptance as shown in Figure 4.11.1 and  $\alpha_n = 0.93$ . The collector has one cover of low-iron glass with  $KL = 0.013$  per sheet. For the month of January average ground reflectance is estimated to be 0.60. Using the isotropic sky model:
- a What are the three components of absorbed radiation?
  - b What is the total absorbed radiation?
  - c What is the average transmittance-absorptance product?
- 5.11** For the Tedlar cover of Figure 5.7.2, estimate the transmittance for blackbody radiation from a source at **a**  $45^\circ\text{C}$  and **b**  $145^\circ\text{C}$ .
- 5.12** A building in Madison has as part of the south surfaces a collector-storage wall with double glazing ( $KL = 0.0125$  per sheet) and a black absorbing surface behind it that has  $\alpha_n = 0.92$  and an angular dependence as shown in Figure 4.11.1. Calculate the absorbed beam, diffuse, ground-reflected, and total radiation for the month of January. Assume that the ground reflectance averages 0.7 for the month. State any assumptions you make.
- 5.13** The surface to be used as the absorber plate in a collector has a normal-incidence absorptance of 0.85. The collector has a single glass cover of low iron content and  $KL = 0.021$  per sheet. Use the data for January 10 in Boulder from Table 2.5.1. Use Equations 2.10.1 and 2.16.7 in your analysis.
- a Plot  $S$  and  $I_T$  for slopes of  $30^\circ$ ,  $45^\circ$ ,  $60^\circ$ , and  $75^\circ$  as a function of hour angle (four graphs). What are the general trends?
  - b Plot  $(\tau\alpha)_{\text{ave}}$  for the four slopes as a function of hour angle. Can you draw any general conclusions?
  - c It is proposed that the collector design is to be modified by the addition of a second cover. For a slope of  $45^\circ$  compare the absorbed radiation for this

day for the two-cover collector with that of the one-cover collector. What can you speculate about the utility of second cover?

- d** There is also the possibility of using a flat-black absorber surface which has an absorptance at normal incidence of 0.96 and an emittance of 0.86. What effect would use of this surface have on absorbed radiation for the  $45^\circ$  slope?

## CHAPTER 5

### S5.1 Digitize data.

Use a digitizing program (e.g., the free program Engauge Digitizer) to digitize the 0.50%  $\text{Fe}_2\text{O}_3$  curve of Figure 5.7.1. Use this data to verify the results of Example 5.7.1.

### S5.2 Glass extinction coefficient as a function of angle.

The data of Figure 5.7.1 consists of both reflection losses and transmission losses. Use the data obtained in Problem S5.1 and plot the extinction coefficient as a function of wavelength. Assume the glass index of refraction is independent of wavelength at a value of 1.526.

### S5.3 Solar transmittance of glass.

For the data of Problem S5.1, plot the solar radiation transmittance as a function of incidence angle.

### S5.4 The monthly average absorbed solar radiation of Example 5.10.1 uses monthly averages of the horizontal beam and diffuse radiation, the factor $R$ , and the transmittance-absorptance. Reevaluate the results in the table for Springfield, IL, using hour-by-hour calculations.

## CHAPTER 6

### 6.1 Compare the value of $U_t$ calculated with Equation 6.4.9 to the graphs of Figure 6.4.4 at:

- a**  $h_w = 5 \text{ W/m}^2 \text{ }^\circ\text{C}$ ,  $\varepsilon_p = 0.95$ ,  $T_p = 60^\circ\text{C}$ ,  $T_a = 10^\circ\text{C}$ , for two covers  
**b**  $h_w = 20 \text{ W/m}^2 \text{ }^\circ\text{C}$ ,  $\varepsilon_p = 0.1$ ,  $T_p = 100^\circ\text{C}$ ,  $T_a = 40^\circ\text{C}$ , for one cover

### 6.2 Calculate the overall loss coefficient for a flat-plate solar collector located in Madison and sloped toward the equator with a slope equal to the latitude. Assume a single glass cover 25 mm above the absorber plate, a wind speed of 6.5 m/s, an absorber long-wave emittance of 0.11, and 70 mm of rock wool back insulation having a conductivity of $0.034 \text{ W/m }^\circ\text{C}$ . The mean plate temperature is $100^\circ\text{C}$ , and the ambient temperature is $25^\circ\text{C}$ . Neglect edge effects and absorption of solar radiation by the glass. The collectors are mounted flush on the surface of a house having a volume of $300 \text{ m}^3$ . The time is noon and $T_{dp} = 20^\circ\text{C}$ .

### 6.3 **a** Verify the convective heat flows shown in Figure 6.4.3(a) using the convection equations of Section 3.11.

- b** What will be the cover temperature, total loss rate, and individual convection and radiation transfers if a set of convection suppression slats with aspect ratio 0.3 is used between plate and cover?

- 6.4** A flat-plate solar collector has two glass covers, a black absorber with  $\varepsilon_p = 0.95$ , mean plate temperature of  $110^\circ\text{C}$  at an ambient temperature of  $10^\circ\text{C}$ , and a wind loss coefficient of  $10 \text{ W/m}^2 \text{ }^\circ\text{C}$ . Estimate its top loss coefficient. If the back of the collector is insulated with 50 mm of mineral wool insulation of  $k = 0.035 \text{ W/m }^\circ\text{C}$ , what is its overall loss coefficient? (Neglect edge effects.) The slope is  $45^\circ$ . Plate-to-cover and cover-to-cover spacing is 25 mm.
- 6.5** A flat-plate collector has a fin-and-tube-type absorber plate.  $U_L = 8.0 \text{ W/m}^2 \text{ }^\circ\text{C}$ , the plate is 0.5 mm thick, the tube center-to-center distance is 100 mm, and the heat transfer coefficient inside the 20-mm-diameter tubes is  $300 \text{ W/m}^2 \text{ }^\circ\text{C}$ . Bond conductance is high. Calculate the collector efficiency factor  $F'$  for **a** copper fins, **b** aluminum fins, and **c** steel fins. If  $\dot{m}/A_c = 0.012 \text{ kg/m}^2\text{s}$ , what are the corresponding  $F_R$  values?
- 6.6** A flat-plate water heating collector absorber plate is copper 1.00 mm thick. Tubes 10 mm in diameter are spaced 160 mm apart. The collector overall loss coefficient is  $3.0 \text{ W/m}^2 \text{ }^\circ\text{C}$  and the inside heat transfer coefficient is  $300 \text{ W/m}^2 \text{ }^\circ\text{C}$ . The solder bond between the plate and tubes is 5 mm wide and averages 2 mm thick. The solder has a conductivity of  $20 \text{ W/m }^\circ\text{C}$ . What is  $F'$  for the collector?
- 6.7** Derive the  $F'$  expression for the air heater shown in Figure 6.14.1(b). Assume  $U_b$  is negligible.
- 6.8** Estimate the useful output of a solar collector when  $F_R U_L = 6.3 \text{ W/m}^2 \text{ }^\circ\text{C}$ ,  $F_R(\tau\alpha) = 0.83$ ,  $T_i = 56^\circ\text{C}$ ,  $T_a = 14^\circ\text{C}$ , and  $I_T = 3.4 \text{ MJ/m}^2$ .
- 6.9** Calculate  $F'$ ,  $F''$ , and  $F_R$  for an air heater of the type shown in Figure 6.14.1(b) having characteristics as listed. Evaluate all properties at  $70^\circ\text{C}$ .

$A_c = 2 \text{ m}^2$	$T_1 = 100^\circ\text{C}$
$U_L = 5.0 \text{ W/m}^2 \text{ }^\circ\text{C}$	$T_2 = 40^\circ\text{C}$
$\varepsilon_1 = \varepsilon_2 = 0.95$	Air flow rate = $0.028 \text{ kg/s}$
Plate spacing 0.02 m	Length of flow channel 2 m
Cross-sectional area of flow channel $0.02 \text{ m}^2$	

- 6.10** The solar energy absorbed by a solar collector  $S$  and the ambient temperatures are given in the table below. The collector has  $U_L = 5.2 \text{ W/m}^2 \text{ }^\circ\text{C}$  and  $F_R = 0.92$ . Determine the useful output of the collector for the day in question if the inlet temperature is constant at  $35^\circ\text{C}$ .

Hour	$S$ , $\text{MJ/m}^2$	$T_a$ , $^\circ\text{C}$	Hour	$S$ , $\text{MJ/m}^2$	$T_a$ , $^\circ\text{C}$
7–8	0.01	−3	12–1	3.42	9
8–9	0.40	0	1–2	3.21	11
9–10	1.90	4	2–3	1.54	5
10–11	2.85	5	3–4	1.07	1
11–12	3.02	7	4–5	0.52	−4

- 6.11** A “rule of thumb” for solar air heaters is that the air flow rate (at  $20^\circ\text{C}$ ) should be 10 liters/s<sup>2</sup> per square meter of collector area. For an air heater with this flow rate for which  $F' = 0.75$  and  $U_L = 6.0 \text{ W/m}^2 \text{ }^\circ\text{C}$ , calculate  $F_R$ .
- 6.12** A solar water heater, when operating, has  $F_R U_L = 5.5 \text{ W/m}^2 \text{ }^\circ\text{C}$ . In an experiment, the pump is turned off, and the plate temperature is measured to be  $118^\circ\text{C}$ . The pump is then started, with the inlet water at  $30^\circ\text{C}$ . What is the useful gain from the collector if the solar radiation does not change?
- 6.13** Determine the mean plate and fluid temperatures for a water heating collector operating under the following conditions:  $U_L = 4.0 \text{ W/m}^2 \text{ }^\circ\text{C}$ ;  $F' = 0.90$ ;  $\dot{m}/A_c = 0.015 \text{ kg/m}^2 \text{ s}$ ; tube diameter 10 mm; inside heat transfer coefficient  $300 \text{ W/m}^2 \text{ }^\circ\text{C}$ ; inlet temperature  $55^\circ\text{C}$ ; ambient temperature  $15^\circ\text{C}$ ; incident radiation  $1000 \text{ W/m}^2$ ;  $(\tau\alpha)_e = 0.85$ ; dust and shading coefficient 1.5%.
- 6.14** What is the critical radiation level for the circumstances of Problem 6.13?
- 6.15** If the circulating pump in Problem 6.13 were to fail, what would you expect the plate temperature to be? What do you expect would happen to  $U_L$  under these circumstances, and how would it affect an estimate of the plate temperature?
- 6.16** Calculate  $(\tau\alpha)_e$  for diffuse radiation incident on a single-cover selective-surface collector. The absorptance of the plate at normal incidence is 0.9, and the ratio  $\alpha/\alpha_n$  for the surface is as given in Figure 4.11.1. The plate emittance is 0.10. Do the calculation for **a**  $KL = 0.0524$  and **b**  $KL = 0.0125$ .
- 6.17** For November 2 in Madison the total solar radiation on a horizontal surface is  $8.0 \text{ MJ/m}^2$  and the air temperature is  $5^\circ\text{C}$ . At 11:30 AM, estimate the steady-state efficiency and exit temperature of an air heater of the type of Figure 6.14.1(b) with parameters as follows:
- Absorber plate,  $\alpha = 0.95$ ,  $\varepsilon = 0.2$
  - Single glass cover,  $\varepsilon_c = 0.88$ ,  $KL = 0.0125$
  - Wind speed 5 m/s, building volume  $400 \text{ m}^3$
  - Air mass flow rate  $0.016 \text{ kg/m}^2 \text{ s}$
  - Air entering temperature  $38^\circ\text{C}$
  - Plate-to-cover spacing 20 mm
  - Air passage depth 10 mm
  - Collector width 1.3 m
  - Collector length 3 m
  - Polyurethane foam back insulation thickness 60 mm
  - Collector tilt  $53^\circ$  (south facing)
- 6.18** Estimate the energy collection and efficiency of a module of a two-cover water heating flat-plate collector operating at a latitude of  $30^\circ$  in a space heating process. The date is March 11 and the hour is 1500 to 1600. Assume  $T_s = T_a$ ;  $(\tau\alpha)_e = 1.02\tau\alpha$ ; all incident solar is beam radiation. Ignore dust and shading and ignore edge losses. Take  $\rho_g = 0.6$ . The design parameters of the module are as follows:

0.75 m wide, 5 m long

Two glass covers,  $KL = 0.0125$  per cover

Metal plate 1.0 mm thick;  $k = 50 \text{ W/m}^\circ\text{C}$

Tubes are 10 mm diameter on 100-mm centers

$\alpha = 0.95$ , independent of incident angle

Back insulation 80 mm thick;  $k = 0.048 \text{ W/m}^\circ\text{C}$

Water flow rate 0.03 kg/s

Heat transfer coefficient inside risers  $300 \text{ W/m}^2^\circ\text{C}$

Slope from horizontal =  $50^\circ$

Cover spacing = 25 mm

Plate emittance  $\varepsilon_p = 0.95$

For this hour, the operating conditions are as follows:

Solar radiation for the hour on a horizontal surface  $1.40 \text{ MJ/m}^2$

Ambient temperature  $2^\circ\text{C}$

Wind heat transfer coefficient  $10 \text{ W/m}^2^\circ\text{C}$

Temperature of water entering collector  $35^\circ\text{C}$

- 6.19** Estimate the hour-by-hour useful gain and day's efficiency for a flat-plate solar collector located in Boulder, CO, and tilted toward the equator with a slope equal to the latitude. Use the hourly radiation data of January 10 from Table 2.5.1. The collector is the same as that in Problem 6.18 and the inlet water temperature is  $25^\circ\text{C}$ .
- 6.20** In an industrial application for ventilating a paint-spraying operation, ambient air is heated with flat-plate solar air heating collectors. The test results of the air heaters show that  $F_R U_L = 4.0 \text{ W/m}^2^\circ\text{C}$  and  $F_R(\tau\alpha) = 0.61$ . The ambient temperature is  $12^\circ\text{C}$  and the solar radiation incident on the collector is  $665 \text{ W/m}^2$ . Calculate the rate of useful energy collection and the collector efficiency.
- 6.21** Based on Equation 6.7.6, would it be better to have an absorber surface in a one-cover collector with **a**  $\alpha = 0.95$  and  $\varepsilon = 0.20$  or **b**  $\alpha = 0.90$  and  $\varepsilon = 0.10$ ? What is the basis of the choice?
- 6.22** A flat-plate water heating collector has the following characteristics:  
 Plate: copper, 0.026-cm-thick, 15-mm-diameter tubes on 80-mm centers,  $\alpha_n = 0.93$ ,  $\varepsilon = 0.11$ ,  $\dot{m}/A_c = 0.0080 \text{ kg/m}^2 \text{ s}$   
 Covers: one glass,  $KL$  for the cover 0.0125, spaced 25 mm from the plate  
 Insulation on back and edge:  $U_{be} = 0.82 \text{ W/m}^2^\circ\text{C}$   
 Collector orientation:  $60^\circ$  slope to south  
 Conditions of operation:  $T_a = 10^\circ\text{C}$ , wind heat transfer coefficient  $20 \text{ W/m}^2^\circ\text{C}$ ,  $T_i = 35^\circ\text{C}$ ,  $h_{fi} = 300 \text{ W/m}^2^\circ\text{C}$   
 For an hour in which  $I_T = 2.60 \text{ MJ/m}^2$  and the radiation is nearly normal to the plane of the collector, estimate  $Q_u/A$ .

- 6.23** An hour-long collector test gives the results shown in the table. For this collector, what are  $F_R(\tau\alpha)_n$  and  $F_R U_L$ ? The collector area is  $3.0 \text{ m}^2$ .

$Q_u$ , MJ	$I_T$ , MJ/m <sup>2</sup>	$T_{ci}$ , °C	$T_a$ , °C
6.80	3.10	16.0	12.0
1.49	3.22	86.1	12.0

- 6.24** A collector has  $F_R(\tau\alpha) = 0.73$  and  $F_R U_L = 6.08 \text{ W/m}^2 \text{ }^\circ\text{C}$ . When  $T_i = T_a$ , what is the instantaneous efficiency? If the instantaneous efficiency is zero, the ambient temperature is  $30^\circ\text{C}$ , and the inlet temperature is  $150^\circ\text{C}$ , what is the radiation on the collector?
- 6.25** The experimental data in the table are from a standard NBS/ASHRAE test on an air heating collector. The module is  $7.83 \times 4.00 \text{ ft}$  for a gross area of  $31.33 \text{ ft}^2$ . The test flow rate is  $562.5 \text{ lb/h}$ . What are  $F_R(\tau\alpha)_n$  and  $F_R U_L$  (in both English and SI units)?

Run	$I_T$ , Btu/ft <sup>2</sup> h	$T_a$ , °F	$T_{f,i}$ , °F	$T_{f,o}$ , °F
1	303.6	77.39	182.51	197.32
2	308.8	78.78	185.21	199.59
3	317.9	78.74	142.26	167.99
4	317.7	79.30	142.25	166.52
5	285.4	57.73	63.43	99.05
6	312.3	58.69	64.21	103.28
7	317.1	63.02	90.12	123.85
8	306.0	63.59	89.57	121.48

- 6.26** An indoor experimental evaluation of a solar water heating collector produced the data in the table below. The collector has a selective coating with  $\alpha$  of 0.87 to 0.92 and  $\varepsilon$  of 0.10 to 0.20. The single glass cover has  $\tau = 0.92$  at normal incidence. The collector dimensions are  $0.914 \times 2.133 \text{ m}$  overall for a gross area of  $1.95 \text{ m}^2$ . Glass (aperture) area is  $1.76 \text{ m}^2$  and the effective absorber area is  $1.72 \text{ m}^2$ . For all of the data in the table, the wind speed was  $3.4 \text{ m/s}$ . For the conditions of these tests, what are  $F_R(\tau\alpha)$  and  $F_R U_L$  based on gross collector area?

$T_a$ , °C	23.9	24.4	25.0	26.7	26.7	24.4	25.6	26.1
$T_i$ , °C	23.9	24.7	46.1	46.7	52.6	53.0	78.5	78.9
$T_o$ , °C	30.7	32.8	51.4	53.3	57.8	58.9	80.9	82.4
$G_T$ , W/m <sup>2</sup>	789	947	789	947	789	947	789	947
$\dot{m}$ , kg/s	0.0363	0.0385	0.0357	0.0362	0.0357	0.0364	0.0348	0.0359

- 6.27** The water heating collector of Problem 6.26 is to be operated at reduced flow rates. Estimate new values of  $F_R(\tau\alpha)_n$  and  $F_R U_L$  based on the gross collector area for flow rates of **a**  $0.020 \text{ kg/s}$  and **b**  $0.010 \text{ kg/s}$ .



- 6.28** The incidence angle modifier coefficient  $b_o$  is normally found experimentally. However, it is possible to estimate it; this can be useful for accounting for incidence angle effects in simulations. For a one-cover collector with a cover with  $KL = 0.0125$  and  $\alpha_n = 0.93$ , estimate  $b_o$  based on a calculation of  $(\tau\alpha)$  at normal incidence and at  $\theta = 60^\circ$ .
- 6.29** A collector with  $F' = 0.88$ ,  $U_L = 4.0 \text{ W/m}^2 \text{ }^\circ\text{C}$ , and  $(\tau\alpha)_{av} = 0.75$  is operated as a water heater with a flow rate per unit area of  $0.012 \text{ kg/m}^2 \text{ s}$ . Water enters at  $17^\circ\text{C}$ , ambient temperature is  $8^\circ\text{C}$ , and  $I_T$  for the hour is  $2.26 \text{ MJ/m}^2$ . The collector area is  $11.2 \text{ m}^2$ . Calculate  $F_R$ ,  $Q_u$ , and  $\eta$  for the hour.
- 6.30** A liquid heating collector has test data from standard collector tests indicating  $F_R U_L = 4.32 \text{ W/m}^2 \text{ }^\circ\text{C}$  and  $F_R (\tau\alpha)_n = 0.81$  when operated at a flow rate of  $0.012 \text{ kg/m}^2 \text{ s}$ . The heat capacity of the liquid is  $3200 \text{ J/kg }^\circ\text{C}$ . If the flow rate is cut in half, what would be the appropriate values of the two parameters to use in a process design?
- 6.31** Calculations of the performance of a flat-plate collector with one cover and a selective surface show that  $(\tau\alpha)_b$  at 4:30 PM is 0.71. At 4:30, the angle of incidence of beam radiation is  $57^\circ$ . At normal incidence, the absorptance of the plate is 0.93 and the transmittance of the cover is 0.91. Estimate  $b_o$  for this collector. What assumptions do you have to make?
- 6.32** Collector tests produce the following results:  $F_R (\tau\alpha)_n = 0.673$ ,  $F_R U_L = 3.07 \text{ W/m}^2 \text{ }^\circ\text{C}$ , and  $b_o = -0.17$ . This collector operates for a day under the conditions listed in the table. Complete the table.

Hour	$I_T$ , $\text{kJ/m}^2$	$T_a$ , $^\circ\text{C}$	$T_i$ , $^\circ\text{C}$	$\theta_b$	$S$	$Q_u/A_c$	$\eta$
8–9	314	−8.3	31.0	58			
9–10	724	−1.7	29.6	45			
10–11	1809	1.7	27.1	34			
11–12	2299	3.3	30.5	26			
12–1	1926	5.6	35.7	26			
1–2	420	7.2	34.3	34			

From 2 PM on, radiation is negligible. What is  $\eta$  for the day?

- 6.33** For February 16 in Madison, WI, for the hour 11 to 12 the incident horizontal radiation is  $585 \text{ W-h/m}^2$  and the ambient temperature is  $-4.4^\circ\text{C}$ . Assume the sky temperature is equal to the ambient temperature.
- What is the hourly output of the collector ( $\text{MJ/h}$ ) and the outlet fluid temperature ( $^\circ\text{C}$ ), assuming that the water inlet temperature stays constant at  $35^\circ\text{C}$
  - The wind heat transfer coefficient has been assumed to be equal to  $10 \text{ W/m}^2\text{-K}$ . Estimate the impact on not knowing the wind coefficient better than plus or minus 50%
  - The heat transfer coefficient inside the tubes is given as  $436 \text{ W/m}^2 \text{ K}$ . Use this value in your solution. Calculate the actual inside heat transfer coefficient.

- d The plate emittance is assumed to be 0.14. The following equation represents the plate emittance as a function of plate temperature

$$\varepsilon_{\text{plate}} = 0.190014695 - 0.000801244186 * T + 0.0000024152548 * T^2 - 1.29071396E - 09 * T^3$$

where  $T$  is the mean plate temperature in kelvins. Do you expect it will be necessary to account for this variation in the plate emittance in evaluating annual performance?

The collector has the following characteristics:

Ins_back=0.07	[m] back insulation thickness
k_ins=0.0245	[W/m K] polyurethane rigid foam
U_edge=0.098	[W/m <sup>2</sup> K] edge loss coefficient
Space=0.028	[m] plate to cover spacing
slope=45	[deg]
SurfAzAng=0	[deg]
GrRef=0.4	
Tubes=8	number of copper tubes in parallel
Sp_tube=0.115	[m]
L=2.5	[m] length in the flow direction
alpha_n=0.881	solar absorptance of absorber plate
epsilon_plate=0.14	IR emittance of absorber plate
Dia_Tube=0.008	[m] use for both inner and outer diameter
Thick_plate=.0005	[m]
k_plate=385	[W/m <sup>2</sup> K] copper
Flow=0.025	[liter/s] total flow through the collector
KL = 0.021	glass $KL$ product
Refrind=1.526	glass refractive index
C_b=1e6	bond conductance
h_fi=436	[W/m <sup>2</sup> K] heat transfer coefficient inside the tubes
N_cov=1	number of covers
h_w=10	[W/m <sup>2</sup> K] with a plus or minus 5 W/m <sup>2</sup> K uncertainty

## CHAPTER 6

### S6.1 Comparing thermal performance of two collectors.

A house building contractor wishes to evaluate bids from two collector manufacturers for a solar system (as modeled in CombiSys) in Madison, WI. Manufacturer A has offered a collector with  $F_R(\tau\alpha)_n = 0.73$  and  $F_R U_L = 3.41 \text{ W/m}^2 \text{ }^\circ\text{C}$  and manufacturer B has offered a collector with  $F_R(\tau\alpha)_n = 0.80$  and  $F_R U_L = 4.15 \text{ W/m}^2 \text{ }^\circ\text{C}$ . The first order incidence angle modifier for both collectors is  $-0.017$ . If the house overall loss coefficient is  $307 \text{ W/K}$ , which collector would you recommend installing based only on performance?

**S6.2** Analysis of a collector top loss coefficient.

The results of Example 6.4.1 are shown in Figure 6.4.3(a). Write a computer program to verify the results of Example 6.4.1. Use your program to plot the top loss coefficient as a function of absorber plate temperature between 0 and 200°C. Compare your results with Figure 6.4.4(d).

**S6.3** Top loss coefficient for two covers.

Develop a computer program to verify the two-cover results of Figure 6.4.3(c). What would be the top loss coefficient if the two-cover system used argon between the two plates rather than air?

**S6.4** Linear and quadratic collector test results.

Collector tests results are often presented in terms of both a linear fit and a quadratic fit. For a collector with the following two representations, what is the predicted annual solar fraction using the CombiSys default settings with the following collector characteristics?

$$\eta = 0.691 - 3.396P/G_T - 0.01968P^2/G_T \text{ and } K_{\tau\alpha} = 1 - 0.194S - 0.006S^2$$

versus

$$\eta = 0.706 - 4.910P/G_T \text{ and } K_{\tau\alpha} = 1 - 0.20S$$

where

$$P = (T_{in} - T_{amb}) \text{ and } S = 1/\cos\theta$$

Note that in CombiSys the second-order IAM coefficient (i.e., the 0.006 above) has been set to zero and cannot be changed from the TRANSED window. However, if you open a TRD file in a text editor such as Notepad and search for the line B1=0, (not the line \*|# B1=0) you can change the zero to -0.006.

**S6.5** Converting between linear and quadratic test results.

Section 6.19 shows how to convert linear collector parameters between the options of using the inlet temperature and the average temperature,  $T_{av} = (T_{inlet} + T_{out})/2$ . When a second-order loss coefficient is nonzero, there is no exact analytical conversion. For a collector with the following representation using the average fluid temperature:

$$\eta = \eta_0 - a_1 \frac{T_{av} - T_a}{G} - a_2 \frac{(T_{av} - T_a)^2}{G}$$

where  $\eta_0 = 0.69$ ,  $a_1 = 3.5 \text{ [W/m}^2 \text{ °C]}$ , and  $a_2 = 0.015 \text{ [W/m}^2 \text{ °C}^2]$ , estimate the value of the three collector parameters when using the inlet temperature representation. That is, find values of  $F_R(\tau\alpha)_n$ ,  $F_R U_L$ , and  $A_2$  in the following equation:

$$\eta = F_R(\tau\alpha)_n - F_R U_L \frac{T_{inlet} - T_a}{G} - A_2 \frac{(T_{inlet} - T_a)^2}{G}$$

You will need to choose three different operating conditions and solve for the three new parameters. Three convenient operating points are when  $\eta = \eta_0$ ,  $\eta = \eta_0/2$ , and  $\eta = 0$ . Collector tests are typically done at a minimum incident radiation level  $G$  of about  $800 \text{ W/m}^2$ . For this analysis use  $G = 800 \text{ W/m}^2$ .

The collector tests were performed at the manufacturer's specified water flow rate of  $40 \text{ kg/h m}^2$ . Plot the efficiency difference (i.e., the efficiency using  $T_{\text{av}}$  minus the efficiency using  $T_{\text{inlet}}$ ) against  $(T_{\text{inlet}} - T_a)/G$ . The difference should be zero at the three chosen points. Note that this difference is not an error but a difference between two models, neither of which is a perfect representation of collector performance.


**S6.6** Complete collector analysis.

Example 6.24.1 uses an EES computer program to simulate a collector test. Develop an EES program to duplicate these results and verify the results by comparing the two figures in the text with figures generated by your program.


## CHAPTER 7

- 7.1 A concentrating collector is to have a tubular receiver with a plug in it so that the liquid being heated flows through an annulus. The inside and outside diameters of the steel outer tube are 0.054 and 0.059 m, respectively, and the outer diameter of the plug is 0.045 m. The assembly is surrounded by a concentric glass tube cover. A collector module is 0.30 m in aperture width and 3.10 m long with the receiver length equal to the reflector length. The water flow rate through the tube is  $0.0168 \text{ kg/s}$ . If  $U_L = 7.5 \text{ W/m}^2 \text{ }^\circ\text{C}$  (based on the absorbing surface area) and the average fluid temperature is  $100^\circ\text{C}$ , what are  $F'$  and  $F_R$  for this collector?
- 7.2 In Examples 7.3.1 and 7.3.2 the receiver surface has an emittance of 0.31. If a selective surface with the same absorptance but with  $\varepsilon = 0.18$  were to be used, what would be the useful gain from the collector?
- 7.3 A CPC collector array has an acceptance half-angle  $\theta_c$  of  $15^\circ$ . It is oriented along an east-west axis in a fixed position so that the slope of the array is  $60^\circ$ . The application is for heating at a location with latitude  $43^\circ$ . For the hour 10 to 11 on January 26, the radiation on a horizontal plane is  $0.36 \text{ MJ/m}^2$  diffuse and  $1.20 \text{ MJ/m}^2$  beam. The CPC is not truncated. It is covered by a single glass cover with  $KL = 0.0370$ .
  - a Estimate the absorbed radiation if the specular reflectance of the concentrator is 0.85. At normal incidence,  $\alpha = 0.95$  and its angular dependence is as shown in Figure 4.11.1.
  - b Estimate the collector output per unit of aperture area for this hour if  $U_L = 9.0 \text{ W/m}^2 \text{ }^\circ\text{C}$  of absorbing area,  $F_R = 0.92$ , the inlet fluid temperature is  $55^\circ\text{C}$ , and  $T_a = -5^\circ\text{C}$ .
- 7.4 A CPC collector array at a location with  $\phi = 45^\circ$  is sloped at an angle of  $65^\circ$  to the south. The acceptance half-angle of the CPC elements is  $9^\circ$ , and they are truncated to a height-aperture ratio of 2.5. The array is covered with a single glass cover with  $KL = 0.0125$ . The reflectance of the CPC is 0.85. Assume that an average absorptance of the receiver can be taken as 0.88 independent of the angle of incidence. For the hour 10 to 11 the incident beam normal radiation as measured with a pyrheliometer is  $1.13 \text{ MJ/m}^2$  and the diffuse on a horizontal surface  $I_d$  is  $0.37 \text{ MJ/m}^2$ .
  - a On January 2, what would be the absorbed radiation?
  - b On March 15, what would be the absorbed radiation?

- 7.5** A linear parabolic concentrator of width 1.80 m, length 10 m, and focal length 0.92 m is fitted with a flat receiver located in the focal plane. It is arranged to be continuously adjusted about a horizontal north-south axis. The latitude is  $32^\circ$  and the date is March 16. The image in the focal plane, when the beam radiation is normal to aperture, can be approximated as shown on the accompanying figure. The receiver is centered on the centerline of the parabola and is 0.022 m wide and 10.5 m long. The loss coefficient will be very near that of the Suntec collector (Figure 7.13.2). For this receiver  $\tau\alpha = 0.78$  and  $\rho$  of the concentrator is 0.87. Assume  $h_{fi} = 3000 \text{ W/m}^2 \text{ }^\circ\text{C}$ .



- a** Estimate the absorbed energy for the hours 9 to 10 and 11 to 12 for this date if  $I_{bn}$  for the hours are  $2.06$  and  $3.14 \text{ MJ/m}^2$ , respectively.
  - b** If the collector is used to boil water at  $120^\circ\text{C}$ , what will be the energy collected during these hours? The ambient temperatures are  $2$  and  $9^\circ\text{C}$ , respectively.
- 7.6** The mean sun-Venus distance is  $67 \times 10^6$  miles. On Venus, what would be the maximum concentration ratio for **a** a linear concentrator and **b** a circular concentrator.
- 7.7** The accompanying figure shows variation of incidence angle modifier  $K_{\tau\alpha}$  with  $\theta_T$  (the incidence angle in the direction transverse to the tubes) for a CPC array. The efficiency curve measured at near-normal incidence gives  $F_R(\tau\alpha)_n = 0.66$  and  $F_R U_L = 1.23 \text{ W/m}^2 \text{ }^\circ\text{C}$ .



A collector of this type is located at  $\phi = 38^\circ$ , with  $\beta = 40^\circ$  and  $\gamma = 0^\circ$ . The tubes are oriented in the north-south (up-and-down) direction. The data in the table are for March 21. Complete the table, assuming that the conditions of operation are close to those under which the tests were made.

Time	$T_i, ^\circ\text{C}$	$T_a, ^\circ\text{C}$	$G_T, \text{W/m}^2$	$K_{\tau\alpha}$	$Q_u, \text{W/m}^2$
noon	75	20	925		
2 PM	75	22	760		
4 PM	75	22	385		

- 7.8** A linear parabolic concentrator of length of 10 m has an aperture of 1.36 m and a focal length of 1.26 m. It is mounted on a horizontal east-west axis with continuous adjustment to minimize the angle of incidence on the aperture. It is at a latitude of  $35^\circ$ . The date is March 21. The receiver is flat and is located at the focal plane. Assume the sun to be the nonuniform solar disk.
- Determine the size of the receiver to intercept 0.95 of the image at noon solar time for a perfect reflector and for a reflector with a standard deviation of angular error  $\sigma = 0.15^\circ$ .
  - The loss coefficient of the receiver is estimated to be  $14 \text{ W/m}^2 \text{ } ^\circ\text{C}$  based on absorber area,  $F_R$  is 0.9,  $\tau\alpha$  is estimated to be 0.78, and  $\rho$  of the concentrator is 0.87. Estimate  $Q_u$  for this collector at the time indicated in part a if  $\sigma = 0.15^\circ$ ;  $I_{bn} = 2.14 \text{ MJ/m}^2$ ,  $T_i = 230^\circ\text{C}$ , and  $T_a = 7^\circ\text{C}$ .
- 7.9** It has been suggested that a solar-thermal power plant should be based on a concentrator similar to the type shown in Figures 7.15.1 and 17.5.1. Sketch such an arrangement, showing schematically the following dimensions: the distance  $L$  from a flat reflecting element to a spherical receiver of diameter  $D$  and width of flat reflector  $W$ . If the reflector size is limited by wind loading to  $W = 10 \text{ m}$  and if (in a large system)  $L_{\max} = 1 \text{ km}$ , what (in terms of  $D$ ) must be the pointing accuracy of the reflector?

## CHAPTER 7

- S7.1** Concentrating collector heat loss.  
Write a computer program that accepts as input the diameter of a concentrating collector-receiver tube, the emittance of the receiver tube, the diameter of the cover glass, the thickness of the glass, the air pressure inside the annulus, the ambient temperature, the wind speed, and the temperature of the absorber tube. The program should calculate the heat loss to the surroundings. Assume radiation losses to the surroundings are to a blackbody at the ambient temperature.
- S7.2** Nonlinear concentrating collector heat loss.  
For the receiver geometry of Example 7.3.2 plot the overall heat loss coefficient as a function of receiver temperature from 100 to  $400^\circ\text{C}$ . Use the computer program of Problem S7.1 to determine over what temperature range it is reasonable to express the heat loss coefficient as a quadratic function?

**S7.3** Comparison of beam radiation to total radiation.

Concentrating solar collectors with a moderate to high concentration ratio ( $C > 6$ ) do not utilize any of the diffuse radiation. Consequently, cloudy/overcast climates are generally not suitable for concentrating collectors. Write a computer program to sum up the beam and the total radiation on both a horizontal north-south and a horizontal east-west single axis tracking system described in Section 1.7. For Albuquerque, New Mexico, and Sault Sainte Marie, Michigan, determine the ratio of annual incident beam radiation to total incident radiation with the two tracking options.

**S7.4** A general collector equation.

Concentrating solar collector test data is sometimes expressed in a form that is also applicable for flat-plate collectors:

$$\frac{Q}{A_c} = F'(\tau\alpha)_n[K_{\tau\alpha}(\theta_b)G_b + K_{\tau\alpha}(\theta_d)G_d] - (c_1 + c_3u)(T_m - T_a) - c_2(T_m - T_a)^2 + c_4E_{LWR} - c_5\frac{dT_m}{dt} - c_6uG$$

where  $F'$  is the collector efficiency factor and the appropriate temperature is  $T_m = (T_{in} + T_{out})/2$ .  $K_{\tau\alpha}(\theta_b)$  and  $K_{\tau\alpha}(\theta_d)$  are the beam and diffuse incidence modifiers,  $c_1$  through  $c_6$  are empirical constants, and  $u$  is the local wind speed.  $E_{LWR}$  is the net incident infrared radiation on the collector from the ground and sky and is equal to

$$E_{LWR} = \sigma T_a^4 \left( \varepsilon_{sky} \frac{1 + \cos \beta}{2} + \varepsilon_g \frac{1 - \cos \beta}{2} - 1 \right)$$

where the sky emittance  $\varepsilon_{sky}$  is the term in the square brackets in Equation 3.9.2. If the two incident angle modifiers are equal and  $c_2$  through  $c_6$  are zero, then the equation reduces to Equation 6.17.5. If  $c_2$  is nonzero, then the equation reduces to Equation 6.17.7. If wind speed is important, as it is in uncovered collectors, then  $c_3$  and  $c_6$  are nonzero. Finally, if  $c_5$  (an effective thermal capacitance) is nonzero, then it is possible to track the collector transients.

Estimate the annual energy production of a concentrating collector in Pueblo, CO, oriented to track on a single east-west axis. The collector has the following characteristics:  $T_{in} = 80^\circ\text{C}$ ,  $\dot{m} = 0.77$  [kg/s],  $A_a = 5.38$  [m<sup>2</sup>],  $L = 4.1$  [m],  $F'(\tau\alpha)_n = 0.590$ ,  $K_{\tau\alpha}(\theta_d) = 0$ ,  $b_0 = 0.52$ ,  $c_1 = 0.932$  [W/m<sup>2</sup> K],  $c_2 = c_3 = c_4 = 0$ ,  $c_5 = 2460$  [J/m<sup>2</sup> K],  $c_6 = 0.0125$  [s/m]. Also estimate the annual energy production with  $c_5$  equal to zero.

**CHAPTER 8**

**8.1** Rework Example 8.3.1, but with a tank containing 500 kg of water and with  $(UA)_s$  of  $5.56$  W/°C. Comment on your results.

**8.2** Develop a set of equations analogous to those in Section 8.4 for a two-node (partially stratified) tank in which water to meet a load is replaced by water at a constant temperature from the mains.

- 8.3** Estimate the pressure drop for Example 8.5.1. Does the pressure drop satisfy the minimum recommended pressure drop of Table 13.2.1?
- 8.4** Estimate the equivalent thermal capacity of a phase change energy storage unit made with paraffin wax (see Table 13.7.1 for properties). The total mass of PCES material is 1300 kg and the temperature change is 40 to 55°C.
- 8.5** For Example 8.10.1 what voltage would be needed to charge the battery in 11 h? If the load resistance is increased to 2  $\Omega$ , how long will it take before the battery reaches a state of charge of 0.2? Under the cycle of this problem what is the battery efficiency?

## CHAPTER 8

- S8.1** A simple half-day hour-by-hour simulation.  
Write a computer program to duplicate the results of Example 8.3.1.
- S8.2** A simple annual simulation.  
Extend the program in Problem S8.1 to an annual simulation where the load in Example 8.3.1 is repeated every 12 h. Assume the useful energy gain from the collectors is 40% of the incident solar radiation on a collector of 8 m<sup>2</sup> and of any slope. If EES is used, prepare a drop-down menu in the Diagram Window to select the city from the CombiSys weather data and use an input box to accept the slope.
- S8.3** A simple pebble bed storage analysis.  
Write a computer program to duplicate the results of Example 8.5.2. If EES is being used, then use the Parametric Table (not arrays) for the bed temperatures. If arrays are used, then EES attempts to solve all of the equations at one time. Although EES will “discover” that only the equations in each time step need be simultaneously solved, the computational and storage overhead are significantly increased over using the Parametric Table. Using arrays or the Parametric Table in this one-day analysis will not make much difference, but in an annual simulation the use of the Parametric Table is required.
- S8.4** A storage battery computer model.  
Verify the results of Example 8.10.1 and then determine the battery cycle efficiency if the charging voltage is reduced to 15.5 V and the discharge resistive load is increased to 2  $\Omega$ . EES provides Function and Procedure capabilities that are useful in reducing programming time when code needs to be reused. Add the Function V<sub>cell</sub> to the EES SETP library.

## CHAPTER 9

- 9.1** A water heating system serving a commercial building maintained at 21°C is set up with a recirculation loop that assures quick availability of hot water at 38°C at all parts of the system. The estimated  $UA$  of this loop is 38.1 W/°C. The  $UA$  of the hot-water tank is 11.0 W/°C. Cold water enters the heater from the mains at 12°C. Hot-water use in the building averages 610 liters/day Monday through Friday and 210 liters/day on weekends.



- a How much energy is required per week to heat the water (without considering losses)?
  - b Estimate the total weekly energy to be supplied to this hot-water system if recirculation is continuous.
  - c If the recirculation system is shut off from 6 PM to 8 AM each night, if the total mass of pipe and water is equivalent to the water in 122 m of 19-mm-diameter tubing and if there is no hot-water use during the hours when the recirculation pump is off, estimate the total weekly energy requirements of the system.
- 9.2** A building has  $(UA)_h = 335 \text{ W/}^\circ\text{C}$  and is to be maintained at  $19^\circ\text{C}$ . The ambient temperature is  $-3^\circ\text{C}$ . Internal generation in the building is equivalent to 1.5 kW. What is the balance temperature? How much energy must be supplied to the building from fuel or solar heating to maintain the building at  $19^\circ\text{C}$ , assuming steady conditions?
- 9.3** The building of Problem 9.2 is located in Madison, WI. Estimate the annual energy that must be delivered to the building to keep it at  $19^\circ\text{C}$  under the following assumptions.
- a The  $(UA)_h$  is  $335 \text{ W/}^\circ\text{C}$ .
  - b The building has additional insulation to reduce  $(UA)_h$  to  $224 \text{ W/}^\circ\text{C}$ .
  - c The building has additional insulation to reduce  $(UA)_h$  to  $112 \text{ W/}^\circ\text{C}$ .

## CHAPTER 9

### S9.1 Degree-day base temperature.

Monthly degree-days can be estimated using Equation 9.3.7, which uses a daily average temperature rather than the 24 hourly temperatures. This approximation was used before the advent of digital computers. For the 12 months in Madison, WI, calculate the degree-days using this approximate method and by summing the hourly values of  $(T_b - T_a)^+$  and dividing by 24. Use base temperatures of 18.3, 15, 12, and  $9^\circ\text{C}$ . Discuss the results. Note that  $18.3^\circ\text{C}$  is  $65^\circ\text{F}$ , the usual base for reporting degree-days in the United States. If a house were maintained at a known fixed temperature, then the constant gains can be calculated from Equation 9.3.3.

### S9.2 Degree-day heat load versus simulation.

The degree-day method of calculating a building load is simplistic and subject to significant errors. The method does not consider the impact of building thermal mass and ignores any time variation of thermal gains. Consider two buildings each with the same  $UA$  of  $350 \text{ W/K}$ . The light-weight building as a very low thermal mass (i.e., zero) and the other has an thermal mass of  $30 \text{ MJ/K}$ . Estimate the annual heating load for the zero mass building using Equation 9.3.6 and the base  $18.3^\circ\text{C}$  degree-days listed for Madison, WI, in Appendix D (the degree-days should be the same as calculated in Problem S9.1). Write a program to also estimate the annual heating load but include the effect of thermal mass. That is, treat the building as a single lump and calculate the hour-by-hour heat gain and loss. Whenever the building temperature falls below  $23.89^\circ\text{C}$  ( $75^\circ\text{F}$ ), the furnace is turned on to maintain the house set

temperature. The house internal gain can be calculated from Equation 9.3.3 (see Problem S9.1)

## CHAPTER 10

**10.1** A water heating system has a fully mixed tank of capacity 400 liters. The tank is located in a building having a temperature of  $19^{\circ}\text{C}$ . The collector area is  $5.0\text{ m}^2$ . The tank area–loss coefficient product  $(UA)_s = 0.81\text{ W}/^{\circ}\text{C}$ ,  $F_R(\tau\alpha) = 0.76$ , and  $F_R U_L = 4.80\text{ W}/\text{m}^2\text{ }^{\circ}\text{C}$ . In a particular hour when the ambient temperature is  $12^{\circ}\text{C}$ , the radiation on the plane of the collector is  $18.0\text{ MJ}$ . The load on the system is  $5.20\text{ MJ}$ . If the tank temperature is  $43^{\circ}\text{C}$  at the beginning of the hour, estimate the temperature at the end of the hour.

**10.2** A fully mixed storage tank containing 1500 kg of water has a loss coefficient–area product of  $11.1\text{ W}/^{\circ}\text{C}$ . The tank starts a particular 24-h period at a temperature of  $45^{\circ}\text{C}$ .  $Q_u$  is added from a collector and  $L_s$  is removed to a load. The loads  $L_s$  are indicated in the table below. The tank is located inside a building where the temperature is  $20^{\circ}\text{C}$ .

Collector data are  $A_c = 30\text{ m}^2$ ,  $F_R(\tau\alpha) = 0.78$ , and  $F_R U_L = 7.62\text{ W}/\text{m}^2\text{ }^{\circ}\text{C}$ . For this purpose, assume that  $(\tau\alpha)$  is independent of angle of incidence. The incident radiation and outdoor ambient temperature are also given in the table. Times shown are the end of the hour.

Time	1 AM	2	3	4	5	6	7	8	9	10	11	12
Load, MJ	12	12	11	11	13	14	18	21	20	20	18	16
$I_T$ , MJ/m <sup>2</sup>									1.09	1.75	2.69	3.78
$T_a$ , $^{\circ}\text{C}$	−4	−4	−5	−3	−1	0	0	1	0	2	4	10

Time	1 PM	2	3	4	5	6	7	8	9	10	11	12
Load MJ	14	14	13	18	22	24	18	20	15	11	10	9
$I_T$ , MJ/m <sup>2</sup>	3.87	3.41	2.77	1.82	1.53							
$T_a$ , $^{\circ}\text{C}$	10	8	8	6	4	4	3	5	6	6	7	6

**a** Estimate the useful gain from the collector for the day.

**b** Check the 24-h energy balance on the tank.

**10.3** Derive Equation 10.2.3.

**10.4** Calculate the value of the collector heat exchanger correction factor  $F'_R/F_R$  for the following conditions:

Heat exchanger effectiveness 0.60

Collector fluid flow rate  $0.70\text{ kg/s}$


Collector fluid heat capacity  $3350\text{ J/kg }^{\circ}\text{C}$

Tank heat exchanger flow rate  $0.70\text{ kg/s}$

$F_R U_L = 3.75\text{ W}/\text{m}^2\text{ }^{\circ}\text{C}$

Collector area  $50\text{ m}^2$


- 10.5** A  $5.2\text{-m}^2$  water heating collector is connected by 20 m of 19-mm-diameter piping on each of the inlet and outlet sides to the storage tank. The pipe is insulated with 18 mm of foam rubber insulation with conductivity  $0.050\text{ W/m}^\circ\text{C}$ . The heat transfer coefficient on the outside of the insulated pipe is  $25\text{ W/m}^2^\circ\text{C}$ .  $F_R = 0.92$  and  $(\dot{m}C_p)_c = 295\text{ W/}^\circ\text{C}$ . The collector has  $F_R(\tau\alpha) = 0.72$  and  $F_R U_L = 4.65\text{ W/m}^2^\circ\text{C}$ . If the insulated piping is exposed to ambient temperature, what will be the equation for useful output of the collector?
- 10.6** An industrial process air heating system is shown in the accompanying sketch. The air being heated by the combination of solar plus auxiliary enters the heating section at  $35^\circ\text{C}$ , is partially heated by solar energy from the storage tank via the load heat exchanger, and then is further heated by the auxiliary exchanger to  $55^\circ\text{C}$ . The collector has an area of  $80\text{ m}^2$ .  $F'_R(\tau\alpha) = 0.78$  and can be considered as constant for this problem.  $F'_R U_L = 4.45\text{ W/m}^2^\circ\text{C}$ . The fully mixed tank has a capacity of 5000 kg. It is well insulated, and  $(UA)_s = 140\text{ kJ/h}^\circ\text{C}$ . The tank is outdoors. The load heat exchanger has an effectiveness near unity (i.e., it is very large) so the return temperature to the tank is always the same as the inlet air temperature. The air to be heated flows at constant rate for 24 h a day at a rate of  $0.83\text{ kg/s}$  and has a heat capacity of  $1013\text{ J/kg}^\circ\text{C}$ . The flow rate through the load heat exchanger is controlled, upto a maximum of  $0.056\text{ kg/s}$  so that the air leaving the load heat exchanger never exceeds  $55^\circ\text{C}$ .



The radiation on the collector and ambient temperature data for a 12-h period are shown in the table. The initial tank temperature is  $47^\circ\text{C}$ . For this period, how much energy is supplied to the load from the tank? How much auxiliary energy is needed?

Time	$T_a, ^\circ\text{C}$	$I_T, \text{MJ/m}^2$	Time	$T_a, ^\circ\text{C}$	$I_T, \text{MJ/m}^2$
6–7	7	0	12–1	15	3.87
7–8	8	0	1–2	14	3.41
8–9	9	1.09	2–3	12	2.77
9–10	9	1.75	3–4	12	1.82
10–11	9	2.69	4–5	12	1.53
11–12	12	3.78	5–6	11	0

- 10.7** The system of Problem 10.6 has a load heat exchanger effectiveness of 0.58. Calculate the solar energy supplied and the auxiliary energy required for the same conditions of operation.
- 10.8** A liquid heating system with a one-cover selective collector with emittance of 0.2 is set up to preheat water from the mains and supply it at  $T_s$  to a boiler, as shown in the accompanying diagram. The characteristics of the system are as follows:



$$F_R(\tau\alpha)_n = 0.73$$

$$F_R U_L = 5.10 \text{ W/m}^2 \text{ } ^\circ\text{C}$$

Heat exchanger effectiveness 0.60

Capacitance rate on collector side 1020 W/°C

Capacitance rate on tank side 1120 W/°C

Collector area 20 m<sup>2</sup>

Tank capacity 1000 liters

Tank  $UA$  6.0 W/°C

Supply water temperature 11°C

Initial tank temperature 35°C

The meteorological data and load flow rate for a 4-h period are shown in the following table:

Hour	$I_T$ , MJ/m <sup>2</sup>	$T_a$ , °C	Load Flow, kg
10–11	0.09	14	150
11–12	1.75	17	150
12–1	3.45	18	0
1–2	2.75	20	150

Make the following assumptions:

The controller turns the pump on whenever energy can be collected.

The  $(\tau\alpha)$  for the hours in question are the same as  $(\tau\alpha)_n$ .

All quantities in the table are constant at their averages over each hour.

The tank is fully mixed.

The tank is in a room at a constant temperature of 20°C.



Calculate:

- The tank temperature at 2 PM.
- The integrated energy balance (over the 4 h) on the tank.

**10.9** For Problem 10.8 any of the following might occur (each independently of the others). For each, indicate how the 2 PM  $T_s$  would be different from that of Problem 10.8 and explain why.

- a** The effectiveness of the collector heat exchanger increases to 0.90.
- b** The absorber surface deteriorates, resulting in an increase in emittance to 0.5.
- c** The pump runs at half speed.
- d** The supply water temperature increases to 14°C.

**10.10** The manufacturer of a solar collector panel supplies the technical data shown in the accompanying figure. You are designing a solar domestic hot-water heating system that uses six of these panels. The panels are connected in three parallel circuits each having two panels in series. Assume the same flow through each parallel circuit. A 50–50 mixture of propylene glycol and water is circulated through the panels. The test fluid in water.



A heat exchanger with an effectiveness of 0.45 separates the collector loop from the tank loop. The heat exchanger is located near the storage tank. (See Figure 20.2.3.) The 12-mm-diameter copper piping connecting the collectors to the tank and exposed to  $T_a$  is 12 m long on both the inlet and outlet of the collector. The heat transfer coefficient on the outside of the pipe insulation is very large. The pipe insulation has an outside diameter of 30 mm and a thermal conductivity of 0.043 W/m °C. The collector loop pump delivers 0.040 liter/s and the tank loop pump delivers 0.050 liter/s.

Calculate the numerical values of the constants  $a$  and  $b$  and develop an equation for the function  $f(\theta)$  in the following equation which gives the useful gain of the collector system in megajoules for an hour period when  $I_T$  is in megajoules per square meter for an hour:

$$Q_u = a[I_T f(\theta) - b(T_{\text{tank}} - T_a)]^+$$

- 10.11** For the north row of the collector array of Example 1.9.3, estimate the output of the collector row for an hour in which the beam radiation on the plane of the (unshaded) collectors is 2.95 MJ/m<sup>2</sup> and the diffuse radiation on this plane is 0.88 MJ/m<sup>2</sup>. (*Note:* Assumptions must be made about the angular distribution of the diffuse and the reflected radiation on the collector row. One approximation would be to assume that the combination of the diffuse from the sky and reflected radiation from the surroundings is in sum isotropic. Other assumptions are possible.)

For this collector,  $F_R(\tau\alpha)_n = 0.83$ ,  $F_R U_L = 4.07$  W/m<sup>2</sup> °C, and  $b_o = -0.14$ . At solar noon,  $T_i = 40^\circ\text{C}$  and  $T_a = 14^\circ\text{C}$ . The water flow rate is 0.011 kg/m<sup>2</sup> s.

- 10.12** An experimental solar heating system is constructed with collectors facing south and arranged in two banks, each of area 50 m<sup>2</sup>, the first of which is at a slope of 20° and the second at a slope of 70°.  $F_R(\tau\alpha)_n = 0.83$ ,  $F_R U_L = 4.07$  W/m<sup>2</sup> °C, and  $b_o = -0.14$ . Flow is in series from the first to the second bank. The water flow rate is 1.10 kg/s. At a latitude of 40° at 3:30 PM on March 16 the collector inlet temperature is 40°C, the ambient temperature is 14°C, and  $G = 580$  W/m<sup>2</sup>. What will be the output of the 100-m<sup>2</sup> array?

## CHAPTER 10

### S10.1 Simple simulation.

A 2-m<sup>2</sup> flat-plate collector receives water at a constant flow rate of 0.04 liters per second and temperature of 25°C. Use EES to read a TMY2 weather data file (see Problems S2.1 and S2.2). The program should use the EES Diagram Window to accept input such as location, collector slope, azimuth,  $F_R(\tau\alpha)$ ,  $F_R U_L$ ,  $b_o$  (or the equivalent collector parameters using the average fluid temperature—see Section 6.19). Use the EES parametric table to display the solar radiation incident on the collector and collector gain. The integrated incident solar energy, and collector energy gain values should be plotted as a function of time. Use angles evaluated at the half hour.

**S10.2** One unstratified tank.


A flat-plate collector receives water from a fully mixed water storage tank and delivers heated water back to the tank (see Problem S10.1). A controller turns the collector-tank circulating water pump on whenever useful energy can be collected. A fixed amount of hot water at a temperature of  $60^{\circ}\text{C}$  or higher are required every hour from 0800 to 1800. When hot water is required mains water enters the storage tank, is mixed with the water in the tank, and mixed tank water flows to an electric inline domestic hot-water heater that is of sufficient capacity to always supply the hot-water demand. Use EES to read a weather data file (see Problem S2.1) and to estimate the hourly radiation on the inclined collector (see Problem S2.2). The program should use the EES Diagram Window to accept input such as collector area, slope, azimuth, collector parameters, main water temperature, hot-water usage, storage tank size, and storage tank loss coefficient ( $UA$ ). The EES Diagram Window should display the estimated monthly energy gain of the water. The integrated values of incident solar, collector gain, energy required, tank losses, and auxiliary energy should be calculated in a parametric table and plotted.

**CHAPTER 11**

- 11.1** Calculate the present worth of a cost that is expected to be \$5700 in 10 years if the market discount rate is **a** 8% per year and **b** 12% per year.
- 11.2** What is the annual loan payment on a loan of \$20,000 which is borrowed at 8.5% for 15 years if all payments are uniform?
- 11.3** What is the present-worth factor for a series of payments over 18 years if the inflation rate is 7.8% per year and the market discount rate is 9.5% per year?
- 11.4** Calculate the present worth of a 10-period series of costs the first of which is \$1000 payable at the end of the first period. The costs inflate at 5% per period. The discount rate  $d$  is **a** 3% per period and **b** 7% per period.
- 11.5** A collector is to be installed which has plastic glazing. It is expected that the glazing will have to be replaced every 3 years. The cost of its replacement now is \$15/m<sup>2</sup> and is expected to inflate at 7% per year. What is the present worth of the cost of maintaining the glazing on a 75-m<sup>2</sup> collector array over a period of 20 years if the market discount rate is 10%/year.
- 11.6** A solar energy system is to be paid for with a loan in the amount of \$2700. The interest rate on the loan is 10.5% per year and the period is 8 years. The market discount rate is 9.5% per year.
- a** Calculate the annual payment to the lender.
  - b** Calculate the monthly payment for the same loan (assuming that  $i = 10.5/12$  per month compounded monthly).
  - c** What is the present worth of the interest payments on the loan of part a?
- 11.7** **a** What is the present worth of a cost that is expected to be \$4500 seven years hence if the discount rate is 8% per year?

- b Fuel for an operation now costs \$700. If the inflation rate is 5% per year, what will it cost at the end of 7 years?
  - c The cost of fuel for an operation will be billed at the end of a year and will be \$700. If the inflation rate is 5% per year, what will be its cost at the end of 7 years?
  - d A cost for maintenance of solar equipment will be \$175 for the first year, payable at the end of the year. If the cost is expected to inflate at 5% per year and the discount rate is 8% per year, what is the present worth of the maintenance cost in the 10th year?
  - e What is the present worth of the *series* of maintenance costs of part d for the 10 years?
- 11.8 In Examples 11.6.3 and 11.6.4, a fixed effective income tax rate of 45% was assumed. What would be the effect on the answer to these examples if the income tax rate was 45% during the first 10 years and 55% in the last 10 years? (*Note:* This could be done quantitatively. Indicate from qualitative considerations what change you expect.)
- 11.9 The first cost of a solar heating system (after tax credits) is \$6000. Of this, area-dependent costs are \$96/m<sup>2</sup>, and the area-independent cost is \$120. The down payment is one-sixth of the cost. The balance is financed by a 5-year, 10%-per-year mortgage. The load is 124 GJ/yr, of which 64% is met by solar energy. Fuel is \$12/GJ and the fuel inflation rate is 7% per year. The discount rate is 9% per year. Assume that maintenance and cost of parasitic power are negligible and there are no property taxes on the solar heating equipment. The owner's effective tax bracket is 0.42. Assume that all payments are made at the end of the year in which they are incurred. Prepare tables of annual costs (as in Example 11.6.3).
  - a If resale value is 0 and  $N_e = 10$  years, what is  $LCS$ ?
  - b If resale value is 0 and  $N_e = 5$  years, what is  $LCS$ ?
  - c If resale value is one-third of the cost and  $N_e = 5$  years, what is  $LCS$ ?
- 11.10 Redo Problem 11.9 by the  $P_1$ ,  $P_2$  method.
- 11.11 If in Problem 11.9 or 11.10 the fuel inflation rate is uncertain to  $\pm 3\%$  (i.e.,  $i_F = 7 \pm 3\%$ , what is the uncertainty in  $LCS$ ? If the calculation of the annual solar fraction is uncertain to  $\pm 2\%$  (i.e.,  $\mathcal{F} = 64 \pm 2\%$ ), what is the uncertainty in  $LCS$ ? If both of these uncertainties exist, what is the uncertainty in  $LCS$ ?
- 11.12 For the conditions of Problem 11.9a:
  - a What is payback time B of Section 11.7 without discounting fuel costs?
  - b What is payback time B if fuel costs are discounted?
- 11.13 For the system of Problem 11.9 or 11.10, thermal performance calculations produce the  $\mathcal{F}$ -versus- $A_c$  curve shown in the accompanying figure. Estimate the optimum collector area and the life-cycle savings at the optimum area.





- 11.14** A solar process is to deliver 70% of an annual energy requirement of 300 GJ. The solar process equipment cost (installed) is \$18,000. The equipment is to be paid for by a 20% down payment and 80% loan at 9% per year over 10 years. The market discount rate is 10%/yr. The resale value is expected to be small. This is not an income-producing facility. Other costs are as follows: insurance, maintenance, and operating power, \$250 in first year, expected to inflate at 6% per year. The owner's federal income tax rate is 40% and the installation is in a state where there is no state income tax. Auxiliary energy supplied is 90 GJ/yr, its initial cost is \$8.80/GJ, and it is expected to rise at 10% per year. What are the life-cycle savings over a 15-year period?
- 11.15** A life-cycle cost economic analysis is to be made for a solar process. The first cost is \$11,000, and it supplies 110 GJ/yr of solar energy to the process (which is not an income producer). The equipment is durable, and it is expected that it can be resold at the end of the period of the analysis for 80% of its installed first cost. Twenty percent of the first cost is paid as cash, and the balance is financed by a loan at 9% interest over 10 years. Insurance, maintenance, and parasitic power are negligible.
- Real estate taxes are 2% of investment, expected to inflate at 6% per year. The effective income tax bracket is 40%. The discount rate is 15% per year.
- Fuel cost in the first year (for auxiliary or for fuel-only operation) is \$10/GJ and is expected to inflate at 14% per year.
- What are the life-cycle savings of this system over 15 years compared to a fuel-only system?
  - What are the life-cycle savings of this system over 20 years compared to a fuel-only system? (*Note:* The change is in the period of the analysis, not the period of the mortgage.)
  - What is the return on investment?
- 11.16** A state's legislation provides tax credits for solar energy systems. The rules state that the life-cycle fuel savings must exceed the total present worth of the costs of the system within a 25-year period. A solar water heater installed on a house cost a total of \$1550; it is expected to meet 60% of an annual load of 19 GJ. The back-up energy source is electricity at \$0.045/kWh average. The rules specify that an inflation rate of 12% per year and a discount rate of 7% per year shall be used. Will this heater meet the criterion?

- 11.17** A solar heating and domestic hot-water system has the following area–solar fraction relationship.

$A_c$	$\mathcal{F}$
0	0
5	9.1
7.5	13.3
15	24.6
30	41.5
45	54.0
60	63.6
75	71.1

There are a number of “figures of merit” that are favored by or used by those designing and evaluating solar energy applications. The criterion of economic viability that we recommend is life-cycle solar savings. In this problem you are to consider *LCS* and three additional criteria. The four criteria are:

- a** Life-cycle savings
- b** Payback time *B* (Section 11.3) with fuel costs discounted
- c** Return on investment
- d** Cash flow, considering principle and interest payments, payments for taxes and insurance, and fuel purchase savings, all in the first year. This is sometimes called the PITI (principle, interest, taxes, and insurance) method.

Economic parameters are as follows (with rates in percent per year):

Mortgage interest rate 5.8%

General inflation rate 2.0%

Period of analysis 20 years

Term of loan 20 years

Property tax rate 3.5%

Effective income tax rate 39%

Down payment 0.2 of investment

Ratio of year 1 miscellaneous costs to investment 0.050

Ratio of assessed valuation to investment 0.90

Ratio of resale value to investment 0.25

$C = 0$  (non-income-producing system)

First-year fuel cost \$11/GJ (what you pay for fuel as it enters the furnace)

Furnace efficiency 0.8

Energy cost inflation rate 5.2%

Discount rate 4.5%

Area-dependent cost \$150/m<sup>2</sup>

Fixed cost \$550

The annual loads are  $2.0645 \times 10^7$  kJ for the domestic hot water and  $1.2475 \times 10^8$  kJ for the house heating.

- a The object is to find economic optimum collector areas (if optima exist) using each of the four methods. How do the results using these four criteria compare? Would you expect them to be different? If so, why?
- b Repeat the process, assuming that the collector unit area costs are \$240/m<sup>2</sup> instead of \$150/m<sup>2</sup>. Are the results very much different?
- c If you have an EES program to do this problem, you can easily explore the effects of other economic parameters. What might be interesting variables to investigate?

## CHAPTER 11

### S11.1 An alternative economic analysis.

When making a projection of the economic viability of using solar for a specific application, the cost of the solar components may not be known. An alternative to calculating the life-cycle savings is to calculate how much can be paid for the solar components to break even. For Example 11.6.4 the optimum area is 39 m<sup>2</sup>. With this area what is the collector cost per unit area that results in a zero life-cycle cost?

### S11.2 CombiSys economics.

The CombiSys program does not include economics as a part of the input and output. For the economic parameters of Example 11.6.4 (except for collector costs), and the default CombiSys parameters, what will a homeowner pay for collectors per unit area if the owner is to just “break even.”

### S11.3 Break-even collector cost.

For the CombiSys default parameters except for collector area and the economic parameters of Example 11.6.4, what is the solar life-cycle savings optimum?

## CHAPTER 12

**12.1** What would be the effect on the amount of solar energy delivered by a collector and tank if the same water heating load were concentrated between the hours of 1700 and 1800, rather than spread out uniformly through the 24 h of the day?

**12.2** Consider the water heater and storage tank of Example 10.9.1. Discuss qualitatively what will happen to the system performance if the following operation or design changes are made. Consider each independently. (*Note:* Whenever possible, use equations to justify qualitative conclusions.)

- a The collector cover glass is removed (e.g., by breakage).
- b The area of the collector is doubled.
- c The same total load is applied for each day but it is all required between 6 PM and midnight.
- d The storage tank design is changed so that water in the tank is thermally stratified rather than mixed.

## CHAPTER 14

- 14.1** For a vertical collector-storage wall located in Albuquerque and having dimensions and overhang as described in Problem 2.25, estimate the monthly average absorbed radiation for the month of April. The wall is double glazed with glass of  $KL = 0.0370$  per sheet. The  $\alpha_n$  of the wall is 0.89.
- 14.2** A direct-gain system has the same geometry as that used to calculate Figure 14.4.3 but is located in Madison, WI. The ground reflectance is 0.6 in December and January, 0.4 in November and February, and 0.2 for other months.
- a** For the month of March, estimate the beam, the diffuse, the ground-reflected, and the total radiation on the shaded receiver and also the total radiation if there were no shading.
- b** Repeat for each month of the year and prepare a plot like Figure 14.4.3.
- 14.3** Redo Example 14.5.1 with these changes: The location is Minneapolis, MN (latitude  $44.9^\circ$ ), the gap is 0.25 m, and the month is February ( $\overline{H} = 8.67 \text{ MJ/m}^2$ ,  $T_a = -6^\circ\text{C}$ ). What is the net gain (or loss) from the window?
- 14.4** What would be the effect of adding night insulation to the collector-storage wall of Problem 14.3? The resistance of the insulation is  $1.6 \text{ m}^2 \text{ }^\circ\text{C/W}$  and it is to be placed over the windows from 6 PM to 6 AM every day during the heating season.

## CHAPTER 18

- 18.1** A basin-type solar still is operating under conditions such that the water temperature is  $60^\circ\text{C}$ , the ambient temperature is  $24^\circ\text{C}$ , and the glass temperature is  $49^\circ\text{C}$ . Estimate the heat fluxes from basin to cover by convection, by evaporation-condensation, and by radiation.

## CHAPTER 19

- 19.1** Determine the collector area to supply 75% of the hot-water requirements of a residence of a family of four in Boulder, CO, based on the meteorological data for the week of January 8 through 14 as given in Table 2.5.2. Figure 12.1.1(b) is the system schematic. Each person requires 45 kg of water per day at a temperature of  $60^\circ\text{C}$  or above. Assume that the load is uniformly distributed over the day from 7 AM to 9 PM. Whenever the storage temperature is less than  $60^\circ\text{C}$ , the auxiliary energy source supplies sufficient energy to heat the water coming from the storage tank to  $60^\circ\text{C}$ . Use the following collector and storage parameters in your analysis:
- Storage mass to collector area  $60 \text{ kg/m}^2$
- Collector tilt  $40^\circ$  to the south
- Collector loss coefficient  $4.0 \text{ W/m}^2 \text{ }^\circ\text{C}$
- Cover transmittance-absorptance product  $(\tau\alpha)_n = 0.77$

Collector efficiency factor  $F' = 0.95$

Flow rate through collector  $50 \text{ kg/m}^2 \text{ h}$

Temperature of supply water to bottom of tank  $15^\circ\text{C}$

Loss coefficient of tank  $1.05 \text{ W/m}^2 \text{ }^\circ\text{C}$

Height-to-diameter ratio of cylindrical tank 3

Ambient temperature at tank  $21^\circ\text{C}$

$\rho_g = 0.2$

Single cover

Glass  $KL = 0.0125$

Normal solar absorptance = 0.9

*Notes:* For a time period as short as a week, the initial tank temperature can significantly affect system performance. You should find the steady periodic solution, in which the final tank temperature is the same as the initial tank temperature.

- 19.2** Do Problem 19.1 with a system like that of Figure 12.1.1(d), where the effectiveness of the collector heat exchanger is **a** 0.78 and **b** 0.35. Assume that the capacitance rates on the two sides of the heat exchanger are the same.
- 19.3** Repeat Problem 19.1 for the first week in July. Use TMY3 Boulder data.

## CHAPTER 20

- 20.1** A well-insulated residence located at Madison ( $\phi = 43^\circ$ ) has an area–loss coefficient product of  $145 \text{ W/}^\circ\text{C}$ . It has on it a collector of  $A_c = 22 \text{ m}^2$  facing south at a slope of  $70^\circ$ . The collector–heat exchanger parameters from the standard collector tests are  $F'_R(\tau\alpha)_n = 0.79$  and  $F'_R U_L = 3.80 \text{ W/m}^2 \text{ }^\circ\text{C}$ . The collector has one cover. The storage tank capacity is 1650 liters. For the load heat exchanger  $\varepsilon_L C_{\min}/(UA)_h = 2.00$ .  $(\tau\alpha)/(\tau\alpha)_n = 0.96$ . Radiation on the collector  $\overline{H}_T$ , calculated by the methods of Chapter 2, is  $10.7 \text{ MJ/m}^2$ . Appendix D provides information on average temperature and degree-days. The water heating load for the building is 2.06 GJ per month. For the month of January:
- a** What are the total loads?
  - b** What are  $X$  and  $Y$ ?
  - c** What is the fraction carried by solar?
  - d** If storage volume is halved, what is  $f$ ?
  - e** If  $\varepsilon_L C_{\min}/(UA)_h$  is reduced to 0.5 and the storage tank volume is halved, what is  $f$ ?
- 20.2** A space heating system in Madison, WI, uses liquid heating collectors. The house and system parameters and weather for a particular month are as follows:
- Days in month = 30
  - Radiation on plane of collector  $\overline{H}_T = 15 \text{ MJ/m}^2$

Average ambient temperature  $-2^{\circ}\text{C}$

Degree-days  $553^{\circ}\text{C-days}$

House area–loss coefficient product  $(UA)_h = 350 \text{ W}/^{\circ}\text{C}$

$$F'_R(\tau\alpha)_n = 0.78$$

$$F'_R U_L = 7.0 \text{ W}/\text{m}^2 \text{ } ^{\circ}\text{C}$$

$$(\tau\alpha)/(\tau\alpha)_n = 0.95$$

Storage volume per unit collector area  $180 \text{ liters}/\text{m}^2$

Load heat exchanger standard size

- a For a collector area of  $100 \text{ m}^2$ , calculate the corrected value of  $X$  for use in an  $f$ -chart.
  - b For a collector area of  $100 \text{ m}^2$ , calculate the corrected value of  $Y$ .
  - c For this collector area, what is  $f$ ?
  - d If the collector area is  $50 \text{ m}^2$ , what is  $f$ ?
- 20.3** A residential building in Madison, WI, is to be fitted with a solar heating system of the standard configuration for air systems shown in Figure 20.2.2. The  $UA$  of the building is  $400 \text{ W}/^{\circ}\text{C}$ . The storage capacity is the standard storage capacity in the  $f$ -chart correlation. Air flow rate is also the standard value. The collector faces south with a slope of  $60^{\circ}$ . The collector to be used has  $F'_R(\tau\alpha)_n = 0.6$  and  $F'_R U_L = 4.0 \text{ W}/\text{m}^2 \text{ } ^{\circ}\text{C}$ ; these were measured at the same flow rate as is to be used in the application. For January, water heating loads are expected to be  $2.15 \text{ GJ}$ , and space heating loads correspond to  $821$  degree-days. Average ambient temperature is  $-8.0^{\circ}\text{C}$ . On the collector  $\overline{H}_T = 13.7 \text{ MJ}/\text{m}^2$  per day, from Example 2.19.1. Assume  $(\tau\alpha)/(\tau\alpha)_n = 0.96$ .
- a What collector area is required to meet  $0.5$  of the January loads?
  - b What is the annual solar fraction for the collector area of part a?
- 20.4** An air system in Madison, WI, has  $A_c = 40 \text{ m}^2$ ,  $F'_R(\tau\alpha)_n = 0.76$ ,  $F'_R U_L = 4.85 \text{ W}/\text{m}^2 \text{ } ^{\circ}\text{C}$ , two covers of high-quality glass,  $\beta = 60^{\circ}$ ,  $\gamma = 0^{\circ}$  air flow rate  $12 \text{ liters}/\text{m}^2 \text{ s}$ , and storage capacity  $0.15 \text{ m}^3/\text{m}^2$  of rock. The building has  $(UA)_h = 300 \text{ W}/^{\circ}\text{C}$ . Calculate  $\mathcal{F}$  for this system. (See Problem 2.18 for  $\rho_g$ .)
- 20.5** A residential building in Madison has an area–loss coefficient product of  $300 \text{ W}/^{\circ}\text{C}$ . A liquid solar heating system is to be used on this building, with its collector mounted at  $60^{\circ}$  slope and facing due south. A constant monthly hot-water load of  $1.9 \text{ GJ}$  is expected. The collector area is to be  $50 \text{ m}^2$ , and the collector–heat exchanger parameters are  $F'_R(\tau\alpha)_n = 0.72$  and  $F'_R U_L = 3.5 \text{ W}/\text{m}^2 \text{ } ^{\circ}\text{C}$ . The collector has two covers with  $KL = 0.0125$ . The storage capacity is to be  $5000$  liters. The load heat exchanger is to be sized so  $\varepsilon_L C_{\min}/(UA)_h = 2.0$ . Estimate the annual solar fraction.
- 20.6** For the heat pump characteristics shown in Figure 20.7.2 and the bin data for the month of January given in the table below, determine the monthly work and auxiliary energy requirements for a house with  $UA = 300 \text{ W}/^{\circ}\text{C}$ . (The bins cover  $2^{\circ}\text{C}$  and are identified by their central temperatures.)  $T_b = 18.3^{\circ}\text{C}$ .

Bin	-26	-24	-22	-20	-18	-16	-14	-12	-10
Hours	5.5	4	11.5	12	33.5	34	40	44	43
Bin	-8	-6	-4	-2	0	2	4	6	8
Hours	77	76	92	110	103.5	46.5	8.5	3	0

- 20.7** If a solar system is added in parallel with the system of Problem 20.6 and supplies 30% of the heating load in January, what are the month's heat pump work and auxiliary energy requirements?

## CHAPTER 21

- 21.1** For the conditions of Problem 20.4, use the generalized  $\phi$  charts to estimate the fraction by solar for the month of January. Assume that the collector receives air at a temperature of 20°C for the whole month. The following information may be useful in making the calculations: For January the average day is 17,  $\delta = -20.9^\circ$ ,  $\omega_s = 69.12^\circ$ ,  $\overline{H}_o = 13.37 \text{ MJ/m}^2$ ,  $\overline{H} = 6.44 \text{ MJ/m}^2$ ,  $T_a = -8^\circ\text{C}$ ,  $T_{\text{day}} = -3^\circ\text{C}$ ,  $\overline{H}_d/\overline{H} = 0.41$ ,  $\rho_g = 0.7$ , load = 213 GJ.

Hours from Noon	$r_t$	$r_d$	$\theta_z$	$\theta$	$(\tau\alpha)/(\tau\alpha)_n$
0	0.179	0.167	63.9	3.9	0.96
0.5	0.176	0.165	64.3	8.1	0.96
1.5	0.152	0.147	67.2	21.6	0.95
2.5	0.108	0.113	72.6	35.6	0.94
3.5	0.055	0.065	80.1	63.0	0.92

- 21.2** Repeat Problem 21.1 using daily utilizability. Assume  $(\tau\alpha)/(\tau\alpha)_n = 0.92$ .
- 21.3** Using the generalized  $\phi$  method, calculate the total energy collection for January in a location at 40° N latitude under the following conditions:  
 $\overline{K}_T = 0.5$   
 $F_R U_L = 4.2 \text{ W/m}^2 \text{ }^\circ\text{C}$   
 $F_R(\tau\alpha) = 0.75 \text{ (constant)}$   
Collector tilt 55° (facing due south)  
 $\overline{T}_a = 0^\circ\text{C}$ ,  $T_i = 50^\circ\text{C}$
- 21.4** Repeat Problem 21.3 using the  $\overline{\phi}$  method.
- 21.5** For Miami, estimate the contribution in July ( $\overline{H} = 20.01 \text{ MJ/m}^2$ ,  $T_a = 28^\circ\text{C}$ ) by solar for an absorption air conditioning system that has a *COP* of 0.7 when the temperature to the generator is greater than 70°C. The solar system characteristics are as given in Example 21.3.1. The collector tilt is 25° to the south. The collector area is 25 m<sup>2</sup>. The cooling load in July is 5.1 GJ. Neglect storage losses.
- 21.6** For Problem 21.5, the tank has an area–loss coefficient product of 7 W/°C. Estimate the reduction in performance due to tank losses if **a** the tank is outside the building and **b** the tank is inside the building.

## CHAPTER 22

- 22.1** A building at Chattanooga, TN (latitude  $35^\circ$ ), has  $16.1 \text{ m}^2$  of south-facing windows. The area–loss coefficient product for the entire building, including the window, is  $200 \text{ W}/^\circ\text{C}$ . The loss coefficient of the window is  $3.45 \text{ W}/\text{m}^2 \text{ }^\circ\text{C}$ . The room thermostat is set at  $18.3^\circ\text{C}$ . The average ground reflectance is 0.40,  $\overline{H} = 9.75 \text{ MJ}/\text{m}^2$ , and  $\overline{T}_a = 6^\circ\text{C}$ .
- If the building has negligible thermal capacitance, what fraction of the February solar radiation on the window is useful in heating the building? Estimate the required auxiliary energy.
  - The building has an effective thermal capacitance of  $20.2 \text{ MJ}/\text{K}$ . Estimate the required auxiliary energy if the allowable temperature swing is  $5^\circ\text{C}$ .
  - Estimate the required auxiliary energy for the conditions of part b but with an allowable temperature swing of  $10^\circ\text{C}$ .
- 22.2** The building and ACPS solar system in Springfield, IL, described in Example 22.5.1, is of medium-weight construction (see Table 9.5.1) and is estimated to have a thermal capacitance of  $22.9 \text{ MJ}/\text{K}$ .
- Estimate the auxiliary energy requirements for January if the construction is heavy as classified in Table 9.5.1.
  - Estimate the auxiliary energy requirements for January if the area of the collector is doubled to  $40 \text{ m}^2$  and the construction was medium.
  - Estimate the auxiliary energy requirements for January if the area of the collector is doubled to  $40 \text{ m}^2$  and the construction is heavy.
  - Based on the January results for parts a, b, and c, comment on the advisability of recommending the heavy construction and the additional collector area.
- 22.3** In Example 14.5.1, the direct-gain window was left uncovered during the night, which resulted in a significant heat loss and a reduced net energy gain. Estimate the average net gain for the month of March that could be obtained with a perfect control system that would cover the window with a perfect insulator ( $U = 0$ ) whenever the rate of energy gain is negative.

## CHAPTER 23

- 23.1** A PV module has the following characteristics:  $I_L = 13.6 \text{ A}$ ,  $I_o = 0.008 \text{ A}$ ,  $a = 23.6 \text{ V}$ ,  $R_s = 0.9 \text{ } \Omega$ ,  $R_{sh} = \infty \text{ } \Omega$ . If this module is connected to a resistive load of  $20 \text{ } \Omega$ , what is the power?
- 23.2** A manufacturer gives the following “nameplate” data for a silicon module at  $1000 \text{ W}/\text{m}^2$  and  $25^\circ\text{C}$ :  $V_{oc} = 186.6 \text{ V}$ ,  $I_{sc} = 13.6 \text{ A}$ ,  $I_{mp} = 11.26 \text{ A}$ ,  $P_{mp} = 1480 \text{ W}$ ,  $N_s = 300$ ,  $\mu_{I,sc} = 0.02 \text{ A}/\text{K}$ , and  $\mu_{V,oc} = -0.716 \text{ V}/\text{K}$ . Estimate the maximum power at an incident solar radiation of  $800 \text{ W}/\text{m}^2$  and a cell temperature of  $30^\circ\text{C}$ .
- 23.3** Eight PV modules are available, each with the  $I$ - $V$  characteristics of Example 23.2.1 (which is the same as the  $25^\circ\text{C}$  curve of Figure 23.2.5). At a radiation level of  $1000 \text{ W}/\text{m}^2$  and a cell temperature of  $25^\circ\text{C}$ , what is the best series/parallel connection plan to maximize power delivered to a resistive load of **a**  $6 \text{ } \Omega$ , **b**  $7 \text{ } \Omega$ , and **c**  $12 \text{ } \Omega$ ?



- 23.4** A PV array has the following characteristics:  $\alpha = 0.92$ ,  $\tau = 0.94$ , and  $U_L = 25 \text{ W/m}^2 \text{ } ^\circ\text{C}$ .
- If the incident radiation is  $1000 \text{ W/m}^2$  and the ambient temperature is  $35^\circ\text{C}$ , estimate the cell temperature.
  - What is  $T_{\text{NOCT}}$  (the nominal operating cell temperature)? What important assumptions are made in your solutions?
- 23.5** The following properties describe a solar cell module at reference conditions (i.e., solar radiation of  $1000 \text{ W/m}^2$  and cell temperature of  $20^\circ\text{C}$ ):  $V_{oc} = 15 \text{ V}$ ,  $I_{sc} = 1.2 \text{ A}$ ,  $I_{mp} = 1.0 \text{ A}$ ,  $V_{mp} = 12.5 \text{ V}$ ,  $\mu_{I,sc} = 0.0005 \text{ A/K}$ ,  $\mu_{V,oc} = -0.05 \text{ V/K}$ ,  $N_s = 24$ , and  $\varepsilon = 1.12 \text{ eV}$ . The module operates at a solar radiation level of  $750 \text{ W/m}^2$  and a cell temperature of  $15^\circ\text{C}$ . **a** What will be the power delivered to a resistive load of  $13.48 \text{ } \Omega$ ? **b** What is the maximum power?
- 23.6** At an incident solar radiation of  $1000 \text{ W/m}^2$  a PV solar system with an area of  $0.1 \text{ m}^2$  has a maximum power output of  $12.2 \text{ W}$  at a cell temperature of  $18.6^\circ\text{C}$  and  $10.0 \text{ W}$  at  $59.2^\circ\text{C}$ . The system NOCT temperature is  $40^\circ\text{C}$ . The efficiency of the maximum power point tracking electronics is  $0.92$ . Estimate the maximum power produced at a radiation level of  $800 \text{ W/m}^2$  and an ambient temperature of  $30^\circ\text{C}$ .
- 23.7** Write a computer program to reproduce the results of Example 23.7.1.

## CHAPTER 23

- S23.1** PV model parameters from manufacturers data.  
Develop a computer program to determine the value of the parameters in Equation 23.2.1 given at reference conditions: the short-circuit current, the open-circuit voltage, the maximum power current and voltage, and the temperature coefficients of both open-circuit voltage and short-circuit current. The resulting nonlinear equations are difficult to solve for many modules unless excellent guesses are used. The guess suggestions in Section 23.2 do not always provide sufficiently accurate values. An alternative is to add an error term to one of the equations and solve the equations for a wide range of values for  $I_o$ . When the error crosses zero, the solution is “near” and the range of  $I_o$  can be reduced. The process can be repeated, each time obtaining better guess values.
- S23.2** Annual performance of a PV system.  
Assume that a PV system has a maximum power point tracker (i.e., the array always operates at  $I_{mp}$  and  $V_{mp}$ ). The array efficiency at reference conditions ( $T_{\text{cell}} = 25^\circ\text{C}$  and  $I_T = 1000 \text{ W/m}^2$ ), the array NOCT, and the array maximum power temperature coefficient (Equation 23.2.16) are known. Write a computer program to predict the hourly, monthly, and annual array output for a nontracking system at a known slope and azimuth. To test the program, predict the monthly and annual output of a  $10\text{-m}^2$  array with  $\eta_{\text{ref}} = 12\%$ ,  $\text{NOCT} = 49^\circ\text{C}$  and  $\mu_{\eta,mp} = -0.005$ , slope =  $40^\circ$  and azimuth =  $-20^\circ$  in Madison, WI. Note that the program developed for Problem S2.4 can be the starting point for this program.

**S23.3** A PV system to charge a battery.

A PV system is to be used to charge batteries in a desert climate. The designers wish to simplify the design by eliminating the inverter and arranging sufficient cells in series so that the maximum power voltage is near the battery charging voltage. Consider the array of Example 23.2.1 with an NOCT of  $50^{\circ}\text{C}$  and the battery of Example 8.10.1. Assume the initial battery state of charge is 0.2, the ambient temperature is  $50^{\circ}\text{C}$ , the wind is not blowing, and the solar radiation incident on the array is  $1000 \text{ W/m}^2$ . Plot the battery state of charge as a function of time.

**S23.4** An economic optimum PV system.

The U.S. Energy Information Administration provided data for the year 2010 showing that the average U.S. household used about 960 kWh of electricity each month. The range of statewide retail prices for electricity was from \$0.080 per kWh in Idaho to \$0.281 per kWh in Hawaii (with a national average of \$0.115). Using the program and PV characteristics of Problem S23.2, determine the size of the PV array that is required to meet 100% of the annual energy use of a typical household in both Boise, ID, and Honolulu, HI. Assume “net metering” is available. With net metering a PV system’s excess electricity will “run the meter backwards,” effectively selling electricity at the homeowner’s retail price. Consequently, it is neither necessary to store excess PV-generated electricity nor is it necessary to meet 100% of the load at all times. For the economic parameters of Example 11.6.3 (i.e.,  $P_1 = 22.169$  and  $P_2 = 1.035$ ), determine the system cost for the homeowner to break even over 20 years.

**CHAPTER 24**

- 24.1** Show that Equation 24.2.11, the Rayleigh distribution, results from setting  $k = 2$  in the Weibull distribution.
- 24.2** Determine the Weibull parameters  $c$  and  $k$  for an average wind speed of 9 m/s and a standard deviation of 3.5 m/s.
- 24.3** Some wind atlases assign wind power categories according to the following table where the wind velocities were calculated using an assumed Rayleigh probability distribution of wind speed. For wind power class 4 verify that the average wind speed range is correct.

Power Class	Wind Power ( $\text{W/m}^2$ )	Speed (m/s)	
1	< 200	< 5.6	Poor
2	200–300	5.6–6.4	Marginal
3	300–400	6.4–7.0	Fair
4	400–500	7.0–7.5	Good
5	500–600	7.5–8.0	Excellent
6	600–800	8.0–8.8	Outstanding
7	> 800	> 8.8	Superb

- 24.4** In Example 24.4.3 for the range of wind speed from 18 to 22 m/s evaluate the average power analytically and compare the results with the numerical evaluation that was used in the example.
- 24.5** Estimate the annual average power for the turbine of Example 24.4.3 for the best and worst years in Madison, WI, as shown in Figure 24.2.3.

## CHAPTER 24

**S24.1** Annual performance of a wind turbine.

Although wind speed data is included in TMY2 data, it is not supplied with the CombiSys weather data. Since these typical meteorological years were selected based upon long-term averages of primarily solar radiation and ambient temperature, they are not suitable for predicting long-term wind performance. Many countries offer wind data that can be used to predict the output from a wind turbine. In the U.S., the NREL website ([www.NREL.gov](http://www.NREL.gov)) contains wind data for many hundreds of sites. The data sets are grouped by state and then identified by longitude and latitude. The data sets are large, consisting of 100 and 80 m wind velocities for every 10 min for a number of years. Choose a site, a year, and the 80 m data and generate a wind duration curve similar to Figure 24.4.1. Divide the data into 20 bins (10 are shown in Figure 24.4.1) and repeat Example 24.4.1 using this data.

**S24.2** An economic wind turbine.

Use the turbine of Example 24.4.3 along with the wind data of problem S24.1 to estimate the annual electrical output of the turbine. Assuming that the results are typical of the local wind conditions, what can a potential investor pay for the turbine if electricity sells for \$0.12 per kWh. Assume that the annual insurance and maintenance is 15% of the initial investment, that the turbine is paid for when installed, and that the investor requires a 10% return on his investment. Ignore inflation and the time value of money.


## SEMESTER PROJECT: INDUSTRIAL AIR HEATER SIMULATION

The following is an example of a system simulation problem given as a semester project. This requires the integration and application to systems of many of the ideas used in short problems in this appendix. The project is open ended in the sense that the student must decide what variables will be treated and how the results will be presented. Appropriate meteorological data must be available. There are many variations on problems of this type; this one includes some complications that can be omitted if a shorter project is wanted.

### The Application

For an industrial operation, a continuous supply of heated air is required at a rate of 1.40 kg/s at a temperature of at least 65°C. The air supply is at a constant temperature of

22°C. The location is Albuquerque, NM. A liquid solar heating system has been proposed to supply part of the needed energy. The major system components are collector, collector heat exchanger, storage tank, load heat exchanger, and auxiliary heat exchanger. They are arranged as shown in the accompanying diagram.



You are assigned the task of evaluating this system and reporting to your management on the technical and economic feasibility of the system. To do this, you are to write a simulation program that will allow you to do year-long simulations of the system and to explore the effects of several critical variables. The results of the thermal analysis will then be used as the basis for an economic analysis.

In the proposed process the air enters the heating section at 22°C, is first heated by solar energy, and then is heated in the auxiliary heat exchanger. It is to leave the heater section at a temperature no lower than 65°C. The auxiliary heat exchanger has the capacity to provide all of the needed energy if necessary. (Thus its cost is common to all systems and does not enter into economic comparisons of systems.)

Freeze protection is to be provided by use of an antifreeze solution in the collector loop. You should consider what, if anything, should be done about boiling.

## Equipment

Some of the component design parameters can be fixed, based on past experience and on equipment that is available. For purposes of these simulations, assume the following:

Collector	$F_R(\tau\alpha)_n = 0.81$ and $F_R U_L = 4.45 \text{ W/m}^2 \text{ } ^\circ\text{C}$ at $\dot{m}/A_c = 0.015 \text{ kg/m}^2 \text{ s}$ , $b_o = -0.12$ , $\gamma = 0$ , $\beta = \text{latitude}$ , and $A_c$ is variable.
Collector heat exchanger	The $UA$ of the exchanger and thus also its effectiveness $\varepsilon_c$ can be specified at any level.
Storage	A wide range of storage tank sizes are available. Based on past experience it is recommended that the ratio of storage tank capacity to collector area be kept at $100 \text{ liters/m}^2$ . Assume that the tanks are cylindrical with a ratio of height to diameter of 1. Assume a loss coefficient for the tanks of $5.5 \text{ W/m}^2 \text{ } ^\circ\text{C}$ .

Load heat exchanger	Cross-flow water-to-air heat exchangers are available in a wide range of sizes. It is recommended that the flow rate on the water side be fixed at 0.30 kg/s. The heat capacity of air under the conditions of this operation can be taken as 1013 J/kg °C. Use the effectiveness of this exchanger $\varepsilon_L$ to describe its operation.
Other Components	The other components, such as piping, ductwork, pumps, controls, etc., are standard. Any assumptions about them should be clearly stated.

## Thermal Analysis

Some thought about this problem will lead you to the following: There are three design variables that are or may be important in determining thermal performance and thus economic feasibility. They are the collector area  $A_c$ , the collector heat exchanger effectiveness  $\varepsilon_c$ , and the load heat exchanger effectiveness  $\varepsilon_L$ . You should explore the effects of these design variables on:

- $L_A$ , auxiliary energy required
- $L_S$ , solar energy delivered across load heat exchanger
- $Q_L$ , energy losses from storage tank

It is also of interest to explore process dynamics, that is, the short-term variations of energy flows and temperatures. It is suggested that for a time period of your choice (a period which would be important in process design) you consider what happens with time to the following variables:

- $T$ , tank temperature
- $T_{As}$ , temperature of air leaving load heat exchanger
- $T_{Ao}$ , temperature of air leaving auxiliary heat exchanger
- $\dot{L}_S$ , rate of solar energy delivery to load
- $\dot{Q}_u$ , rate of solar energy delivery to tank
- $I_T$ , radiation incident on collector
- $\dot{L}_A$ , rate of delivery of auxiliary energy to load

You will have to make assumptions in order to write the simulation program. In particular, you will have to decide how you wish to model the storage tank. Considering it to be a fully mixed tank leads to the simplest program and has the advantage of producing conservative results.

You will need some guidance in selecting collector area ranges to explore. This can be obtained by use of the design methods described in Chapters 20 and 21. (These methods provide a first estimate only; they are not a substitute for the simulations.) As a first suggestion, you should cover a range of at least 100 to 400 m<sup>2</sup> (but this may not be an adequate range). Also note that you can calculate the total minimum amount of energy required to heat the air from 22 to 65°C, you can estimate roughly what the annual

efficiency of the collector might be, and thus you can get a rough first estimate of the solar contribution of a system.

## Economic Analysis

Based on the thermal analysis, an economic analysis is to be prepared. This does not need to be done in detail but should be sufficient to indicate to your management what the economic feasibility of this project might be. In order to do this, assume the following economic parameters:

Cost of collectors \$250/m<sup>2</sup>

Cost of storage \$0.50/liter

Fixed costs \$20,000

Cost now of delivering auxiliary energy \$10/GJ

Cost of heat exchangers \$5 per unit of watts per degree Celsius

## Your Procedure

Prepare a simulation program in the language of your choice. You will need two meteorological data files, one a one-day file of hourly data for debugging your program and a second a TMY (typical meteorological year) file of hourly data which you will use for the simulations.

## Your Report

An executive summary should be included in your report. It should be one or two pages in length and should contain the essential facts of what you did and what conclusions you reached. It is intended for managers who are not familiar with the details of solar processes but who have strong engineering backgrounds

The technical report itself should follow standard technical report format. It should include such items as the basis of the calculations, assumptions made, tables or charts of data, analysis of your results, notes of what might be done about practical problems such as boiling and freezing, and whatever else may be appropriate. It should be the kind of report you would prepare for your supervisor who has some familiarity with the technology.

# Nomenclature

## B.1 SYMBOLS

Below is a partial listing of symbols. Those that are used infrequently or in limited parts of the book are defined locally and do not appear on this list. In some cases references to the section where a symbol is defined or where there might be confusion about its significance are given in parentheses. A special table of radiation nomenclature is provided in Section B.2.

$A$	Area, auxiliary, altitude
$A_a$	Aperture area
$A_c$	Collector area
$A_i$	Anisotropy index (2.16)
$A_r$	Receiver area
$a$	Photovoltaic model curve-fitting parameter (23.2)
$a, b$	Coefficients in empirical relationships
$b_o$	Incidence angle modifier coefficient (6.17)
$C$	Cost, concentration ratio (7.2), capacitance rate (3.17), building thermal capacitance (9.5)
$C_A$	Cost per unit of collector area (11.1)
$C_E$	Cost of equipment (11.1)
$C_F$	Cost of energy from fuel (11.1)
$C_1, C_2$	Planck's first and second radiation constants
$C_b$	Bond conductance
$C_p$	Specific heat
$D$	Diameter (defined locally), down-payment fraction
$d$	Dust factor, market discount rate
$E$	Energy, equation of time
$E_g$	Bandgap energy (23.2)
$e$	Emissive power, base of natural logarithm
$F$	Fin efficiency factor (6.5), control function (defined locally)
$F'$	Collector efficiency factor (6.5)
$F''$	Collector flow factor (6.7)
$F_R$	Collector heat removal factor (6.7)
$F'_R$	Collector heat exchanger factor (10.2)
$F_{i-j}$	Diffuse energy leaving surface $i$ that is incident on surface $j$ without reflection/diffuse energy leaving surface $i$ (view factor)
$f$	Fraction, modulating factor (2.16), monthly solar fraction (10.10)

$f_i$	Fraction shaded (14.4)
$\mathcal{F}$	Annual fraction by solar energy (10.10)
$G$	Irradiance (see Section B.2)
$G_{sc}$	Solar constant, W/m <sup>2</sup>
$g$	Gravitational constant
$H$	Daily irradiation (see Section B.2)
$h$	Heat transfer coefficient, Planck's constant, hour
$h_{fi}$	Heat transfer coefficient inside tube or duct
$h_r$	Radiation heat transfer coefficient (3.10)
$h_w$	Wind heat transfer coefficient (3.15)
$I$	Hourly irradiation (see Section B.2), current (23.2)
$I_{Tc}$	Hourly critical radiation on tilted surface
$i$	Inflation rate
$K$	Extinction coefficient
$K_T$	Daily clearness index (2.11)
$\overline{K}_T$	Monthly average daily clearness index (2.12)
$K_{\tau\alpha}$	Incidence angle modifier (6.17)
$k$	Thermal conductivity, Boltzmann constant
$k_T$	Hourly clearness index (2.10)
$\overline{k}_T$	Monthly average hourly clearness index
$L$	Longitude, length, distance, loss, load
$\dot{L}$	Load rate
$L_0$	Load with zero area solar energy system
$L_A$	Load met by auxiliary energy
$L_S$	Load met by solar energy
$l$	Length, thickness
$m$	Mass, air mass, mean, mortgage interest rate
$\dot{m}$	Flow rate
$n$	Day of year (1.6), index of refraction, hours of bright sunshine in a day
$N$	Number of covers, day length, term of mortgage or economic analysis
$N_p$	Payback time
$P$	Power
$P_1$	Ratio of life-cycle fuel savings to first-year fuel energy cost (11.8)
$P_2$	Ratio of owning cost to initial cost (11.8)
$p$	Pressure, vapor pressure
$PWF$	Present-worth factor (11.8)
$Q$	Energy, energy per unit time
$q$	Energy per unit time per unit length or area
$R$	Ratio of total radiation on a tilted plane to that on the plane of measurement (usually horizontal) (2.15), heat transfer resistance
$\overline{R}$	Monthly average $R$ (2.19)
$R_b$	Ratio of beam radiation on a tilted plane to that on the plane of measurement (usually horizontal) (1.8)
$\overline{R}_b$	Monthly average $R_b$ (2.19)



$R_d$	Ratio of diffuse radiation on a tilted plane to that on the plane of measurement (usually horizontal)
$R_n$	Noon radiation ratio (2.24)
$ROI$	Return on investment (11.7)
$r$	Radius
$r_d$	Ratio of diffuse radiation in an hour to diffuse in a day
$r_r$	Mirror radius (7.9)
$r_t$	Ratio of total radiation in an hour to total in a day
$S$	Absorbed solar radiation per unit area
$\bar{S}$	Monthly average absorbed solar radiation per unit area (5.10)
$s$	Shade factor
$T$	Temperature
$T_{dp}$	Dew point temperature
$t$	Time
$U$	Overall heat transfer coefficient
$U_L$	Collector overall heat loss coefficient
$V$	Volume, velocity, voltage (23.2)
$v$	Specific volume
$W$	Distance between tubes
$X$	Dimensionless collector loss ratio (20.2)
$X'$	Modified dimensionless loss ratio (21.4)
$X_c$	Dimensionless critical radiation level (2.22)
$\bar{X}_c$	Monthly average critical radiation ratio (2.23)
$Y$	Dimensionless absorbed energy ratio (20.2, 21.3)

## Greek

$\alpha$	Absorptance, thermal diffusivity
$\alpha_s$	Solar altitude angle
$\alpha_o$	Object altitude angle
$\alpha_p$	Profile angle (1.9)
$\beta$	Slope
$\gamma$	Surface azimuth angle, bond thickness, intercept factors
$\gamma_s$	Solar azimuth angle (8.5)
$\gamma_o$	Object azimuth angle (1.9)
$\delta$	Declination, thickness (defined locally), dispersion
$\delta_{ij}$	Delta function: $\delta_{ij} = 1$ when $i = j$ and $\delta_{ij} = 0$ when $i \neq j$
$\varepsilon$	Emittance, effectiveness (3.17)
$\eta$	Efficiency (defined locally)
$\theta$	Angle (defined locally), angle between surface normal and incident radiation
$\theta_c$	Acceptance half-angle of compound parabolic concentrator (7.6)
$\theta_z$	Zenith angle
$\lambda$	Wavelength
$\lambda_c$	Cutoff wavelength of selective surface
$\mu$	Absolute viscosity, cosine of polar angle

$\nu$	Kinematic viscosity, frequency
$\rho$	Reflectance, density
$\sigma$	Stefan-Boltzmann constant, standard deviation
$\tau$	Transmittance
$\phi$	Latitude, angle (defined locally), utilizability (2.22)
$\phi_r$	Rim angle (7.9)
$\psi$	Angle (defined locally), ground coverage of collector array
$\omega$	Hour angle, solid angle
$\omega_s$	Sunset (or sunrise) hour angle

## Subscripts

$A$	Auxiliary
$a$	Air, ambient, absorbed, aperture, annual
$b$	Blackbody, beam, back, bond, bed
$c$	Collector, critical, cover, corrected, cold
$d$	Diffuse, day
$e$	Effective, equivalent, edge
$f$	Fin, fluid, fuel
$g$	Glass, ground, glazing
$h$	Hot
$i$	Incident, inlet
$l$	Loss
$m$	Moving, mean
$n$	Normal, noon
$o$	Overall, out, extraterrestrial
$p$	Plate
$r$	Radiation, reflected, receiver
$s$	Storage, sunset, specular, scattered
$T$	Tilted
$t$	Top
$u$	Useful
$w$	Wind
$z$	Zenith
$\lambda$	Wavelength

## B.2 RADIATION NOMENCLATURE (SEE SECTION 1.5)

$G$	Irradiance ( $\text{W}/\text{m}^2$ )
$H$	Irradiation for a day ( $\text{J}/\text{m}^2$ ); can also be considered as an average daily rate ( $\text{J}/\text{day m}^2$ )
$I$	Irradiation for an hour ( $\text{J}/\text{m}^2$ ); can also be considered as an average hourly rate ( $\text{J}/\text{h m}^2$ )

**Subscripts**

$b$	Beam
$d$	Diffuse
$n$	Normal
$T$	On tilted plane
$o$	Extraterrestrial

The absence of subscript  $b$  or  $d$  means total radiation. The absence of subscript  $n$  or  $T$  means radiation on a horizontal surface. A “bar” above  $G$ ,  $H$  or  $I$  means monthly average.

**Examples**

$G_o$	Extraterrestrial irradiance on horizontal plane
$I_d$	An hour’s diffuse radiation on a horizontal plane
$\overline{H}_b$	Monthly average daily beam radiation on a horizontal surface
$\overline{H}_T$	Monthly average daily radiation (beam plus diffuse) on a tilted plane

# International System of Units

## BASIC UNITS

Meter, m	Length
Kilogram, kg	Mass
Second, s	Time
Kelvin, K	Temperature

## DERIVED UNITS

All other units are derived from basic and supplementary units. Some derived units have special names.

The following decimal prefixes are recommended for use with the International System of Units (SI):

Tera	T	$10^{12}$	Giga	G	$10^9$
Mega	M	$10^6$	Kilo	k	$10^3$
Milli	m	$10^{-3}$	Micro	$\mu$	$10^{-6}$
Nano	n	$10^{-9}$	Pico	p	$10^{-12}$
Femto	f	$10^{-15}$	Atto	a	$10^{-18}$

The use of the following prefixes should be limited:

Hecto	h	$10^2$	Deca	da	10
Deci	d	$10^{-1}$	Centi	c	$10^{-2}$

## SOME CONVERSIONS OF UNITS

Exact conversion factors are indicated by an asterisk.

- **Length: m, m/s**

$$1 \text{ ft} = 0.3048 \text{ m}^*$$

$$1 \text{ in} = 25.4 \text{ mm}^*$$

$$1 \text{ mile} = 1.609 \text{ km}$$

$$1 \text{ ft/min} = 0.00508 \text{ m/s}^*$$

$$1 \text{ mile/h} = 0.4770 \text{ m/s}$$

$$1 \text{ km/h} = 0.27778 \text{ m/s}$$

- **Area:  $\text{m}^2$**

$$1 \text{ ft}^2 = 0.09290304 \text{ m}^2^*$$

$$1 \text{ in.}^2 = 0.00064516 \text{ m}^2^*$$

$$1 \text{ mile}^2 = 2.590 \text{ km}^2$$

- **Volume:  $\text{m}^3$ ,  $\text{m}^3/\text{kg}$ ,  $\text{m}^3/\text{s}$**

$$(\text{Note: } 1 \text{ liter} = 10^{-3} \text{ m}^3.)$$

$$1 \text{ ft}^3 = 28.32 \text{ liters}$$

$$1 \text{ U.K. gal} = 4.546 \text{ liters}$$

$$1 \text{ U.S. gal} = 3.785 \text{ liters}$$

$$1 \text{ ft}^3/\text{lb} = 0.006243 \text{ m}^3/\text{kg}$$

$$1 \text{ cfm} = 0.4719 \text{ liter/s}$$

$$1 \text{ U.K. gpm} = 0.07577 \text{ liter/s}$$

$$1 \text{ U.S. gpm} = 0.06301 \text{ liter/s}$$

$$1 \text{ cfm/ft}^2 = 5.080 \text{ liters/m}^2 \text{ s}$$

- **Mass: kg,  $\text{kg}/\text{m}^3$ ,  $\text{kg}/\text{s}$ ,  $\text{kg}/\text{m}^2 \text{ s}$**

$$1 \text{ lb} = 0.45359237 \text{ kg}^*$$

$$1 \text{ oz} = 28.35 \text{ g}$$

$$1 \text{ lb/ft}^3 = 16.02 \text{ kg/m}^3$$

$$1 \text{ g/cm}^3 = 10^3 \text{ kg/m}^3$$

$$1 \text{ lb/h} = 0.0001256 \text{ kg/s}$$

$$1 \text{ lb/ft}^2 \text{ h} = 0.001356 \text{ kg/m}^2 \text{ s}$$

- **Force: Newton  $\text{N} = \text{kg m} / \text{s}^2$ ,  $\text{N/m}$**

- **Pascal  $\text{Pa} \equiv \text{N/m}^2$**

$$1 \text{ lbf} = 4.448 \text{ N}$$

$$1 \text{ lbf/ft} = 14.59 \text{ N/m}$$

$$1 \text{ dyne/cm} = 1 \text{ (mN)/m}$$

$$1 \text{ mm H}_2\text{O} = 9.80665 \text{ Pa}^*$$

$$1 \text{ bar} = 10^5 \text{ Pa}$$

$$1 \text{ psi} = 6.894 \text{ kPa}$$

$$1 \text{ in. H}_2\text{O} = 249.1 \text{ Pa}$$

$$1 \text{ mm Hg} = 133.3 \text{ Pa}$$

$$1 \text{ in. Hg} = 3.378 \text{ kPa}$$

$$1 \text{ atm} = 101.325 \text{ kPa}^*$$

• **Energy: Joule  $J \equiv \text{Nm} = \text{Ws}$ ,  
 $J / \text{kg}$ ,  $J/\text{kg } ^\circ\text{C}$**

$$1 \text{ kWh} = 3.6 \text{ MJ}^*$$

$$1 \text{ Btu} = 1.055 \text{ kJ}$$

$$1 \text{ therm} = 105.5 \text{ MJ}$$

$$1 \text{ kcal} = 4.1868 \text{ kJ}^*$$

$$1 \text{ Btu/lb} = 2.326 \text{ kJ/kg}^*$$

$$1 \text{ Btu/lb } ^\circ\text{F} = 4.1868 \text{ kJ/kg } ^\circ\text{C}^*$$

$$1 \text{ Btu/ft}^2 = 0.01136 \text{ MJ/m}^2$$

$$1 \text{ cal/cm}^2 = 1 \text{ langley} = 0.04187 \text{ MJ/m}^2$$

• **Power: Watt  $W \equiv J/s = \text{Nm/s}$ ,  
 $W/\text{m}^2$ ,  $W/\text{m}^2 ^\circ\text{C}$ ,  $W/\text{m } ^\circ\text{C}$**

$$1 \text{ Btu/h} = 0.2931 \text{ W}$$

$$1 \text{ kcal/h} = 1.163 \text{ W}^*$$

$$1 \text{ hp} = 0.7457 \text{ kW}$$

$$1 \text{ ton refr.} = 3.517 \text{ kW}$$

$$1 \text{ W/ft}^2 = 10.76 \text{ W/m}^2$$

$$1 \text{ Btu/h ft}^2 ^\circ\text{F} = 5.678 \text{ W/m}^2 ^\circ\text{C}$$

$$1 \text{ Btu/h ft } ^\circ\text{F} = 1.731 \text{ W/m } ^\circ\text{C}$$

$$1 \text{ Btu/h ft}^2 ^\circ\text{F/in.} = 0.1443 \text{ W/m } ^\circ\text{C}$$

$$1 \text{ Btu/ft}^2 \text{ h} = 3.155 \text{ W/m}^2$$

• **Viscosity:  $\text{Pa s} = \text{N s/m}^2 = \text{kg/m s}$**

$$1 \text{ cP (centipoise)} = 10^{-3} \text{ Pa s}$$

$$1 \text{ lbf h/ft}^2 = 0.1724 \text{ MPa s}$$

## Meteorological Data

Previous editions of this book included an extensive meteorological database. These data were subject to change as additional measurements became available, as further refinements were made in the processing of existing data, and as the inevitable errors were uncovered and corrected. For many years obtaining reliable weather data was difficult and time consuming. In recent years data have been made instantly available on the Internet by national weather services, research laboratories, and commercial organizations. When designing a solar system the best data should always be used. Since data in a book are old when the book is published, it was decided to include only a limited data set.

The meteorological data in this appendix are used in example problems in the text, in designing typical systems by the methods presented in Part III, and for use in exercises in Appendix A. The data include  $\overline{H}$ , the monthly average daily radiation on a horizontal surface, in MJ/m<sup>2</sup>;  $\overline{K}_T$ , the monthly average clearness index;  $\overline{T}$ , the 24-h monthly average ambient temperature, in °C; and  $DD$ , the average number of degree-days in the month to the base temperature 18.3°C.

The data for the U.S. stations are from the SOLMET program (Cinquenami et al., 1978); the Canadian data are from the *Canadian Climate Normals* (1982); the European radiation data are from the CEC's *European Solar Radiation Atlas* (1984); the remaining world radiation data are from the *Solar Radiation and Radiation Balance Data (The World Network)* (1970, 1976, 1982); and the temperature data are from *World Weather Records* (1965). All of the degree-days are calculated by the method presented in Section 9.3.

Weather data for the United States were rehabilitated in 1992 by the National Renewable Energy Laboratory (formerly the Solar Energy Research Institute) as part of the *National Solar Radiation Data Base* (2008) effort. These data are available at <http://rredc.nrel.gov/solar/>. For worldwide data the METEONORM data set is particularly useful and is periodically updated.

The table is arranged alphabetically by region: Africa, Asia, Europe, North America, Pacific, and South America. Within each region stations are grouped by country (and state or province for the United States and Canada.)

## REFERENCES

- Canadian Climate Normals, 1951–1980*, Vol. 1, *Solar Radiation*, Vol. 2, *Temperatures*, Ministry of Supply and Services Canada, Ottawa (1982).
- (CEC), Commission of the European Communities, *European Solar Radiation Atlas*, Vol. 1, *Global Radiation on Horizontal Surfaces*, Vol. 2, *Inclined Surfaces* (W. Palz, ed.), Verlag TÜ V Rheinland, Köln (1984).

Cinquemani, V., J. Owenby, and R. G. Baldwin, report prepared for U.S. Department of Energy by the National Oceanic and Atmospheric Administration (1978). "Input Data for Solar Systems." *METEONORM, Global Meteorological Database for Applied Climatology*, available from Meteotest, Bern, Switzerland.

*National Solar Radiation Data Base User's Manual (1961–1990)*, (2008), available from <http://redc.nrel.gov/solar/>.

*World Weather Records, 1951–1960*, Vols. 1–6, U.S. Government Printing Office, Washington, DC (1965).

*Solar Radiation and Radiation Balance Data (The World Network)*, 1964–1968 (1970), 1969–1973 (1976), 1974–1979 (1982), Hydrometeorological Publishing House, Leningrad.

### **AFRICA**

#### **-Egypt-**

Cairo

#### **-South Africa**

Pretoria

### **ASIA**

#### **-India-**

New Delhi

#### **-Singapore-**

Singapore

### **EUROPE**

#### **-Belgium-**

Brussels

#### **-Germany-**

Stuttgart

#### **-Greece-**

Athens

#### **-Russia-**

Moscow

#### **-Spain-**

Almeria

#### **-Ukraine-**

Kiev

### **NORTH AMERICA**

#### **Canada**

#### **-Manitoba-**

Winnipeg

#### **-Ontario-**

Ottawa

#### **Caribbean**

San Juan, PR

#### **Mexico**

Ciudad University

#### **United States**

#### **-Alaska-**

Fairbanks

#### **-Arizona-**

Phoenix

#### **-California-**

Fresno

#### **-Colorado-**

Denver

#### **-Georgia-**

Atlanta

#### **-Hawaii**

Honolulu

#### **-Illinois**

Springfield

#### **-Massachusetts-**

Boston

#### **-Nevada-**

Reno

#### **-New Mexico-**

Albuquerque

#### **-New York-**

New York (CentralPark)

#### **-Oregon-**

Portland

#### **-Texas-**

Austin

#### **-Wisconsin-**

Madison

### **PACIFIC**

#### **-Australia-**

Aspendale

### **SOUTH AMERICA**

#### **-Argentina-**

Buenos Aires

#### **-Venezuela-**

Caracas

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
<b><u>Africa</u></b>												
<b>Egypt</b>												
Cairo				Latitude			30.0		Longitude			31.2
$\overline{H}$	11.84	15.60	19.32	23.15	26.32	27.95	27.10	25.23	21.97	17.86	13.24	11.12
$\overline{K}_T$	.56	.60	.61	.63	.66	.68	.67	.66	.66	.65	.59	.56
$\overline{T}$	14	15	17	21	25	27	28	28	26	24	19	15
$DD$	143	104	69	12	1	0	0	0	0	2	32	116
<b>South Africa</b>												
Pretoria				Latitude			−25.8		Longitude			28.1
$\overline{H}$	23.39	22.40	20.24	16.68	15.29	14.17	15.28	17.79	20.41	21.88	23.60	24.53
$\overline{K}_T$	.55	.56	.57	.57	.65	.67	.69	.67	.63	.57	.57	.57
$\overline{T}$	21	21	20	17	13	10	10	13	16	20	20	21
$DD$	11	9	20	64	170	250	259	170	86	20	18	11
<b><u>Asia</u></b>												
<b>India</b>												
New Delhi				Latitude			28.6		Longitude			77.1
$\overline{H}$	11.34	13.81	16.15	19.88	21.10	18.69	18.03	16.88	18.04	15.60	12.39	10.52
$\overline{K}_T$	.51	.52	.50	.54	.53	.46	.45	.44	.53	.55	.54	.51
$\overline{T}$	15	18	23	29	33	35	31	30	30	26	20	16
$DD$	132	52	5	0	0	0	0	0	0	0	20	87
<b>Singapore</b>												
Singapore				Latitude			1.0		Longitude			103.6
$\overline{H}$	16.71	17.64	17.88	16.69	15.40	15.11	15.59	15.78	16.24	15.63	13.90	14.37
$\overline{K}_T$	.47	.47	.47	.45	.44	.45	.45	.44	.44	.42	.39	.41
$\overline{T}$	26	26	27	27	27	28	27	27	27	27	26	26
$DD$	0	0	0	0	0	0	0	0	0	0	0	0
<b><u>Europe</u></b>												
<b>Belgium</b>												
Brussels				Latitude			50.8		Longitude			4.2
$\overline{H}$	2.29	4.53	7.93	12.38	16.46	17.72	16.71	14.71	10.87	6.26	3.00	1.77
$\overline{K}_T$	.27	.32	.36	.40	.43	.43	.42	.43	.43	.38	.30	.24
$\overline{T}$	4	3	7	9	12	17	16	17	16	11	6	3
$DD$	455	424	368	285	218	98	115	95	110	242	371	474
<b>Germany</b>												
Stuttgart				Latitude			48.5		Longitude			9.1
$\overline{H}$	3.47	5.98	9.60	14.59	17.87	19.43	19.55	16.12	13.07	7.99	3.94	2.72
$\overline{K}_T$	.35	.39	.42	.46	.46	.47	.49	.47	.50	.45	.35	.32
$\overline{T}$	−0	3	8	9	13	17	18	19	16	11	5	3
$DD$	576	425	324	284	161	66	54	35	95	239	402	471
<b>Greece</b>												
Athens				Latitude			38.0		Longitude			23.4
$\overline{H}$	6.57	9.40	13.59	18.08	22.56	24.72	24.86	22.28	17.59	12.22	8.18	6.09
$\overline{K}_T$	.40	.43	.48	.51	.57	.59	.61	.60	.57	.52	.46	.40
$\overline{T}$	10	10	11	15	20	25	28	28	23	19	14	11
$DD$	260	234	231	114	25	1	0	0	5	37	140	231



	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
<b>Russia</b>												
Moscow												
	Latitude						55.5		Longitude			37.4
$\overline{H}$	2.23	4.85	8.83	12.87	17.90	20.65	18.21	14.97	9.40	4.35	1.79	1.17
$\overline{K}_T$	.39	.44	.46	.44	.48	.50	.46	.46	.41	.32	.26	.26
$\overline{T}$	-10	-10	-4	5	12	17	19	17	11	5	-2	-7
DD	874	778	697	409	208	81	46	79	220	429	606	778
<b>Spain</b>												
Almeria												
	Latitude						36.8		Longitude			-2.3
$\overline{H}$	9.80	12.56	15.38	19.67	24.11	25.97	26.76	23.67	18.95	14.41	10.42	9.14
$\overline{K}_T$	.57	.56	.53	.56	.60	.62	.66	.64	.61	.60	.57	.58
$\overline{T}$	12	12	14	16	18	22	25	25	23	19	16	13
DD	220	195	157	107	68	23	9	8	14	53	117	191
<b>Ukraine</b>												
Kiev												
	Latitude						50.4		Longitude			30.3
$\overline{H}$	3.39	5.87	9.37	14.08	19.00	21.97	19.94	17.12	12.66	6.93	2.96	2.08
$\overline{K}_T$	.38	.41	.42	.45	.49	.53	.50	.50	.50	.42	.29	.28
$\overline{T}$	-6	-5	-1	8	15	19	20	19	14	8	1	-3
DD	756	658	583	323	132	48	27	40	139	337	507	657
<b>North America</b>												
<b>Canada</b>												
<b>Manitoba</b>												
Winnipeg												
	Latitude						49.9		Longitude			-97.1
$\overline{H}$	5.25	9.05	14.06	17.74	20.90	22.74	22.99	19.00	13.32	8.15	4.64	3.82
$\overline{K}_T$	.57	.62	.62	.56	.54	.55	.57	.55	.52	.48	.44	.49
$\overline{T}$	-19	-16	-8	3	11	17	20	18	12	6	-5	-14
DD	1165	949	821	448	229	88	45	65	191	381	684	1001
<b>Ontario</b>												
Ottawa												
	Latitude						45.5		Longitude			-75.4
$\overline{H}$	5.74	9.44	13.61	16.75	19.88	21.37	21.28	18.11	13.36	8.58	4.72	4.33
$\overline{K}_T$	.48	.54	.55	.51	.51	.51	.53	.51	.48	.44	.36	.41
$\overline{T}$	-11	-9	-3	6	13	18	21	19	15	9	2	-7
DD	896	770	651	377	181	58	27	42	132	308	498	793
<b>Caribbean</b>												
<b>Puerto Rico</b>												
San Juan												
	Latitude						18.4		Longitude			-66.0
$\overline{H}$	15.05	17.44	20.30	21.47	20.58	20.63	21.27	20.87	19.00	17.20	15.53	14.03
$\overline{K}_T$	.54	.56	.58	.57	.53	.53	.55	.55	.53	.53	.54	.53
$\overline{T}$	24	24	25	25	26	27	27	27	27	27	26	25
DD	18	14	15	11	9	6	6	6	6	7	9	14
<b>Mexico</b>												
Ciudad University												
	Latitude						19.4		Longitude			-99.1
$\overline{H}$	16.48	18.28	21.36	21.84	20.05	19.62	18.48	17.70	15.88	16.48	15.69	15.59
$\overline{K}_T$	.60	.59	.61	.58	.51	.50	.47	.46	.44	.51	.56	.60
$\overline{T}$	12	14	16	17	17	17	16	16	16	15	13	12
DD	194	130	82	57	53	59	87	87	91	119	154	191

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
<b>United States</b>												
<b>Alaska</b>												
Fairbanks												
				Latitude			64.8		Longitude			−147.5
$\overline{H}$	0.34	2.51	7.66	13.55	18.21	19.89	17.51	12.69	8.05	3.32	0.84	0.02
$\overline{K}_T$	.28	.45	.55	.54	.51	.48	.46	.43	.45	.42	.40	.05
$\overline{T}$	−24	−19	−13	−2	9	15	16	13	7	−4	−16	−24
$DD$	1323	1050	955	602	316	140	126	194	350	685	1035	1299
<b>Arizona</b>												
Phoenix												
				Latitude			33.4		Longitude			−112.1
$\overline{H}$	11.60	15.60	20.59	26.73	30.38	31.10	28.23	26.02	22.88	17.90	13.06	10.57
$\overline{K}_T$	.60	.65	.68	.74	.76	.75	.69	.69	.71	.69	.64	.59
$\overline{T}$	11	13	15	20	25	29	33	32	29	22	15	11
$DD$	251	175	134	52	14	2	0	1	2	28	128	233
<b>California</b>												
Fresno												
				Latitude			36.8		Longitude			−119.5
$\overline{H}$	7.45	11.49	17.78	23.75	28.19	31.02	30.47	27.51	22.54	16.22	10.09	6.52
$\overline{K}_T$	.43	.52	.62	.67	.71	.74	.75	.74	.72	.67	.55	.41
$\overline{T}$	7	10	12	16	20	23	27	26	23	18	12	8
$DD$	347	247	212	122	57	20	6	10	21	85	213	337
<b>Colorado</b>												
Denver												
				Latitude			39.8		Longitude			
$\overline{H}$	9.54	12.79	17.37	21.33	24.24	26.68	25.80	23.21	19.60	14.77	10.03	8.30
$\overline{K}_T$	.62	.62	.63	.62	.61	.64	.63	.63	.65	.65	.61	.60
$\overline{T}$	−1	0	3	9	14	19	23	22	17	11	4	0
$DD$	609	505	488	308	182	80	37	45	109	251	433	563
<b>Georgia</b>												
Atlanta												
				Latitude			33.7		Longitude			−105.0
$\overline{H}$	8.14	11.00	14.80	19.14	21.05	21.73	20.57	19.39	16.14	13.62	10.02	7.66
$\overline{K}_T$	.43	.46	.49	.53	.53	.52	.51	.52	.50	.53	.50	.43
$\overline{T}$	6	7	11	16	21	24	26	25	22	17	11	6
$DD$	393	315	252	108	41	12	8	9	23	99	239	375
<b>Hawaii</b>												
Honolulu												
				Latitude			21.3		Longitude			−157.5
$\overline{H}$	13.39	15.85	18.41	20.39	22.13	22.75	22.73	22.32	20.55	17.48	14.37	12.86
$\overline{K}_T$	.51	.53	.54	.54	.56	.57	.58	.58	.58	.56	.53	.51
$\overline{T}$	22	22	23	24	25	26	27	27	27	26	25	23
$DD$	15	12	13	8	5	2	2	1	1	3	5	11
<b>Illinois</b>												
Springfield												
				Latitude			39.8		Longitude			−89.4
$\overline{H}$	6.63	9.77	12.97	17.20	21.17	23.80	23.36	20.50	16.50	12.13	7.68	5.57
$\overline{K}_T$	.43	.47	.47	.50	.53	.57	.57	.56	.55	.54	.46	.40
$\overline{T}$	−3	−1	4	12	17	23	25	24	20	14	6	−1
$DD$	657	538	443	212	85	18	10	14	47	167	387	592

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
Massachusetts													
Boston	Latitude				42.4				Longitude				−71.0
$\overline{H}$	5.40	8.05	11.54	15.05	18.40	20.63	19.85	16.88	14.30	10.10	5.71	4.58	
$\overline{K}_T$	.39	.42	.44	.44	.47	.49	.49	.47	.49	.48	.38	.37	
$\overline{T}$	−2	−1	3	9	15	20	23	22	18	13	7	1	
$DD$	618	538	464	279	139	40	17	24	67	184	335	549	
Nevada													
Reno	Latitude				39.5				Longitude				−119.5
$\overline{H}$	9.09	13.05	18.72	24.51	28.65	30.67	30.55	27.31	22.67	16.24	10.36	8.01	
$\overline{K}_T$	.59	.63	.68	.71	.72	.73	.75	.74	.75	.71	.62	.57	
$\overline{T}$	−0	3	5	8	13	16	21	19	16	10	4	1	
$DD$	572	436	428	309	196	102	37	54	115	262	417	550	
New Mexico													
Albuquerque	Latitude				35.1				Longitude				−106.4
$\overline{H}$	11.54	15.23	20.06	25.30	28.82	30.41	28.25	26.00	22.39	17.56	12.87	10.53	
$\overline{K}_T$	.63	.66	.68	.71	.72	.73	.69	.70	.70	.70	.66	.63	
$\overline{T}$	2	4	8	13	19	24	26	25	21	15	7	2	
$DD$	513	391	333	171	63	11	5	8	27	142	346	498	
New York													
New York	Latitude				40.8				Longitude				−73.6
$\overline{H}$	5.68	8.19	11.77	15.48	18.57	19.41	19.16	16.83	13.78	10.17	6.05	4.59	
$\overline{K}_T$	.39	.41	.43	.45	.47	.46	.47	.46	.46	.46	.38	.35	
$\overline{T}$	0	1	5	11	17	22	25	24	20	15	9	2	
$DD$	568	493	418	236	116	38	20	26	58	158	306	514	
Oregon													
Portland	Latitude				45.6				Longitude				−122.4
$\overline{H}$	3.52	6.29	10.15	14.85	18.88	20.12	23.13	19.00	13.81	8.21	4.40	2.95	
$\overline{K}_T$	.30	.37	.41	.45	.48	.48	.57	.54	.50	.42	.34	.29	
$\overline{T}$	3	6	8	10	14	17	20	19	17	12	7	5	
$DD$	464	347	337	251	167	94	51	55	93	209	332	422	
Texas													
Austin	Latitude				30.3				Longitude				−97.5
$\overline{H}$	9.81	12.77	16.22	18.22	20.81	23.52	23.90	21.92	18.23	15.13	11.20	9.37	
$\overline{K}_T$	.47	.50	.52	.50	.52	.57	.59	.58	.55	.55	.51	.47	
$\overline{T}$	10	12	15	20	24	28	29	29	26	21	15	11	
$DD$	280	202	141	51	20	6	3	3	9	43	139	239	
Wisconsin													
Madison	Latitude				43.13				Longitude				−89.33
$\overline{H}$	6.44	9.89	12.86	16.05	21.36	23.04	22.58	20.33	14.59	10.48	6.37	5.74	
$\overline{K}_T$	.47	.52	.48	.47	.54	.55	.55	.56	.49	.48	.42	.47	
$\overline{T}$	−8	−5	1	9	14	19	22	20	15	11	2	−5	
$DD$	821	656	537	280	136	30	1	25	103	232	479	699	

Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec

**Pacific**

**Australia**

Melbourne	Latitude				−37.5				Longitude				144.6
$\overline{H}$	24.74	21.91	17.06	11.31	7.67	6.40	7.12	9.45	13.36	18.07	22.09	24.31	
$\overline{K}_T$	.57	.57	.54	.48	.45	.46	.47	.46	.48	.50	.53	.55	
$\overline{T}$	20	20	18	15	13	10	10	11	12	14	16	18	
$DD$	19	18	39	107	184	244	271	244	181	133	80	39	

**South America**

**Argentina**

Buenos Aires	Latitude				−34.6				Longitude				−58.3
$\overline{H}$	25.20	22.91	18.51	13.44	9.69	7.40	8.18	11.49	15.00	18.93	23.95	24.73	
$\overline{K}_T$	.58	.59	.57	.54	.51	.46	.48	.52	.51	.52	.57	.56	
$\overline{T}$	24	23	21	16	13	11	11	12	14	17	20	22	
$DD$	2	3	12	87	170	222	229	200	137	68	19	7	


**Venezuela**

Caracas	Latitude				10.5				Longitude				−66.6
$\overline{H}$	14.65	16.15	16.94	16.24	15.92	16.05	16.86	17.10	16.82	15.11	14.22	13.50	
$\overline{K}_T$	.46	.47	.46	.43	.42	.43	.45	.45	.45	.43	.44	.44	
$\overline{T}$	19	20	21	22	22	22	21	22	22	22	21	20	
$DD$	24	13	8	3	3	4	6	4	3	4	7	14	

## Average Shading Factors for Overhangs

The following charts show monthly average fraction of receiver area receiving beam radiation as a function of relative overhang dimensions for latitudes  $35^\circ$ ,  $45^\circ$ , and  $55^\circ$ . For use in the southern hemisphere, interchange months as shown in Figure 1.8.2. See Section 14.4 for methods of use of these factors and interpolation routines.

Utzinger, D. M., M.S. Thesis, Mechanical Engineering, University of Wisconsin-Madison (1979). “Analysis of Building Components Related to Direct Solar Heating of Buildings.”



**Figure E.1** Monthly mean fraction of vertical receiver area receiving beam radiation as function of relative overhang dimensions for latitude  $35^\circ$ . For the southern hemisphere interchange months as shown in Figure 1.8.2.




Figure E.1 (Continued)




Figure E.1 (Continued)






Figure E.1 (Continued)





Figure E.1 (Continued)



**Figure E.2** Monthly mean fraction of vertical receiver area receiving beam radiation as function of relative overhang dimensions for latitude  $45^\circ$ . For the southern hemisphere interchange months as shown in Figure 1.8.2.




Figure E.2 (Continued)




Figure E.2 (Continued)




Figure E.2 (Continued)





Figure E.2 (Continued)



**Figure E.3** Monthly mean fraction of vertical receiver area receiving beam radiation as function of relative overhang dimensions for latitude  $55^\circ$ . For the southern hemisphere interchange months as shown in Figure 1.8.2.






Figure E.3 (Continued)




Figure E.3 (Continued)




Figure E.3 (Continued)




Figure E.3 (Continued)

# Index

---

## A

- Abbot, C. G., 6, 44, 45
- Abbot silver disc pyrheliometer, 45
- Abdel-Khalik, S. I., 278, 398–400, 527–529
- Abetti, G., 354
- Absorbers (concentrating collectors), 322, 323
  - cylindrical absorber arrays, 323–337
  - tubular, with CPC reflectors, 344
- Absorptance:
  - cover systems, 206–211
  - opaque materials, 174–176
    - angular dependence of, 196–197
    - broadband, 182–183
    - calculation of, 183–186
    - of cavity receivers, 197–198
    - measurement of, 186–188
    - relationship of reflectance and, 181–182
  - passive room-window combinations, 554
- Absorption, 60
  - by blackbodies, 139
  - in CPC collectors, 345–349
  - through glazing, 206, 219–223
    - monthly average, 223–229
    - of photovoltaic cells, 231–234
    - of rooms, 229–230
- Absorption coolers, 576–578
  - applications of, 591
  - continuous, 576–577
  - intermittent, 577–578
  - operating experience with, 589–591
  - refrigeration, 575
  - simulation air conditioning study, 585–588
  - theory of, 578–584
  - types of, 576–578
- Acceptance angle (nonimaging concentrators), 338
- Actinometers, 44, 46, 47
- Active collection–passive storage (ACPS)
  - systems, 563–565
  - costs of, 572
  - design methods for, 736–742
- Active heating. *See also* Water heating
  - for building heating, 505–541
    - air systems, 507–509, 513–517
    - architectural considerations, 539–541
    - auxiliary energy during off-peak periods, 533–535
    - CSU House II air system, 513–517
    - CSU House III flat-plate liquid system, 511–513
    - economics of, 536–539
    - history of, 506–507
    - liquid systems, 509–511
    - modes of operation, 510–511
    - overheating, 535
    - parametric study of, 517–521
    - phase change storage systems, 527–529
    - seasonal energy storage systems, 530–533
    - solar energy-heat pump systems, 521–527
  - design methods for, 668–669
  - f*-chart method, 668–690
    - for air systems, 679–683
    - for liquid systems, 673–679
    - and parallel solar energy–heat pump systems, 686–690
    - results of, 685–686
    - for service water heating, 683–684
  - utilizability methods, 692–709
    - daily utilizability, 696–709
    - hourly utilizability, 693–696
- Advances in Solar Energy*, 745
- AEIC-EEI Heat Pump Committee, 622
- Afeef, M., 634
- Africa, weather data for, 865
- Agnihotri, O. P., 173, 188n.8
- AIA Research Corporation, 545, 566, 570
- Air heating:
  - building heating, 507–511, 513–517
    - active collection–passive storage systems, 563–564
    - CSU House II, 513–517
    - CSU House III, 511–513
  - energy storage in, 375
  - f*-chart method for, 679–683
  - flat-plate collectors, 312–313
    - flow rate data corrections, 306–307
    - thermal performance, 291, 299–300
  - for industrial processes, 604
    - open-circuit, 607–611
    - recirculating, 611–613
- Air mass, 9–10

- Ajami, F., 398  
 Akbarzadeh, A., 558  
 Alaska, weather data for, 866  
 ALCC (annualized life-cycle cost), 453  
 ALCS (annualized life-cycle savings), 453  
 Alexander, G., 622–624  
 Allen, R. W., 580  
 Altamont Pass, California, 777  
 American Society of Testing and Materials, 6  
 American Solar Energy Society, 544–545, 601  
 American Wind Energy Association, 775  
 Ammonia-water coolers, 580, 581  
 Anand, D. K., 665  
 Anderson, B., 546  
 Anderson, E. E., 30  
 Anderson, J. V., 686, 688, 689  
 Anderson, L. B., 539  
 Anderson, R., 571  
 Andrassy, S., 503  
 Angle(s) of incidence, 15, 202–203  
     defined, 13  
     and transmittance-absorptance product, 214–215  
 Angles of refraction, 202–203  
 Ångström, K., 45  
 Ångström compensating pyrheliometer, 45–46  
 Angular dependence:  
     and radiation transmission through glazing, 214–215  
     of solar absorptance, 196–197  
 Angular-hemispherical reflectance, 178, 186  
 Anisotropic sky, 91–97  
 Anisotropy index, 92  
*Annals of the International Geophysical Year (IGY)*, 49, 51  
 Annual cash flow (savings), 466–467  
 Annualized life-cycle cost (ALCC), 453  
 Annualized life-cycle savings (ALCS), 453  
 Antifreeze loop/heat exchanger systems, 424, 480, 481, 484  
 Aperture:  
     concentrating collectors, 323, 324  
     solar, 713, 714  
 Aquifer energy storage, 396  
 Architectural considerations:  
     with active heating, 539–541  
     overhangs and wingwalls, 34–35  
     with passive heating, 544  
 Area concentration ratio, 325  
 Argentina, weather data for, 869  
 Arizona, weather data for, 866  
 Arnold, J. N., 154, 155, 157  
 Army, M. D., 410  
 ASHRAE, 290, 409, 415, 418, 622, 687, 728  
*ASHRAE Cooling and Heating Load Calculation Manual*, 412  
*ASHRAE Handbook of Fundamentals*, 412, 416, 546, 576  
 ASHRAE standard atmosphere, 70–71  
 Asia, weather data for, 865  
*ASME Journal of Solar Energy Engineering*, 621  
 Aspliden, C. I., 779  
 Atacama Desert, Chile, solar ponds in, 646  
 Atmospheric attenuation, available solar radiation and, 43, 59–64  
 Attwater, C. R., 530  
 Augmentation of available radiation, 97–101  
 Australia, weather data for, 869  
 Auxiliary energy, 409  
     for building heating, 510, 546  
     for direct-gain systems, 555–557  
     and economics of passive heating, 572  
     electric, for off-peak active heating systems, 533–535  
     with vented vs. unvented storage walls, 558  
     for water heating, 479, 481, 486–488  
 Available solar radiation, 43–133  
     atmospheric attenuation, 43, 59–64  
     augmentation of, 97–101  
     beam and diffuse components of:  
         daily radiation, 77–79  
         hourly radiation, 74–77  
         monthly radiation, 79–81  
     data on, 54–59  
     definitions related to, 43–44  
     distribution of clear/cloudy days/hours, 71–74  
     estimation of:  
         average radiation, 64–68  
         clear-sky radiation, 68–71  
         hourly radiation, from daily data, 81–84  
     instruments for measuring:  
         duration of sunshine, 53  
         pyranometers, 48–53  
         pyrheliometers and pyrheliometric scales, 44–48  
     moving surfaces, beam radiation on, 101–103  
     and receiving surface orientation, 112–114

- on sloped surfaces, 84–89
  - anisotropic sky, 91–97
  - average radiation: isotropic sky, 103–106
  - average radiation: KT method, 107–112
  - isotropic sky, 89–90, 103–106
- utilizability, 115–118
  - daily, 126–132
  - generalized, 118–126
- Average solar radiation:
  - estimation of, 64–68
  - isotropic sky, 103–106
  - KT method, 107–112
  - monthly absorbed, 223–229
  - monthly mean daily radiation, 37–40
- B**
  - Bacon, F. T., 401
  - Baer, S., 527
  - Balcomb, J. D., 392, 413, 450, 558, 561, 571, 669, 712, 714–721
  - Balcomb house (New Mexico), 566, 568–569
  - Bankston, C., 530, 532, 533
  - Bankston, C. A., 394, 396
  - Bannerot, R. B., 101
  - Bannister, J. W., 77
  - Barakat, S. A., 417
  - Baranov, V. K., 338
  - Barber, R. E., 597
  - Barley, C. D., 450, 669
  - Battery storage, 402–406, 763
  - Batty, J. C., 637
  - Bauerle, G., 401
  - Baum, V. A., 594, 628
  - Beadwall panels, 546–547
  - Beam radiation:
    - clear-sky, 68–71
    - and collector performance prediction, 296–297
    - daily, 77–79
    - defined, 10
    - direction of, 12–20
    - hourly, 74–77
    - incidence angle modifier for, 289
    - monthly, 79–81
    - on moving surfaces, 101–103
    - ratio on tilted surfaces to horizontal surfaces, 23–29
  - Beckman, W. A., 104, 146, 197, 212, 239, 280, 297, 302, 336, 347, 425, 426, 449, 468, 471, 577, 668, 674, 679, 692, 700, 701, 705, 708, 709, 763, 771
  - Beekman, D. M., 597
  - Belgium, weather data for, 865
  - Bell, R., 193
  - Bellani spherical distillation pyranometer, 53
  - Belton, G., 398
  - Bendt, P., 74, 361, 669
  - Benford, F., 12
  - Bennett, I., 67
  - Benning, A. C., 192
  - Benseman, R. F., 81
  - Berdahl, P., 148
  - Biancardi, R., 597
  - Bin method, 687–690
  - Blackbodies, 139–140
    - radiation tables for, 142–144
    - total energy emitted by, 141–142
    - wavelengths of emissions from, 140–141, 188
  - Blinn, J. C., 581, 583
  - Bliss, R. W., 148, 275, 506, 600, 622
  - Bloch, M. R., 646, 647
  - Blytas, G. C., 577
  - Bock, J. E., 12
  - Bode, H., 402
  - Boeing, 368
  - Boiling protection (water heating), 483–486
  - Bond, J. A., 597
  - Bonds, L. P., 614
  - Bouguer's law, 206
  - Bowen, I. S., 646
  - Brandemuehl, M. J., 212, 347, 468, 471
  - Braun, J., 394, 530–532
  - Braun, J. E., 20, 491
  - Bridgers, F. H., 622
  - Brinkworth, B., 424
  - Broadband absorptance, 182–183
  - Broadband emittance, 182–183
  - Brunstrom, C., 395
  - Brunt, D., 148
  - Bryant, H. C., 634
  - Buchberg, H., 154, 654
  - Buckles, W. E., 488, 683
  - Buehl, W. M., 277
  - Buhrman, R. A., 192
  - Building heating:
    - active, 505–541
      - air systems, 507–509, 513–517
      - architectural considerations, 539–541
      - auxiliary electric energy during off-peak periods, 533–535
      - CSU House II air system, 513–517

Building heating (*continued*)

- CSU House III flat-plate liquid system, 511–513
  - economics of, 536–539
  - history of, 506–507
  - liquid systems, 509–511
  - modes of operation, 510–511
  - overheating of, 535
  - parametric study of, 517–521
  - phase change storage systems, 527–529
  - seasonal energy storage systems, 530–533
  - solar energy-heat pump systems, 521–527
- combined solar heating and cooling systems, 584–585
- CombiSys space heating subsystem, xx
  - degree-day method, 412–415
  - hybrid systems, 563–565, 736–743
    - active collection with passive storage, 736–742
    - both passive and full active heating systems, 742–743
  - passive, 544–563, 711–735
    - applications of, 565–570
    - approaches to, 711–712
    - collector-storage walls and roofs, 557–561
    - comfort criteria, 546
    - concepts of, 545–546
    - costs and economics of, 571–573
    - direct gain systems, 229–230, 552–557
    - heat distribution in, 571
    - heating loads, 546
    - movable insulation and controls, 546–547
    - shading, 547–552
    - solar-load ratio method, 712–721
    - and storage media performance, 373
    - sunspaces, 561–563
    - unutilizability design method, 721–735
  - simulation of, xix–xxiv
- Building loss coefficients, 415–417
- Building thermal capacitance, 417
- Butso, K. D., 413
- Butz, L. W., 581, 654

## C

- Cabot, Godfrey L., 506
- California, weather data for, 866
- Campbell Soup Co., 614
- Campbell-Stokes sunshine recorder, 53
- Canada, J. R., 447
- Canada, weather data for, 866

- Canadian Climate Normals*, 863
- Caracol, 646
- Caribbean, weather data for, 866
- Carlsson, B., 398
- Carvalho, M. J., 490
- Casamajor, A. B., 617
- Casella, 50
- Cavity receivers:
  - absorptance of, 197–198
  - with paraboloidal concentrators, 367
- CEC, *see* Commission of the European Communities
- Cell temperature (PV systems), 757–759
- Central-receiver collectors, 368–369
- Central-receiver systems, 628–629
- Chant, R. E., 77, 79, 132
- Charters, W. W. S., 154, 161, 392
- Chemical energy storage, 400–402
- Chiam, H. F., 101
- Chinnappa, J. C. V., 577
- Chiou, J. P., 280
- Choi, H., 160
- Choudhury, N. K. D., 77, 79
- Chow, S. P., 336, 337
- Chromosphere (sun), 5
- Chung, R., 576
- CHX, *see* Collector heat exchanger
- Cinquenami, V., 863
- Circumsolar diffuse radiation, 85
- Circumsolar ratio (CSR), 91
- Clark, D. R., 125, 765, 767, 768, 770
- Clear/cloudy days/hours, distribution of, 71–74
- Clearness indexes, 71–72
- Clear-sky radiation, estimation of, 68–71
- Close, D., 599
- Close, D. J., 192, 193, 195, 310, 429, 452, 481, 483, 491, 492, 506, 611, 653–654
- Coatings, high-absorptance, 192–193
- CoDoPro (Collector Design Program), 313
- Coefficient of performance (COP), 516, 522, 580
- Colbeck, I., 634
- Collares-Pereira, M., 77, 78n.12, 79, 80n.13, 81, 115, 692, 696
- Collection efficiency, 238
- Collectors. *See also individual types and specific components*
  - in CombiSys, xix–xx, 798
  - ICS water heaters, 494–496
  - loads and outputs of, 373–375
  - solar-mechanical systems, 621–622



- and storage unit design, 375
- tracking surface angles for, 20–23
- windows as, 545
- Collector Design Program (CoDoPro), 313
- Collector efficiency factor:
  - flat-plate collectors, 257–261
  - and liquid heater design, 275–277
- Collector flow factor, flat-plate collectors, 263–266
- Collector heat exchanger (CHX):
  - in CombiSys, xx
  - defined, 423
  - in liquid-based heating systems, 509–510
- Collector heat exchanger factor, 424–425
- Collector heat removal factor, flat-plate collectors, 262–266
- Collector-storage roofs:
  - costs of, 571
  - passive building heating systems, 557–561
- Collector-storage walls, 392–394
  - costs of, 571–572
  - defined, 545
  - design parameters for, 715
  - loss control with, 546
  - passive building heating systems, 557–561
  - unutilizability design method, 727–735
- Collector-tank heat exchanger, in CombiSys, 798
- Collier, R., K., 592
- Colorado, weather data for, 866
- Colorado State University (CSU):
  - CSU House I cooling, 582, 663
  - CSU House II air system, 513–517, 540, 599–600, 685
  - CSU House III flat-plate liquid system, 511–513, 589–591
- Combined solar heating and cooling, 584–585
- CombiSys, xix
  - collector heat exchanger in, xx
  - collector in, xix–xx
  - domestic hot water subsystem in, xx
  - finding/installing, 797–798
  - on-line plots, xxiii
  - output from, xxiii–xxiv
  - solar storage tank in, xx
  - space heating subsystem in, xx
  - weather data in, xix
- COMBISYS.OUT file, xxiii–xxiv
- Comfort criteria, for passive building heating systems, 546
- Commission of the European Communities (CEC), 55, 565, 570
- Commonwealth Scientific and Industrial Research Organization (CSIRO ), 493
- Component models (system thermal calculations), 422–423
- Compound parabolic concentrators (CPCs):
  - optical characteristics of, 338–344
  - orientation and absorbed energy for, 345–349
  - performance of, 332–334, 349–351
- Concentrating collectors, 322–370
  - central-receiver collectors, 368–369
  - compound parabolic concentrators:
    - optical characteristics of, 338–344
    - orientation and absorbed energy for, 345–349
    - performance of, 332–334, 349–351
  - concentration ratio, 325–327
  - configurations for, 323–325
  - cylindrical absorber arrays, 335–337
  - incidence angle modifiers and energy balances, 361–367
  - linear imaging concentrators:
    - geometry of, 351–354
    - imperfect, imaged from, 359–361
    - perfectly-oriented, images formed by, 354–359
  - nonimaging concentrators, 337–344
  - optical performance of, 334–335
  - paraboloidal concentrators, 367–368
  - practical considerations for, 369–370
  - ray-trace methods for evaluating, 361
  - thermal performance of, 327–334
  - types of, 322
- Concentration ratio:
  - concentrating collectors, 325–327, 368
  - defined, 322
  - variation in, 322
- Concentrators (in concentrating collectors), 322, 323
- Concentric cylinders, natural convection between, 153–154
- Connelly, M., 669
- Continuous absorption cycles (cooling), 576–577
- Controls:
  - collector-storage walls, 558
  - passive heating systems, 547, 558
  - photovoltaic systems, 763
  - system thermal calculations, 429–431

- Control function (CPC collectors), 346
  - Convection suppression, 154–158
  - Convective zone (sun), 4
  - Converse, A. O., 525, 622
  - Converters, photovoltaic, 746–747
  - Cook, F. W., 81
  - Cooling, 575–601
    - absorption coolers, 576–578
    - applications of, 591
    - operating experience with, 589–591
    - refrigeration, 575
    - simulation air conditioning study, 585–588
    - theory of, 578–584
    - types of, 576–578
    - combined solar heating and cooling, 584–585
    - desiccant cooling, 592–596
    - passive, 601
    - solar-mechanical, 596–599
    - solar-related methods, 599–601
    - and water heating, 497
  - Cooling loads, 417–418
  - Cooper, P. I., 13, 294–295, 491, 645
  - COP, *see* Coefficient of performance
  - Corona (sun), 5
  - Costs of solar process systems, 447–450.
    - See also* Economic evaluation
    - active heating systems, 536–537
    - flat-plate collector installation, 312
    - passive building heating systems, 571–573
  - Coulson, K. L., 9, 44, 48, 51, 52, 84–85, 92
  - Cover systems. *See also* Glazing, radiation transmission through
    - flat-plate collectors, 268–271, 278, 311
    - optical properties of, 206–211
    - refractive index of materials, 205–206
    - spectral dependence of transmittance, 215–218
    - for swimming pools, 502
  - CPCs, *see* Compound parabolic concentrators
  - Crawford, E., 159, 161, 163
  - Critical radiation level:
    - defined, 115
    - for flat-plate collectors, 266–267
  - CSIRO (Commonwealth Scientific and Industrial Research Organization), 493
  - CSR (circumsolar ratio), 91
  - CSU, *see* Colorado State University
  - Cummings, N. W., 647
  - Cuomo, J. J., 193
  - Cylindrical absorber arrays, for concentrating collectors, 335–337
  - Czapek, E. L., 546
  - Czarnecki, J. T., 114, 497
- D**
- Daily clearness index, 71
  - Daily utilizability, 126–132, 696–699
    - defined, 128–129
    - f*-chart method, 699–709
  - Dalenbäck, J.-O., 490, 532
  - Daniels, F., 577
  - Davey, E. T., 308, 309
  - Davies, J. A., 91
  - Davis, M. W., 758
  - Daylighting, 544
  - Declination, 12
  - Deflation, 455
  - De Garmo, E. P., 447
  - Degelman, L. O., 665
  - Degree-day method:
    - cooling, 418
    - for country weather data, 863
    - space heating, 412–415
  - DeJong, B., 56
  - Delyannis, E., 640
  - Denmark, wind energy in, 775
  - Denver bus maintenance facility, 609–611
  - Denver House, 512, 540
  - Desiccant cooling, 592–596
  - Design variables, economics of systems and, 450–452
  - Design year, 664, 665
  - DeSoto, W., 231, 753
  - Dewar collectors, 335–336
  - DeWinter, F., 424, 503
  - DeWitt, D. P., 153, 159
  - DHW, *see* Domestic hot water subsystem
  - Dickenson, W. W., 617
  - Dietz, A. G. H., 202, 216, 271, 546
  - Diffuse radiation:
    - circumsolar, 85
    - and collector performance prediction, 296–297
    - daily, 77–79
    - defined, 10
    - hourly, 74–77
    - monthly, 79–81
    - ratio on tilted surfaces to horizontal surfaces, 23
    - transmittance for, 211–213

Diffuse reflection, 177  
 Diffuse surfaces, 146  
 Direct-coupled systems, load characteristics for, 759–763  
 Direct gain, 545  
 Direct-gain systems:  
   for building heating, 552–557  
     absorptance of rooms, 229–230  
     unutilizability design method, 721–727  
   combined with ACPS, 565  
   design parameters for, 715  
   loss control in, 546  
   problems associated with, 570  
 Directional absorptance, 174  
 Directional emittance, 174  
 Directional selectivity, 193–194  
*Directory of SRCC Certified Solar Collector Ratings*, 299n.18, 300  
 Direct solar drying, 647  
 Direct solar radiation, *see* Beam radiation  
 Discounting, 454–456  
 Dispersion angle (linear imaging concentrators), 359  
 Distillation, 640–645  
 Doldrums, 778  
 Domestic hot water subsystem (DHW).  
   *See also* Water heating  
   in CombiSys, xx, 798  
   *f*-chart method for, 669–672, 685  
   low-flow systems, 479  
 “Double-U” design method, *see*  
   Unutilizability design method  
   (passive systems)  
 Drain-back (drain-down) systems, 484, 510–513  
 Drain-out systems, 484  
 Drummond, A. J., 6, 51  
 Dual-source solar energy–heat pump systems, 523, 524  
 Duct loss factors, 423, 426–429  
 Duffie, J. A., 77, 79, 239, 327, 361, 576, 686  
 Duffie, N. A., 611  
 Duncan, C. H., 6  
 Dunkle, R. V., 142, 166, 167, 192, 294–295, 308, 309, 592, 593, 642, 643  
 Dunn, J. R., 393  
 Duration of sunshine, instruments for measuring, 53  
 Dust, flat-plate collector performance and, 271–272

## E

Earth tempering, 601  
 Eckard, S. E., 597  
 Eckstein, J. H., 402, 747, 761, 765  
 Economic evaluation, 447–476  
   active collection–passive storage systems, 564  
   annual cash flow (savings), 466–467  
   building heating, 536–539  
   costs, 447–450  
   design variables, 450–452  
   discounting and inflation, 454–456  
   figures of merit for, 452–454  
   industrial process heat, 606–607  
   life-cycle savings method, 459–463  
    $P_1$ ,  $P_2$  method, 467–472  
   passive building heating, 571–573  
   payback time, 464–466  
   present-worth factor, 456–458  
   return on investment, 467  
   solar savings fraction in analysis of, 475  
   uncertainties in, 472–475  
   water heating, 499–501  
 Edwards, D. E., 367  
 Edwards, D. K., 154, 192, 195, 209  
 EES (Engineering Equation Solver), 240  
 Effectiveness-NTU method:  
   for heat exchangers, 168–170  
   for packed beds, 387–388  
 Effective transmittance-absorptance product (flat-plate collectors), 268–271  
 Efficiency tests (flat-plate collectors):  
   converting data from, 303–305  
   performing, 290–295  
 Egypt, weather data for, 865  
 Eibling, J. A., 20  
 Eldridge, F. R., 774  
 Electromagnetic spectrum, 138–139  
 Ellul, W. H. J., 166, 167  
 El Paso, Texas, solar pond in, 639–640  
 Elsherbiny, S. M., 158  
 El-Wakil, M. M., 774, 790  
 Emissive power, 10  
 Emittance, 174–176  
   by blackbodies, 140  
   broadband, 182–183  
   calculation of, 183–186  
   measurement of, 186–188  
   relationship of reflectance and, 181–182  
 ENERGY-10 program, 711

- Energy balances:
  - concentrating collectors, 361–367
  - direct-gain systems, 555
  - flat-plate collectors, 237–238
  - heat pump–solar energy heating system, 524
  - with hybrid heating systems, 565
  - industrial process heat storage, 605
  - and Kirchhoff's law, 176
  - solar ponds, 646
  - storage walls, 392
  - water storage tanks, 377–378
- Energy (product) storage, 373–406
  - active collection–passive storage systems, 563
  - active systems:
    - liquid systems, 676–679
    - phase change systems, 527–529
    - seasonal systems, 530–533
  - architectural considerations for, 541
  - battery storage, 402–406
  - chemical energy storage, 400–402
  - ICS water heaters, 494–496
  - for industrial process heat, 605
  - packed beds, 165–167, 384–391
  - passive building heating systems, 545
    - collector-storage walls and roofs, 557–561, 727–735
    - sunspaces, 229–230, 561–563
  - phase change energy storage, 396–400
  - photovoltaic systems, 763
  - seasonal storage, 394–396
  - solar process loads and collector outputs, 373–375
  - in solar process systems, 375–376
  - solar storage tank, xx
  - storage walls, 392–394
  - stratification in storage tanks, 379–384
  - water heating, 494–496
  - water storage, 376–379
- Engineering Equation Solver (EES), 240
- Eppler normal-incidence pyrheliometer (NIP), 46
- Eppler precision spectral pyranometer (PSP), 48, 49
- Eppler pyranometer, 48, 49, 51, 52
- Equilibrium (stagnation) temperatures, 310
- Erbs, D. G., 75, 76, 78, 80, 413, 418
- ERDA Solar Workshop, 629
- Etter, D. E., 639
- Europe, weather data for, 865–866
- European Solar Radiation Atlas*, 55, 109, 863
- European Union, 290
- Evans, B. L., 565, 736, 738–740, 742, 743
- Evans, D. L., 115, 354–357, 360, 765, 767, 768
- Evaporation, 646–647
- Evaporative processes:
  - direct solar drying, 647
  - distillation, 640–645
  - evaporation, 646–647
  - solar ponds, 635–640
    - applications of, 639–640
    - salt-gradient, 635–637
    - theory of, 637–639
- Experiments, simulations and, 655, 663
- Extraterrestrial radiation. *See also* Solar radiation
  - on horizontal surfaces, 37–41
  - spectral distribution of, 6–8
  - variation of, 8–9
  - wavelengths of, 188
- F**
- Fanger, P. O., 546
- Fanney, A. H., 231, 232, 685, 686, 745
- Farber, E. A., 70–71
- Farber, J., 503
- f*-chart method, 668–690
  - for air systems, 679–683
  - for liquid systems, 673–679
  - and parallel solar energy–heat pump systems, 686–690
  - results of, 685–686
  - for service water heating, 683–684
- Fender, D. A., 393
- Flat parallel plates, natural convection
  - between, 149–153
- Flat-plate collectors, 236–319
  - air heaters, 280–287
  - characterizing, 288–289
  - collector heat removal factor, 262–266
  - critical radiation level for, 266–267
  - CSU House III flat-plate liquid system, 511–513
  - described, 236–237
  - dust and shading effects, 271–272
  - effective transmittance-absorptance product, 268–271
  - energy balance equation for, 237–238
  - with flat covers vs. cylindrical covers, 278
  - flow distribution in, 308–309
  - flow factor, 263–266
  - heat capacity effects in, 272–275

- liquid heater plate geometries, 275–280
- mean fluid temperature, 267
- mean plate temperature, 267–268
- overall heat loss coefficient for, 240–254
- performance measurements for, 287–288
- practical considerations for, 310–313
- in situ performance, 309–310
- temperature distributions, 238–240
  - collector efficiency factor, 257–261
  - in flow direction, 261–262
  - between tubes, 254–261
- test data for, 289, 299–302
  - conversion of, 302–305
  - flow rate corrections, 305–307
- tests for, 289–298
  - basic method of testing, 290
  - efficiency tests, 290–295
  - general test procedure, 291
  - incident angle tests, 290, 295–297
  - time constant, 290, 297–298
- tube, 254–251, 275
- Flow direction:
  - in liquid heaters, 277
  - temperature distributions in, 261–262
- Flow distribution, in flat-plate collectors, 308–309
- Flow rates:
  - active air systems, 680–681
  - corrections of flat-plate collector test data, 305–307
  - low-flow hot-water systems, 479
- Flux concentration ratio, 325
- Forced-circulation systems (water heating), 479–481, 488–489
- Forristall, R., 327, 363
- Foskett, L. W., 53
- Foster, N. B., 53
- Foster sunshine switch, 53
- FPL Energy, 624
- Francey, J. L., 419
- Freeman, T. L., 525, 526
- Freeze protection (water heating), 483–484
- Freris, L. L., 780, 796
- Fresnel reflectors, 324
- Fritz, S., 60, 62
- Frohlich, C., 6, 9
- Fuel expense, 448–449, 538
- Fuess, 50
- Fujii, I., 401
- Funaro, G., 565
- Furbo, S., 481
- G**
- Garg, H. P., 10, 271, 491, 653
- Gari, H. N., 379, 380
- Gaul, H., 362
- Generalized utilizability, 118–126
- Generators, photovoltaic, 761–764
  - characteristics and models, 747–757
  - high-flux generators, 770–771
- Geological Survey, 646
- Georgia, weather data for, 866
- Germany, weather data for, 865
- Gier, J. T., 186, 192
- Gild Bend pumping system, 622–624
- Gillett, W. B., 289n.13, 291, 298, 745
- Gilon, Y., 625, 626
- Gilroy Foods, 615, 616
- Glass, 202
  - etched and unetched, 218–219
  - spectral transmittance of, 215–216
- Glazing, radiation transmission through, 202–234
  - absorption, 206, 219–223
  - monthly average, 223–229
  - of photovoltaic cells, 231–234
  - of rooms, 229–230
  - and building loss coefficients, 415
  - for collector-storage walls, 545
  - optical properties of cover systems, 206–211
  - and reflection of radiation, 202–206
  - spectral dependence of transmittance, 215–218
  - surface layers' effects on, 218–219
  - transmittance-absorptance product, 213–215
  - transmittance for diffuse radiation, 211–213
- Global radiation, 10
- Golding, P., 419
- Gold Kist soybean plant, 607–609
- Gordon, J., 763
- Gordon, J. M., 493
- Govaer, D., 502
- Graham, B. J., 615, 616
- Grashof number, 149
- Grassie, S. L., 101
- Gray surfaces, infrared radiation between, 146–147
- Greco, C., 566
- Greece, weather data for, 865
- Green Bay water heating plant, 615–617
- Grid-connected PV systems, 763
- Grimmer, C. P., 193
- Grimmer, D. P., 101

Groiss pyranometer, 48  
 Gross reference load, 713  
 Ground-reflected radiation:  
   and collector performance prediction, 296–297  
   thermal energy storage in, 395–396  
 Ground temperatures, 601  
 Gruntfest, I., 397  
 Gueymard, C., 63  
 Guinn, G. R., 607, 608, 617, 618  
 Gulachenski, E. M., 764  
 Gupta, B. K., 173, 188n.8  
 Gupta, C. L., 491, 653, 654  
 Gutierrez, G., 487

**H**

Hail damage, 311–312  
 Hall, B. R., 617, 618  
 Hall, I. J., 664  
 Hamid, Y. H., 280  
 Hamilton, D. C., 98  
 Harats, Y., 193, 195, 369, 625, 626  
 Harding, G. L., 193  
 Harrison, D., 546  
 Hatch, W. L., 413  
 Hatheway, F. M., 525  
 Hawaii, weather data for, 866  
 Hawley, R. W., 167  
 Hay, H. R., 560, 600  
 Hay, J. E., 85, 91  
 HDKR model, 91–93, 96, 97, 221–222  
 Heat capacity, of flat-plate collectors, 272–275  
 Heat distribution, in passive buildings, 571  
 Heat exchangers:  
   for active liquid systems, 677–679  
   antifreeze loop/heat exchanger systems, 424, 480, 481, 484  
   collector heat exchanger factor, 424–425  
   effectiveness-NTU calculations for, 168–170  
   in hot water systems, 481  
 Heating, *see* Active heating; Passive heating  
 Heating loads, in passive building heating systems, 546  
 Heat loss coefficient, overall, 240–254  
 Heaton, H. S., 159, 161  
 Heat pumps:  
   in active building heating/cooling systems, 521–527, 530  
   for cooling, 600  
   in parallel solar energy–heat pump systems, 686–690

Heat table method, 668  
 Heat transfer, 138–170  
   blackbodies, 139–140  
   convection suppression, 154–158  
   electromagnetic spectrum, 138–139  
   heat exchangers, 168–170  
   infrared radiation between gray surfaces, 146–147  
   internal flow coefficients, 159–163  
   natural convection:  
     between flat parallel plates, 149–153  
     between horizontal concentric cylinders, 153–154  
   photon radiation, 139  
   Planck's law, 140–141  
   and pressure drop:  
     in packed beds, 165–167  
     in perforated plates, 167–168  
   radiation flux, 144–146  
   radiation heat transfer coefficient, 147–149  
   radiation intensity, 144–146  
   radiation tables, 142–144  
   sky radiation, 147–148  
   Stefan-Boltzmann equation, 141–142  
   vee-corrugated enclosures, 158  
   Wien's displacement law, 140–141  
   wind convection coefficients, 163–165  
 Hedstrom, J. C., 669  
 Hemispherical absorptance, 175–176  
 Hemispherical-angular reflectance, 178, 186  
 Hemispherical emittance, 175–176  
 Hemispherical reflectances, 178–181  
 Henderson, J. B., 63  
 Herzog, M. E., 74, 109  
 Hickey, J. R., 6, 9  
 High-flux generators (PV systems), 770–771  
 Hildebrandt, A. F., 368  
 Hill, J. E., 289, 298–300  
 Hinterberger, H., 338, 343  
 Hodgins, J. W., 398  
 Hoffman, T. W., 398  
 Hohlraum, 186  
 Hollands, K. G. T., 74–76, 101, 150, 153, 154, 157, 194, 280, 324, 345n.9, 490, 491  
 Hollingsworth, F. M., 546  
 Honeywell, 199  
 Hooper, F. C., 530  
 Horizon brightening, 85  
 Horizontal concentric cylinders, natural convection between, 153–154

- Horizontal surfaces:
  - extraterrestrial radiation on, 37–41
  - ratio of beam radiation on tilted surfaces to, 23–29
- Hottel, H. C., 24n.7, 25, 68, 69, 81, 89, 115, 146, 192, 209, 238, 250, 271, 275, 287, 622, 692
- Hot-water loads, 410–412
- Hot water systems, *see* Water heating
- Hour angle, 13
- Hourly clearness index, 72
- Hourly radiation:
  - beam and diffuse components of, 74–77
  - estimation from daily data, 81–84
- Hourly utilizability, 693–696
- Howell, J. R., 101, 142, 146, 176, 202, 206, 209
- Huget, R. G., 74
- Hughes, P. J., 387–389, 533, 534
- Hull, D. E., 431
- Hull, J. R., 634–638
- Huxtable, D. D., 401
- Hybrid systems, 736–743
  - active collection with passive storage, 563–565, 736–742
  - both passive and full active heating systems, 565, 742–743
  - concepts related to, 545–546
- I**
- IAMs, *see* Incidence angle modifiers
- Ibáñez, M., 72
- Ibele, W. C., 621
- ICS (integral collector storage) systems, 494–496
- IEA (International Energy Agency), 301, 310
- IGY (Annals of the International Geophysical Year)*, 49, 51
- Illinois, weather data for, 866
- Imaging collectors, 326. *See also* Linear imaging concentrators
- Incidence angle modifiers (IAMs):
  - for concentrating collectors, 334–335, 361–367
  - defined, 223
  - for flat-plate collectors, 289
  - for photovoltaic panels, 232
- Incidence angle modifier coefficient, 295
- Incident angle tests, for flat-plate collectors, 290, 295–297
- Income tax savings, 449, 450, 500
- Incropera, F. P., 153, 159
- India, weather data for, 865
- Industrial process heat, 604–619
  - air heating:
    - open-circuit, 607–611
    - recirculating, 611–613
  - economics of, 606–607
  - integration of energy and processes, 604–605
  - mechanical design considerations, 605–606
  - water heating:
    - once-through, 613–614
    - recirculating, 615–617
    - shallow-pond, 617–619
- Infiltration, 416–417
- Infinite-NTU method (packed beds), 388–389
- Infinite storage capacity, hypothetical, 722, 737
- Inflation, 454–456
- Infrared radiation exchange, between gray surfaces, 146–147
- Insolation, 10
- Instantaneous efficiency, 289
  - defined, 289
  - of flat-plate collectors, 290–295
- Insulation:
  - with collector-storage wall systems, 558–560
  - movable:
    - in direct-gain systems, 552–555
    - in passive building heating systems, 546–547
    - in sunspaces, 563
  - and passive heating performance, 719
  - transparent, 415–416
- Integral collector storage (ICS) systems, 494–496
- Intercept factors, 334, 365–366
- Interfaces, for solar–conventional industrial process heat, 605–606
- Intermittent absorption cooling, 577–578
- Internal flow coefficients, 159–163
- International Energy Agency (IEA), 301, 310
- International Pyrheliometer Comparisons (IPC), 46
- International Pyrheliometric Scale 1956, 46
- International Solar Energy Society, 601
- International System of Units, 861–862
- Investments:
  - in passive systems, 571
  - in solar systems, 447–448
- IPC (International Pyrheliometer Comparisons), 46

Iqbal, M., 6, 9, 11, 14, 44, 60–62, 81  
 Irradiance, 10  
 Irradiation, 10  
 Isotropic diffuse model, 89–90  
 Isotropic sky:  
   defined, 85  
   radiation on sloped surfaces, 89–90,  
   103–106  
 Israeli Dead Sea ponds, 639–640

## J

Jaffe et al 1987, 625  
 James, S. R., 298  
 Jeffreson, C. P., 389  
 Jensen, C., 625  
 Jeys, T. H., 47  
 Jilar, T., 532  
 Johnson, F. S., 6  
 Johnson, T. E., 397, 527  
 Jones, D. E., 282  
 Jones, R. E., 35, 547  
 Jordan, R. C., 69, 71n.9, 72–74, 77, 79, 81–84,  
   89, 103, 109, 115–117, 122–124, 132,  
   622, 625, 692–694  
 Jurinak, J. J., 400, 528, 529, 595, 596

## K

Kakaç, S., 159  
 Karaki, S., 386, 512–517, 589–591,  
   599–600  
 Karman, V. D., 524–525  
 Kasten, F., 10n.3  
 Kauffman, K., 397  
 Kays, W. M., 159, 161, 163, 168, 169,  
   424  
 Kearney, D., 193, 195, 369, 625, 626  
 Kearney, D. W., 625, 626  
 Kenna, J., 669  
 Kenna, J. P., 745  
 Kennard, E. H., 140  
 Khouzam, K., 759  
 King, D. L., 231, 232, 748, 758  
 Kipp & Zonen actinometer, 46, 47  
 Kirchhoff's law, 176–177  
 Kirkpatrick, A. D., 571  
 Klein, S. A., 14, 77, 79, 103, 107, 109, 115,  
   126–128, 132, 214, 215, 223, 224, 227,  
   228, 250, 267, 272, 274, 488, 517, 547,  
   549, 551, 565, 575, 653, 656, 664, 665,  
   668, 670, 683, 685, 692, 696, 736, 739,  
   740, 743, 763

Kleinbach, E. M., 384  
 Klucher, T. M., 91, 92  
 Knight, K. M., 74, 665  
 Knudsen, S., 481  
 Kondratyev, K. Y., 10, 44, 62, 84  
 Koo, J. M., 313  
 Kooi, C. F., 634, 637  
 Kovarik, M., 431  
 KT method (average radiation), 107–112  
 Kuharich, R. R., 622  
 Kuhn, J. K., 382–384, 387  
 Kunz, S., 664  
 Kusuda, T., 289  
 Kutscher, C. F., 167, 285, 287

## L

Lamb, J. A., 193  
 Lambertian surfaces, 146  
 Lameiro, G., 669  
 Lampert, C. M., 173, 192, 195  
 Landis, F., 398  
 Lane, R., 615  
 Larsson, M., 395  
 Laszlo, T. S., 322  
 Latimer, J. R., 51  
 Latitude, 12  
 Lavan, Z., 278, 279, 382  
 LCC, *see* Life-cycle cost  
 LCR (load collector ratio), 713  
 LCR<sub>s</sub> (load collector ratio for the solar  
   aperture), 714  
 LCS, *see* Life-cycle savings  
 Least cost solar energy, 452  
 Lebens, R. M., 546, 712  
 Lee, T. K., 635  
 Leonard, J. A., 363  
 Lesse, P. F., 431  
 LI-COR pyranometers, 50, 51  
 Life-cycle cost (LCC), 452, 454, 475  
 Life-cycle savings (LCS), 452, 459–463, 475,  
   538  
 Lightstone, M. F., 490  
 Lin, R. J. H., 195  
 Linear imaging concentrators:  
   concentration ratios of, 326  
   geometry of, 351–354  
   imperfect, imaged from, 359–361  
   perfectly-oriented, images formed by,  
   354–359  
   thermal performance, 328–332  
 Linke-Feussner pyrheliometer, 47



- Liquid heating, 313
    - active collection–passive storage systems, 563
    - drain-back systems, 484, 510–513
    - f*-chart method for, 673–679
    - flow rate data corrections, 305–306
    - freeze protection for, 311
    - for industrial processes, 604–605
    - plate geometries for heaters, 275–280
    - thermal performance of, 291, 299–300
  - Lithium bromide–water air conditioners, 576–584
  - Littler, J., 562
  - Liu, B. Y. H., 69, 71n.9, 72–74, 77, 79, 81–84, 89, 103, 109, 115–117, 122–124, 132, 692–694
  - Liu, W., 496
  - Lloyd, J. R., 164
  - Loads, 409–420
    - building loss coefficients, 415–417
    - and building thermal capacitance, 417
    - and collector outputs, 373–375
    - cooling, 417–418
    - defined, 409
    - direct-coupled photovoltaic systems, 759–763
    - on direct-gain systems, 555
    - hot-water, 411–412
    - in passive cooling, 601
    - in passive heating systems, 546, 711–712
    - space heating:
      - degree-day method, 412–415
      - swimming pool heating, 418–420
      - time-dependent, 409–411
  - Load collector ratio (*LCR*), 713
  - Load collector ratio for the solar aperture (*LCR<sub>s</sub>*), 714
  - Load heat exchangers, 510
  - Local flux concentration ratio, 325
  - Local mirror radius (linear imaging concentrators), 352
  - Local winds, 778, 779
  - Lodwig, E., 592
  - Loehrke, R. I., 379, 380
  - Löf, G. O. G., 55, 56, 67, 167, 311–312, 327, 361, 365, 366, 491, 502, 506, 536, 581, 592, 654
  - Löf, L. G. A., 502
  - Loferski, J. J., 757
  - London, A. L., 168, 424
  - Long-wave radiation:
    - absorptance and emittance for, 188–189
    - defined, 43
  - Lorsch, J. G., 541
  - Los Alamos National Laboratory, 597, 669
  - Los Alamos Scientific Laboratory, 711
  - Lose, P. D., 354
  - Low-flow hot-water systems:
    - flow rates in, 479
    - pumped systems, 490–491
  - Lutz, D. J., 411
  - Luz International Limited, 624, 628
  - Luz power systems (California), 369, 624–628
- M**
- McAdams, W. H., 159, 163–165
  - McCorquodale, J. A., 166
  - McDaniels, D. K., 101
  - McDonald, G. E., 192
  - MacDonald, T. H., 48
  - McDonnell-Douglas, 368
  - McFarland, R. D., 712
  - McIntire, W. R., 297
  - McKay, D. C., 85
  - Mahone, D., 570
  - Main storage tank (in CombiSys), 798
  - Manitoba, weather data for, 866
  - Manwell, J. F., 777, 779, 780, 786, 788, 796
  - Mar, H. Y. B., 195, 218, 219
  - Marcus, R. J., 401
  - Mariner* satellite, 6, 8
  - Marlatt, W. P., 609, 610
  - Martin, D. C., 192, 193
  - Martin, M., 148
  - Martin Marietta, 368
  - Marvin, W. C., 387, 524, 526
  - Massachusetts, weather data for, 868
  - Massachusetts Institute of Technology (MIT), 506, 570
  - Masters, L. W., 311
  - Mather, G. R., Jr., 336
  - Mattox, D. M., 192, 196
  - Matz, R., 635
  - Maximum power point trackers (PV systems), 759, 763
  - Maycock, P. D., 745
  - Mazria, E., 30, 546, 712
  - Meador, M., 597
  - Mead, Egypt, irrigation plant, 621
  - Mean fluid temperature (flat-plate collectors), 267

- Mean plate temperature (flat-plate collectors), 267–268
  - Mechanical design considerations:
    - for flat-plate collectors, 311
    - for industrial process heat, 605–606
  - MEC (Munters Environmental Control) system, 594–595
  - Meinel, A. B., 193
  - Melnikov, G. K., 338
  - Menicucci, D. F., 770
  - Mercer, W. E., 161
  - Messenger, R. A., 745, 752, 763
  - METEONORM data set, 863
  - Meteorological (weather) data, 863–869
    - in CombiSys, xix
    - for simulations, 663–666
    - for specific locations, 865–869
    - in system thermal calculations, 422
  - Method 5000, 712
  - Mexico, weather data for, 866
  - Meyer, B. A., 154–157
  - Michelson pyrheliometer, 47
  - Mirror radius (linear imaging concentrators), 352
  - MIT (Massachusetts Institute of Technology), 506, 570
  - Mitchell, J. C., 20, 346
  - Mitchell, J. W., 164, 165, 412, 415, 418, 525, 526, 591, 663, 664, 686
  - MIT House IV, 506, 510, 540, 685
  - MIT House V, 527
  - Modified-Euler method, 657
  - Moll-Gorczynski pyranometer, 48, 49
  - Moll-Gorczynski pyrheliometer, 47
  - Monochromatic angular-hemispherical reflectance, 178–181
  - Monochromatic directional absorptance, 174, 181
  - Monochromatic directional emittance, 174, 181
  - Monochromatic hemispherical absorptance, 175–176
  - Monochromatic hemispherical-angular reflectance, 179
  - Monochromatic hemispherical emittance, 175–176
  - Monsen, W. A., 721, 723, 725, 727–729, 732, 736, 765
  - Monthly average clearness index, 71
  - Monthly mean daily extraterrestrial radiation, 37–40
  - Monthly radiation:
    - absorption through glazing, 223–229
    - beam and diffuse components of, 79–81
    - monthly mean daily radiation, 37–40
    - and receiving surface orientation, 112–114
  - Moon, J. R., 289n.13, 298
  - Moon, P., 60
  - Moore, S. W., 192, 288
  - Moran, W. P., 164
  - Morgan, W. R., 98
  - Morrison, C. A., 70–71
  - Morrison, D. J., 398–400, 527
  - Morrison, G. L., 491, 493
  - Morse, R. N., 114, 645
  - Mouchot, 621
  - Movable insulation:
    - in direct-gain systems, 552–555
    - in passive building heating systems, 546–547
    - in sunspaces, 563
  - Moving surfaces, beam radiation on, 101–103
  - Mullett, L. B., 634
  - Multinode approach (storage tanks), 379–382
  - Mumma, S. A., 524, 526
  - Mumma, S. D., 387
  - Munters Environmental Control (MEC) system, 594–595
  - Murray, W. D., 398
  - Murty, M. V. R. K., 361
  - Mutch, J. J., 410, 488
  - Myer, A., 712
- N**
- National Aeronautics and Space Administration (NASA), 6, 63
  - National Bureau of Standards (NBS), 289
  - National Climatic Data Center, 59
  - National Passive Solar Conferences, 545
  - National Renewable Energy Laboratory (NREL), 20, 59, 780, 863
  - National Security and Resources Study Center, 597
  - National Solar Radiation Data Base (NSRDB), 55, 863
  - Natural circulation water heaters, *see* Passive water heaters
  - Natural convection:
    - between flat parallel plates, 149–153
    - between horizontal concentric cylinders, 153–154
  - NBS (National Bureau of Standards), 289

- Neeper, D. A., 280  
 Nelson, J., 745  
 Nelson, J. S., 595  
 Nelson, K. E., 367  
 Net glazing area, 713  
 Net load coefficient, 713  
 Net present worth, 452  
 Net reference load, 713  
 Neumann, A., 91  
 Nevada, weather data for, 868  
 New Mexico, weather data for, 868  
 New York, weather data for, 868  
 Nielsen, C. E., 634, 636, 637  
 Night cold storage systems, 599  
 Niles, P. W. B., 560  
*Nimbus* satellite, 6, 8, 9  
 NIP (Eppley normal-incidence pyrheliometer), 46  
 Niyogi, B., 541  
 NOAA (U.S. National Oceanic and Atmospheric Administration), 55, 59  
 NOCT (nominal operating cell temperature), 758  
 Nomenclature:  
     radiation, 859–860  
     symbols list, 856–859  
 Nominal operating cell temperature (NOCT), 758  
 Nonabsorbing glass, solar transmittance of, 205  
 Nonimaging concentrators, 326  
     concentration ratios of, 326  
     optical characteristics of, 337–344  
 Normal-incidence pyrheliometer (NIP), 46  
 Normalized radiation levels, 37  
 Norris, D. J., 50, 51, 67  
 North America, weather data for, 866–868  
 Northeast trade winds, 778  
 Norton, B., 491  
 NREL, *see* National Renewable Energy Laboratory  
 NSDN (U.S. National Solar Data Network), 685–686  
 NSRDB (National Solar Radiation Data Base), 55, 863  
 Nusselt number, 149–150
- O**
- Oberndorfer, G., 384  
 Odeillo, France solar house, 566, 568  
 Offenhartz, P. O., 400  
 Off-peak periods, auxiliary electric energy for, 533–535  
 O’Gallagher, J. J., 344  
 Ohanessian, P., 392  
 Olgyay, V., 546  
 Olseth, J. A., 91  
 Olson, T. J., 597–599, 622  
 Once-through air heating, 607–611  
 Once-through water heating, 613–614  
 One-dimensional wind turbine model, 786–790  
 On-line plots (CombiSys), xxiii  
 Ontario, weather data for, 866  
 Oonk, R. L., 581, 584, 654  
 Opaque materials:  
     measurement of properties, 186–188  
     optimum properties, 195–196  
     radiation characteristics of, *see* Radiation surface characteristics  
 Open-circuit air heating, 607–611  
 Operating costs:  
     defined, 448  
     for industrial process heating, 606  
 Optical characteristics/properties:  
     of compound parabolic concentrators, 338–344  
     of concentrating collectors, 334–335  
     of cover systems, 206–211  
     of nonimaging concentrators, 337–344  
 Optical system (concentrating collectors), 322, 323, 334–335  
 Optimum properties, of opaque materials, 195–196  
 Oregon, weather data for, 868  
 Orgill, J. F., 75, 76  
 Orientation:  
     concentrating collectors, 324–325  
     compound parabolic concentrators, 345–349  
     of linear imaging concentrators, 354–359  
     and monthly average daily radiation, 112–114  
     in series arrays with sections having different orientations, 435–437  
 Ortabasi, U., 277  
 Overall heat loss coefficient, 240–254  
 Overhangs:  
     average shading factors for, 870–885  
     in passive heating systems, 547–552  
     shading by, 34–35  
 Overheating (active building heating systems), 535

**P**

- $P_1$ ,  $P_2$  method, 467–472
- Pacific Northwest Laboratory, 780
- Pacific region, weather data for, 869
- Packed (pebble) beds:
  - active air systems, 682–683
  - night chilling of, 599–600
  - pressure drop in, 165–167
  - storage in, 384–391
    - advantages of, 385–386
    - heating and cooling of, 386–387
    - Hughes models for, 387–388
    - Schumann model for, 386–387, 389
- Page, J. K., 79, 109
- Paraboloidal concentrators, 367–368
- Parallel solar energy–heat pump systems, 523, 524, 686–690
- Parsons, R. E., 617
- Partially shaded collectors, performance of, 433–435
- Pasadena Ostrich Farm system, 621
- PASOLE, 712
- Passive cooling, 601
- Passive Cooling Handbook*, 601
- Passive heating:
  - building heating, 544–563, 711–735
    - active systems vs., 544
    - applications of, 565–570
    - approaches to, 711–712
    - collector-storage walls and roofs, 557–561
    - comfort criteria, 546
    - concepts of, 545–546
    - costs and economics of, 571–573
    - direct gain systems, 552–557
    - energy storage in, 375
    - heat distribution in, 571
    - heating loads, 546
    - movable insulation and controls, 546–547
    - shading, 547–552
    - solar-load ratio method, 712–721
    - and storage media performance, 373
    - sunspaces, 561–563
    - unutilizability design method, 721–735
    - water heating, 479, 480, 482, 491–494
- Passive Solar Design Handbook*, 712, 720
- Passive Solar Heating Analysis*, 712, 720
- The Passive Solar Journal*, 544–545
- Passive (natural circulation) water heaters, 479, 480, 482, 491–494
- Pawleski, M. J., 663
- Payback time, 453, 464–466
- Pebble beds, 384. *See also* Packed beds
- Perers, B., 295
- Perez, R. R., 86, 91, 93–96
- Perforated plates, heat transfer and pressure drop in, 167–168
- Performance:
  - of concentrating collectors, 327–334
    - compound parabolic concentrators, 332–334, 349–351
    - linear imaging concentrators, 328–332
    - receiver thermal losses, 327–328
  - of flat-plate collectors, 287–298
    - basic method of testing, 290
    - efficiency tests, 290–295
    - general test procedure, 291
    - incident angle tests, 290, 295–297
    - in situ, 309–310
    - test data for, 289, 299–307
    - time constant, 290, 297–298
  - modeling, *see* System thermal calculations
  - of partially shaded collectors, 433–435
  - predicting, 43
  - solar cooling performance factor, 590–591
  - of solar ponds, 637–639
- Peterson, L. J., 154
- Pettit, R. B., 192, 196
- Phase change storage systems:
  - active building heating systems, 527–529
  - materials/media for, 396–400
- Photoelectric sunshine recorder, 53
- Photons, 746
- Photon radiation, 139
- Photosphere (sun), 4–5
- Photovoltaic converters, *see* Solar (photovoltaic) cells
- Photovoltaic pyranometers, 50
- Photovoltaic Specialists Conferences, 745
- Photovoltaic (PV) systems, 745–771
  - applications, 764–765
  - cell temperature, 757–759
  - controls, 763
  - converters (solar cells), 746–747
  - design procedures, 765–770
  - direct-coupled systems load characteristics, 759–763
  - generator characteristics and models, 747–757
  - high-flux generators, 770–771
  - maximum power point trackers, 763
- Pipe loss factors, 423, 426–429

- PITI (principal payment, interest, taxes, and insurance), 452–453  
 Planck's law, 140–141  
 Planetary wind patterns, 778  
 Plug flow approach (storage tanks), 379, 382–384  
 Polarization, 204–207  
 Poole, D. R., 401  
 Prandtl number, 149–150  
 Precision spectral pyranometer (PSP), 48, 49  
 Present worth, 455–456, 459–462  
 Present-worth factor (PWF), 456–458  
 Pressure drop:  
   in flat-plate collectors, 308–309  
   in packed beds, 165–167  
   in perforated plates, 167–168  
 Price, H., 628  
 Prigmore, D. R., 597  
 Probert, S. D., 491  
*Proceedings of the 1957 Solar Furnace Symposium*, 322  
*Proceedings of the 1978 DOE Workshop on Systems Studies for Central Solar Thermal Electric*, 629  
*Proceedings of the ERDA Solar Workshop*, 629  
*Proceedings of the Solar Industrial Process Heat Conference* (1978), 604  
*Proceedings of the Solar Industrial Process Heat Symposium* (1977), 604  
 Proctor, D., 295, 298, 645, 668  
 Product storage, 375. *See also* Energy (product) storage  
 Profile angle, 17, 19  
 Programmed orienting systems, 325  
 Projected area, 713  
 Property taxes, on installations, 449  
 PSP (Eppley precision spectral pyranometer), 48, 49  
 Public Utilities Regulatory Policies Act (PURPA), 625  
 Puerto Rico, weather data for, 866  
 PV systems, *see* Photovoltaic systems  
 PWF (present-worth factor), 456–458  
 Pyranometers, 44, 48–53  
 Pyrheliometers, 44–48  
 Pyrheliometric scale, 46–48
- R**
- Rabl, A., 77, 78n.12, 79, 80n.13, 81, 115, 239, 325, 337, 338, 340–344, 350, 354n.11, 357, 362, 367, 634, 692, 696
- Radiant exitance, 10  
 Radiant exposure, 10  
 Radiant self-exitance, 10  
 Radiation flux, 144–146  
 Radiation heat transfer coefficient, 147–149  
 Radiation intensity, 144–146  
 Radiation surface characteristics, 173–199  
   absorptance, 174–176  
     broadband, 182–183  
     calculation of, 183–186  
     of cavity receivers, 197–198  
     measurement of, 186–188  
     reflectance and, 181–182  
   angular dependence of solar absorptance, 196–197  
   emittance, 174–176  
     broadband, 182–183  
     calculation of, 183–186  
     measurement of, 186–188  
     reflectance and, 181–182  
 Kirchhoff's law, 176–177  
   measurement of properties, 186–188  
   optimum properties, 195–196  
   reflectance, 177–181  
     absorptance, emittance, and, 181–182  
     measurement of, 186–188  
     specular, 198–199  
   selective surfaces, 188–195  
   specularly reflecting surfaces, 198–199  
 Radiation tables, 142–144  
 Radiosity, 10  
 Radosevich, L. G., 369, 630, 632  
 Raithby, G. D., 152, 153  
 Randall, K. R., 153, 155, 158  
 Rankine cycle cooling systems, 596–599  
 Rauschenbach, H. S., 745, 747  
 Rayleigh number, 149–150  
 Rayleigh scattering, 60–61  
 Raymond, E., 506, 527  
 Ray-trace methods:  
   for evaluating concentrating collectors, 361  
   optical properties of cover systems, 206, 209  
 Read, K. A., 297  
 Read, W. R., 611, 645  
 Read, W. R. W., 497  
 Receivers (concentrating collectors), 322–324, 326  
   central-receiver collectors, 368–369  
   CPC-type concentrators and shape of, 343–344

Receivers (concentrating collectors)  
(*continued*)

- intercept factor, 334
- loss coefficients for, 363
- thermal losses from, 327–328
- Recirculating air heating, 611–613
- Recirculating water heating, 615–617
- Reflectance, 85, 177–181
  - and absorptance, 181–182
  - absorptance, emittance, and, 181–182
  - of cover systems, 206–211
  - and emittance, 181–182
  - measurement of, 186–188
  - specular, 198–199
- Reflection:
  - and radiation transmission through glazing, 202–206
  - through two cover interfaces, 204
- Refractive indices, 203–206
- Refrigeration, 575
- Reindl, D. T., 75, 76, 91, 92, 575
- Remund, J., 664
- Retrofit heaters:
  - building heating, 537
  - industrial processes, 605, 606
  - water, 496–497
- Return on investment (ROI), 467
  - defined, 454
  - for industrial process heat, 606
- Reversing layer (sun), 5
- Richtmyer, F. K., 140
- Riggs, J. L., 447
- Robinson, N., 5, 10, 44, 62
- Robitzsch pyranometers, 50
- Rock pile, 384. *See also* Packed beds
- Rohsenow, W. M., 160
- ROI, *see* Return on investment
- Romero, M., 629, 633
- Roofs:
  - collector-storage:
    - costs of, 571
    - passive building heating systems, 557–561
  - double, for passive cooling, 601
- Rooms, absorptance of, 229–230
- Roulet, J. R., 654
- Ruegg, R. T., 447
- Russia, weather data for, 866
- Ruth, D. W., 77, 79, 132

**S**

- Safety, with flat-plate collectors, 312
- Safwat, H. H., 295
- Salt-gradient solar ponds, 635–637
- Salt production, 646
- Saluja, G., 257
- Sander, D. M., 417
- Sandia National Laboratories, 764, 765, 770
- Santala, T., 193
- Sapsford, C. M., 493
- Sargent, S. L., 142, 577, 597
- Sarofim, A. F., 146
- Saunier, G. Y., 74
- Scaling problems (water heating), 486
- Scattering (radiation), 59–60
- Schmidt, R. N., 192
- Schmitt, D., 665
- Schöffner, P., 748n.1, 771
- Schroder, D. K., 747
- Schumann, T. E. W., 386
- Schwedler, M. C. A., 561, 562
- SCPF (solar cooling performance factor), 590–591
- SCRS (Solar Constant Reference Scale), 46
- Seasonal energy storage systems:
  - active building heating systems, 530–533
  - large systems, 394–396
- Seasonal industrial processes, 606–607
- Sebald, A. V., 558
- See, D. S., 646, 647
- SEF (solar energy factor), 498, 499
- SEGS (Solar Electric Generating Systems), 624–628
- Selcuk, K., 280
- Selcuk, M. K., 324, 647
- Selective surfaces, 188–192
  - absorptance and emittance, 188–191
  - directional selectivity, 193–194
  - mechanisms of selectivity, 192–195
- Seraphin, B. O., 193
- Series arrays:
  - with sections having different orientations, 435–437
  - system thermal calculations for, 431–433
- Series solar energy–heat pump systems, 523, 524
- Shading, 29–37
  - of central-receiver collectors, 368
  - of collectors in multirow arrays, 35–37
  - and flat-plate collector performance, 271–272

- by overhangs or wingwalls, 34–35
  - average shading factors for overhangs, 870–885
  - in passive heating systems, 547–552
- in passive cooling systems, 601
- performance of partially shaded collectors, 433–435
- by trees, buildings, or other obstructions, 30–34
- Shallow-pond water heating, 617–619
- Shepard, C. M., 402
- Sheridan, N. L., 101
- Sheridan, N. R., 576, 577, 653
- Shewen, E. C., 166, 167, 280
- Short-cut simulations, 669
- Short-wave radiation, 43
- Shurcliff, W. A., 539, 546
- SIAP, 50
- Siegel, M. D., 765
- Siegel, R., 142, 146, 176, 202, 206, 209
- Silver disc pyrheliometer, 45
- Simmons, J. A., 400
- Simon, F. F., 291
- Simpson, W. T., 611, 612
- Simulations, 422, 653–666
  - in active system design, 668–669
  - air conditioning, 585–588
  - and experiments, 655, 663
  - of heat pump–solar energy heating systems, 524–526
  - information from, 655–656
  - limitations of, 666
  - meteorological data for, 663–666
  - programs for, 653–654
  - short-cut, 669
  - of sunspaces, 561–562
  - TRNSYS program, 656–662, 800–803
  - utility of, 654–655
- Singapore, weather data for, 865
- Sjerps-Koomen, E. A., 232
- Skartveit, A., 91
- Skinrood, A. C., 369, 630, 632
- Skoda, L. F., 311
- Sky models, 85
  - anisotropic sky, 91–97
  - isotropic sky, 89–90
- Sky radiation, 147–148. *See also* Diffuse radiation
  - anisotropic sky, 91–97
  - clear-sky radiation estimation, 68–71
  - isotropic sky, 89–90, 103–106
- Sky radiation cooling systems, 600
- Slope, 12
- Sloped surfaces, available solar radiation on, 84–89
  - anisotropic sky, 91–97
  - average radiation:
    - isotropic sky, 103–106
    - KT method, 107–112
    - isotropic sky, 89–90, 103–106
- SLR (solar-load ratio) method, 712–721
- SMARTS program, 63
- Smith, C. C., 609, 610
- Smith, R. N., 398
- Sokolov, M., 496
- Solar Age*, 311
- Solar altitude angle, 13, 19, 20
- Solar aperture, 713, 714
- Solar azimuth angle, 13, 16, 19, 20
- Solar (photovoltaic) cells, 746–747. *See also* Photovoltaic (PV) systems
  - absorptance of, 231–234
  - maximizing output of, 763
  - modules of, 749
  - temperature of operation, 757–759
  - used with concentrators, 771
  - voltage-current relationships of, 747
- Solar constant, 5–6
- Solar Constant Reference Scale (SCRS), 46
- Solar cooling performance factor (SCPF), 590–591
- Solar-electrical systems, *see* Thermal power systems
- Solar Electric Generating Systems (SEGS), 624–628
- Solar Energy* (journal), 545
- Solar energy factor (SEF), 498, 499
- Solar energy–heat pump systems:
  - active building heating systems, 521–527, 686–690
  - for seasonal storage, 530
- Solar Energy Unit, University College Cardiff, 669
- Solar fraction, 444–445, 546
- Solar furnaces, 322. *See also* Concentrating collectors
- Solar geometry:
  - beam radiation:
    - angles for tracking surfaces, 20–23
    - direction of, 12–20
    - ratio on tilted surfaces to horizontal surfaces, 23–29



- Solar geometry (*continued*)
  - shading, 29–37
    - of collectors in multirow arrays, 35–37
    - by overhangs or wingwalls, 34–35
    - by trees, buildings, or other obstructions, 30–34
  - solar constant, 5–6
- Solar house (term), 505. *See also individual houses, e.g.: MIT House IV*
- Solarimeters, 44
- Solar-load ratio (SLR) method, 712–721
- Solar-mechanical systems. *See also Thermal power systems*
  - cooling, 596–599
  - thermal conversion systems for, 621–622
- Solar noon, 17
- Solar One (solar house, University of Delaware), 527, 757
- Solar One power plant (California), 369, 630–633
- Solar ponds, 635–640
  - applications of, 639–640
  - salt-gradient, 635–637
  - theory of, 637–639
- Solar position charts, 20, 30
- Solar radiation, 3–41
  - angles for tracking surfaces, 20–23
  - available, *see* Available solar radiation
  - beam radiation ratio on tilted to horizontal surfaces, 23–29
  - defined, 43
  - definitions related to, 9–11
  - direction of beam radiation, 12–20
  - extraterrestrial radiation on horizontal surfaces, 37–41
  - shading, 29–37
  - solar constant, 5–6
  - solar time, 11–12
  - spectral distribution of extraterrestrial radiation, 6–8
  - the sun, 3–5
  - variation of extraterrestrial radiation, 8–9
- Solar Radiation and Radiation Balance Data*, 55, 863
- Solar radiation network (SOLRAD), 59
- Solar Rating and Certification Corporation (SRCC), 299n.18, 498
- Solar-related methods, for cooling, 599–601
- Solar savings, 449–450, 461–463
- Solar savings fraction, 444–445
  - in analysis of system economics, 475
  - passive systems, 713
- Solar sky radiation, *see* Diffuse radiation; Sky radiation
- Solar storage tank, in CombiSys, xx
- Solar time, 11–12
- Solar Two power plant (California), 369, 633
- Solar wall, 713
- SOLCOST method, 669
- SOLMET* program, 55n.4, 59
- SOLRAD (solar radiation network), 59
- Souka, A. F., 295
- South Africa, weather data for, 865
- South America, weather data for, 869
- Southeast trade winds, 778
- Sowell, R. P., 192, 196
- Sowell, R. R., 192, 196
- Space heating. *See also* Building heating
  - in CombiSys, xx, 798
  - degree-day method, 412–415
  - and water heating, 497
- Spain, weather data for, 866
- Sparrow, E. M., 161, 163
- Spectral dependence, of transmittance through glazing, 215–218
- Spectral distribution:
  - of extraterrestrial radiation, 6–8
  - of total solar radiation, 61–63
- Spectrolab pyranometer, 48
- Specular reflectance, 177, 198–199
- Spencer, G. H., 361
- Spencer, J. W., 9, 11, 14
- Speyer, E., 277n.9, 530
- Spiegler, K. S., 647
- Sputtering processes, 193
- SRCC (Solar Rating and Certification Corporation), 299n.18, 498
- Stagnation (equilibrium) temperatures (flat-plate collectors), 310
- Stanhill, G., 77, 79
- Stefanakos, E., 640
- Stefan-Boltzmann equation, 141–142
- Steinmann, D. E., 613
- Stewart, R., 44, 51, 53
- Stirewalt, E. N., 745
- Storage, *see* Energy (product) storage
- Storage tanks:
  - for non-energy products of processes, 375
  - stratification in, 379–384
  - in hot-water systems, 481



- multinode approach, 379–382
- plug flow approach, 379, 382–384
- water, 376–379
- Storage walls, *see* Collector-storage walls
- Stratification (in storage tanks), 379–384
  - in hot-water systems, 481
  - multinode approach, 379–382
  - plug flow approach, 379, 382–384
- Streed, E. R., 289, 293
- Stuetzle, T., 328, 333
- Suhr, H. B., 646
- Summers, D. N., 285
- The sun, 3–5
- Sun, Y. T., 548
- Sun Angle Calculator, 20
- Sunray Energy, 624
- Sunrise hour angle, 17, 19
- Sun-seeking orienting systems, 325
- Sunset hour angle, 17, 19
- Sunspaces:
  - costs of, 572
  - defined, 545
  - design parameters for, 716
  - in passive building heating systems, 229–230, 561–563
- Supercooling (energy recovery), 398
- Surfaces, radiation characteristics of, *see* Radiation surface characteristics
- Surface azimuth angle, 13
- Surface layers, and radiation transmission through glazing, 218–219
- Surface orientation, available solar radiation and, 112–114
- Swaminathan, C., 577
- Swartman, R. K., 577
- Swearingen, J. S., 577
- Swimming pools:
  - heating loads for, 418–420
  - water heating for, 502–503
- Swinbank, W. C., 148
- Symbols list, 856–859
- System models, 441–444
- System thermal calculations, 422–445
  - collector heat exchanger factor, 424–425
  - component models, 422–423
  - controls, 429–431
  - duct and pipe loss factors, 426–429
  - modified collector equations, 438–441
  - performance of partially shaded collectors, 433–435
  - series arrays, 431–433, 435–437

- solar fraction, 444–445
- solar savings fraction, 444–445
- system models, 441–444
- Szokolay, S. V., 539, 546

## T

- Tabor, H., 150, 192, 195, 252, 288, 363, 493, 635, 636, 639
- Talbert, S. B., 640, 641, 645
- Talwalkar, A. T., 647
- Tan, H. M., 161
- Tanishita, I., 494
- Tax credits/deductions, 448, 450, 537
- Taylor, K. J., 647
- Teagan, W. P., 597
- Telkes, M., 397, 506, 527
- Temperature(s):
  - and efficiency of solar-mechanical systems, 621–622
  - in flat-plate collectors:
    - equilibrium (stagnation) temperature, 310
    - mean fluid/mean plate temperature, 267–268
  - ground, 601
  - in industrial process heat applications, 604–605
  - in salt-gradient solar ponds, 636
  - of solar cell operation, 757–759
- Temperature distributions (flat-plate collectors), 238–240
  - collector efficiency factor, 257–261
  - in flow direction, 261–262
  - between tubes, 254–261
- Temps, R. C., 92
- Terrell, R. E., 622
- Tesfamichael, T., 296
- Tests:
  - for flat-plate collectors, 289–298
    - basic method of testing, 290
    - efficiency tests, 290–295
    - general test procedure, 291
    - incident angle tests, 290, 295–297
    - time constant, 290, 297–298
  - of water heaters, 497–499
- Test data (flat-plate collectors), 289, 299–302
  - conversion of, 302–305
  - flow rate corrections, 305–307
- Texas, weather data for, 868
- Theilacker, J. C., 107, 109
- Thekaekara, M. P., 6, 9, 44, 60
- Thermal capacitance, building, 417

- Thermal conversion systems, 621–622
  - Thermal power systems, 621–633
    - central-receiver systems, 628–629
    - Gild Bend pumping system, 622–624
    - Luz systems, 624–628
    - Solar One power plant, 630–633
    - Solar Two power plant, 633
    - thermal conversion in, 621–622
  - Thermal radiation, 138
  - Thermosyphon, 479. *See also* Passive (natural circulation) water heaters
  - Theunissen, P.-H., 297, 336
  - Thom, H. C. S., 413
  - Thomas, R. N., 5
  - Thompson, T., 382
  - Thomsen, S. M., 218
  - Thornton, J. A., 193
  - Threlkeld, J. L., 622
  - Tilted surfaces, ratio of beam radiation on horizontal surfaces to, 23–29
  - Time, solar vs. standard, 11–12
  - Time constant:
    - defined, 297
    - and flat-plate collector thermal performance, 290, 297–298
  - Time-dependent loads, 409–411. *See also* Loads
  - Time value of money, 454–455
  - TMY, *see* Typical meteorological year
  - Total load coefficient, 713
  - Total solar radiation, 10
  - Touloukian, Y. S., 188
  - Townsend, T. U., 747, 762
  - Tracking surfaces, angles for, 20–23
  - Trade winds, 778
  - Transmittance:
    - of cover systems, 206–211
    - for diffuse radiation, 211–213
    - effects of dust and shading on, 271–272
    - through glazing, 202–234
      - absorption, 206, 219–229, 231–234
      - optical properties of cover systems, 206–211
      - and reflection of radiation, 202–206
      - spectral dependence of transmittance, 215–218
      - and surface layers, 218–219
      - surface layers' effects on, 218–219
      - transmittance-absorptance product, 213–215
      - transmittance for diffuse radiation, 211–213
  - Transmittance-absorptance product, 213–214, 268–271
  - Transparent insulation, 415–416
  - Transparent Insulation Technology*, 561
  - Trewartha, G. T., 66
  - Trickett-Norris pyranometer, 48
  - TRNSED:
    - defined, 799
    - inputs and default parameters for, xx–xxii, 799–800
  - TRNSYS, 656–662. *See also* Simulations
    - CombiSys version of, xix. *See also* CombiSys
    - components and combinations in library of, 657–659
    - example of, 660–662
    - running simulation with, 800–803
    - TRNSED front-end of, xx–xxii, 799
    - Users Manual*, 491, 561
  - Trombe, F., 194, 392, 393, 558, 566
  - Trombe-Michel walls, 545n.1
  - Trombe walls, 545n.1
  - Tschernitz, J. L., 611, 612
  - Tube collectors, 275
    - temperature distributions between tubes, 254–261
    - thermal performance test data for, 301–302
  - Tuller, S. E., 77, 79
  - Tybout, R. A., 536, 654
  - Typical meteorological year (TMY), 59, 664, 665
- U**
- Ukraine, weather data for, 866
  - Uncertainties, in system economics, 472–475
  - Unger, T. A., 192
  - U.S. Department of Energy, 654, 776
  - U.S. Forest Products Laboratory, 611
  - U.S. Home Finance Agency, 150
  - U.S. Hydrographic Office, 20
  - U.S. National Oceanic and Atmospheric Administration (NOAA), 55, 59
  - U.S. National Solar Data Network (NSDN), 685–686
  - United States, weather data for, 863, 866–868
  - University of Delaware, 527
  - University of Houston-Sandia, 368
  - University of Minnesota, 199
  - University of Queensland, Australia, 577

Unutilizability (“double-U”) design method  
 (passive systems):  
 collector-storage walls, 727–735  
 direct gain, 721–727  
 Utilizability (of available solar radiation):  
 daily, 126–132  
 generalized, 118–126  
 Utilizability methods, 668, 692–709  
 daily utilizability, 696–709  
 hourly utilizability, 693–696  
 Utzinger, D. M., 393, 547, 549–551, 559,  
 728n.4  
 Utzinger, M. D., 558

## V

Vacuum sputtering processes, 193  
 Van Koppen, C. W. J., 379, 490  
 Vant-Hull, L. L., 47, 368  
 Variation, of extraterrestrial radiation, 8–9  
 Vaxman, B., 496  
 Vee-corrugated enclosures, heat transfer in,  
 158  
 Venezuela, weather data for, 869  
 Ventilation, passive cooling and, 601  
 Ventre, J., 745, 752, 763  
 Vernon, R. W., 291  
 Vielha Hospital, Catalonia, Spain, 568–570  
 Villefontaine, France apartment buildings,  
 568–570  
 Vindum, J. O., 614

## W

Wäckelgård, E., 296  
 Walls:  
 collector-storage walls, 392–394  
 costs of, 571–572  
 defined, 545  
 design parameters for, 715  
 loss control with, 546  
 passive building heating systems,  
 557–561  
 unutilizability design method, 727–735  
 loss coefficients of, 415–416  
 solar, 713  
 wingwalls, 34–35, 547–552  
 Wallasey School (England), 565, 566  
 Wang, Y., 486  
 Ward, D. S., 513, 581  
 Ward, J. C., 668  
 Warehouse heating, passive, 570  
 Washburn, J., 192, 195

Water heating, 479–503  
 antifreeze loop/heat exchanger systems, 480,  
 481, 484  
 auxiliary energy for, 486–488  
 boiling protection, 483–486  
 common system configurations, 479, 480  
 economics of, 499–501  
 energy storage in, 375  
*f*-chart method for, 683–684  
 forced-circulation systems, 479–481,  
 488–489  
 freeze protection, 483–484  
 hot-water loads, 410–412  
 for industrial processes, 604–605  
 once-through, 613–614  
 recirculating, 615–617  
 shallow-pond, 617–619  
 integral collector storage systems, 494–496  
 low-flow pumped systems, 490–491  
 passive (natural circulation) water heaters,  
 479, 480, 482, 491–494  
 retrofit heaters, 496–497  
 scaling problems in, 486  
 simulation of, xix–xxiv  
 in space heating and cooling systems, 497  
 swimming pools, 418–420, 502–503  
 testing and rating heaters, 497–499  
 time-dependent loads for, 410–411  
 Water storage (of energy), 376–379  
 Watmuff, J. H., 164  
 Weather data, *see* Meteorological (weather)  
 data  
 Wei, J., 419  
 Weinberger, H., 635  
 Weinberger, Z., 636  
 Weir, A. D., 647  
 Weiss, W., 411, 507, 535, 539  
 Weitbrecht, V., 308  
 Welford, W. T., 338, 342, 361  
 Westerlies, 778  
 Whillier, A., 17, 18, 25, 72, 74, 81, 115–118,  
 209, 218, 238, 250, 254, 257, 275, 692,  
 693  
 White, J. A., 447  
 Whitlow, E. P., 577  
 Wiebelt, J. A., 63  
 Wien’s displacement law, 140–141  
 Wijesundera, N. E., 272, 274  
 Wilkins, E. S., 635  
 Williams, D. A., 195, 577  
 Willson, R. C., 6, 8

- Wilson, B. W., 647  
 Wind convection coefficients, 163–165  
 Wind duration curve, 781–782  
 Wind energy, 774–796  
     estimating wind turbine average power and energy production, 791–796  
     one-dimensional wind turbine model, 786–790  
     wind resources, 778–785  
*Wind Energy Resource Atlas of the United States*, 780  
 Windows:  
     in direct-gain systems, 552–555  
     direct gain through, 545  
     loss coefficients of, 415, 416  
     and room absorptance, 229–230  
 Wind turbines:  
     average power and energy production estimation, 791–796  
     one-dimensional model, 786–790  
     types of, 774–776  
 Wingwalls:  
     in passive heating systems, 547–552  
     shading by, 34–35  
 Winn, C. B., 431, 669  
 Winston, R., 338, 342, 343, 361  
 Winter, C. J., 629  
 Wirsum, M. C., 288, 610, 611  
 Wisconsin, weather data for, 868  
 Wittenberg, L. J., 639  
 WMO, *see* World Meteorological Organization  
 Woertz, B. B., 24n.7, 25, 89, 192, 209, 271, 287  
 Wohlers, H. C., 401  
 Wolf, M., 745  
 World Meteorological Organization (WMO), 44, 46, 48, 55  
*The World Network*, 55, 863  
 World Radiation Center (WRC), 6, 7  
 World Radiometric Reference (WRR), 46  
*World Weather Records*, 863  
 WRC (World Radiation Center), 6, 7  
 WRR (World Radiometric Reference), 46  
 Wuestling, M. D., 490  
  
**Y**  
 Yanagimachi, M., 600, 622  
 Yang, K. C., 613  
 Yanishevskiy pyranometer, 48  
 Yanishevskiy pyrliometer, 47  
 Yellott, J. I., 44, 560, 600  
 Young, A., 10n.3  
 Yusoff, M. B., 310, 429  
  
**Z**  
 Zarmi, Y., 428n.4, 493, 502  
 Zenith, 16  
 Zenith angle, 13  
 Zero-storage-capacity building, hypothetical, 722, 737–738  
 Zhang, H-F., 278, 279  
 Zollner, A., 496